



**Wright Water Engineers, Inc.**

2490 West 26th Ave., Suite 100A  
Denver, Colorado 80211  
(303) 480-1700 TEL  
(303) 480-1020 FAX

www.wrightwater.com  
e-mail: wlorenz@wrightwater.com

January 8, 2018

**Via: Electronic Submittal**

**PCD Project No. PPR-17-043**

El Paso County  
Engineering Division  
200 South Cascade Avenue, Suite 100  
Colorado Springs, CO 80903-2208

**Re: Amendment #1 to the Drainage Letter for the Forest Lakes Metropolitan District Water Intake and Treatment Plant Project**

Wright Water Engineers, Inc. (WWE), on behalf of the Forest Lakes Metropolitan District (FLMD), has prepared this El Paso County Drainage Letter Amendment #1 in response to verbal El Paso County comments received on January 4, 2018. This Amendment #1 to the original "Drainage Letter for the Forest Lakes Metropolitan District Water Intake and Treatment Plant Project" dated November 11, 2017 (original drainage letter) addresses these additional comments from El Paso County.

**Purpose of Amendment**

On January 4, 2018, El Paso County contacted WWE and requested additional documentation regarding the potential discharge of emergency overflow water from the two 18" diameter emergency overflow pipes, one from the water treatment plant (WTP) clearwell and the other from the Backwash Reclaim Basin (see Attachment E in the original drainage letter for the location of these pipes). El Paso County requested WWE provide a summary of the potential impacts this emergency overflow discharge may have on downstream stormwater infrastructure during a 100-year storm event.

This Amendment #1 provides a summary of the maximum potential overflow discharge from each emergency overflow pipe followed by an analysis of the capacity of the downstream infrastructure to convey this additional emergency discharge during a 100-year storm event.

**Proposed Clearwell and Backwash Reclaim Basin Emergency Overflow Rates**

The proposed WTP site has two emergency overflow locations, the clearwell inside the WTP and the Backwash Reclaim Basin located outside and east of the WTP. The following provides a summary of the potential emergency overflow discharge rate for each location.

***Clearwell Emergency Overflow***

In order for an overflow to occur from the clearwell the following situation would need to occur:

- Both high service pumps are inoperable,

- the clearwell is completely full,
- and the monitoring system in the WTP is not signaling an alarm to shut down production.

In this situation, the overflow rate from the clearwell into the 18" diameter overflow pipe is equal to the maximum amount of treated water that the plant is able to produce. The WTP has a treatment capacity of 0.5 million gallons per day (mgd) or 350 gallons per minute (gpm). Therefore, the flow from the clearwell into the overflow pipe would be 350 gpm or 0.78 cfs.

### ***Backwash Reclaim Basin Emergency Overflow***

In order for an overflow to occur from the Backwash Reclaim Basin the following situation would need to occur:

- Both backwash recycle pumps are inoperable,
- the Backwash Reclaim Basin is completely full,
- and a filter backwash cycle occurs in the plant.

In this situation, the overflow rate from the Backwash Reclaim Basin into the 18" diameter overflow pipe is equal to the maximum amount of backwash water that the plant is able to produce. The WTP has a high rate backwash rate of 1050 gpm, and only one filter is backwashed at a time. Therefore, the flow from the Backwash Reclaim Basin into the overflow pipe would be 1050 gpm or 2.34 cfs.

This results in a total emergency overflow rate from both locations of 3.12 cfs.

### **Capacity of Downstream Stormwater Drainage Infrastructure During a 100-year Event and Emergency Overflow Condition**

As shown on Attachment E in the original drainage letter, both 18" diameter overflow pipes route to the now existing stormwater drainage system for the Forest Lakes Filings 2A & 2B project. These 18" diameter overflow pipes eventually discharge into an existing 24" RCP which ties into an existing 48" RCP. According to the previously approved Forest Lakes Filings 2A and 2B project, at the tie-in point (Sta. 6+01.45), the 48" RCP has a 100-year flowrate of 176.5 cfs which is maintained until the pipe outfalls into the existing detention basin ±500 LF downstream. See Attachment A1 for the stormwater utility drawings from the Forest Lakes Filing 2A and 2B project.

The added flowrate of 3.12 cfs, as a result of an emergency overflow situation occurring during a 100-year storm event, will result in a 1.8% increase in the flowrate of the existing 48" RCP. This is within the carrying capacity of the 48" RCP trunk line. In order to demonstrate the emergency overflows will have a negligible impact on the existing infrastructure, WWE developed a Hydraflow Storm Sewer hydraulic model for the existing 48" RCP line using the Forest Lakes Filings 2A and 2B design sheets. As shown in Attachment B1, the addition of the emergency overflow discharge during a 100-year design storm is estimated to cause a ±0.04' increase at the downstream outfall of the existing 48".


## Summary and Conclusions

In summary, construction of the FLMD WTP will not adversely affect the downstream drainage infrastructure associated with the March 2016 “Preliminary & Final Drainage Report for Forest Lakes Filings 2A & 2B” prepared by Classic Consulting Engineers & Surveyors. The downstream drainage infrastructure has sufficient carrying capacity to convey potential emergency overflow discharges from the WTP during a 100-year event.


Sincerely,

WRIGHT WATER ENGINEERS, INC.

By

  
Hayes A. Lemhart, P.E.  
Associate Water Resources Engineer

Reviewed By

  
Wayne F. Lorenz, P.E.  
Chief Design Engineer

Attachments

**Attachment A1 – Forest Lakes Filling No. 2b Storm Sewer Plans (Sheets 9 and 10)**

**Attachment B1 – Hydraflow Storm Sewers Model Results**

Z:\Project Files\02-03\031-090\031-090.300\Engineering\Site Development Plan - El Paso County\Drainage Letter\FLMD WTP - Drainage Letter Amendment #1.docx

## **Attachment A1**


N:\17502\DRAWINGS\CONSTRUCTION\FIG. NO. 2B\STORM\17502-STN-FL2B-10.dwg, 11/2/2017 11:35:06 PM, 1:1

**STORM SEWER:**


ALL STORM SEWER AND DETENTION/WATER QUALITY PONDS ARE TO BE OWNED AND MAINTAINED BY THE FOREST LAKES METROPOLITAN DISTRICT.

**NOTE:**


EXISTING UTILITIES SHOWN IN AN APPROXIMATE WAY ONLY. ALL EXISTING UTILITIES TO BE POTHOLED AND VERIFIED BOTH HORIZONTALLY & VERTICALLY PRIOR TO CONSTRUCTION & CONFLICTS REPORTED TO ENGINEER.




**PROPOSED PRIVATE 18" RCP LAT 'F' TO 5' TYPE R SUMP INLET**




**PROPOSED PRIVATE 24' RCP LAT 'E' TO 10' TYPE R SUMP INLET**




**PROPOSED PRIVATE 18" RCP LAT 'D' TO TYPE D GRATED INLET**




**PROPOSED PRIVATE 24' RCP TO EXISTING LAKE DRAIN (EMERGENCY DRAIN ONLY)**



**PROPOSED PRIVATE 18' RCP LATERAL 'J' FOR CONNECTION**



**LEGEND**



48 HOURS BEFORE YOU DIG,  
CALL UTILITY LOCATORS  
**811**  
UTILITY NOTIFICATION CENTER OF COLORADO  
IT'S THE LAW

THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. THE CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE CAUSED BY HIS FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES.

**NO. REVISION**

1 ADD MANHOLE AND 18" STUB (LAT. J) FOR DISTRICT CONNECTION 11/01/17

**DATE**

**REVIEW:**

PREPARED UNDER MY DIRECT SUPERVISION FOR AND ON BEHALF OF  
CLASSIC CONSULTING ENGINEERS AND SURVEYORS, LLC

KYLE R. CAMPBELL, COLORADO P.E. #29794

DATE



619 N. Cascade Avenue, Suite 200  
Colorado Springs, Colorado 80903

(719)785-0790  
(719)785-0799(fax)


FOREST LAKES FILING NO. 2B  
STORM SEWER PLAN  
LAT 'D', LAT 'E', LAT 'F', LAKE DRAIN  
PLAN & PROFILE

DESIGNED BY	MAL	SCALE	DATE	12/21/15
DRAWN BY	MAL	(H) 1" = 50'	SHEET	10 OF 11
CHECKED BY		(V) 1" = 5'	JOB NO.	1175.02






N:\17502\DRAWINGS\CONSTRUCTION\FILING NO. 2B\STORM\17502-STN-FL2B-03.dwg, 8/28/2017 12:57:05 AM, 1:1



**STORM SEWER:**  
ALL STORM SEWER AND DETENTION/WATER QUALITY PONDS ARE TO BE OWNED AND MAINTAINED BY THE FOREST LAKES METROPOLITAN DISTRICT.

**NOTE:**  
EXISTING UTILITIES SHOWN IN AN APPROXIMATE WAY ONLY. ALL EXISTING UTILITIES TO BE POTHOLED AND VERIFIED BOTH HORIZONTALLY & VERTICALLY PRIOR TO CONSTRUCTION & CONFLICTS REPROTED TO ENGINEER.

**PROPOSED PRIVATE 48" RCP STORM SEWER (BYPASS MAIN)**



LEGEND	
	PROPOSED FIRE HYDRANT
	PROPOSED WATER MAIN
	PROPOSED SANITARY SEWER MAIN
	PROPOSED STORM SEWER
	PROPOSED STORM INLET
	ROW/BOUNDARY LINE
	EXISTING FIRE HYDRANT
	EXISTING WATER MAIN
	EXISTING SANITARY SEWER MAIN
	EXISTING STORM SEWER
	EXISTING STORM INLET
	EXISTING GAS MAIN
	EXISTING ELECTRIC

48 HOURS BEFORE YOU DIG,  
CALL UTILITY LOCATORS  
**811**  
UTILITY NOTIFICATION CENTER OF COLORADO  
IT'S THE LAW

THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. THE CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE CAUSED BY HIS FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES.

NO. REVISION	DATE


REVIEW:  
PREPARED UNDER MY DIRECT SUPERVISION FOR AND ON BEHALF OF  
CLASSIC CONSULTING ENGINEERS AND SURVEYORS, LLC

KYLE R. CAMPBELL, COLORADO P.E. #29794      DATE



FOREST LAKES FILING NO. 2B STORM SEWER PLAN 48" BYPASS MAIN PLAN & PROFILE			
DESIGNED BY	MAL	SCALE	DATE 12/21/15
DRAWN BY	MAL	(H) 1" = 50'	SHEET 9 OF 11
CHECKED BY	(V) 1" = 5'	JOB NO.	1175.02

## **Attachment B1**





# My Report100-year flow conditions without clearwell and backwash reclaim basin overflow

Line No.	Line ID	Flow Rate (cfs)	Line Size (in)	Line Type	Line Length (ft)	Invert Dn (ft)	Invert Up (ft)	Line Slope (%)	HGL Dn (ft)	HGL Up (ft)	Minor Loss (ft)	HGL Jnct (ft)	DnStm Ln No	Junct Type	Gnd/Rim El Dn (ft)	Gnd/Rim El Up (ft)
1		176.50	48	Cir	76.880	6850.50	6851.27	1.00	6854.50	6855.66	2.30	6857.96	Outfall	None	6850.50	6864.00
2		176.50	48	Cir	109.520	6851.27	6861.07	8.95	6857.96	6864.83	n/a	6864.83	1	None	6864.00	6869.00
3		176.50	48	Cir	294.200	6861.07	6866.25	1.76	6864.98	6870.01	n/a	6870.01	2	None	6869.00	6880.00
4		176.50	48	Cir	15.850	6866.25	6866.53	1.77	6870.17	6870.29	n/a	6870.29	3	MH	6880.00	6880.00
5		176.50	48	Cir	144.080	6866.73	6873.75	4.87	6870.44	6877.51	n/a	6877.51	4	None	6880.00	6883.00
6		176.50	48	Cir	202.300	6873.75	6877.80	2.00	6877.67	6881.56	n/a	6881.56	5	None	6883.00	6886.00
7		176.50	48	Cir	45.100	6877.80	6878.70	2.00	6881.71	6882.46	n/a	6882.46	6	None	6886.00	6887.00
8		0.01	24	Cir	22.110	6868.58	6868.78	0.90	6873.51	6873.51	0.00	6873.51	4	None	6880.00	6880.50
Project File: Existing 48in RCP Storm Sewer.stm													Number of lines: 8		Date: 1/5/2018	
NOTES: ** Critical depth																

Line No.	Line ID	Flow Rate (cfs)	Line Size (in)	Line Type	Line Length (ft)	Invert Dn (ft)	Invert Up (ft)	Line Slope (%)	HGL Dn (ft)	HGL Up (ft)	Minor Loss (ft)	HGL Jct (ft)	DnStm Ln No	Junct Type	Gnd/Rim El Dn (ft)	Gnd/Rim El Up (ft)
1		179.62	48	Cir	76.880	6850.50	6851.27	1.00	6854.50	6855.70	2.38	6858.09	Outfall	None	6850.50	6864.00
2		179.62	48	Cir	109.520	6851.27	6861.07	8.95	6858.09	6864.84	2.49	6864.84	1	None	6864.00	6869.00
3		179.62	48	Cir	294.200	6861.07	6866.25	1.76	6864.99	6870.02	1.43	6870.02	2	None	6869.00	6880.00
4		179.62	48	Cir	15.850	6866.25	6866.53	1.77	6870.17	6870.30	3.33	6870.30	3	MH	6880.00	6880.00
5		176.50	48	Cir	144.080	6866.73	6873.75	4.87	6870.56	6877.51	n/a	6877.51	4	None	6880.00	6883.00
6		176.50	48	Cir	202.300	6873.75	6877.80	2.00	6877.67	6881.56	n/a	6881.56	5	None	6883.00	6886.00
7		176.50	48	Cir	45.100	6877.80	6878.70	2.00	6881.71	6882.46	n/a	6882.46	6	None	6886.00	6887.00
8		3.12	24	Cir	22.110	6868.58	6868.78	0.90	6873.61	6873.62	0.02	6873.63	4	None	6880.00	6880.50
Project File: Existing 48in RCP Storm Sewer w Emerg. Overflows.stm													Number of lines: 8		Date: 1/5/2018	
NOTES: ** Critical depth																