



ENTECH
ENGINEERING, INC.

505 ELKTON DRIVE
COLORADO SPRINGS, CO 80907
PHONE (719) 531-5599
FAX (719) 531-5238

**SOIL, GEOLOGY, GEOLOGIC HAZARD STUDY
EAGLE RISING SUBDIVISION
PARCEL NOS. 52290-00-034 & 52290-00-035
EL PASO COUNTY, COLORADO**

Prepared for

**Casas Limited Partnership #4
IQ Investors, LLC
P.O. Box 2076
Colorado Springs, Colorado 80901**

Attn: Steve Jacobs

PCD File No. SP-205

June 29, 2022
Revised January 25, 2023

Respectfully Submitted,

ENTECH ENGINEERING, INC.


Logan L. Langford, P.G.
Geologist

LLL/mw

Encl.

Entech Job No. 221458
AAprojects/2022/221458/sgghs

Reviewed by:



Joseph C. Goode, Jr., P.E.
President

TABLE OF CONTENTS

1.0 SUMMARY 1
2.0 GENERAL SITE CONDITIONS AND PROJECT DESCRIPTION 2
3.0 SCOPE OF THE REPORT 3
4.0 FIELD INVESTIGATION 3
5.0 SOIL, GEOLOGY AND ENGINEERING GEOLOGY 4
 5.1 General Geology 4
 5.2 Soil Conservation Survey 4
 5.3 Site Stratigraphy 5
 5.4 Soil Conditions 6
 5.5 Groundwater 7
6.0 ENGINEERING GEOLOGY – IDENTIFICATION AND MITIGATION OF GEOLOGIC HAZARDS 7
 6.1 Relevance of Geologic Conditions to Land Use Planning 11
7.0 ECONOMIC MINERAL RESOURCES 13
8.0 ROADWAY AND EMBANKMENT CONSTRUCTION RECOMMENDATIONS 14
9.0 EROSION CONTROL 15
10.0 CLOSURE 16
BIBLIOGRAPHY 17

TABLES

Table 1: Summary of Laboratory Test Results

FIGURES

- Figure 1: Vicinity Map
- Figure 2: USGS Map
- Figure 3: Development Plan/Percolation Test Location Plan
- Figure 4: Soil Survey Map
- Figure 5: Falcon NW Quadrangle Geology Map
- Figure 6: Geology Map/Engineering Geology
- Figure 7: Floodplain Map
- Figure 8: Perimeter Drain Detail
- Figure 9: Underslab Drainage Layer (Capillary Break)
- Figure 10: Interceptor Drain Detail

- APPENDIX A: Site Photographs
- APPENDIX B: Test Boring Logs from the Profile Holes
- APPENDIX C: Laboratory Test Results
- APPENDIX D: Embankment Fill & Water Line Density Reports
- APPENDIX E: Soil Survey Descriptions

1.0 SUMMARY

Project Location

The project lies in a portion of the E ½ of Section 29, Township 12 South, Range 65 West of the 6th Principal Meridian in El Paso County, Colorado. The site is located approximately ½ mile east of the city limits of Colorado Springs, Colorado.

Project Description

Total acreage involved in the project is approximately 70 acres. The proposed site development consists of 17 single-family rural residential lots. The houses on Lots 6 and 15 are to remain. There are also numerous accessory structures existing on Lots 6, 7, 8, 15, and 16 that will remain. The structures include a large barn, detached garages, garden structures, storage containers, and a greenhouse structure. The development will utilize central water and on-site wastewater treatment systems.

Scope of Report

This report presents the results of our geologic evaluation, treatment of engineering geologic hazard study.

Land Use and Engineering Geology

This site was found to be suitable for the proposed development. Areas were encountered where the geologic conditions will impose some constraints on development and land use. These include areas of seasonal and potentially seasonal shallow groundwater areas, drainage areas, floodplains, areas of ponded water, artificial fill, potentially expansive soils, areas of downslope creep, potentially unstable slopes, and shallow bedrock. Based on the proposed development plan, it appears that these areas will have some impact on the development. These conditions will be discussed in greater detail in the report.

In general, it is our opinion that the development can be achieved if the observed geologic conditions on site are either avoided or properly mitigated. All recommendations are subject to the limitations discussed in the report.

2.0 GENERAL SITE CONDITIONS AND PROJECT DESCRIPTION

The site is located in a portion of the E ½ of Section 29, Township 12 South, Range 65 West of the 6th Principal Meridian in El Paso County, Colorado. The site is located approximately ½ mile east of the city limits of Colorado Springs, Colorado, at the south end of Kurie Road, east of Black Forest Road. The location of the site is as shown on the Vicinity Map, Figure 1.

The topography of the site varies from gently to moderately sloping generally to the south with some steeper slopes along the drainages on-site. The drainages on site flow in easterly and southerly directions through the property. Cottonwood Creek flows along the eastern side of the property. Water was observed flowing in Cottonwood Creek at the time of the investigation. Two dams with ponded water are located on the property in the Cottonwood Creek drainage. The northern dam has a gentle upstream face with no observed erosion and a 3:1 downstream face. Ponderosa Pines with field grasses and weeds were previously observed on the dam with an area of willows at the eastern end. Soft soils were observed in the area of the willows. A small steeper area on the western end of the downstream face was observed. The southern dam has a gentle upstream face with no observed erosion and a 2:1 downstream face. Field grasses and weeds were observed on the dam with an area of willows in the eastern portion of the downstream face of the dam. Soft soils were noted across the entire downstream face of the southern dam. Both dams have outlet works. The willows and soft soils associated with the dams were removed during dam improvements observed by Entech following the original site investigation conducted in 2012, and are further discussed later in this report. Other minor drainages are located on the property. No water was observed flowing in the minor drainages at the time of this investigation. The roadway and several drainage improvements have been completed since the original investigation in 2012. The northern and southern dams were reconstructed and observed by Entech Engineering, Inc. Roadway base, water main, electric, and communication utilities have been installed. Density testing on the reconstructed dams and the water main placed for the subdivision, these reports and density testing results are included in Appendix D.

The site boundaries are indicated on the USGS Map, Figure 2. Previous land uses have included grazing and pasture land. The houses on Lots 6 and 15 are to remain. There are also numerous accessory structures existing on Lots 6, 7, 8, 15, and 16 that will remain. The structures include a large barn, detached garages, garden structures, storage containers, and a

greenhouse structure. The site contains primarily field grasses and weeds with ponderosa pine coverage in the northern portions of the site and deciduous trees and shrubs along Cottonwood Creek. Site photographs, taken June 21, 2022, are included in Appendix A.

Total acreage involved in the proposed development is approximately 70 acres. Seventeen single-family rural residential lots are proposed. Lot sizes range from approximately 2.5 to 7 acres. The area will be serviced by central water and individual on-site wastewater treatment systems. The proposed Development Plan by Land Resource Associates is presented in Figure 3.

3.0 SCOPE OF THE REPORT

The scope of the report includes a general geologic analysis utilizing published geologic data. Detailed site-specific mapping will be conducted to obtain general information in respect to major geographic and geologic features, geologic descriptions and their effects on the development of the property.

4.0 FIELD INVESTIGATION

Our field investigation on this site consisted of the preparation of a geologic map of any bedrock features and significant surficial deposits. The Natural Resource Conservation Service (NRCS), previously the Soil Conservation Service (SCS) survey was also reviewed to evaluate the site. The position of mappable units within the subject property are shown on the Geologic Map. Our mapping procedures involved both field reconnaissance and measurements and aerial photo reconnaissance and interpretation. The same mapping procedures have also been utilized to produce the Engineering Geology Map which identified pertinent geologic conditions affecting development. The field mapping was performed by personnel of Entech Engineering, Inc. on March 16, 2012, and the site was recently revisited on June 21, 2022 to verify that no significant changes have occurred.

Six (6) percolation tests were performed on the site to determine general suitability of the site for the proposed development. The locations of the profile holes are indicated on the Percolation Test Location Plan/Development Plan, Figure 4. The Test Boring Logs from the Profile Holes are presented in Appendix B. Results of this testing will be discussed later in this report.

Laboratory testing was also performed on some of the soils to classify and determine the soils engineering characteristics. Laboratory tests include grain-size analysis, ASTM D-422, and Atterberg Limits, ASTM D-4318. Swell testing included both FHA Swell Tests and Swell/Consolidation Tests. Results of the laboratory testing are included in Appendix C. A Summary of Laboratory Test Results is presented in Table 1.

5.0 SOIL, GEOLOGY AND ENGINEERING GEOLOGY

5.1 General Geology

Physiographically, the site lies in the western portion of the Great Plains Physiographic Province. Approximately 11 miles to the west is a major structural feature known as the Rampart Range Fault. This fault marks the boundary between the Great Plains Physiographic Province and the Southern Rocky Mountain Province. The site exists within the southeastern edge of a large structural feature known as the Denver Basin. Bedrock in the area tends to be very gently dipping in a northerly direction (Reference 1). The rocks in the area of the site are sedimentary in nature, and typically Tertiary to Upper Cretaceous in age. The bedrock underlying the site consists of the Dawson Arkose Formation. Overlying this formation are unconsolidated deposits of residual, man-made, and alluvial soils of the Quaternary Age. The residual soils are produced by the in-situ action of weathering of the bedrock on site. The alluvial soils were deposited by water in the drainages on site. Man-made soils exist as earthen dams, fill piles, and areas of fill associated with the existing buildings on site. The site's stratigraphy will be discussed in more detail in Section 5.3.

5.2 Soil Conservation Survey

The Natural Resource Conservation Service (Reference 2), previously the Soil Conservation Service (Reference 3) has mapped 2 soil types and one water type associated with the ponds on site (Figure 4). In general, the soils vary from gravelly loamy sand to sandy loam. The soils are described as follows:

<u>Type</u>	<u>Description</u>
8	Blakeland loamy sand, 1-9% slopes
40	Kettle gravelly loamy sand, 3-8% slopes
71	Pring coarse sandy loam, 3-8% slopes

Complete descriptions of each soil type are presented in Appendix E. The soils have generally been described to have rapid permeabilities. The soils have been described as good potential for use as homesites. Possible hazards with soil erosion are present on the site. The erosion potential can be controlled with vegetation. The majority of the soils have been described to have slight to moderate erosion hazards.

5.3 Site Stratigraphy

The Falcon NW Quadrangle Geology Map showing the site is presented in Figure 6 (Reference 4). The Geology Map prepared for the site is presented in Figure 7. Three mappable units were identified on this site which are described as follows:

Qaf Artificial Fill of Holocene Age: These are man-made fill deposits associated with earthen dams on-site, fill piles, and areas of fill associated with the existing structures on site.

Qal Recent Alluvium of Holocene Age: These are recent deposits that have been deposited in the drainages that exist on-site. These materials consist of silty to clayey sands and sandy clays. Some of these alluviums contain highly organic soils.

Tkd Dawson Formation of Tertiary to Cretaceous Age: The Dawson formation typically consists of arkosic sandstone with interbedded fine-grained sandstone, siltstone and claystone. Overlying this formation is a variable layer of residual soil. The residual soils were derived from the in-situ weathering of the bedrock materials on-site. These soils typically consisted of silty to clayey sands and sandy clays.

The soils listed above were mapped from site-specific mapping, the *Geologic Map of the Falcon NW Quadrangle* distributed by the Colorado Geological Survey in 2003 (Reference 4), the *Geologic Map of the Colorado Springs-Castle Rock Area*, distributed by the US Geological Survey in 1979 (Reference 5), the *Geologic Map of the Pueblo 1^o x 2^o Quadrangle*, distributed by the US Geological Survey in 1978 (Reference 6). The Test Borings from the profile holes were also used in evaluating the site and are included in Appendix B. The Geology Map prepared for the site is presented in Figure 6.

5.4 Soil Conditions

The soils encountered in the Profile Holes of the percolation tests can be grouped into 3 general soil and rock types: A slightly silty to silty sand (SM-SW, SM); Soil Type 1, a silty clay (CL); Soil Type 2, a slightly silty to silty sandstone (SM-SW, SM); Soil Type 3, a very sandy claystone and claystone-siltstone (CL, CL-ML); Soil Type 4. The soils were classified using the Unified Soil Classification System (USCS).

Soil Type 1 consists of slightly silty to silty sand (SM-SW, SM), encountered in the upper soil profile in all of the profile holes to depths ranging from 2 to 4 feet. These soils were encountered at very dense states and at moist conditions. Samples tested had 11 percent and 19 percent passing the 200 Sieve. The sands typically have low expansion potential.

Soil Type 2 consists of silty clay (CL). The silty clay was encountered in one of the profile holes at 3 feet extending to 8 feet. The clay was encountered at very stiff consistencies and moist conditions. The sample tested had 99 percent of the soil size particles passing the No. 200 sieve. An FHA Swell pressure of 510 psf was measured on the clay. This swell is in the low expansion range. A consolidation of 0.1 percent was measured on the clay in the Swell/Consolidation Test indicating low potential for consolidation.

Soil Type 3 consists of slightly silty to silty sandstone (SM-SW, SM). The sandstone was encountered in all of the profile holes at depths ranging from 2 to 12 feet and extending to depths ranging from 8 feet to the termination of the borings (15 feet). The sandstone was encountered at very dense states and moist conditions. Samples tested had 11 percent to 28 percent passing the 200 sieve. The sandstone typically has low expansion potential.

Soil Type 4 consists of very sandy claystone and claystone-siltstone (CL, CL-ML). This material was encountered in 3 of the profile holes at depths ranging from 4 to 14 feet and extending to depths ranging from 12 feet to the termination of the borings (15 feet). The claystone was encountered at hard consistencies and at moist conditions. The samples tested had 51 percent to 57 percent passing the 200 sieve. A swell of 1.0 percent was measured in the Swell/Consolidation Test. FHA Swell pressures of 60 psf and 410 psf were measured on the claystone. These swells are in the low expansion range. Moderately to highly expansive claystone is common in the area.

The Test Boring Logs from the Profile Holes are presented in Appendix B. Laboratory Test Results are presented in Appendix C. A Summary of Laboratory Test Results is presented in Table 1.

5.5 Groundwater

Groundwater was encountered at 7 feet and 14.5 feet in Profile Hole Nos. 1 and 4, respectively. Groundwater was not encountered in the other profile holes which were drilled to 15 feet. Areas of seasonal and potentially seasonal shallow groundwater and ponded water have been mapped in the drainages on-site. These areas are discussed in the following section. Fluctuation in groundwater conditions may occur due to variations in rainfall and other factors not readily apparent at this time.

It should be noted that in the sandy materials on site, some groundwater conditions might be encountered due to the variability in the soil profile. Isolated sand and gravel layers within the soils, sometimes only a few feet in thickness and width, can carry water in the subsurface. Groundwater may also flow on top of the underlying bedrock or clays. Builders and planners should be cognizant of the potential for the occurrence of such subsurface water features during construction on-site and deal with each individual problem as necessary at the time of construction.

6.0 ENGINEERING GEOLOGY – IDENTIFICATION AND MITIGATION OF GEOLOGIC HAZARDS

As mentioned previously, detailed mapping has been performed on this site to produce an Engineering Geology Map (Figure 6). This map shows the location of various geologic conditions of which the developers should be cognizant during the planning, design and construction stages of the project. These hazards and the recommended mitigation techniques are as follows:

Floodplain – constraint

Areas of the site are mapped within a floodplain zone according to the FEMA Map Nos. 08041CO527G and 08041CO535G, dated December 7, 2018 (Figure 7, Reference 7). These areas exist in the southern pond area and downstream from the dam. It has been designated

as a preservation area on the development plant. Lots immediately adjacent to the floodplain may experience higher groundwater levels during peak flows. Subsurface Perimeter Drains are recommended for structures adjacent to the floodplain to help prevent the intrusion of water into areas below grade. Typical drain details are presented in Figure 8. Finished floor levels must be located a minimum of one foot above floodplain levels. Exact locations of floodplain and specific drainage studies are beyond the scope of this report.

Expansive Soils – constraint

Expansive soils were encountered in some of the test borings drilled on-site and as a part of the previous investigations (References 3 and 4). The site is classified in areas of low to moderate swell potential according to the *Map of Potentially Swelling Soil and Rock in the Front Range Urban Corridor, Colorado* by Hart, 1974 (Reference 9); however, highly expansive clays and claystone are typically encountered in the area. These areas are sporadic; therefore, none have been indicated on the map. Expansive clays and claystone, if encountered, can cause differential movement in the structure foundation.

Mitigation: Mitigation of expansive soils will require special foundation design. Overexcavation and replacement with non-expansive soils at a minimum 95% of its maximum Modified Proctor Dry Density, ASTM D-1557 is a suitable mitigation which is common in the area. Drilled piers are another option that is used in areas where highly expansive soils are encountered. Typical minimum pier depths are on the order of 25 feet or more and require penetration into the bedrock material a minimum of 4 to 6 feet, depending upon building loads. Floor slabs on expansive soils should be expected to experience movement. Overexcavation and replacement has been successful in minimizing slab movements. The use of structural floors can be considered for basement construction on highly expansive clays. Final recommendations should be determined after additional investigation of each building site.

Seasonal Shallow Groundwater Area – constraint

In these areas, we would anticipate the potential for periodically high subsurface moisture conditions and frost heave potential on a seasonal basis. Additional, highly organic soils could be encountered in these areas. The majority of these areas are associated with the Cottonwood Creek drainage area and are designated as open space. Where structures encroach on these areas, the following precautions are recommended.

Mitigation: Foundations must have a minimum 30-inch depth for frost protection. In areas where high subsurface moisture conditions are anticipated periodically, subsurface perimeter drains

are recommended to help prevent the intrusion of water into areas below grade. These areas may experience higher groundwater levels during period of higher precipitation where water can flow through permeable sands on top of less permeable bedrock materials. Additionally, where shallow groundwater is encountered, underslab drains or interceptor drains may be necessary. Typical drain details are presented in Figures 8 through 10. Due to lot sizes, it is anticipated these areas could be avoided by structures. Any grading in these areas should be done to direct surface flow around construction to avoid areas of ponded water near structures. All organic material would be completely removed prior to any fill placement. Additional investigation on the lots prior to construction is recommended to provide final foundation and subsurface drain recommendations.

Potentially Seasonal Shallow Groundwater Area – constraint

In these areas, we would anticipate the potential for periodically high subsurface moisture conditions, frost heave potential and highly organic soils. The majority of these areas lie within drainages which can be avoided by the proposed development. Construction in or adjacent to any portions of these areas, if required, should follow the precautions for seasonal shallow groundwater areas.

Areas of Ponded Water – constraint

These are areas where the ponds exist and areas within the drainages where standing water was observed. The two larger ponds in the eastern portion of the site are to be avoided by development. During periods of high runoff, water could also pond behind the small earthen dam in the north central portion of the site north of Lot 3. According to the development plan, an access driveway is planned for this area. It is anticipated the pond area can be avoided or filled if needed. Should construction be considered in these areas, regrading will be necessary in order to fill the area above the groundwater level. All soft or organic soils should be removed prior to fill placement. The same mitigation techniques for seasonal shallow groundwater areas are recommended for structures that encroach on these areas as well.

Potentially Unstable Slopes – constraint

A cut-slope in the central area of Lot 4 has been identified as potentially unstable. Considerable care must be exercised in these areas not to create a condition which would tend to activate instability.

Mitigation: The potentially unstable slope along the north pond areas is in an area designated as open space and will be avoided by development. The cut slope in the central portion of the site is cut in sandstone and appears to be stable in its present state. Structures should be located a minimum of 20 from any potentially unstable slope unless stabilized. Stabilization could involve regrading the slope to no steeper than 3:1 or the use of retaining walls. Proper control of drainage at both the surface and in the subsurface is extremely important. Areas of ponded water at the surface should be avoided above these slopes. Utility trenches, basement excavations and other subsurface features should not be permitted to become water traps which may promote saturation of the subsurface materials.

Downslope Creep Areas – constraint

These areas are acceptable as building sites, however, in areas identified with this hazard classification, we would anticipate accelerated lateral and vertical movement of the near surface soils in the downslope direction. These are minor areas located along the Cottonwood Creek drainage that is designated as open space. Structures encroaching on these areas may require the following mitigation.

Mitigation: The design of foundations in these areas should account for the additional pressure on the structure due to the creep potential. Tie-beams, buttresses and counterforts may be necessary in some areas. Deep cuts in these areas should be avoided. Proper control of drainage at both the surface and subsurface is important. Saturation of materials should be avoided that may create unstable conditions. It is anticipated, due to lot sizes, these areas could be avoided by development.

Artificial Fill – constraint

Fill associated with earthen dams, fill piles and fill associated with existing structures were observed on site. Additionally, other areas of artificial fill may be encountered in areas other than those mapped. These areas of fill are considered uncontrolled for construction purposes.

Mitigation: The earthen dams are in the area designated as open space and can be avoided by development. The fill piles are limited and it is anticipated they will be removed during site grading. Any uncontrolled fill encountered beneath foundation will require removal and recompaction at a minimum of 95% of its maximum Modified Proctor Dry Density, ASTM D-1557.

6.1 Relevance of Geologic Conditions to Land Use Planning

We understand that the development will be single-family rural residential consisting of seventeen lots. The houses on Lots 6 and 15 are to remain. There are also numerous accessory structures existing on Lots 6, 7, 8, 15, and 16 that will remain. The structures include a large barn, detached garages, garden structures, storage containers, and a greenhouse structure. It is our opinion that the existing geologic and engineering geologic conditions will impose some constraints on the proposed development and construction. The most significant problems affecting development will be those associated with the drainages on site which can be avoided. Other hazards on site may be satisfactorily mitigated through proper engineering design and construction practices.

The upper residual soils are typically at very dense states and very stiff to hard consistencies. The granular soils encountered in the upper soil profiles of the test borings should provide good support for foundations. Expansive soils were encountered on portions of the site that may require mitigation. Foundations anticipated for the site are standard spread footings possibly in conjunction with overexcavation in areas of expansive soils. Areas containing arkosic sandstone will have high allowable bearing conditions. Difficult excavation should be anticipated in areas of shallow bedrock. Expansive layers may also be encountered in the soil and bedrock on this site. Areas of expansive soils encountered on site are sporadic; therefore, none have been indicated on the maps. Expansive soils, if encountered, will require special foundation design and/or overexcavation. These soils will not prohibit development.

Areas of seasonal and potentially seasonal high groundwater areas, ponded water and floodplains were encountered on site. The areas of seasonal high groundwater, and ponded water and floodplain are primarily located within no-build zones or can be avoided. Due to the size of the lots and the proposed development, the areas mapped as potentially seasonal high groundwater can likely be avoided by construction. Any grading done in these areas should direct surface water away from construction to avoid areas of ponded water near structures. Structures should not block drainages.

Areas of fill were observed on site associated with dams, fill piles and existing buildings and development. The dams are located within no-build areas on Lot 16 and within Tract A, and it is anticipated the dams will be avoided by development. The willows on the northern and

southern dams have been removed and the soft soils recompacted. The small steeper portion of the downstream face of the northern dam at the western end has also been regraded to no steeper than 2.5:1. The repair work of the dams was observed by personnel of Entech Engineering, Inc., and density testing performed on the embankment fill. The southern dams downstream face was 2:1 and had loose soils and some willows. The willows have been removed and the downstream face recompacted and regraded to no steeper than 2.5:1. Wet, soft soils should be expected at the toe of the dams and further stabilization may be necessary. Well-defined spillways exist which should be maintained for both dams. It is anticipated other areas of fill will be removed during site grading or construction of individual structures. Any uncontrolled fill encountered beneath foundations should be removed and recompacted at a minimum of 95% of its maximum Modified Proctor Dry Density, ASTM D-1557.

Areas mapped as potentially unstable slopes and downslope creep areas have been mapped on this site. The majority of these areas exist along the pond area in the northeast portion of the site in areas designated as open space. Another area exists on tract in the western portion of the site where a cut slope exists. Sandstone bedrock was observed in the cut and appears to be stable in its present state. Structures should be located a minimum distance of 20 feet from any potentially unstable slope unless the slope is stabilized. Stabilization could involve regarding the slope to no steeper than 3:1. Structures encroaching on downslope creep areas or potentially unstable slopes may require additional foundation reinforcement or stiffeners. Due to the size of the lots, it is anticipated these areas can be avoided by construction.

In summary, development of the site can be achieved if the items mentioned above are mitigated. These items can be mitigated through proper design and construction or through avoidance. Investigation on each lot is recommended prior to construction.

7.0 ECONOMIC MINERAL RESOURCES

Some of the sandy materials on-site could be considered a low-grade sand resource. According to the *El Paso County Aggregate Resource Evaluation Map* (Reference 8), portions of the site have been mapped as upland and floodplain deposits. According to the *Atlas of Sand, Gravel and Quarry Aggregate Resources, Colorado Front Range Counties* distributed by the Colorado Geological Survey (Reference 9), the site is not mapped with any resources. According to the *Evaluation of Mineral and Mineral Fuel Potential* (Reference 10), the area of the site has been mapped as “Little or No Potential” for industrial minerals. Some of the sandy materials on site could be considered an aggregate resource. However, considering the silty to clayey nature of much of these materials and abundance of similar materials through the region and the close proximity to developed land, they would be considered to have little significance as an economic resource.

According to the *Evaluation of Mineral and Mineral Fuel Potential of El Paso County State Mineral Lands* (Reference 10), the site is mapped within the Denver Basin Coal Region. However, the area of the site has been mapped as “Poor” for coal resources. No active or inactive mines have been mapped in the area of the site. No metallic mineral resources have been mapped on the site (Reference 10).

The site has been mapped as “Fair” for oil and gas resources (Reference 10). No oil or gas fields have been discovered in the area of the site. The sedimentary rocks in the area may lack the geologic structure for trapping oil or gas; therefore, it may not be considered a significant resource. Hydraulic fracturing is a new method that is being used to extract oil and gas from rocks. It utilizes pressurized fluid to extract oil and gas from rocks that would not normally be productive. The area of the site has not been explored to determine if the rocks underlying the site would be commercially viable utilizing hydraulic fracturing. The practice of hydraulic fracturing has come under review due to concerns about environmental impacts, health and safety.

8.0 ROADWAY AND EMBANKMENT CONSTRUCTION RECOMMENDATIONS

In general, the site soils are suitable for any additional roadways and embankments. Groundwater should be expected to be encountered in deeper cuts and along drainages and low-lying areas. If excavations encroach on the groundwater level unstable soil conditions may be encountered. Excavation of saturated soils will be difficult with rubber-tired equipment. Stabilization using shot rock or geogrids may be necessary.

Any areas to receive fill should have all topsoil, organic material or debris removed. Prior to fill placement Entech should observe the subgrade. Fill must be properly benched and compacted to minimize potentially unstable conditions in slope areas. Fill slopes should be 3:1. The subgrade should be scarified and moisture conditioned to within 2% of optimum moisture content and compacted to a minimum of 95% of its maximum Modified Proctor Dry Density, ASTM D-1557, prior to placing new fill. Areas receiving fill may require stabilization with rock or fabric if shallow groundwater conditions are encountered.

New fill should be placed in thin lifts not to exceed 6 inches after compaction while maintaining at least 95% of its maximum Modified Proctor Dry Density, ASTM D-1557. These materials should be placed at a moisture content conducive to compaction, usually 0 to $\pm 2\%$ of Proctor optimum moisture content. The placement and compaction of fill should be observed and tested by Entech during construction. Entech should approve any import materials prior to placing or hauling them to the site. Additional investigation may be required for final gravel roadway designs.

9.0 EROSION CONTROL

The soil types observed on the site are mildly to highly susceptible to wind erosion, and moderately to highly susceptible to water erosion. A minor wind erosion and dust problem may be created for a short time during and immediately after construction. Should the problem be considered severe enough during this time, watering of the cut areas or the use of chemical palliative may be required to control dust. However, once construction has been completed and vegetation re-established, the potential for wind erosion should be considerably reduced.

With regard to water erosion, loosely compacted soils will be the most susceptible to water erosion, residually weathered soils and weathered bedrock materials become increasingly less susceptible to water erosion. For the typical soils observed on site, allowable velocities or unvegetated and unlined earth channels would be on the order of 3 to 4 feet/second, depending upon the sediment load carried by the water. Permissible velocities may be increased through the use of vegetation to something on the order of 4 to 7 feet/second, depending upon the type of vegetation established. Should the anticipated velocities exceed these values, some form of channel lining material may be required to reduce erosion potential. These might consist of some of the synthetic channel lining materials on the market or conventional riprap. In cases where ditch-lining materials are still insufficient to control erosion, small check dams or sediment traps may be required. The check dams will serve to reduce flow velocities, as well as provide small traps for containing sediment. The determination of the amount, location and placement of ditch linings, check dams and of the special erosion control features should be performed by or in conjunction with the drainage engineer who is more familiar with the flow quantities and velocities.

Cut and fill slope areas will be subjected primarily to sheetwash and rill erosion. Unchecked rill erosion can eventually lead to concentrated flows of water and gully erosion. The best means to combat this type of erosion is, where possible, the adequate re-vegetation of cut and fill slopes. Cut and fill slopes having gradients more than three (3) horizontal to one (1) vertical become increasingly more difficult to revegetate successfully. Therefore, recommendations pertaining to the vegetation of the cut and fill slopes may require input from a qualified landscape architect and/or the Soil Conservation Service.

10.0 CLOSURE

It is our opinion that the existing geologic engineering and geologic conditions will impose some constraints on development and construction of the site. The majority of these conditions can be avoided by construction. Others can be mitigated through proper engineering design and construction practices. The proposed development and use is consistent with anticipated geologic and engineering geologic conditions.

It should be pointed out that because of the nature of data obtained by random sampling of such variable and non-homogeneous materials as soil and rock, it is important that we be informed of any differences observed between surface and subsurface conditions encountered in construction and those assumed in the body of this report. Individual investigations for building sites and septic systems will be required prior to construction. Construction and design personnel should be made familiar with the contents of this report. Reporting such discrepancies to Entech Engineering, Inc. soon after they are discovered would be greatly appreciated and could possibly help avoid construction and development problems.

This report has been prepared for Casas Limited Partnership #4 and IQ Investors, LLC for application to the proposed project in accordance with generally accepted geologic soil and engineering practices. No other warranty expressed or implied is made.

We trust that this report has provided you with all the information that you required. Should you require additional information, please do not hesitate to contact Entech Engineering, Inc.

BIBLIOGRAPHY

1. Scott, Glen R.; Taylor, Richard B.; Epis, Rudy C. and Wobus, Reinhard A. 1978. *Geologic Structure Map of the Pueblo 1° x 2° Quadrangle, South-Central Colorado*. Sheet 2. U.S. Geologic Survey. Map I-1022.
2. Natural Resource Conservation Service, June 20, 2007. *Web Soil Survey*. United States Department Agriculture, <http://web soil survey.nrcs.usda.gov>.
3. United States Department of Agriculture Soil Conservation Service. June 1981. *Soil Survey of El Paso County Area, Colorado*.
4. Madole, Richard F. 2003. *Geologic Map of the Falcon NW Quadrangle, El Paso County, Colorado*. Colorado Geological Survey. Open-File Report 03-8.
5. Trimble, Donald E. and Machette, Michael N. 1979. *Geologic Map of the Colorado Springs-Castle Rock Area, Front Range Urban Corridor, Colorado*. USGS, Map I-857-F.
6. Scott, Glenn R.; Taylor, Richard B.; Epis, Rudy C. and Wobus, Reinhard A. 1978. *Geologic Map of the Pueblo 1° x 2° Quadrangle, South-Central Colorado*. Sheet 1. US Geological Survey. Map I-1022.
7. Federal Emergency Management Agency. December 7, 2018. *Flood Insurance Rate Maps for the City of Colorado Springs, Colorado*. Map Numbers 08041CO527G and 08041CO535G.
8. El Paso County Planning Development. December 1995. *El Paso County Aggregate Resource Evaluation Maps*.
9. Schwochow, S.D.; Shroba, R.R. and Wicklein, P.C. 1974. *Atlas of Sand, Gravel, and Quarry Aggregate Resources, Colorado Front Range Counties*. Colorado Geological Survey. Special Publication 5-B.
10. Keller, John W.; TerBest, Harry and Garrison, Rachel E. 2003. *Evaluation of Mineral and Mineral Fuel Potential of El Paso County State Mineral Lands Administered by the Colorado State Land Board*. Colorado Geological Survey. Open-File Report 03-07.

TABLE

TABLE 1
SUMMARY OF LABORATORY TEST RESULTS

CLIENT CASA'S LIMITED PARTNERSHIP
PROJECT EAGLE RISING SUBDIVISION
JOB NO. 221458

SOIL TYPE	TEST BORING NO.	DEPTH (FT)	WATER (%)	DRY DENSITY (PCF)	PASSING NO. 200 SIEVE (%)	LIQUID LIMIT (%)	PLASTIC INDEX (%)	SULFATE (WT %)	FHA SWELL (PSF)	SWELL/ CONSOL (%)	UNIFIED CLASSIFICATION	SOIL DESCRIPTION
1	3	2-3			18.9						SM	SAND, SILTY
1	4	2-3			10.9	NV	NP				SM-SW	SAND, SLIGHTLY SILTY
1	6	2-3			48.3						SM	SAND, VERY SILTY
2	6	5	17.3	104.7	99.0				510	-0.1	CL	CLAY, SANDY
3	1	2-3			12.3						SM	SANDSTONE, SILTY
3	2	2-3			28.4	35	2				SM	SANDSTONE, SILTY
3	4	5			10.9						SM-SW	SANDSTONE, SLIGHTLY SILTY
3	5	5			37.2						SM	SANDSTONE, SILTY
4	1	10			51.4	37	18		410		CL	CLAYSTONE, VERY SANDY
4	1	15			53.1	28	7		60		CL-ML	CLAYSTONE-SILTSTONE, VERY SANDY
4	3	10	15.7	115.6	56.6	12	5			1.0	CL-ML	CLAYSTONE-SILTSTONE, VERY SANDY

FIGURES

Forest Enterprises
Temporarily closed

SITE

Black Forest Rd

Eagle Wing Dr

PROJECT WAY

Rising Eagle Pt

Briarclate Pkwy

Black Forest Rd

Calnroom Way

Calnroom Way



ENTECH
ENGINEERING, INC.
305 ELKTON DRIVE
COLORADO SPRINGS, CO 80907 (719) 531-5399

VICINITY MAP
EAGLE RISING
EL PASO COUNTY, COLORADO, CO.
FOR: CASAS LIMITED PARTNERSHIP #4

DRAWN:
LLL


DATE:
6/22/22

CHECKED:

DATE:

JOB NO.:
221458

FIG NO.:
1



ENTECH
ENGINEERING, INC.
 208 ELAKTON DRIVE
 COLORADO SPRINGS, CO. 80907 (719) 531-9099

USGS MAP
 EAGLE RISING
 EL PASO COUNTY, COLORADO, CO.
 FOR: CASAS LIMITED PARTNERSHIP #4

DRAWN:
 LLL

DATE:
 6/22/22

CHECKED:

DATE:

JOB NO.:
 221458


FIG NO.:
 2

APPROVED BY AND ACCEPTABLE TO THE EL PASO COUNTY ATTORNEYS OFFICE.
 12. ALL RECORDED EASEMENTS WHOSE LOCATION CAN BE DEFINED ARE SHOWN ON THE PLAN. A UTILITY MAINTENANCE EASEMENT WHICH AFFECTS THE ENTIRE PROPERTY IS RECORDED IN BK 3673 PG 917 OF THE EL PASO COUNTY PUBLIC RECORDS.
 13. UTILITY LINES PROVIDING SERVICE TO EXISTING BUILDINGS AND FACILITIES MAY BE RELOCATED DEPENDING UPON FINAL UTILITY ENGINEERING PROVIDED BY INDIVIDUAL UTILITY COMPANIES.


DEVELOPMENT DATA -

SINGLE FAMILY RESIDENTIAL - 17 LOTS, 55.29 AC, 78%
 OPEN SPACE (TRACT A) - 12.08 AC, 17%
 PUBLIC ROAD ROW - 2.11 AC, 3%
 COUNTY PROPOSED BRIARGATE (ASPHALT) - 1.43 AC
 KURIE ROAD CUL-DE-SAC (GRAVEL) - 0.34 AC
 EAGLE WING DRIVE CUL-DE-SAC (ASPHALT) - 0.34 AC
 PRIVATE ROAD ROW (TRACT B) - EAGLE WING DRIVE - 1.31 AC, 2% (GRAVEL)
 TOTAL PROJECT - 17 LOTS, 70.79 AC, 100%
 MIN LOT SIZE - 2.5 AC
 AVE LOT SIZE - 3.25 AC
 GROSS DENSITY - 1 LOT PER 4.16 AC
 MAX BLDG HEIGHT - 35 FEET
 EXISTING ZONING - RR-25

30' PERIMETER UTILITY & DRAINAGE EASEMENT
 DRAINAGE EASEMENT WIDTH VARIES



NOTE: A PAVEMENT DESIGN REPORT WILL BE REQUIRED BEFORE PLACEMENT OF G




- Legend:**
- TB - APPROXIMATE TEST BORING LOCATION AND NUMBER
 - P2 - APPROXIMATE PHOTOGRAPH LOCATION AND DIRECTION


REVISION	BY

ENTTECH ENGINEERING, INC.
 505 ELKTON DRIVE
 COLORADO SPRINGS, CO. 80907
 (719) 531-5599

DEVELOPMENT PLAN/TEST BORING LOCATION MAP
 EAGLE RISING FILING NO. 1
 EL PASO COUNTY, COLORADO, CO.
 FOR: CASAS LIMITED PARTNERSHIP #4

DRAWN L.L. CHECKED
DATE 1/25/23
SCALE AS SHOWN
JOB NO. 221458
FIGURE No. 3





ENTECH
ENGINEERING, INC.
 305 ELKTON DRIVE
 COLORADO SPRINGS, CO. 80907 (719) 531-5799

SOIL SURVEY MAP
EAGLE RISING
 EL PASO COUNTY, COLORADO, CO.
 FOR: CASAS LIMITED PARTNERSHIP #4

DRAWN:
 LLL


DATE:
 6/22/22

CHECKED:

DATE:

JOB NO.:
 221458

FIG NO.:
 4




ENTECH
ENGINEERING, INC.
305 ELKTON DRIVE
COLORADO SPRINGS, CO. 80907 (719) 531-5399

FALCON NW QUADRANGLE GEOLOGIC MAP
EAGLE RISING
EL PASO COUNTY, COLORADO, CO.
FOR: CASAS LIMITED PARTNERSHIP #4


DRAWN: LLL	DATE: 6/22/22	CHECKED:	DATE:
---------------	------------------	----------	-------

JOB NO.:
221458

FIG NO.:
5


THE "POW" A UTILITY RIGHT OF WAY EASEMENT WHICH AFFECTS THE ENTIRE PROPERTY IS RECORDED IN BK 3673 PG 917 OF THE EL PASO COUNTY PUBLIC RECORDS. UTILITY LINES PROVIDING SERVICE TO EXISTING BUILDINGS AND FACILITIES MAY BE RELOCATED DEPENDING UPON FINAL UTILITY ENGINEERING PROVIDED BY INDIVIDUAL UTILITY COMPANIES.

DEVELOPMENT DATA -
 SINGLE FAMILY RESIDENTIAL - 17 LOTS, 55.29 AC, 78%
 IN SPACE (TRACT A) - 12.08 AC, 17%
 PUBLIC ROAD ROW - 2.11 AC, 3%
 COUNTY PROPOSED BRIARGATE (ASPHALT) - 1.43 AC
 KURIE ROAD CUL-DE-SAC (GRAVEL) - 0.34 AC
 EAGLE WING DRIVE CUL-DE-SAC (ASPHALT) - 0.34 AC
 VATE ROAD ROW (TRACT B) - EAGLE WING DRIVE - 1.31 AC, 2% (GRAVEL)
 TOTAL PROJECT - 17 LOTS, 70.79 AC, 100%
 LOT SIZE - 2.5 AC
 LOT SIZE - 3.25 AC
 DSS DENSITY - 1 LOT PER 4.16 AC
 MAX BLDG HEIGHT - 35 FEET
 ZONING - RR2.5



- LEGEND:**
- Qaf - **Artificial Fill of Quaternary Age:**
Man-made fill deposits
 - Qal - **Recent Alluvium of Quaternary Age:**
Water Deposited sands and clays
 - TKd - **Dawson Formation of Tertiary and Cretaceous Age:**
Arkosic sandstone with siltstone and claystone lenses
 - fp - floodplain
 - w - ponded water
 - sw - seasonal shallow groundwater
 - psw - potentially seasonal shallow groundwater
 - dsc - downslope creep
 - pu - potentially unstable slope

PH1 Approximate location of profile hole



REVISION	BY

ENTTECH
 ENGINEERING, INC.
 COLORADO SPRINGS, CO. 80907 (719) 531-5599

GEOLOGY/ENGINEERING GEOLOGY MAP
 EAGLE RISING FILING NO. 1
 EL PASO COUNTY, COLORADO, CO.
 FOR: CASAS LIMITED PARTNERSHIP #4

DRAWN L.L.L.
CHECKED
DATE 1/25/23
SCALE AS SHOWN
JOB NO. 221458
FIGURE NO. 6



SITE

08041C0527G
eff. 12/7/2018

600ft

Zone
AE
7.12
7.10
7.025



N



ENTECH
ENGINEERING, INC.
565 ELKTON DRIVE
COLORADO SPRINGS, CO. 80907 (719) 531-0599

FLOODPLAIN MAP
EAGLE RISING
EL PASO COUNTY, COLORADO, CO.
FOR: CASAS LIMITED PARTNERSHIP #4

DRAWN:
LLL


DATE:
6/22/22

CHECKED:

DATE:

JOB NO.:
221458

FIG NO.:
7




ENTECH
ENGINEERING, INC.
 505 ELKTON DRIVE
 COLORADO SPRINGS, CO. 80907 (719) 531-5599

TYP. UNDERSLAB DRAINAGE LAYER (CAPILLARY BREAK)

DRAWN BY:	DATE DRAWN:	DESIGNED BY:	CHECKED:
-----------	-------------	--------------	----------

JOB NO.:
 221458
 FIG NO.:
 9



NOTE:
 EXTEND INTERCEPTOR DRAIN TO UNDERDRAIN OR TO SUMP.
 BENCH DRAIN INTO NATIVE SOILS 12 INCHES MINIMUM.

INTERCEPTOR DRAIN DETAIL

N.T.S.



ENTECH
ENGINEERING, INC.
 505 ELKTON DRIVE
 COLORADO SPRINGS, CO. 80907 (719) 531-5599

INTERCEPTOR DRAIN DETAIL

DRAWN BY:
DPS

DATE DRAWN:


DATE

CHECKED:
DPS

JOB NO.:
221458

FIG. NO.:
10

APPENDIX A: Site Photographs





Looking north from the eastern side of the site from Eagle Wing Drive.

June 21, 2022



Looking southeast from the eastern side of the site.

June 21, 2022




Looking north from the southwest corner of the site.

June 21, 2022



Looking east along earthen dam in the southern portion of the site.

June 21, 2022



Looking south from the central portion of the site.

June 21, 2022





Looking north from the central portion of the site.

June 21, 2022



Looking east from the west-central portion of the site.

June 21, 2022





Looking west from the east-central portion of the site.

June 21, 2022



**Looking south from
the eastern portion of
the site.**

June 21, 2022



**Looking northwest
from the northeastern
portion of the site.**

June 21, 2022

APPENDIX B: Test Boring Logs from Profile Holes

TEST BORING NO. 1
 DATE DRILLED 11/15/2011
 Job # 221458

TEST BORING NO. 2
 DATE DRILLED 11/15/2011
 CLIENT CASA'S LIMITED PARTNERSHIP
 LOCATION EAGLE RISING SUBDIVISION

REMARKS	Depth (ft)	Symbol	Samples	Blows per foot	Watercontent %	Soil Type	REMARKS	Depth (ft)	Symbol	Samples	Blows per foot	Watercontent %	Soil Type
WATER @ 7', 11/16/11							DRY TO 15', 11/16/11						
SAND, SILTY, TAN						1	SAND, SILTY, TAN						1
SANDSTONE, SILTY, FINE TO COARSE GRAINED, TAN, VERY DENSE, MOIST	5			50 9"	9.9	3	SANDSTONE, SILTY, FINE TO COARSE GRAINED WITH FINE GRAINED LENSES, TAN, VERY DENSE, MOIST	5			50 7"	9.1	3
				50 5"	10.4	3					50 5"	4.2	3
CLAYSTONE, VERY SANDY, BROWN, HARD, MOIST	10			50 6"	12.0	4		10			50 4"	6.6	3
CLAYSTONE-SILTSTONE, VERY SANDY, GRAY BROWN, HARD, MOIST	15			50 4"	10.1	4		15			50 4"	10.0	3
	20							20					



ENTECH
ENGINEERING, INC.

505 ELKTON DRIVE
 COLORADO SPRINGS, COLORADO 80907

TEST BORING LOG

DRAWN:	DATE:	CHECKED:	DATE:
		LLL	6/22/22

JOB NO.:
 221458

FIG NO.:
 B-1

TEST BORING NO. 3
 DATE DRILLED 11/15/2011
 Job # 221458

TEST BORING NO. 4
 DATE DRILLED 11/15/2011
 CLIENT CASA'S LIMITED PARTNERSHIP
 LOCATION EAGLE RISING SUBDIVISION

REMARKS	Depth (ft)	Symbol	Samples	Blows per foot	Watercontent %	Soil Type	REMARKS	Depth (ft)	Symbol	Samples	Blows per foot	Watercontent %	Soil Type
DRY TO 15', 11/16/11							WATER @ 14.5', 11/16/11						
SAND, SILTY, FINE TO COARSE GRAINED, BROWN, VERY DENSE, MOIST				50 6"	9.9	1	SAND, SLIGHTLY SILTY, FINE TO COARSE GRAINED, BROWN, VERY DENSE, MOIST				50 6"	10.2	1
CLAYSTONE-SILTSTONE, VERY SANDY, BROWN, HARD, MOIST	5			50 5"	11.8	4	SANDSTONE, SLIGHTLY SILTY, FINE TO COARSE GRAINED, VERY DENSE, MOIST	5			50 6"	11.1	3
	10			50 6"	15.6	4		10			50 5"	14.7	3
SANDSTONE, SILTY, FINE TO COARSE GRAINED, BROWN, VERY DENSE, MOIST	15			50 4"	8.7	3	CLAYSTONE, VERY SANDY, GRAY, HARD, VERY MOIST	15			50 3"	16.6	4
	20							20					



ENTECH
ENGINEERING, INC.

505 ELKTON DRIVE
 COLORADO SPRINGS, COLORADO 80907

TEST BORING LOG

DRAWN:	DATE:	CHECKED:	DATE:
		LL	6/22/22

JOB NO.:
 221458

FIG NO.:
 B-2

TEST BORING NO. 5
 DATE DRILLED 4/9/2012
 Job # 221458

TEST BORING NO. 6
 DATE DRILLED 4/9/2012
 CLIENT CASA'S LIMITED PARTNERSHIP
 LOCATION EAGLE RISING SUBDIVISION

REMARKS	Depth (ft)	Symbol	Samples	Blows per foot	Watercontent %	Soil Type	REMARKS	Depth (ft)	Symbol	Samples	Blows per foot	Watercontent %	Soil Type
DRY TO 14', 4/10/12							DRY TO 14', 4/10/12						
SAND, SILTY, FINE TO MEDIUM GRAINED, BROWN, MEDIUM DENSE, MOIST				25	2.6	1	SAND, VERY SILTY, FINE TO MEDIUM GRAINED, BROWN, MEDIUM DENSE, MOIST				16	4.3	1
SANDSTONE, SILTY, FINE TO MEDIUM GRAINED, TAN, VERY DENSE, MOIST	5			50 7"	8.2	3	CLAY, SILTY, BROWN, VERY STIFF, MOIST	5			43	16.0	2
	10			50 6"	8.7	3	SANDSTONE, SILTY, FINE TO MEDIUM GRAINED, TAN, VERY DENSE, MOIST	10			50 6"	11.3	3
	15			50 6"	10.8	3		15			50 6"	11.3	3
	20							20					



ENTECH
ENGINEERING, INC.

505 ELKTON DRIVE
 COLORADO SPRINGS, COLORADO 80907

TEST BORING LOG


DRAWN:	DATE:	CHECKED:	DATE:
		LLI	6/22/22

JOB NO.:
 221458

FIG NO.:
 B-3

APPENDIX C: Laboratory Test Results

UNIFIED CLASSIFICATION	SM	CLIENT	CASA'S LIMITED PARTNERSHIP
SOIL TYPE #	1	PROJECT	EAGLE RISING SUBDIVISION
TEST BORING #	3	JOB NO.	221458
DEPTH (FT)	2-3	TEST BY	BL



U.S. Sieve #	Percent Finer
3"	
1 1/2"	
3/4"	
1/2"	100.0%
3/8"	98.6%
4	95.2%
10	64.5%
20	45.0%
40	36.3%
100	23.9%
200	18.9%

Atterberg Limits
 Plastic Limit
 Liquid Limit
 Plastic Index

Swell
 Moisture at start
 Moisture at finish
 Moisture increase
 Initial dry density (pcf)
 Swell (psf)



**ENTECH
ENGINEERING, INC.**

505 ELKTON DRIVE
COLORADO SPRINGS, COLORADO 80907

**LABORATORY TEST
RESULTS**


DRAWN:	DATE:	CHECKED: LLL	DATE: 6/22/22
--------	-------	-----------------	------------------

JOB NO:
221458

FIG NO:

C-1

<u>UNIFIED CLASSIFICATION</u>	SM-SW	<u>CLIENT</u>	CASA'S LIMITED PARTNERSHIP
<u>SOIL TYPE #</u>	1	<u>PROJECT</u>	EAGLE RISING SUBDIVISION
<u>TEST BORING #</u>	4	<u>JOB NO.</u>	221458
<u>DEPTH (FT)</u>	2-3	<u>TEST BY</u>	BL



<u>U.S. Sieve #</u>	<u>Percent Finer</u>
3"	
1 1/2"	
3/4"	
1/2"	
3/8"	
4	100.0%
10	98.4%
20	84.1%
40	55.4%
100	33.1%
200	10.9%

<u>Atterberg Limits</u>	
Plastic Limit	NP
Liquid Limit	NV
Plastic Index	NP

<u>Swell</u>	
Moisture at start	
Moisture at finish	
Moisture increase	
Initial dry density (pcf)	
Swell (psf)	



**ENTECH
ENGINEERING, INC.**

505 ELKTON DRIVE
COLORADO SPRINGS, COLORADO 80907


**LABORATORY TEST
RESULTS**

<u>DRAWN:</u>	<u>DATE:</u>	<u>CHECKED:</u>	<u>DATE:</u>
		LLL	6/22/22

JOB NO.:
221458

FIG NO.:
C-2

UNIFIED CLASSIFICATION	SM	CLIENT	CASA'S LIMITED PARTNERSHIP
SOIL TYPE #	1	PROJECT	EAGLE RISING SUBDIVISION
TEST BORING #	6	JOB NO.	221458
DEPTH (FT)	2-3	TEST BY	BL



U.S. Sieve #	Percent Finer
3"	
1 1/2"	
3/4"	
1/2"	
3/8"	100.0%
4	99.0%
10	91.6%
20	76.1%
40	62.6%
100	49.1%
200	48.3%

Atterberg Limits
 Plastic Limit
 Liquid Limit
 Plastic Index

Swell
 Moisture at start
 Moisture at finish
 Moisture increase
 Initial dry density (pcf)
 Swell (psf)



ENTECH ENGINEERING, INC.
 505 ELKTON DRIVE
 COLORADO SPRINGS, COLORADO 80907


LABORATORY TEST RESULTS

DRAWN:	DATE:	CHECKED:	DATE:
		LL	6/22/22

JOB NO.:
221458

FIG NO.:
C-3

UNIFIED CLASSIFICATION	CL	CLIENT	CASA'S LIMITED PARTNERSHIP
SOIL TYPE #	2	PROJECT	EAGLE RISING SUBDIVISION
TEST BORING #	6	JOB NO.	221458
DEPTH (FT)	5	TEST BY	BL



U.S. Sieve #	Percent Finer
3"	
1 1/2"	
3/4"	
1/2"	
3/8"	
4	
10	
20	
40	
100	100.0%
200	99.0%

Atterberg Limits
 Plastic Limit
 Liquid Limit
 Plastic Index

Swell	
Moisture at start	15.0%
Moisture at finish	23.3%
Moisture increase	8.3%
Initial dry density (pcf)	99
Swell (psf)	510



**ENTECH
ENGINEERING, INC.**

505 ELKTON DRIVE
COLORADO SPRINGS, COLORADO 80907


**LABORATORY TEST
RESULTS**

DRAWN:	DATE:	CHECKED:	DATE:
		LLL	6/22/22

JOB NO.:
221458

FIG NO.:
C-4

UNIFIED CLASSIFICATION	SM	CLIENT	CASA'S LIMITED PARTNERSHIP
SOIL TYPE #	3	PROJECT	EAGLE RISING SUBDIVISION
TEST BORING #	1	JOB NO.	221458
DEPTH (FT)	2-3	TEST BY	BL



U.S. Sieve #	Percent Finer
3"	
1 1/2"	
3/4"	
1/2"	
3/8"	100.0%
4	93.0%
10	72.6%
20	59.6%
40	38.3%
100	23.5%
200	12.3%

Atterberg Limits
 Plastic Limit
 Liquid Limit
 Plastic Index

Swell
 Moisture at start
 Moisture at finish
 Moisture increase
 Initial dry density (pcf)
 Swell (psf)




ENTECH ENGINEERING, INC.
 505 ELKTON DRIVE
 COLORADO SPRINGS, COLORADO 80907

LABORATORY TEST RESULTS

DRAWN:	DATE:	CHECKED:	DATE:
		LLL	6/22/22

JOB NO.: 221458
 FIG NO.: C-5

UNIFIED CLASSIFICATION	SM	CLIENT	CASA'S LIMITED PARTNERSHIP
SOIL TYPE #	3	PROJECT	EAGLE RISING SUBDIVISION
TEST BORING #	2	JOB NO.	221458
DEPTH (FT)	2-3	TEST BY	BL



U.S. Sieve #	Percent Finer
3"	
1 1/2"	
3/4"	
1/2"	
3/8"	
4	
10	
20	100.0%
40	96.5%
100	42.0%
200	28.4%

Atterberg Limits	
Plastic Limit	33
Liquid Limit	35
Plastic Index	2

Swell	
Moisture at start	
Moisture at finish	
Moisture increase	
Initial dry density (pcf)	
Swell (psf)	



**ENTECH
ENGINEERING, INC.**

505 ELKTON DRIVE
COLORADO SPRINGS, COLORADO 80907


**LABORATORY TEST
RESULTS**

DRAWN:	DATE:	CHECKED:	DATE:
		LLL	6/22/22

JOB NO.:
221458

FIG NO.:
C-6

UNIFIED CLASSIFICATION	SM-SW	CLIENT	CASA'S LIMITED PARTNERSHIP
SOIL TYPE #	3	PROJECT	EAGLE RISING SUBDIVISION
TEST BORING #	4	JOB NO.	221458
DEPTH (FT)	5	TEST BY	BL



U.S. Sieve #	Percent Finer
3"	
1 1/2"	
3/4"	
1/2"	
3/8"	100.0%
4	96.3%
10	67.7%
20	35.0%
40	22.5%
100	13.5%
200	10.9%

**Atterberg
Limits**
Plastic Limit
Liquid Limit
Plastic Index

Swell
Moisture at start
Moisture at finish
Moisture increase
Initial dry density (pcf)
Swell (psf)



**ENTECH
ENGINEERING, INC.**

505 ELKTON DRIVE
COLORADO SPRINGS, COLORADO 80907


**LABORATORY TEST
RESULTS**

DRAWN:	DATE:	CHECKED:	DATE:
		LLL	6/22/22

JOB NO:
221458

FIG NO:
L-7

UNIFIED CLASSIFICATION	SM	CLIENT	CASA'S LIMITED PARTNERSHIP
SOIL TYPE #	3	PROJECT	EAGLE RISING SUBDIVISION
TEST BORING #	5	JOB NO.	221458
DEPTH (FT)	5	TEST BY	BL



U.S. Sieve #	Percent Finer
3"	
1 1/2"	
3/4"	
1/2"	
3/8"	100.0%
4	95.1%
10	80.7%
20	63.1%
40	47.1%
100	37.8%
200	37.2%

Atterberg Limits
 Plastic Limit
 Liquid Limit
 Plastic Index

Swell
 Moisture at start
 Moisture at finish
 Moisture increase
 Initial dry density (pcf)
 Swell (psf)



**ENTECH
ENGINEERING, INC.**

505 ELKTON DRIVE
COLORADO SPRINGS, COLORADO 80907


**LABORATORY TEST
RESULTS**

DRAWN:	DATE:	CHECKED: LLC	DATE: 6/22/22
--------	-------	-----------------	------------------

JOB NO.:
221458

FIG NO.:
C-8

UNIFIED CLASSIFICATION	CL	CLIENT	CASA'S LIMITED PARTNERSHIP
SOIL TYPE #	4	PROJECT	EAGLE RISING SUBDIVISION
TEST BORING #	1	JOB NO.	221458
DEPTH (FT)	10	TEST BY	BL



U.S. Sieve #	Percent Finer
3"	
1 1/2"	
3/4"	
1/2"	
3/8"	100.0%
4	96.5%
10	88.3%
20	79.5%
40	74.8%
100	65.2%
200	51.4%

Atterberg Limits	
Plastic Limit	19
Liquid Limit	37
Plastic Index	18

Swell	
Moisture at start	9.3%
Moisture at finish	20.7%
Moisture increase	11.4%
Initial dry density (pcf)	100
Swell (psf)	410



**ENTECH
ENGINEERING, INC.**

505 ELKTON DRIVE
COLORADO SPRINGS, COLORADO 80907


**LABORATORY TEST
RESULTS**

DRAWN:	DATE:	CHECKED:	DATE:
		LL	6/22/22

JOB NO.:
221458

FIG NO.:
C-9

UNIFIED CLASSIFICATION	CL-ML	CLIENT	CASA'S LIMITED PARTNERSHIP
SOIL TYPE #	4	PROJECT	EAGLE RISING SUBDIVISION
TEST BORING #	1	JOB NO.	221458
DEPTH (FT)	15	TEST BY	BL



U.S. Sieve #	Percent Finer
3"	
1 1/2"	
3/4"	
1/2"	
3/8"	100.0%
4	97.8%
10	89.8%
20	79.9%
40	74.1%
100	62.4%
200	53.1%

Atterberg Limits	
Plastic Limit	21
Liquid Limit	28
Plastic Index	7

Swell	
Moisture at start	9.9%
Moisture at finish	17.5%
Moisture increase	7.6%
Initial dry density (pcf)	103
Swell (psf)	60



**ENTECH
ENGINEERING, INC.**

505 ELKTON DRIVE
COLORADO SPRINGS, COLORADO 80907

**LABORATORY TEST
RESULTS**

DRAWN:

DATE:

CHECKED:

DATE:

LLL


6/22/22

JOB NO.:
221458

FIG NO.:

L-10

UNIFIED CLASSIFICATION	CL-ML	CLIENT	CASA'S LIMITED PARTNERSHIP
SOIL TYPE #	4	PROJECT	EAGLE RISING SUBDIVISION
TEST BORING #	3	JOB NO.	221458
DEPTH (FT)	10	TEST BY	BL



U.S. Sieve #	Percent Finer
3"	
1 1/2"	
3/4"	
1/2"	
3/8"	100.0%
4	99.7%
10	97.8%
20	94.6%
40	89.1%
100	71.9%
200	56.6%

Atterberg Limits	
Plastic Limit	7
Liquid Limit	12
Plastic Index	5

Swell	
Moisture at start	
Moisture at finish	
Moisture increase	
Initial dry density (pcf)	
Swell (psf)	



**ENTECH
ENGINEERING, INC.**

505 ELKTON DRIVE
COLORADO SPRINGS, COLORADO 80907

**LABORATORY TEST
RESULTS**

DRAWN:	DATE:	CHECKED:	DATE:
		LLL	6/22/22


JOB NO.:
221458

FIG NO.:
C-11

CONSOLIDATION TEST RESULTS

TEST BORING #	6	DEPTH(ft)	5
DESCRIPTION	CL	SOIL TYPE	2
NATURAL UNIT DRY WEIGHT (PCF)			105
NATURAL MOISTURE CONTENT			17.3%
SWELL/CONSOLIDATION (%)			-0.1%

JOB NO. 221458
 CLIENT CASA'S LIMITED PARTNERSHIP
 PROJECT EAGLE RISING SUBDIVISION



ENTECH
ENGINEERING, INC.

505 ELKTON DRIVE
 COLORADO SPRINGS, COLORADO 80907

**SWELL CONSOLIDATION
 TEST RESULTS**

DRAWN:	DATE:	CHECKED:	DATE:
		LLL	6/22/22


JOB NO.:
 221458

FIG NO.:
 C-12

CONSOLIDATION TEST RESULTS

TEST BORING #	3	DEPTH(ft)	10
DESCRIPTION	CL-MI SOIL TYPE	4	
NATURAL UNIT DRY WEIGHT (PCF)	116		
NATURAL MOISTURE CONTENT	15.7%		
SWELL/CONSOLIDATION (%)	1.0%		

JOB NO. 221458
 CLIENT CASA'S LIMITED PARTNERSHIP
 PROJECT EAGLE RISING SUBDIVISION



ENTECH ENGINEERING, INC.
 505 ELKTON DRIVE
 COLORADO SPRINGS, COLORADO 80907

SWELL CONSOLIDATION TEST RESULTS			
DRAWN:	DATE:	CHECKED:	DATE:
		LLL	6/22/22

JOB NO.: 221458
 FIG NO.: C-13

**APPENDIX D: Embankment Fill and Water Line Fill,
Density Reports, Entech Job No. 131928**

April 18, 2014

Casas Limited Partnership #4
P.O. Box 2076
Colorado Springs, CO 80901



ENTECH
ENGINEERING, INC.

505 ELKTON DRIVE
COLORADO SPRINGS, CO 80907
PHONE (719) 531-5599
FAX (719) 531-5238

Attn: Steve Jacobs

Re: Subsurface Soil Investigation
North Dam, Eagle Rising
El Paso County, Colorado

Dear Mr. Jacobs:

As requested, personnel have conducted a Subsurface Soil Investigation at the above referenced site. At the time of the investigation, the central area of the dam had been excavated approximately 8 to 10 feet. The Subsurface Soil Investigation consisted of drilling two test borings in the excavated area on April 2, 2014. The Test Boring Logs are included with this letter.


Eight feet of loose to medium dense silty sands were encountered overlying clayey sand and clayey sandstone. Groundwater was encountered at 7 and 8 feet in the test borings.

To minimize seepage in the dam, it is recommended the central area (core of the dam) be excavated down to clayey sand or sandstone and replaced with compacted clayey sand. The silty sand can be used on the dam faces. The compacted soil should be free of organics, debris and cobbles greater than 3-inches in diameter. The base of the excavation should be stabilized and compacted prior to fill placement. All fill placed within the area should be approved by Entech, and be compacted to a minimum of 92 percent of the soils maximum dry density as determined by the Modified Proctor Test (ASTM D-1557) for sands and a minimum of 95 percent of the soils maximum dry density as determined by the Standard Proctor Test (ASTM D-698) for clayey materials. Fill material should be placed in horizontal lifts such that each finished lift has a compacted thickness of six inches or less. Fill should be placed at water contents conducive to achieving adequate compaction, usually within ± 2 percent of the optimum water content as determined by ASTM D-1557. Entech Engineering Inc. should observe and test fill placement to ensure proper compaction.

We trust that this has provided you with the information you required. If you have any questions or need additional information, please do not hesitate to contact us.

Respectfully Submitted,


ENTECH ENGINEERING, INC.



Kristen A. Andrew-Hoeser, P.G.
Engineering Geologist

KAH/lpb

Entech Job No. 131928
2MSW/1eV/2013/131928ssi

Reviewed by:


Joseph C. Goode, Jr., P.E.
President



TEST BORING NO. 1
 DATE DRILLED 4/2/2014
 Job # 221458

TEST BORING NO. 2
 DATE DRILLED 4/2/2014
 CLIENT CASA'S LIMITED PARTNERSHIP
 LOCATION EAGLE RISING SUBDIVISION

REMARKS	Depth (ft)	Symbol	Samples	Blows per foot	Watercontent %	Soil Type	REMARKS	Depth (ft)	Symbol	Samples	Blows per foot	Watercontent %	Soil Type
WATER @ 8', 4/2/14							WATER @ 7', 4/2/14						
SAND, SILTY, FINE TO COARSE GRAINED, TAN, MEDIUM DENSE TO LOOSE, MOIST	5			11	6.8		SAND, SILTY, FINE TO COARSE GRAINED, BROWN, LOOSE TO MEDIUM DENSE, MOIST	5			6	6.7	
	5			9	5.1			5			12	10.9	
SAND, CLAYEY, FINE GRAINED, GRAY BROWN, LOOSE, VERY MOIST	10			6	27.0		SANDSTONE, CLAYEY, FINE TO COARSE GRAINED, GRAY, VERY DENSE, MOIST	10			50 11"	11.0	
SANDSTONE, CLAYEY, FINE TO COARSE GRAINED, GRAY, VERY DENSE, MOIST	15			50 10"	13.5			15					
	20							20					



ENTECH
ENGINEERING, INC.

505 ELKTON DRIVE
 COLORADO SPRINGS, COLORADO 80907

TEST BORING LOG

DRAWN:	DATE:	CHECKED:	DATE:
--------	-------	----------	-------

JOB NO.:
 131928

FIG NO.:
 A-



ENTECH
ENGINEERING, INC.

505 ELKTON DRIVE
COLORADO SPRINGS, CO 80907
PHONE (719) 531-5599
FAX (719) 531-5238

May 13, 2014

Casas Limited Partnership #4
PO Box 2076
Colorado Spring, CO 80901

Attn: Steve Jacobs

Re: Density Testing – Embankment Fill
70 Acre Kurie Road Parcel
Black Forest, Colorado
Report No. 4, Tests 28 and 29

Dear Mr. Jacobs:

As requested, personnel of Entech Engineering, Inc. have performed density testing at the above referenced site.

Density testing on this site was performed on May 5, 2014. The density testing indicates that the materials have been adequately compacted at the depths and locations noted. Results of the density tests are attached with this letter.

We trust that this has provided you with the information you required. Should you have any questions or need further information, please do not hesitate to contact us.

Respectfully Submitted,

ENTECH ENGINEERING, INC.


Joseph C. Goode, Jr., P.E.
President

JCG/pw

Encl.

Entech Job No. 131928
3MSW/DEN/2013/ 131928.1c1c





Client: Casas Limited Partnership #4	Entech Job #: 131928.1	Proctor Value Key: M = modified, ASTM D-1557 S = standard, ASTM D-698 T = AASHTO, T-180
Project: 70 Acre Kurie Road Parcel	Tested By: J. Lynn	
Subject: Embankment Fill	Report Date: 05-15-2014	

Test #	Test Location	Testing Date	Percent Compaction	Percent Required	Percent Moisture	Soil Type	Proctor Type/Value	Pass/Fail <input checked="" type="checkbox"/> = Fail
28	Downstream slope on the south dam, center of the dam, at grade.	5/5/14	98	95	13.8	SC	M - 117.9 @ 12.9	<input type="checkbox"/>
29	Downstream slope on the south dam, 30' west of the east end of the dam, at grade.	5/5/14	96	95	13.1	SC	M - 117.9 @ 12.9	<input type="checkbox"/>

Comments:

Scope of Observation: PERIODIC; CONTRACTOR'S OR CLIENT'S REPRESENTATIVE ADVISED

All dimensions are approximate. Cl. = Centerline

	<p>ENTECH ENGINEERING, INC. 505 Elkton Drive Colorado Springs, CO 80907 (719) 531-5599 • (719) 531-5238 (fax)</p>	<p>FIELD DENSITY RESULTS</p>	 <p>Joseph C. Goode, Jr., P.E.</p>
--	--	------------------------------	--



ENTECH
ENGINEERING, INC.

505 ELKTON DRIVE
COLORADO SPRINGS, CO 80907
PHONE (719) 531-5599
FAX (719) 531-5238

April 30, 2014

Casa's Limited Partnership #4
PO Box 2076
Colorado Spring, CO 80901

Attn: Steve Jacobs

Re: Density Testing – Water Line Trench Backfill
70 Acre Kurie Road Parcel
Black Forest, Colorado
Report No. 1, Test 1

Dear Mr. Jacobs:

As requested, personnel of Entech Engineering, Inc. have performed density testing at the above referenced site.

Density testing on this site was performed on April 25, 2014. The density testing indicates that the materials have been adequately compacted at the depth and location noted. Results of the density tests are attached with this letter.

We trust that this has provided you with the information you required. Should you have any questions or need further information, please do not hesitate to contact us.

Respectfully Submitted,

ENTECH ENGINEERING, INC.


Joseph C. Goode, Jr., P.E.
President

JCG/pw

Encl.

Entech Job No. 131928
3MSWIDEN/2013/ 131928.3cl





Client: Casas Limited Partnership #4	Entech Job #: 131928.3	Proctor Value Key: M = modified, ASTM D-1557 S = standard, ASTM D-698 T = AASHTO, T-180
Project: 70 Acre Kurie Road Parcel	Tested By: J. Lynn	
Subject: Water Line Trench Backfill	Report Date: 04-29-2014	

Test #	Test Location	Testing Date	Percent Compaction	Percent Required	Percent Moisture	Soil Type	Proctor Type/Value	Pass/Fail <input checked="" type="checkbox"/> = Fail
1	Kurie Road, 50' north of the hydrant, 4' below grade.	4/25/14	95	95	10.3	SM	M - 125.9 @ 9.0	<input type="checkbox"/>

Comments:

Scope of Observation: PERIODIC; CONTRACTOR'S OR CLIENT'S REPRESENTATIVE ADVISED

All dimensions are approximate. Cl. = Centerline

 <p>ENTECH ENGINEERING, INC. 505 Elkton Drive Colorado Springs, CO 80907 (719) 531-5599 • (719) 531-5238 (fax)</p>	<p>FIELD DENSITY RESULTS</p>	 <p>Joseph C. Goode, Jr., P.E.</p>
---	------------------------------	--



ENTECH
ENGINEERING, INC.

505 ELKTON DRIVE
COLORADO SPRINGS, CO 80907
PHONE (719) 531-5599
FAX (719) 531-5238

May 7, 2014

Casa's Limited Partnership #4
PO Box 2076
Colorado Spring, CO 80901

Attn: Steve Jacobs

Re: Density Testing – Water Line Trench Backfill
70 Acre Kurie Road Parcel
Black Forest, Colorado
Report No. 2, Tests 2 and 3

Dear Mr. Jacobs:

As requested, personnel of Entech Engineering, Inc. have performed density testing at the above referenced site.

Density testing on this site was performed on April 28 through 30, 2014. The density testing indicates that the materials have been adequately compacted at the depths and locations noted. Results of the density tests are attached with this letter.

We trust that this has provided you with the information you required. Should you have any questions or need further information, please do not hesitate to contact us.

Respectfully Submitted,

ENTECH ENGINEERING, INC.


Joseph C. Goode, Jr., P.E.
President

JCG/pw

Encl.

Entech Job No. 131928
3MSW/DEN/2013/ 131928.3cda





Client: Casas Limited Partnership #4	Entech Job #: 131928.3	Proctor Value Key: M = modified, ASTM D-1557 S = standard, ASTM D-698 T = AASHTO, T-180
Project: 70 Acre Kurie Road Parcel	Tested By: J. Lynn	
Subject: Water Line Trench Backfill	Report Date: 05-06-2014	

Test #	Test Location	Testing Date	Percent Compaction	Percent Required	Percent Moisture	Soil Type	Proctor Type/Value	Pass/Fail <input checked="" type="checkbox"/> = Fail
2	45' south of the driveway to 10235 Kurie Road, 2' below grade.	4/28/14	96	95	9.4	SM	M - 125.9 @ 9.0	<input type="checkbox"/>
3	In the driveway to 10185 Kurie Road, 75' south of the north end of the driveway entrance, at grade.	4/30/14	96	95	9.6	SM	M - 125.9 @ 9.0	<input type="checkbox"/>

Comments:

Scope of Observation: PERIODIC; CONTRACTOR'S OR CLIENT'S REPRESENTATIVE ADVISED

All dimensions are approximate. Cl. = Centerline

	<p>ENTECH ENGINEERING, INC. 505 Elston Drive Colorado Springs, CO 80907 (719) 531-5688 • (719) 531-5238 (fax)</p>	<p>FIELD DENSITY RESULTS</p>	 <p>Joseph C. Goode, Jr., P.E.</p>
--	--	------------------------------	--



ENTECH
ENGINEERING, INC.

505 ELKTON DRIVE
COLORADO SPRINGS, CO 80907
PHONE (719) 531-5599
FAX (719) 531-5238

May 13, 2014

Casa's Limited Partnership #4
PO Box 2076
Colorado Spring, CO 80901

Attn: Steve Jacobs

Re: Density Testing – Water Line Trench Backfill
70 Acre Kurie Road Parcel
Black Forest, Colorado
Report No. 3, Tests 4 and 5

Dear Mr. Jacobs:

As requested, personnel of Entech Engineering, Inc. have performed density testing at the above referenced site.

Density testing on this site was performed on May 5, 2014. The density testing indicates that the materials have been adequately compacted at the depths and locations noted. Results of the density tests are attached with this letter.

We trust that this has provided you with the information you required. Should you have any questions or need further information, please do not hesitate to contact us.

Respectfully Submitted,

ENTECH ENGINEERING, INC.


Joseph C. Goode, Jr., P.E.
President

JCG/pw

Encl.

Entech Job No. 131928
3MISW/DEN/2013/ 131928.3cb





Client: Casas Limited Partnership #4	Entech Job #: 131928.3	Proctor Value Key: M = modified, ASTM D-1557 S = standard, ASTM D-698 T = AASHTO, T-180
Project: 70 Acre Kurie Road Parcel	Tested By: J. Lynn	
Subject: Water Line Trench Backfill	Report Date: 05-12-2014	

Test #	Test Location	Testing Date	Percent Compaction	Percent Required	Percent Moisture	Soil Type	Proctor Type/Value	Pass/Fail <input checked="" type="checkbox"/> = Fail
4	In the driveway to House #10195, 105' north of the gate by the house, 2' below grade.	5/5/14	95	95	9.1	SM	M - 125.9 @ 9.0	<input type="checkbox"/>
5	In the driveway to House #10195, 200' north of the gate by the house, at grade.	5/5/14	96	95	8.7	SM	M - 125.9 @ 9.0	<input type="checkbox"/>

Comments:

Scope of Observation: PERIODIC; CONTRACTOR'S OR CLIENT'S REPRESENTATIVE ADVISED

All dimensions are approximate. Cl. = Centerline

	<p>ENTECH ENGINEERING, INC. 505 Elkton Drive Colorado Springs, CO 80907 (719) 531-5899 • (719) 531-5238 (fax)</p>	<p>FIELD DENSITY RESULTS</p>	 <p>Joseph C. Goode, Jr., P.E.</p>
--	--	------------------------------	--

APPENDIX E: Soil Survey Descriptions

El Paso County Area, Colorado

8—Blakeland loamy sand, 1 to 9 percent slopes

Map Unit Setting

National map unit symbol: 369v
Elevation: 4,600 to 5,800 feet
Mean annual precipitation: 14 to 16 inches
Mean annual air temperature: 46 to 48 degrees F
Frost-free period: 125 to 145 days
Farmland classification: Not prime farmland

Map Unit Composition

Blakeland and similar soils: 98 percent
Minor components: 2 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Blakeland

Setting

Landform: Hills, flats
Landform position (three-dimensional): Side slope, talf
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Alluvium derived from sedimentary rock and/or eolian deposits derived from sedimentary rock

Typical profile

A - 0 to 11 inches: loamy sand
AC - 11 to 27 inches: loamy sand
C - 27 to 60 inches: sand

Properties and qualities

Slope: 1 to 9 percent
Depth to restrictive feature: More than 80 inches
Drainage class: Somewhat excessively drained
Runoff class: Low
Capacity of the most limiting layer to transmit water (Ksat): High to very high (5.95 to 19.98 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate, maximum content: 5 percent
Available water supply, 0 to 60 inches: Low (about 4.5 inches)

Interpretive groups

Land capability classification (irrigated): 3e
Land capability classification (nonirrigated): 6e
Hydrologic Soil Group: A
Ecological site: R049XB210CO - Sandy Foothill
Hydric soil rating: No

Minor Components

Other soils

Percent of map unit: 1 percent

Hydric soil rating: No

Pleasant

Percent of map unit: 1 percent

Landform: Depressions

Hydric soil rating: Yes

Data Source Information

Soil Survey Area: El Paso County Area, Colorado

Survey Area Data: Version 19, Aug 31, 2021

El Paso County Area, Colorado

40—Kettle gravelly loamy sand, 3 to 8 percent slopes

Map Unit Setting

National map unit symbol: 368g
Elevation: 7,000 to 7,700 feet
Farmland classification: Not prime farmland

Map Unit Composition

Kettle and similar soils: 85 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Kettle

Setting

Landform: Hills
Landform position (three-dimensional): Side slope
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Sandy alluvium derived from arkose

Typical profile

E - 0 to 16 inches: gravelly loamy sand
Bt - 16 to 40 inches: gravelly sandy loam
C - 40 to 60 inches: extremely gravelly loamy sand

Properties and qualities

Slope: 3 to 8 percent
Depth to restrictive feature: More than 80 inches
Drainage class: Somewhat excessively drained
Runoff class: Low
Capacity of the most limiting layer to transmit water (Ksat): High
(2.00 to 6.00 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water supply, 0 to 60 inches: Low (about 3.4 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 4e
Hydrologic Soil Group: B
Ecological site: F048AY908CO - Mixed Conifer
Hydric soil rating: No

Minor Components

Other soils

Percent of map unit:
Hydric soil rating: No

Pleasant

Percent of map unit:

Landform: Depressions

Hydric soil rating: Yes

Data Source Information

Soil Survey Area: El Paso County Area, Colorado

Survey Area Data: Version 19, Aug 31, 2021

El Paso County Area, Colorado

71—Pring coarse sandy loam, 3 to 8 percent slopes

Map Unit Setting

National map unit symbol: 369k

Elevation: 6,800 to 7,600 feet

Farmland classification: Not prime farmland

Map Unit Composition

Pring and similar soils: 85 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Pring

Setting

Landform: Hills

Landform position (three-dimensional): Side slope

Down-slope shape: Linear

Across-slope shape: Linear

Parent material: Arkosic alluvium derived from sedimentary rock

Typical profile

A - 0 to 14 inches: coarse sandy loam

C - 14 to 60 inches: gravelly sandy loam

Properties and qualities

Slope: 3 to 8 percent

Depth to restrictive feature: More than 80 inches

Drainage class: Well drained

Runoff class: Low

Capacity of the most limiting layer to transmit water (Ksat): High
(2.00 to 6.00 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Available water supply, 0 to 60 inches: Low (about 6.0 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 3e

Hydrologic Soil Group: B

Ecological site: R048AY222CO - Loamy Park

Hydric soil rating: No

Minor Components

Pleasant

Percent of map unit:

Landform: Depressions

Hydric soil rating: Yes

Other soils

Percent of map unit:

Hydric soil rating: No

Data Source Information

Soil Survey Area: El Paso County Area, Colorado

Survey Area Data: Version 19, Aug 31, 2021