



INNOVATIVE DESIGN. **CLASSIC RESULTS.**

**MASTER DEVELOPMENT DRAINAGE PLAN
AMENDMENT AND
PRELIMINARY DRAINAGE REPORT
FOR
FOREST LAKES (FILINGS 5, 6, & 7)
EL PASO COUNTY, COLORADO**

November 2018

Prepared for:
FOREST LAKES RESIDENTIAL DEVELOPMENT, LLC
6385 CORPORATE DRIVE, SUITE 200
COLORADO SPRINGS CO 80919
(719) 592-9333

Prepared by:
CLASSIC CONSULTING ENGINEERS & SURVEYORS
619 N. CASCADE AVENUE, SUITE 200
COLORADO SPRINGS CO 80903
(719) 785-0790

Job no. 1175.21


PCD File No. PUDSP181



MASTER DEVELOPMENT DRAINAGE PLAN AMENDMENT AND PRELIMINARY DRAINAGE REPORT FOR FOREST LAKES (FIL. 5, 6, & 7)

ENGINEER'S STATEMENT:

The attached drainage plan and report were prepared under my direction and supervision and are correct to the best of my knowledge and belief. Said drainage report has been prepared according to the criteria established by the El Paso County for drainage reports and said report is in conformity with the master plan of the drainage basin. I accept responsibility for any liability caused by any negligent acts, errors, or omissions on my part in preparing this report.



Kyle R Campbell, Colorado P.E. #29794

3-19-19

Date

DEVELOPER'S STATEMENT:

I, the developer, have read and will comply with all of the requirements specified in this drainage report and plan.

Business Name: Forest Lakes Residential Development, LLC

By: _____

Title: _____

Managing Partner

Address: 6385 Corporate Drive, Suite 200

Colorado Springs, CO 80919

EL PASO COUNTY ONLY:

Filed in accordance with the requirements of the Drainage Criteria Manual, Volumes 1 and 2, El Paso County Engineering Criteria Manual and Land Development Code as amended.

Jennifer Irvine, P.E.

County Engineer / ECM Administrator

Approved

by Elizabeth Nijkamp

El Paso County Planning and Community Development

on behalf of Jennifer Irvine, County Engineer, ECM Administrator



04/01/2019 5:01:37 PM



MASTER DEVELOPMENT DRAINAGE PLAN AMENDMENT AND PRELIMINARY DRAINAGE REPORT FOR FOREST LAKES (FIL. 5, 6, & 7)

TABLE OF CONTENTS:

PURPOSE	Page 4
PROJECT DESCRIPTION	Page 4
PREVIOUS REPORTS	Page 5
SOILS & GEOLOGY	Page 6
DRAINAGE CRITERIA	Page 6
FLOODPLAIN STATEMENT	Page 7
EXISTING MAJOR DRAINAGEWAYS	Page 7
PROPOSED DRAINAGE CONDITIONS	Page 8
DRAINAGE AND BRIDGE FEES	Page 14
SUMMARY	Page 14
REFERENCES	Page 15

APPENDICES

VICINITY MAP
SOILS MAP (S.C.S. SURVEY)
F.E.M.A. MAP
EXISTING CONDITIONS CALCULATIONS
DEVELOPED CONDITIONS CALCULATIONS
DETENTION POND "A"
DETENTION POND "B"
DETENTION POND "C"
DRAINAGE MAPS



MASTER DEVELOPMENT DRAINAGE PLAN AMENDMENT AND PRELIMINARY DRAINAGE REPORT FOR FOREST LAKES (FIL. 5, 6, & 7)

PURPOSE

This document is the Master Development Drainage Plan Amendment and Preliminary Drainage Report for Forest Lakes (Filings 5, 6, & 7). The purpose of this report is to identify general onsite and offsite drainage patterns, storm sewer corridors and areas tributary to the site, and to safely route developed storm water runoff to adequate treatment and outfall facilities. Based upon the revisions to the Filings 5, 6, & 7 site layout. The proposed Filings 5, 6, & 7 development shall be in adherence to the El Paso County approved Master Development Drainage Plan for Forest Lakes as well as current County Drainage Criteria.

PROJECT DESCRIPTION

The Forest Lakes development is a phased master planned community located in northern El Paso County, Colorado. The master planned land includes areas of open space, residential, trails, drainage, preservation and two water supply reservoirs. The property lies to the east of Pike National Forest, north of the United States Air Force Academy, west of Interstate 25 and south of the Town of Monument. The Forest Lakes property is located in portions of Sections 27, 28, 29 and 33 of Township 11 South, Range 67 West of the Sixth Principal Meridian and covers approximately 900 acres. The proposed amendment area (Filings 5, 6, & 7) is the far westerly area east of Filing 1 and is comprised of 287 acres. Watersheds that impact the Filings 5, 6, & 7 property include Beaver Creek, Hell Creek and North Beaver Creek. These watersheds are tributary to Monument Creek. Monument Creek itself passes along the eastern boundary of the overall Forest Lakes property in a north to south direction. The purpose of the amended Master Development Drainage Plan analysis is to provide existing and updated developed peak flow data for the 5-year and 100-year recurrence intervals within the Filings 5, 6, & 7 portion of the property. This information has been used to develop overall drainage design information and to identify the required storm drainage and flood control facilities within the Filings 5, 6, & 7 property. The vicinity map for the Filings 5, 6, & 7 Amendment area is presented in the Appendix of this report.

The initial approved Master Development Drainage Plan titled, "Forest Lakes Master Development Drainage Plan", was approved by Kiowa Engineering Corporation and dated April 11, 2002. The following is an excerpt from that report:

"The hydrology analysis for the initially approved Forest Lakes Master Development Drainage Plan was completed in three phases. The first phase is a regional hydrologic analysis. The regional hydrology model uses an elliptical rainfall distribution patterns based upon Hydromet 52. The regional analysis was conducted in order to assess the development's overall impact upon peak



discharges within Monument Creek as it passes in Forest Lakes development. The hydrology development in the Monument Creek Drainage Basin Planning Study (DBPS) was utilized as a basis for the regional analysis. The existing and developed basin hydrologic conditions were analyzed. The second phase was a localized hydrologic analysis that focused upon determining the peak discharges along the major drainageways within the property. For this phase, a Type II storm pattern was assumed over the drainage basins associated with the Forest Lakes development. This analysis was developed in order to provide information in use in modeling floodplains and sizing of major drainageway facilities. The third phase was an on-site developed condition hydrologic analysis, using the Rational Method to determine the peak flows within the property to size and locate on site hydraulic structures.”

For this Filings 5, 6, & 7 Amendment, detailed analysis of initial/local systems will be deferred to the future final drainage reports when platting is proposed.

Presented on Exhibit A (map from initial MDDP in appendix) is information for the major sub-watershed information that impact the Forest Lakes property, including Hell Creek, Beaver Creek and North Beaver Creek. The sub-watersheds shown on Exhibit A were used in the hydrologic analysis for the regional and localized hydrologic analysis described above. Beaver Creek courses through the center of the Forest Lakes Development from west to east. The most significant feature within the Beaver Creek watershed is Bristlecone Lake and Pinon Lake which are not affected by this Filings 5, 6, & 7 Amendment. These lakes and their embankments were constructed in 1986 as water supply reservoirs.

The site is located within the Beaver Creek Drainage Basin.

PREVIOUS REPORTS

Several studies were reviewed in the preparation of the initial Master Development Drainage Plan and this Filings 5, 6, & 7 Amendment. These studies include:

1. Master Plan Level Geologic Hazards Evaluation and Preliminary Geotechnical Investigation, Forest Lakes Master Development Plan, prepared by CTL/Thompson, Inc. dated July 31, 2001.
2. Forest Lakes Master Development Drainage Plan, prepared by Kiowa Engineering Corporation dated April 11, 2002.
3. City of Colorado Springs and El Paso County Flood Insurance Study, prepared by Federal Emergency Management Agency, dated Marcy 1997.



4. City of Colorado Springs Drainage Criteria Manual Volume 1, May 2014.
5. Drainage Criteria Manual (Volume 3) latest revision April 2008, Urban Drainage and Flood Criteria District.
6. Baseline Hydrology Study, Monument Creek Drainage Basin Planning Study, prepared by CH2M Hill, Inc. and Kiowa Engineering Corporation dated May 1992.
7. Forest Lakes Master Drainage Plan and Phase 1 Drainage Report, prepared by KKBNA, Inc. dated November 1986.
8. Procedures for Determining Peak Flows in Colorado, Incorporates and Supplements Technical Release No. 55, prepared by Soil Conservation Service, dated March 1980.

The Forest Lakes Master Development Drainage Plan (MDDP) dated November 1986, was prepared as a part of the planning for the property which originally began in 1986. This MDDP (1986) was prepared using the City/County drainage criteria that were in affect at the time. Peak flow data was developed for the watersheds that pass through the property. Drainageway improvements, detention basin plans and roadway crossing sizes were developed for the proposed development condition for the initially developed areas.

SOILS AND GEOLOGY

Soils within the watersheds that are tributary to the Forest Lakes property vary between soil types A through D, as identified by the U.S. Department of Agriculture, Soil Conservation Service. Soils are classified in hydrologic groups A, B, C, and D according to their infiltration capacity. Type D soils are dominant in the forested areas west of Monument Creek. These soils are generally associated with the Pikes Peak Granite found in the region. This is particularly true for the forested portion of the Beaver Creek watershed. The decomposed granite soils exhibit extremely high rates of runoff and are very susceptible to erosion and sedimentation. Hydrologic Soils Group A soils consist chiefly of well-drained sand and gravel and have a low runoff potential. The soils within the Forest Lakes property are predominantly soil type B. See Appendix for additional information.

DRAINAGE CRITERIA

The hydrology for the major sub-watersheds (i.e., Beaver Creek), were estimated using the methods outlined in the initial Master Development Drainage Plan. Exhibit A presents the major sub-watersheds that impact the Forest Lakes property. All updated calculations for the Filings 5, 6, & 7 Amendment area were performed using the following:



Hydrologic calculations were performed using the City of Colorado Springs/El Paso County Drainage Criteria Manual, as revised in November 1991 and October 1994. Stormwater quality analysis and Extended Detention Basin (EDB) design are per the Urban Drainage and Flood Control District Manual and UD-BMP Version 3.01 spreadsheet. The Preliminary drainage calculations within this report use the Rational Method to estimate stormwater runoff to the three pond locations. Future Final Drainage Report(s) will provide a more detailed basin breakdown and utilize this runoff method to calculate the runoff to each inlets and storm sewer pipes. Also, the future Final Drainage Reports will provide the final design for each of the three full spectrum detention and water quality facilities and detailed IRF calculations/exhibits to support the tributary impervious values used.

FLOODPLAIN STATEMENT

A portion of this site is located within a floodplain as determined by the Flood Insurance Rate Maps (F.I.R.M.) Map Numbers 08041 C0267G, CO266G, CO258G, & CO259G effective date, December 7, 2018 (See Appendix for overlay exhibit). No proposed development is anticipated to take place within the floodplain other than one proposed roadway crossing as reflected on the drainage maps.

EXISTING MAJOR DRAINAGEWAYS

Three major drainageways flow onto the Forest Lakes site, including North Beaver Creek, South Beaver Creek and Hell Creek. Hell Creek, North and South Beaver Creek converge in the western portion of the site to form Beaver Creek. Beaver Creek continues through the site on an easterly course through Bristle Cone Lake over the reservoir spillway. The drainageways are well defined and heavily vegetated. The bottom width of the drainageways range from 5-feet in the smaller Hell Creek to 10-feet in the larger Beaver Creek.

The intent of the Filings 5, 6, & 7 site development is to leave the major drainageways in their existing form to the greatest practical extent possible. Developed runoff is routed to the three full spectrum detention and water quality facilities prior to releasing into these downstream channels. The original MDDP provided channel hydraulic analysis and determined with the use of full spectrum detention for the developed runoff, there are no channel improvements required. Therefore, there is no need for any additional hydraulic studies within these channels. Minimal disturbance only to the fringe of the wetland areas is proposed, no mouse area disturbance is anticipated. Proper permitting for the wetlands disturbance will be in place prior to any construction.



One road crossing of the existing drainageway is planned with Filings 5, 6, & 7. This crossing will be along North Beaver Creek upstream of the confluence between North and South Beaver Creek. The proposed culverts under the road crossings along North Beaver Creek have been designed to convey the 100-year Bulked Stream Flow (debris flow rate) from the CTL Thompson study of 4,130 cfs. A full hydraulic analysis will be completed with the Final Drainage Report and will meet the allowable bridge clearance criteria of at least 2 feet of freeboard between the box culvert ceiling and 100-yr water surface elevation. Per the CTL Thompson 'Debris Flow Report', we will work with the original HEC-RAS model to properly design this culvert to pass the entire debris flow rate.

PROPOSED DRAINAGE CONDITIONS

As reflected in the approved Kiowa MDDP, the site is influenced by off-site tributary flows from the west and north. Also, as reflected in the MDDP, on-site full spectrum detention and water quality facilities will detain and treat the developed runoff from the proposed site prior to releasing at or below historic rates to the downstream channels. As previously mentioned, the rational method was used to estimate developed runoff values. Appropriate peak runoff calculations have been used and will be verified with the future final drainage reports.

DESIGN POINT 1 ($Q_5 = 54.8$ cfs and $Q_{100} = 132.2$ cfs) is the developed runoff from the proposed single family development, Basin A, 37.55 acres. This runoff is collected in a public storm sewer system and routed to the proposed Full Spectrum Detention and Storm Water Quality Facility – Pond A. This facility is an extended detention basin (EDB) per the current drainage criteria and UDFCD (Urban Drainage Flood Control District) standards. A composite impervious value was determined using the Site-Level Low Impact Development (LID) Design Effective Impervious Calculator (IRF Form) located in the Appendix of this report. With the tributary area of 37.55 acres and a calculated 41.4% imperviousness, the total required Excess Urban Runoff Volume (EURV) is 1.642 Ac.-ft. A future Final Drainage Report will provide the detailed breakdown used on the IRF form and exact tributary imperviousness value for each pond.

Impact structures or other means of energy dissipation will be provided at all pipe daylight point into and out of the proposed ponds and bypass storm systems. Final pond design, outlet structure sizing, trickle channel and forebay details will be included with final construction drawings for review and approval by El Paso County prior to construction approval. The EURV design of this pond ensures that all discharges (2, 5, 10, 25, 50 and 100 year) will be released at or below historic release rates. Two preliminary pond sizing forms (UD-Detention v.3.07 & EDB Design Procedure Form) are included in the Appendix of this report and show the following outlet box features in order to maintain release rates at or below historic levels:



4' wide by 4' deep outlet box

4" initial surcharge volume, 350 square feet, 2.5' deep micropool (bottom = 7105.50)

Bottom of pond/top of Micropool = 7108.00

EURV = Top of Box = 7114.00 Required EURV = 1.642 ac.-ft. Provided EURV = 1.83 ac.-ft.

- (3) orifice holes - 3 square inch bottom hole (1" x 3")
- 4 square inch middle hole (2" x 2")
- 4 square inch top hole (2" x 2")

30" RCP outlet pipe at invert out = 7107.80

45' length emergency spillway at 7117.00, Top of pond berm elevation = 7120.00, 12' wide minimum width.

Using an equivalent undeveloped area of land, Basin EX-A of 37.55 acres, a historic release rate and thus an allowable release rate for Pond A is $Q_5 = 12.1$ cfs and $Q_{100} = 80.9$ cfs. Per the UD-Detention form, the restricted release rate from the facility is $Q_5 = 0.67$ cfs and $Q_{100} = 52.1$ cfs with a 100-year water surface elevation in the pond of 7116.46. Final pond design and release rates will be finalized with the final drainage report for the proposed subdivision.

DESIGN POINT 2 ($Q_5 = 22.0$ cfs and $Q_{100} = 147.5$ cfs) is the historic undeveloped runoff from the off-site Basin OS-1, 77.01 acres of adjacent national forest. This runoff sheet flows east directly toward the proposed lots and cul-de-sac roadways. A series of CDOT Type C grate inlets will be installed along the eastern edge of Basin OS-1, behind the lots to intercept this historic runoff prior to draining into the proposed development. A bypass or diversion pipe system will be installed from these grated inlets to the south and into the proposed development but this pipe will not connect with the proposed development runoff and Pond A tributary storm pipe. Swales and berming will be installed to route this historic runoff to the grated inlets. In the event of inlet clogging the overflow path will be down the shared lot line swales of the adjacent home lots. Riprap or concrete 'V'-notched swales will be installed along these shared lot lines when the proposed home lots back up to the significant hill side throughout the property. Maintenance of these grated inlets and diversion storm pipe system is by the Forest Lakes Metro District. Energy dissipation of this historic runoff will be provided at the exit point of this bypass main into the South Beaver Creek corridor. Future final drainage reports will discuss erosion protection and adequate downstream corridors from all pipe release points to the existing channels.

DESIGN POINT 3 ($Q_5 = 23.7$ cfs and $Q_{100} = 186.5$ cfs) is the combined runoff from the historic bypass of Design Point 2 and the release rate of Pond A into the South Beaver Creek mouse limits. The historic release rate into South



Beaver Creek from this portion of the development is $Q_5 = 32.7$ cfs and $Q_{100} = 219.5$ cfs. Therefore, the proposed development will not hinder the downstream corridor as the flow rates are less than in the existing conditions.

DESIGN POINT 4 ($Q_5 = 64.1$ cfs and $Q_{100} = 176.0$ cfs) is the developed runoff from the proposed single family development and existing open space area, Basin B, 59.94 acres. This runoff is collected in a public storm sewer system and routed to the proposed Full Spectrum Detention and Storm Water Quality Facility – Pond B. This facility is an extended detention basin (EDB) per the current drainage criteria and UDFCD (Urban Drainage Flood Control District) standards. A Preliminary composite impervious value was determined using the Site-Level Low Impact Development (LID) Design Effective Impervious Calculator (IRF Form) located in the Appendix of this report. With the tributary area of 59.94 acres and a calculated 28.8% imperviousness, the total required Excess Urban Runoff Volume (EURV) is 1.771 Ac.-ft. A future Final Drainage Report will provide the detailed breakdown used on the IRF form and exact tributary imperviousness value for each pond.

Impact structures or other means of energy dissipation will be provided at all pipe daylight point into and out of the proposed ponds and bypass storm systems. Final pond design, outlet structure sizing, trickle channel and forebay details will be included with final construction drawings for review and approval by El Paso County prior to construction approval. The EURV design of this pond ensures that all discharges (2, 5, 10, 25, 50 and 100 year) will be released at or below historic release. Two preliminary pond sizing forms (UD-Detention v.3.07 & EDB Design Procedure Form) are included in the Appendix of this report and show the following outlet box features in order to maintain release rates at or below historic levels:

6' wide by 4' deep outlet box

5" initial surcharge volume, 350 square feet, 2.5' deep micropool (bottom = 7049.50)

Bottom of pond/top of Micropool = 7054.00

EURV = Top of Box = 7059.80 Required EURV = 1.771 ac.-ft. Provided EURV = 1.92 ac.-ft.

- (3) orifice holes - 4 square inch bottom hole (2" x 2")**
- 8 square inch middle hole (4" x 2")**
- 12 square inch top hole (4" x 3")**

30" RCP outlet pipe at invert out = 7051.80

50' length emergency spillway at 7063.00, Top of pond berm elevation = 7066.00, 12' wide minimum width.

Using an equivalent undeveloped area of land, Basin EX-B of 37.55 acres, a historic release rate and thus an allowable release rate for Pond B is $Q_5 = 18.7$ cfs and $Q_{100} = 125.6$ cfs. Per the UD-Detention form, the restricted release rate



from the facility is $Q_5 = 1.3$ cfs and $Q_{100} = 84.2$ cfs with a 100-year water surface elevation in the pond of 7062.75. Final pond design and release rates will be finalized with the final drainage report for the proposed subdivision.

DESIGN POINT 5 ($Q_5 = 1441$ cfs and $Q_{100} = 4130$ cfs) is the interpolated historic flow rate within North Beaver Creek channel from the referenced CTL Thompson Debris Flow report. This runoff rate is much higher than the MDDP 100-year rate of 2,950 cfs. The purpose of including this design point and basin in this analysis is to show that the runoff rate in South Beaver Creek is less with the installation of the proposed three detention facilities for the developed runoff. This historic runoff stays within the established North Beaver Creek corridor and continues south-east into the proposed development toward Design Point 6.

DESIGN POINT 6 ($Q_5 = 1433$ cfs and $Q_{100} = 4116$ cfs) is the flow rate within North Beaver Creek channel from DP-5 and Basin D, 24.98 acres of onsite property mostly comprised of open space/undeveloped area. At this location is a proposed roadway crossing (Mesa Top Drive) and (3) single cell box culverts (8' high x 15' wide @ 0.50% grade) to convey this runoff to the south and Design Point 9. A UD-Culvert v.3.04 from UDFCD (located in the Appendix) was used to preliminarily estimate the headwater depth and provide riprap energy dissipation calculations; Type M riprap, 80' length of protection and 63' wide. Preliminary box culvert sizing was also completed using the Bentley FlowMaster program, results included in the Appendix and include a velocity less than 20 ft/sec and normal depth less of 4.63'. The inside of the box culvert is 8' high, therefore there is 3.37' of freeboard over the debris flow rate within the box culvert. As previously mentioned, a full hydraulic analysis will be completed with the Final Drainage Report and in conjunction with CTL Thompson and the HEC-RAS channel model. This runoff continues south to Design Point 9.

DESIGN POINT 7 ($Q_5 = 9.8$ cfs and $Q_{100} = 66.1$ cfs) is the runoff generated from off-site Basin OS-3, 10.31 acres of existing large lot single family homes and undeveloped land to the north, and onsite Basin F, 16.61 acres of 2 large home lots (over 5 acre lots). The majority of these lots will remain undeveloped except for the driveway and actual home footprint, and as these lots are over 5 acres in size, detention and water quality is not required. Therefore, multiple grated inlets will intercept this runoff and a diversion/bypass pipe will route the runoff to the south-west along Mesa Top Drive and directly discharging into North Beaver Creek. Design Point 8 also contains bypass runoff and connects to this system prior to discharging into the creek. As with all proposed storm sewer, these grated inlets and diversion pipe will be owned and maintained by the Forest Lakes Metro District.



DESIGN POINT 8 ($Q_5 = 8.7$ cfs and $Q_{100} = 58.2$ cfs) is the runoff generated from off-site Basin OS-2, 19.91 acres of existing large lot single family homes and undeveloped land to the north, and onsite Basin E, 8.96 acres of 2 large home lots (over 5 acre lots). The majority of these lots will remain undeveloped except for the driveway and actual home footprint, and as these lots are over 5 acres in size, detention and water quality is not required. Therefore, multiple grated inlets will intercept this runoff and a diversion/bypass pipe will route the runoff to the south, connecting with the bypass main from Design Point 7. Energy dissipation of this historic runoff will be provided at the exit point of this bypass main into the North Beaver Creek corridor, downstream of the box culvert crossing at Design Point 6.

DESIGN POINT 9 ($Q_5 = 1440$ cfs and $Q_{100} = 4164$ cfs) is the combined flow rate within North Beaver Creek channel downstream of the proposed box culverts and discharge point from Design Points 7 & 8. This runoff continues south-east in the natural North Beaver Creek corridor where it combines with the release from Pond B at Design Point 10.

DESIGN POINT 10 ($Q_5 = 1441$ cfs and $Q_{100} = 4192$ cfs) is the runoff within North Beaver Creek channel downstream of Design Point 9 and including the restricted release rate from Pond B. The historic release rate into North Beaver Creek in the undeveloped conditions is $Q_5 = 1448$ cfs and $Q_{100} = 4216$ cfs. Therefore, the proposed development will not hinder the downstream corridor as the flow rates are less than in the existing conditions.

DESIGN POINT 11 ($Q_5 = 46.9$ cfs and $Q_{100} = 117.2$ cfs) is the developed runoff from the proposed single family development and existing open space area, Basin C, 30.28 acres. This runoff is collected in a public storm sewer system and routed to the proposed Full Spectrum Detention and Storm Water Quality Facility – Pond C. This facility in an extended detention basin (EDB) per the current drainage criteria and UDFCD (Urban Drainage Flood Control District) standards. A composite impervious value was determined using the Site-Level Low Impact Development (LID) Design Effective Impervious Calculator (IRF Form) located in the Appendix of this report. With the tributary area of 30.28 acres and a calculated 35.5% imperviousness, the total required Excess Urban Runoff Volume (EURV) is 1.121 Ac.-ft. A future Final Drainage Report will provide the detailed breakdown used on the IRF form and exact tributary imperviousness value for each pond. The emergency spillway for this facility will drain onto the proposed Forest Lakes Drive and south through the open space between Lots 27 & 28 and into Beaver Creek.

Impact structures or other means or energy dissipation will be provided at all pipe daylight point into and out of the proposed ponds and bypass storm systems. Final pond design, outlet structure sizing, trickle channel and forebay details will be included with final construction drawings for review and approval by El Paso County prior to construction



approval. The EURV design of this pond ensures that all discharges (2, 5, 10, 25, 50 and 100 year) will be released at or below historic release. Two preliminary pond sizing forms (UD-Detention v.3.07 & EDB Design Procedure Form) are included in the Appendix of this report and show the following outlet box features in order to maintain release rates at or below historic levels:

6' wide by 4' deep outlet box

4" initial surcharge volume, 350 square feet, 2.5' deep micropool (bottom = 7027.50)

Bottom of pond/top of Micropool = 7030.00

EURV = Top of Box = 7034.00 Required EURV = 1.121 ac.-ft. Provided EURV = 1.18 ac.-ft.

- (3) orifice holes - 3 square inch bottom hole (1" x 3")**
- 3 square inch middle hole (1" x 3")**
- 6 square inch top hole (2" x 3")**

30" RCP outlet pipe at invert out = 7029.80

38' length emergency spillway at 7039.00, Top of pond berm elevation = 7042.00, 12' wide minimum width.

Using an equivalent undeveloped area of land, Basin EX-C of 37.55 acres, a historic release rate and thus an allowable release rate for Pond C is $Q_5 = 10.2$ cfs and $Q_{100} = 68.6$ cfs. Per the UD-Detention form, the restricted release rate from the facility is $Q_5 = 0.55$ cfs and $Q_{100} = 33.5$ cfs with a 100-year water surface elevation in the pond of 7035.70. Final pond design and release rates will be finalized with the final drainage report for the proposed subdivision.

DESIGN POINT 12 ($Q_5 = 1442$ cfs and $Q_{100} = 4200$ cfs) is the runoff within North Beaver Creek channel downstream of Design Point 10 and including the restricted release rate from Pond C. The historic release rate into North Beaver Creek in the undeveloped conditions is $Q_5 = 1452$ cfs and $Q_{100} = 4242$ cfs. Therefore, the proposed development will not hinder the downstream corridor as the flow rates are less than in the existing conditions.

EURV and Stormwater Quality Capture Volume: The standard Extended Detention Basin spreadsheet has been provided in the Appendix of this report to provide sizing based upon UDFCD requirements for EURV, with a minimum drain time of 72 hours. A PUD Modification is proposed for this project due to areas of proposed home lots (back yards only) directly discharging into the adjacent floodplain and Preble's Jumping Mouse limits. All major imperviousness (roads, driveways, and rooftops) are all treated by downstream full spectrum detention and water quality facilities. There is a 300'+ open space (native vegetation) between the property line (end of back yards) and waters of the State of Colorado; and other than a small patio, no additional anticipated imperviousness within the direct release back yard drainage basins.



Detention Maintenance, Ownership and Access: The Metro District for Forest Lakes will own and maintain Detention Facility A, B and C. Access to the pond will be provided per the current El Paso County Criteria and UDFCD criteria. An El Paso County Detention Pond Maintenance Agreement will be required indicating these Facilities to be ultimately owned and maintained by the Metro District.

DRAINAGE AND BRIDGE FEES

Forest Lakes Filings 5, 6, & 7 is to be platted in the future and is within the Beaver Creek Miscellaneous Drainage Basin. The fees in place at the time of platting will be calculated within future Final Drainage Reports.

If available, existing Drainage Fee credits will be utilized to offset portions of the required fees due for this development, as to be defined in future Final Drainage Reports. Multiple plats are anticipated for this Filings 5, 6, & 7 area.

SUMMARY

Developed runoff from the proposed Forest Lakes Filings 5, 6, & 7 are proposed to outfall to three proposed public storm systems serving three separate Full Spectrum Detention and Storm Water Quality facilities (owned and maintained by the Forest Lakes Metropolitan District) prior to discharging to downstream facilities. The proposed Full Spectrum detention/water quality ponds were sized using the current and applicable drainage criteria and provide release rates below existing allowable release rates and therefore the proposed development does not overburden downstream facilities. Future Final Drainage Reports will further define and provide additional analysis for all on-site storm facilities as the project moves forward.

PREPARED BY:



Matthew Larson
Project Manager

Sm/117521/MDDP Amendment.doc



REFERENCES

1. City of Colorado Springs and El Paso County Drainage Criteria Manual Volume 1, May 2014.
2. Drainage Criteria Manual (Volume 3) latest revision April 2008, Urban Drainage and Flood Criteria District.
3. "Forest Lakes Master Development Drainage Plan," by Kiowa Engineering Corporation, revised April 11, 2002.
4. "Preliminary and Final Drainage Report Forest Lakes Subdivision Filing No. 1," by Kiowa Engineering Corporation, filed September 8, 2004.
5. "Drainage Report Amendment for Preliminary and Final Drainage Report Forest Lakes Subdivision Filing No. 1," by Classic Consulting Engineers & Surveyors, LLC, dated August 2015.
6. "Debris Flow/Mudflow Analysis Forest Lakes Subdivision (Phase 2) Lindbergh Road and W. Baptist Road El Paso County, Colorado," by CTL Thompson Inc., dated August 6, 2018.



VICINITY MAP







FIGURE 1
VICINITY MAP
FOREST LAKES MDDP

000135figure(F)(6.5x11)(01/08/02)

SOILS MAP (S.C.S. SURVEY)





Map Scale: 1:11,600 if printed on A landscape (11" x 8.5") sheet.




Map projection: Web Mercator Corner coordinates: WGS84 Edge tics: UTM Zone 13N WGS84




FILS-7
SITE

MAP LEGEND



MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
 Web Soil Survey URL:
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: El Paso County Area, Colorado
 Survey Area Data: Version 16, Sep 10, 2018

Soil Survey Area: Pike National Forest, Eastern Part, Colorado,
 Parts of Douglas, El Paso, Jefferson, and Teller Counties
 Survey Area Data: Version 5, Sep 10, 2018

Your area of interest (AOI) includes more than one soil survey area. These survey areas may have been mapped at different scales, with a different land use in mind, at different times, or at different levels of detail. This may result in map unit symbols, soil properties, and interpretations that do not completely agree across soil survey area boundaries.

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Jul 4, 2010—Oct 16, 2017

MAP LEGEND

MAP INFORMATION

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Hydrologic Soil Group

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
38	Jarre-Tecolote complex, 8 to 65 percent slopes	B	247.0	38.2%
65	Perrypark gravelly sandy loam, 3 to 9 percent slopes	B	33.1	5.1%
68	Peyton-Pring complex, 3 to 8 percent slopes	B	190.3	29.4%
Subtotals for Soil Survey Area			470.3	72.8%
Totals for Area of Interest			646.2	100.0%

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
2	Aquolls, 1 to 10 percent slopes	A/D	0.0	0.0%
22	Kassler very gravelly coarse sandy loam, 5 to 35 percent slopes	A	68.0	10.5%
43	Sphinx gravelly coarse sandy loam, 40 to 70 percent slopes	D	6.0	0.9%
46	Sphinx-Rock outcrop complex, 15 to 80 percent slopes	D	12.5	1.9%
47	Sphinx, warm-Rock outcrop complex, 15 to 80 percent slopes	D	75.2	11.6%
48	Tecolote very gravelly sandy loam, 15 to 40 percent slopes, very stony	B	14.1	2.2%
Subtotals for Soil Survey Area			175.8	27.2%
Totals for Area of Interest			646.2	100.0%

Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.


Rating Options

Aggregation Method: Dominant Condition

Component Percent Cutoff: None Specified

Tie-break Rule: Higher

F.E.M.A. MAP



N:\11752 DRAWINGS\EXHIBITS\FEMA MAP OVERLAY.dwg, 2/19/2019 9:49:56 AM, 1:500

29

29

28

PIKE NATIONAL FOREST
EL PASO COUNTY

PIKE NATIONAL FOREST
EL PASO COUNTY

MAP NO. 08041 C0258G

MAP NO. 08041 C0259G

MAP NO. 08041 C0266G

MAP NO. 08041 C0267G

EL PASO COUNTY
UNINCORPORATED AREAS
080059

EL PASO COUNTY
UNINCORPORATED AREAS
080059

EL PASO COUNTY
UNINCORPORATED AREAS
080059

FLOODING EFFECTS FROM
NORTH BEAVER CREEK

ZONE AE

ZONE AE

ZONE AE

ZONE AE

ZONE AE

ZONE AE

ZONE
AE

LIMIT OF
STUDY

LIMIT OF
STUDY

SPAATZ RD

Unnamed Road

North Beaver Creek

North Beaver Creek

North Beaver Creek

Beaver Creek

Beaver Creek

Beaver Creek


FOREST LAKES DR

DIAMONDBACK RD

DIAMONDBACK RD

32

↑
N
1" = 500'



**EXISTING CONDITIONS CALCULATIONS
(FROM PREVIOUSLY APPROVED KIOWA MDDP)**



Forest Lakes MDDP
Time of Concentration Calculation

Basin Design	Contributing Basin	Channel Slope	Channel Slope	Channel Length	Channel Length	Channel Velocity	Channel Velocity	Channel Velocity	Channel Velocity	Channel Velocity	Basin Design
		(%)	(%)	(ft)	(ft)	(ft/sec)	(ft/sec)	(ft/sec)	(ft/sec)	(ft/sec)	
OS1		20.0%	20.0%	1000 ft	900 ft	0.9 ft/sec	5.0 ft/sec	1112 sec.	180 sec.	21.5 min.	OS1
OS2		20.0%	20.0%	700 ft		0.8 ft/sec		931 sec.		15.5 min.	OS2
OS3		20.0%	20.0%	400 ft		0.6 ft/sec		703 sec.		11.7 min.	OS3
OS4		5.0%	5.0%	500 ft	2200 ft	0.4 ft/sec	4.0 ft/sec	1248 sec.	550 sec.	30.0 min.	OS4
OSSA		5.0%	5.0%	400 ft	100 ft	0.4 ft/sec	5.0 ft/sec	1116 sec.	20 sec.	18.9 min.	OSSA
OSSB		4.0%	4.0%	400 ft	900 ft	0.3 ft/sec	4.0 ft/sec	1202 sec.	223 sec.	23.8 min.	OSSB
OS7		4.0%	4.0%	900 ft		0.5 ft/sec		1803 sec.		30.1 min.	OS7
DP A1	A, OS1	20.0%	14.0%	1000 ft	1370 ft	0.9 ft/sec	4.5 ft/sec	1099 sec.	304 sec.	25.0 min.	DP A1
DP C1	B, C, OS2	20.0%	8.0%	700 ft	100 ft	0.8 ft/sec	4.0 ft/sec	876 sec.	25 sec.	18.4 min.	DP C1
DP D1	A, D, OS1	20.0%	14.0%	1000 ft	1370 ft	0.9 ft/sec	4.5 ft/sec	1086 sec.	304 sec.	29.3 min.	DP D1
DP G1	G, OS3	20.0%	3.2%	750 ft	400 ft	0.8 ft/sec	3.6 ft/sec	952 sec.		17.7 min.	DP G1
DP H1	H, K, L, OS4	5.0%	5.0%	500 ft	330 ft	0.5 ft/sec	2.5 ft/sec	1101 sec.	94 sec.	23.2 min.	DP H1
DP H2	L, OS4	5.0%	5.0%	500 ft	330 ft	0.4 ft/sec	3.5 ft/sec	1145 sec.	94 sec.	24.0 min.	DP H2
DP I1	M2, O	18.0%	1.1%	450 ft	270 ft	0.6 ft/sec	2.1 ft/sec	736 sec.		14.4 min.	DP I1
DP M1	M1, M2, O	20.0%	17.9%	300 ft	420 ft	0.5 ft/sec	5.5 ft/sec	573 sec.	76 sec.	12.5 min.	DP M1
DP M2	N, S, OSSB	9.0%	10.9%	300 ft	1370 ft	0.4 ft/sec	5.0 ft/sec	748 sec.	274 sec.	17.0 min.	DP M2
DP Q1	Q, OSS, OSSA-B	4.0%	5.0%	400 ft	2700 ft	0.3 ft/sec	4.0 ft/sec	1202 sec.	675 sec.	31.3 min.	DP Q1
DP Q2	N, Q, R, S, T, U, OSS, OSSA, B	5.0%	5.3%	750 ft	3100 ft	0.5 ft/sec	4.0 ft/sec	1492 sec.	775 sec.	37.8 min.	DP Q2
DP T1	W, X, Y, Z	13.5%	2.6%	480 ft	4500 ft	0.6 ft/sec	3.0 ft/sec	815 sec.	1500 sec.	38.4 min.	DP T1
DP Z1	OSS, DD, EE, FF, GG	4.0%	3.0%	190 ft	1330 ft	0.3 ft/sec	2.1 ft/sec	563 sec.		20.0 min.	DP Z1
DP GG1		4.0%	3.0%	500 ft	2800 ft	0.4 ft/sec	3.5 ft/sec	1265 sec.	810 sec.	34.6 min.	DP GG1

Equations:

Time of Concentration (Overland) = $1.87(1.1 - C_3)L^{0.5} S^{-0.33}$

C_3 = Runoff coefficient for five-year flow

L = Length of overland flow in feet

S = Slope of flow path in percent

Velocity (Road) = $10(10.0 + 0.075S - 0.03)$

S = Slope of flow path in percent

Forest Lakes MDDP Time of Concentration Calculation

Basin Design P.	Contributing Basin		Slope		Channel		Runoff Coef.		Velocity		Channel		Channel		Basin Design P.
	Area	Basin	Channel	Slope	Channel	Area	Channel	Channel	Channel	Channel	Channel	Channel	Channel	Channel	
A	13.3%	8.8%	8.4%	300 IF	170 IF	550 IF	0.30	0.5 ft/sec	4.5 ft/sec	5.8 ft/sec	656 sec.	38 sec.	95 sec.	13.2 min.	
B	13.3%	8.0%	8.0%	300 IF	100 IF	660 IF	0.30	0.5 ft/sec	4.0 ft/sec	5.7 ft/sec	656 sec.	25 sec.	117 sec.	13.3 min.	
C	8.3%	6.7%	4.8%	300 IF	60 IF	770 IF	0.35	0.4 ft/sec	3.5 ft/sec	4.4 ft/sec	719 sec.	17 sec.	176 sec.	15.2 min.	
D	33.3%	7.4%	4.3%	540 IF	340 IF	800 IF	0.30	0.8 ft/sec	4.5 ft/sec	4.1 ft/sec	649 sec.	76 sec.	194 sec.	15.3 min.	
E	22.7%	14.8%	1.6%	440 IF	270 IF	500 IF	0.30	0.7 ft/sec	5.5 ft/sec	2.5 ft/sec	665 sec.	49 sec.	198 sec.	15.2 min.	
E1	25.0%	9.0%	9.0%	400 IF	400 IF	500 IF	0.30	0.7 ft/sec	3.0 ft/sec	6.0 ft/sec	615 sec.	200 sec.	84 sec.	11.6 min.	
F	5.8%	5.8%	4.2%	70 IF	600 IF	710 IF	0.30	0.2 ft/sec	3.0 ft/sec	4.1 ft/sec	1414 sec.	439 sec.	173 sec.	10.2 min.	
G	5.0%	5.0%	1.6%	500 IF	330 IF	500 IF	0.30	0.4 ft/sec	3.5 ft/sec	2.5 ft/sec	1174 sec.	94 sec.	198 sec.	24.4 min.	
H	24.3%	1.1%	1.1%	370 IF	270 IF	270 IF	0.38	0.6 ft/sec	5.0 ft/sec	2.1 ft/sec	597 sec.	30 sec.	128 sec.	12.1 min.	
I	15.0%	10.0%	3.2%	300 IF	150 IF	470 IF	0.47	0.7 ft/sec	5.5 ft/sec	3.6 ft/sec	568 sec.	27 sec.	132 sec.	10.0 min.	
J	23.3%	13.3%	4.4%	300 IF	300 IF	90 IF	0.35	0.5 ft/sec	5.5 ft/sec	4.2 ft/sec	615 sec.	78 sec.	21 sec.	9.8 min.	
K	13.3%	18.6%	10.9%	300 IF	1370 IF	970 IF	0.30	0.4 ft/sec	5.0 ft/sec	4.5 ft/sec	748 sec.	274 sec.	214 sec.	17.0 min.	
L	9.0%	20.0%	5.2%	300 IF	280 IF	140 IF	0.30	0.6 ft/sec	5.0 ft/sec	2.9 ft/sec	590 sec.	51 sec.	48 sec.	14.3 min.	
M	18.3%	15.1%	2.1%	300 IF	430 IF	140 IF	0.30	0.3 ft/sec	3.5 ft/sec	5.0 ft/sec	532 sec.	86 sec.	246 sec.	11.1 min.	
M1	25.0%	6.5%	5.6%	300 IF	300 IF	430 IF	0.30	0.6 ft/sec	5.0 ft/sec	4.7 ft/sec	573 sec.	76 sec.	53 sec.	10.8 min.	
M2	5.0%	17.9%	3.8%	340 IF	1580 IF	250 IF	0.35	0.6 ft/sec	3.9 ft/sec	3.9 ft/sec	523 sec.	86 sec.	33 sec.	11.0 min.	
N	21.7%	14.0%	2.7%	200 IF	1460 IF	1460 IF	0.50	0.4 ft/sec	14.60 ft/sec	3.3 ft/sec	634 sec.	406 sec.	406 sec.	17.3 min.	
O	14.7%	8.0%	2.7%	200 IF	1700 IF	1700 IF	0.50	0.3 ft/sec	17.00 ft/sec	3.3 ft/sec	476 sec.	442 sec.	442 sec.	15.3 min.	
P	8.0%	2.7%	2.7%	120 IF	220 IF	660 IF	0.30	0.7 ft/sec	3.8 ft/sec	3.8 ft/sec	364 sec.	518 sec.	518 sec.	14.7 min.	
Q	18.0%	3.6%	3.6%	500 IF	220 IF	800 IF	0.60	0.2 ft/sec	2.1 ft/sec	2.1 ft/sec	767 sec.	58 sec.	58 sec.	13.7 min.	
R	13.5%	5.3%	2.0%	480 IF	320 IF	660 IF	0.40	0.7 ft/sec	3.0 ft/sec	2.8 ft/sec	723 sec.	107 sec.	236 sec.	17.7 min.	
S	4.5%	3.0%	3.0%	430 IF	750 IF	750 IF	0.30	0.4 ft/sec	3.0 ft/sec	3.5 ft/sec	1128 sec.	0 sec.	217 sec.	22.4 min.	
T	4.5%	1.9%	1.9%	190 IF	800 IF	800 IF	0.60	0.3 ft/sec	2.7 ft/sec	2.7 ft/sec	560 sec.	293 sec.	293 sec.	14.2 min.	
U	2.2%	1.1%	1.1%	90 IF	1330 IF	1330 IF	0.60	0.2 ft/sec	2.1 ft/sec	2.1 ft/sec	468 sec.	628 sec.	628 sec.	17.3 min.	
V	2.9%	1.4%	1.4%	140 IF	630 IF	630 IF	0.60	0.3 ft/sec	2.4 ft/sec	2.4 ft/sec	468 sec.	264 sec.	264 sec.	12.2 min.	
W	2.0%	2.0%	1.9%	300 IF	300 IF	640 IF	0.60	0.4 ft/sec	2.0 ft/sec	2.7 ft/sec	771 sec.	35 sec.	35 sec.	13.4 min.	
X	1.9%	0.8%	0.8%	160 IF	360 IF	360 IF	0.60	0.3 ft/sec	1.8 ft/sec	1.8 ft/sec	576 sec.	234 sec.	234 sec.	13.5 min.	
Y	3.3%	4.7%	4.7%	60 IF	1270 IF	1270 IF	0.30	0.2 ft/sec	4.3 ft/sec	4.3 ft/sec	291 sec.	198 sec.	198 sec.	8.1 min.	
Z	20.0%	2.0%	2.0%	760 IF	300 IF	300 IF	0.30	0.8 ft/sec	2.8 ft/sec	2.8 ft/sec	913 sec.	293 sec.	293 sec.	20.1 min.	
AA	4.0%	3.0%	2.1%	500 IF	460 IF	290 IF	0.30	0.3 ft/sec	2.5 ft/sec	2.9 ft/sec	1265 sec.	184 sec.	106 sec.	22.9 min.	
BB	2.3%	2.2%	2.8%	300 IF	160 IF	860 IF	0.30	0.3 ft/sec	4.0 ft/sec	3.3 ft/sec	1172 sec.	1172 sec.	101 sec.	24.3 min.	
CC	2.2%	4.0%	2.9%	500 IF	160 IF	160 IF	0.30	0.4 ft/sec	2.5 ft/sec	3.3 ft/sec	1196 sec.	40 sec.	258 sec.	24.9 min.	
DD	4.0%	1.3%	2.4%	300 IF	300 IF	1600 IF	0.30	0.2 ft/sec	3.1 ft/sec	3.1 ft/sec	1265 sec.	64 sec.	64 sec.	22.1 min.	
EE	1.3%	16.0%	4.1%	300 IF	550 IF	1460 IF	0.30	0.5 ft/sec	5.5 ft/sec	5.5 ft/sec	1413 sec.	100 sec.	514 sec.	32.1 min.	
FF	8.0%	8.0%	4.1%	500 IF	2390 IF	1460 IF	0.30	0.5 ft/sec	4.0 ft/sec	4.0 ft/sec	1006 sec.	598 sec.	598 sec.	12.0 min.	
GG															26.7 min.
HH															
II															
JJ															

Equations:
 $Time\ of\ Concentration\ (Overland) = 1.87(L^{0.1}C)^{0.5}S^{-0.33}$
 $C_p =$ Runoff coefficient for five-year flow
 $L =$ Length of overland flow in feet
 $S =$ Slope of flow path in percent
 $Velocity\ (ft/sec) = 10(10^{0.5}S)^{0.33}$
 $S =$ Slope of flow path in percent

Forest Lakes MDDP
Runoff Coefficient Calculation

Basin	Area 1 (Slope/Asph)			Area 2 (Lawn)			Basin C ₁	Basin C ₂	Basin
	% Area	C ₁	C ₂	% Area	C ₁	C ₂			
J	37 %	0.60	0.70	63 %	0.25	0.35	0.38	0.48	J
K	63 %	0.60	0.70	38 %	0.25	0.35	0.47	0.57	K

Design Point	Basin	Area	% Area	C ₁	C ₂	C ₁	C ₂
DP AI	A	13.60 ac	19.80 %	0.30	0.40	0.06	0.08
	OS1	55.10 ac	80.20 %	0.25	0.35	0.20	0.28
		68.70 ac	100.0 %			0.26	0.36

Design Point	Basin	Area	% Area	C ₁	C ₂	C ₁	C ₂
DP CI	B	3.74 ac	17.58 %	0.30	0.40	0.05	0.07
	C	9.27 ac	43.58 %	0.35	0.45	0.15	0.20
	OS2	8.26 ac	38.83 %	0.25	0.35	0.10	0.14
		21.27 ac	100.0 %			0.30	0.40

Design Point	Basin	Area	% Area	C ₁	C ₂	C ₁	C ₂
DP DI	A	13.60 ac	15.05 %	0.30	0.40	0.05	0.06
	D	21.66 ac	23.97 %	0.30	0.40	0.07	0.10
	OS1	55.10 ac	60.98 %	0.25	0.35	0.15	0.21
		90.36 ac	100.0 %			0.27	0.37

Design Point	Basin	Area	% Area	C ₁	C ₂	C ₁	C ₂
DP GI	G	3.63 ac	18.01 %	0.30	0.40	0.05	0.07
	OS3	16.53 ac	81.99 %	0.25	0.35	0.20	0.29
		20.16 ac	100.0 %			0.26	0.36

Design Point	Basin	Area	% Area	C ₁	C ₂	C ₁	C ₂
DP HI	H	15.90 ac	58.61 %	0.30	0.40	0.18	0.23
	K	5.60 ac	20.64 %	0.47	0.57	0.10	0.12
	L	5.63 ac	20.75 %	0.35	0.45	0.07	0.09
		27.13 ac	100.0 %			0.35	0.45

Design Point	Basin	Area	% Area	C ₁	C ₂	C ₁	C ₂
DP HZ	H	15.90 ac	35.36 %	0.30	0.40	0.11	0.14
	K	5.60 ac	12.46 %	0.47	0.57	0.06	0.07
	L	5.63 ac	12.52 %	0.35	0.45	0.04	0.06
	J	15.59 ac	34.68 %	0.30	0.40	0.10	0.14
	OS4	2.24 ac	4.98 %	0.25	0.35	0.01	0.02
		44.96 ac	100.0 %			0.32	0.42

Design Point	Basin	Area	% Area	C ₁	C ₂	C ₁	C ₂
DP II	J	15.59 ac	87.44 %	0.30	0.40	0.26	0.35
	OS4	2.24 ac	12.56 %	0.25	0.35	0.03	0.04
		17.83 ac	100.0 %			0.29	0.39

Forest Lakes MDDP
Runoff Coefficient Calculation

Design Point	Basin	Area	% Area	C ₁	C ₂	C ₃	C ₄
DP Q2	N	8.09 ac	8.96 %	0.30	0.40	0.03	0.04
	Q	14.45 ac	16.00 %	0.35	0.45	0.06	0.07
	OS5,OS5A-B	67.77 ac	75.04 %	0.25	0.35	0.19	0.26
		90.31 ac	100.0 %			0.27	0.37

Design Point	Basin	Area	% Area	C ₁	C ₂	C ₃	C ₄
DP T1	N	8.09 ac	6.59 %	0.30	0.40	0.02	0.03
	Q	14.45 ac	11.77 %	0.35	0.45	0.04	0.05
	R	10.87 ac	8.85 %	0.50	0.60	0.04	0.05
	S	6.67 ac	5.43 %	0.50	0.60	0.03	0.03
	T	5.01 ac	4.08 %	0.30	0.40	0.01	0.02
	U	9.96 ac	8.11 %	0.40	0.50	0.03	0.04
	OS5,OS5A-B	67.77 ac	55.18 %	0.25	0.35	0.14	0.19
	122.82 ac	100.0 %			0.31	0.41	

DEVELOPED CONDITIONS CALCULATIONS



JOB NAME: FOREST LAKES - FILINGS 5, 6, 7
 JOB NUMBER: 1175.21
 DATE: 11/20/18
 CALCULATED BY: MAL

PRELIMINARY DRAINAGE REPORT ~ BASIN RUNOFF COEFFICIENT SUMMARY

BASIN	IMPERVIOUS AREA / STREETS				TOTAL AREA (AC)				LOTS/LANDSCAPE/UNDEV. AREAS (NOT PAVEMENT)				WEIGHTED				WEIGHTED CA			
	AREA (AC)	C(5)	C(100)		AREA (AC)	C(5)	C(100)		AREA (AC)	C(5)	C(100)		C(5)	C(100)	CA(2)	CA(5)	CA(10)	CA(25)	CA(50)	CA(100)
	A	37.55	0.90	0.96		32.65	0.32	0.51		32.65	0.32	0.51		0.40	0.57	13.18	14.86	16.59	18.97	20.00
B	59.94	0.90	0.96		52.39	0.23	0.45		52.39	0.23	0.45		0.31	0.51	15.63	18.84	22.14	26.48	28.65	30.82
C	30.28	0.90	0.96		24.55	0.25	0.46		24.55	0.25	0.46		0.37	0.55	10.01	11.29	12.88	14.72	15.75	16.79
D	24.98	0.90	0.96		24.98	0.11	0.37		24.98	0.11	0.37		0.11	0.37	1.00	2.75	4.75	6.74	7.99	9.24
E	8.96	0.90	0.96		8.96	0.09	0.36		8.96	0.09	0.36		0.09	0.36	0.27	0.81	1.52	2.33	2.78	3.23
F	16.61	0.90	0.96		16.61	0.09	0.36		16.61	0.09	0.36		0.09	0.36	0.50	1.49	2.82	4.32	5.15	5.98
OS-1	77.01	0.90	0.96		77.01	0.09	0.36		77.01	0.09	0.36		0.09	0.36	2.31	6.93	13.09	20.02	23.87	27.72
OS-2	19.91	0.90	0.96		19.91	0.09	0.36		19.91	0.09	0.36		0.09	0.36	0.60	1.79	3.38	5.18	6.17	7.17
OS-3	10.31	0.90	0.96		10.31	0.09	0.36		10.31	0.09	0.36		0.09	0.36	0.31	0.93	1.75	2.68	3.20	3.71
EX. A	37.55	0.90	0.96		37.55	0.09	0.36		37.55	0.09	0.36		0.09	0.36	1.13	3.38	6.38	9.76	11.64	13.52
EX. B	59.94	0.90	0.96		59.94	0.09	0.36		59.94	0.09	0.36		0.09	0.36	1.80	5.39	10.19	15.58	18.58	21.58
EX. C	30.28	0.90	0.96		30.28	0.09	0.36		30.28	0.09	0.36		0.09	0.36	0.91	2.73	5.15	7.87	9.39	10.90

JOB NAME: FOREST LAKES - FILINGS 5, 6, 7
 JOB NUMBER: 1175.21
 DATE: 11/20/2018
 CALCD BY: MAL

PRELIMINARY DRAINAGE REPORT ~ BASIN RUNOFF SUMMARY

BASIN	WEIGHTED					OVERLAND			STREET / CHANNEL FLOW				INTENSITY					TOTAL FLOWS					
	CA(2)	CA(5)	CA(10)	CA(25)	CA(50)	CA(100)	C(5)	Length (ft)	Height (ft)	Tc (min)	Length (ft)	Slope (%)	Velocity (fps)	Tc (min)	Tc (min)	I(2) (in/hr)	I(5) (in/hr)	I(10) (in/hr)	I(25) (in/hr)	I(50) (in/hr)	I(100) (in/hr)	Q(5) (cfs)	Q(100) (cfs)
A	13.18	14.86	16.69	18.97	20.00	21.36	0.09	330	120	10.1	1580	5.2%	8.0	3.3	13.4	2.94	3.69	4.30	4.92	5.53	6.19	54.8	132.2
B	15.63	18.84	22.14	26.48	28.65	30.82	0.09	500	170	12.7	1800	6.0%	8.6	3.5	16.2	2.72	3.40	3.97	4.54	5.10	5.71	64.1	176.0
C	10.01	11.29	12.88	14.72	15.75	16.79	0.09	60	8	6.0	2040	6.5%	8.9	3.8	9.8	3.32	4.16	4.85	5.54	6.24	6.98	46.9	117.2
D	1.00	2.75	4.75	6.74	7.99	9.24	0.09	100	20	6.8	2040	6.0%	8.6	4.0	10.8	3.21	4.02	4.69	5.36	6.03	6.75	11.0	62.4
E	0.27	0.81	1.52	2.33	2.78	3.23	0.09	150	20	9.5	720	5.3%	8.1	1.5	11.0	3.18	3.99	4.65	5.32	5.98	6.69	3.2	21.6
F	0.50	1.49	2.82	4.32	5.15	5.98	0.09	90	20	6.2	1030	6.8%	9.1	1.9	8.1	3.55	4.45	5.19	5.93	6.67	7.46	6.6	44.6
OS-1	2.31	6.93	13.09	20.02	23.87	27.72	0.09	460	64	16.4	2000	14.0%	13.1	2.5	19.0	2.53	3.17	3.70	4.23	4.76	5.32	22.0	147.5
OS-2	0.60	1.79	3.38	5.18	6.17	7.17	0.09	400	60	14.9	450	15.0%	13.6	0.6	15.5	2.78	3.47	4.05	4.63	5.21	5.83	6.2	41.8
OS-3	0.31	0.93	1.75	2.68	3.20	3.71	0.09	200	60	8.4	210	30.0%	19.2	0.2	8.6	3.48	4.35	5.09	5.81	6.54	7.32	4.0	27.2

JOB NAME: FOREST LAKES - FILINGS 5, 6, 7
 JOB NUMBER: 1175.21
 DATE: 11/20/2018
 CALC'D BY: MAL

PRELIMINARY DRAINAGE REPORT ~ BASIN RUNOFF SUMMARY

BASIN	WEIGHTED				OVERLAND			STREET / CHANNEL FLOW			INTENSITY					TOTAL FLOWS							
	CA(2)	CA(5)	CA(10)	CA(25)	CA(50)	CA(100)	C(5)	Length (ft)	Height (ft)	Tc (min)	Length (ft)	Slope (%)	Velocity (fps)	Tc (min)	Tc (min)	I(2) (in/hr)	I(5) (in/hr)	I(10) (in/hr)	I(25) (in/hr)	I(50) (in/hr)	I(100) (in/hr)	Q(5) (cfs)	Q(100) (cfs)
EX. A	1.13	3.38	6.38	9.76	11.64	13.52	0.09	420	120	12.4	1300	8.0%	9.9	2.2	14.6	2.85	3.57	4.16	4.76	5.35	5.99	12.1	80.9
EX. B	1.80	5.39	10.19	15.58	18.58	21.58	0.09	500	170	12.7	1500	6.4%	8.9	2.8	15.6	2.77	3.47	4.04	4.62	5.20	5.82	18.7	125.6
EX. C	0.91	2.73	5.15	7.87	9.39	10.90	0.09	280	46	11.4	800	3.6%	6.6	1.5	12.9	2.99	3.75	4.37	5.00	5.62	6.29	10.2	68.6

THE FOLLOWING BASINS ARE INCLUDED TO CALCULATE ALLOWABLE RELEASE RATES FROM THE PONDS

THESE BASINS MATCH THE AREAS TRIBUTARY TO EACH FACILITY AND THEREFORE A MAP IS NOT NEEDED

JOB NAME: FOREST LAKES - FILLINGS 5, 6, 7
 JOB NUMBER: 1175.21
 DATE: 11/20/18
 CALCULATED BY: MAL

PRELIMINARY DRAINAGE REPORT ~ SURFACE ROUTING SUMMARY

Design Point(s)	Contributing Basins	Equivalent CA(5)	Equivalent CA(100)	Maximum Tc	Intensity		Flow		FEATURE
					I(5)	I(100)	Q(5)	Q(100)	
1	BASIN A	14.86	21.36	13.4	3.69	6.19	54.8	132.2	POND A
2	BASIN OS-1	6.93	27.72	19.0	3.17	5.32	22.0	147.5	GRATED INLETS & BYPASS STORM
3	POND A RELEASE	0.55	7.32	13.4	3.69	6.19	2.0	45.3	30" OUTLET PIPE
4	DP-2 + POND A RELEASE	7.48	35.04	19.0	3.17	5.32	23.7	186.5	EXISTING CHANNEL
5	BASIN B	18.84	30.82	16.2	3.40	5.71	64.1	176.0	POND B
6	BASIN OS-4	1000.00	1708.50	60.0	1.44	2.42	1441.5	4129.9	FROM CTL REPORT - NORTH BEAVER CREEK DEBRIS FLOW RATE
7	DP-5 + BASIN D	1002.75	1717.74	60.5	1.43	2.40	1433.0	4116.3	Proposed Box Culvert - Triple 15' x 8'
8	BASIN F + BASIN OS-3	2.42	9.69	10.5	4.06	6.82	9.8	66.1	GRATED INLETS & BYPASS STORM
9	BASIN E + BASIN OS-2	2.60	10.39	17.0	3.34	5.60	8.7	58.2	GRATED INLETS & BYPASS STORM
10	DP-6 + DP-7 + DP-8	1007.77	1737.83	60.5	1.43	2.40	1440.1	4164.4	EXISTING CHANNEL
11	POND B RELEASE	0.65	11.31	16.2	3.40	5.71	2.2	64.6	30" OUTLET PIPE
12	DP-9 + POND B RELEASE	1008.42	1749.14	60.5	1.43	2.40	1441.1	4191.5	EXISTING CHANNEL
13	BASIN C	11.29	16.79	9.8	4.16	6.98	46.9	117.2	POND C
14	POND C RELEASE	0.29	3.51	9.8	4.16	6.98	1.2	24.5	30" OUTLET PIPE
15	DP-10 + POND C RELEASE	1008.71	1752.65	60.5	1.43	2.40	1441.5	4199.9	EXISTING CHANNEL


JOB NAME: FOREST LAKES - FILLINGS 5, 6, 7
 JOB NUMBER: 1175.21
 DATE: 11/20/18
 CALCULATED BY: MAL

PRELIMINARY DRAINAGE REPORT ~ SURFACE ROUTING SUMMARY

Design Point(s)	Contributing Basins	Equivalent CA(5)	Equivalent CA(100)	Maximum Tc	Intensity		Flow		FEATURE
					I(5)	I(100)	Q(5)	Q(100)	
THE FOLLOWING ARE TO COMPARE THE HISTORIC FLOW RATES WITHIN THE CHANNEL (UNDEVELOPED CONDITIONS)									
EX-DP-3	BASIN OS-1 + BASIN EX-A	10.31	41.24	19.0	3.17	5.32	32.7	219.5	EXISTING CHANNEL
EX-DP-10	DP-9 + BASIN EX-B	1013.16	1759.41	60.5	1.43	2.40	1447.8	4216.1	EXISTING CHANNEL
EX-DP-12	EX-DP-10 + BASIN EX-C	1015.89	1770.31	60.5	1.43	2.40	1451.7	4242.3	EXISTING CHANNEL

Determination of Culvert Headwater and Outlet Protection

Project: **FOREST LAKES PHASE 2**
 Basin ID: **DP-6 - MESA TOP ROAD CROSSING OF NORTH BEAVER CREEK**



Preliminary
Rock Protection
Calculation

Soil Type:
 Choose One:
 Sandy
 Non-Sandy

Supercritical Flow! Using Ha to calculate protection type.

Design Information (Input):	
Design Discharge	Q = <input type="text" value="4130"/> cfs
Circular Culvert:	
Barrel Diameter in Inches	D = <input type="text"/> inches
Inlet Edge Type (Choose from pull-down list)	<input type="text" value="OR"/>
Box Culvert:	
Barrel Height (Rise) in Feet	Height (Rise) = <input type="text" value="8"/> ft
Barrel Width (Span) in Feet	Width (Span) = <input type="text" value="45"/> ft
Inlet Edge Type (Choose from pull-down list)	<input type="text" value="1.5 : 1 Bevel w/ 90 Deg. Headwall"/>
Number of Barrels	No = <input type="text" value="1"/>
Inlet Elevation	Elev IN = <input type="text" value="7050"/> ft
Outlet Elevation <u>OR</u> Slope	Elev OUT = <input type="text" value="7049"/> ft
Culvert Length	L = <input type="text" value="120"/> ft
Manning's Roughness	n = <input type="text" value="0.013"/>
Bend Loss Coefficient	k _b = <input type="text" value="0"/>
Exit Loss Coefficient	k _e = <input type="text" value="1"/>
Tailwater Surface Elevation	Elev Y _t = <input type="text"/> ft
Max Allowable Channel Velocity	V = <input type="text" value="5"/> ft/s

Required Protection (Output):	
Tailwater Surface Height	Y _t = <input type="text" value="3.20"/> ft
Flow Area at Max Channel Velocity	A _t = <input type="text" value="826.00"/> ft ²
Culvert Cross Sectional Area Available	A = <input type="text" value="360.00"/> ft ²
Entrance Loss Coefficient	k _e = <input type="text" value="0.20"/>
Friction Loss Coefficient	k _f = <input type="text" value="0.23"/>
Sum of All Losses Coefficients	k _s = <input type="text" value="1.43"/> ft
Culvert Normal Depth	Y _n = <input type="text" value="3.92"/> ft
Culvert Critical Depth	Y _c = <input type="text" value="6.40"/> ft
Tailwater Depth for Design	d = <input type="text" value="7.20"/> ft
Adjusted Diameter <u>OR</u> Adjusted Rise	H _a = <input type="text" value="5.96"/> ft
Expansion Factor	1/(2*tan(θ)) = <input type="text" value="4.67"/>
Flow/Diameter ^{2.5} <u>OR</u> Flow/(Span * Rise ^{1.5})	Q/WH ^{1.5} = <input type="text" value="4.06"/> ft ^{0.5} /s
Froude Number	Fr = <input type="text" value="2.08"/> Supercritical!
Tailwater/Adjusted Diameter <u>OR</u> Tailwater/Adjusted Rise	Y _t /H = <input type="text" value="0.54"/>
Inlet Control Headwater	HW _i = <input type="text" value="9.96"/> ft
Outlet Control Headwater	HW _o = <input type="text" value="9.13"/> ft
Design Headwater Elevation	HW = <input type="text" value="7,059.96"/> ft
Headwater/Diameter <u>OR</u> Headwater/Rise Ratio	HW/H = <input type="text" value="1.25"/>
Minimum Theoretical Riprap Size	d ₅₀ = <input type="text" value="12"/> in
Nominal Riprap Size	d ₅₀ = <input type="text" value="12"/> in
UDFCD Riprap Type	Type = <input type="text" value="M"/>
Length of Protection	L _p = <input type="text" value="80"/> ft
Width of Protection	T = <input type="text" value="63"/> ft

DP-6 - MESA TOP CROSSING

Project Description

Friction Method Manning Formula
Solve For Normal Depth

Input Data

Roughness Coefficient	0.013	
Channel Slope	0.00500	ft/ft
Height	8.00	ft
Bottom Width	45.00	ft
Discharge	4130.00	ft ³ /s

Results

Normal Depth	4.63	ft
Flow Area	208.37	ft ²
Wetted Perimeter	54.26	ft
Hydraulic Radius	3.84	ft
Top Width	45.00	ft
Critical Depth	6.40	ft
Percent Full	57.9	%
Critical Slope	0.00185	ft/ft
Velocity	19.82	ft/s
Velocity Head	6.10	ft
Specific Energy	10.74	ft
Froude Number	1.62	
Discharge Full	6574.11	ft ³ /s
Slope Full	0.01267	ft/ft
Flow Type	Supercritical	

GVF Input Data

Downstream Depth	0.00	ft
Length	0.00	ft
Number Of Steps	0	

GVF Output Data

Upstream Depth	0.00	ft
Profile Description		
Profile Headloss	0.00	ft
Average End Depth Over Rise	0.00	%
Normal Depth Over Rise	57.88	%
Downstream Velocity	Infinity	ft/s

DP-6 - MESA TOP CROSSING

GVF Output Data

Upstream Velocity	Infinity	ft/s
Normal Depth	4.63	ft
Critical Depth	6.40	ft
Channel Slope	0.00500	ft/ft
Critical Slope	0.00185	ft/ft

DETENTION POND "A"



Site-Level Low Impact Development (LID) Design Effective Impervious Calculator LID Credit by Impervious Reduction Factor (IRF) Method

User Input

Calculated cells

***Design Storm: 1-Hour Rain Depth	WQCV Event	0.53	inches
***Minor Storm: 1-Hour Rain Depth	10-Year Event	1.75	inches
***Major Storm: 1-Hour Rain Depth	100-Year Event	2.52	inches
Optional User Defined Storm	CUHP		
(CUHP) NOAA 1 Hour Rainfall Depth and Frequency for User Defined Storm	100-Year Event		

Max Intensity for Optional User Defined Storm

0

Designer: Matt Larson

Company: Classic Consulting Engineers & Surveyors, LLC

Date: February 18, 2019

Project: FOREST LAKES - PHASE 2

Location: POND A - PRELIMINARY DESIGN

SITE INFORMATION (USER-INPUT)

Sub-basin Identifier	TRIB BASIN																		
Receiving Pervious Area Soil Type	Sandy Loam																		
Total Area (ac., Sum of DCIA, UIA, RPA, & SPA)	37.550																		
Directly Connected Impervious Area (DCIA, acres)	13.270																		
Unconnected Impervious Area (UIA, acres)	2.270																		
Receiving Pervious Area (RPA, acres)	0.930																		
Separate Pervious Area (SPA, acres)	21.080																		
RPA Treatment Type: Conveyance (C), Volume (V), or Permeable Pavement (PP)	C																		

CALCULATED RESULTS (OUTPUT)

Total Calculated Area (ac, check against input)	37.550																		
Directly Connected Impervious Area (DCIA, %)	35.3%																		
Unconnected Impervious Area (UIA, %)	6.0%																		
Receiving Pervious Area (RPA, %)	2.5%																		
Separate Pervious Area (SPA, %)	56.1%																		
A _s (RPA / UIA)	0.410																		
I _s Check	0.710																		
f / I for WQCV Event:	2.0																		
f / I for 10-Year Event:	0.5																		
f / I for 100-Year Event:	0.3																		
f / I for Optional User Defined Storm CUHP:																			
IRF for WQCV Event:	0.73																		
IRF for 10-Year Event:	0.93																		
IRF for 100-Year Event:	0.96																		
IRF for Optional User Defined Storm CUHP:																			
Total Site Imperviousness: I _{total}	41.4%																		
Effective Imperviousness for WQCV Event:	39.8%																		
Effective Imperviousness for 10-Year Event:	41.0%																		
Effective Imperviousness for 100-Year Event:	41.2%																		
Effective Imperviousness for Optional User Defined Storm CUHP:																			

LID / EFFECTIVE IMPERVIOUSNESS CREDITS

WQCV Event CREDIT: Reduce Detention By:	2.3%	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
10-Year Event CREDIT**: Reduce Detention By:	1.1%	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
100-Year Event CREDIT**: Reduce Detention By:	0.6%	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
User Defined CUHP CREDIT: Reduce Detention By:																			

Total Site Imperviousness: 41.4%

Total Site Effective Imperviousness for WQCV Event: 39.8%

Total Site Effective Imperviousness for 10-Year Event: 41.0%

Total Site Effective Imperviousness for 100-Year Event: 41.2%

Total Site Effective Imperviousness for Optional User Defined Storm CUHP:

Notes:

* Use Green-Ampt average infiltration rate values from Table 3-3.

** Flood control detention volume credits based on empirical equations from Storage Chapter of USDCM.

*** Method assumes that 1-hour rainfall depth is equivalent to 1-hour intensity for calculation purposes

Design Procedure Form: Extended Detention Basin (EDB)

Designer: Matt Larson
Company: Classic Consulting Engineers & Surveyors, LLC
Date: February 18, 2019
Project: FOREST LAKES - PHASE 2
Location: POND A - PRELIMINARY DESIGN

<p>1. Basin Storage Volume</p> <p>A) Effective Imperviousness of Tributary Area, I_a</p> <p>B) Tributary Area's Imperviousness Ratio ($i = I_a / 100$)</p> <p>C) Contributing Watershed Area</p> <p>D) For Watersheds Outside of the Denver Region, Depth of Average Runoff Producing Storm</p> <p>E) Design Concept (Select EURV when also designing for flood control)</p> <p>F) Design Volume (WQCV) Based on 40-hour Drain Time ($V_{DESIGN} = (1.0 * (0.91 * i^3 - 1.19 * i^2 + 0.78 * i) / 12 * Area)$)</p> <p>G) For Watersheds Outside of the Denver Region, Water Quality Capture Volume (WQCV) Design Volume ($V_{WQCV\ OTHER} = (d_s * (V_{DESIGN} / 0.43))$)</p> <p>H) User Input of Water Quality Capture Volume (WQCV) Design Volume (Only if a different WQCV Design Volume is desired)</p> <p>I) Predominant Watershed NRCS Soil Group</p> <p>J) Excess Urban Runoff Volume (EURV) Design Volume For HSG A: $EURV_A = 1.68 * i^{1.28}$ For HSG B: $EURV_B = 1.36 * i^{1.08}$ For HSG C/D: $EURV_{C,D} = 1.20 * i^{1.08}$ </p>	<p>$I_a =$ <u> 41.4 </u> %</p> <p>$i =$ <u> 0.414 </u></p> <p>Area = <u> 37.550 </u> ac</p> <p>$d_s =$ <u> 0.42 </u> in</p> <div style="border: 1px solid black; padding: 2px; margin: 5px 0;"> Choose One <input type="radio"/> Water Quality Capture Volume (WQCV) <input checked="" type="radio"/> Excess Urban Runoff Volume (EURV) </div> <p>$V_{DESIGN} =$ <u> 0.574 </u> ac-ft</p> <p>$V_{DESIGN\ OTHER} =$ <u> 0.561 </u> ac-ft</p> <p>$V_{DESIGN\ USER} =$ _____ ac-ft</p> <div style="border: 1px solid black; padding: 2px; margin: 5px 0;"> Choose One <input type="radio"/> A <input checked="" type="radio"/> B <input type="radio"/> C / D </div> <p>EURV = <u> 1.642 </u> ac-ft</p>
<p>2. Basin Shape: Length to Width Ratio (A basin length to width ratio of at least 2:1 will improve TSS reduction.)</p>	<p>L : W = <u> 2.0 </u> : 1</p>
<p>3. Basin Side Slopes</p> <p>A) Basin Maximum Side Slopes (Horizontal distance per unit vertical, 4:1 or flatter preferred)</p>	<p>Z = <u> 4.00 </u> ft / ft</p>
<p>4. Inlet</p> <p>A) Describe means of providing energy dissipation at concentrated inflow locations:</p>	<p>_____</p> <p>_____</p> <p>_____</p> <p>_____</p>

Design Procedure Form: Extended Detention Basin (EDB)

Sheet 2 of 4

Designer: Matt Larson
 Company: Classic Consulting Engineers & Surveyors, LLC
 Date: November 19, 2018
 Project: FOREST LAKES - PHASE 2
 Location: POND A

<p>5. Forebay</p> <p>A) Minimum Forebay Volume ($V_{MIN} =$ <u> 3% </u> of the WQCV)</p> <p>B) Actual Forebay Volume</p> <p>C) Forebay Depth ($D_F =$ <u> 18 </u> inch maximum)</p> <p>D) Forebay Discharge</p> <p style="margin-left: 20px;">i) Undetained 100-year Peak Discharge</p> <p style="margin-left: 20px;">ii) Forebay Discharge Design Flow ($Q_F = 0.02 * Q_{100}$)</p> <p>E) Forebay Discharge Design</p> <p>F) Discharge Pipe Size (minimum 8-inches)</p> <p>G) Rectangular Notch Width</p>	<p>$V_{MIN} =$ <u> 0.017 </u> ac-ft</p> <p>$V_F =$ <u> 0.020 </u> ac-ft</p> <p>$D_F =$ <u> 12.0 </u> in</p> <p>$Q_{100} =$ <u> 132.20 </u> cfs</p> <p>$Q_F =$ <u> 2.64 </u> cfs</p> <div style="border: 1px solid black; padding: 5px; margin: 10px 0;"> <p>Choose One</p> <p><input type="radio"/> Berm With Pipe</p> <p><input checked="" type="radio"/> Wall with Rect. Notch</p> <p><input type="radio"/> Wall with V-Notch Weir</p> </div> <p align="right"><i>(flow too small for berm w/ pipe)</i></p> <p>Calculated $D_p =$ <u> </u> in</p> <p>Calculated $W_N =$ <u> 11.9 </u> in</p>
<p>6. Trickle Channel</p> <p>A) Type of Trickle Channel</p> <p>F) Slope of Trickle Channel</p>	<div style="border: 1px solid black; padding: 5px; margin: 10px 0;"> <p>Choose One</p> <p><input checked="" type="radio"/> Concrete</p> <p><input type="radio"/> Soft Bottom</p> </div> <p>$S =$ <u> 0.0050 </u> ft / ft</p>
<p>7. Micropool and Outlet Structure</p> <p>A) Depth of Micropool (2.5-foot minimum)</p> <p>B) Surface Area of Micropool (10 ft² minimum)</p> <p>C) Outlet Type</p> <p>D) Smallest Dimension of Orifice Opening Based on Hydrograph Routing (Use UD-Detention)</p> <p>E) Total Outlet Area</p>	<p>$D_M =$ <u> 2.5 </u> ft</p> <p>$A_M =$ <u> 350 </u> sq ft</p> <div style="border: 1px solid black; padding: 5px; margin: 10px 0;"> <p>Choose One</p> <p><input checked="" type="radio"/> Orifice Plate</p> <p><input type="radio"/> Other (Describe):</p> </div> <hr/> <hr/> <p>$D_{orifice} =$ <u> 1.00 </u> inches</p> <p>$A_{tot} =$ <u> 6.00 </u> square inches</p>

Design Procedure Form: Extended Detention Basin (EDB)

Sheet 3 of 4

Designer: Matt Larson
Company: Classic Consulting Engineers & Surveyors, LLC
Date: November 19, 2018
Project: FOREST LAKES - PHASE 2
Location: POND A

<p>8. Initial Surcharge Volume</p> <p>A) Depth of Initial Surcharge Volume (Minimum recommended depth is 4 inches)</p> <p>B) Minimum Initial Surcharge Volume (Minimum volume of 0.3% of the WQCV)</p> <p>C) Initial Surcharge Provided Above Micropool</p>	<p>$D_{IS} =$ <u> 4 </u> in</p> <p>$V_{IS} =$ <u> 73.3 </u> cu ft</p> <p>$V_s =$ <u> 116.7 </u> cu ft</p>
<p>9. Trash Rack</p> <p>A) Water Quality Screen Open Area: $A_t = A_{cat} * 38.5 * (e^{-0.095D})$</p> <p>B) Type of Screen (If specifying an alternative to the materials recommended in the USDCM, indicate "other" and enter the ratio of the total open area to the total screen area for the material specified.)</p> <p style="padding-left: 40px;">Other (Y/N): <u> N </u></p> <p>C) Ratio of Total Open Area to Total Area (only for type "Other")</p> <p>D) Total Water Quality Screen Area (based on screen type)</p> <p>E) Depth of Design Volume (EURV or WQCV) (Based on design concept chosen under 1E)</p> <p>F) Height of Water Quality Screen (H_{TR})</p> <p>G) Width of Water Quality Screen Opening ($W_{opening}$) (Minimum of 12 inches is recommended)</p>	<p>$A_t =$ <u> 210 </u> square inches</p> <p><u> S.S. Well Screen with 60% Open Area </u></p> <hr/> <hr/> <p>User Ratio =</p> <p>$A_{total} =$ <u> 350 </u> sq. in.</p> <p>$H =$ <u> 5 </u> feet</p> <p>$H_{TR} =$ <u> 88 </u> inches</p> <p>$W_{opening} =$ <u> 12.0 </u> inches</p>

Design Procedure Form: Extended Detention Basin (EDB)

Sheet 4 of 4

Designer: Matt Larson
Company: Classic Consulting Engineers & Surveyors, LLC
Date: November 19, 2018
Project: FOREST LAKES - PHASE 2
Location: POND A

<p>10. Overflow Embankment</p> <p>A) Describe embankment protection for 100-year and greater overtopping:</p> <p>B) Slope of Overflow Embankment (Horizontal distance per unit vertical, 4:1 or flatter preferred)</p>	<p>45' WIDE SPILLWAY AT ELEV. 7117.00</p> <hr/> <hr/> <p align="center">10.00</p>
<p>11. Vegetation</p>	<p>Choose One</p> <p><input type="radio"/> Irrigated</p> <p><input checked="" type="radio"/> Not Irrigated</p>
<p>12. Access</p> <p>A) Describe Sediment Removal Procedures</p>	<p>12' WIDE ACCESS ROAD W/ MIN. 30' CL RADIUS TO POND BOTTOM</p> <hr/> <hr/> <hr/> <hr/>
<p>Notes:</p> <hr/> <hr/> <hr/>	

JOB NAME: FOREST LAKES PHASE 2
 JOB NUMBER: 1175.21
 DATE: 02/19/19
 CALCULATED BY: MAL

POND A EURV

POND SIZING WITH PONDPACK EQUATION:
 INSERT POND DESIGN SIZE INFO: (RED)

POND ELEVATION :	
(from lowest to highest)	
7108.00	
7108.00	
7110.00	
7112.00	
7113.00	
7114.00	

AREA (BTM to TOP):		
	-	acres
123	0.00	acres
11,955	0.27	acres
17,846	0.41	acres
21,004	0.48	acres
23,897	0.55	acres
	-	acres
	-	acres
	-	acres
	-	acres
	-	acres
	-	acres
	-	acres

PRELIMINARY SIZE:		VOLUME =		1/3{(EL2-EL1)*(A1+A2+((A1*A2)^.5))}		CUMMULATIVE VOLUME:	
-	AC-FT	from	7,108	to	7,108		
0.20	AC-FT	from	7,108	to	7,110	0.20	
0.67	AC-FT	from	7,110	to	7,112	0.87	
0.44	AC-FT	from	7,112	to	7,113	1.32	
0.51	AC-FT	from	7,113	to	7,114	1.83	
-	AC-FT	from	7,114	to	-	1.83	
-	AC-FT	from	-	to	-	1.83	
-	AC-FT	from	-	to	-	1.83	
-	AC-FT	from	-	to	-	1.83	
-	AC-FT	from	-	to	-	1.83	
-	AC-FT	from	-	to	-	1.83	

*SIZING IS FOR PRELIMINARY PURPOSES ONLY.

VOLUME = 1.83 AC-FT

APPROXIMATE SURFACE AREA REQUIREMENT

POND DEPTH (FT)	POND VOLUME			SURFACE AREA (SF)
	AC-FT	=	CF	
4	1.83	=	79,501	19,875
6	1.83	=	79,501	13,250
8	1.83	=	79,501	9,938
10	1.83	=	79,501	7,950

JOB NAME: FOREST LAKES PHASE 2
 JOB NUMBER: 1175.21
 DATE: 02/19/19
 CALCULATED BY: MAL

POND A SPILLWAY

POND SIZING WITH PONDPACK EQUATION:
 INSERT POND DESIGN SIZE INFO: (RED)

POND ELEVATION :	
(from lowest to highest)	
7108.00	
7108.00	
7110.00	
7112.00	
7114.00	
7116.00	
7117.00	

AREA (BTM to TOP):		
	-	acres
123	0.00	acres
11,955	0.27	acres
17,846	0.41	acres
23,897	0.55	acres
30,889	0.71	acres
34,317	0.79	acres
	-	acres
	-	acres
	-	acres
	-	acres
	-	acres

PRELIMINARY SIZE:		CUMMULATIVE VOLUME:				
VOLUME = $1/3\{(EL2-EL1)*(A1+A2+((A1*A2)^.5))\}$						
-	AC-FT	from	7,108	to	7,108	
0.20	AC-FT	from	7,108	to	7,110	0.20
0.67	AC-FT	from	7,110	to	7,112	0.87
0.95	AC-FT	from	7,112	to	7,114	1.82
1.24	AC-FT	from	7,114	to	7,116	3.06
0.74	AC-FT	from	7,116	to	7,117	3.80
-	AC-FT	from	7,117	to	-	3.80
-	AC-FT	from	-	to	-	3.80
-	AC-FT	from	-	to	-	3.80
-	AC-FT	from	-	to	-	3.80
-	AC-FT	from	-	to	-	3.80

*SIZING IS FOR PRELIMINARY PURPOSES ONLY.

VOLUME = 3.80 AC-FT

APPROXIMATE SURFACE AREA REQUIREMENT

POND DEPTH (FT)	POND VOLUME			SURFACE AREA (SF)
	AC-FT	=	CF	
4	3.80	=	#####	41,403
6	3.80	=	#####	27,602
8	3.80	=	#####	20,702
10	3.80	=	#####	16,561

JOB NAME: FOREST LAKES PHASE 2
 JOB NUMBER: 1175.21
 DATE: 02/19/19
 CALCULATED BY: MAL

POND A - TOP OF BERM

POND SIZING WITH PONDPACK EQUATION:
 INSERT POND DESIGN SIZE INFO: (RED)

POND ELEVATION :	
(from lowest to highest)	
	7108.00
	7108.00
	7110.00
	7112.00
	7114.00
	7116.00
	7118.00
	7120.00

AREA (BTM to TOP):		
	-	acres
123	0.00	acres
11,955	0.27	acres
17,846	0.41	acres
23,897	0.55	acres
30,889	0.71	acres
38,385	0.88	acres
46,144	1.06	acres
	-	acres
	-	acres
	-	acres
	-	acres

PRELIMINARY SIZE:		CUMMULATIVE VOLUME:		
VOLUME = $1/3\{(EL2-EL1)*(A1+A2+((A1*A2)^.5))\}$				
-	AC-FT	from 7,108	to 7,108	0.20
0.20	AC-FT	from 7,108	to 7,110	0.87
0.67	AC-FT	from 7,110	to 7,112	1.82
0.95	AC-FT	from 7,112	to 7,114	3.06
1.24	AC-FT	from 7,114	to 7,116	4.63
1.57	AC-FT	from 7,116	to 7,118	6.55
1.92	AC-FT	from 7,118	to 7,120	6.55
-	AC-FT	from 7,120	to -	6.55
-	AC-FT	from -	to -	6.55
-	AC-FT	from -	to -	6.55
-	AC-FT	from -	to -	6.55

*SIZING IS FOR PRELIMINARY PURPOSES ONLY.


VOLUME = 6.55 AC-FT

APPROXIMATE SURFACE AREA REQUIREMENT

POND DEPTH (FT)	POND VOLUME			SURFACE AREA (SF)
	AC-FT	=	CF	
4	6.55	=	#####	71,341
6	6.55	=	#####	47,560
8	6.55	=	#####	35,670
10	6.55	=	#####	28,536

DETENTION BASIN STAGE-STORAGE TABLE BUILDER


UD-Detention, Version 3.07 (February 2017)



Detention Basin Outlet Structure Design

UD-Detention, Version 3.07 (February 2017)

Project: FOREST LAKES PHASE 2
Basin ID: POND A - PRELIMINARY DESIGN



	Stage (ft)	Zone Volume (ac-ft)	Outlet Type
Zone 1 (WQCV)	2.97	0.574	Orifice Plate
Zone 2 (EURV)	5.47	1.063	Orifice Plate
Zone 3 (100-year)	7.86	1.438	Weir&Pipe (Restrict)
		3.075	Total

User Input: Orifice at Underdrain Outlet (typically used to drain WQCV in a Filtration BMP)

Underdrain Orifice Invert Depth = ft (distance below the filtration media surface)
Underdrain Orifice Diameter = inches

Calculated Parameters for Underdrain

Underdrain Orifice Area = ft²
Underdrain Orifice Centroid = feet

User Input: Orifice Plate with one or more orifices or Elliptical Slot Weir (typically used to drain WQCV and/or EURV in a sedimentation BMP)

Invert of Lowest Orifice = ft (relative to basin bottom at Stage = 0 ft)
Depth at top of Zone using Orifice Plate = ft (relative to basin bottom at Stage = 0 ft)
Orifice Plate: Orifice Vertical Spacing = inches
Orifice Plate: Orifice Area per Row = inches

Calculated Parameters for Plate

WQ Orifice Area per Row = ft²
Elliptical Half-Width = feet
Elliptical Slot Centroid = feet
Elliptical Slot Area = ft²

User Input: Stage and Total Area of Each Orifice Row (numbered from lowest to highest)

	Row 1 (required)	Row 2 (optional)	Row 3 (optional)	Row 4 (optional)	Row 5 (optional)	Row 6 (optional)	Row 7 (optional)	Row 8 (optional)
Stage of Orifice Centroid (ft)	0.00	2.00	4.00					
Orifice Area (sq. inches)	3.00	4.00	4.00					

	Row 9 (optional)	Row 10 (optional)	Row 11 (optional)	Row 12 (optional)	Row 13 (optional)	Row 14 (optional)	Row 15 (optional)	Row 16 (optional)
Stage of Orifice Centroid (ft)								
Orifice Area (sq. inches)								

User Input: Vertical Orifice (Circular or Rectangular)

	Not Selected	Not Selected
Invert of Vertical Orifice =	N/A	N/A
Depth at top of Zone using Vertical Orifice =	N/A	N/A
Vertical Orifice Diameter =	N/A	N/A

ft (relative to basin bottom at Stage = 0 ft)
ft (relative to basin bottom at Stage = 0 ft)
inches

Calculated Parameters for Vertical Orifice

	Not Selected	Not Selected
Vertical Orifice Area =	N/A	N/A
Vertical Orifice Centroid =	N/A	N/A

ft²
feet

User Input: Overflow Weir (Dropbox) and Grate (Flat or Sloped)

	Zone 3 Weir	Not Selected
Overflow Weir Front Edge Height, H _o =	6.00	N/A
Overflow Weir Front Edge Length =	4.00	N/A
Overflow Weir Slope =	4.00	N/A
Horiz. Length of Weir Sides =	4.00	N/A
Overflow Grate Open Area % =	85%	N/A
Debris Clogging % =	50%	N/A

ft (relative to basin bottom at Stage = 0 ft)
feet
H:V (enter zero for flat grate)
feet
%, grate open area/total area
%

Calculated Parameters for Overflow Weir

	Zone 3 Weir	Not Selected
Height of Grate Upper Edge, H ₁ =	7.00	N/A
Over Flow Weir Slope Length =	4.12	N/A
Grate Open Area / 100-yr Orifice Area =	2.86	N/A
Overflow Grate Open Area w/o Debris =	14.02	N/A
Overflow Grate Open Area w/ Debris =	7.01	N/A

feet
feet
should be ≥ 4
ft²
ft²

User Input: Outlet Pipe w/ Flow Restriction Plate (Circular Orifice, Restrictor Plate, or Rectangular Orifice)

	Zone 3 Restrictor	Not Selected
Depth to Invert of Outlet Pipe =	0.20	N/A
Outlet Pipe Diameter =	30.00	N/A
Restrictor Plate Height Above Pipe Invert =	30.00	N/A

ft (distance below basin bottom at Stage = 0 ft)
inches
inches

Calculated Parameters for Outlet Pipe w/ Flow Restriction Plate

	Zone 3 Restrictor	Not Selected
Outlet Orifice Area =	4.91	N/A
Outlet Orifice Centroid =	1.25	N/A
Half-Central Angle of Restrictor Plate on Pipe =	3.14	N/A

ft²
feet
radians

User Input: Emergency Spillway (Rectangular or Trapezoidal)

Spillway Invert Stage = ft (relative to basin bottom at Stage = 0 ft)
Spillway Crest Length = feet
Spillway End Slopes = H:V
Freeboard above Max Water Surface = feet

Calculated Parameters for Spillway




Spillway Design Flow Depth = feet
Stage at Top of Freeboard = feet
Basin Area at Top of Freeboard = acres

Routed Hydrograph Results

	WQCV	EURV	2 Year	5 Year	10 Year	25 Year	50 Year	100 Year	500 Year
Design Storm Return Period =									
One-Hour Rainfall Depth (in) =	0.53	1.07	1.19	1.50	1.75	2.00	2.25	2.52	3.10
Calculated Runoff Volume (acre-ft) =	0.574	1.637	1.295	1.797	2.532	3.761	4.592	5.682	7.788
OPTIONAL Override Runoff Volume (acre-ft) =									
Inflow Hydrograph Volume (acre-ft) =	0.574	1.638	1.296	1.799	2.534	3.766	4.598	5.679	7.789
Predevelopment Unit Peak Flow, q (cfs/acre) =	0.00	0.00	0.02	0.03	0.31	0.96	1.32	1.76	2.54
Predevelopment Peak Q (cfs) =	0.0	0.0	0.7	1.154	11.7	36.1	49.7	65.9	95.5
Peak Inflow Q (cfs) =	14.2	40.2	31.9	44.0	61.8	91.2	111.0	136.4	185.6
Peak Outflow Q (cfs) =	0.3	0.6	0.5	0.666	6.1	28.1	40.0	52.1	97.5
Ratio Peak Outflow to Predevelopment Q =	N/A	N/A	N/A	0.6	0.5	0.8	0.8	0.8	1.0
Structure Controlling Flow =	Plate	Plate	Plate	Plate	Overflow Grate 1	Overflow Grate 1	Overflow Grate 1	Overflow Grate 1	Spillway
Max Velocity through Grate 1 (fps) =	N/A	N/A	N/A	N/A	0.4	1.9	2.8	3.6	4.4
Max Velocity through Grate 2 (fps) =	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Time to Drain 97% of Inflow Volume (hours) =	43	67	62	69	72	68	65	62	57
Time to Drain 99% of Inflow Volume (hours) =	45	72	66	75	79	77	76	75	72
Maximum Ponding Depth (ft) =	2.88	5.34	4.65	5.65	6.59	7.40	7.86	8.46	9.38
Area at Maximum Ponding Depth (acres) =	0.33	0.50	0.45	0.52	0.60	0.66	0.70	0.75	0.82
Maximum Volume Stored (acre-ft) =	0.545	1.573	1.242	1.727	2.251	2.766	3.072	3.512	4.232

Detention Basin Outlet Structure Design

UD-Detention, Version 3.07 (February 2017)



S-A-V-D Chart Axis Override

	X-axis	Left Y-Axis	Right Y-Axis
minimum bound			
maximum bound			

DETENTION POND "B"

Site-Level Low Impact Development (LID) Design Effective Impervious Calculator

LID Credit by Impervious Reduction Factor (IRF) Method

User Input

Calculated cells

***Design Storm: 1-Hour Rain Depth	WQCV Event	0.53	inches
***Minor Storm: 1-Hour Rain Depth	10-Year Event	1.75	inches
***Major Storm: 1-Hour Rain Depth	100-Year Event	2.52	inches
Optional User Defined Storm	CUHP		
(CUHP) NOAA 1 Hour Rainfall Depth and Frequency for User Defined Storm	100-Year Event		

Max Intensity for Optional User Defined Storm: 0

Designer: Matt Larson
 Company: Classic Consulting Engineers & Surveyors, LLC
 Date: February 18, 2019
 Project: FOREST LAKES - PHASE 2
 Location: POND B - PRELIMINARY DESIGN

SITE INFORMATION (USER-INPUT)

Sub-basin Identifier	TRIB BASIN														
Receiving Pervious Area Soil Type	Sandy Loam														
Total Area (ac, Sum of DCIA, UIA, RPA, & SPA)	59.940														
Directly Connected Impervious Area (DCIA, acres)	15.110														
Unconnected Impervious Area (UIA, acres)	2.170														
Receiving Pervious Area (RPA, acres)	0.890														
Separate Pervious Area (SPA, acres)	41.770														
RPA Treatment Type: Conveyance (C), Volume (V), or Permeable Pavement (PP)	C														

CALCULATED RESULTS (OUTPUT)

Total Calculated Area (ac, check against input)	59.940														
Directly Connected Impervious Area (DCIA, %)	25.2%														
Unconnected Impervious Area (UIA, %)	3.6%														
Receiving Pervious Area (RPA, %)	1.5%														
Separate Pervious Area (SPA, %)	69.7%														
A _s (RPA / UIA)	0.410														
I _p Check	0.710														
f / I for WQCV Event:	2.0														
f / I for 10-Year Event:	0.5														
f / I for 100-Year Event:	0.3														
f / I for Optional User Defined Storm CUHP:															
IRF for WQCV Event:	0.73														
IRF for 10-Year Event:	0.93														
IRF for 100-Year Event:	0.96														
IRF for Optional User Defined Storm CUHP:															
Total Site Imperviousness: I _{total}	28.8%														
Effective Imperviousness for WQCV Event:	27.9%														
Effective Imperviousness for 10-Year Event:	28.6%														
Effective Imperviousness for 100-Year Event:	28.7%														
Effective Imperviousness for Optional User Defined Storm CUHP:															

LID / EFFECTIVE IMPERVIOUSNESS CREDITS

WQCV Event CREDIT: Reduce Detention By:	2.2%	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
10-Year Event CREDIT: Reduce Detention By:	0.9%	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
100-Year Event CREDIT: Reduce Detention By:	0.5%	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
User Defined CUHP CREDIT: Reduce Detention By:															

Total Site Imperviousness:	28.8%
Total Site Effective Imperviousness for WQCV Event:	27.9%
Total Site Effective Imperviousness for 10-Year Event:	28.6%
Total Site Effective Imperviousness for 100-Year Event:	28.7%
Total Site Effective Imperviousness for Optional User Defined Storm CUHP:	

Notes:
 * Use Green-Ampt average infiltration rate values from Table 3-3.
 ** Flood control detention volume credits based on empirical equations from Storage Chapter of USDCM.
 *** Method assumes that 1-hour rainfall depth is equivalent to 1-hour intensity for calculation purposes

Design Procedure Form: Extended Detention Basin (EDB)

Designer: Matt Larson
Company: Classic Consulting Engineers & Surveyors, LLC
Date: February 18, 2019
Project: FOREST LAKES - PHASE 2
Location: POND B - PRELIMINARY DESIGN

<p>1. Basin Storage Volume</p> <p>A) Effective Imperviousness of Tributary Area, I_a</p> <p>B) Tributary Area's Imperviousness Ratio ($i = I_a / 100$)</p> <p>C) Contributing Watershed Area</p> <p>D) For Watersheds Outside of the Denver Region, Depth of Average Runoff Producing Storm</p> <p>E) Design Concept (Select EURV when also designing for flood control)</p> <p>F) Design Volume (WQCV) Based on 40-hour Drain Time ($V_{DESIGN} = (1.0 * (0.91 * i^3 - 1.19 * i^2 + 0.78 * i) / 12 * Area)$)</p> <p>G) For Watersheds Outside of the Denver Region, Water Quality Capture Volume (WQCV) Design Volume ($V_{WQCV\ OTHER} = (d_s * (V_{DESIGN} / 0.43))$)</p> <p>H) User Input of Water Quality Capture Volume (WQCV) Design Volume (Only if a different WQCV Design Volume is desired)</p> <p>I) Predominant Watershed NRCS Soil Group</p> <p>J) Excess Urban Runoff Volume (EURV) Design Volume For HSG A: $EURV_A = 1.68 * i^{1.28}$ For HSG B: $EURV_B = 1.36 * i^{1.08}$ For HSG C/D: $EURV_{C/D} = 1.20 * i^{1.08}$ </p>	<p>$I_a =$ <u> 28.8 </u> %</p> <p>$i =$ <u> 0.288 </u></p> <p>Area = <u> 59.940 </u> ac</p> <p>$d_s =$ <u> 0.42 </u> in</p> <div style="border: 1px solid black; padding: 5px; margin: 5px 0;"> Choose One <input type="radio"/> Water Quality Capture Volume (WQCV) <input checked="" type="radio"/> Excess Urban Runoff Volume (EURV) </div> <p>$V_{DESIGN} =$ <u> 0.738 </u> ac-ft</p> <p>$V_{DESIGN\ OTHER} =$ <u> 0.720 </u> ac-ft</p> <p>$V_{DESIGN\ USER} =$ _____ ac-ft</p> <div style="border: 1px solid black; padding: 5px; margin: 5px 0;"> Choose One <input type="radio"/> A <input checked="" type="radio"/> B <input type="radio"/> C / D </div> <p>EURV = <u> 1.771 </u> ac-ft</p>
<p>2. Basin Shape: Length to Width Ratio (A basin length to width ratio of at least 2:1 will improve TSS reduction.)</p>	<p>L : W = <u> 2.0 </u> : 1</p>
<p>3. Basin Side Slopes</p> <p>A) Basin Maximum Side Slopes (Horizontal distance per unit vertical, 4:1 or flatter preferred)</p>	<p>Z = <u> 4.00 </u> ft / ft</p>
<p>4. Inlet</p> <p>A) Describe means of providing energy dissipation at concentrated inflow locations:</p>	<p>_____</p> <p>_____</p> <p>_____</p> <p>_____</p>

Design Procedure Form: Extended Detention Basin (EDB)

Sheet 2 of 4

Designer: Matt Larson
Company: Classic Consulting Engineers & Surveyors, LLC
Date: November 20, 2018
Project: FOREST LAKES - PHASE 2
Location: POND B

<p>5. Forebay</p> <p>A) Minimum Forebay Volume ($V_{MIN} =$ <u> 3% </u> of the WQCV)</p> <p>B) Actual Forebay Volume</p> <p>C) Forebay Depth ($D_F =$ <u> 18 </u> inch maximum)</p> <p>D) Forebay Discharge</p> <p style="margin-left: 20px;">i) Undetained 100-year Peak Discharge</p> <p style="margin-left: 20px;">ii) Forebay Discharge Design Flow ($Q_F = 0.02 * Q_{100}$)</p> <p>E) Forebay Discharge Design</p> <p style="margin-left: 20px;">F) Discharge Pipe Size (minimum 8-inches)</p> <p>G) Rectangular Notch Width</p>	<p>$V_{MIN} =$ <u> 0.022 </u> ac-ft</p> <p>$V_F =$ <u> 0.025 </u> ac-ft</p> <p>$D_F =$ <u> 12.0 </u> in</p> <p>$Q_{100} =$ <u> 176.00 </u> cfs</p> <p>$Q_F =$ <u> 3.52 </u> cfs</p> <div style="border: 1px solid black; padding: 5px; margin: 10px 0;"> <p>Choose One</p> <p><input type="radio"/> Berm With Pipe</p> <p><input checked="" type="radio"/> Wall with Rect. Notch</p> <p><input type="radio"/> Wall with V-Notch Weir</p> </div> <p align="right">(flow too small for berm w/ pipe)</p> <p>Calculated $D_p =$ <u> </u> in</p> <p>Calculated $W_N =$ <u> 15.1 </u> in</p>
<p>6. Trickle Channel</p> <p>A) Type of Trickle Channel</p> <p style="margin-left: 20px;">F) Slope of Trickle Channel</p>	<div style="border: 1px solid black; padding: 5px; margin: 10px 0;"> <p>Choose One</p> <p><input checked="" type="radio"/> Concrete</p> <p><input type="radio"/> Soft Bottom</p> </div> <p>$S =$ <u> 0.0050 </u> ft / ft</p>
<p>7. Micropool and Outlet Structure</p> <p>A) Depth of Micropool (2.5-foot minimum)</p> <p>B) Surface Area of Micropool (10 ft² minimum)</p> <p>C) Outlet Type</p> <p style="margin-left: 20px;">D) Smallest Dimension of Orifice Opening Based on Hydrograph Routing (Use UD-Detention)</p> <p>E) Total Outlet Area</p>	<p>$D_M =$ <u> 2.5 </u> ft</p> <p>$A_M =$ <u> 250 </u> sq ft</p> <div style="border: 1px solid black; padding: 5px; margin: 10px 0;"> <p>Choose One</p> <p><input checked="" type="radio"/> Orifice Plate</p> <p><input type="radio"/> Other (Describe):</p> </div> <hr style="border: 0; border-top: 1px solid black; margin: 5px 0;"/> <hr style="border: 0; border-top: 1px solid black; margin: 5px 0;"/> <p>$D_{orifice} =$ <u> 1.00 </u> inches</p> <p>$A_{tot} =$ <u> 6.00 </u> square inches</p>

Design Procedure Form: Extended Detention Basin (EDB)

Sheet 3 of 4

Designer: Matt Larson
Company: Classic Consulting Engineers & Surveyors, LLC
Date: November 20, 2018
Project: FOREST LAKES - PHASE 2
Location: POND B

<p>8. Initial Surcharge Volume</p> <p>A) Depth of Initial Surcharge Volume (Minimum recommended depth is 4 inches)</p> <p>B) Minimum Initial Surcharge Volume (Minimum volume of 0.3% of the WQCV)</p> <p>C) Initial Surcharge Provided Above Micropool</p>	<p>$D_{IS} =$ <u> 5 </u> in</p> <p>$V_{IS} =$ <u> 94.2 </u> cu ft</p> <p>$V_s =$ <u> 104.2 </u> cu ft</p>
<p>9. Trash Rack</p> <p>A) Water Quality Screen Open Area: $A_t = A_{cal} * 38.5 * (e^{-0.095D})$</p> <p>B) Type of Screen (If specifying an alternative to the materials recommended in the USDCM, indicate "other" and enter the ratio of the total open area to the total screen area for the material specified.)</p> <p style="padding-left: 40px;">Other (Y/N): <u> N </u></p> <p>C) Ratio of Total Open Area to Total Area (only for type "Other")</p> <p>D) Total Water Quality Screen Area (based on screen type)</p> <p>E) Depth of Design Volume (EURV or WQCV) (Based on design concept chosen under 1E)</p> <p>F) Height of Water Quality Screen (H_{TR})</p> <p>G) Width of Water Quality Screen Opening ($W_{opening}$) (Minimum of 12 inches is recommended)</p>	<p>$A_t =$ <u> 210 </u> square inches</p> <p><u> S.S. Well Screen with 60% Open Area </u></p> <hr/> <hr/> <p>User Ratio =</p> <p>$A_{total} =$ <u> 350 </u> sq. in.</p> <p>$H =$ <u> 5.3 </u> feet</p> <p>$H_{TR} =$ <u> 91.6 </u> inches</p> <p>$W_{opening} =$ <u> 12.0 </u> inches</p>

Design Procedure Form: Extended Detention Basin (EDB)

Designer: Matt Larson
Company: Classic Consulting Engineers & Surveyors, LLC
Date: November 20, 2018
Project: FOREST LAKES - PHASE 2
Location: POND B

<p>10. Overflow Embankment</p> <p>A) Describe embankment protection for 100-year and greater overtopping:</p> <p>B) Slope of Overflow Embankment (Horizontal distance per unit vertical, 4:1 or flatter preferred)</p>	<p>50' WIDE CONCRETE SPILLWAY AT ELEV. 7061.00</p> <hr/> <hr/> <p align="center">10.00</p>
<p>11. Vegetation</p>	<p>Choose One</p> <p><input type="radio"/> Irrigated</p> <p><input checked="" type="radio"/> Not Irrigated</p>
<p>12. Access</p> <p>A) Describe Sediment Removal Procedures</p>	<p>12' WIDE ACCESS ROAD W/ MIN. 30' CL RADIUS TO POND BOTTOM</p> <hr/> <hr/> <hr/> <hr/>
<p>Notes:</p> <hr/> <hr/> <hr/>	

JOB NAME: FOREST LAKES PHASE 2
 JOB NUMBER: 1175.21
 DATE: 02/19/19
 CALCULATED BY: MAL

POND B EURV

POND SIZING WITH PONDPACK EQUATION:
 INSERT POND DESIGN SIZE INFO: (RED)

POND ELEVATION :	
(from lowest to highest)	
	7054.00
	7054.00
	7056.00
	7058.00
	7059.80

AREA (BTM to TOP):		
	-	acres
100	0.00	acres
15,020	0.34	acres
19,411	0.45	acres
24,125	0.55	acres
	-	acres
	-	acres
	-	acres
	-	acres
	-	acres
	-	acres
	-	acres
	-	acres
	-	acres

PRELIMINARY SIZE:						CUMMULATIVE VOLUME:	
VOLUME = $1/3\{(EL2-EL1)*(A1+A2+((A1*A2)^.5))\}$							
-	AC-FT	from	7,054	to	7,054		
0.25	AC-FT	from	7,054	to	7,056		0.25
0.78	AC-FT	from	7,056	to	7,058		1.03
0.89	AC-FT	from	7,058	to	7,060		1.92
-	AC-FT	from	7,060	to	-		1.92
-	AC-FT	from	-	to	-		1.92
-	AC-FT	from	-	to	-		1.92
-	AC-FT	from	-	to	-		1.92
-	AC-FT	from	-	to	-		1.92
-	AC-FT	from	-	to	-		1.92
-	AC-FT	from	-	to	-		1.92

*SIZING IS FOR PRELIMINARY PURPOSES ONLY.

VOLUME = 1.92 AC-FT

APPROXIMATE SURFACE AREA REQUIREMENT

POND DEPTH (FT)	POND VOLUME			SURFACE AREA (SF)
	AC-FT	=	CF	
4	1.92	=	83,497	20,874
6	1.92	=	83,497	13,916
8	1.92	=	83,497	10,437
10	1.92	=	83,497	8,350

JOB NAME: FOREST LAKES PHASE 2
 JOB NUMBER: 1175.21
 DATE: 02/19/19
 CALCULATED BY: MAL

POND B - SPILLWAY

POND SIZING WITH PONDPACK EQUATION:
 INSERT POND DESIGN SIZE INFO: (RED)

POND ELEVATION :	
(from lowest to highest)	
	7054.00
	7054.00
	7056.00
	7058.00
	7060.00
	7062.00
	7063.00

AREA (BTM to TOP):		
	-	acres
100	0.00	acres
15,020	0.34	acres
19,411	0.45	acres
24,125	0.55	acres
29,262	0.67	acres
31,943	0.73	acres
	-	acres
	-	acres
	-	acres
	-	acres
	-	acres
	-	acres

PRELIMINARY SIZE:		CUMMULATIVE VOLUME:		
VOLUME = $1/3\{(EL2-EL1)*(A1+A2+((A1*A2)^.5))\}$				
-	AC-FT	from 7,054	to 7,054	
0.25	AC-FT	from 7,054	to 7,056	0.25
0.78	AC-FT	from 7,056	to 7,058	1.03
0.99	AC-FT	from 7,058	to 7,060	2.02
1.21	AC-FT	from 7,060	to 7,062	3.23
0.70	AC-FT	from 7,062	to 7,063	3.92
-	AC-FT	from 7,063	to -	3.92
-	AC-FT	from -	to -	3.92
-	AC-FT	from -	to -	3.92
-	AC-FT	from -	to -	3.92
-	AC-FT	from -	to -	3.92

*SIZING IS FOR PRELIMINARY PURPOSES ONLY.

VOLUME = 3.92 AC-FT

APPROXIMATE SURFACE AREA REQUIREMENT

POND DEPTH (FT)	POND VOLUME			SURFACE AREA (SF)
	AC-FT	=	CF	
4	3.92	=	#####	42,714
6	3.92	=	#####	28,476
8	3.92	=	#####	21,357
10	3.92	=	#####	17,086

JOB NAME: FOREST LAKES PHASE 2
 JOB NUMBER: 1175.21
 DATE: 02/19/19
 CALCULATED BY: MAL

POND B - TOP OF BERM

POND SIZING WITH PONDPACK EQUATION:

INSERT POND DESIGN SIZE INFO: (RED)

POND ELEVATION :	
(from lowest to highest)	
	7054.00
	7054.00
	7056.00
	7058.00
	7060.00
	7062.00
	7064.00
	7066.00

AREA (BTM to TOP):		
	-	acres
100	0.00	acres
15,020	0.34	acres
19,411	0.45	acres
24,125	0.55	acres
29,262	0.67	acres
34,880	0.80	acres
40,925	0.94	acres
	-	acres
	-	acres
	-	acres
	-	acres

PRELIMINARY SIZE:		CUMMULATIVE VOLUME:		
VOLUME = $1/3\{(EL2-EL1)*(A1+A2+((A1*A2)^.5))\}$				
-	AC-FT	from 7,054	to 7,054	0.25
0.25	AC-FT	from 7,054	to 7,056	1.03
0.78	AC-FT	from 7,056	to 7,058	2.02
0.99	AC-FT	from 7,058	to 7,060	3.23
1.21	AC-FT	from 7,060	to 7,062	4.68
1.46	AC-FT	from 7,062	to 7,064	6.40
1.72	AC-FT	from 7,064	to 7,066	6.40
-	AC-FT	from 7,066	to -	6.40
-	AC-FT	from -	to -	6.40
-	AC-FT	from -	to -	6.40
-	AC-FT	from -	to -	6.40

*SIZING IS FOR PRELIMINARY PURPOSES ONLY.


VOLUME = 6.40 AC-FT

APPROXIMATE SURFACE AREA REQUIREMENT

POND DEPTH (FT)	POND VOLUME			SURFACE AREA (SF)
	AC-FT	=	CF	
4	6.40	=	#####	69,739
6	6.40	=	#####	46,492
8	6.40	=	#####	34,869
10	6.40	=	#####	27,895

DETENTION BASIN STAGE-STORAGE TABLE BUILDER

UD-Detention, Version 3.07 (February 2017)



Required Volume Calculation

Selected BMP Type =	EDB	
Watershed Area =	59.94	acres
Watershed Length =	2,300	ft
Watershed Slope =	0.060	ft/ft
Watershed Imperviousness =	28.80%	percent
Percentage Hydrologic Soil Group A =	0.0%	percent
Percentage Hydrologic Soil Group B =	100.0%	percent
Percentage Hydrologic Soil Groups C/D =	0.0%	percent
Desired WQCV Drain Time =	40.0	hours
Location for 1-hr Rainfall Depths =	User Input	
Water Quality Capture Volume (WQCV) =	0.738	acre-feet
Excess Urban Runoff Volume (EURV) =	1.766	acre-feet
2-yr Runoff Volume (P1 = 1.19 in.) =	1,348	acre-feet
5-yr Runoff Volume (P1 = 1.5 in.) =	1,925	acre-feet
10-yr Runoff Volume (P1 = 1.75 in.) =	2,571	acre-feet
25-yr Runoff Volume (P1 = 2 in.) =	5,052	acre-feet
50-yr Runoff Volume (P1 = 2.25 in.) =	6,413	acre-feet
100-yr Runoff Volume (P1 = 2.52 in.) =	8,194	acre-feet
500-yr Runoff Volume (P1 = 3.1 in.) =	11,589	acre-feet
Approximate 2-yr Detention Volume =	1,258	acre-feet
Approximate 5-yr Detention Volume =	1,806	acre-feet
Approximate 10-yr Detention Volume =	2,659	acre-feet
Approximate 25-yr Detention Volume =	3,102	acre-feet
Approximate 50-yr Detention Volume =	3,270	acre-feet
Approximate 100-yr Detention Volume =	3,883	acre-feet

**Optional User Override
1-hr Precipitation**

1.19	inches
1.50	inches
1.75	inches
2.00	inches
2.25	inches
2.52	inches
3.10	inches


Stage-Storage Calculation

Zone 1 Volume (WQCV) =	0.738	acre-feet
Zone 2 Volume (EURV - Zone 1) =	1.028	acre-feet
Zone 3 Volume (100-year - Zones 1 & 2) =	2.117	acre-feet
Total Detention Basin Volume =	3,883	acre-feet
Initial Surcharge Volume (ISV) =	user	ft ³
Initial Surcharge Depth (ISD) =	user	ft
Total Available Detention Depth (H _{tot}) =	user	ft
Depth of Trickle Channel (H _{TC}) =	user	ft
Slope of Trickle Channel (S _{TC}) =	user	ft/ft
Slopes of Main Basin Sides (S _{mb}) =	user	H:V
Basin Length-to-Width Ratio (R _{mb}) =	user	
Initial Surcharge Area (A _{ISV}) =	user	ft ²
Surcharge Volume Length (L _{ISV}) =	user	ft
Surcharge Volume Width (W _{ISV}) =	user	ft
Depth of Basin Floor (H _{100yr}) =	user	ft
Length of Basin Floor (L _{100yr}) =	user	ft
Width of Basin Floor (W _{100yr}) =	user	ft
Area of Basin Floor (A _{100yr}) =	user	ft ²
Volume of Basin Floor (V _{100yr}) =	user	ft ³
Depth of Main Basin (H _{MB}) =	user	ft
Length of Main Basin (L _{MB}) =	user	ft
Width of Main Basin (W _{MB}) =	user	ft
Area of Main Basin (A _{MB}) =	user	ft ²
Volume of Main Basin (V _{MB}) =	user	ft ³
Calculated Total Basin Volume (V _{tot}) =	user	acre-feet

Depth Increment =	0.25 ft									
Stage - Storage Description	Stage (ft)	Optional Override Stage (ft)	Length (ft)	Width (ft)	Area (ft²)	Optional Override Area (ft²)	Area (acre)	Volume (ft³)	Volume (ac-ft)	
Top of Micropool	--	0.00	--	--	--	100	0.002			
	--	2.00	--	--	--	15,020	0.345	14,970	0.344	
	--	4.00	--	--	--	19,411	0.446	49,551	1.138	
	--	6.00	--	--	--	24,125	0.554	93,087	2.137	
	--	8.00	--	--	--	29,262	0.672	146,474	3.363	
	--	9.00	--	--	--	31,943	0.733	177,076	4.065	
	--	10.00	--	--	--	34,880	0.801	210,488	4.832	
	--	12.00	--	--	--	40,925	0.940	286,293	6.572	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	
	--	--	--	--	--	--	--	--	--	

DETENTION BASIN STAGE-STORAGE TABLE BUILDER


UD-Detention, Version 3.07 (February 2017)



Detention Basin Outlet Structure Design

UD-Detention, Version 3.07 (February 2017)

Project: FOREST LAKES PHASE 2
Basin ID: POND B - PRELIMINARY DESIGN



	Stage (ft)	Zone Volume (ac-ft)	Outlet Type
Zone 1 (WQCV)	3.06	0.738	Orifice Plate
Zone 2 (EURV)	5.31	1.028	Orifice Plate
Zone 3 (100-year)	8.75	2.117	Weir&Pipe (Restrict)
		3.883	Total

User Input: Orifice at Underdrain Outlet (typically used to drain WQCV in a Filtration BMP)

Underdrain Orifice Invert Depth = ft (distance below the filtration media surface)
Underdrain Orifice Diameter = inches

Calculated Parameters for Underdrain

Underdrain Orifice Area = ft²
Underdrain Orifice Centroid = feet

User Input: Orifice Plate with one or more orifices or Elliptical Slot Weir (typically used to drain WQCV and/or EURV in a sedimentation BMP)

Invert of Lowest Orifice = ft (relative to basin bottom at Stage = 0 ft)
Depth at top of Zone using Orifice Plate = ft (relative to basin bottom at Stage = 0 ft)
Orifice Plate: Orifice Vertical Spacing = inches
Orifice Plate: Orifice Area per Row = inches

Calculated Parameters for Plate

WQ Orifice Area per Row = ft²
Elliptical Half-Width = feet
Elliptical Slot Centroid = feet
Elliptical Slot Area = ft²

User Input: Stage and Total Area of Each Orifice Row (numbered from lowest to highest)

	Row 1 (required)	Row 2 (optional)	Row 3 (optional)	Row 4 (optional)	Row 5 (optional)	Row 6 (optional)	Row 7 (optional)	Row 8 (optional)
Stage of Orifice Centroid (ft)	0.00	2.00	4.00					
Orifice Area (sq. inches)	4.00	8.00	12.00					
	Row 9 (optional)	Row 10 (optional)	Row 11 (optional)	Row 12 (optional)	Row 13 (optional)	Row 14 (optional)	Row 15 (optional)	Row 16 (optional)
Stage of Orifice Centroid (ft)								
Orifice Area (sq. inches)								

User Input: Vertical Orifice (Circular or Rectangular)

Invert of Vertical Orifice = ft (relative to basin bottom at Stage = 0 ft)
Depth at top of Zone using Vertical Orifice = ft (relative to basin bottom at Stage = 0 ft)
Vertical Orifice Diameter = inches

Calculated Parameters for Vertical Orifice

Vertical Orifice Area = ft²
Vertical Orifice Centroid = feet

User Input: Overflow Weir (Dropbox) and Grate (Flat or Sloped)

Overflow Weir Front Edge Height, H_o = ft (relative to basin bottom at Stage = 0 ft)
Overflow Weir Front Edge Length = feet
Overflow Weir Slope = H:V (enter zero for flat grate)
Horiz. Length of Weir Sides = feet
Overflow Grate Open Area % = % , grate open area/total area
Debris Clogging % = %

Calculated Parameters for Overflow Weir

Height of Grate Upper Edge, H_g = feet
Over Flow Weir Slope Length = feet
Grate Open Area / 100-yr Orifice Area = should be ≥ 4
Overflow Grate Open Area w/o Debris = ft²
Overflow Grate Open Area w/ Debris = ft²

User Input: Outlet Pipe w/ Flow Restriction Plate (Circular Orifice, Restrictor Plate, or Rectangular Orifice)

Depth to Invert of Outlet Pipe = ft (distance below basin bottom at Stage = 0 ft)
Outlet Pipe Diameter = inches
Restrictor Plate Height Above Pipe Invert = inches

Calculated Parameters for Outlet Pipe w/ Flow Restriction Plate

Outlet Orifice Area = ft²
Outlet Orifice Centroid = feet
Half-Central Angle of Restrictor Plate on Pipe = radians

User Input: Emergency Spillway (Rectangular or Trapezoidal)

Spillway Invert Stage = ft (relative to basin bottom at Stage = 0 ft)
Spillway Crest Length = feet
Spillway End Slopes = H:V
Freeboard above Max Water Surface = feet

Calculated Parameters for Spillway




Spillway Design Flow Depth = feet
Stage at Top of Freeboard = feet
Basin Area at Top of Freeboard = acres

Routed Hydrograph Results

	WQCV	EURV	2 Year	5 Year	10 Year	25 Year	50 Year	100 Year	500 Year
Design Storm Return Period =									
One-Hour Rainfall Depth (in) =	0.53	1.07	1.19	1.50	1.75	2.00	2.25	2.52	3.10
Calculated Runoff Volume (acre-ft) =	0.738	1.766	1.348	1.925	2.971	5.052	6.413	8.194	11.589
OPTIONAL Override Runoff Volume (acre-ft) =									
Inflow Hydrograph Volume (acre-ft) =	0.738	1.766	1.349	1.926	2.973	5.054	6.417	8.195	11.597
Predevelopment Unit Peak Flow, q (cfs/acre) =	0.00	0.00	0.01	0.02	0.23	0.75	1.03	1.38	2.01
Predevelopment Peak Q (cfs) =	0.0	0.0	0.8	1.412	13.8	44.8	61.9	82.9	120.6
Peak Inflow Q (cfs) =	14.0	33.2	25.4	36.1	55.4	93.3	117.8	149.4	209.2
Peak Outflow Q (cfs) =	0.5	1.2	0.9	1.263	9.5	44.0	62.4	84.2	158.2
Ratio Peak Outflow to Predevelopment Q =	N/A	N/A	N/A	0.9	0.7	1.0	1.0	1.0	1.3
Structure Controlling Flow =	Plate	Plate	Plate	Plate	Overflow Grate 1	Overflow Grate 1	Overflow Grate 1	Overflow Grate 1	Spillway
Max Velocity through Grate 1 (fps) =	N/A	N/A	N/A	N/A	0.4	2.0	2.9	3.9	4.5
Max Velocity through Grate 2 (fps) =	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Time to Drain 97% of Inflow Volume (hours) =	39	52	48	52	54	49	46	42	35
Time to Drain 99% of Inflow Volume (hours) =	41	56	52	57	60	58	56	55	52
Maximum Ponding Depth (ft) =	2.91	5.05	4.26	5.34	6.62	7.58	8.08	8.75	9.52
Area at Maximum Ponding Depth (acres) =	0.39	0.50	0.46	0.52	0.59	0.65	0.68	0.72	0.77
Maximum Volume Stored (acre-ft) =	0.678	1.635	1.251	1.783	2.492	3.086	3.410	3.877	4.448

Detention Basin Outlet Structure Design

UD-Detention, Version 3.07 (February 2017)



S-A-V-D Chart Axis Override

	X-axis	Left Y-Axis	Right Y-Axis
minimum bound			
maximum bound			

DETENTION POND "C"



Site-Level Low Impact Development (LID) Design Effective Impervious Calculator LID Credit by Impervious Reduction Factor (IRF) Method

User Input

Calculated cells

***Design Storm: 1-Hour Rain Depth	WQCV Event	0.53	inches
***Minor Storm: 1-Hour Rain Depth	10-Year Event	1.75	inches
***Major Storm: 1-Hour Rain Depth	100-Year Event	2.52	inches
Optional User Defined Storm	CUHP		
(CUHP) NOAA 1-Hour Rainfall Depth and Frequency for User Defined Storm	100-Year Event		
Max Intensity for Optional User Defined Storm		0	

Designer: Matt Larson
Company: Classic Consulting Engineers & Surveyors, LLC
Date: February 18, 2019
Project: FOREST LAKES - PHASE 2
Location: POND C - PRELIMINARY DESIGN

SITE INFORMATION (USER-INPUT)

Sub-basin Identifier	TRIB BASIN																
Receiving Pervious Area Soil Type	Sandy Loam																
Total Area (ac., Sum of DCIA, UIA, RPA, & SPA)	30.280																
Directly Connected Impervious Area (DCIA, acres)	9.570																
Unconnected Impervious Area (UIA, acres)	1.170																
Receiving Pervious Area (RPA, acres)	0.480																
Separate Pervious Area (SPA, acres)	19.060																
RPA Treatment Type: Conveyance (C), Volume (V), or Permeable Pavement (PP)	C																

CALCULATED RESULTS (OUTPUT)

Total Calculated Area (ac., check against input)	30.280																
Directly Connected Impervious Area (DCIA, %)	31.6%																
Unconnected Impervious Area (UIA, %)	3.9%																
Receiving Pervious Area (RPA, %)	1.6%																
Separate Pervious Area (SPA, %)	62.9%																
A _r (RPA / UIA)	0.410																
I _a Check	0.710																
f / I for WQCV Event:	2.0																
f / I for 10-Year Event:	0.5																
f / I for 100-Year Event:	0.3																
f / I for Optional User Defined Storm CUHP:																	
IRF for WQCV Event:	0.73																
IRF for 10-Year Event:	0.93																
IRF for 100-Year Event:	0.96																
IRF for Optional User Defined Storm CUHP:																	
Total Site Imperviousness: I _{total}	35.5%																
Effective Imperviousness for WQCV Event:	34.4%																
Effective Imperviousness for 10-Year Event:	35.2%																
Effective Imperviousness for 100-Year Event:	35.3%																
Effective Imperviousness for Optional User Defined Storm CUHP:																	

LID / EFFECTIVE IMPERVIOUSNESS CREDITS

WQCV Event CREDIT: Reduce Detention By:	1.8%	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
10-Year Event CREDIT*: Reduce Detention By:	0.8%	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
100-Year Event CREDIT**: Reduce Detention By:	0.4%	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
User Defined CUHP CREDIT: Reduce Detention By:																	

Total Site Imperviousness:	35.5%
Total Site Effective Imperviousness for WQCV Event:	34.4%
Total Site Effective Imperviousness for 10-Year Event:	35.2%
Total Site Effective Imperviousness for 100-Year Event:	35.3%
Total Site Effective Imperviousness for Optional User Defined Storm CUHP:	

Notes:

- * Use Green-Ampt average infiltration rate values from Table 3-3.
- ** Flood control detention volume credits based on empirical equations from Storage Chapter of USDCM.
- *** Method assumes that 1-hour rainfall depth is equivalent to 1-hour intensity for calculation purposes

Design Procedure Form: Extended Detention Basin (EDB)

Designer: Matt Larson
Company: Classic Consulting Engineers & Surveyors, LLC
Date: February 18, 2019
Project: FOREST LAKES - PHASE 2
Location: POND C - PRELIMINARY DESIGN

<p>1. Basin Storage Volume</p> <p>A) Effective Imperviousness of Tributary Area, I_a</p> <p>B) Tributary Area's Imperviousness Ratio ($i = I_a / 100$)</p> <p>C) Contributing Watershed Area</p> <p>D) For Watersheds Outside of the Denver Region, Depth of Average Runoff Producing Storm</p> <p>E) Design Concept (Select EURV when also designing for flood control)</p> <p>F) Design Volume (WQCV) Based on 40-hour Drain Time ($V_{DESIGN} = (1.0 * (0.91 * i^3 - 1.19 * i^2 + 0.78 * i) / 12 * Area)$)</p> <p>G) For Watersheds Outside of the Denver Region, Water Quality Capture Volume (WQCV) Design Volume ($V_{WQCV\ OTHER} = (d_6 * V_{DESIGN} / 0.43)$)</p> <p>H) User Input of Water Quality Capture Volume (WQCV) Design Volume (Only if a different WQCV Design Volume is desired)</p> <p>I) Predominant Watershed NRCS Soil Group</p> <p>J) Excess Urban Runoff Volume (EURV) Design Volume For HSG A: $EURV_A = 1.68 * i^{1.28}$ For HSG B: $EURV_B = 1.36 * i^{1.08}$ For HSG C/D: $EURV_{C/D} = 1.20 * i^{1.08}$ </p>	<p>$I_a =$ <u> 35.5 </u> %</p> <p>$i =$ <u> 0.355 </u></p> <p>Area = <u> 30,280 </u> ac</p> <p>$d_6 =$ <u> 0.42 </u> in</p> <div style="border: 1px solid black; padding: 5px; margin: 5px 0;"> Choose One <input type="radio"/> Water Quality Capture Volume (WQCV) <input checked="" type="radio"/> Excess Urban Runoff Volume (EURV) </div> <p>$V_{DESIGN} =$ <u> 0.423 </u> ac-ft</p> <p>$V_{DESIGN\ OTHER} =$ <u> 0.413 </u> ac-ft</p> <p>$V_{DESIGN\ USER} =$ _____ ac-ft</p> <div style="border: 1px solid black; padding: 5px; margin: 5px 0;"> Choose One <input type="radio"/> A <input checked="" type="radio"/> B <input type="radio"/> C / D </div> <p>EURV = <u> 1.121 </u> ac-ft</p>
<p>2. Basin Shape: Length to Width Ratio (A basin length to width ratio of at least 2:1 will improve TSS reduction.)</p>	<p>L : W = <u> 2.0 </u> : 1</p>
<p>3. Basin Side Slopes</p> <p>A) Basin Maximum Side Slopes (Horizontal distance per unit vertical, 4:1 or flatter preferred)</p>	<p>Z = <u> 4.00 </u> ft / ft</p>
<p>4. Inlet</p> <p>A) Describe means of providing energy dissipation at concentrated inflow locations:</p>	<p>_____</p> <p>_____</p> <p>_____</p> <p>_____</p>

Design Procedure Form: Extended Detention Basin (EDB)

Sheet 2 of 4

Designer: Matt Larson
Company: Classic Consulting Engineers & Surveyors, LLC
Date: November 20, 2018
Project: FOREST LAKES - PHASE 2
Location: POND C

<p>5. Forebay</p> <p>A) Minimum Forebay Volume ($V_{FMIN} =$ <u> 3% </u> of the WQCV)</p> <p>B) Actual Forebay Volume</p> <p>C) Forebay Depth ($D_F =$ <u> 18 </u> inch maximum)</p> <p>D) Forebay Discharge</p> <p style="margin-left: 20px;">i) Undetained 100-year Peak Discharge</p> <p style="margin-left: 20px;">ii) Forebay Discharge Design Flow ($Q_F = 0.02 * Q_{100}$)</p> <p>E) Forebay Discharge Design</p> <p>F) Discharge Pipe Size (minimum 8 inches)</p> <p>G) Rectangular Notch Width</p>	<p>$V_{FMIN} =$ <u> 0.012 </u> ac-ft</p> <p>$V_F =$ <u> 0.015 </u> ac-ft</p> <p>$D_F =$ <u> 12.0 </u> in</p> <p>$Q_{100} =$ <u> 117.20 </u> cfs</p> <p>$Q_F =$ <u> 2.34 </u> cfs</p> <div style="border: 1px solid black; padding: 5px; margin: 5px 0;"> <p>Choose One</p> <p><input type="radio"/> Berm With Pipe</p> <p><input checked="" type="radio"/> Wall with Rect. Notch</p> <p><input type="radio"/> Wall with V-Notch Weir</p> </div> <p align="right">(flow too small for berm w/ pipe)</p> <p>Calculated $D_c =$ <u> </u> in</p> <p>Calculated $W_N =$ <u> 10.8 </u> in</p>
<p>6. Trickle Channel</p> <p>A) Type of Trickle Channel</p> <p>F) Slope of Trickle Channel</p>	<div style="border: 1px solid black; padding: 5px; margin: 5px 0;"> <p>Choose One</p> <p><input checked="" type="radio"/> Concrete</p> <p><input type="radio"/> Soft Bottom</p> </div> <p>$S =$ <u> 0.0050 </u> ft / ft</p>
<p>7. Micropool and Outlet Structure</p> <p>A) Depth of Micropool (2.5-foot minimum)</p> <p>B) Surface Area of Micropool (10 ft² minimum)</p> <p>C) Outlet Type</p> <p>D) Smallest Dimension of Orifice Opening Based on Hydrograph Routing (Use UD-Detention)</p> <p>E) Total Outlet Area</p>	<p>$D_M =$ <u> 2.5 </u> ft</p> <p>$A_M =$ <u> 250 </u> sq ft</p> <div style="border: 1px solid black; padding: 5px; margin: 5px 0;"> <p>Choose One</p> <p><input checked="" type="radio"/> Orifice Plate</p> <p><input type="radio"/> Other (Describe):</p> </div> <p>_____</p> <p>_____</p> <p>$D_{orifice} =$ <u> 1.00 </u> inches</p> <p>$A_{ot} =$ <u> 6.00 </u> square inches</p>

Design Procedure Form: Extended Detention Basin (EDB)

Sheet 3 of 4

Designer: Matt Larson
Company: Classic Consulting Engineers & Surveyors, LLC
Date: November 20, 2018
Project: FOREST LAKES - PHASE 2
Location: POND C

<p>8. Initial Surcharge Volume</p> <p>A) Depth of Initial Surcharge Volume (Minimum recommended depth is 4 inches)</p> <p>B) Minimum Initial Surcharge Volume (Minimum volume of 0.3% of the WQCV)</p> <p>C) Initial Surcharge Provided Above Micropool</p>	<p>$D_{IS} =$ <u> 4 </u> in</p> <p>$V_{IS} =$ <u> 54.0 </u> cu ft</p> <p>$V_s =$ <u> 83.3 </u> cu ft</p>
<p>9. Trash Rack</p> <p>A) Water Quality Screen Open Area: $A_t = A_{ref} * 38.5 * (e^{-0.095D})$</p> <p>B) Type of Screen (If specifying an alternative to the materials recommended in the USDCM, indicate "other" and enter the ratio of the total open area to the total screen area for the material specified.)</p> <p style="padding-left: 40px;">Other (Y/N): <u> N </u></p> <p>C) Ratio of Total Open Area to Total Area (only for type "Other")</p> <p>D) Total Water Quality Screen Area (based on screen type)</p> <p>E) Depth of Design Volume (EURV or WQCV) (Based on design concept chosen under 1E)</p> <p>F) Height of Water Quality Screen (H_{TR})</p> <p>G) Width of Water Quality Screen Opening ($W_{opening}$) (Minimum of 12 inches is recommended)</p>	<p>$A_t =$ <u> 210 </u> square inches</p> <p><u> S.S. Well Screen with 60% Open Area </u></p> <hr/> <hr/> <p>User Ratio =</p> <p>$A_{total} =$ <u> 350 </u> sq. in.</p> <p>$H =$ <u> 5 </u> feet</p> <p>$H_{TR} =$ <u> 88 </u> inches</p> <p>$W_{opening} =$ <u> 12.0 </u> inches</p>

Design Procedure Form: Extended Detention Basin (EDB)

Designer: Matt Larson
Company: Classic Consulting Engineers & Surveyors, LLC
Date: November 20, 2018
Project: FOREST LAKES - PHASE 2
Location: POND C

<p>10. Overflow Embankment</p> <p>A) Describe embankment protection for 100-year and greater overtopping:</p> <p>B) Slope of Overflow Embankment (Horizontal distance per unit vertical, 4:1 or flatter preferred)</p>	<p>38' WIDE SPILLWAY AT ELEV. 7039.00</p> <hr/> <hr/> <p>10.00</p>
<p>11. Vegetation</p>	<p>Choose One</p> <p><input type="radio"/> Irrigated</p> <p><input checked="" type="radio"/> Not Irrigated</p>
<p>12. Access</p> <p>A) Describe Sediment Removal Procedures</p>	<p>12' WIDE ACCESS ROAD W/ MIN. 30' CL RADIUS TO POND BOTTOM</p> <hr/> <hr/> <hr/> <hr/>
<p>Notes: _____</p> <hr/> <hr/> <hr/>	

JOB NAME: FOREST LAKES PHASE 2
 JOB NUMBER: 1175.21
 DATE: 02/19/19
 CALCULATED BY: MAL

POND C EURV

POND SIZING WITH PONDPACK EQUATION:

INSERT POND DESIGN SIZE INFO: (RED)

POND ELEVATION :	
(from lowest to highest)	
	7030.00
	7030.00
	7032.00
	7034.00

AREA (BTM to TOP):		
	-	acres
390	0.01	acres
16,854	0.39	acres
22,197	0.51	acres
	-	acres
	-	acres
	-	acres
	-	acres
	-	acres
	-	acres
	-	acres
	-	acres

PRELIMINARY SIZE:

VOLUME = $\frac{1}{3}\{(EL2-EL1)\cdot(A1+A2+((A1\cdot A2)^{.5}))\}$

CUMMULATIVE VOLUME:

-	AC-FT	from	7,030	to	7,030	
0.30	AC-FT	from	7,030	to	7,032	0.30
0.88	AC-FT	from	7,032	to	7,034	1.18
-	AC-FT	from	7,034	to	-	1.18
-	AC-FT	from	-	to	-	1.18
-	AC-FT	from	-	to	-	1.18
-	AC-FT	from	-	to	-	1.18
-	AC-FT	from	-	to	-	1.18
-	AC-FT	from	-	to	-	1.18
-	AC-FT	from	-	to	-	1.18
-	AC-FT	from	-	to	-	1.18

*SIZING IS FOR PRELIMINARY PURPOSES ONLY.

VOLUME = 1.18 AC-FT

APPROXIMATE SURFACE AREA REQUIREMENT

POND DEPTH (FT)	POND VOLUME		SURFACE AREA (SF)
	AC-FT	CF	
4	1.18	= 51,612	12,903
6	1.18	= 51,612	8,602
8	1.18	= 51,612	6,452
10	1.18	= 51,612	5,161

JOB NAME: FOREST LAKES PHASE 2
 JOB NUMBER: 1175.21
 DATE: 02/19/19
 CALCULATED BY: MAL

POND C - SPILLWAY

POND SIZING WITH PONDPACK EQUATION:
 INSERT POND DESIGN SIZE INFO: (RED)

POND ELEVATION :	
(from lowest to highest)	
	7030.00
	7030.00
	7032.00
	7034.00
	7036.00
	7038.00
	7039.00

AREA (BTM to TOP):		
	-	acres
390	0.01	acres
16,854	0.39	acres
22,197	0.51	acres
28,151	0.65	acres
34,588	0.79	acres
37,856	0.87	acres
	-	acres
	-	acres
	-	acres
	-	acres
	-	acres

PRELIMINARY SIZE:						CUMMULATIVE VOLUME:	
VOLUME = $1/3\{(EL2-EL1)*(A1+A2+((A1*A2)^{.5}))\}$							
-	AC-FT	from	7,030	to	7,030		
0.30	AC-FT	from	7,030	to	7,032		0.30
0.88	AC-FT	from	7,032	to	7,034		1.18
1.14	AC-FT	from	7,034	to	7,036		2.33
1.42	AC-FT	from	7,036	to	7,038		3.75
0.82	AC-FT	from	7,038	to	7,039		4.57
-	AC-FT	from	7,039	to	-		4.57
-	AC-FT	from	-	to	-		4.57
-	AC-FT	from	-	to	-		4.57
-	AC-FT	from	-	to	-		4.57
-	AC-FT	from	-	to	-		4.57

*SIZING IS FOR PRELIMINARY PURPOSES ONLY.

VOLUME = 4.57 AC-FT

APPROXIMATE SURFACE AREA REQUIREMENT

POND DEPTH (FT)	POND VOLUME			SURFACE AREA (SF)
	AC-FT	=	CF	
4	4.57	=	#####	49,797
6	4.57	=	#####	33,198
8	4.57	=	#####	24,899
10	4.57	=	#####	19,919

JOB NAME: FOREST LAKES PHASE 2
 JOB NUMBER: 1175.21
 DATE: 02/19/19
 CALCULATED BY: MAL

POND C - TOP OF BERM

POND SIZING WITH PONDPACK EQUATION:
 INSERT POND DESIGN SIZE INFO: (RED)

POND ELEVATION :	
(from lowest to highest)	
	7030.00
	7030.00
	7032.00
	7034.00
	7036.00
	7038.00
	7040.00
	7042.00

AREA (BTM to TOP):		
	-	acres
390	0.01	acres
16,854	0.39	acres
22,197	0.51	acres
28,151	0.65	acres
34,588	0.79	acres
41,409	0.95	acres
48,674	1.12	acres
	-	acres
	-	acres
	-	acres
	-	acres

PRELIMINARY SIZE:						CUMMULATIVE VOLUME:	
VOLUME = $1/3\{(EL2-EL1)*(A1+A2+((A1*A2)^{.5}))\}$							
-	AC-FT	from	7,030	to	7,030		
0.30	AC-FT	from	7,030	to	7,032		0.30
0.88	AC-FT	from	7,032	to	7,034		1.18
1.14	AC-FT	from	7,034	to	7,036		2.33
1.42	AC-FT	from	7,036	to	7,038		3.75
1.72	AC-FT	from	7,038	to	7,040		5.47
2.05	AC-FT	from	7,040	to	7,042		7.52
-	AC-FT	from	7,042	to	-		7.52
-	AC-FT	from	-	to	-		7.52
-	AC-FT	from	-	to	-		7.52
-	AC-FT	from	-	to	-		7.52

*SIZING IS FOR PRELIMINARY PURPOSES ONLY.


VOLUME = 7.52 AC-FT

APPROXIMATE SURFACE AREA REQUIREMENT

POND DEPTH (FT)	POND VOLUME			SURFACE AREA (SF)
	AC-FT	=	CF	
4	7.52	=	#####	81,891
6	7.52	=	#####	54,594
8	7.52	=	#####	40,945
10	7.52	=	#####	32,756

DETENTION BASIN STAGE-STORAGE TABLE BUILDER


UD-Detention, Version 3.07 (February 2017)



Detention Basin Outlet Structure Design

UD-Detention, Version 3.07 (February 2017)

Project: FOREST LAKES PHASE 2
Basin ID: POND C - PRELIMINARY DESIGN



	Stage (ft)	Zone Volume (ac-ft)	Outlet Type
Zone 1 (WQCV)	2.07	0.423	Orifice Plate
Zone 2 (EURV)	3.66	0.695	Orifice Plate
Zone 3 (100-year)	5.67	1.120	Weir&Pipe (Restrict)
		2.238	Total

User Input: Orifice at Underdrain Outlet (typically used to drain WQCV in a Filtration BMP)

Underdrain Orifice Invert Depth = ft (distance below the filtration media surface)
Underdrain Orifice Diameter = inches

Calculated Parameters for Underdrain

Underdrain Orifice Area = ft²
Underdrain Orifice Centroid = feet

User Input: Orifice Plate with one or more orifices or Elliptical Slot Weir (typically used to drain WQCV and/or EURV in a sedimentation BMP)

Invert of Lowest Orifice = ft (relative to basin bottom at Stage = 0 ft)
Depth at top of Zone using Orifice Plate = ft (relative to basin bottom at Stage = 0 ft)
Orifice Plate: Orifice Vertical Spacing = inches
Orifice Plate: Orifice Area per Row = inches

Calculated Parameters for Plate

WQ Orifice Area per Row = ft²
Elliptical Half-Width = feet
Elliptical Slot Centroid = feet
Elliptical Slot Area = ft²

User Input: Stage and Total Area of Each Orifice Row (numbered from lowest to highest)

	Row 1 (required)	Row 2 (optional)	Row 3 (optional)	Row 4 (optional)	Row 5 (optional)	Row 6 (optional)	Row 7 (optional)	Row 8 (optional)
Stage of Orifice Centroid (ft)	0.00	1.33	2.66					
Orifice Area (sq. inches)	3.00	3.00	6.00					

	Row 9 (optional)	Row 10 (optional)	Row 11 (optional)	Row 12 (optional)	Row 13 (optional)	Row 14 (optional)	Row 15 (optional)	Row 16 (optional)
Stage of Orifice Centroid (ft)								
Orifice Area (sq. inches)								

User Input: Vertical Orifice (Circular or Rectangular)

	Not Selected	Not Selected	
Invert of Vertical Orifice =	N/A	N/A	ft (relative to basin bottom at Stage = 0 ft)
Depth at top of Zone using Vertical Orifice =	N/A	N/A	ft (relative to basin bottom at Stage = 0 ft)
Vertical Orifice Diameter =	N/A	N/A	inches

Calculated Parameters for Vertical Orifice

	Not Selected	Not Selected	
Vertical Orifice Area =	N/A	N/A	ft ²
Vertical Orifice Centroid =	N/A	N/A	feet

User Input: Overflow Weir (Dropbox) and Grate (Flat or Sloped)

	Zone 3 Weir	Not Selected	
Overflow Weir Front Edge Height, H _o =	4.00	N/A	ft (relative to basin bottom at Stage = 0 ft)
Overflow Weir Front Edge Length =	6.00	N/A	feet
Overflow Weir Slope =	4.00	N/A	H:V (enter zero for flat grate)
Horiz. Length of Weir Sides =	4.00	N/A	feet
Overflow Grate Open Area % =	85%	N/A	% grate open area/total area
Debris Clogging % =	50%	N/A	%

Calculated Parameters for Overflow Weir

	Zone 3 Weir	Not Selected	
Height of Grate Upper Edge, H _g =	5.00	N/A	feet
Overflow Weir Slope Length =	4.12	N/A	feet
Grate Open Area / 100-yr Orifice Area =	8.32	N/A	should be ≥ 4
Overflow Grate Open Area w/o Debris =	21.03	N/A	ft ²
Overflow Grate Open Area w/ Debris =	10.51	N/A	ft ²

User Input: Outlet Pipe w/ Flow Restriction Plate (Circular Orifice, Restrictor Plate, or Rectangular Orifice)

	Zone 3 Restrictor	Not Selected	
Depth to Invert of Outlet Pipe =	0.20	N/A	ft (distance below basin bottom at Stage = 0 ft)
Outlet Pipe Diameter =	24.00	N/A	inches
Restrictor Plate Height Above Pipe Invert =	18.00	N/A	inches

Calculated Parameters for Outlet Pipe w/ Flow Restriction Plate

	Zone 3 Restrictor	Not Selected	
Outlet Orifice Area =	2.53	N/A	ft ²
Outlet Orifice Centroid =	0.83	N/A	feet
Half-Central Angle of Restrictor Plate on Pipe =	2.09	N/A	radians

User Input: Emergency Spillway (Rectangular or Trapezoidal)

Spillway Invert Stage = ft (relative to basin bottom at Stage = 0 ft)
Spillway Crest Length = feet
Spillway End Slopes = H:V
Freeboard above Max Water Surface = feet

Calculated Parameters for Spillway




Spillway Design Flow Depth = feet
Stage at Top of Freeboard = feet
Basin Area at Top of Freeboard = acres

Routed Hydrograph Results

	WQCV	EURV	2 Year	5 Year	10 Year	25 Year	50 Year	100 Year	500 Year
Design Storm Return Period =									
One-Hour Rainfall Depth (in) =	0.53	1.07	1.19	1.50	1.75	2.00	2.25	2.52	3.10
Calculated Runoff Volume (acre-ft) =	0.423	1.118	0.871	1.224	1.789	2.808	3.486	4.375	6.081
OPTIONAL Override Runoff Volume (acre-ft) =									
Inflow Hydrograph Volume (acre-ft) =	0.423	1.118	0.871	1.223	1.790	2.809	3.487	4.377	6.075
Predevelopment Unit Peak Flow, q (cfs/acre) =	0.00	0.00	0.01	0.02	0.18	0.62	0.86	1.16	1.69
Predevelopment Peak Q (cfs) =	0.0	0.0	0.3	0.585	5.6	18.8	26.0	35.1	51.2
Peak Inflow Q (cfs) =	6.8	17.8	13.9	19.5	28.3	44.2	54.7	68.4	94.2
Peak Outflow Q (cfs) =	0.2	0.5	0.4	0.553	4.6	18.7	26.2	28.1	31.8
Ratio Peak Outflow to Predevelopment Q =	N/A	N/A	N/A	0.9	0.8	1.0	1.0	0.8	0.6
Structure Controlling Flow =	Plate	Plate	Plate	Plate	Overflow Grate 1	Overflow Grate 1	Outlet Plate 1	Outlet Plate 1	Outlet Plate 1
Max Velocity through Grate 1 (fps) =	N/A	N/A	N/A	N/A	0.2	0.8	1.2	1.3	1.5
Max Velocity through Grate 2 (fps) =	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Time to Drain 97% of Inflow Volume (hours) =	38	59	54	60	62	58	56	53	48
Time to Drain 99% of Inflow Volume (hours) =	40	63	57	65	68	66	65	64	62
Maximum Ponding Depth (ft) =	1.99	3.50	3.00	3.71	4.42	4.98	5.27	5.95	7.46
Area at Maximum Ponding Depth (acres) =	0.38	0.48	0.45	0.49	0.54	0.58	0.60	0.64	0.75
Maximum Volume Stored (acre-ft) =	0.388	1.045	0.813	1.142	1.507	1.825	1.989	2.416	3.470

Detention Basin Outlet Structure Design

UD-Detention, Version 3.07 (February 2017)



S-A-V-D Chart Axis Override

	X-axis	Left Y-Axis	Right Y-Axis
minimum bound			
maximum bound			

DRAINAGE MAPS









EXHIBIT A
 OVERALL EXISTING HYDROLOGY
 FOREST LAKES DEVELOPMENT
 MASTER DEVELOPMENT DRAINAGE PLAN
 FOREST LAKES, LLC
 EL PASO COUNTY, COLORADO

Kiowa Engineering Corporation
 2814 International Circle
 Colorado Springs, Colorado
 80910 - 3127
 (719) 630 - 7342



LEGEND	
LM1050	DRAINAGE BASIN DESIGNATION
352.54 ac	DRAINAGE BASIN AREA
2.2 cfs	5-YEAR RUNOFF
4.3 cfs	100-YEAR RUNOFF
△	DESIGN POINT
—	DRAINAGE BASIN BOUNDARY
→	FLOW DIRECTION

SUB-BASINS	BASIN AREA (sq mi)	5-YEAR		100-YEAR	
		PEAK FLOW (cfs)	MAX. STAGE (Elev)	PEAK FLOW (cfs)	MAX. STAGE (Elev)
NBC151	0.77	329		920	
NBC153	0.82	106		490	
SBC141	0.91	388		1,060	
SBC143	1.28	196		890	
BC1210	0.66	37		280	
BC1220	0.47	69		280	
Bristle Cone	22.03	3,185	6892.5	11,970	6895.6
BC1230	0.12	8		64	
BC1240	0.37	22		150	
BC1250	0.04	2		21	
Pinon	0.41	9	6850.1	75	6850.3
BC1260	0.12	7		59	
BC1270	0.18	12		79	
BC1280	0.09	6		42	
HLC145	0.56	351		770	
HYC161	0.73	266		780	
HYC163	0.71	40		320	
HYC165	0.45	21		160	
HYC167	0.6	64		330	
DESIGN POINTS					
DP143	20.35	4,524		14,080	
DP145	20.9	4,756		14,690	
DP155	25.93	3,470		13,370	
DP167	26.8	3,499		13,550	
DP1220	22.03	4,827		15,120	
DP1230	22.57	3,185		12,040	
DP1250	0.41	24		170	




(1) PEAK FLOWS INTO MONUMENT CREEK FROM BEAVER CREEK.
 3,459 cfs @ 1170
 13,550 cfs @ 1170

(2) DP167A PEAK FLOWS FROM REGIONAL HYDROLOGICAL ANALYSIS (MONUMENT CREEK DEPS MODEL)
 5,087 cfs @ 1170
 20,081 cfs @ 1170

EXHIBIT B
LOCALIZED EXISTING HYDROLOGY
 24-HOUR TYPE II STORM
FOREST LAKES DEVELOPMENT
MASTER DEVELOPMENT DRAINAGE PLAN
 FOREST LAKES, LLC
 EL PASO COUNTY, COLORADO

Kiowa Engineering Corporation
 2814 International Circle
 Colorado Springs, Colorado
 80910 - 3127
 (719) 630 - 7342



LEGEND	
○ LM1050 352.54 ac	DRAINAGE BASIN DESIGNATION
○	DRAINAGE BASIN AREA
— 4 cfs 7 cfs	5-YEAR RUNOFF 100-YEAR RUNOFF
△	DESIGN POINT
—	DRAINAGE BASIN BOUNDARY
→	FLOW DIRECTION

(1) PEAK FLOWS INTO MONUMENT CREEK FROM BEAVER CREEK.
 (2) DP167A PEAK FLOWS FROM REGIONAL HYDROLOGICAL ANALYSIS (MONUMENT CREEK DIPS MORE)

SUB-BASINS	BASIN AREA (sq mi)	5-YEAR (1)		100-YEAR (1)	
		PEAK FLOW (cfs)	MAX. STAGE (Elev)	PEAK FLOW (cfs)	MAX. STAGE (Elev)
NBC151	0.77	329		920	
NBC153	0.82	108		500	
SBC141	0.91	388		1,070	
SBC143	1.28	201		910	
BC1210	0.66	49		320	
BC1220	0.47	74		290	
Bristle Cone	22.03	3,211	6891.9	12,020	6894.6
BC1230	0.12	10		68	
BC1240	0.37	25		160	
BC1250	0.04	10		40	
Pinon	0.41	12	6850.1	87	6850.3
BC1260	0.12	7		59	
BC1270	0.18	16		90	
BC1280	0.09	6		42	
HLC145	0.56	372		800	
HYC161	0.73	266		780	
HYC163	0.71	44		330	
HYC165	0.45	30		190	
HYC167	0.6	64		320	
DESIGN POINTS					
DP143	20.35	4,528		14,090	
DP145	20.9	4,772		14,720	
DP155	25.93	3,507		13,460	
DP167	26.8	3,538		13,650	
DP1220	22.03	4,860		15,190	
DP1230	22.57	3,216		12,100	
DP1250	0.41	31		190	






EXHIBIT C
LOCALIZED FUTURE HYDROLOGY
 24-HOUR TYPE II STORM
FOREST LAKES DEVELOPMENT
MASTER DEVELOPMENT DRAINAGE PLAN
 FOREST LAKES, LLC
 EL PASO COUNTY, COLORADO

Kiowa Engineering Corporation
 2814 International Circle
 Colorado Springs, Colorado
 80910-3127
 (719) 630-7342

(1) THE DISCHARGES LISTED BELOW REPRESENT THE BASINS AS FULLY DEVELOPED WITHOUT DETENTION.



LEGEND


- LM1050 DRAINAGE BASIN DESIGNATION
- 382.54 ac DRAINAGE BASIN AREA
- $\frac{2.2 \text{ cfs}}{4.3 \text{ cfs}}$ 5-YEAR RUNOFF
100-YEAR RUNOFF
- \triangle DESIGN POINT
- DRAINAGE BASIN BOUNDARY
- C-13 CONVEYANCE ELEMENT/
HYDRAULIC STRUCTURE
- - - TIME OF CONCENTRATION FLOW PATH
- DETENTION BASIN LOCATION
- - - 100-YEAR FLOODPLAIN LIMITS

SUMMARY OF DRAINAGE BASINS AND DESIGN POINTS

BASIN / DP	DEVELOPED CONDITION		BASIN / DP	DEVELOPED CONDITION		BASIN / DP	DEVELOPED CONDITION	
	5 Year	100 Year		5 Year	100 Year		5 Year	100 Year
A	15 cfs	35 cfs	T	5 cfs	13 cfs	OS5	22 cfs	54 cfs
B	4 cfs	10 cfs	U	12 cfs	27 cfs	OS5A	17 cfs	41 cfs
C	11 cfs	25 cfs	V	5 cfs	17 cfs	OS7	6 cfs	14 cfs
D	22 cfs	51 cfs	W	11 cfs	22 cfs	OS7	6 cfs	16 cfs
E	24 cfs	57 cfs	X	13 cfs	26 cfs	DP A1	46 cfs	114 cfs
E1	11 cfs	25 cfs	Y	9 cfs	18 cfs	DP C1	19 cfs	46 cfs
F	5 cfs	13 cfs	Z	9 cfs	18 cfs	DP D1	57 cfs	140 cfs
G	4 cfs	10 cfs	AA	12 cfs	24 cfs	DP G1	18 cfs	40 cfs
H	13 cfs	30 cfs	BB	3 cfs	6 cfs	DP H1	26 cfs	56 cfs
I	18 cfs	41 cfs	CC	21 cfs	49 cfs	DP H2	47 cfs	110 cfs
J	10 cfs	22 cfs	DD	12 cfs	28 cfs	DP I1	26 cfs	68 cfs
K	11 cfs	23 cfs	EE	15 cfs	35 cfs	DP M1	29 cfs	68 cfs
L	7 cfs	17 cfs	FF	9 cfs	21 cfs	DP M2	57 cfs	135 cfs
M	20 cfs	48 cfs	GG	6 cfs	13 cfs	DP O1	30 cfs	76 cfs
M1	13 cfs	31 cfs	HH	7 cfs	17 cfs	DP O2	49 cfs	120 cfs
M2	9 cfs	19 cfs	II	26 cfs	62 cfs	DP T1	76 cfs	178 cfs
N	7 cfs	17 cfs	JJ	21 cfs	50 cfs	DP Z1	35 cfs	71 cfs
O	22 cfs	53 cfs	BC1240	48 cfs	160 cfs	DP GG1	40 cfs	95 cfs
P	18 cfs	40 cfs	OS1	39 cfs	96 cfs	DP 143	4,528 cfs	14,090 cfs
Q	18 cfs	36 cfs	OS2	7 cfs	17 cfs	DP 145	4,772 cfs	14,720 cfs
R	18 cfs	39 cfs	OS3	14 cfs	34 cfs	DP 1220	4,880 cfs	15,190 cfs
S	11 cfs	24 cfs	OS4	12 cfs	30 cfs	DP 1230	3,216 cfs	12,100 cfs

SUMMARY OF DRAINAGE CONVEYANCES

CONVEYANCE NUMBER	SIZE / TYPE	CONVEYANCE NUMBER	SIZE / TYPE
A-1	ROADSIDE SWALE	V-1	54-INCH RCP
A-2	48-INCH RCP CULVERT	X-1	24-INCH RCP
A-3	ROADSIDE SWALE	X-2	36-INCH RCP
C-1	30-INCH RCP	BB-1	ROADSIDE SWALE
D-1	48-INCH RCP CULVERT	DD-1	24-INCH RCP
E-1	24-INCH RCP	DD-2	36-INCH RCP
E-2	30-INCH RCP	DD-3	36-INCH RCP
G-1	ROADSIDE SWALE	HH-1	24-INCH RCP
G-2	30-INCH RCP	HH-2	30-INCH RCP
H-1	42-INCH RCP	JJ-1	36-INCH RCP CULVERT
I-1	36-INCH RCP		
M-1	36-INCH RCP CULVERT	BC-1	3 - 15' x 8' RCB CULVERT
M-2	36-INCH RCP	BC-2	70-FT CLEAR SPAN BRIDGE
M-3	36-INCH RCP	BC-5	54-INCH RCP CULVERT
P-1	ROADSIDE SWALE		
P-2	30-INCH RCP CULVERT		
Q-1	ROADSIDE SWALE		
Q-2	48-INCH RCP CULVERT		
Q-3	42-INCH RCP		
Q-4	42-INCH RCP		



Kiowa Engineering Corporation
 2814 International Circle
 Colorado Springs, Colorado
 80910-3127
 (719) 630-7342

FOREST LAKES
MASTER DEVELOPMENT DRAINAGE PLAN
 PROPOSED HYDROLOGIC SUBBASINS & DRAINAGE STRUCTURES
 EL PASO COUNTY, COLORADO

Project No.: 00013
 Date: April 11, 2002
 Design: RNW/MWE
 Drawn: MWE
 Check: RNW
 Revisions:

UNPLATTED
FOREST SERVICE
DEPT. OF AGRICULTURE
UNITED STATES OF AMERICA

EXISTING DEBRIS
FLOWLINE

40 ACRE LOT
OWNER, TIMOTHY R.
PETERSON TRUST

40 ACRE LOT
OWNER, TIMOTHY R.
PETERSON TRUST

EXISTING 5 ACRE
HOME LOTS

OS-4
465 Q100 = 4,130 CFS
FROM DEBRIS FLOW REPORT

OS-2
19.91

E
8.96

D
24.98

OS-1
77.01

B
59.94

A
37.55


POND 'B'
- 59.94 ACRES AT 28.8%
IMPERVIOUS TRIBUTARY AREA
- EURLV = 1,765 AC. FT.
- Q100 IN = 149.4 CFS
- ALLOWABLE Q100 OUT = 82.9 CFS
- TOTAL 100YR VOLUME REQUIRED
= 3,883 AC.-FT.

POND 'A'
- 37.55 ACRES AT 41.4%
IMPERVIOUS TRIBUTARY AREA
- EURLV = 1,637 AC. FT.
- Q100 IN = 136.4 CFS
- ALLOWABLE Q100 OUT = 65.9 CFS
- TOTAL 100YR VOLUME REQUIRED
= 3,075 AC.-FT.

NOTES:

SWALES/BERMING TO BE COMPLETED TO ROUTE RUNOFF INTO INLETS. OVERFLOW PATH FOR THESE GRATED INLETS IS DOWN ADJACENT SHARED LOT LINES (SEE LOT DRAINAGE DETAILS ON SHEET 11). FINAL ROUTING AND DESIGNED TO BE COMPLETED WITH FINAL DRAINAGE REPORT(S).

INLETS AND PIPE TO BE OWNED AND MAINTAINED BY THE METRO DISTRICT FOR FOREST LAKES.



BASIN RUNOFF (RATIONAL)		
BASIN	Q5 (CFS)	Q100 (CFS)
A	54.8	132.2
B	64.1	176.0
C	46.9	117.2
D	11.0	62.4
E	3.2	21.6
F	6.6	44.6
OS-1	22.0	147.5
OS-2	6.2	41.8
OS-3	4.0	27.2
EX. A	12.1	80.9
EX. B	18.7	125.6
EX. C	10.2	68.6

DESIGN POINT SUMMARY (RATIONAL METHOD)			
DESIGN POINT	Q5 (CFS)	Q100 (CFS)	FEATURE
1	54.8	132.2	POND A
	2.0	45.3	30" OUTLET PIPE
2	22.0	147.5	GRATED INLET & BYPASS STORM
3	23.7	186.5	EXISTING CHANNEL
4	64.1	176.0	POND B
	2.2	64.6	30" OUTLET PIPE
5	1441.5	4129.9	FROM CTL REPORT - NORTH BEAVER CREEK DEBRIS FLOW RATE
6	1433.0	4116.3	PROP. BOX CULVERTS-(3) 15'x8'
7	9.8	66.1	GRATED INLET & BYPASS STORM
8	8.7	58.2	GRATED INLET & BYPASS STORM
9	1440.1	4164.4	EXISTING CHANNEL
10	1441.1	4191.5	EXISTING CHANNEL
	46.9	117.2	POND C
	1.2	24.5	30" OUTLET PIPE
12	1441.5	4199.9	EXISTING CHANNEL

LEGEND

- EXISTING GROUND CONTOUR (7000)
- PROPOSED FINISHED CONTOUR (7000)
- SUBDIVISION BOUNDARY
- LOT LINE
- PREBLES MOUSE LIMITS
- 100-YR FLOODPLAIN LIMITS
- DEBRIS FLOWLINE
- PROPOSED BASIN BOUNDARY
- DIRECTION OF DRAINAGE
- EXISTING STORM SEWER
- EXISTING STORM INLET
- PROPOSED STORM SEWER
- PROPOSED STORM INLET
- LOW POINT/HIGH POINT (LP/HP)
- BASIN IDENTIFIER
- AREA IN ACRES
- DESIGN POINT
- EXISTING WETLANDS


N:\11722\DRAWINGS\DEVELOPMENT\DR-01.dwg, 3/10/2019, 4:26:30 PM, 1:1

CLASSIC CONSULTING ENGINEERS & SURVEYORS

FOREST LAKES - FILINGS 5, 6, & 7
MDDP AMENDMENT &
PRELIMINARY DRAINAGE REPORT
DEVELOPED CONDITIONS


DESIGNED BY: MAL SCALE: (H) 1" = 150' DATE: 11/18/18
DRAWN BY: MAL SHEET: 1 OF 2
CHECKED BY: (V) 1" = N/A JOB NO.: 1175.21

619 N. Cascade Avenue, Suite 200 (719)785-0790
Colorado Springs, Colorado 80903 (719)785-0799(fax)



BASIN RUNOFF (RATIONAL)		
BASIN	Q5 (CFS)	Q100 (CFS)
A	54.8	132.2
B	64.1	176.0
C	46.9	117.2
D	11.0	62.4
E	3.2	21.6
F	6.6	44.6
OS-1	22.0	147.5
OS-2	6.2	41.8
OS-3	4.0	27.2
EX. A	12.1	80.9
EX. B	18.7	125.6
EX. C	10.2	68.6

DESIGN POINT SUMMARY (RATIONAL METHOD)			
DESIGN POINT	Q5 (CFS)	Q100 (CFS)	FEATURE
1	54.8	132.2	POND A
	2.0	45.3	30" OUTLET PIPE
2	22.0	147.5	GRATED INLET & BYPASS STORM
3	23.7	186.5	EXISTING CHANNEL
4	64.1	176.0	POND B
	2.2	64.6	30" OUTLET PIPE
5	1441.5	4129.9	FROM CIL REPORT- NORTH BEAVER CREEK DEBRIS FLOW RATE
6	1433.0	4116.3	PROP. BOX CULVERTS-(3) 15'x8'
7	9.8	66.1	GRATED INLET & BYPASS STORM
8	8.7	58.2	GRATED INLET & BYPASS STORM
9	1440.1	4164.4	EXISTING CHANNEL
10	1441.1	4191.5	EXISTING CHANNEL
11	46.9	117.2	POND C
	1.2	24.5	30" OUTLET PIPE
12	1441.5	4199.9	EXISTING CHANNEL



POND 'C'
 - 30.28 ACRES AT 35.5%
 IMPERVIOUS TRIBUTARY AREA
 - EURV = 1.118 AC. FT.
 - Q100 IN = 68.4 CFS
 - ALLOWABLE Q100 OUT = 35.1 CFS
 - TOTAL 100YR VOLUME REQUIRED
 = 2.238 AC.-FT.

FUTURE FINAL DRAINAGE REPORT
 WILL PROVIDE HYDRAULIC
 ANALYSIS FROM ALL DISCHARGE
 POINTS TO THE CREEKS

N:\1752\DRAWINGS\DEVELOPMENT\DR-01.dwg, 3/10/2019, 4:26:43 PM, 1:1

LEGEND	
EXISTING GROUND CONTOUR	(7000)
PROPOSED FINISHED CONTOUR	7000
SUBDIVISION BOUNDARY	---
LOT LINE	---
PREBLES MOUSE LIMITS	---
100-YR FLOODPLAIN LIMITS	---
DEBRIS FLOWLINE	---
PROPOSED BASIN BOUNDARY	---
DIRECTION OF DRAINAGE	→
EXISTING STORM SEWER	---
EXISTING STORM INLET	---
PROPOSED STORM SEWER	---
PROPOSED STORM INLET	---
LOW POINT/HIGH POINT	LP/HP
BASIN IDENTIFIER	(D)
AREA IN ACRES	1.41
DESIGN POINT	(1)
EXISTING WETLANDS	---

619 N. Cascade Avenue, Suite 200
 Colorado Springs, Colorado 80903
 (719)785-0790
 (719)785-0799(Fax)

FOREST LAKES - FILINGS 5, 6, & 7
 MDDP AMENDMENT &
 PRELIMINARY DRAINAGE REPORT
 DEVELOPED CONDITIONS

DESIGNED BY	MAL	SCALE	DATE	11/18/18
DRAWN BY	MAL	(H) 1"= 150'	SHEET	2 OF 2
CHECKED BY	(V) 1"= N/A	JOB NO.	1175.21	