

Luminaire Schedule							
Symbol	Qty	Label	Arrangement	LMF	Lum. Lumens	Lum. Watts	Part Number
	8	K-5SH 2@180	2 @ 180°	1.010	16897	130	OSQ-A-NM-5SH-K-40K-UL-_-PML w/OSQ-DA_

Calculation Summary (Footcandles calculated using predicted lumen values @ 50K hrs of operation and 5°C ambient)						
Label	Units	Avg	Max	Min	Avg/Min	Max/Min
Grade	Fc	0.32	3.6	0.0	N.A.	N.A.
Lot	Fc	1.28	3.6	0.2	6.40	18.00

Pole Schedule
 (8) CL-SSP-4011-25-D2- (25' X 4" X 11ga STEEL SQUARE POLE)
 Poles to be mounted atop of 3' concrete base
 Customer to verify poles meet local windzone requirements

Fixtures mounted at 28' AFG as specified in fixture label

Additional Equipment:
 (16) OSQ-DA Direct Arm Mount
 (1) XA-SENSREM Hand-Held Remote

*** CUSTOMER TO VERIFY ORDERING INFORMATION AND CATALOGUE NUMBER PRIOR TO PLACING ORDER ***

