



VICINITY MAP
NO SCALE


HOUSE FOOTPRINT
NO SCALE



SITE PLAN
SCALE: 1" = 20'



HOUSE ELEVATION
SCALE: 1/8" = 1'-0"



RETAINING WALL SECTION
NTS

SITE INFO:

ADDRESS:
6141 COFFEE POT ROAD

LEGAL:
SITE 2-125 (AR) SITE ADDITION TO CRYSTAL PARK SUBDIVISION NO. 2, A PORTION NORTHWEST ONE QUARTER OF SECTION 18, TOWNSHIP 14 SOUTH, RANGE 67 WEST OF THE SIXTH PRINCIPLE MERIDIAN, EL PASO COUNTY, STATE OF COLORADO.


SITE DATA:
LOT SIZE = 00,000 SQFT
BUILDING FOOTPRINT =
HOUSE = 0000 SQFT
GARAGE = 0000 SQFT
PORCH = 0000 SQFT
DECK = 0000 SQFT
TOTAL = 0000 SQFT
LOT COVERAGE = 00%
ZONING = FUD
TAX SCHEDULE # = 74100-00-161
BUILDING HEIGHT = SEE ELEVATIONS

TOPO INFO:
AS PROVIDED BY JOHN KRATZ
PROFESSIONAL SURVEYOR

SITE NOTES:

- 1) Topographic information is as supplied by others. See below for info.
- 2) Dashed lines indicate existing contours. Solid lines indicate proposed contours.
- 3) Contractor to verify easements.
- 4) Contractor to limit cut and fill areas and limit material and vehicle storage to the building areas in order to minimize vegetation and site disturbance.
- 5) Final landscaping to be determined by the Contractor/Owner(s). It shall minimize impact to the site. All landscaping to be completed by the Contractor/Owner(s).
- 6) Use wattles and silt fencing to minimize erosion during construction. And also stabilize area with seeded blankets for erosion control as necessary.
- 7) Earth materials are not to be stockpiled on streets or sidewalks, but on site or staging areas.
- 8) Contractor is required to provide positive drainage away from and around structure in all directions as shown.
- 9) Any boulder retaining walls shall be 48" max high and 48"-60" min apart laterally if 2) or more retaining walls exist. Or retaining walls shall be engineered by a licensed CO soils engineer.
- 10) General Contractor, Subcontractors, Suppliers, and Owner(s) shall familiarize themselves & verify all notes, dimensions and information on drawing(s) prior to starting construction. It shall be the responsibility of those parties to report any changes and/or discrepancies to the Designer. Questions regarding these drawings such as: drawing interpretation, dimensions, notes, scale and other similar questions shall be brought to the attention of the Designer immediately, in writing. Failure to do any of the above shall relieve the designer of any errors. Designer shall not be responsible for any changes not noted in writing to this plan.

SITE LEGEND:



SITE TERMS:

ABBREVIATIONS:
BOW = BOTTOM OF RETAINING WALL
(E) = EXISTING TO REMAIN
LL = LOWER LEVEL
ML = MAIN LEVEL
(N) = NEW CONSTRUCTION
(R) = REMOVE
R.O.W. = RIGHT OF WAY
SB = SETBACK
SQ. FT. OR SF = SQUARE FEET
TOP = TOP OF FOUNDATION
TOW = TOW OF RETAINING WALL
UL = UPPER LEVEL
WO = WALKOUT

REVISIONS

LGA STUDIOS
201 E. Las Animas Street
Suite 113
Colorado Springs, CO. 80903
Phone: (719) 635-0880
Fax: (719) 999-8310
LGAstudiosmailbox@gmail.com
www.lgastudios.com

CONTRACTOR
PALACE HOMES
1238 WEST COLORADO AVE. #710
COLORADO SPRINGS, CO. 80904
PHONE: 719.632.8838
FAX: 719.632.8838
EMAIL: INFO@PALACEHOMESINC.COM

THE
WALLACE RESIDENCE
6141 COFFEE POT ROAD
COMPUTER FILE #P-1767

DRAWN BY: JP & DMS

CHECKED BY: LGAstudios
PLOT 01/20/20 9:56 AM

SITE PLAN
VICINITY MAP
SITE NOTES

Sheet #
SP1
OF 1 Sheets

Copyright 2018 by LGA Studios. No part of this plan may be reproduced or transmitted in any form or by any means, electronic or mechanical, including photocopying, recording, or any information storage and retrieval system, without the written approval of LGA Studios and the owner. No derivative work of this plan may be made without prior written permission. The user of this plan does not warrant the accuracy of any building, unless approved in writing by LGA Studios.