



COLORADO
Department of Transportation
Region 2

5615 Wills Blvd.
Pueblo, CO 81008-2349

April 16, 2020

El Paso County
Attn: Steven Jacobsen, P.E.
El Paso County Dept. of Public Works
3275 Akers Drive
Colorado Springs, CO 80922

Dear Mr. Jacobsen,

This letter is written to confirm that the CDOT Project on SH 94 & Peyton Intersection (#21543) in El Paso County, complies with the requirements of the Colorado Department of Transportation (CDOT) erosion and sediment control processes and the CDOT Municipal Separate Storm Sewer System (MS4) permit. This project includes four phases. The first phase, consists of the driveway relocation on NE quadrant and field access gate relocation on NW quadrant. Phase two will consist of completing eastbound shoulder and embankment and remove paved access to CenturyLink facility on CDOT ROW. Phase three will consist of completing westbound roadway and embankment. Phase four will consist of mill and fill HMA over project limit.

CDOT has created a Storm Water Management Plan (SWMP) and Kiewit Construction will administer this SWMP in compliance with CDOT Standards. The project has also been issued a CDPS SCP from CDPHE. All earthwork, additional impervious surfaces and drainage installations will be supported with adequate control measures per CDOT Standards. A pre-construction baseline vegetation density has been recorded and upon construction completion, CDOT will be responsible for the re-establishment of all disturbed areas within the limits of disturbance to a minimum of 70% of the baseline vegetative cover prior to initiating the closure of the storm water permit.

CDOT and Kiewit will take full administrative control of the storm water responsibilities during the construction of this project within CDOT ROW. This administrative control will avoid overlap of MS4 permitting requirements with El Paso County's permit, and the project will follow CDOT's construction storm water requirements as follows:

CDOT has a MS4 permit with CDPHE and is required by this permit to comply with the construction storm water program elements as outlined in CDOT Erosion Control and Storm Water Quality Guide, CDOT Standard Specifications 107.25 and 208, CDOT Standard Plan M-208-1 Temporary Erosion Control, CDOT Contractor Compliance Program and the CDPHE Consent Order to CDOT. This project has been reviewed and approved by the CDOT Region 2 Environmental Program.

CDOT assumes full jurisdictional control for the construction and the storm water activities for the entire project. This includes ownership of the construction storm water permit coverage, and monthly oversight



inspections and enforcement responsibility. Kiewit is responsible for administrative SWMP maintenance, weekly and post-storm event storm water and erosion control inspections following CDOT Standards. Once construction completion is near, if necessary, Kiewit will comply with any additional El Paso County permitting regulations as required.

It is understood that El Paso County reserves the right to protect their MS4 if contaminated or polluted water flows off the project and into the county storm sewer system per County Ordinance 07-01 for Prohibiting Illicit Discharge.

Sincerely,

Yun Han, Project Engineer, Region 2 North Program

