



LSC TRANSPORTATION CONSULTANTS, INC.
2504 East Pikes Peak Avenue, Suite 304
Colorado Springs, CO 80909
(719) 633-2868
FAX (719) 633-5430
E-mail: lsc@lsctrans.com
Website: <http://www.lsctrans.com>

Rising Moon
Traffic Impact Study
(LSC #S244050)
PCD File No.: SP243
September 6, 2024

Traffic Engineer's Statement

This traffic report and supporting information were prepared under my responsible charge and they comport with the standard of care. So far as is consistent with the standard of care, said report was prepared in general conformance with the criteria established by the County for traffic reports.



Developer's Statement

I, the Developer, have read and will comply with all commitments made on my behalf within this report.

Date

Rising Moon

Traffic Impact Study

Prepared for:

Pikes Peak Habitat for Humanity
c/o Bobby Ingels
Vice President
Norwood Development Group
111 South Tejon Street, Suite 222
Colorado Springs CO, 80903

SEPTEMBER 6, 2024

LSC Transportation Consultants, Inc.
Prepared by: Jeffrey C. Hodsdon, P.E.

PCD File No. SP243
LSC #S244050



CONTENTS

REPORT CONTENTS	1
LIST OF OTHER TRAFFIC REPORTS USED IN THE PREPARATION OF THIS REPORT	2
LAND USE AND ACCESS	2
Proposed Land Use	2
Proposed Site Access Locations	2
INTERSECTION SIGHT DISTANCE	3
Evaluation Elements	3
Sight Distance Field Measurements	3
Intersection Sight Distance	3
Stopping Sight Distance to Downstream Intersection.....	4
STREET AND TRAFFIC CONDITIONS AND MTCP CLASSIFICATION.....	4
Study Area Street System	4
Existing Traffic Volumes.....	5
Existing Intersection Levels of Service and Safety Records	5
Existing Pedestrian and Bicycle Facilities.....	5
TRIP GENERATION.....	5
TRIP DISTRIBUTION AND ASSIGNMENT	6
Trip Directional Distribution	6
Site-Generated Traffic.....	6
Existing + Site-Generated Traffic Volumes	7
2044 Background Traffic Volumes	7
2044 Total Traffic Volumes	7
LEVEL OF SERVICE ANALYSIS	7
Intersection Level of Service	7
Proposed West Site Access/Peaceful Meadow Street	8
Proposed East Site Access/Peaceful Meadow Street	8
Horizonview Drive/Hazy Morning Drive	8
Horizonview Drive/Prairie Sage Drive (Future).....	9
Hazy Morning Drive/Harvest Moon Terrace.....	9
Peaceful Meadow Street/Prairie Sage Drive	9

STREET CLASSIFICATIONS.....	9
ROADWAY IMPROVEMENTS.....	9
MTCP-Identified Roadway Improvements.....	10
Intersection Improvements – Auxiliary Turn Lanes.....	10
Auxiliary-Turn-Lane-Needs Evaluation and Recommendations - El Paso County Intersections	10
Auxiliary Turn Lane Needs Evaluation and Recommendations – City of Colorado Springs Intersections	12
Roadway Segment Recommendations	13
COUNTY ROAD IMPROVEMENT FEE PROGRAM	13
Transportation Impact Fees.....	13
Reimbursable Improvements	13
MULTI-MODAL TRANSPORTATION AND TDM OPPORTUNITIES.....	13
DEVIATIONS	13
FINDINGS AND CONCLUSIONS.....	13
Enclosures:	14

Table 3 and Table 5

Figure 1 - Figure 9

Appendix Figure 1

Traffic Count Reports

Synchro LOS Reports



LSC TRANSPORTATION CONSULTANTS, INC.
2504 E. Pikes Peak Ave., Suite 304
Colorado Springs, CO 80909
(719) 633-2868
FAX (719) 633-5430
E-mail: lsc@lsctrans.com
Website: <http://www.lsctrans.com>

September 6, 2024

Bobby Ingels
Vice President
Norwood Development Group
111 South Tejon Street, Suite 222
Colorado Springs CO, 80903

RE: Rising Moon
El Paso County, CO
Traffic Impact Study
LSC #S244050
PCD File No. SP243

Dear Mr. Ingels,

LSC Transportation Consultants, Inc. has prepared this Traffic Impact Study for the proposed Rising Moon subdivision in El Paso County, Colorado. The 9-acre site (El Paso County parcel ID 5503101010) is located generally east of Horizonview Drive and north of Peaceful Meadow Street.

Approximately 41 lots for single-family residential dwelling units are proposed. Access to the site is proposed to Peaceful Meadow Street.

This report has been prepared for submittal to El Paso County.

REPORT CONTENTS

The preparation of this report included the following:

- An inventory of existing roadway and traffic conditions on major thoroughfares adjacent to the site, including surface conditions, functional classification, widths, pavement markings, traffic-control signs, posted speed limits, intersection and access spacing, roadway and intersection alignments, roadway grades, and auxiliary turn lanes;
- Weekday peak-hour turning-movement traffic counts at the following "study-area" intersections:
 - Horizonview Drive/Hazy Morning Drive
 - Hazy Morning Drive/Harvest Moon Terrace
 - Peaceful Meadow Street/Harvest Moon Terrace
 - Horizonview Drive/Prairie Sage Drive (long-term only)

- Estimated average daily traffic (ADT) volumes on the study-area roadway segments;
- Projections of 20-year background traffic volumes on the study-area roadways adjacent to the site;
- The proposed site land use and access plan;
- Estimates of average weekday and weekday peak-hour trip generation for the proposed development and the estimated directional distribution of site-generated vehicle trips on roadways and intersections adjacent to and in the vicinity of the site;
- Projected site-generated and resulting total daily and peak-hour intersection traffic volumes at the study-area intersections;
- Intersection level of service (LOS) analysis at the study-area intersections; and
- Findings and recommendations.

LIST OF OTHER TRAFFIC REPORTS USED IN THE PREPARATION OF THIS REPORT

The following previously-completed traffic report was utilized in preparation of this study:

- *Meadoworks Filings 1-4 Development Plan* – by SM Rocha, LLC (March 2022) ([OAR2187](#))

For Reference: The following studies were completed more than five years ago:

- *Cuchares Ranch Filing 7* – by LSC Transportation Consultants, Inc. (May 2014) ([SF141](#))
- *Cuchares Ranch Filing 6* – by LSC Transportation Consultants, Inc. (April 2013) ([SF132](#))

LAND USE AND ACCESS

Proposed Land Use

The proposed Colorado Center Habitat for Humanity subdivision would consist of 41 lots for single-family residential dwelling units. A copy of the site plan is shown in Figure 2.

Proposed Site Access Locations

Figure 2 also shows the proposed access plan for the site. Access to/from the site is proposed via Peaceful Meadow Street at two locations. The proposed west access would be via a new north leg of the existing Peaceful Meadow Street/Harvest Moon Terrace intersection (as an extension of Harvest Moon Terrace north into the site). A second access to Peaceful Meadow Street is proposed 220 feet east of this intersection.

The 9-acre site (El Paso County parcel ID 5503101010) is located generally east of Horizonview Drive and north of Peaceful Meadow Street. Both proposed site accesses would be full-movement intersections.

INTERSECTION SIGHT DISTANCE

Evaluation Elements

Intersection Sight Distance (also referred to as “entering” or “departure” sight distance) - The criteria are contained in *ECM* Section 2.3.6.G, including Table 2-21.

Stopping Sight Distance to Downstream Intersection - Stopping sight distance along a roadway to a downstream access or intersection must meet stopping sight-distances in *ECM* Table 2-17. The criteria used for this application of stopping sight distance are from a driver’s eye of an approaching vehicle (3.5-feet height) to a height of 3.5 feet at the center of the access/intersection downstream.

Sight Distance Field Measurements

LSC conducted field-checks of the available sight distance at the access points and study-area intersections. Sight-distance field measurements utilized a driver’s-eye height of 3.5 feet and a height of 3.5 feet for a vehicle traveling along Peaceful Meadow Street. The following analysis corresponds to field-measured sight distances for the proposed site-access intersections. Field-measured sight distances for passenger vehicles are as follows:

- Proposed west site access on Peaceful Meadow Street
 - To the east – unobstructed to Peaceful Meadow/Breaking Dawn (730 feet)
 - To the west – unobstructed to current terminus of Peaceful Meadow Street
- Proposed east site access on Peaceful Meadow Street
 - To the east – unobstructed to Peaceful Meadow/Breaking Dawn (510 feet)
 - To the west – unobstructed to current terminus of Peaceful Meadow Street

Intersection Sight Distance

Intersection sight distance at the proposed site-access locations shown in the site plan assumes that lines of sight for both access points would be kept clear of any sight-distance obstructions. This includes landscaping, signage, etc. proposed for the residential development.

With a 25-mile-per-hour (mph) posted speed limit on Peaceful Meadow Street, the field-measured sight distances for both proposed site accesses would exceed the *ECM*-prescribed requirement for intersection sight distance for passenger vehicles (335 feet), as shown in the *ECM* Table 2-21.

Stopping Sight Distance to Downstream Intersection

Based on the field measurements, the “stopping sight distance to downstream intersection” would exceed the 150-foot County standard in both directions for stopping sight distance at a posted speed of 25 mph. Approaching the proposed site-access intersections on Peaceful Meadow Street, the line-of-sight is unobstructed to Peaceful Meadow Street/Breaking Dawn Street from the east and unobstructed to the future Prairie Sage Drive/Peaceful Meadow Street intersection from the west.

STREET AND TRAFFIC CONDITIONS AND MTCP CLASSIFICATION

Study Area Street System

Figure 1 shows the roads adjacent to and in the vicinity of the site. Adjacent roads serving the site are identified below, followed by a brief description of each:

Horizonview Drive is an urban, non-arterial street extending north-to-south for 1.4 miles between Drennan Road and Bradley Road. The street is 40-feet wide (curb-to-curb) with 6-inch vertical curbs on each side, detached sidewalks adjacent to most developed parcels, and no pavement markings. The street is like a residential collector-type street, as there is no individual residential lot driveway access to Horizonview. The right-of-way is about 80-feet. The posted speed limit along this paved road is 30 mph. No auxiliary turn lanes currently exist at the stop-sign-controlled T-intersection of Horizonview Drive/Hazy Morning Drive. The study intersections are within a section of Horizonview that is owned and maintained by the City of Colorado Springs. A 2,000-foot section to the south is owned and maintained by El Paso County.

Peaceful Meadow Street is an Urban Local roadway extending east-to-west for 875 feet between Breaking Dawn Street (to the east) and its terminus to the west. Additional development plans indicate that Peaceful Meadow Street would be extended approximately 300 feet to the west to form a new full-movement, four-leg intersection with Horizonview Drive. The posted speed limit along this paved road is 25 mph.

Hazy Morning Drive is an Urban Local street extending east-to-west for 0.3 miles between Horizonview Drive and Sleepy Creek Drive. The posted speed limit along this paved road is 25 mph. No auxiliary turn lanes currently exist at any intersection along Hazy Morning Drive.

Harvest Moon Terrace is a Urban Local street extending north-to-south for 570 feet between Hazy Morning Drive and Peaceful Meadow Street. The posted speed limit along this paved road is 25 mph. A north leg of the current T-intersection of Harvest Moon Terrace/Peaceful Meadow Street is planned to be constructed with this development.

Please refer to Figure 3 for existing intersection laneage, traffic control, peak-hour volumes, and average daily traffic volumes.

Existing Traffic Volumes

Vehicular turning-movement counts were conducted at the following intersections. Raw count data is attached, for reference:

Table 1: Existing Count Dates and Locations

Horizonview Drive + Hazy Morning Drive			
Peak	Date	Start	End
AM	Thursday, February 15, 2024	6:30 am	8:30 am
PM	Tuesday, February 13, 2024	4:00 pm	6:00 pm
Hazy Morning Drive + Harvest Moon Terrace			
Peak	Date	Start	End
AM	Thursday, February 15, 2024	6:30 am	8:30 am
PM	Tuesday, February 13, 2024	4:00 pm	6:00 pm
Peaceful Meadow Street + Harvest Moon Terrace			
Peak	Date	Start	End
AM	Thursday, February 15, 2024	6:30 am	8:30 am
PM	Tuesday, February 13, 2024	4:00 pm	6:00 pm

Existing Intersection Levels of Service and Safety Records

Please refer to the Level of Service section for current levels of service, including methodology, analysis, and findings.

Three years of crash data were collected at the intersection of Horizonview Drive/Hazy Morning Drive. No crashes were reported at this stop-sign-controlled intersection.

Existing Pedestrian and Bicycle Facilities

The south side of Peaceful Meadow Street currently has sidewalks. This development will be required to install a sidewalk along the north side of Peaceful Meadow Street. Sidewalks will be constructed near the site along Horizonview Drive as part of the Meadowworks project. This is detailed further in the Recommendations section of this report.

TRIP GENERATION

Estimates of the vehicle trips projected to be generated by the proposed Rising Moon residential subdivision have been made using the nationally published trip-generation rates from *Trip Generation, 11th Edition, 2021* by the Institute of Transportation Engineers (ITE). Corresponding trip-generation rates from ITE Land Use Category “210 – Single-Family (Detached) Housing” have been used to develop the trip-generation estimates for the proposed 41-dwelling-unit residential site.

Table 2 below presents a summary of the estimated external site trip generation. A detailed trip-generation estimate for the site, including ITE rates for the proposed land uses, is presented in Table 3 (attached).

The proposed subdivision is projected to generate about 387 total vehicle trips on the average weekday during a 24-hour period, with approximately half entering and half exiting the site. During the morning peak hour, approximately 8 entering vehicles and 22 exiting vehicles are estimated to be generated. Approximately 25 entering and 15 exiting vehicles are estimated to be generated by the site during the afternoon peak hour.

Table 2: Estimated Site Vehicle-Trip Generation

Analysis Period	Weekday		
	In	Out	Total
Morning Peak Hour	8	22	30
Afternoon Peak Hour	25	15	40
Daily/24-hour	194	194	387

TRIP DISTRIBUTION AND ASSIGNMENT

Trip Directional Distribution

The directional-distribution estimate of site-generated vehicle trips to the study-area roads and intersections is a necessary component in determining the site's traffic impacts. Figure 4 shows the percentages of the site-generated vehicle trips projected to be oriented to and from the site's major approaches. Estimates have been based on the following factors: the area traffic impact studies, the traffic-count data, the proposed land use, the area roadway system serving the site, proposed future roadway connections in the vicinity of the site, and the site's geographic location relative to the Fountain Valley area and the overall greater El Paso County/Colorado Springs area.

Site-Generated Traffic

Site-generated traffic volumes have been estimated at the following intersections:

- Proposed west site access/Peaceful Meadow Street/Harvest Moon Terrace
- Proposed east site access/Peaceful Meadow Street
- Horizonview Drive/Prairie Sage Drive (future)
- Horizonview Drive/Hazy Morning Drive
- Hazy Morning Drive/Harvest Moon Terrace
- Peaceful Meadow Street/Prairie Sage Drive (future)

These site-generated volumes have been calculated by applying directional-distribution percentages estimated by LSC (from Figure 4) to the trip-generation estimates (from Table 3). Figure 5 shows the projected short-term site-generated traffic volumes for the weekday morning

and afternoon peak hours. Projected long-term site-generated traffic volumes for the weekday morning and afternoon peak hours are shown in Figure 6.

Existing + Site-Generated Traffic Volumes

Figure 7 shows the sum of the existing traffic volumes (from Figure 3) and short-term site-generated peak-hour traffic volumes (shown in Figure 5). These volumes represent the projected short-term total traffic following site buildout. These volumes assume conditions prior to the adjacent Meadoworks development.

2044 Background Traffic Volumes

Long-term background traffic volumes at Horizonview intersections are estimates by LSC, based in part on existing count data and projections in the Meadoworks TIS. Estimated site-generated traffic for the 41-dwelling-unit Rising Moon residential development has **not** been included in 2044 background traffic volumes.

The projected traffic volumes for all the study-area intersections incorporate LSC estimates of local area traffic-pattern and volume shifts that will result with new street connections west of this site that are shown on the Meadoworks development plan. Appendix Figure 1 summarizes shifts in existing travel patterns/volumes with these future street connections.

Please refer to Figure 8 for estimated long-term background volumes and assumed laneage at the study-area intersections.

2044 Total Traffic Volumes

Figure 9 shows the sum of 2044 background traffic volumes (from Figure 8) plus long-term site-generated traffic volumes (from Figure 6).

LEVEL OF SERVICE ANALYSIS

Intersection Level of Service

Level of service (LOS) is a quantitative measure of the level of congestion or delay at an intersection and is indicated on a scale from “A” to “F.” LOS A is indicative of little congestion or delay. LOS F indicates a high level of congestion or delay. Table 4 shows the level of service delay ranges for signalized and unsignalized intersections.

Table 4: Intersection Levels of Service Delay Ranges

Level of Service	Signalized Intersections	Unsignalized Intersections
	Average Control Delay (seconds per vehicle)	Average Control Delay (seconds per vehicle) ⁽¹⁾
A	10.0 sec or less	10.0 sec or less
B	10.1-20.0 sec	10.1-15.0 sec
C	20.1-35.0 sec	15.1-25.0 sec
D	35.1-55.0 sec	25.1-35.0 sec
E	55.1-80.0 sec	35.1-50.0 sec
F	80.1 sec or more	50.1 sec or more

(1) For unsignalized intersections, if V/C ratio is greater than 1.0 the level of service is LOS F, regardless of the projected average control delay per vehicle.

LOS values have been included in each figure for each turning movement/approach during the weekday morning and afternoon peak hours for the proposed site-access intersections and off-site intersections in the study area:

- Figure 3: 2024 Existing Traffic, Lane Geometry, Traffic Control, and LOS
- Figure 7: 2024 Existing + Site Traffic, Lane Geometry, Traffic Control, and LOS
- Figure 8: 2044 Background Traffic, Lane Geometry, Traffic Control, and LOS
- Figure 9: 2044 Background + Site Traffic, Lane Geometry, Traffic Control, and LOS

LOS calculations for long-term scenarios were based upon the recommended lane geometries and traffic controls outlined in the figures above.

Proposed West Site Access/Peaceful Meadow Street

All movements at this intersection currently operate at and are projected to remain at LOS A during both peak hours with the addition of site-generated traffic.

Proposed East Site Access/Peaceful Meadow Street

All movements at this intersection are projected to operate at LOS A during both peak hours with the addition of site-generated traffic.

Horizonview Drive/Hazy Morning Drive

All movements at this intersection currently operate at and are projected to remain at LOS B or better during both peak hours with the addition of site-generated traffic.

Horizonview Drive/Prairie Sage Drive (Future)

Based on the site plan shown in the *Meadoworks Filings 1-4* report by SM Rocha from March 2022 ([OAR2187](#)), a new connection to Horizonview Drive (Prairie Sage Drive) is proposed with the Meadoworks development. This is reflected in the long-term analysis in this study. All movements at this intersection are projected to remain at LOS C or better during both peak hours, with or without the addition of Rising Moon site-generated traffic.

Hazy Morning Drive/Harvest Moon Terrace

All movements at this intersection are projected to operate at LOS A during both peak hours with the addition of site-generated traffic.

Peaceful Meadow Street/Prairie Sage Drive

Regarding the intersection LOS for Hazy Morning/Harvest Moon, this future intersection is shown as part of the planned Meadoworks project. The intersection volumes and associated levels of service were not specifically detailed for this intersection in the SM Rocha TIS report. The site plan shown in Figure 2 of that report shows street connections to the north and east (connecting to Peaceful Meadow Street). Since intersection volumes, laneage, and other information were not detailed in that study, we have included estimates of trips to be added as a result of this currently-proposed development's trip generation (shown in Figure 6 of our traffic report). These volumes can be used for reference, if needed, as part of a city application for Filing No. 4 of Meadoworks.

The Rising Moon parcel was previously set aside for a school site, which was presumably anticipated as part of the Meadoworks planning process. The currently-estimated site-generated traffic volumes for Rising Moon would be significantly lower than if this parcel were developed with a school use.

STREET CLASSIFICATIONS

The proposed subdivision streets are proposed as an Urban Local streets.

ROADWAY IMPROVEMENTS

Section B.6.1.D of the *ECM* requires that a recommended improvements summary table be included with traffic studies. Please refer to Table 5, which presents the recommendations for roadway improvements.

MTCP-Identified Roadway Improvements

State whether the MTCP or other approved corridor study calls for the construction of improvements in the immediate area.

No roadway improvement projects within the immediate area/study area have been identified as being needed by the year 2040 per Map 13 and Table 4 of El Paso County's 2016 MTCP. See the attached MTCP maps for reference.

Intersection Improvements – Auxiliary Turn Lanes

Auxiliary-Turn-Lane-Needs Evaluation and Recommendations - El Paso County Intersections

Auxiliary-turn-lane-needs evaluation for El Paso County intersections in the study area is presented below. These findings are based on Urban Local street classifications and auxiliary-turn-lane criteria in the *ECM*.

ECM Requirements for Auxiliary Turn Lanes

Appendix B.8 List ECM criteria for stacking, storage, and taper for every affected auxiliary lane and access and state whether this access can be met. If it cannot be met, state the required modifications so that it can be met.

Left-Turn Deceleration Lanes

According to the El Paso County *Engineering Criteria Manual (ECM)*, exclusive left-turn lanes shall be provided for any access on "Minor Arterials and lower classifications" with a projected peak-hour ingress turning volume of 25 vehicles per hour (vph) or greater.

Right-Turn Deceleration Lane

Per Section 2.3.7.D.1 of the *ECM* for Minor Arterials and lower classifications, exclusive right-turn lanes shall be provided for any access with a projected peak-hour ingress turning volume of 50 vehicles per hour (vph) or greater.

Right-Turn Acceleration Lanes

Right-turn acceleration lanes are generally not required on Minor Arterials and lower classifications roadways, per Section 2.3.7.D.2 of the *ECM*.

Colorado State Highway Access Code (CSHAC) Applicable Criteria

The CDOT Access Code standards are adopted by reference per *ECM* section 1.5. Moreover, left- and right-turn -deceleration and acceleration lane criteria in the *ECM* was derived from the CSHAC. Auxiliary turn-lane requirements in the *CSHAC* are primarily for the purposes of mitigating “speed-change differential” between through traffic on a major road (without a stop condition) and turning traffic from the major road onto a minor road.

The following definitions are presented in CSHAC Section 1.5

(29) "*Deceleration lane*" means a speed-change lane, including tapered areas, for the purpose of enabling a vehicle that is to make an exit to turn from a roadway to slow to the safe speed on the ramp ahead after it has left the mainstream of faster-moving traffic. [§ 42-1-102(23), C.R.S.]

(75) "*Speed change lane*" means a separate lane for the purpose of enabling a vehicle entering or leaving a roadway to increase or decrease its speed to a rate at which it can more safely merge or diverge with through traffic. Acceleration and deceleration lanes are speed change lanes.

Generally, the character and function of Urban Local streets differ significantly from the type of roadways referenced in the above definitions. Urban local streets do not have “mainstream [or] high-speed moving traffic,” and so there is no speed-differential to mitigate. This is the case for the County Urban Local street intersections within study area.

Moreover, notwithstanding the above, even if the County turn-lane thresholds were followed strictly for Urban Local street intersections within study area, the following criteria in the CSHAC applies to intersection Nos. 2, 3 and 4.

3.5 (5) The auxiliary lanes required in the category design standards may be waived when the 20th year predicted roadway volumes conflicting with the turning vehicle are below the following minimum volume thresholds. The right turn deceleration lane may be dropped if the volume in the travel lane is predicted to be below 150 DHV. The left turn deceleration lane may be dropped if the opposing traffic is predicted to be below 100 DHV. The right turn acceleration lane may be dropped if the adjacent traveled lane is predicted to be below 120 DHV. The left turn acceleration lane may be dropped if the volume in the inside lane in the direction of travel is predicted to be below 120 DHV.

LSC has reviewed the potential need for right- and left-turn “bays,” or “stacking lanes” (different from “deceleration lanes”) on stop-sign-controlled approaches to the study-area intersections for other reasons – such as purposes of maintaining an acceptable LOS or mitigate any potential queuing and blocking issues. The traffic analysis findings do not indicate any such issues. All individual turning movements at the study-area intersections are projected to operate at LOS C or better with existing laneage. Projected queues are not anticipated to result in queuing or blocking issues on any approach.

Findings

Peaceful Meadow Street/Harvest Moon Terrace/Proposed West Site Access

No auxiliary turn lanes would be required on any approach at the proposed Peaceful Meadow Street/proposed west site-access intersection.

Peaceful Meadow Street/Proposed East Site Access

No auxiliary turn lanes would be required on any approach at the proposed Peaceful Meadow Street/proposed east site-access intersection.

Auxiliary Turn Lane Needs Evaluation and Recommendations – City of Colorado Springs Intersections

City of Colorado Springs Criteria for Collector Streets

Per Section 8.1 of the City of Colorado Springs' *Traffic Criteria Manual*, "Turn-Lane requirements on lower classification roads are determined on a case-by-case basis depending on recommendations from a traffic impact study and approved by City Engineering."

Horizonview Drive/Hazy Morning Drive

Right- and Left-Turn Deceleration Lanes

Per the City of Colorado Springs requirement of the Meadowworks development above, no auxiliary turn lanes on Horizonview would be necessary given the City-directed striping configuration for Horizonview Drive (through this study area) for two 12-foot-wide through lanes with 8-foot shoulders.

Horizonview Drive/Prairie Sage Drive (future, by others)

Left- and Right-Turn Deceleration Lanes

Per the City of Colorado Springs requirement of the Meadowworks development above, no auxiliary turn lanes on Horizonview would be necessary given the City-directed striping configuration for Horizonview Drive (through this study area) for two 12-foot-wide through lanes with 8-foot shoulders.

Roadway Segment Recommendations

Construct the subdivision streets to Urban Local standards.

COUNTY ROAD IMPROVEMENT FEE PROGRAM

Transportation Impact Fees

Per *ECM* Appendix B: *State what the current applicable Transportation Impact Fees are and what option the developer will be selecting for payment.*

This project will be required to participate in the El Paso County Road Improvement Fee Program. The applicant will select the “opt-out” option (no PID) and would pay the “Full Fee” amount at building permit. The current (2024) fee amount associated with this option is \$3,830 per dwelling unit (subject to change). Based on 41 lots, the total building permit fee for this plat would be \$157,030.

Reimbursable Improvements

No potentially-reimbursable roadway improvements would apply as there are no *MTCP*-identified roadway improvement projects within the immediate area/study area.

MULTI-MODAL TRANSPORTATION AND TDM OPPORTUNITIES

No multi-modal transportation improvement projects have been identified as being needed by the year 2040 per Map 15 and Table 5 of El Paso County’s 2016 *MTCP*. No public schools are located within a 2-mile radius of the site. The Improvements Table (Table 5) presents required sidewalk improvements by others and LSC-recommended sidewalk improvements for this development.

Urban Local streets are designed to accommodate bicycles. Horizonview will be able to accommodate bicycles with the existing street width and with the restriping for paved shoulders as required of the Meadowworks development by the City of Colorado Springs.

DEVIATIONS

No deviations to *ECM* design criteria are proposed with this subdivision.

FINDINGS AND CONCLUSIONS

- The site is projected to generate about 387 new driveway vehicle-trips on the average weekday.
- During the weekday morning peak hour of adjacent street traffic, 8 vehicles would enter the site while 22 vehicles would exit.

- During the weekday afternoon peak hour of adjacent street traffic, 25 vehicles would enter the site while 15 vehicles would exit.
- All individual approaches and turn lanes at all study-area intersections would operate at LOS C or better during both short-term and long-term peak hours, with or without the addition of site-generated traffic.
- Please refer to the “Auxiliary Turn-Lane Analysis” section for evaluation details.
- Please refer to the attached Roadway Improvements Table.
- The subdivision roads are proposed as Urban Local.
- No deviations are proposed with this submittal.
- The El Paso County Roadway Improvement Fee Program fee amounts are detailed in that section of this report.

* * * * *

Please contact me if you have any questions regarding this report.

Respectfully Submitted,

LSC TRANSPORTATION CONSULTANTS, INC.

By: Jeffrey C. Hodsdon, P.E.
Principal

JCH/JAB:jas

Enclosures: Table 3 and Table 5
Figure 1 - Figure 9
Appendix Figure 1
Traffic Count Reports
Synchro LOS Reports

Table 3 and Table 5



Table 3: Detailed Trip Generation Estimate

ITE	Value	Units ¹	Trip Generation Rates ²						Total Driveway Trips Generated					
			Average	A.M.		P.M.		Average	A.M.		P.M.			
Code	Description		Weekday	In	Out	In	Out	Weekday	In	Out	In	Out		
210	Single-Family (Detached) Housing	41	DU	9.43	0.18	0.53	0.59	0.35	387	8	22	25	15	

¹ DU = dwelling units
² Source: *Trip Generation, 11th Edition (2021)* by the Institute of Transportation Engineers (ITE)

Note: Based on ITE average rates
Updated by LSC: April 1, 2024

Table 5. Recommended Improvements

Item #	Improvement	Timing	Jurisdiction	Responsibility
Roadway Segment Improvements				
1	Construct Subdivision Streets to county Urban Local standards	With this development	EI Paso County	Applicant/Developer
2	Restripe Horizonview for two through lanes plus paved shoulders	w/Meadowworks development	City of Colorado Springs	Meadowworks Developer
Peaceful Meadow Street/east and west site access intersection Improvements				
3	Install north-facing Stop signs on the southbound approaches.	With the development	EI Paso County	Applicant/Developer
Multi-Modal Improvements				
4	Construct Sidewalks along Horizonview	w/Meadowworks development	City of Colorado Springs	Meadowworks Developer
5	Construct Sidewalks along the Peaceful Meadow Street frontage	With the development	EI Paso County	Applicant/Developer

Source: LSC Transportation Consultants, Inc. (9-6-24)

Figures 1-9





Not to scale





1" = 150'
scale

Shining Star Dr

Peaceful Meadow St

Harvest Moon
Terrace

220'


260'



Figure 2

Site Plan

Rising Moon (LSC# S244050)



Not to scale




Figure 4
Directional Distribution
Rising Moon (LSC# S244050)








Figure 5

Short-Term Site-Generated Traffic

Rising Moon (LSC# S244050)

↑ N
NTS











Figure 6
Long-Term
Site-Generated Traffic

Rising Moon (LSC# S244050)






Figure 8

2044 Background Traffic, Lane Geometry, Traffic Control, and LOS

Rising Moon (LSC# S244050)





Figure 9
2044 Total Traffic, Lane Geometry, Traffic Control, and LOS

Rising Moon (LSC# S244050)

Appendix Figure 1





Appendix Figure 1

LSC Estimates of Shifted Existing Traffic (with Planned Future New Street Connection to Horizonview Dr)

Rising Moon (LSC# S244050)

Traffic Counts



Traffic Counts



LSC Transportation Consultants, Inc.

2504 E. Pikes Peak Ave, Suite 304
 Colorado Springs, CO 80909
 719-633-2868

File Name : Horizon View Dr - Hazy Morning Dr AM
 Site Code : S244050
 Start Date : 2/15/2024
 Page No : 1

Groups Printed- Unshifted


Start Time	Horizon View Dr Southbound					Hazy Morning Dr Westbound					Horizon View Dr Northbound					Eastbound					Int. Total
	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	
06:30	0	1	0	0	1	1	0	5	0	6	0	2	0	0	2	0	0	0	0	0	9
06:35	0	1	0	0	1	1	0	5	0	6	0	2	0	0	2	0	0	0	0	0	9
06:40	0	2	0	0	2	2	0	5	0	7	1	2	0	0	3	0	0	0	0	0	12
06:45	0	3	0	0	3	0	0	4	0	4	0	9	0	0	9	0	0	0	0	0	16
06:50	0	2	0	0	2	2	0	2	0	4	0	2	0	0	2	0	0	0	0	0	8
06:55	0	5	0	0	5	2	0	4	0	6	0	6	0	0	6	0	0	0	0	0	17
Total	0	14	0	0	14	8	0	25	0	33	1	23	0	0	24	0	0	0	0	0	71
07:00	0	4	0	0	4	3	0	4	0	7	3	4	0	0	7	0	0	0	0	0	18
07:05	0	2	0	0	2	3	0	5	0	8	1	4	0	0	5	0	0	0	0	0	15
07:10	0	2	0	0	2	2	0	10	0	12	0	4	0	0	4	0	0	0	0	0	18
07:15	0	6	0	0	6	4	0	7	0	11	3	3	0	0	6	0	0	0	0	0	23
07:20	0	2	0	0	2	3	0	5	0	8	1	8	0	0	9	0	0	0	0	0	19
07:25	0	3	0	0	3	1	0	9	0	10	4	6	0	0	10	0	0	0	0	0	23
07:30	0	9	2	0	11	1	0	6	0	7	2	1	0	0	3	0	0	0	0	0	21
07:35	0	1	2	0	3	3	0	5	0	8	2	6	0	0	8	0	0	0	0	0	19
07:40	0	4	0	0	4	2	0	6	0	8	1	5	0	0	6	0	0	0	0	0	18
07:45	0	4	0	0	4	3	0	10	0	13	2	6	0	0	8	0	0	0	0	0	25
07:50	0	4	0	0	4	0	0	4	0	4	2	4	0	0	6	0	0	0	0	0	14
07:55	0	5	0	0	5	3	0	4	0	7	0	4	0	0	4	0	0	0	0	0	16
Total	0	46	4	0	50	28	0	75	0	103	21	55	0	0	76	0	0	0	0	0	229
08:00	0	5	0	0	5	1	0	10	0	11	2	3	0	0	5	0	0	0	0	0	21
08:05	0	9	0	0	9	0	0	4	0	4	1	1	0	0	2	0	0	0	0	0	15
08:10	0	6	0	0	6	0	0	3	0	3	2	2	0	0	4	0	0	0	0	0	13
08:15	0	5	0	0	5	0	0	5	0	5	2	2	0	0	4	0	0	0	0	0	14
08:20	0	4	0	0	4	4	0	2	0	6	3	1	0	0	4	0	0	0	0	0	14
08:25	0	4	0	0	4	1	0	7	0	8	1	4	0	0	5	0	0	0	0	0	17
Grand Total	0	93	4	0	97	42	0	131	0	173	33	91	0	0	124	0	0	0	0	0	394
Apprch %	0	95.9	4.1	0		24.3	0	75.7	0		26.6	73.4	0	0		0	0	0	0	0	
Total %	0	23.6	1	0	24.6	10.7	0	33.2	0	43.9	8.4	23.1	0	0	31.5	0	0	0	0	0	

LSC Transportation Consultants, Inc.

2504 E. Pikes Peak Ave, Suite 304
 Colorado Springs, CO 80909
 719-633-2868

File Name : Horizon View Dr - Hazy Morning Dr AM
 Site Code : S244050
 Start Date : 2/15/2024
 Page No : 2

	Horizon View Dr Southbound					Hazy Morning Dr Westbound					Horizon View Dr Northbound					Eastbound					
	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
Peak Hour Analysis From 06:30 to 08:25 - Peak 1 of 1																					
Peak Hour for Entire Intersection Begins at 07:05																					
07:05	0	2	0	0	2	3	0	5	0	8	1	4	0	0	5	0	0	0	0	0	15
07:10	0	2	0	0	2	2	0	10	0	12	0	4	0	0	4	0	0	0	0	0	18
07:15	0	6	0	0	6	4	0	7	0	11	3	3	0	0	6	0	0	0	0	0	23
07:20	0	2	0	0	2	3	0	5	0	8	1	8	0	0	9	0	0	0	0	0	19
07:25	0	3	0	0	3	1	0	9	0	10	4	6	0	0	10	0	0	0	0	0	23
07:30	0	9	2	0	11	1	0	6	0	7	2	1	0	0	3	0	0	0	0	0	21
07:35	0	1	2	0	3	3	0	5	0	8	2	6	0	0	8	0	0	0	0	0	19
07:40	0	4	0	0	4	2	0	6	0	8	1	5	0	0	6	0	0	0	0	0	18
07:45	0	4	0	0	4	3	0	10	0	13	2	6	0	0	8	0	0	0	0	0	25
07:50	0	4	0	0	4	0	0	4	0	4	2	4	0	0	6	0	0	0	0	0	14
07:55	0	5	0	0	5	3	0	4	0	7	0	4	0	0	4	0	0	0	0	0	16
08:00	0	5	0	0	5	1	0	10	0	11	2	3	0	0	5	0	0	0	0	0	21
Total Volume	0	47	4	0	51	26	0	81	0	107	20	54	0	0	74	0	0	0	0	0	232
% App. Total	0	92.2	7.8	0		24.3	0	75.7	0		27	73	0	0		0	0	0	0	0	
PHF	.000	.435	.167	.000	.386	.542	.000	.675	.000	.686	.417	.563	.000	.000	.617	.000	.000	.000	.000	.000	.773




LSC Transportation Consultants, Inc.

2504 E. Pikes Peak Ave, Suite 304
 Colorado Springs, CO 80909
 719-633-2868

File Name : Horizon View Dr - Hazy Morning Dr AM
 Site Code : S244050
 Start Date : 2/15/2024
 Page No : 3

	Horizon View Dr Southbound					Hazy Morning Dr Westbound					Horizon View Dr Northbound					Eastbound					
Start Time	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
Peak Hour Analysis From 06:30 to 08:25 - Peak 1 of 1																					
Peak Hour for Each Approach Begins at:																					
+0 mins.	0	9	2	0	11	3	0	5	0	8	0	6	0	0	6	0	0	0	0	0	
+5 mins.	0	1	2	0	3	2	0	10	0	12	3	4	0	0	7	0	0	0	0	0	
+10 mins.	0	4	0	0	4	4	0	7	0	11	1	4	0	0	5	0	0	0	0	0	
+15 mins.	0	4	0	0	4	3	0	5	0	8	0	4	0	0	4	0	0	0	0	0	
+20 mins.	0	4	0	0	4	1	0	9	0	10	3	3	0	0	6	0	0	0	0	0	
+25 mins.	0	5	0	0	5	1	0	6	0	7	1	8	0	0	9	0	0	0	0	0	
+30 mins.	0	5	0	0	5	3	0	5	0	8	4	6	0	0	10	0	0	0	0	0	
+35 mins.	0	9	0	0	9	2	0	6	0	8	2	1	0	0	3	0	0	0	0	0	
+40 mins.	0	6	0	0	6	3	0	10	0	13	2	6	0	0	8	0	0	0	0	0	
+45 mins.	0	5	0	0	5	0	0	4	0	4	1	5	0	0	6	0	0	0	0	0	
+50 mins.	0	4	0	0	4	3	0	4	0	7	2	6	0	0	8	0	0	0	0	0	
+55 mins.	0	4	0	0	4	1	0	10	0	11	2	4	0	0	6	0	0	0	0	0	
Total Volume	0	60	4	0	64	26	0	81	0	107	21	57	0	0	78	0	0	0	0	0	
% App. Total	0	93.8	6.2	0		24.3	0	75.7	0		26.9	73.1	0	0		0	0	0	0	0	
PHF	.000	.556	.167	.000	.485	.542	.000	.675	.000	.686	.438	.594	.000	.000	.650	.000	.000	.000	.000	.000	



LSC Transportation Consultants, Inc.

2504 E. Pikes Peak Ave, Suite 304
 Colorado Springs, CO 80909
 719-633-2868

File Name : Horizon View Dr - Hazy Morning Dr PM B
 Site Code : S244050
 Start Date : 2/13/2024
 Page No : 1

Groups Printed- Unshifted


Start Time	Horizon View Dr Southbound					Hazy Morning Dr Westbound					Horizon View Dr Northbound					Eastbound					Int. Total
	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	
16:00	0	5	3	0	8	2	0	1	0	3	4	7	0	0	11	0	0	0	0	0	22
16:05	0	1	0	0	1	3	0	3	0	6	3	1	0	0	4	0	0	0	0	0	11
16:10	0	6	1	0	7	1	0	0	0	1	8	6	0	0	14	0	0	0	0	0	22
16:15	0	1	2	0	3	0	0	1	0	1	7	2	0	0	9	0	0	0	0	0	13
16:20	0	4	0	0	4	0	0	4	0	4	3	6	0	0	9	0	0	0	0	0	17
16:25	0	4	1	0	5	0	0	4	0	4	5	5	0	0	10	0	0	0	0	0	19
16:30	0	3	3	0	6	0	0	5	0	5	7	5	0	0	12	0	0	0	0	0	23
16:35	0	2	1	0	3	0	0	2	0	2	6	6	0	0	12	0	0	0	0	0	17
16:40	0	2	3	0	5	0	0	7	0	7	7	5	0	0	12	0	0	0	0	0	24
16:45	0	3	1	0	4	2	0	4	0	6	4	4	0	0	8	0	0	0	0	0	18
16:50	0	7	2	0	9	2	0	1	0	3	4	10	0	0	14	0	0	0	0	0	26
16:55	0	6	3	0	9	1	0	2	0	3	7	7	0	0	14	0	0	0	0	0	26
Total	0	44	20	0	64	11	0	34	0	45	65	64	0	0	129	0	0	0	0	0	238
17:00	0	7	0	0	7	0	0	4	0	4	10	2	0	0	12	0	0	0	0	0	23
17:05	0	6	2	0	8	0	0	0	0	0	9	2	0	0	11	0	0	0	0	0	19
17:10	0	5	2	0	7	0	0	1	0	1	6	0	0	0	6	0	0	0	0	0	14
17:15	0	1	2	0	3	3	0	4	0	7	4	4	0	0	8	0	0	0	0	0	18
17:20	0	8	2	0	10	2	0	2	0	4	7	3	0	0	10	0	0	0	0	0	24
17:25	0	7	1	0	8	2	0	5	0	7	3	2	0	0	5	0	0	0	0	0	20
17:30	0	6	0	0	6	0	0	2	0	2	6	3	0	0	9	0	0	0	0	0	17
17:35	0	7	1	0	8	1	0	0	0	1	5	4	0	0	9	0	0	0	0	0	18
17:40	0	5	3	0	8	1	0	3	0	4	5	5	0	0	10	0	0	0	0	0	22
17:45	0	7	1	0	8	0	0	2	0	2	4	2	0	0	6	0	0	0	0	0	16
17:50	0	8	1	0	9	0	0	2	0	2	7	5	0	0	12	0	0	0	0	0	23
17:55	0	3	3	0	6	2	0	3	0	5	7	1	0	0	8	0	0	0	0	0	19
Total	0	70	18	0	88	11	0	28	0	39	73	33	0	0	106	0	0	0	0	0	233
Grand Total	0	114	38	0	152	22	0	62	0	84	138	97	0	0	235	0	0	0	0	0	471
Apprch %	0	75	25	0		26.2	0	73.8	0		58.7	41.3	0	0		0	0	0	0	0	
Total %	0	24.2	8.1	0	32.3	4.7	0	13.2	0	17.8	29.3	20.6	0	0	49.9	0	0	0	0	0	

LSC Transportation Consultants, Inc.

2504 E. Pikes Peak Ave, Suite 304
 Colorado Springs, CO 80909
 719-633-2868

File Name : Horizon View Dr - Hazy Morning Dr PM B
 Site Code : S244050
 Start Date : 2/13/2024
 Page No : 2

	Horizon View Dr Southbound					Hazy Morning Dr Westbound					Horizon View Dr Northbound					Eastbound					
	Start Time	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total
Peak Hour Analysis From 16:00 to 17:55 - Peak 1 of 1																					
Peak Hour for Entire Intersection Begins at 16:30																					
16:30	0	3	3	0	6	0	0	5	0	5	7	5	0	0	12	0	0	0	0	0	23
16:35	0	2	1	0	3	0	0	2	0	2	6	6	0	0	12	0	0	0	0	0	17
16:40	0	2	3	0	5	0	0	7	0	7	7	5	0	0	12	0	0	0	0	0	24
16:45	0	3	1	0	4	2	0	4	0	6	4	4	0	0	8	0	0	0	0	0	18
16:50	0	7	2	0	9	2	0	1	0	3	4	10	0	0	14	0	0	0	0	0	26
16:55	0	6	3	0	9	1	0	2	0	3	7	7	0	0	14	0	0	0	0	0	26
17:00	0	7	0	0	7	0	0	4	0	4	10	2	0	0	12	0	0	0	0	0	23
17:05	0	6	2	0	8	0	0	0	0	0	9	2	0	0	11	0	0	0	0	0	19
17:10	0	5	2	0	7	0	0	1	0	1	6	0	0	0	6	0	0	0	0	0	14
17:15	0	1	2	0	3	3	0	4	0	7	4	4	0	0	8	0	0	0	0	0	18
17:20	0	8	2	0	10	2	0	2	0	4	7	3	0	0	10	0	0	0	0	0	24
17:25	0	7	1	0	8	2	0	5	0	7	3	2	0	0	5	0	0	0	0	0	20
Total Volume	0	57	22	0	79	12	0	37	0	49	74	50	0	0	124	0	0	0	0	0	252
% App. Total	0	72.2	27.8	0		24.5	0	75.5	0		59.7	40.3	0	0		0	0	0	0	0	
PHF	.000	.594	.611	.000	.658	.333	.000	.440	.000	.583	.617	.417	.000	.000	.738	.000	.000	.000	.000	.000	.808




LSC Transportation Consultants, Inc.


2504 E. Pikes Peak Ave, Suite 304
 Colorado Springs, CO 80909
 719-633-2868

File Name : Horizon View Dr - Hazy Morning Dr PM B
 Site Code : S244050
 Start Date : 2/13/2024
 Page No : 3

Start Time	Horizon View Dr Southbound					Hazy Morning Dr Westbound					Horizon View Dr Northbound					Eastbound				
	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total
Peak Hour Analysis From 16:00 to 17:55 - Peak 1 of 1																				
Peak Hour for Each Approach Begins at:																				
16:50	0	7	2	0	9	0	0	5	0	5	8	6	0	0	14	0	0	0	0	0
+0 mins.	0	6	3	0	9	0	0	2	0	2	7	2	0	0	9	0	0	0	0	0
+5 mins.	0	7	0	0	7	0	0	7	0	7	3	6	0	0	9	0	0	0	0	0
+10 mins.	0	6	2	0	8	2	0	4	0	6	5	5	0	0	10	0	0	0	0	0
+15 mins.	0	5	2	0	7	2	0	1	0	3	7	5	0	0	12	0	0	0	0	0
+20 mins.	0	1	2	0	3	1	0	2	0	3	6	6	0	0	12	0	0	0	0	0
+25 mins.	0	8	2	0	10	0	0	4	0	4	7	5	0	0	12	0	0	0	0	0
+30 mins.	0	7	1	0	8	0	0	0	0	0	4	4	0	0	8	0	0	0	0	0
+35 mins.	0	6	0	0	6	0	0	1	0	1	4	10	0	0	14	0	0	0	0	0
+40 mins.	0	7	1	0	8	3	0	4	0	7	7	0	0	14	0	0	0	0	0	0
+45 mins.	0	5	3	0	8	2	0	2	0	4	10	2	0	0	12	0	0	0	0	0
+50 mins.	0	7	1	0	8	2	0	5	0	7	9	2	0	0	11	0	0	0	0	0
+55 mins.	0	72	19	0	91	12	0	37	0	49	77	60	0	0	137	0	0	0	0	0
Total Volume	0	72	19	0	91	12	0	37	0	49	77	60	0	0	137	0	0	0	0	0
% App. Total	0	79.1	20.9	0		24.5	0	75.5	0		56.2	43.8	0	0		0	0	0	0	0
PHF	.000	.750	.528	.000	.758	.333	.000	.440	.000	.583	.642	.500	.000	.000	.815	.000	.000	.000	.000	.000



Peak Hour Data



LSC Transportation Consultants, Inc.

2504 E. Pikes Peak Ave, Suite 304
 Colorado Springs, CO 80909
 719-633-2868

File Name : Harvest Moon Terrace - Peaceful Meadow St AM V
 Site Code : S244050
 Start Date : 2/15/2024

Page No : 1

Groups Printed- Unshifted


Start Time	Southbound					Peaceful Meadow St Westbound					Harvest Moon Terrace Northbound					Peaceful Meadow St Eastbound					Int. Total
	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	
06:30	0	0	0	0	0	0	0	1	0	1	0	0	0	0	0	0	0	0	0	0	1
06:35	0	0	0	0	0	0	0	1	0	1	0	0	0	0	0	0	0	0	0	0	1
06:40	0	0	0	0	0	0	0	2	0	2	1	0	0	0	1	0	0	0	0	0	3
06:45	0	0	0	0	0	0	0	3	0	3	0	0	0	0	0	0	0	0	0	0	3
*** BREAK ***																					
06:55	0	0	0	0	0	0	0	2	0	2	0	0	0	0	0	0	0	0	0	0	2
Total	0	0	0	0	0	0	0	9	0	9	1	0	0	0	1	0	0	0	0	0	10
07:00	0	0	0	0	0	0	0	3	0	3	0	0	0	0	0	0	0	0	0	0	3
07:05	0	0	0	0	0	0	0	3	0	3	0	0	0	0	0	0	0	0	0	0	3
07:10	0	0	0	0	0	0	0	3	0	3	0	0	0	0	0	0	0	0	0	0	3
07:15	0	0	0	0	0	0	0	4	0	4	1	0	0	0	1	0	0	0	0	0	5
07:20	0	0	0	0	0	0	0	2	0	2	1	0	0	0	1	0	0	0	0	0	3
07:25	0	0	0	0	0	0	0	1	0	1	1	0	0	0	1	0	0	0	0	0	2
07:30	0	0	0	0	0	0	0	3	0	3	1	0	0	0	1	0	0	0	0	0	4
07:35	0	0	0	0	0	0	0	3	0	3	2	0	0	0	2	0	0	0	0	0	5
07:40	0	0	0	0	0	0	0	2	0	2	1	0	0	0	1	0	0	0	0	0	3
07:45	0	0	0	0	0	0	0	4	0	4	1	0	0	0	1	0	0	0	0	0	5
07:50	0	0	0	0	0	0	0	1	0	1	0	0	0	0	0	0	0	0	0	0	1
07:55	0	0	0	0	0	0	0	2	0	2	1	0	0	0	1	0	0	0	0	0	3
Total	0	0	0	0	0	0	0	31	0	31	9	0	0	0	9	0	0	0	0	0	40
08:00	0	0	0	0	0	0	0	5	0	5	0	0	0	0	0	0	0	0	0	0	5
08:05	0	0	0	0	0	0	0	2	0	2	1	0	0	0	1	0	0	0	0	0	3
08:10	0	0	0	0	0	0	0	2	0	2	0	0	0	0	0	0	0	0	0	0	2
08:15	0	0	0	0	0	0	0	2	0	2	1	0	0	0	1	0	0	0	0	0	3
08:20	0	0	0	0	0	0	0	2	0	2	1	0	0	0	1	0	0	0	0	0	3
08:25	0	0	0	0	0	0	0	3	0	3	0	0	0	0	0	0	0	0	0	0	3
Grand Total	0	0	0	0	0	0	0	56	0	56	13	0	0	0	13	0	0	0	0	0	69
Apprch %	0	0	0	0	0	0	0	100	0	100	0	0	0	0	0	0	0	0	0	0	
Total %	0	0	0	0	0	0	0	81.2	0	81.2	18.8	0	0	0	18.8	0	0	0	0	0	

LSC Transportation Consultants, Inc.

2504 E. Pikes Peak Ave, Suite 304
 Colorado Springs, CO 80909
 719-633-2868

File Name : Harvest Moon Terrace - Peaceful Meadow St AM V
 Site Code : S244050
 Start Date : 2/15/2024
 Page No : 2

	Southbound					Peaceful Meadow St Westbound					Harvest Moon Terrace Northbound					Peaceful Meadow St Eastbound					
	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
Peak Hour Analysis From 06:30 to 08:25 - Peak 1 of 1																					
Peak Hour for Entire Intersection Begins at 07:05																					
07:05	0	0	0	0	0	0	0	3	0	3	0	0	0	0	0	0	0	0	0	0	3
07:10	0	0	0	0	0	0	0	3	0	3	0	0	0	0	0	0	0	0	0	0	3
07:15	0	0	0	0	0	0	0	4	0	4	1	0	0	0	1	0	0	0	0	0	5
07:20	0	0	0	0	0	0	0	2	0	2	1	0	0	0	1	0	0	0	0	0	3
07:25	0	0	0	0	0	0	0	1	0	1	1	0	0	0	1	0	0	0	0	0	2
07:30	0	0	0	0	0	0	0	3	0	3	1	0	0	0	1	0	0	0	0	0	4
07:35	0	0	0	0	0	0	0	3	0	3	2	0	0	0	2	0	0	0	0	0	5
07:40	0	0	0	0	0	0	0	2	0	2	1	0	0	0	1	0	0	0	0	0	3
07:45	0	0	0	0	0	0	0	4	0	4	1	0	0	0	1	0	0	0	0	0	5
07:50	0	0	0	0	0	0	0	1	0	1	0	0	0	0	0	0	0	0	0	0	1
07:55	0	0	0	0	0	0	0	2	0	2	1	0	0	0	1	0	0	0	0	0	3
08:00	0	0	0	0	0	0	0	5	0	5	0	0	0	0	0	0	0	0	0	0	5
Total Volume	0	0	0	0	0	0	0	33	0	33	9	0	0	0	9	0	0	0	0	0	42
% App. Total	0	0	0	0	0	0	0	100	0	100	100	0	0	0	0	0	0	0	0	0	0
PHF	.000	.000	.000	.000	.000	.000	.000	.550	.000	.550	.375	.000	.000	.000	.375	.000	.000	.000	.000	.000	.700




LSC Transportation Consultants, Inc.

2504 E. Pikes Peak Ave, Suite 304
 Colorado Springs, CO 80909
 719-633-2868

File Name : Harvest Moon Terrace - Peaceful Meadow St AM V
 Site Code : S244050
 Start Date : 2/15/2024
 Page No : 3

	Southbound					Peaceful Meadow St Westbound					Harvest Moon Terrace Northbound					Peaceful Meadow St Eastbound						
	Start Time	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
Peak Hour Analysis From 06:30 to 08:25 - Peak 1 of 1																						
Peak Hour for Each Approach Begins at:																						
+0 mins.	06:30	0	0	0	0	0	0	0	3	0	3	0	0	0	0	0	0	0	0	0	0	0
+5 mins.		0	0	0	0	0	0	0	3	0	3	1	0	0	0	1	0	0	0	0	0	0
+10 mins.		0	0	0	0	0	0	0	4	0	4	1	0	0	0	1	0	0	0	0	0	0
+15 mins.		0	0	0	0	0	0	0	2	0	2	1	0	0	0	1	0	0	0	0	0	0
+20 mins.		0	0	0	0	0	0	0	1	0	1	1	0	0	0	1	0	0	0	0	0	0
+25 mins.		0	0	0	0	0	0	0	3	0	3	2	0	0	0	2	0	0	0	0	0	0
+30 mins.		0	0	0	0	0	0	0	3	0	3	1	0	0	0	1	0	0	0	0	0	0
+35 mins.		0	0	0	0	0	0	0	2	0	2	1	0	0	0	1	0	0	0	0	0	0
+40 mins.		0	0	0	0	0	0	0	4	0	4	0	0	0	0	0	0	0	0	0	0	0
+45 mins.		0	0	0	0	0	0	0	1	0	1	1	0	0	0	1	0	0	0	0	0	0
+50 mins.		0	0	0	0	0	0	0	2	0	2	0	0	0	0	0	0	0	0	0	0	0
+55 mins.		0	0	0	0	0	0	0	5	0	5	1	0	0	0	1	0	0	0	0	0	0
Total Volume		0	0	0	0	0	0	0	33	0	33	10	0	0	0	10	0	0	0	0	0	0
% App. Total		0	0	0	0	0	0	0	100	0	100	100	0	0	0	0	0	0	0	0	0	0
PHF	.000	.000	.000	.000	.000	.000	.550	.000	.550	.417	.000	.000	.000	.000	.417	.000	.000	.000	.000	.000	.000	



LSC Transportation Consultants, Inc.

2504 E. Pikes Peak Ave, Suite 304
 Colorado Springs, CO 80909
 719-633-2868

File Name : Harvest Moon Terrace - Peaceful Meadow St PM V

Site Code : S244050

Start Date : 2/13/2024

Page No : 1

Groups Printed- Unshifted


	Southbound					Peaceful Meadow St Westbound					Harvest Moon Terrace Northbound					Peaceful Meadow St Eastbound					Int. Total		
	Start Time	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total		
16:00	0	0	0	0	0	0	0	0	1	0	1	3	0	0	0	0	3	0	0	0	0	0	4
16:05	0	0	0	0	0	0	0	0	2	0	2	0	0	0	0	0	0	0	0	0	0	0	2
16:10	0	0	0	0	0	0	0	0	0	0	0	6	0	0	0	0	6	0	0	0	0	0	6
16:15	0	0	0	0	0	0	0	0	0	0	0	5	0	0	0	0	5	0	0	0	0	0	5
16:20	0	0	0	0	0	0	0	0	4	0	4	1	0	0	0	0	1	0	0	0	0	0	5
16:25	0	0	0	0	0	0	0	0	1	0	1	3	0	0	0	0	3	0	0	0	0	0	4
16:30	0	0	0	0	0	0	0	0	1	0	1	4	0	0	0	0	4	0	0	0	0	0	5
16:35	0	0	0	0	0	0	0	0	0	0	0	4	0	0	0	0	4	0	0	0	0	0	4
16:40	0	0	0	0	0	0	0	0	4	0	4	5	0	0	0	0	5	0	0	0	0	0	9
16:45	0	0	0	0	0	0	0	0	4	0	4	2	0	0	0	0	2	0	0	0	0	0	6
16:50	0	0	0	0	0	0	0	0	1	0	1	2	0	0	0	0	2	0	0	0	0	0	3
16:55	0	0	0	0	0	0	0	0	1	0	1	5	0	0	0	0	5	0	0	0	0	0	6
Total		0	0	0	0	0	0	0	19	0	19	40	0	0	0	0	40	0	0	0	0	0	59
17:00	0	0	0	0	0	0	0	0	3	0	3	6	0	0	0	0	6	0	0	0	0	0	9
17:05	0	0	0	0	0	0	0	0	0	0	0	5	0	0	0	0	5	0	0	0	0	0	5
17:10	0	0	0	0	0	0	0	0	1	0	1	0	0	0	0	0	0	0	0	0	0	0	1
17:15	0	0	0	0	0	0	0	0	1	0	1	3	0	0	0	0	3	0	0	0	0	0	4
17:20	0	0	0	0	0	0	0	0	3	0	3	3	0	0	0	0	3	0	0	0	0	0	6
17:25	0	0	0	0	0	0	0	0	3	0	3	1	0	0	0	0	1	0	0	0	0	0	4
17:30	0	0	0	0	0	0	0	0	1	0	1	2	0	0	0	0	2	0	0	0	0	0	3
17:35	0	0	0	0	0	0	0	0	1	0	1	3	0	0	0	0	3	0	0	0	0	0	4
17:40	0	0	0	0	0	0	0	0	2	0	2	2	0	0	0	0	2	0	0	0	0	0	4
17:45	0	0	0	0	0	0	0	0	1	0	1	1	0	0	0	0	1	0	0	0	0	0	2
17:50	0	0	0	0	0	0	0	0	1	0	1	2	0	0	0	0	2	0	0	0	0	0	3
17:55	0	0	0	0	0	0	0	0	2	0	2	1	0	0	0	0	1	0	0	0	0	0	3
Total		0	0	0	0	0	0	0	19	0	19	29	0	0	0	0	29	0	0	0	0	0	48
Grand Total		0	0	0	0	0	0	0	38	0	38	69	0	0	0	0	69	0	0	0	0	0	107
Apprch %		0	0	0	0	0	0	0	100	0	100	0	0	0	0	0	0	0	0	0	0	0	0
Total %		0	0	0	0	0	0	0	35.5	0	35.5	64.5	0	0	0	0	64.5	0	0	0	0	0	0

LSC Transportation Consultants, Inc.

2504 E. Pikes Peak Ave, Suite 304
Colorado Springs, CO 80909
719-633-2868

File Name : Harvest Moon Terrace - Peaceful Meadow St PM V
Site Code : S244050
Start Date : 2/13/2024
Page No : 2

	Southbound					Peaceful Meadow St Westbound					Harvest Moon Terrace Northbound					Peaceful Meadow St Eastbound					
Start Time	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
Peak Hour Analysis From 16:00 to 17:55 - Peak 1 of 1																					
Peak Hour for Entire Intersection Begins at 16:10																					
16:10	0	0	0	0	0	0	0	0	0	0	6	0	0	0	6	0	0	0	0	0	6
16:15	0	0	0	0	0	0	0	0	0	0	5	0	0	0	5	0	0	0	0	0	5
16:20	0	0	0	0	0	0	0	4	0	4	1	0	0	0	1	0	0	0	0	0	5
16:25	0	0	0	0	0	0	0	1	0	1	3	0	0	0	3	0	0	0	0	0	4
16:30	0	0	0	0	0	0	0	1	0	1	4	0	0	0	4	0	0	0	0	0	5
16:35	0	0	0	0	0	0	0	0	0	0	4	0	0	0	4	0	0	0	0	0	4
16:40	0	0	0	0	0	0	0	4	0	4	5	0	0	0	5	0	0	0	0	0	9
16:45	0	0	0	0	0	0	0	4	0	4	2	0	0	0	2	0	0	0	0	0	6
16:50	0	0	0	0	0	0	0	1	0	1	2	0	0	0	2	0	0	0	0	0	3
16:55	0	0	0	0	0	0	0	1	0	1	5	0	0	0	5	0	0	0	0	0	6
17:00	0	0	0	0	0	0	0	3	0	3	6	0	0	0	6	0	0	0	0	0	9
17:05	0	0	0	0	0	0	0	0	0	0	5	0	0	0	5	0	0	0	0	0	5
Total Volume	0	0	0	0	0	0	0	19	0	19	48	0	0	0	48	0	0	0	0	0	67
% App. Total	0	0	0	0	0	0	0	100	0	100	0	0	0	0	0	0	0	0	0	0	
PHF	.000	.000	.000	.000	.000	.000	.000	.396	.000	.396	.667	.000	.000	.000	.667	.000	.000	.000	.000	.000	.620




LSC Transportation Consultants, Inc.

2504 E. Pikes Peak Ave, Suite 304
 Colorado Springs, CO 80909
 719-633-2868

File Name : Harvest Moon Terrace - Peaceful Meadow St PM V
 Site Code : S244050
 Start Date : 2/13/2024
 Page No : 3

Start Time	Southbound					Peaceful Meadow St Westbound					Harvest Moon Terrace Northbound					Peaceful Meadow St Eastbound					
	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
Peak Hour Analysis From 16:00 to 17:55 - Peak 1 of 1																					
Peak Hour for Each Approach Begins at:																					
16:00	0	0	0	0	0	0	0	4	0	4	6	0	0	0	0	6	0	0	0	0	0
+0 mins.	0	0	0	0	0	0	0	4	0	4	5	0	0	0	0	5	0	0	0	0	0
+5 mins.	0	0	0	0	0	0	0	1	0	1	1	0	0	0	0	1	0	0	0	0	0
+10 mins.	0	0	0	0	0	0	0	1	0	1	3	0	0	0	0	3	0	0	0	0	0
+15 mins.	0	0	0	0	0	0	0	1	0	1	4	0	0	0	0	4	0	0	0	0	0
+20 mins.	0	0	0	0	0	0	0	3	0	3	5	0	0	0	0	5	0	0	0	0	0
+25 mins.	0	0	0	0	0	0	0	0	0	0	4	0	0	0	0	4	0	0	0	0	0
+30 mins.	0	0	0	0	0	0	0	1	0	1	5	0	0	0	0	5	0	0	0	0	0
+35 mins.	0	0	0	0	0	0	0	1	0	1	2	0	0	0	0	2	0	0	0	0	0
+40 mins.	0	0	0	0	0	0	0	3	0	3	2	0	0	0	0	2	0	0	0	0	0
+45 mins.	0	0	0	0	0	0	0	3	0	3	5	0	0	0	0	5	0	0	0	0	0
+50 mins.	0	0	0	0	0	0	0	1	0	1	6	0	0	0	0	6	0	0	0	0	0
+55 mins.	0	0	0	0	0	0	0	1	0	1	5	0	0	0	0	5	0	0	0	0	0
Total Volume	0	0	0	0	0	0	0	23	0	23	48	0	0	0	0	48	0	0	0	0	0
% App. Total	0	0	0	0	0	0	0	100	0	100	100	0	0	0	0	0	0	0	0	0	0
PHF	.000	.000	.000	.000	.000	.000	.000	.479	.000	.479	.667	.000	.000	.000	.000	.667	.000	.000	.000	.000	.000



LSC Transportation Consultants, Inc.

2504 E. Pikes Peak Ave, Suite 304
 Colorado Springs, CO 80909
 719-633-2868

File Name : Harvest Moon Terrace - Hazy Morning Dr AM B
 Site Code : S244050
 Start Date : 2/15/2024
 Page No : 1

Groups Printed- Bank 1


Start Time	Harvest Moon Terrace Southbound					Hazy Morning Dr Westbound					Northbound					Hazy Morning Dr Eastbound					Int. Total
	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	
06:30	4	0	0	0	4	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	4
06:35	3	0	0	0	3	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	3
06:40	5	0	0	0	5	0	0	0	0	0	0	0	0	0	0	0	0	1	0	1	6
06:45	3	0	0	0	3	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	3
06:50	0	0	2	0	2	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	2
06:55	2	0	0	0	2	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	2
Total	17	0	2	0	19	0	0	0	0	0	0	0	0	0	0	0	0	1	0	1	20
07:00	3	0	0	0	3	0	0	0	0	0	0	0	0	0	0	0	0	1	0	1	4
07:05	6	0	0	0	6	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	6
07:10	4	0	0	0	4	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	4
07:15	6	0	0	0	6	0	0	0	0	0	0	0	0	0	0	0	0	1	0	1	7
07:20	7	0	0	0	7	1	0	0	0	1	0	0	0	0	0	0	0	0	1	0	9
07:25	4	0	0	0	4	0	0	0	0	0	0	0	0	0	0	0	0	2	0	2	6
07:30	4	0	0	0	4	0	0	0	0	0	0	0	0	0	0	0	0	2	0	2	6
07:35	4	0	0	0	4	0	0	0	0	0	0	0	0	0	0	0	0	2	0	2	6
07:40	3	0	0	0	3	0	0	0	0	0	0	0	0	0	0	0	0	1	0	1	4
07:45	8	0	0	0	8	0	0	0	0	0	0	0	0	0	0	0	0	2	0	2	10
*** BREAK ***																					
07:55	2	0	0	0	2	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	2
Total	51	0	0	0	51	1	0	0	0	1	0	0	0	0	0	0	0	12	0	12	64
08:00	7	0	0	0	7	0	0	0	0	0	0	0	0	0	0	0	0	1	0	1	8
08:05	3	0	0	0	3	0	0	0	0	0	1	0	0	0	1	0	0	1	0	1	5
08:10	2	0	0	0	2	0	0	0	0	0	0	0	0	0	0	0	0	1	0	1	3
08:15	2	0	0	0	2	0	0	0	0	0	0	0	0	0	0	0	0	2	0	2	4
08:20	2	0	0	0	2	0	0	0	0	0	0	0	0	0	0	0	0	2	0	2	4
08:25	4	0	0	0	4	0	0	0	0	0	0	0	0	0	0	0	0	1	0	1	5
Grand Total	88	0	2	0	90	1	0	0	0	1	1	0	0	0	1	0	0	21	0	21	113
Apprch %	97.8	0	2.2	0		100	0	0	0		100	0	0	0		0	0	100	0		
Total %	77.9	0	1.8	0	79.6	0.9	0	0	0	0.9	0.9	0	0	0	0.9	0	0	18.6	0	18.6	

LSC Transportation Consultants, Inc.

2504 E. Pikes Peak Ave, Suite 304
 Colorado Springs, CO 80909
 719-633-2868

File Name : Harvest Moon Terrace - Hazy Morning Dr AM B
 Site Code : S244050
 Start Date : 2/15/2024
 Page No : 2

	Harvest Moon Terrace Southbound					Hazy Morning Dr Westbound					Northbound					Hazy Morning Dr Eastbound					
	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
Peak Hour Analysis From 06:30 to 08:25 - Peak 1 of 1																					
Start Time																					
07:05	6	0	0	0	6	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	6
07:10	4	0	0	0	4	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	4
07:15	6	0	0	0	6	0	0	0	0	0	0	0	0	0	0	0	0	1	0	1	7
07:20	7	0	0	0	7	1	0	0	0	1	0	0	0	0	0	0	0	1	0	1	9
07:25	4	0	0	0	4	0	0	0	0	0	0	0	0	0	0	0	0	2	0	2	6
07:30	4	0	0	0	4	0	0	0	0	0	0	0	0	0	0	0	0	2	0	2	6
07:35	4	0	0	0	4	0	0	0	0	0	0	0	0	0	0	0	0	2	0	2	6
07:40	3	0	0	0	3	0	0	0	0	0	0	0	0	0	0	0	0	1	0	1	4
07:45	8	0	0	0	8	0	0	0	0	0	0	0	0	0	0	0	0	2	0	2	10
07:50	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
07:55	2	0	0	0	2	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	2
08:00	7	0	0	0	7	0	0	0	0	0	0	0	0	0	0	0	0	1	0	1	8
Total Volume	55	0	0	0	55	1	0	0	0	1	0	0	0	0	0	0	0	12	0	12	68
% App. Total	100	0	0	0		100	0	0	0		0	0	0	0	0	0	0	100	0	0	
PHF	.573	.000	.000	.000	.573	.083	.000	.000	.000	.083	.000	.000	.000	.000	.000	.000	.000	.500	.000	.500	.567




LSC Transportation Consultants, Inc.

2504 E. Pikes Peak Ave, Suite 304
 Colorado Springs, CO 80909
 719-633-2868

File Name : Harvest Moon Terrace - Hazy Morning Dr AM B
 Site Code : S244050
 Start Date : 2/15/2024
 Page No : 3

Start Time	Harvest Moon Terrace Southbound					Hazy Morning Dr Westbound					Northbound					Hazy Morning Dr Eastbound					
	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
Peak Hour Analysis From 06:30 to 08:25 - Peak 1 of 1																					
Peak Hour for Each Approach Begins at:																					
07:05	6	0	0	0	6	0	0	0	0	0	0	0	0	0	0	0	0	0	2	0	2
+5 mins.	4	0	0	0	4	0	0	0	0	0	0	0	0	0	0	0	0	0	2	0	2
+10 mins.	6	0	0	0	6	0	0	0	0	0	0	0	0	0	0	0	0	0	2	0	2
+15 mins.	7	0	0	0	7	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	1
+20 mins.	4	0	0	0	4	0	0	0	0	0	0	0	0	0	0	0	0	0	2	0	2
+25 mins.	4	0	0	0	4	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
+30 mins.	4	0	0	0	4	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
+35 mins.	3	0	0	0	3	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	1
+40 mins.	8	0	0	0	8	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	1
+45 mins.	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	1
+50 mins.	2	0	0	0	2	1	0	0	0	1	0	0	0	0	0	0	0	0	2	0	2
+55 mins.	7	0	0	0	7	0	0	0	0	0	1	0	0	0	0	1	0	0	2	0	2
Total Volume	55	0	0	0	55	1	0	0	0	1	1	0	0	0	0	1	0	0	16	0	16
% App. Total	100	0	0	0	100	0	0	0	0	100	0	0	0	0	0	0	0	0	100	0	0
PHF	.573	.000	.000	.000	.573	.083	.000	.000	.000	.083	.083	.000	.000	.000	.083	.000	.000	.667	.000	.667	



LSC Transportation Consultants, Inc.

2504 E. Pikes Peak Ave, Suite 304
 Colorado Springs, CO 80909
 719-633-2868

File Name : Harvest Moon Terrace - Hazy Morning Dr PM B
 Site Code : S244050
 Start Date : 2/13/2024
 Page No : 1

Groups Printed- Bank 1


Start Time	Harvest Moon Terrace Southbound					Hazy Morning Dr Westbound					Northbound					Hazy Morning Dr Eastbound					Int. Total
	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	
16:00	1	0	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	4	0	4	5
16:05	1	0	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	3	0	3	4
16:10	1	0	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	8	0	8	9
16:15	1	0	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	5	0	5	6
16:20	4	0	0	0	4	0	0	0	0	0	0	0	0	0	0	0	0	2	0	2	6
16:25	1	0	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	5	0	5	6
16:30	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	6	0	6	6
16:35	2	0	0	0	2	0	0	0	0	0	0	0	0	0	0	0	0	7	0	7	9
16:40	6	0	0	0	6	0	0	0	0	0	0	0	0	0	0	0	0	5	0	5	11
16:45	4	0	0	0	4	0	0	0	0	0	0	0	0	0	0	0	0	3	0	3	7
16:50	2	0	0	0	2	0	0	0	0	0	0	0	0	0	0	0	0	3	0	3	5
16:55	1	0	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	5	0	5	6
Total	24	0	0	0	24	0	0	0	0	0	0	0	0	0	0	0	0	56	0	56	80
17:00	4	0	0	0	4	0	0	0	0	0	0	0	0	0	0	0	0	6	0	6	10
17:05	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	6	0	6	6
17:10	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	1	1
17:15	4	0	0	0	4	0	0	0	0	0	0	0	0	0	0	0	0	2	0	2	6
17:20	2	0	0	0	2	0	0	0	0	0	0	0	0	0	0	0	0	5	0	5	7
17:25	5	0	0	0	5	0	0	0	0	0	0	0	0	0	0	0	0	2	0	2	7
17:30	1	0	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	4	0	4	5
17:35	1	0	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	3	0	3	4
17:40	3	0	0	0	3	0	0	0	0	0	0	0	0	0	0	0	0	4	0	4	7
17:45	2	0	0	0	2	0	0	0	0	0	0	0	0	0	0	0	0	5	0	5	7
17:50	2	0	0	0	2	0	0	0	0	0	0	0	0	0	0	0	0	4	0	4	6
17:55	3	0	0	0	3	0	0	0	0	0	0	0	0	0	0	0	0	5	0	5	8
Total	27	0	0	0	27	0	0	0	0	0	0	0	0	0	0	0	0	47	0	47	74
Grand Total	51	0	0	0	51	0	0	0	0	0	0	0	0	0	0	0	0	103	0	103	154
Apprch %	100	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	100	0	0	0
Total %	33.1	0	0	0	33.1	0	0	0	0	0	0	0	0	0	0	0	0	66.9	0	66.9	0

LSC Transportation Consultants, Inc.

2504 E. Pikes Peak Ave, Suite 304
 Colorado Springs, CO 80909
 719-633-2868

File Name : Harvest Moon Terrace - Hazy Morning Dr PM B
 Site Code : S244050
 Start Date : 2/13/2024
 Page No : 2

	Harvest Moon Terrace Southbound					Hazy Morning Dr Westbound					Northbound					Hazy Morning Dr Eastbound					
	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
Peak Hour Analysis From 16:00 to 17:55 - Peak 1 of 1																					
Start Time																					
16:10	1	0	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	8	0	8	9
16:15	1	0	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	5	0	5	6
16:20	4	0	0	0	4	0	0	0	0	0	0	0	0	0	0	0	0	2	0	2	6
16:25	1	0	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	5	0	5	6
16:30	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	6	0	6	6
16:35	2	0	0	0	2	0	0	0	0	0	0	0	0	0	0	0	0	7	0	7	9
16:40	6	0	0	0	6	0	0	0	0	0	0	0	0	0	0	0	0	5	0	5	11
16:45	4	0	0	0	4	0	0	0	0	0	0	0	0	0	0	0	0	3	0	3	7
16:50	2	0	0	0	2	0	0	0	0	0	0	0	0	0	0	0	0	3	0	3	5
16:55	1	0	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	5	0	5	6
17:00	4	0	0	0	4	0	0	0	0	0	0	0	0	0	0	0	0	6	0	6	10
17:05	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	6	0	6	6
Total Volume	26	0	0	0	26	0	0	0	0	0	0	0	0	0	0	0	0	61	0	61	87
% App. Total	100	0	0	0	100	0	0	0	0	0	0	0	0	0	0	0	0	100	0	100	0
PHF	.361	.000	.000	.000	.361	.000	.000	.000	.000	.000	.000	.000	.000	.000	.000	.000	.000	.635	.000	.635	.659




LSC Transportation Consultants, Inc.

2504 E. Pikes Peak Ave, Suite 304
 Colorado Springs, CO 80909
 719-633-2868

File Name : Harvest Moon Terrace - Hazy Morning Dr PM B
 Site Code : S244050
 Start Date : 2/13/2024
 Page No : 3

Start Time	Harvest Moon Terrace Southbound					Hazy Morning Dr Westbound					Northbound					Hazy Morning Dr Eastbound					
	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
Peak Hour Analysis From 16:00 to 17:55 - Peak 1 of 1																					
Peak Hour for Each Approach Begins at:																					
16:35	2	0	0	0	2	0	0	0	0	0	0	0	0	0	0	0	0	0	8	0	8
+0 mins.	2	0	0	0	2	0	0	0	0	0	0	0	0	0	0	0	0	0	5	0	5
+5 mins.	6	0	0	0	6	0	0	0	0	0	0	0	0	0	0	0	0	0	2	0	2
+10 mins.	4	0	0	0	4	0	0	0	0	0	0	0	0	0	0	0	0	0	5	0	5
+15 mins.	2	0	0	0	2	0	0	0	0	0	0	0	0	0	0	0	0	0	5	0	5
+20 mins.	1	0	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	6	0	6
+25 mins.	4	0	0	0	4	0	0	0	0	0	0	0	0	0	0	0	0	0	7	0	7
+30 mins.	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	5	0	5
+35 mins.	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	3	0	3
+40 mins.	4	0	0	0	4	0	0	0	0	0	0	0	0	0	0	0	0	0	3	0	3
+45 mins.	2	0	0	0	2	0	0	0	0	0	0	0	0	0	0	0	0	0	5	0	5
+50 mins.	5	0	0	0	5	0	0	0	0	0	0	0	0	0	0	0	0	0	6	0	6
+55 mins.	1	0	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	6	0	6
Total Volume	31	0	0	0	31	0	0	0	0	0	0	0	0	0	0	0	0	0	61	0	61
% App. Total	100	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	100	0	0
PHF	.431	.000	.000	.000	.431	.000	.000	.000	.000	.000	.000	.000	.000	.000	.000	.000	.000	.635	.000	.635	



Level of Service Reports



HCM 6th TWSC
1: Horizonview & Hazy Morning

2024 Existing
AM

Intersection

Int Delay, s/veh 4.7

Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations	W	B	B			
Traffic Vol, veh/h	81	26	54	20	4	47
Future Vol, veh/h	81	26	54	20	4	47
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	-	-	-	-
Veh in Median Storage, #	0	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	83	83	83	83	83	83
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	98	31	65	24	5	57

Major/Minor	Minor1	Major1	Major2		
Conflicting Flow All	144	77	0	0	89
Stage 1	77	-	-	-	-
Stage 2	67	-	-	-	-
Critical Hdwy	6.42	6.22	-	-	4.12
Critical Hdwy Stg 1	5.42	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-
Follow-up Hdwy	3.518	3.318	-	-	2.218
Pot Cap-1 Maneuver	849	984	-	-	1506
Stage 1	946	-	-	-	-
Stage 2	956	-	-	-	-
Platoon blocked, %	-	-	-	-	-
Mov Cap-1 Maneuver	846	984	-	-	1506
Mov Cap-2 Maneuver	846	-	-	-	-
Stage 1	946	-	-	-	-
Stage 2	953	-	-	-	-

Approach	WB	NB	SB
HCM Control Delay, s	9.8	0	0.6
HCM LOS	A		

Minor Lane/Major Mvmt	NBT	NBR	WBLn1	SBL	SBT
Capacity (veh/h)	-	-	876	1506	-
HCM Lane V/C Ratio	-	-	0.147	0.003	-
HCM Control Delay (s)	-	-	9.8	7.4	0
HCM Lane LOS	-	-	A	A	A
HCM 95th %tile Q(veh)	-	-	0.5	0	-

HCM 6th TWSC
2: Hazy Morning & Harvest Moon

2024 Existing
AM

Intersection

Int Delay, s/veh 4.4

Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Vol, veh/h	12	12	52	1	0	55
Future Vol, veh/h	12	12	52	1	0	55
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	83	83	83	83	83	83
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	14	14	63	1	0	66

Major/Minor	Major1	Major2	Minor2			
Conflicting Flow All	64	0	-	0	106	64
Stage 1	-	-	-	-	64	-
Stage 2	-	-	-	-	42	-
Critical Hdwy	4.12	-	-	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	2.218	-	-	-	3.518	3.318
Pot Cap-1 Maneuver	1538	-	-	-	892	1000
Stage 1	-	-	-	-	959	-
Stage 2	-	-	-	-	980	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	1538	-	-	-	884	1000
Mov Cap-2 Maneuver	-	-	-	-	884	-
Stage 1	-	-	-	-	950	-
Stage 2	-	-	-	-	980	-

Approach	EB	WB	SB			
HCM Control Delay, s	3.7	0	8.9			
HCM LOS			A			

Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1	
Capacity (veh/h)	1538	-	-	-	1000	
HCM Lane V/C Ratio	0.009	-	-	-	0.066	
HCM Control Delay (s)	7.4	0	-	-	8.9	
HCM Lane LOS	A	A	-	-	A	
HCM 95th %tile Q(veh)	0	-	-	-	0.2	

HCM 6th TWSC
4: Harvest Moon & Peaceful Meadow

2024 Existing
AM

Intersection

Int Delay, s/veh 7.4

Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations	↑		↔	↔		
Traffic Vol, veh/h	0	0	50	0	0	13
Future Vol, veh/h	0	0	50	0	0	13
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	83	83	83	83	83	83
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	0	0	60	0	0	16

Major/Minor	Major1	Major2	Minor1		
Conflicting Flow All	0	0	1	0	121
Stage 1	-	-	-	-	1
Stage 2	-	-	-	-	120
Critical Hdwy	-	-	4.12	-	6.42
Critical Hdwy Stg 1	-	-	-	-	5.42
Critical Hdwy Stg 2	-	-	-	-	5.42
Follow-up Hdwy	-	-	2.218	-	3.518
Pot Cap-1 Maneuver	-	-	1622	-	874
Stage 1	-	-	-	-	1022
Stage 2	-	-	-	-	905
Platoon blocked, %	-	-	-	-	-
Mov Cap-1 Maneuver	-	-	1622	-	842
Mov Cap-2 Maneuver	-	-	-	-	842
Stage 1	-	-	-	-	1022
Stage 2	-	-	-	-	872

Approach	EB	WB	NB
HCM Control Delay, s	0	7.3	8.4
HCM LOS			A

Minor Lane/Major Mvmt	NBLn1	EBT	EBR	WBL	WBT
Capacity (veh/h)	1084	-	-	1622	-
HCM Lane V/C Ratio	0.014	-	-	0.037	-
HCM Control Delay (s)	8.4	-	-	7.3	0
HCM Lane LOS	A	-	-	A	A
HCM 95th %tile Q(veh)	0	-	-	0.1	-

Intersection

Int Delay, s/veh 2.7

Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations	W	B	B			
Traffic Vol, veh/h	37	12	50	74	22	57
Future Vol, veh/h	37	12	50	74	22	57
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	-	-	-	-
Veh in Median Storage, #	0	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	78	78	83	83	83	83
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	47	15	60	89	27	69

Major/Minor	Minor1	Major1	Major2		
Conflicting Flow All	228	105	0	0	149
Stage 1	105	-	-	-	-
Stage 2	123	-	-	-	-
Critical Hdwy	6.42	6.22	-	-	4.12
Critical Hdwy Stg 1	5.42	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-
Follow-up Hdwy	3.518	3.318	-	-	2.218
Pot Cap-1 Maneuver	760	949	-	-	1432
Stage 1	919	-	-	-	-
Stage 2	902	-	-	-	-
Platoon blocked, %	-	-	-	-	-
Mov Cap-1 Maneuver	745	949	-	-	1432
Mov Cap-2 Maneuver	745	-	-	-	-
Stage 1	919	-	-	-	-
Stage 2	884	-	-	-	-

Approach	WB	NB	SB
HCM Control Delay, s	10	0	2.1
HCM LOS	B		

Minor Lane/Major Mvmt	NBT	NBR	WBLn1	SBL	SBT
Capacity (veh/h)	-	-	786	1432	-
HCM Lane V/C Ratio	-	-	0.08	0.019	-
HCM Control Delay (s)	-	-	10	7.6	0
HCM Lane LOS	-	-	B	A	A
HCM 95th %tile Q(veh)	-	-	0.3	0.1	-

HCM 6th TWSC
2: Hazy Morning & Harvest Moon

2024 Existing
PM

Intersection

Int Delay, s/veh 4.7

Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Vol, veh/h	61	35	23	0	0	26
Future Vol, veh/h	61	35	23	0	0	26
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	83	83	78	78	78	78
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	73	42	29	0	0	33

Major/Minor	Major1	Major2	Minor2			
Conflicting Flow All	29	0	-	0	217	29
Stage 1	-	-	-	-	29	-
Stage 2	-	-	-	-	188	-
Critical Hdwy	4.12	-	-	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	2.218	-	-	-	3.518	3.318
Pot Cap-1 Maneuver	1584	-	-	-	771	1046
Stage 1	-	-	-	-	994	-
Stage 2	-	-	-	-	844	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	1584	-	-	-	735	1046
Mov Cap-2 Maneuver	-	-	-	-	735	-
Stage 1	-	-	-	-	947	-
Stage 2	-	-	-	-	844	-

Approach	EB	WB	SB			
HCM Control Delay, s	4.7	0	8.6			
HCM LOS			A			
<hr/>						
Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1	
Capacity (veh/h)	1584	-	-	-	1046	
HCM Lane V/C Ratio	0.046	-	-	-	0.032	
HCM Control Delay (s)	7.4	0	-	-	8.6	
HCM Lane LOS	A	A	-	-	A	
HCM 95th %tile Q(veh)	0.1	-	-	-	0.1	

HCM 6th TWSC
4: Harvest Moon & Peaceful Meadow

2024 Existing
PM

Intersection

Int Delay, s/veh 8.1

Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations	↑		↔	↔		
Traffic Vol, veh/h	0	0	25	0	0	65
Future Vol, veh/h	0	0	25	0	0	65
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	83	83	78	78	83	83
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	0	0	32	0	0	78

Major/Minor	Major1	Major2	Minor1		
Conflicting Flow All	0	0	1	0	65 1
Stage 1	-	-	-	-	1 -
Stage 2	-	-	-	-	64 -
Critical Hdwy	-	-	4.12	-	6.42 6.22
Critical Hdwy Stg 1	-	-	-	-	5.42 -
Critical Hdwy Stg 2	-	-	-	-	5.42 -
Follow-up Hdwy	-	-	2.218	-	3.518 3.318
Pot Cap-1 Maneuver	-	-	1622	-	941 1084
Stage 1	-	-	-	-	1022 -
Stage 2	-	-	-	-	959 -
Platoon blocked, %	-	-	-	-	-
Mov Cap-1 Maneuver	-	-	1622	-	922 1084
Mov Cap-2 Maneuver	-	-	-	-	922 -
Stage 1	-	-	-	-	1022 -
Stage 2	-	-	-	-	940 -

Approach	EB	WB	NB
HCM Control Delay, s	0	7.3	8.6
HCM LOS			A

Minor Lane/Major Mvmt	NBLn1	EBT	EBR	WBL	WBT
Capacity (veh/h)	1084	-	-	1622	-
HCM Lane V/C Ratio	0.072	-	-	0.02	-
HCM Control Delay (s)	8.6	-	-	7.3	0
HCM Lane LOS	A	-	-	A	A
HCM 95th %tile Q(veh)	0.2	-	-	0.1	-

Intersection

Int Delay, s/veh 5.1

Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations	W	B	A			
Traffic Vol, veh/h	96	33	54	26	6	47
Future Vol, veh/h	96	33	54	26	6	47
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	-	-	-	-
Veh in Median Storage, #	0	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	83	83	83	83	83	83
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	116	40	65	31	7	57

Major/Minor	Minor1	Major1	Major2		
Conflicting Flow All	152	81	0	0	96
Stage 1	81	-	-	-	-
Stage 2	71	-	-	-	-
Critical Hdwy	6.42	6.22	-	-	4.12
Critical Hdwy Stg 1	5.42	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-
Follow-up Hdwy	3.518	3.318	-	-	2.218
Pot Cap-1 Maneuver	840	979	-	-	1498
Stage 1	942	-	-	-	-
Stage 2	952	-	-	-	-
Platoon blocked, %	-	-	-	-	-
Mov Cap-1 Maneuver	836	979	-	-	1498
Mov Cap-2 Maneuver	836	-	-	-	-
Stage 1	942	-	-	-	-
Stage 2	947	-	-	-	-

Approach	WB	NB	SB
HCM Control Delay, s	10.1	0	0.8
HCM LOS	B		

Minor Lane/Major Mvmt	NBT	NBR	WBLn1	SBL	SBT
Capacity (veh/h)	-	-	868	1498	-
HCM Lane V/C Ratio	-	-	0.179	0.005	-
HCM Control Delay (s)	-	-	10.1	7.4	0
HCM Lane LOS	-	-	B	A	A
HCM 95th %tile Q(veh)	-	-	0.7	0	-

Intersection

Int Delay, s/veh 4.8

Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Vol, veh/h	12	20	52	1	0	77
Future Vol, veh/h	12	20	52	1	0	77
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	78	78	83	83	83	83
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	15	26	63	1	0	93

Major/Minor	Major1	Major2	Minor2			
Conflicting Flow All	64	0	-	0	120	64
Stage 1	-	-	-	-	64	-
Stage 2	-	-	-	-	56	-
Critical Hdwy	4.12	-	-	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	2.218	-	-	-	3.518	3.318
Pot Cap-1 Maneuver	1538	-	-	-	876	1000
Stage 1	-	-	-	-	959	-
Stage 2	-	-	-	-	967	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	1538	-	-	-	867	1000
Mov Cap-2 Maneuver	-	-	-	-	867	-
Stage 1	-	-	-	-	949	-
Stage 2	-	-	-	-	967	-

Approach	EB	WB	SB			
HCM Control Delay, s	2.8	0	9			
HCM LOS			A			

Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1	
Capacity (veh/h)	1538	-	-	-	1000	
HCM Lane V/C Ratio	0.01	-	-	-	0.093	
HCM Control Delay (s)	7.4	0	-	-	9	
HCM Lane LOS	A	A	-	-	A	
HCM 95th %tile Q(veh)	0	-	-	-	0.3	

Intersection						
Int Delay, s/veh	0.7					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Vol, veh/h	2	13	50	0	0	4
Future Vol, veh/h	2	13	50	0	0	4
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	83	83	78	78	78	78
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	2	16	64	0	0	5
Major/Minor	Major1	Major2	Minor2			
Conflicting Flow All	64	0	-	0	84	64
Stage 1	-	-	-	-	64	-
Stage 2	-	-	-	-	20	-
Critical Hdwy	4.12	-	-	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	2.218	-	-	-	3.518	3.318
Pot Cap-1 Maneuver	1538	-	-	-	918	1000
Stage 1	-	-	-	-	959	-
Stage 2	-	-	-	-	1003	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	1538	-	-	-	917	1000
Mov Cap-2 Maneuver	-	-	-	-	917	-
Stage 1	-	-	-	-	958	-
Stage 2	-	-	-	-	1003	-
Approach	EB	WB	SB			
HCM Control Delay, s	1	0	8.6			
HCM LOS			A			
Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1	SBLn2
Capacity (veh/h)	1538	-	-	-	1000	-
HCM Lane V/C Ratio	0.002	-	-	-	0.005	-
HCM Control Delay (s)	7.3	0	-	-	8.6	-
HCM Lane LOS	A	A	-	-	A	-
HCM 95th %tile Q(veh)	0	-	-	-	0	-

Intersection												
Int Delay, s/veh	4.3											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	+	+	+	+	+	+	+	+	+	+	+	+
Traffic Vol, veh/h	0	0	0	54	0	0	0	6	15	0	18	0
Future Vol, veh/h	0	0	0	54	0	0	0	6	15	0	18	0
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Free	Free	Stop	Stop	Stop	Stop	Stop	Stop
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	-	-	-	-	-	-	-	-	-	-	-	-
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	78	78	78	78	78	78	83	83	83	78	78	78
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	0	0	0	69	0	0	0	7	18	0	23	0
Major/Minor												
Major1		Major2			Minor1			Minor2				
Conflicting Flow All	0	0	0	1	0	0	151	139	1	152	139	0
Stage 1	-	-	-	-	-	-	1	1	-	138	138	-
Stage 2	-	-	-	-	-	-	150	138	-	14	1	-
Critical Hdwy	4.12	-	-	4.12	-	-	7.12	6.52	6.22	7.12	6.52	6.22
Critical Hdwy Stg 1	-	-	-	-	-	-	6.12	5.52	-	6.12	5.52	-
Critical Hdwy Stg 2	-	-	-	-	-	-	6.12	5.52	-	6.12	5.52	-
Follow-up Hdwy	2.218	-	-	2.218	-	-	3.518	4.018	3.318	3.518	4.018	3.318
Pot Cap-1 Maneuver	-	-	-	1622	-	-	816	752	1084	815	752	-
Stage 1	-	-	-	-	-	-	1022	895	-	865	782	-
Stage 2	-	-	-	-	-	-	853	782	-	1006	895	-
Platoon blocked, %	-	-	-	-	-	-	-	-	-	-	-	-
Mov Cap-1 Maneuver	-	-	-	1622	-	-	-	720	1084	769	720	-
Mov Cap-2 Maneuver	-	-	-	-	-	-	-	720	-	769	720	-
Stage 1	-	-	-	-	-	-	1022	895	-	865	748	-
Stage 2	-	-	-	-	-	-	791	748	-	981	895	-
Approach												
EB			WB			NB			SB			
HCM Control Delay, s	0			7.3								
HCM LOS	-											
Minor Lane/Major Mvmt												
NBLn1		EBL	EBT	EBR	WBL	WBT	WBR	SBLn1				
Capacity (veh/h)	-	-	-	-	1622	-	-	-				
HCM Lane V/C Ratio	-	-	-	-	0.043	-	-	-				
HCM Control Delay (s)	-	0	-	-	7.3	0	-	-				
HCM Lane LOS	-	A	-	-	A	A	-	-				
HCM 95th %tile Q(veh)	-	-	-	-	0.1	-	-	-				

Intersection

Int Delay, s/veh 3

Movement	WBL	WBR	NBT	NBR	SBL	SBT
----------	-----	-----	-----	-----	-----	-----

Lane Configurations						
Traffic Vol, veh/h	47	17	50	92	30	57
Future Vol, veh/h	47	17	50	92	30	57
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	-	-	-	-
Veh in Median Storage, #	0	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	83	83	83	83	83	83
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	57	20	60	111	36	69

Major/Minor	Minor1	Major1	Major2
-------------	--------	--------	--------

Conflicting Flow All	257	116	0	0	171	0
Stage 1	116	-	-	-	-	-
Stage 2	141	-	-	-	-	-
Critical Hdwy	6.42	6.22	-	-	4.12	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	-	-	2.218	-
Pot Cap-1 Maneuver	732	936	-	-	1406	-
Stage 1	909	-	-	-	-	-
Stage 2	886	-	-	-	-	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	712	936	-	-	1406	-
Mov Cap-2 Maneuver	712	-	-	-	-	-
Stage 1	909	-	-	-	-	-
Stage 2	862	-	-	-	-	-

Approach	WB	NB	SB
----------	----	----	----

HCM Control Delay, s	10.3	0	2.6
----------------------	------	---	-----

HCM LOS	B
---------	---

Minor Lane/Major Mvmt	NBT	NBR	WBLn1	SBL	SBT
Capacity (veh/h)	-	-	760	1406	-
HCM Lane V/C Ratio	-	-	0.101	0.026	-
HCM Control Delay (s)	-	-	10.3	7.6	0
HCM Lane LOS	-	-	B	A	A
HCM 95th %tile Q(veh)	-	-	0.3	0.1	-

Intersection

Int Delay, s/veh 3.3

Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Vol, veh/h	35	87	23	0	0	41
Future Vol, veh/h	35	87	23	0	0	41
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	83	83	78	78	78	78
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	42	105	29	0	0	53

Major/Minor	Major1	Major2	Minor2			
Conflicting Flow All	29	0	-	0	218	29
Stage 1	-	-	-	-	29	-
Stage 2	-	-	-	-	189	-
Critical Hdwy	4.12	-	-	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	2.218	-	-	-	3.518	3.318
Pot Cap-1 Maneuver	1584	-	-	-	770	1046
Stage 1	-	-	-	-	994	-
Stage 2	-	-	-	-	843	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	1584	-	-	-	748	1046
Mov Cap-2 Maneuver	-	-	-	-	748	-
Stage 1	-	-	-	-	966	-
Stage 2	-	-	-	-	843	-

Approach	EB	WB	SB			
HCM Control Delay, s	2.1	0	8.6			
HCM LOS			A			

Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1	
Capacity (veh/h)	1584	-	-	-	1046	
HCM Lane V/C Ratio	0.027	-	-	-	0.05	
HCM Control Delay (s)	7.3	0	-	-	8.6	
HCM Lane LOS	A	A	-	-	A	
HCM 95th %tile Q(veh)	0.1	-	-	-	0.2	

Intersection

Int Delay, s/veh 0.6

Movement EBL EBT WBT WBR SBL SBR

Lane Configurations						
Traffic Vol, veh/h	5	65	25	0	0	3
Future Vol, veh/h	5	65	25	0	0	3
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	83	83	78	78	78	78
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	6	78	32	0	0	4

Major/Minor Major1 Major2 Minor2

Conflicting Flow All	32	0	-	0	122	32
Stage 1	-	-	-	-	32	-
Stage 2	-	-	-	-	90	-
Critical Hdwy	4.12	-	-	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	2.218	-	-	-	3.518	3.318
Pot Cap-1 Maneuver	1580	-	-	-	873	1042
Stage 1	-	-	-	-	991	-
Stage 2	-	-	-	-	934	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	1580	-	-	-	870	1042
Mov Cap-2 Maneuver	-	-	-	-	870	-
Stage 1	-	-	-	-	987	-
Stage 2	-	-	-	-	934	-

Approach EB WB SB

HCM Control Delay, s 0.5 0 8.5

HCM LOS A

Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1
Capacity (veh/h)	1580	-	-	-	1042
HCM Lane V/C Ratio	0.004	-	-	-	0.004
HCM Control Delay (s)	7.3	0	-	-	8.5
HCM Lane LOS	A	A	-	-	A
HCM 95th %tile Q(veh)	0	-	-	-	0

Intersection												
Int Delay, s/veh	1.6											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	+	+	+	+	+	+	+	+	+	+	+	+
Traffic Vol, veh/h	0	0	0	28	0	0	0	21	70	0	12	0
Future Vol, veh/h	0	0	0	28	0	0	0	21	70	0	12	0
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Free	Free	Stop	Stop	Stop	Stop	Stop	Stop
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	-	-	-	-	-	-	-	-	-	-	-	-
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	78	78	78	78	78	78	83	83	83	78	78	78
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	0	0	0	36	0	0	0	25	84	0	15	0
Major/Minor												
Major1		Major2			Minor1		Minor2					
Conflicting Flow All	0	0	0	1	0	0	81	73	1	128	73	0
Stage 1	-	-	-	-	-	-	1	1	-	72	72	-
Stage 2	-	-	-	-	-	-	80	72	-	56	1	-
Critical Hdwy	4.12	-	-	4.12	-	-	7.12	6.52	6.22	7.12	6.52	6.22
Critical Hdwy Stg 1	-	-	-	-	-	-	6.12	5.52	-	6.12	5.52	-
Critical Hdwy Stg 2	-	-	-	-	-	-	6.12	5.52	-	6.12	5.52	-
Follow-up Hdwy	2.218	-	-	2.218	-	-	3.518	4.018	3.318	3.518	4.018	3.318
Pot Cap-1 Maneuver	-	-	-	1622	-	-	907	817	1084	845	817	-
Stage 1	-	-	-	-	-	-	1022	895	-	938	835	-
Stage 2	-	-	-	-	-	-	929	835	-	956	895	-
Platoon blocked, %	-	-	-	-	-	-	-	-	-	-	-	-
Mov Cap-1 Maneuver	-	-	-	1622	-	-	-	799	1084	748	799	-
Mov Cap-2 Maneuver	-	-	-	-	-	-	-	799	-	748	799	-
Stage 1	-	-	-	-	-	-	1022	895	-	938	817	-
Stage 2	-	-	-	-	-	-	891	817	-	857	895	-
Approach												
EB			WB			NB			SB			
HCM Control Delay, s	0			7.3								
HCM LOS	-											
Minor Lane/Major Mvmt												
NBLn1		EBL	EBT	EBR	WBL	WBT	WBR	SBLn1				
Capacity (veh/h)	-	-	-	-	1622	-	-	-				
HCM Lane V/C Ratio	-	-	-	-	0.022	-	-	-				
HCM Control Delay (s)	-	0	-	-	7.3	0	-	-				
HCM Lane LOS	-	A	-	-	A	A	-	-				
HCM 95th %tile Q(veh)	-	-	-	-	0.1	-	-	-				

Intersection

Int Delay, s/veh 1.8

Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations	W	B			A	
Traffic Vol, veh/h	53	24	243	11	3	288
Future Vol, veh/h	53	24	243	11	3	288
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	-	-	-	-
Veh in Median Storage, #	0	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	83	83	92	92	92	92
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	64	29	264	12	3	313

Major/Minor	Minor1	Major1	Major2		
Conflicting Flow All	589	270	0	0	276
Stage 1	270	-	-	-	-
Stage 2	319	-	-	-	-
Critical Hdwy	6.42	6.22	-	-	4.12
Critical Hdwy Stg 1	5.42	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-
Follow-up Hdwy	3.518	3.318	-	-	2.218
Pot Cap-1 Maneuver	471	769	-	-	1287
Stage 1	775	-	-	-	-
Stage 2	737	-	-	-	-
Platoon blocked, %	-	-	-	-	-
Mov Cap-1 Maneuver	470	769	-	-	1287
Mov Cap-2 Maneuver	470	-	-	-	-
Stage 1	775	-	-	-	-
Stage 2	735	-	-	-	-

Approach	WB	NB	SB
HCM Control Delay, s	13.1	0	0.1
HCM LOS	B		

Minor Lane/Major Mvmt	NBT	NBR	WBLn1	SBL	SBT
Capacity (veh/h)	-	-	535	1287	-
HCM Lane V/C Ratio	-	-	0.173	0.003	-
HCM Control Delay (s)	-	-	13.1	7.8	0
HCM Lane LOS	-	-	B	A	A
HCM 95th %tile Q(veh)	-	-	0.6	0	-

Intersection						
Int Delay, s/veh	5.2					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Vol, veh/h	3	11	25	1	0	52
Future Vol, veh/h	3	11	25	1	0	52
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	83	83	83	83	83	83
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	4	13	30	1	0	63
Major/Minor	Major1	Major2	Minor2			
Conflicting Flow All	31	0	-	0	52	31
Stage 1	-	-	-	-	31	-
Stage 2	-	-	-	-	21	-
Critical Hdwy	4.12	-	-	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	2.218	-	-	-	3.518	3.318
Pot Cap-1 Maneuver	1582	-	-	-	957	1043
Stage 1	-	-	-	-	992	-
Stage 2	-	-	-	-	1002	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	1582	-	-	-	954	1043
Mov Cap-2 Maneuver	-	-	-	-	954	-
Stage 1	-	-	-	-	989	-
Stage 2	-	-	-	-	1002	-
Approach	EB	WB	SB			
HCM Control Delay, s	1.6	0	8.7			
HCM LOS			A			
Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1	SBLn2
Capacity (veh/h)	1582	-	-	-	1043	-
HCM Lane V/C Ratio	0.002	-	-	-	0.06	-
HCM Control Delay (s)	7.3	0	-	-	8.7	-
HCM Lane LOS	A	A	-	-	A	-
HCM 95th %tile Q(veh)	0	-	-	-	0.2	-

Intersection						
Int Delay, s/veh	2.5					
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations	↑		↔	↔		
Traffic Vol, veh/h	18	1	20	32	2	3
Future Vol, veh/h	18	1	20	32	2	3
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	78	78	83	83	78	78
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	23	1	24	39	3	4
Major/Minor	Major1	Major2	Minor1			
Conflicting Flow All	0	0	24	0	111	24
Stage 1	-	-	-	-	24	-
Stage 2	-	-	-	-	87	-
Critical Hdwy	-	-	4.12	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	-	-	2.218	-	3.518	3.318
Pot Cap-1 Maneuver	-	-	1591	-	886	1052
Stage 1	-	-	-	-	999	-
Stage 2	-	-	-	-	936	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	-	-	1591	-	873	1052
Mov Cap-2 Maneuver	-	-	-	-	873	-
Stage 1	-	-	-	-	999	-
Stage 2	-	-	-	-	922	-
Approach	EB	WB	NB			
HCM Control Delay, s	0	2.8	8.7			
HCM LOS			A			
Minor Lane/Major Mvmt	NBLn1	EBT	EBR	WBL	WBT	
Capacity (veh/h)	972	-	-	1591	-	
HCM Lane V/C Ratio	0.007	-	-	0.015	-	
HCM Control Delay (s)	8.7	-	-	7.3	0	
HCM Lane LOS	A	-	-	A	A	
HCM 95th %tile Q(veh)	0	-	-	0	-	

Intersection												
Int Delay, s/veh		3.9										
Movement	SEL	SET	SER	NWL	NWT	NWR	NEL	NET	NER	SWL	SWT	SWR
Lane Configurations	+	+	+	+	+	+	+	+	+	+	+	+
Traffic Vol, veh/h	4	156	7	20	223	24	10	0	70	67	0	11
Future Vol, veh/h	4	156	7	20	223	24	10	0	70	67	0	11
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Free	Free	Stop	Stop	Stop	Stop	Stop	Stop
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	-	-	-	-	-	-	-	-	-	-	-	-
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	83	83	83	92	92	92	83	83	83	83	83	83
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	5	188	8	22	242	26	12	0	84	81	0	13
Major/Minor												
Major1		Major2			Minor1			Minor2				
Conflicting Flow All	268	0	0	196	0	0	508	514	192	543	505	255
Stage 1	-	-	-	-	-	-	202	202	-	299	299	-
Stage 2	-	-	-	-	-	-	306	312	-	244	206	-
Critical Hdwy	4.12	-	-	4.12	-	-	7.12	6.52	6.22	7.12	6.52	6.22
Critical Hdwy Stg 1	-	-	-	-	-	-	6.12	5.52	-	6.12	5.52	-
Critical Hdwy Stg 2	-	-	-	-	-	-	6.12	5.52	-	6.12	5.52	-
Follow-up Hdwy	2.218	-	-	2.218	-	-	3.518	4.018	3.318	3.518	4.018	3.318
Pot Cap-1 Maneuver	1296	-	-	1377	-	-	475	464	850	451	470	784
Stage 1	-	-	-	-	-	-	800	734	-	710	666	-
Stage 2	-	-	-	-	-	-	704	658	-	760	731	-
Platoon blocked, %	-	-	-	-	-	-	-	-	-	-	-	-
Mov Cap-1 Maneuver	1296	-	-	1377	-	-	459	453	850	399	459	784
Mov Cap-2 Maneuver	-	-	-	-	-	-	459	453	-	399	459	-
Stage 1	-	-	-	-	-	-	797	731	-	707	653	-
Stage 2	-	-	-	-	-	-	679	645	-	682	728	-
Approach												
SE		NW			NE			SW				
HCM Control Delay, s	0.2			0.6			10.4			15.7		
HCM LOS							B			C		
Minor Lane/Major Mvmt												
NELn1		NWL	NWT	NWR	SEL	SET	SERSWLn1					
Capacity (veh/h)	768	1377	-	-	1296	-	-	-	-	429	-	-
HCM Lane V/C Ratio	0.126	0.016	-	-	0.004	-	-	-	-	0.219	-	-
HCM Control Delay (s)	10.4	7.7	0	-	7.8	0	-	-	-	15.7	-	-
HCM Lane LOS	B	A	A	-	A	A	-	-	-	C	-	-
HCM 95th %tile Q(veh)	0.4	0	-	-	0	-	-	-	-	0.8	-	-

Intersection

Int Delay, s/veh 0.9

Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations	W	B	A			
Traffic Vol, veh/h	18	11	297	40	20	298
Future Vol, veh/h	18	11	297	40	20	298
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	-	-	-	-
Veh in Median Storage, #	0	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	78	78	92	92	92	92
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	23	14	323	43	22	324

Major/Minor	Minor1	Major1	Major2		
Conflicting Flow All	713	345	0	0	366
Stage 1	345	-	-	-	-
Stage 2	368	-	-	-	-
Critical Hdwy	6.42	6.22	-	-	4.12
Critical Hdwy Stg 1	5.42	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-
Follow-up Hdwy	3.518	3.318	-	-	2.218
Pot Cap-1 Maneuver	398	698	-	-	1193
Stage 1	717	-	-	-	-
Stage 2	700	-	-	-	-
Platoon blocked, %	-	-	-	-	-
Mov Cap-1 Maneuver	389	698	-	-	1193
Mov Cap-2 Maneuver	389	-	-	-	-
Stage 1	717	-	-	-	-
Stage 2	685	-	-	-	-

Approach	WB	NB	SB
HCM Control Delay, s	13.4	0	0.5
HCM LOS	B		

Minor Lane/Major Mvmt	NBT	NBR	WBLn1	SBL	SBT
Capacity (veh/h)	-	-	468	1193	-
HCM Lane V/C Ratio	-	-	0.079	0.018	-
HCM Control Delay (s)	-	-	13.4	8.1	0
HCM Lane LOS	-	-	B	A	A
HCM 95th %tile Q(veh)	-	-	0.3	0.1	-

Intersection						
Int Delay, s/veh	2.6					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Vol, veh/h	3	57	5	0	0	24
Future Vol, veh/h	3	57	5	0	0	24
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	83	83	78	78	78	78
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	4	69	6	0	0	31
Major/Minor	Major1	Major2	Minor2			
Conflicting Flow All	6	0	-	0	83	6
Stage 1	-	-	-	-	6	-
Stage 2	-	-	-	-	77	-
Critical Hdwy	4.12	-	-	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	2.218	-	-	-	3.518	3.318
Pot Cap-1 Maneuver	1615	-	-	-	919	1077
Stage 1	-	-	-	-	1017	-
Stage 2	-	-	-	-	946	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	1615	-	-	-	916	1077
Mov Cap-2 Maneuver	-	-	-	-	916	-
Stage 1	-	-	-	-	1014	-
Stage 2	-	-	-	-	946	-
Approach	EB	WB	SB			
HCM Control Delay, s	0.4	0	8.4			
HCM LOS			A			
Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1	
Capacity (veh/h)	1615	-	-	-	1077	
HCM Lane V/C Ratio	0.002	-	-	-	0.029	
HCM Control Delay (s)	7.2	0	-	-	8.4	
HCM Lane LOS	A	A	-	-	A	
HCM 95th %tile Q(veh)	0	-	-	-	0.1	

Intersection						
Int Delay, s/veh	3.5					
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations	↑		↔	↔		
Traffic Vol, veh/h	30	2	5	22	1	31
Future Vol, veh/h	30	2	5	22	1	31
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	78	78	78	78	78	78
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	38	3	6	28	1	40
Major/Minor	Major1	Major2	Minor1			
Conflicting Flow All	0	0	41	0	80	40
Stage 1	-	-	-	-	40	-
Stage 2	-	-	-	-	40	-
Critical Hdwy	-	-	4.12	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	-	-	2.218	-	3.518	3.318
Pot Cap-1 Maneuver	-	-	1568	-	922	1031
Stage 1	-	-	-	-	982	-
Stage 2	-	-	-	-	982	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	-	-	1568	-	918	1031
Mov Cap-2 Maneuver	-	-	-	-	918	-
Stage 1	-	-	-	-	982	-
Stage 2	-	-	-	-	978	-
Approach	EB	WB	NB			
HCM Control Delay, s	0	1.4	8.7			
HCM LOS			A			
Minor Lane/Major Mvmt	NBLn1	EBT	EBR	WBL	WBT	
Capacity (veh/h)	1027	-	-	1568	-	
HCM Lane V/C Ratio	0.04	-	-	0.004	-	
HCM Control Delay (s)	8.7	-	-	7.3	0	
HCM Lane LOS	A	-	-	A	A	
HCM 95th %tile Q(veh)	0.1	-	-	0	-	

Intersection																			
Int Delay, s/veh	3.3																		
Movement	SEL	SET	SER	NWL	NWT	NWR	NEL	NET	NER	SWL	SWT	SWR							
Lane Configurations	+	+	+	+	+	+	+	+	+	+	+	+							
Traffic Vol, veh/h	13	228	23	67	155	86	7	0	46	44	0	8							
Future Vol, veh/h	13	228	23	67	155	86	7	0	46	44	0	8							
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0							
Sign Control	Free	Free	Free	Free	Free	Free	Stop	Stop	Stop	Stop	Stop	Stop							
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None							
Storage Length	-	-	-	-	-	-	-	-	-	-	-	-							
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-							
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-							
Peak Hour Factor	92	92	92	92	92	92	83	83	83	83	83	83							
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2							
Mvmt Flow	14	248	25	73	168	93	8	0	55	53	0	10							
Major/Minor																			
Major1		Major2			Minor1		Minor2												
Conflicting Flow All	261	0	0	273	0	0	655	696	261	677	662	215							
Stage 1	-	-	-	-	-	-	289	289	-	361	361	-							
Stage 2	-	-	-	-	-	-	366	407	-	316	301	-							
Critical Hdwy	4.12	-	-	4.12	-	-	7.12	6.52	6.22	7.12	6.52	6.22							
Critical Hdwy Stg 1	-	-	-	-	-	-	6.12	5.52	-	6.12	5.52	-							
Critical Hdwy Stg 2	-	-	-	-	-	-	6.12	5.52	-	6.12	5.52	-							
Follow-up Hdwy	2.218	-	-	2.218	-	-	3.518	4.018	3.318	3.518	4.018	3.318							
Pot Cap-1 Maneuver	1303	-	-	1290	-	-	379	365	778	367	382	825							
Stage 1	-	-	-	-	-	-	719	673	-	657	626	-							
Stage 2	-	-	-	-	-	-	653	597	-	695	665	-							
Platoon blocked, %	-	-	-	-	-	-	-	-	-	-	-	-							
Mov Cap-1 Maneuver	1303	-	-	1290	-	-	352	336	778	320	352	825							
Mov Cap-2 Maneuver	-	-	-	-	-	-	352	336	-	320	352	-							
Stage 1	-	-	-	-	-	-	710	664	-	648	584	-							
Stage 2	-	-	-	-	-	-	602	557	-	637	656	-							
Approach																			
SE			NW			NE			SW										
HCM Control Delay, s	0.4		1.7			10.9			17.4										
HCM LOS	B						C												
Minor Lane/Major Mvmt																			
NELn1		NWL	NWT	NWR	SEL	SET	SERSWLn1												
Capacity (veh/h)	671	1290	-	-	1303	-	-	-	353	-	-	-							
HCM Lane V/C Ratio	0.095	0.056	-	-	0.011	-	-	-	0.177	-	-	-							
HCM Control Delay (s)	10.9	8	0	-	7.8	0	-	-	17.4	-	-	-							
HCM Lane LOS	B	A	A	-	A	A	-	-	C	-	-	-							
HCM 95th %tile Q(veh)	0.3	0.2	-	-	0	-	-	-	0.6	-	-	-							

Intersection						
Int Delay, s/veh	2					
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations	W	B			A	
Traffic Vol, veh/h	62	24	245	15	3	294
Future Vol, veh/h	62	24	245	15	3	294
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	-	-	-	-
Veh in Median Storage, #	0	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	83	83	92	92	92	92
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	75	29	266	16	3	320
Major/Minor	Minor1	Major1		Major2		
Conflicting Flow All	600	274	0	0	282	0
Stage 1	274	-	-	-	-	-
Stage 2	326	-	-	-	-	-
Critical Hdwy	6.42	6.22	-	-	4.12	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	-	-	2.218	-
Pot Cap-1 Maneuver	464	765	-	-	1280	-
Stage 1	772	-	-	-	-	-
Stage 2	731	-	-	-	-	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	463	765	-	-	1280	-
Mov Cap-2 Maneuver	463	-	-	-	-	-
Stage 1	772	-	-	-	-	-
Stage 2	729	-	-	-	-	-
Approach	WB	NB		SB		
HCM Control Delay, s	13.6	0		0.1		
HCM LOS	B					
Minor Lane/Major Mvmt	NBT	NBR	WBLn1	SBL	SBT	
Capacity (veh/h)	-	-	520	1280	-	
HCM Lane V/C Ratio	-	-	0.199	0.003	-	
HCM Control Delay (s)	-	-	13.6	7.8	0	
HCM Lane LOS	-	-	B	A	A	
HCM 95th %tile Q(veh)	-	-	0.7	0	-	

Intersection						
Int Delay, s/veh	5.5					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Vol, veh/h	7	11	25	1	0	61
Future Vol, veh/h	7	11	25	1	0	61
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	83	83	83	83	83	83
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	8	13	30	1	0	73
Major/Minor	Major1	Major2	Minor2			
Conflicting Flow All	31	0	-	0	60	31
Stage 1	-	-	-	-	31	-
Stage 2	-	-	-	-	29	-
Critical Hdwy	4.12	-	-	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	2.218	-	-	-	3.518	3.318
Pot Cap-1 Maneuver	1582	-	-	-	947	1043
Stage 1	-	-	-	-	992	-
Stage 2	-	-	-	-	994	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	1582	-	-	-	942	1043
Mov Cap-2 Maneuver	-	-	-	-	942	-
Stage 1	-	-	-	-	987	-
Stage 2	-	-	-	-	994	-
Approach	EB	WB	SB			
HCM Control Delay, s	2.8	0	8.7			
HCM LOS			A			
Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1	SBLn2
Capacity (veh/h)	1582	-	-	-	1043	-
HCM Lane V/C Ratio	0.005	-	-	-	0.07	-
HCM Control Delay (s)	7.3	0	-	-	8.7	-
HCM Lane LOS	A	A	-	-	A	-
HCM 95th %tile Q(veh)	0	-	-	-	0.2	-

Intersection

Int Delay, s/veh 0.6

Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Vol, veh/h	2	21	52	0	0	4
Future Vol, veh/h	2	21	52	0	0	4
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	78	78	83	83	78	78
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	3	27	63	0	0	5

Major/Minor	Major1	Major2	Minor2			
Conflicting Flow All	63	0	-	0	96	63
Stage 1	-	-	-	-	63	-
Stage 2	-	-	-	-	33	-
Critical Hdwy	4.12	-	-	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	2.218	-	-	-	3.518	3.318
Pot Cap-1 Maneuver	1540	-	-	-	903	1002
Stage 1	-	-	-	-	960	-
Stage 2	-	-	-	-	989	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	1540	-	-	-	901	1002
Mov Cap-2 Maneuver	-	-	-	-	901	-
Stage 1	-	-	-	-	958	-
Stage 2	-	-	-	-	989	-

Approach	EB	WB	SB			
HCM Control Delay, s	0.6	0	8.6			
HCM LOS			A			

Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1	
Capacity (veh/h)	1540	-	-	-	1002	
HCM Lane V/C Ratio	0.002	-	-	-	0.005	
HCM Control Delay (s)	7.3	0	-	-	8.6	
HCM Lane LOS	A	A	-	-	A	
HCM 95th %tile Q(veh)	0	-	-	-	0	

Intersection

Int Delay, s/veh 4.1

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Vol, veh/h	3	19	1	22	34	0	2	3	4	0	7	11
Future Vol, veh/h	3	19	1	22	34	0	2	3	4	0	7	11
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Free	Free	Stop	Stop	Stop	Stop	Stop	Stop
RT Channelized	-	-	None									
Storage Length	-	-	-	-	-	-	-	-	-	-	-	-
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	78	78	78	83	83	83	78	78	78	78	78	78
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	4	24	1	27	41	0	3	4	5	0	9	14

Major/Minor	Major1	Major2			Minor1			Minor2				
Conflicting Flow All	41	0	0	25	0	0	140	128	25	132	128	41
Stage 1	-	-	-	-	-	-	33	33	-	95	95	-
Stage 2	-	-	-	-	-	-	107	95	-	37	33	-
Critical Hdwy	4.12	-	-	4.12	-	-	7.12	6.52	6.22	7.12	6.52	6.22
Critical Hdwy Stg 1	-	-	-	-	-	-	6.12	5.52	-	6.12	5.52	-
Critical Hdwy Stg 2	-	-	-	-	-	-	6.12	5.52	-	6.12	5.52	-
Follow-up Hdwy	2.218	-	-	2.218	-	-	3.518	4.018	3.318	3.518	4.018	3.318
Pot Cap-1 Maneuver	1568	-	-	1589	-	-	830	763	1051	840	763	1030
Stage 1	-	-	-	-	-	-	983	868	-	912	816	-
Stage 2	-	-	-	-	-	-	898	816	-	978	868	-
Platoon blocked, %	-	-	-	-	-	-	-	-	-	-	-	-
Mov Cap-1 Maneuver	1568	-	-	1589	-	-	798	748	1051	820	748	1030
Mov Cap-2 Maneuver	-	-	-	-	-	-	798	748	-	820	748	-
Stage 1	-	-	-	-	-	-	980	865	-	909	802	-
Stage 2	-	-	-	-	-	-	861	802	-	966	865	-

Approach	EB	WB			NB			SB			
HCM Control Delay, s	1	2.9			9.2			9.1			
HCM LOS					A			A			
<hr/>											
Minor Lane/Major Mvmt	NBLn1	EBL	EBT	EBR	WBL	WBT	WBR	SBLn1	SBTn1	SBRn1	SBLn2
Capacity (veh/h)	872	1568	-	-	1589	-	-	898	-	-	-
HCM Lane V/C Ratio	0.013	0.002	-	-	0.017	-	-	0.026	-	-	-
HCM Control Delay (s)	9.2	7.3	0	-	7.3	0	-	9.1	-	-	-
HCM Lane LOS	A	A	A	-	A	A	-	A	-	-	-
HCM 95th %tile Q(veh)	0	0	-	-	0.1	-	-	0.1	-	-	-

Intersection

Int Delay, s/veh 4.3

Movement	SEL	SET	SER	NWL	NWT	NWR	NEL	NET	NER	SWL	SWT	SWR
Lane Configurations												
Traffic Vol, veh/h	6	156	7	20	223	26	10	0	70	73	0	18
Future Vol, veh/h	6	156	7	20	223	26	10	0	70	73	0	18
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Free	Free	Stop	Stop	Stop	Stop	Stop	Stop
RT Channelized	-	-	None									
Storage Length	-	-	-	-	-	-	-	-	-	-	-	-
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	87	87	87	92	92	92	83	83	83	83	83	83
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	7	179	8	22	242	28	12	0	84	88	0	22

Major/Minor	Major1	Major2			Minor1			Minor2				
Conflicting Flow All	270	0	0	187	0	0	508	511	183	539	501	256
Stage 1	-	-	-	-	-	-	197	197	-	300	300	-
Stage 2	-	-	-	-	-	-	311	314	-	239	201	-
Critical Hdwy	4.12	-	-	4.12	-	-	7.12	6.52	6.22	7.12	6.52	6.22
Critical Hdwy Stg 1	-	-	-	-	-	-	6.12	5.52	-	6.12	5.52	-
Critical Hdwy Stg 2	-	-	-	-	-	-	6.12	5.52	-	6.12	5.52	-
Follow-up Hdwy	2.218	-	-	2.218	-	-	3.518	4.018	3.318	3.518	4.018	3.318
Pot Cap-1 Maneuver	1293	-	-	1387	-	-	475	466	859	453	472	783
Stage 1	-	-	-	-	-	-	805	738	-	709	666	-
Stage 2	-	-	-	-	-	-	699	656	-	764	735	-
Platoon blocked, %	-	-	-	-	-	-	-	-	-	-	-	-
Mov Cap-1 Maneuver	1293	-	-	1387	-	-	453	454	859	401	460	783
Mov Cap-2 Maneuver	-	-	-	-	-	-	453	454	-	401	460	-
Stage 1	-	-	-	-	-	-	800	734	-	705	653	-
Stage 2	-	-	-	-	-	-	667	644	-	685	731	-

Approach	SE	NW			NE			SW			
HCM Control Delay, s	0.3	0.6			10.3			15.7			
HCM LOS					B			C			
<hr/>											
Minor Lane/Major Mvmt	NELn1	NWL	NWT	NWR	SEL	SET	SERSWLn1				
Capacity (veh/h)	772	1387	-	-	1293	-	-	444			
HCM Lane V/C Ratio	0.125	0.016	-	-	0.005	-	-	0.247			
HCM Control Delay (s)	10.3	7.6	0	-	7.8	0	-	15.7			
HCM Lane LOS	B	A	A	-	A	A	-	C			
HCM 95th %tile Q(veh)	0.4	0	-	-	0	-	-	1			

Intersection						
Int Delay, s/veh	1					
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations	W	B		A		
Traffic Vol, veh/h	23	11	304	51	20	303
Future Vol, veh/h	23	11	304	51	20	303
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	-	-	-	-
Veh in Median Storage, #	0	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	78	78	92	92	92	92
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	29	14	330	55	22	329
Major/Minor	Minor1	Major1	Major2			
Conflicting Flow All	731	358	0	0	385	0
Stage 1	358	-	-	-	-	-
Stage 2	373	-	-	-	-	-
Critical Hdwy	6.42	6.22	-	-	4.12	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	-	-	2.218	-
Pot Cap-1 Maneuver	389	686	-	-	1173	-
Stage 1	707	-	-	-	-	-
Stage 2	696	-	-	-	-	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	380	686	-	-	1173	-
Mov Cap-2 Maneuver	380	-	-	-	-	-
Stage 1	707	-	-	-	-	-
Stage 2	680	-	-	-	-	-
Approach	WB	NB	SB			
HCM Control Delay, s	14	0	0.5			
HCM LOS	B					
Minor Lane/Major Mvmt	NBT	NBR	WBLn1	SBL	SBT	
Capacity (veh/h)	-	-	444	1173	-	
HCM Lane V/C Ratio	-	-	0.098	0.019	-	
HCM Control Delay (s)	-	-	14	8.1	0	
HCM Lane LOS	-	-	B	A	A	
HCM 95th %tile Q(veh)	-	-	0.3	0.1	-	

Intersection						
Int Delay, s/veh	3.3					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Vol, veh/h	14	57	5	0	0	29
Future Vol, veh/h	14	57	5	0	0	29
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	83	83	83	83	83	83
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	17	69	6	0	0	35
Major/Minor	Major1	Major2	Minor2			
Conflicting Flow All	6	0	-	0	109	6
Stage 1	-	-	-	-	6	-
Stage 2	-	-	-	-	103	-
Critical Hdwy	4.12	-	-	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	2.218	-	-	-	3.518	3.318
Pot Cap-1 Maneuver	1615	-	-	-	888	1077
Stage 1	-	-	-	-	1017	-
Stage 2	-	-	-	-	921	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	1615	-	-	-	878	1077
Mov Cap-2 Maneuver	-	-	-	-	878	-
Stage 1	-	-	-	-	1006	-
Stage 2	-	-	-	-	921	-
Approach	EB	WB	SB			
HCM Control Delay, s	1.4	0	8.5			
HCM LOS			A			
Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1	SBLn2
Capacity (veh/h)	1615	-	-	-	1077	-
HCM Lane V/C Ratio	0.01	-	-	-	0.032	-
HCM Control Delay (s)	7.3	0	-	-	8.5	-
HCM Lane LOS	A	A	-	-	A	-
HCM 95th %tile Q(veh)	0	-	-	-	0.1	-

Intersection

Int Delay, s/veh 0.8

Movement EBL EBT WBT WBR SBL SBR

Lane Configurations						
Traffic Vol, veh/h	7	61	27	0	0	3
Future Vol, veh/h	7	61	27	0	0	3
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	83	83	78	78	78	78
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	8	73	35	0	0	4

Major/Minor Major1 Major2 Minor2

Conflicting Flow All	35	0	-	0	124	35
Stage 1	-	-	-	-	35	-
Stage 2	-	-	-	-	89	-
Critical Hdwy	4.12	-	-	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	2.218	-	-	-	3.518	3.318
Pot Cap-1 Maneuver	1576	-	-	-	871	1038
Stage 1	-	-	-	-	987	-
Stage 2	-	-	-	-	934	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	1576	-	-	-	867	1038
Mov Cap-2 Maneuver	-	-	-	-	867	-
Stage 1	-	-	-	-	982	-
Stage 2	-	-	-	-	934	-

Approach EB WB SB

HCM Control Delay, s	0.8	0	8.5
HCM LOS		A	

Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1
Capacity (veh/h)	1576	-	-	-	1038
HCM Lane V/C Ratio	0.005	-	-	-	0.004
HCM Control Delay (s)	7.3	0	-	-	8.5
HCM Lane LOS	A	A	-	-	A
HCM 95th %tile Q(veh)	0	-	-	-	0

Intersection

Int Delay, s/veh 4.7

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Vol, veh/h	11	34	2	6	24	0	1	8	34	0	4	8
Future Vol, veh/h	11	34	2	6	24	0	1	8	34	0	4	8
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Free	Free	Stop	Stop	Stop	Stop	Stop	Stop
RT Channelized	-	-	None									
Storage Length	-	-	-	-	-	-	-	-	-	-	-	-
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	78	78	78	78	78	78	78	78	78	78	78	78
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	14	44	3	8	31	0	1	10	44	0	5	10

Major/Minor	Major1	Major2		Minor1		Minor2						
Conflicting Flow All	31	0	0	47	0	0	129	121	46	148	122	31
Stage 1	-	-	-	-	-	-	74	74	-	47	47	-
Stage 2	-	-	-	-	-	-	55	47	-	101	75	-
Critical Hdwy	4.12	-	-	4.12	-	-	7.12	6.52	6.22	7.12	6.52	6.22
Critical Hdwy Stg 1	-	-	-	-	-	-	6.12	5.52	-	6.12	5.52	-
Critical Hdwy Stg 2	-	-	-	-	-	-	6.12	5.52	-	6.12	5.52	-
Follow-up Hdwy	2.218	-	-	2.218	-	-	3.518	4.018	3.318	3.518	4.018	3.318
Pot Cap-1 Maneuver	1582	-	-	1560	-	-	844	769	1023	820	768	1043
Stage 1	-	-	-	-	-	-	935	833	-	967	856	-
Stage 2	-	-	-	-	-	-	957	856	-	905	833	-
Platoon blocked, %	-	-	-	-	-	-	-	-	-	-	-	-
Mov Cap-1 Maneuver	1582	-	-	1560	-	-	823	758	1023	768	757	1043
Mov Cap-2 Maneuver	-	-	-	-	-	-	823	758	-	768	757	-
Stage 1	-	-	-	-	-	-	927	826	-	958	852	-
Stage 2	-	-	-	-	-	-	937	852	-	848	826	-

Approach	EB	WB		NB		SB						
HCM Control Delay, s	1.7	1.5		9		9						
HCM LOS				A		A						
<hr/>												
Minor Lane/Major Mvmt	NBLn1	EBL	EBT	EBR	WBL	WBT	WBR	SBLn1				
Capacity (veh/h)	955	1582	-	-	1560	-	-	926				
HCM Lane V/C Ratio	0.058	0.009	-	-	0.005	-	-	0.017				
HCM Control Delay (s)	9	7.3	0	-	7.3	0	-	9				
HCM Lane LOS	A	A	A	-	A	A	-	A				
HCM 95th %tile Q(veh)	0.2	0	-	-	0	-	-	0.1				

Intersection																			
Int Delay, s/veh	3.6																		
Movement	SEL	SET	SER	NWL	NWT	NWR	NEL	NET	NER	SWL	SWT	SWR							
Lane Configurations	+	+	+	+	+	+	+	+	+	+	+	+							
Traffic Vol, veh/h	21	228	23	67	155	93	7	0	46	49	0	13							
Future Vol, veh/h	21	228	23	67	155	93	7	0	46	49	0	13							
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0							
Sign Control	Free	Free	Free	Free	Free	Free	Stop	Stop	Stop	Stop	Stop	Stop							
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None							
Storage Length	-	-	-	-	-	-	-	-	-	-	-	-							
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-							
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-							
Peak Hour Factor	92	92	92	92	92	92	83	83	83	83	83	83							
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2							
Mvmt Flow	23	248	25	73	168	101	8	0	55	59	0	16							
Major/Minor																			
Major1		Major2			Minor1			Minor2											
Conflicting Flow All	269	0	0	273	0	0	680	722	261	699	684	219							
Stage 1	-	-	-	-	-	-	307	307	-	365	365	-							
Stage 2	-	-	-	-	-	-	373	415	-	334	319	-							
Critical Hdwy	4.12	-	-	4.12	-	-	7.12	6.52	6.22	7.12	6.52	6.22							
Critical Hdwy Stg 1	-	-	-	-	-	-	6.12	5.52	-	6.12	5.52	-							
Critical Hdwy Stg 2	-	-	-	-	-	-	6.12	5.52	-	6.12	5.52	-							
Follow-up Hdwy	2.218	-	-	2.218	-	-	3.518	4.018	3.318	3.518	4.018	3.318							
Pot Cap-1 Maneuver	1295	-	-	1290	-	-	365	353	778	354	371	821							
Stage 1	-	-	-	-	-	-	703	661	-	654	623	-							
Stage 2	-	-	-	-	-	-	648	592	-	680	653	-							
Platoon blocked, %	-	-	-	-	-	-	-	-	-	-	-	-							
Mov Cap-1 Maneuver	1295	-	-	1290	-	-	334	322	778	307	339	821							
Mov Cap-2 Maneuver	-	-	-	-	-	-	334	322	-	307	339	-							
Stage 1	-	-	-	-	-	-	688	647	-	640	581	-							
Stage 2	-	-	-	-	-	-	593	552	-	618	639	-							
Approach																			
SE			NW			NE			SW										
HCM Control Delay, s	0.6		1.7			11			17.9										
HCM LOS	B						C												
Minor Lane/Major Mvmt																			
Capacity (veh/h)	662	1290	-	-	1295	-	-	-	353	-	-	-							
HCM Lane V/C Ratio	0.096	0.056	-	-	0.018	-	-	-	0.212	-	-	-							
HCM Control Delay (s)	11	8	0	-	7.8	0	-	-	17.9	-	-	-							
HCM Lane LOS	B	A	A	-	A	A	-	-	C	-	-	-							
HCM 95th %tile Q(veh)	0.3	0.2	-	-	0.1	-	-	-	0.8	-	-	-							