CONSTRUCTION DOCUMENTS FOR

BLACK FOREST OFFICE

N1/2 NE1/4 SE1/4 SE1/4 OF SECTION 07, TOWNSHIP 12 SOUTH, RANGE 65 WEST OF THE 6TH P.M., EL PASO COUNTY, COLORADO

2N CIVIL GENERAL NOTES:

1. THE OWNER/DEVELOPER AND/OR THEIR ASSIGNS IS HEREBY NOTIFIED THAT IT IS TYPICAL AND LIKELY THAT SOME MOVEMENT OF THE SURFACE GRADES WILL OCCUR OVER TIME DUE TO VARIOUS FACTORS THAT ARE NOT IN CONTROL OF THE DESIGNERS. THUS, A ROUTINE AND DILIGENT MAINTENANCE PROGRAM IS REQUIRED TO MAINTAIN THE PROPER GRADING AND DRAINAGE THROUGHOUT THE PROJECT.
2. PROPOSED CONTOURS AND SPOT ELEVATIONS AS SHOWN HEREIN ARE DEFINED AS FINISHED ELEVATION AFTER PAVING, LANDSCAPING, ETC. CONTRACTOR SHALL COORDINATE WITH GEOTECH FOR PAVEMENT THICKNESS AND LANDSCAPE FOR THICKNESS OF TOPSOIL AND SOD.
3. CONTRACTOR SHALL REVIEW THE GEOTECHNICAL REPORT FOR THIS PROJECT FOR PAVEMENT DESIGN AND RECOMMENDATIONS REGARDING EXCAVATION, COMPACTION, EMBANKMENT, AND TOPSOIL REMOVAL AND REPLACEMENT. FINAL PAVEMENT DESIGN TO BE DETERMINED BY THE GEOTECHNICAL ENGINEER. CONTRACTOR TO COORDINATE THIS WORK. THE CONSTRUCTION METHODS FOR EXCAVATION/EMBANKMENTS, COMPACTION, AND SUBGRADE PREPARATION SHALL BE IN STRICT CONFORMANCE WITH THE GEOTECHNICAL ENGINEER'S RECOMMENDATIONS. ENGINEER SHALL BE NOTIFIED IMMEDIATELY OF DISCREPANCIES BETWEEN THE GEOTECHNICAL REPORT RECOMMENDATIONS AND REQUIREMENTS OF THESE CONSTRUCTION DOCUMENTS AND SPECIFICATIONS.
4. EXISTING GRADES AND SPOT ELEVATIONS SHOWN ON THIS DRAWING HAVE BEEN PLOTTED FROM BEST AVAILABLE INFORMATION AND ARE SHOWN TO THE EXTENT KNOWN. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO FIELD VERIFY EXISTING GRADE CONDITIONS AT THE LIMITS OF CONSTRUCTION AND AT LOCATIONS THAT INTERFACE WITH EXISTING OR PROPOSED BUILDINGS AND NOTIFY THE CIVIL ENGINEER OF ANY DISCREPANCIES THAT CONTRADICT THE CIVIL ENGINEER'S INTENT FOR DRAINAGE PATTERNS, MAXIMUM AND MINIMUM SLOPES, AND PROPOSED ELEVATIONS AS SHOWN ON THE PLAN. THE ENGINEER WILL NOT BE LIABLE FOR ANY COSTS ASSOCIATED WITH CHANGES TO THE DESIGN WITHOUT PROPER NOTIFICATION.
5. CONTRACTOR LAYDOWN / MATERIAL AREA, CONCRETE WASHOUT AREA AND STOCKPILE AREA ARE SHOWN FOR INFORMATION ONLY. FINAL LOCATIONS OF THESE AREAS SHALL BE COORDINATED BETWEEN THE CONTRACTOR AND OWNER'S REPRESENTATIVE. STORM WATER MANAGEMENT IS STRICTLY THE CONTRACTOR'S RESPONSIBILITY AND THE CONTRACTOR MUST ADHERE TO LOCAL AND STATE JURISDICTIONAL CRITERIA.
6. SLOPE OF INLET FLOWLINE OR GRATE TO MATCH STREET GRADE UNLESS INLET IS AT A SUMP LOCATION. ALL DIMENSIONS, CURVE DATA AND LINE DATA ARE AT FLOWLINE UNLESS OTHERWISE NOTED.
7. NOTICE TO BIDDERS - UNLESS APPROVAL BLOCKS ARE SIGNED AND THE PLANS ARE STAMPED BY A PROFESSIONAL ENGINEER., THESE DOCUMENTS ARE PENDING JURISDICTIONAL APPROVAL AND SUBJECT TO CHANGE.
8. SAW CUTTING OF EXISTING PAVEMENT AND CONCRETE, WHERE REQUIRED, SHALL BE DONE TO A NEAT WORK LINE WITH A CUTTING WHEEL ATTACHED TO A BLADE, OR OTHER METHOD AS APPROVED BY THE ENGINEER.
9. 2N CIVIL, LLC ASSUMES NO RESPONSIBILITY FOR UTILITY LOCATIONS. THE UTILITIES SHOWN ON THESE DRAWINGS HAVE BEEN PLOTTED FROM THE BEST AVAILABLE INFORMATION. IT IS, HOWEVER, THE CONTRACTOR'S RESPONSIBILITY TO FIELD VERIFY THE LOCATION OF ALL UTILITIES PRIOR TO THE COMMENCEMENT OF ANY CONSTRUCTION. NOTIFY ENGINEER OF ANY DISCREPANCIES PRIOR TO CONSTRUCTION.
10. THE UTILITIES SHOWN ON THESE PLANS HAVE BEEN PLOTTED FROM THE BEST AVAILABLE INFORMATION. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY UTILITY LOCATIONS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO PROTECT EXISTING UTILITIES FROM DAMAGE THROUGHOUT THE CONSTRUCTION OF THIS PROJECT. THE CONTRACTOR SHALL CALL THE UTILITY NOTIFICATION CENTER OF COLORADO FOR UTILITY LOCATIONS 2 WORKING DAYS PRIOR TO COMMENCING CONSTRUCTION.
11. EXISTING SITE FEATURES TO BE DEMOLISHED (INCLUDING BUT NOT LIMITED TO BUILDINGS, CONCRETE SLABS, FENCING, TREES) HAVE BEEN OMITTED FROM THIS CONSTRUCTION DRAWING SET FOR CLARITY.
12. ALL AREAS DISTURBED BEYOND CONSTRUCTION LIMITS SHALL BE RESEEDED/MULCHED AT THE CONTRACTOR'S EXPENSE.

VICINITY MAP

SHEET INDEX

1	COVER SHEET
2	SITE AND UTILITY PLAN
3	GRADING PLAN
4	ESCD COVER SHEET
5	ESCD - INITIAL PHASE
6	ESCD - INTERIM PHASE
7	ESCD - FINAL PHASE
8-10	EROSION CONTROL DETAILS
11-12	POND DETAILS

PROJECT TEAM

OWNER

BLACK FOREST, LLC
8655 TABLE BUTTE ROAD
COLORADO SPRINGS, CO 80908

CIVIL ENGINEER

2N CIVIL, LLC
6 INVERNESS COURT EAST, SUITE 125
ENGLEWOOD, CO 80112
MR. TODD WEST
303.925.0544

ARCHITECT

PWN ARCHITECTS & PLANNERS
4949 S SYRACUSE ST #320
DENVER, CO 80237
303.649.9880

STRUCTURAL

THE LEFFLER GROUP
165 SOUTH UNION BLVD, SUITE 360
LAKEWOOD, CO 80228
720-890-4095

MECHANICAL, ELECTRICAL, PLUMBING

COLORADO COMFORT CONSULTING ENGINEERINGS, INC.
7891 LEWIS COURT
ARVADA, CO 80005
PH: 303-956-8811
EMAIL: DesEng1@Comcast.net

CAUTION: NOTICE TO CONTRACTOR

THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES AND, WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CALL THE LOCAL UTILITY LOCATION CENTER AT LEAST 48 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATIONS OF THE UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATE ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THE PLANS.

811 Know what's below. Call before you dig.

J:\Projects\19\19015\dwg\Site Plan\CD - Cover Sheet.dwg 1/18/2021

2N CIVIL
303.925.0544
www.2ncivil.com

PREPARED FOR:
BLACK FOREST, LLC
12740 BLACK FOREST ROAD
COLORADO SPRINGS, CO 80908

Cover Sheet
CONSTRUCTION DOCUMENTS
BLACK FOREST OFFICE
COLORADO SPRINGS, COLORADO

REVISIONS:
1. EL PASO CNTY COMMENTS 1-7-21 — BY: TEW — DATE: 1-19-21
2.
3.
4.

PROJECT NUMBER: 19015
ISSUED DATE: 12-03-2020
DESIGNED BY: TEW
REVIEWED BY: RCE

Cover Sheet

SCALE: 1" = 30'

MATERIAL LEGEND

- EXISTING ASPHALT
- PROPOSED CONCRETE
- PROPOSED ASPHALT
- PROPOSED GRAVEL
- PROPOSED BUILDING
- PROPOSED LANDSCAPE ELEMENTS

LEGEND

- PROPERTY BOUNDARY
- EXISTING EASEMENT
- EXISTING SIGN
- EXISTING CURB & GUTTER
- EXISTING HYDRANT
- BUILDING SETBACK
- PROPOSED EASEMENT
- PROPOSED CURB AND GUTTER (CATCH)
- PROPOSED CURB AND GUTTER (SPILL)
- PROPOSED FENCE
- PROPOSED SIGN
- PROPOSED FIRE HYDRANT
- SURVEY CONTROL POINT
- FOUND PROPERTY CORNER

CAUTION: NOTICE TO CONTRACTOR

THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES AND, WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CALL THE LOCAL UTILITY LOCATION CENTER AT LEAST 48 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATIONS OF THE UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATE ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THE PLANS.

811 Know what's below. Call before you dig.

BENCHMARK

SURVEY CONTROL POINTS AS SHOWN HEREON. ALL ELEVATIONS ARE BASED UPON NAVD88 VERTICAL DATUM.

DETAILED DRAINAGE CONSTRUCTION PLANS AND SPECIFICATIONS ENGINEER'S STATEMENT:

THESE DETAILED PLANS AND SPECIFICATIONS WERE PREPARED UNDER MY DIRECTION AND SUPERVISION. SAID DETAILED PLANS AND SPECIFICATIONS HAVE BEEN PREPARED ACCORDING TO THE CRITERIA ESTABLISHED BY THE CITY/COUNTY FOR DETAILED DRAINAGE PLANS AND SPECIFIC~TIONS, AND SAID DETAILED PLANS AND SPECIFICATIONS ARE IN CONFORMITY WITH THE MASTER PLAN OF THE DRAINAGE BASIN. SAID DETAILED DRAINAGE PLANS AND SPECIFICATIONS MEET THE PURPOSES FOR WHICH THE PARTICULAR DRAINAGE FACILITY(S) IS DESIGNED. I ACCEPT RESPONSIBILITY FOR ANY LIABILITY CAUSED BY ANY NEGLIGENT ACTS, ERRORS OR OMISSIONS ON MY PART IN PREPARATION OF THE DETAILED DRAINAGE PLANS AND SPECIFICATIONS.

EL PASO COUNTY PLAN REVIEW IS PROVIDED ONLY FOR GENERAL CONFORMANCE WITH COUNTY DESIGN CRITERIA. EL PASO COUNTY IS NOT RESPONSIBLE FOR THE ACCURACY AND ADEQUACY OF THE DESIGN, DIMENSIONS, AND/OR ELEVATIONS WHICH SHALL BE CONFIRMED AT THE JOB SITE. EL PASO COUNTY THROUGH THE APPROVAL OF THIS DOCUMENT ASSUMES NO RESPONSIBILITY FOR COMPLETENESS AND/OR ACCURACY OF THIS DOCUMENT.

2N CIVIL
303.925.0544
www.2ncivil.com

PREPARED FOR:
BLACK FOREST, LLC
12740 BLACK FOREST ROAD
COLORADO SPRINGS, CO 80908

Site and Utility Plan
CONSTRUCTION DOCUMENTS
BLACK FOREST OFFICE
COLORADO SPRINGS, COLORADO

REVISIONS:	BY:	DATE:
1. EL PASO CNTY COMMENTS 1-7-21	TEW	1-19-21
2.		
3.		
4.		

PROJECT NUMBER:	19015
ISSUED DATE:	12-03-2020
DESIGNED BY:	TEW
REVIEWED BY:	RCE

Site and Utility Plan

J:\Projects\19\19015\dwg\Site Plan\Utility Plan.dwg 1/18/2021

MATERIAL LEGEND

- EXISTING ASPHALT
- PROPOSED CONCRETE
- PROPOSED ASPHALT
- PROPOSED GRAVEL
- PROPOSED BUILDING
- PROPOSED LANDSCAPE ELEMENTS

LEGEND

- PROPERTY BOUNDARY
- EXISTING EASEMENT
- EXISTING SIGN
- EXISTING CURB & GUTTER
- EXISTING HYDRANT
- BUILDING SETBACK
- PROPOSED EASEMENT
- PROPOSED CURB AND GUTTER (CATCH)
- PROPOSED CURB AND GUTTER (SPILL)
- PROPOSED FENCE
- PROPOSED SIGN
- PROPOSED FIRE HYDRANT
- SURVEY CONTROL POINT
- FOUND PROPERTY CORNER

CAUTION: NOTICE TO CONTRACTOR

THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES AND, WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CALL THE LOCAL UTILITY LOCATION CENTER AT LEAST 48 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATIONS OF THE UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATE ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THE PLANS.

811 Know what's below. Call before you dig.

BENCHMARK

SURVEY CONTROL POINTS AS SHOWN HEREON. ALL ELEVATIONS ARE BASED UPON NAVD88 VERTICAL DATUM.

DETAILED DRAINAGE CONSTRUCTION PLANS AND SPECIFICATIONS ENGINEER'S STATEMENT:

THESE DETAILED PLANS AND SPECIFICATIONS WERE PREPARED UNDER MY DIRECTION AND SUPERVISION. SAID DETAILED PLANS AND SPECIFICATIONS HAVE BEEN PREPARED ACCORDING TO THE CRITERIA ESTABLISHED BY THE CITY/COUNTY FOR DETAILED DRAINAGE PLANS AND SPECIFIC-TIONS, AND SAID DETAILED PLANS AND SPECIFICATIONS ARE IN CONFORMITY WITH THE MASTER PLAN OF THE DRAINAGE BASIN. SAID DETAILED DRAINAGE PLANS AND SPECIFICATIONS MEET THE PURPOSES FOR WHICH THE PARTICULAR DRAINAGE FACILITY(S) IS DESIGNED. I ACCEPT RESPONSIBILITY FOR ANY LIABILITY CAUSED BY ANY NEGLIGENT ACTS, ERRORS OR OMISSIONS ON MY PART IN PREPARATION OF THE DETAILED DRAINAGE PLANS AND SPECIFICATIONS.

EL PASO COUNTY PLAN REVIEW IS PROVIDED ONLY FOR GENERAL CONFORMANCE WITH COUNTY DESIGN CRITERIA. EL PASO COUNTY IS NOT RESPONSIBLE FOR THE ACCURACY AND ADEQUACY OF THE DESIGN, DIMENSIONS, AND/OR ELEVATIONS WHICH SHALL BE CONFIRMED AT THE JOB SITE. EL PASO COUNTY THROUGH THE APPROVAL OF THIS DOCUMENT ASSUMES NO RESPONSIBILITY FOR COMPLETENESS AND/OR ACCURACY OF THIS DOCUMENT.

2N CIVIL
303.925.0544
www.2ncivil.com

PREPARED FOR:
BLACK FOREST, LLC
12740 BLACK FOREST ROAD
COLORADO SPRINGS, CO 80908

Grading and Drainage Plan
CONSTRUCTION DOCUMENTS
BLACK FOREST OFFICE
COLORADO SPRINGS, COLORADO

REVISIONS:	BY:	DATE:
1. EL PASO CNTY COMMENTS 1-7-21	TEW	1-19-21
2.		
3.		
4.		

PROJECT NUMBER:	19015
ISSUED DATE:	12-03-2020
DESIGNED BY:	TEW
REVIEWED BY:	RCE

Grading and Drainage Plan

J:\Projects\19\19015\dwg\Site Plan\Grading and Drainage Plan.dwg 1/18/2021

GRADING, EROSION, AND SEDIMENT CONTROL PLANS FOR

BLACK FOREST OFFICE

N1/2 NE1/4 SE1/4 SE1/4 OF SECTION 07, TOWNSHIP 12 SOUTH, RANGE 65 WEST OF THE 6TH P.M., EL PASO COUNTY, COLORADO

PROJECT TEAM

OWNER

BLACK FOREST, LLC
8655 TABLE BUTTE ROAD
COLORADO SPRINGS, CO 80908

STORMWATER MANAGER

CHRIS RICHARDSON
CMG CORPORATION
6615 VINCENT DR.
COLORADO SPRINGS, CO 80918

CIVIL ENGINEER

2N CIVIL, LLC
6 INVERNESS COURT EAST, SUITE 125
ENGLEWOOD, CO 80112
MR. TODD WEST
303.925.0544

LANDSCAPE ARCHITECT

PWN ARCHITECTS & PLANNERS
4949 S SYRACUSE ST #320
DENVER, CO 80237
303.649.9880

VICINITY MAP

BMP	PROJECT STAGE: INITIAL At outset of construction, prior to any land disturbance activities	INTERIM During clearing and grubbing, earthwork operations	FINAL During last steps of construction process for long-term stabilization
Silt Fence		MAINTAINED	TO BE REMOVED
Vehicle Tracking Control		MAINTAINED	TO BE REMOVED
Concrete Washout Area		MAINTAINED	TO BE REMOVED
Stabilized Staging Area		MAINTAINED	TO BE REMOVED
Sediment Control Log			TO BE REMOVED
Inlet Protect			TO BE REMOVED
Culvert Inlet Protection		MAINTAINED	TO BE REMOVED
Sediment Basin		MAINTAINED	TO BE REMOVED
Diversion Ditch		MAINTAINED	TO BE REMOVED
Erosion Control Blanket			TO REMAIN
Seeding and Mulching			TO REMAIN
Permanent Landscaping			

STANDARD NOTES FOR EL PASO COUNTY GRADING AND EROSION CONTROL PLANS

1. Stormwater discharges from construction sites shall not cause or threaten to cause pollution, contamination, or degradation of State Waters. All work and earth disturbance shall be done in a manner that minimizes pollution of any on-site or off-site waters, including wetlands.

2. Notwithstanding anything depicted in these plans in words or graphic representation, all design and construction related to roads, storm drainage and erosion control shall conform to the standards and requirements of the most recent version of the relevant adopted El Paso County standards, including the Land Development Code, the Engineering Criteria Manual, the Drainage Criteria Manual, and the Drainage Criteria Manual Volume 2. Any deviations from regulations and standards must be requested, and approved, in writing.

3. A separate Stormwater Management Plan (SMWP) for this project shall be completed and an Erosion and Stormwater Quality Control Permit (ESQCP) issued prior to commencing construction. Management of the SWMP during construction is the responsibility of the designated Qualified Stormwater Manager or Certified Erosion Control Inspector. The SWMP shall be located on site at all times during construction and shall be kept up to date with work progress and changes in the field.

4. Once the ESQCP is approved and a "Notice to Proceed" has been issued, the contractor may install the initial stage erosion and sediment control measures as indicated on the approved GEC. A Preconstruction Meeting between the contractor, engineer, and El Paso County will be held prior to any construction. It is the responsibility of the applicant to coordinate the meeting time and place with County staff.

5. Control measures must be installed prior to commencement of activities that could contribute pollutants to stormwater. control measures for all slopes, channels, ditches, and disturbed land areas shall be installed immediately upon completion of the disturbance.

6. xAll temporary sediment and erosion control measures shall be maintained and remain in effective operating condition until permanent soil erosion control measures are implemented and final stabilization is established. All persons engaged in land disturbance activities shall assess the adequacy of control measures at the site and identify if changes to those control measures are needed to ensure the continued effective performance of the control measures. All changes to temporary sediment and erosion control measures must be incorporated into the Stormwater Management Plan.

7. Temporary stabilization shall be implemented on disturbed areas and stockpiles where ground disturbing construction activity has permanently ceased or temporarily ceased for longer than 14 days.

8. Final stabilization must be implemented at all applicable construction sites. Final stabilization is achieved when all ground disturbing activities are complete and all disturbed areas either have a uniform vegetative cover with individual plant density of 70 percent of pre-disturbance levels established or equivalent permanent alternative stabilization method is implemented. All temporary sediment and erosion control measures shall be removed upon final stabilization and before permit closure.

9. All permanent stormwater management facilities shall be installed as designed in the approved plans. Any proposed changes that effect the design or function of permanent stormwater management structures must be approved by the ECM Administrator prior to implementation.

SHEET INDEX

4	COVER SHEET
5	ESCD - INITIAL PHASE
6	ESCD - INTERIM PHASE
7	ESCD - FINAL PHASE
8-10	EROSION CONTROL DETAILS

FLOODPLAIN STATEMENT:

BASED ON THE FEMA MAP NO. 08041C0315G WITH AN EFFECTIVE DATE OF 12/07/18 (INCLUDED IN THE APPENDIX) THE SITE IS LOCATED WITHIN ZONE X, AREAS OF MINIMAL FLOOD HAZARD. NO PORTION OF THE SITE IS LOCATED WITHIN THE 100 YEAR FLOODPLAIN.

EROSION CONTROL PHASING NOTES:

1. INITIAL STAGE BMPS SHALL BE INSTALLED AT THE OUTSET OF CONSTRUCTION, PRIOR TO ANY OTHER LAND-DISTURBING ACTIVITIES. INITIAL CONTROLS ARE TO BE PLACED ON EXISTING GRADES.
2. CONTRACTOR TO ESTABLISH PERIMETER CONTROLS (IP, SF), VTC AND SSA PRIOR TO COMMENCING CONSTRUCTION.
3. INTERIM STAGE BMPS SHALL BE BASED ON PROPOSED GRADES AND DRAINAGE FEATURES AND ARE INSTALLED AFTER INITIAL SITE CONSTRUCTION. FOR SOME BMPS SUCH AS INLET PROTECTION, INTERIM CONTROLS ARE INSTALLED AFTER THE CONSTRUCTION OF SITE INFRASTRUCTURE.
4. FINAL STAGE BMPS SHALL BE INSTALLED AS ONE OF THE LAST STEPS IN THE CONSTRUCTION ACTIVITY, SUCH AS FINAL SEEDING AND MULCHING.
5. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO PHASE THE FINAL BMPS AS THE CONSTRUCTION PROGRESSES.

SOIL TYPE NOTE:

1. THE HYDROLOGIC SOILS GROUP (HSG) FOR THE AREA SHOWN WITHIN THE LIMIT OF CONSTRUCTION IS TYPE B. TYPE B SOILS EXHIBIT A MODERATE INFILTRATION RATE WHEN THOROUGHLY WET.

EXISTING VEGETATION:

1. THE SITE CONSISTS OF THE FOLLOWING GROUND COVER AND PERCENTAGES. 40% - DISTURBED CENTRAL SHORTGRASS PRAIRIE, 30% - REFORESTATION AREA, 25% - DISTURBED SOIL, AND 5% - EXISTING ASPHALT.

ADDITIONAL NOTES:

1. NO CONCRETE BATCH PLANTS ARE PROPOSED FOR THIS PROJECT.
2. NO STREAMS OR WETLANDS ARE WITHIN 50 FEET OF THE PROJECT AREA.

ANTICIPATED TIMING/PHASING SCHEDULE:

Project start date is planned for: Spring 2021
Initial phase – Spring 2021 (2 day duration)
Interim phase – June 2021 (9 month duration)
Final phase – Spring 2022

EARTHWORK NOTE:

1. EARTHWORK QUANTITIES SHOWN ARE RAW NUMBERS AND HAVE NOT BEEN ADJUSTED TO ACCOUNT FOR SHRINK, SWELL, COMPACTION, UTILITY SPOILS, TOPSOIL, PLAY PIT EXCAVATION, ETC. THE VALUES REFLECT FINISH GRADE AND DO NOT ACCOUNT FOR ASPHALT/CONCRETE PAVING, PLAYPIT MATERIAL, CRUSHER FINES, SAND, SOD, ETC. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL EARTHWORK VALUES.

CUT REQUIRED: 7,485 CY

FILL REQUIRED: 2,885 CY

NET CUT REQUIRED: 4,600 CY

ENGINEER'S STATEMENT

These detailed plans and specifications were prepared under my direction and supervision. Said plans and specifications have been prepared according to the criteria established by the County for detailed roadway, drainage, grading and erosion control plans and specifications, and said plans and specifications are in conformity with applicable master drainage plans and master transportation plans. Said plans and specifications meet the purposes for which the particular roadway and drainage facilities are designed and are correct to the best of my knowledge and belief. I accept responsibility for any liability caused by any negligent acts, errors or omissions on my part in preparation of these detailed plans and specifications.

Engineer of Record Signature Date

OWNER'S STATEMENT

I, the owner/developer have read and will comply with the requirements of the grading and erosion control plan and all of the requirements specified in these detailed plans and specifications.

Black Forest, LLC
8655 Table Butte Road
Colorado Springs, CO 80905 Date

EL PASO COUNTY

County plan review is provided only for general conformance with County Design Criteria. The County is not responsible for the accuracy and adequacy of the design, dimensions, and/ or elevations which shall be confirmed at the job site. The County through the approval of this document assumes no responsibility for completeness and/ or accuracy of this document.

Filed in accordance with the requirements of the El Paso County Land Development Code, Drainage Criteria Manual, Volumes 1 and 2, and Engineering Criteria Manual as amended.

In accordance with ECM Section 1.12, these construction documents will be valid for construction for a period of 2 years from the date signed by the El Paso County Engineer. If construction has not started within those 2 years, the plans will need to be resubmitted for approval, including payment of review fees at the Planning and Community Development Directors discretion.

Jennifer Irvine, P.E.
County Engineer / ECM Administrator Date

CAUTION: NOTICE TO CONTRACTOR

THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES AND, WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CALL THE LOCAL UTILITY LOCATION CENTER AT LEAST 48 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATIONS OF THE UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATE ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THE PLANS.

811 Know what's below. Call before you dig.

J:\Projects\19015\dwg\Site Plan\EC Plan - Cover Sheet.dwg 1/18/2021

2N CIVIL
303.925.0544
www.2ncivil.com

PREPARED FOR:
BLACK FOREST, LLC
12740 BLACK FOREST ROAD
COLORADO SPRINGS, CO 80908

ESCD Cover Sheet
CONSTRUCTION DOCUMENTS
BLACK FOREST OFFICE
COLORADO SPRINGS, COLORADO

REVISIONS:
1. EL PASO CNTY COMMENTS 1-7-21 — BY: TEW — DATE: 1-19-21
2.
3.
4.

PROJECT NUMBER: 19015
ISSUED DATE: 12-03-2020
DESIGNED BY: TEW
REVIEWED BY: RCE

ESCD Cover Sheet

MATERIAL LEGEND

- EXISTING ASPHALT
- PROPOSED CONCRETE
- PROPOSED ASPHALT
- PROPOSED GRAVEL
- PROPOSED BUILDING
- PROPOSED LANDSCAPE ELEMENTS

LEGEND

- PROPERTY BOUNDARY
- EXISTING EASEMENT
- EXISTING SIGN
- EXISTING CURB & GUTTER
- EXISTING HYDRANT
- BUILDING SETBACK
- PROPOSED EASEMENT
- PROPOSED CURB AND GUTTER (CATCH)
- PROPOSED CURB AND GUTTER (SPILL)
- PROPOSED FENCE
- PROPOSED SIGN
- PROPOSED FIRE HYDRANT
- SURVEY CONTROL POINT
- FOUND PROPERTY CORNER

BMP LEGEND

- LOC — LIMITS OF CONSTRUCTION
- CIP — CULVERT INLET PROTECTION
- CWA — CONCRETE WASHOUT AREA
- DD — DIVERSION DITCH
- ECB — EROSION CONTROL BLANKET
- IP — INLET PROTECTION
- SCL — SEDIMENT CONTROL LOG
- SM — SEEDING & MULCHING
- SF — SILT FENCE
- SSA — STABILIZED STAGING AREA
- VTC — VEHICLE TRACKING CONTROL

N

0 30' 60'

SCALE: 1" = 30'

EROSION CONTROL NOTES:

1. THE BMPS SHOWN ON THIS INITIAL STAGE ECSD DRAWING SHALL BE INSTALLED AT THE OUTSET OF CONSTRUCTION, PRIOR TO ANY OTHER LAND-DISTURBING ACTIVITIES. INITIAL CONTROLS ARE TO BE PLACED ON EXISTING GRADES, BUT SHALL BE BASED IN PART ON PROPOSED GRADING OPERATIONS.
2. REFER TO EROSION AND SEDIMENT CONTROL REPORT FOR THIS PROJECT FOR ADDITIONAL DETAILS AND STORMWATER MANAGEMENT REQUIREMENTS.
3. CONTRACTOR TO ESTABLISH PERIMETER CONTROLS, VTC AND SB PRIOR TO COMMENCING CLEARING AND GRUBBING.
4. SEDIMENT BASINS SHALL BE INSTALLED PRIOR TO ANY OTHER LAND DISTURBANCE ACTIVITY THAT RELIES ON BASIN AS A STORMWATER CONTROL.
5. SEE CONSTRUCTION PLANS FOR DETAILS OF PERMANENT DRAINAGE FACILITIES SUCH AS EXTENDED DETENTION BASIN, CULVERTS, AND STORM DRAIN INLETS.
6. IF ANY BMP REQUIRES MODIFICATION, THE PLAN SHALL BE RED-LINED AND APPROVAL SHALL BE OBTAINED FROM THE COUNTY INSPECTOR PRIOR TO PROCEEDING, UNLESS IT IS AN EMERGENCY SITUATION THAT REQUIRES IMMEDIATE ATTENTION.
7. REMOVAL OF BMPS SHALL NOT OCCUR WITHOUT THE APPROVAL OF THE COUNTY INSPECTOR.

CAUTION: NOTICE TO CONTRACTOR

THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES AND, WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CALL THE LOCAL UTILITY LOCATION CENTER AT LEAST 48 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATIONS OF THE UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATE ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THE PLANS.

811 Know what's below.

BENCHMARK

SURVEY CONTROL POINTS AS SHOWN HEREON. ALL ELEVATIONS ARE BASED UPON NAVD88 VERTICAL DATUM.

2N CIVIL
303.925.0544
www.2ncivil.com

PREPARED FOR:
BLACK FOREST, LLC
12740 BLACK FOREST ROAD
COLORADO SPRINGS, CO 80908

ESCD - Initial Phase
CONSTRUCTION DOCUMENTS
BLACK FOREST OFFICE
COLORADO SPRINGS, COLORADO

REVISIONS:	BY:	DATE:
1. EL PASO CNTY COMMENTS 1-7-21	TEW	1-19-21
2.		
3.		
4.		

PROJECT NUMBER:	19015
ISSUED DATE:	12-03-2020
DESIGNED BY:	TEW
REVIEWED BY:	RCE

ESCD - Initial Phase

J:\Projects\19\19015\dwg\Site Plan\EC Plan - Initial.dwg 1/18/2021

MATERIAL LEGEND

- EXISTING ASPHALT
- PROPOSED CONCRETE
- PROPOSED ASPHALT
- PROPOSED GRAVEL
- PROPOSED BUILDING
- PROPOSED LANDSCAPE ELEMENTS

LEGEND

- PROPERTY BOUNDARY
- EXISTING EASEMENT
- EXISTING SIGN
- EXISTING CURB & GUTTER
- EXISTING HYDRANT
- BUILDING SETBACK
- PROPOSED EASEMENT
- PROPOSED CURB AND GUTTER (CATCH)
- PROPOSED CURB AND GUTTER (SPILL)
- PROPOSED FENCE
- PROPOSED SIGN
- PROPOSED FIRE HYDRANT
- SURVEY CONTROL POINT
- FOUND PROPERTY CORNER

BMP LEGEND

- LOC — LIMITS OF CONSTRUCTION
- CIP — CULVERT INLET PROTECTION
- CWA — CONCRETE WASHOUT AREA
- DD — DIVERSION DITCH
- ECB — EROSION CONTROL BLANKET
- IP — INLET PROTECTION
- SCL — SEDIMENT CONTROL LOG
- SM — SEEDING & MULCHING
- SF — SILT FENCE
- SSA — STABILIZED STAGING AREA
- VTC — VEHICLE TRACKING CONTROL

N

0 30' 60'

SCALE: 1" = 30'

EROSION CONTROL NOTES:

1. THE BMPS SHOWN ON THIS INTERIM STAGE ECSD DRAWING SHALL BE BASED ON PROPOSED GRADES AND DRAINAGE FEATURES AND ARE INSTALLED AFTER INITIAL SITE GRADING. FOR SOME BMPS SUCH AS INLET PROTECTION, INTERIM CONTROLS ARE INSTALLED AFTER THE CONSTRUCTION OF SITE INFRASTRUCTURE.
2. BMPS WERE INSTALLED IN INITIAL STAGE AND SHALL BE LEFT IN PLACE IN INTERIM STAGE.
3. SEE CONSTRUCTION PLANS FOR DETAILS OF PERMANENT DRAINAGE FACILITIES SUCH AS EXTENEDED DETENTION BASIN, CULVERTS, AND STORM DRAIN INLETS.
4. REFER TO EROSION AND SEDIMENT CONTROL REPORT FOR THIS PROJECT FOR ADDITIONAL DETAILS AND STORMWATER MANAGEMENT REQUIREMENTS.
5. ANY WASTE AND DISPOSAL ITEMS SHALL BE PROCESSED THROUGH THE STAGING AREA AND PROPERLY DISPOSED OF OFF-SITE.
6. IF ANY BMP REQUIRES MODIFICATION, THE PLAN SHALL BE RED-LINED AND APPROVAL SHALL BE OBTAINED FROM THE COUNTY INSPECTOR PRIOR TO PROCEEDING, UNLESS IT IS AN EMERGENCY SITUATION THAT REQUIRES IMMEDIATE ATTENTION.
7. REMOVAL OF BMPS SHALL NOT OCCUR WITHOUT THE APPROVAL OF THE COUNTY INSPECTOR.
8. SILT FENCE SHALL REMAIN UNTIL 70% COVERAGE OF PRE-DISTURBANCE LEVEL OF VEGETATION HAS BEEN ESTABLISHED.

CAUTION: NOTICE TO CONTRACTOR

THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES AND, WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CALL THE LOCAL UTILITY LOCATION CENTER AT LEAST 48 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATIONS OF THE UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATE ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THE PLANS.

811 Know what's below.

BENCHMARK

SURVEY CONTROL POINTS AS SHOWN HEREON. ALL ELEVATIONS ARE BASED UPON NAVD88 VERTICAL DATUM.

AREA OF DISTURBANCE = 93582.357 SQ. FT
2.15 AC

2N CIVIL
303.925.0544
www.2ncivil.com

PREPARED FOR:
BLACK FOREST, LLC
12740 BLACK FOREST ROAD
COLORADO SPRINGS, CO 80908

ESCD -Interim Phase
CONSTRUCTION DOCUMENTS
BLACK FOREST OFFICE
COLORADO SPRINGS, COLORADO

REVISIONS:	BY:	DATE:
1. EL PASO CNTY COMMENTS 1-7-21	TEW	1-19-21
2.		
3.		
4.		

PROJECT NUMBER:	19015
ISSUED DATE:	12-03-2020
DESIGNED BY:	TEW
REVIEWED BY:	RCE

ESCD -Interim Phase

J:\Projects\19\19015\dwg\Site Plan\EC Plan - Interim.dwg 1/18/2021

MATERIAL LEGEND

- EXISTING ASPHALT
- PROPOSED CONCRETE
- PROPOSED ASPHALT
- PROPOSED GRAVEL
- PROPOSED BUILDING
- PROPOSED LANDSCAPE ELEMENTS

LEGEND

- PROPERTY BOUNDARY
- EXISTING EASEMENT
- EXISTING SIGN
- EXISTING CURB & GUTTER
- EXISTING HYDRANT
- BUILDING SETBACK
- PROPOSED EASEMENT
- PROPOSED CURB AND GUTTER (CATCH)
- PROPOSED CURB AND GUTTER (SPILL)
- PROPOSED FENCE
- PROPOSED SIGN
- PROPOSED FIRE HYDRANT
- SURVEY CONTROL POINT
- FOUND PROPERTY CORNER

BMP LEGEND

- LOC — LIMITS OF CONSTRUCTION
- CIP — CULVERT INLET PROTECTION
- CWA — CONCRETE WASHOUT AREA
- DD — DIVERSION DITCH
- ECB — EROSION CONTROL BLANKET
- IP — INLET PROTECTION
- SCL — SEDIMENT CONTROL LOG
- SM — SEEDING & MULCHING
- SF — SILT FENCE
- SSA — STABILIZED STAGING AREA
- VTC — VEHICLE TRACKING CONTROL

N

0 30' 60'

SCALE: 1" = 30'

EROSION CONTROL NOTES:

1. THE BMPS SHOWN ON THIS FINAL STAGE ECSD DRAWING SHALL BE INSTALLED AS ONE OF THE LAST STEPS IN THE CONSTRUCTION PROCESS, SUCH AS FINAL SEEDING AND MULCHING.
2. SHADED BMPS WERE INSTALLED IN INITIAL OR INTERIM ECSD PLAN AND, UNLESS OTHERWISE INDICATED, SHALL BE LEFT IN PLACE UNTIL REVEGETATION ESTABLISHMENT IS APPROVED BY THE COUNTY.
3. SEE CONSTRUCTION PLANS FOR DETAILS OF PERMANENT DRAINAGE FACILITIES SUCH AS EXTENDED DETENTION BASIN, CULVERTS, AND STORM DRAIN INLETS.
4. STAGING AREAS SHALL BE RESTORED TO PROPOSED CONDITIONS AFTER CONSTRUCTION IS COMPLETE.
5. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO PHASE THE FINAL BMPS AS THE CONSTRUCTION PHASES PROGRESS.
6. REFER TO EROSION AND SEDIMENT CONTROL REPORT FOR THIS PROJECT FOR ADDITIONAL DETAILS AND STORMWATER MANAGEMENT REQUIREMENTS.
7. IF ANY BMP REQUIRES MODIFICATION, THE PLAN SHALL BE RED-LINED AND APPROVAL SHALL BE OBTAINED FROM THE COUNTY INSPECTOR PRIOR TO PROCEEDING, UNLESS IT IS AN EMERGENCY SITUATION THAT REQUIRES IMMEDIATE ATTENTION.

CAUTION: NOTICE TO CONTRACTOR

THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES AND, WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CALL THE LOCAL UTILITY LOCATION CENTER AT LEAST 48 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATIONS OF THE UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATE ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THE PLANS.

811 Know what's below.

BENCHMARK

SURVEY CONTROL POINTS AS SHOWN HEREON. ALL ELEVATIONS ARE BASED UPON NAVD88 VERTICAL DATUM.

2N CIVIL
303.925.0544
www.2ncivil.com

PREPARED FOR:
BLACK FOREST, LLC
12740 BLACK FOREST ROAD
COLORADO SPRINGS, CO 80908

ESCD - Final Phase
CONSTRUCTION DOCUMENTS
BLACK FOREST OFFICE
COLORADO SPRINGS, COLORADO

REVISIONS:	BY:	DATE:
1. EL PASO CNTY COMMENTS 1-7-21	TEW	1-19-21
2.		
3.		
4.		

PROJECT NUMBER:	19015
ISSUED DATE:	12-03-2020
DESIGNED BY:	TEW
REVIEWED BY:	RCE

ESCD - Final Phase

J:\Projects\19\19015\dwg\Site Plan\7 ESCD - Final Phase.dwg 1/18/2021

Table VT-1

	Case 1	Case 2
Gravel Thickness	9"	3"
Filter Fabric	YES	NO

City of Colorado Springs
Storm Water Quality

Figure VT-1
Vehicle Tracking
Application Examples

DEN:M:\153722.CS.CB\Fig\VT-1/5-99

VEHICLE TRACKING

NTS

VEHICLE TRACKING NOTES

INSTALLATION REQUIREMENTS

1. ALL ENTRANCES TO THE CONSTRUCTION SITE ARE TO BE STABILIZED PRIOR TO CONSTRUCTION BEGINNING.

2. CONSTRUCTION ENTRANCES ARE TO BE BUILT WITH AN APRON TO ALLOW FOR TURNING TRAFFIC, BUT SHOULD NOT BE BUILT OVER EXISTING PAVEMENT EXCEPT FOR A SLIGHT OVERLAP.

3. AREAS TO BE STABILIZED ARE TO BE PROPERLY GRADED AND COMPACTED PRIOR TO LAYING DOWN GEOTEXTILE AND STONE.

4. CONSTRUCTION ROADS, PARKING AREAS, LOADING/UNLOADING ZONES, STORAGE AREAS, AND STAGING AREAS ARE TO BE STABILIZED.

5. CONSTRUCTION ROADS ARE TO BE BUILT TO CONFORM TO SITE GRADES, BUT SHOULD NOT HAVE SIDE SLOPES OR ROAD GRADES THAT ARE EXCESSIVELY STEEP.

MAINTENANCE REQUIREMENTS

1. REGULAR INSPECTIONS ARE TO BE MADE OF ALL STABILIZED AREAS, ESPECIALLY AFTER STORM EVENTS.

2. STONES ARE TO BE REAPPLIED PERIODICALLY AND WHEN REPAIR IS NECESSARY.

3. SEDIMENT TRACKED ONTO PAVED ROADS IS TO BE REMOVED DAILY BY SHOVELING OR SWEEPING. SEDIMENT IS NOT TO BE WASHED DOWN STORM SEWER DRAINS.

4. STORM SEWER INLET PROTECTION IS TO BE IN PLACE, INSPECTED, AND CLEANED IF NECESSARY.

5. OTHER ASSOCIATED SEDIMENT CONTROL MEASURES ARE TO BE INSPECTED TO ENSURE GOOD WORKING CONDITION.

City of Colorado Springs
Stormwater Quality

Figure VT-2
Vehicle Tracking
Application Examples

SF–1. SILT FENCE

SILT FENCE INSTALLATION NOTES

1. SILT FENCE MUST BE PLACED AWAY FROM THE TOE OF THE SLOPE TO ALLOW FOR WATER PONDING. SILT FENCE AT THE TOE OF A SLOPE SHOULD BE INSTALLED IN A FLAT LOCATION AT LEAST SEVERAL FEET (2–5 FT) FROM THE TOE OF THE SLOPE TO ALLOW ROOM FOR PONDING AND DEPOSITION.

2. A UNIFORM 6" X 4" ANCHOR TRENCH SHALL BE EXCAVATED USING TRENCHER OR SILT FENCE INSTALLATION DEVICE. NO ROAD GRADERS, BACKHOES, OR SIMILAR EQUIPMENT SHALL BE USED.

3. COMPACT ANCHOR TRENCH BY HAND WITH A "JUMPING JACK" OR BY WHEEL ROLLING. COMPACTION SHALL BE SUCH THAT SILT FENCE RESISTS BEING PULLED OUT OF ANCHOR TRENCH BY HAND.

4. SILT FENCE SHALL BE PULLED TIGHT AS IT IS ANCHORED TO THE STAKES. THERE SHOULD BE NO NOTICEABLE SAG BETWEEN STAKES AFTER IT HAS BEEN ANCHORED TO THE STAKES.

5. SILT FENCE FABRIC SHALL BE ANCHORED TO THE STAKES USING 1" HEAVY DUTY STAPLES OR NAILS WITH 1" HEADS. STAPLES AND NAILS SHOULD BE PLACED 3" ALONG THE FABRIC DOWN THE STAKE.

6. AT THE END OF A RUN OF SILT FENCE ALONG A CONTOUR, THE SILT FENCE SHOULD BE TURNED PERPENDICULAR TO THE CONTOUR TO CREATE A "J–HOOK." THE "J–HOOK" EXTENDING PERPENDICULAR TO THE CONTOUR SHOULD BE OF SUFFICIENT LENGTH TO KEEP RUNOFF FROM FLOWING AROUND THE END OF THE SILT FENCE (TYPICALLY 10' – 20').

7. SILT FENCE SHALL BE INSTALLED PRIOR TO ANY LAND DISTURBING ACTIVITIES.

SILT FENCE MAINTENANCE NOTES

1. INSPECT BMPs EACH WORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION. MAINTENANCE OF BMPs SHOULD BE PROACTIVE, NOT REACTIVE. INSPECT BMPs AS SOON AS POSSIBLE (AND ALWAYS WITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE EROSION, AND PERFORM NECESSARY MAINTENANCE.

2. FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN BMPs IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE DOCUMENTED THOROUGHLY.

3. WHERE BMPs HAVE FAILED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON DISCOVERY OF THE FAILURE.

4. SEDIMENT ACCUMULATED UPSTREAM OF THE SILT FENCE SHALL BE REMOVED AS NEEDED TO MAINTAIN THE FUNCTIONALITY OF THE BMP, TYPICALLY WHEN DEPTH OF ACCUMULATED SEDIMENTS IS APPROXIMATELY 6".

5. REPAIR OR REPLACE SILT FENCE WHEN THERE ARE SIGNS OF WEAR, SUCH AS SAGGING, TEARING, OR COLLAPSE.

6. SILT FENCE IS TO REMAIN IN PLACE UNTIL THE UPSTREAM DISTURBED AREA IS STABILIZED AND APPROVED BY THE LOCAL JURISDICTION, OR IS REPLACED BY AN EQUIVALENT PERIMETER SEDIMENT CONTROL BMP.

7. WHEN SILT FENCE IS REMOVED, ALL DISTURBED AREAS SHALL BE COVERED WITH TOPSOIL, SEEDED AND MULCHED OR OTHERWISE STABILIZED AS APPROVED BY LOCAL JURISDICTION.

(DETAIL ADAPTED FROM TOWN OF PARKER, COLORADO AND CITY OF AURORA, NOT AVAILABLE IN AUTOCAD)

NOTE: MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

SSA–1. STABILIZED STAGING AREA

STABILIZED STAGING AREA INSTALLATION NOTES

1. SEE PLAN VIEW FOR
   –LOCATION OF STAGING AREA(S).
   –CONTRACTOR MAY ADJUST LOCATION AND SIZE OF STAGING AREA WITH APPROVAL FROM THE LOCAL JURISDICTION.

2. STABILIZED STAGING AREA SHOULD BE APPROPRIATE FOR THE NEEDS OF THE SITE. OVERSIZING RESULTS IN A LARGER AREA TO STABILIZE FOLLOWING CONSTRUCTION.

3. STAGING AREA SHALL BE STABILIZED PRIOR TO OTHER OPERATIONS ON THE SITE.

4. THE STABILIZED STAGING AREA SHALL CONSIST OF A MINIMUM 3" THICK GRANULAR MATERIAL.

5. UNLESS OTHERWISE SPECIFIED BY LOCAL JURISDICTION, ROCK SHALL CONSIST OF DOT SECT. #703, AASHTO #3 COARSE AGGREGATE OR 6" (MINUS) ROCK.

6. ADDITIONAL PERIMETER BMPs MAY BE REQUIRED INCLUDING BUT NOT LIMITED TO SILT FENCE AND CONSTRUCTION FENCING.

STABILIZED STAGING AREA MAINTENANCE NOTES

1. INSPECT BMPs EACH WORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION. MAINTENANCE OF BMPs SHOULD BE PROACTIVE, NOT REACTIVE. INSPECT BMPs AS SOON AS POSSIBLE (AND ALWAYS WITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE EROSION, AND PERFORM NECESSARY MAINTENANCE.

2. FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN BMPs IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE DOCUMENTED THOROUGHLY.

3. WHERE BMPs HAVE FAILED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON DISCOVERY OF THE FAILURE.

4. ROCK SHALL BE REAPPLIED OR REGRADED AS NECESSARY IF RUTTING OCCURS OR UNDERLYING SUBGRADE BECOMES EXPOSED.

STABILIZED STAGING AREA MAINTENANCE NOTES

5. STABILIZED STAGING AREA SHALL BE ENLARGED IF NECESSARY TO CONTAIN PARKING, STORAGE, AND UNLOADING/LOADING OPERATIONS.

6. THE STABILIZED STAGING AREA SHALL BE REMOVED AT THE END OF CONSTRUCTION. THE GRANULAR MATERIAL SHALL BE REMOVED OR, IF APPROVED BY THE LOCAL JURISDICTION, USED ON SITE, AND THE AREA COVERED WITH TOPSOIL, SEEDED AND MULCHED OR OTHERWISE STABILIZED IN A MANNER APPROVED BY LOCAL JURISDICTION.

NOTE: MANY MUNICIPALITIES PROHIBIT THE USE OF RECYCLED CONCRETE AS GRANULAR MATERIAL FOR STABILIZED STAGING AREAS DUE TO DIFFICULTIES WITH RE–ESTABLISHMENT OF VEGETATION IN AREAS WHERE RECYCLED CONCRETE WAS PLACED.

NOTE: MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

(DETAILS ADAPTED FROM DOUGLAS COUNTY, COLORADO, NOT AVAILABLE IN AUTOCAD)

CWA–1. CONCRETE WASHOUT AREA

CWA INSTALLATION NOTES

1. SEE PLAN VIEW FOR:
   –CWA INSTALLATION LOCATION.

2. DO NOT LOCATE AN UNLINED CWA WITHIN 400' OF ANY NATURAL DRAINAGE PATHWAY OR WATERBODY. DO NOT LOCATE WITHIN 1,000' OF ANY WELLS OR DRINKING WATER SOURCES. IF SITE CONSTRAINTS MAKE THIS INFEASIBLE, OR IF HIGHLY PERMEABLE SOILS EXIST ON SITE, THE CWA MUST BE INSTALLED WITH AN IMPERMEABLE LINER (16 MIL MIN. THICKNESS) OR SURFACE STORAGE ALTERNATIVES USING PREFABRICATED CONCRETE WASHOUT DEVICES OR A LINED ABOVE GROUND STORAGE ARE SHOULD BE USED.

3. THE CWA SHALL BE INSTALLED PRIOR TO CONCRETE PLACEMENT ON SITE.

4. CWA SHALL INCLUDE A FLAT SUBSURFACE PIT THAT IS AT LEAST 8' BY 8' SLOPES LEADING OUT OF THE SUBSURFACE PIT SHALL BE 3:1 OR FLATTER. THE PIT SHALL BE AT LEAST 3' DEEP.

5. BERM SURROUNDING SIDES AND BACK OF THE CWA SHALL HAVE MINIMUM HEIGHT OF 1'.

6. VEHICLE TRACKING PAD SHALL BE SLOPED 2% TOWARDS THE CWA.

7. SIGNS SHALL BE PLACED AT THE CONSTRUCTION ENTRANCE, AT THE CWA, AND ELSEWHERE AS NECESSARY TO CLEARLY INDICATE THE LOCATION OF THE CWA TO OPERATORS OF CONCRETE TRUCKS AND PUMP RIGS.

8. USE EXCAVATED MATERIAL FOR PERIMETER BERM CONSTRUCTION.

CWA MAINTENANCE NOTES

1. INSPECT BMPs EACH WORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION. MAINTENANCE OF BMPs SHOULD BE PROACTIVE, NOT REACTIVE. INSPECT BMPs AS SOON AS POSSIBLE (AND ALWAYS WITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE EROSION, AND PERFORM NECESSARY MAINTENANCE.

2. FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN BMPs IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE DOCUMENTED THOROUGHLY.

3. WHERE BMPs HAVE FAILED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON DISCOVERY OF THE FAILURE.

4. THE CWA SHALL BE REPAIRED, CLEANED, OR ENLARGED AS NECESSARY TO MAINTAIN CAPACITY FOR CONCRETE WASTE. CONCRETE MATERIALS, ACCUMULATED IN PIT, SHALL BE REMOVED ONCE THE MATERIALS HAVE REACHED A DEPTH OF 2'.

5. CONCRETE WASHOUT WATER, WASTED PIECES OF CONCRETE AND ALL OTHER DEBRIS IN THE SUBSURFACE PIT SHALL BE TRANSPORTED FROM THE JOB SITE IN A WATER–TIGHT CONTAINER AND DISPOSED OF PROPERLY.

6. THE CWA SHALL REMAIN IN PLACE UNTIL ALL CONCRETE FOR THE PROJECT IS PLACED.

7. WHEN THE CWA IS REMOVED, COVER THE DISTURBED AREA WITH TOP SOIL, SEED AND MULCH OR OTHERWISE STABILIZED IN A MANNER APPROVED BY THE LOCAL JURISDICTION.

(DETAIL ADAPTED FROM DOUGLAS COUNTY, COLORADO AND THE CITY OF PARKER, COLORADO, NOT AVAILABLE IN AUTOCAD).

NOTE: MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

2N CIVIL
303.925.0544
www.2ncivil.com

PREPARED FOR:
BLACK FOREST, LLC
12740 BLACK FOREST ROAD
COLORADO SPRINGS, CO 80908

ESCD Details 1
CONSTRUCTION DOCUMENTS
BLACK FOREST OFFICE
COLORADO SPRINGS, COLORADO

DATE: 1-19-21
BY: TEW

REVISIONS:
1. EL PASO CNTY COMMENTS 1-7-21
2.
3.
4.

PROJECT NUMBER: 19015
ISSUED DATE: 12-03-2020
DESIGNED BY: TEW
REVIEWED BY: RCE

ESCD Details 1

J:\Projects\19\19015\dwg\Site Plan\8 ESCD Details 2.dwg 11/18/2021

IP–1. BLOCK AND ROCK SOCK SUMP OR ON GRADE INLET PROTECTION

BLOCK AND CURB SOCK INLET PROTECTION INSTALLATION NOTES

1. SEE ROCK SOCK DESIGN DETAIL FOR INSTALLATION REQUIREMENTS.

2. CONCRETE "CINDER" BLOCKS SHALL BE LAID ON THEIR SIDES AROUND THE INLET IN A SINGLE ROW, ABUTTING ONE ANOTHER WITH THE OPEN END FACING AWAY FROM THE CURB.

3. GRAVEL BAGS SHALL BE PLACED AROUND CONCRETE BLOCKS, CLOSELY ABUTTING ONE ANOTHER AND JOINTED TOGETHER IN ACCORDANCE WITH ROCK SOCK DESIGN DETAIL.

IP–2. CURB ROCK SOCKS UPSTREAM OF INLET PROTECTION

CURB ROCK SOCK INLET PROTECTION INSTALLATION NOTES

1. SEE ROCK SOCK DESIGN DETAIL INSTALLATION REQUIREMENTS.

2. PLACEMENT OF THE SOCK SHALL BE APPROXIMATELY 30 DEGREES FROM PERPENDICULAR IN THE OPPOSITE DIRECTION OF FLOW.

3. SOCKS ARE TO BE FLUSH WITH THE CURB AND SPACED A MINIMUM OF 5 FEET APART.

4. AT LEAST TWO CURB SOCKS IN SERIES ARE REQUIRED UPSTREAM OF ON–GRADE INLETS.

CULVERT INLET PROTECTION PLAN

SECTION A

SECTION B

CIP–1. CULVERT INLET PROTECTION

CULVERT INLET PROTECTION INSTALLATION NOTES

1. SEE PLAN VIEW FOR
–LOCATION OF CULVERT INLET PROTECTION.

2. SEE ROCK SOCK DESIGN DETAIL FOR ROCK GRADATION REQUIREMENTS AND JOINTING DETAIL.

CULVERT INLET PROTECTION MAINTENANCE NOTES

1. INSPECT BMPs EACH WORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION. MAINTENANCE OF BMPs SHOULD BE PROACTIVE, NOT REACTIVE. INSPECT BMPs AS SOON AS POSSIBLE (AND ALWAYS WITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE EROSION, AND PERFORM NECESSARY MAINTENANCE.

2. FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN BMPs IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE DOCUMENTED THOROUGHLY.

3. WHERE BMPs HAVE FAILED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON DISCOVERY OF THE FAILURE.

4. SEDIMENT ACCUMULATED UPSTREAM OF THE CULVERT SHALL BE REMOVED WHEN THE SEDIMENT DEPTH IS ½ THE HEIGHT OF THE ROCK SOCK.

5. CULVERT INLET PROTECTION SHALL REMAIN IN PLACE UNTIL THE UPSTREAM DISTURBED AREA IS PERMANENTLY STABILIZED AND APPROVED BY THE LOCAL JURISDICTION.

(DETAILS ADAPTED FROM AURORA, COLORADO, NOT AVAILABLE IN AUTOCAD)

NOTE: MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

GENERAL INLET PROTECTION INSTALLATION NOTES

1. SEE PLAN VIEW FOR:
–LOCATION OF INLET PROTECTION.
–TYPE OF INLET PROTECTION (IP.1, IP.2, IP.3, IP.4, IP.5, IP.6)

2. INLET PROTECTION SHALL BE INSTALLED PROMPTLY AFTER INLET CONSTRUCTION OR PAVING IS COMPLETE (TYPICALLY WITHIN 48 HOURS). IF A RAINFALL/RUNOFF EVENT IS FORECAST, INSTALL INLET PROTECTION PRIOR TO ONSET OF EVENT.

3. MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

INLET PROTECTION MAINTENANCE NOTES

1. INSPECT BMPs EACH WORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION. MAINTENANCE OF BMPs SHOULD BE PROACTIVE, NOT REACTIVE. INSPECT BMPs AS SOON AS POSSIBLE (AND ALWAYS WITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE EROSION, AND PERFORM NECESSARY MAINTENANCE.

2. FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN BMPs IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE DOCUMENTED THOROUGHLY.

3. WHERE BMPs HAVE FAILED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON DISCOVERY OF THE FAILURE.

4. SEDIMENT ACCUMULATED UPSTREAM OF INLET PROTECTION SHALL BE REMOVED AS NECESSARY TO MAINTAIN BMP EFFECTIVENESS, TYPICALLY WHEN STORAGE VOLUME REACHES 50% OF CAPACITY, A DEPTH OF 6" WHEN SILT FENCE IS USED, OR ¼ OF THE HEIGHT FOR STRAW BALES.

5. INLET PROTECTION IS TO REMAIN IN PLACE UNTIL THE UPSTREAM DISTURBED AREA IS PERMANENTLY STABILIZED, UNLESS THE LOCAL JURISDICTION APPROVES EARLIER REMOVAL OF INLET PROTECTION IN STREETS.

6. WHEN INLET PROTECTION AT AREA INLETS IS REMOVED, THE DISTURBED AREA SHALL BE COVERED WITH TOP SOIL, SEEDED AND MULCHED, OR OTHERWISE STABILIZED IN A MANNER APPROVED BY THE LOCAL JURISDICTION.

(DETAIL ADAPTED FROM TOWN OF PARKER, COLORADO AND CITY OF AURORA, COLORADO, NOT AVAILABLE IN AUTOCAD)

NOTE: MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

NOTE: THE DETAILS INCLUDED WITH THIS FACT SHEET SHOW COMMONLY USED, CONVENTIONAL METHODS OF INLET PROTECTION IN THE DENVER METROPOLITAN AREA. THERE ARE MANY PROPRIETARY INLET PROTECTION METHODS ON THE MARKET. UDFCD NEITHER ENDORSES NOR DISCOURAGES USE OF PROPRIETARY INLET PROTECTION; HOWEVER, IN THE EVENT PROPRIETARY METHODS ARE USED, THE APPROPRIATE DETAIL FROM THE MANUFACTURER MUST BE INCLUDED IN THE SWMP AND THE BMP MUST BE INSTALLED AND MAINTAINED AS SHOWN IN THE MANUFACTURER'S DETAILS.

NOTE: SOME MUNICIPALITIES DISCOURAGE OR PROHIBIT THE USE OF STRAW BALES FOR INLET PROTECTION. CHECK WITH LOCAL JURISDICTION TO DETERMINE IF STRAW BALE INLET PROTECTION IS ACCEPTABLE.

TRENCHED SEDIMENT CONTROL LOG

SECTION Ⓐ
TRENCHED SEDIMENT CONTROL LOG

LOG JOINTS

SCL–1. TRENCHED SEDIMENT CONTROL LOG

SCL–3. SEDIMENT CONTROL LOGS TO CONTROL SLOPE LENGTH

SEDIMENT CONTROL LOG INSTALLATION NOTES

1. SEE PLAN VIEW FOR LOCATION AND LENGTH OF SEDIMENT CONTROL LOGS.

2. SEDIMENT CONTROL LOGS THAT ACT AS A PERIMETER CONTROL SHALL BE INSTALLED PRIOR TO ANY UPGRADIENT LAND–DISTURBING ACTIVITIES.

3. SEDIMENT CONTROL LOGS SHALL CONSIST OF STRAW, COMPOST, EXCELSIOR OR COCONUT FIBER, AND SHALL BE FREE OF ANY NOXIOUS WEED SEEDS OR DEFECTS INCLUDING RIPS, HOLES AND OBVIOUS WEAR.

4. SEDIMENT CONTROL LOGS MAY BE USED AS SMALL CHECK DAMS IN DITCHES AND SWALES. HOWEVER, THEY SHOULD NOT BE USED IN PERENNIAL STREAMS.

5. IT IS RECOMMENDED THAT SEDIMENT CONTROL LOGS BE TRENCHED INTO THE GROUND TO A DEPTH OF APPROXIMATELY ⅓ OF THE DIAMETER OF THE LOG. IF TRENCHING TO THIS DEPTH IS NOT FEASIBLE AND/OR DESIRABLE (SHORT TERM INSTALLATION WITH DESIRE NOT TO DAMAGE LANDSCAPE) A LESSER TRENCHING DEPTH MAY BE ACCEPTABLE WITH MORE ROBUST STAKING. COMPOST LOGS THAT ARE 8 LB/FT DO NOT NEED TO BE TRENCHED.

6. THE UPHILL SIDE OF THE SEDIMENT CONTROL LOG SHALL BE BACKFILLED WITH SOIL OR FILTER MATERIAL THAT IS FREE OF ROCKS AND DEBRIS. THE SOIL SHALL BE TIGHTLY COMPACTED INTO THE SHAPE OF A RIGHT TRIANGLE USING A SHOVEL OR WEIGHTED LAWN ROLLER OR BLOWN IN PLACE.

7. FOLLOW MANUFACTURERS' GUIDANCE FOR STAKING. IF MANUFACTURERS' INSTRUCTIONS DO NOT SPECIFY SPACING, STAKES SHALL BE PLACED ON 4' CENTERS AND EMBEDDED A MINIMUM OF 6" INTO THE GROUND. 3" OF THE STAKE SHALL PROTRUDE FROM THE TOP OF THE LOG. STAKES THAT ARE BROKEN PRIOR TO INSTALLATION SHALL BE REPLACED. COMPOST LOGS SHOULD BE STAKED 10' ON CENTER.

SEDIMENT CONTROL LOG MAINTENANCE NOTES

1. INSPECT BMPs EACH WORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION. MAINTENANCE OF BMPs SHOULD BE PROACTIVE, NOT REACTIVE. INSPECT BMPs AS SOON AS POSSIBLE (AND ALWAYS WITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE EROSION, AND PERFORM NECESSARY MAINTENANCE.

2. FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN BMPs IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE DOCUMENTED THOROUGHLY.

3. WHERE BMPs HAVE FAILED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON DISCOVERY OF THE FAILURE.

4. SEDIMENT ACCUMULATED UPSTREAM OF SEDIMENT CONTROL LOG SHALL BE REMOVED AS NEEDED TO MAINTAIN FUNCTIONALITY OF THE BMP, TYPICALLY WHEN DEPTH OF ACCUMULATED SEDIMENTS IS APPROXIMATELY ½ OF THE HEIGHT OF THE SEDIMENT CONTROL LOG.

5. SEDIMENT CONTROL LOG SHALL BE REMOVED AT THE END OF CONSTRUCTION.COMPOST FROM COMPOST LOGS MAY BE LEFT IN PLACE AS LONG AS BAGS ARE REMOVED AND THE AREA SEEDED. IF DISTURBED AREAS EXIST AFTER REMOVAL, THEY SHALL BE COVERED WITH TOP SOIL, SEEDED AND MULCHED OR OTHERWISE STABILIZED IN A MANNER APPROVED BY THE LOCAL JURISDICTION.

(DETAILS ADAPTED FROM TOWN OF PARKER, COLORADO, JEFFERSON COUNTY, COLORADO, DOUGLAS COUNTY, COLORADO, AND CITY OF AURORA, COLORADO, NOT AVAILABLE IN AUTOCAD)

NOTE: MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

SEDIMENT BASIN PLAN

*EXCEPT WHERE THE HOLES EXCEED 1" DIAMETER, THEN UP TO TWO COLUMNS OF SAME SIZED HOLES MAY BE USED

SECTION A

TABLE SB–1. SIZING INFORMATION FOR STANDARD SEDIMENT BASIN

Upstream Drainage Area (rounded to nearest acre). (ac)	Basin Bottom Width (W), (ft)	Spillway Crest Length (CL), (ft)	Hole Diameter (HD), (in)
1	12 ½	2	9/32
2	21	3	13/64
3	28	5	¼
4	33 ½	6	9/64
5	38 ½	8	5/32
6	43	9	21/32
7	47 ¼	11	23/32
8	51	12	25/32
9	55	13	⅞
10	58 ¼	15	15/16
11	61	16	31/32
12	64	18	1
13	67 ½	19	1 1/16
14	70 ½	21	1 ⅛
15	73 ¼	22	1 3/16

SEDIMENT BASIN INSTALLATION NOTES

1. SEE PLAN VIEW FOR:
–LOCATION OF SEDIMENT BASIN.
–TYPE OF BASIN (STANDARD BASIN OR NONSTANDARD BASIN).
–FOR STANDARD BASIN, BOTTOM WIDTH W, CREST LENGTH CL, AND HOLE DIAMETER, HD.
–FOR NONSTANDARD BASIN, SEE CONSTRUCTION DRAWINGS FOR DESIGN OF BASIN INCLUDING RISER HEIGHT H, NUMBER OF COLUMNS N, HOLE DIAMETER HD AND PIPE DIAMETER D.

2. FOR STANDARD BASIN, BOTTOM DIMENSION MAY BE MODIFIED AS LONG AS BOTTOM AREA IS NOT REDUCED.

3. SEDIMENT BASINS SHALL BE INSTALLED PRIOR TO ANY OTHER LAND–DISTURBING ACTIVITY THAT RELIES ON ON BASINS AS AS A STORMWATER CONTROL.

4. EMBANKMENT MATERIAL SHALL CONSIST OF SOIL FREE OF DEBRIS, ORGANIC MATERIAL, AND ROCKS OR CONCRETE GREATER THAN 3 INCHES AND SHALL HAVE A MINIMUM OF 15 PERCENT BY WEIGHT PASSING THE NO. 200 SIEVE.

5. EMBANKMENT MATERIAL SHALL BE COMPACTED TO AT LEAST 95 PERCENT OF MAXIMUM DENSITY IN ACCORDANCE WITH ASTM D698.

6. PIPE SCH 40 OR GREATER SHALL BE USED.

7. THE DETAILS SHOWN ON THESE SHEETS PERTAIN TO STANDARD SEDIMENT BASIN(S) FOR DRAINAGE AREAS LESS THAN 15 ACRES. SEE CONSTRUCTION DRAWINGS FOR EMBANKMENT, STORAGE VOLUME, SPILLWAY, OUTLET, AND OUTLET PROTECTION DETAILS FOR ANY SEDIMENT BASIN(S) THAT HAVE BEEN INDIVIDUALLY DESIGNED FOR DRAINAGE AREAS LARGER THAN 15 ACRES.

2N CIVIL
303.925.0544
www.2ncivil.com

PREPARED FOR:
BLACK FOREST, LLC
12740 BLACK FOREST ROAD
COLORADO SPRINGS, CO 80908

ESCD Details 2
CONSTRUCTION DOCUMENTS
BLACK FOREST OFFICE
COLORADO SPRINGS, COLORADO

REVISIONS:	BY:	DATE:
1. ELPASO CNTY COMMENTS 1-7-21	TEW	1-19-21
2.		
3.		
4.		

PROJECT NUMBER:	19015
ISSUED DATE:	12-03-2020
DESIGNED BY:	TEW
REVIEWED BY:	RCE

ESCD Details 2

J:\Projects\19\19015\dwg\Site Plan\8 ESCD Details 2.dwg 1/18/2021

Surface Roughening (SR) EC-1

SR–1. SURFACE ROUGHENING
FOR STEEP SLOPES (3:1 OR STEEPER)

SR–2. SURFACE ROUGHENING
FOR LOW SLOPES (LESS THAN 3:1)

EC-1 Surface Roughening (SR)

SURFACE ROUGHENING INSTALLATION NOTES

1. SEE PLAN VIEW FOR:
   –LOCATION(S) OF SURFACE ROUGHENING.

2. SURFACE ROUGHENING SHALL BE PROVIDED PROMPTLY AFTER COMPLETION OF FINISHED GRADING (FOR AREAS NOT RECEIVING TOPSOIL) OR PRIOR TO TOPSOIL PLACEMENT OR ANY FORECASTED RAIN EVENT.

3. AREAS WHERE BUILDING FOUNDATIONS, PAVEMENT, OR SOD WILL BE PLACED WITHOUT DELAY IN THE CONSTRUCTION SEQUENCE, SURFACE ROUGHENING IS NOT REQUIRED.

4. DISTURBED SURFACES SHALL BE ROUGHENED USING RIPPING OR TILLING EQUIPMENT ON THE CONTOUR OR TRACKING UP AND DOWN A SLOPE USING EQUIPMENT TREADS.

5. A FARMING DISK SHALL NOT BE USED FOR SURFACE ROUGHENING.

SURFACE ROUGHENING MAINTENANCE NOTES

1. INSPECT BMPs EACH WORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION. MAINTENANCE OF BMPs SHOULD BE PROACTIVE, NOT REACTIVE. INSPECT BMPs AS SOON AS POSSIBLE (AND ALWAYS WITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE EROSION, AND PERFORM NECESSARY MAINTENANCE.

2. FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN BMPs IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE DOCUMENTED THOROUGHLY.

3. WHERE BMPs HAVE FAILED, REPAIR OR REPLACE UPON DISCOVERY OF THE FAILURE.

4. VEHICLES AND EQUIPMENT SHALL NOT BE DRIVEN OVER AREAS THAT HAVE BEEN SURFACE ROUGHENED.

5. IN NON–TURF GRASS FINISHED AREAS, SEEDING AND MULCHING SHALL TAKE PLACE DIRECTLY OVER SURFACE ROUGHENED AREAS WITHOUT FIRST SMOOTHING OUT THE SURFACE.

6. IN AREAS NOT SEEDED AND MULCHED AFTER SURFACE ROUGHENING, SURFACES SHALL BE RE–ROUGHENED AS NECESSARY TO MAINTAIN GROOVE DEPTH AND SMOOTH OVER RILL EROSION.

(DETAILS ADAPTED FROM TOWN OF PARKER, COLORADO, NOT AVAILABLE IN AUTOCAD)

NOTE: MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

Rolled Erosion Control Products (RECP) EC-6

ECB–3. OUTSIDE OF DRAINAGEWAY

STAKING PATTERNS BY ECB TYPE

STAKING PATTERNS BY SLOPE OR CHANNEL TYPE

DIVERSION DITCH INSTALLATION NOTES

1. SEE PLAN VIEW FOR:
   - LOCATION OF DIVERSION DITCH.
   - TYPE OF DITCH (UNLINED, ECB LINED, PLASTIC LINED OR RIPRAP LINED).
   - LENGTH OF EACH TYPE OF DITCH.
   - DEPTH, "D", AND WIDTH, "W" DIMENSIONS.
   - FOR ECB LINED DITCH, EROSION CONTROL BLANKET TYPE (SEE DETAIL 9).
   - FOR RIPRAP LINED DITCH, SIZE OF RIPRAP, "Dso".
2. SEE DRAINAGE PLANS FOR DETAILS OF ANY PERMANENT CONVEYANCE FACILITIES OR DIVERSION DITCHES EXCEEDING A 2–YEAR FLOW RATE OF 10 CFS.
3. DIVERSION DITCHES INDICATED ON INITIAL GESC PLAN SHALL BE INSTALLED PRIOR TO ANY LAND–DISTURBING ACTIVITIES.
4. FOR ECB LINED DITCHES, INSTALLATION OF EROSION CONTROL BLANKET SHALL CONFORM TO THE REQUIREMENTS OF DETAIL 9.
5. IN LOCATIONS WHERE CONSTRUCTION TRAFFIC MUST CROSS A DIVERSION DITCH, THE PERMITTEES SHALL INSTALL A TEMPORARY CULVERT.

DIVERSION DITCH MAINTENANCE NOTES

1. THE GESC MANAGER SHALL INSPECT AS NECESSARY TO ENSURE THE ADEQUACY AND FUNCTIONALITY OF THE CONTROL MEASURE.
2. DIVERSION DITCHES ARE TO REMAIN IN PLACE UNTIL THE END OF CONSTRUCTION, OR, IF APPROVED BY SEMSWA, LEFT IN PLACE.
3. IF DIVERSION DITCHES ARE REMOVED, THE DISTURBED AREA SHALL BE DRILL SEEDED AND CRIMP MULCHED OR OTHERWISE STABILIZED IN A MANNER APPROVED BY SEMSWA.

DD DIVERSION DITCH 8

Temporary and Permanent Seeding (TS/PS) EC-2

Seeding dates for the highest success probability of perennial species along the Front Range are generally in the spring from April through early May and in the fall after the first of September until the ground freezes. If the area is irrigated, seeding may occur in summer months, as well. See Table TS/PS-3 for appropriate seeding dates.

Table TS/PS-1. Minimum Drill Seeding Rates for Various Temporary Annual Grasses

Species[a] (Common name)	Growth Season[b]	Pounds of Pure Live Seed (PLS)/acre[c]	Planting Depth (inches)
1. Oats	Cool	35 - 50	1 - 2
2. Spring wheat	Cool	25 - 35	1 - 2
3. Spring barley	Cool	25 - 35	1 - 2
4. Annual ryegrass	Cool	10 - 15	½
5. Millet	Warm	3 - 15	½ - ¾
6. Sudangrass	Warm	5–10	½ - ¾
7. Sorghum	Warm	5–10	½ - ¾
8. Winter wheat	Cool	20–35	1 - 2
9. Winter barley	Cool	20–35	1 - 2
10. Winter rye	Cool	20–35	1 - 2
11. Triticale	Cool	25–40	1 - 2

[a] Successful seeding of annual grass resulting in adequate plant growth will usually produce enough dead-plant residue to provide protection from wind and water erosion for an additional year. This assumes that the cover is not disturbed or mowed closer than 8 inches.

Hydraulic seeding may be substituted for drilling only where slopes are steeper than 3:1 or where access limitations exist. When hydraulic seeding is used, hydraulic mulching should be applied as a separate operation, when practical, to prevent the seeds from being encapsulated in the mulch.

[b] See Table TS/PS-3 for seeding dates. Irrigation, if consistently applied, may extend the use of cool season species during the summer months.

[c] Seeding rates should be doubled if seed is broadcast, or increased by 50 percent if done using a Brillion Drill or by hydraulic seeding.

EC-2 Temporary and Permanent Seeding (TS/PS)

Table TS/PS-2. Minimum Drill Seeding Rates for Perennial Grasses

Common[a] Name	Botanical Name	Growth Season[b]	Growth Form	Seeds/ Pound	Pounds of PLS/acre
Alakali Soil Seed Mix					
Alkali sacaton	*Sporobolus airoides*	Cool	Bunch	1,750,000	0.25
Basin wildrye	*Elymus cinereus*	Cool	Bunch	165,000	2.5
Sodar streambank wheatgrass	*Agropyron riparium 'Sodar'*	Cool	Sod	170,000	2.5
Jose tall wheatgrass	*Agropyron elongatum 'Jose'*	Cool	Bunch	79,000	7.0
Arriba western wheatgrass	*Agropyron smithii 'Arriba'*	Cool	Sod	110,000	5.5
Total					**17.75**
Fertile Loamy Soil Seed Mix					
Ephriam crested wheatgrass	*Agropyron cristatum 'Ephriam'*	Cool	Sod	175,000	2.0
Dural hard fescue	*Festuca ovina 'duriuscula'*	Cool	Bunch	565,000	1.0
Lincoln smooth brome	*Bromus inermis leyss 'Lincoln'*	Cool	Sod	130,000	3.0
Sodar streambank wheatgrass	*Agropyron riparium 'Sodar'*	Cool	Sod	170,000	2.5
Arriba western wheatgrass	*Agropyron smithii 'Arriba'*	Cool	Sod	110,000	7.0
Total					**15.5**
High Water Table Soil Seed Mix					
Meadow foxtail	*Alopecurus pratensis*	Cool	Sod	900,000	0.5
Redtop	*Agrostis alba*	Warm	Open sod	5,000,000	0.25
Reed canarygrass	*Phalaris arundinacea*	Cool	Sod	68,000	0.5
Lincoln smooth brome	*Bromus inermis leyss 'Lincoln'*	Cool	Sod	130,000	3.0
Pathfinder switchgrass	*Panicum virgatum 'Pathfinder'*	Warm	Sod	389,000	1.0
Alkar tall wheatgrass	*Agropyron elongatum 'Alkar'*	Cool	Bunch	79,000	5.5
Total					**10.75**
Transition Turf Seed Mix[c]					
Ruebens Canadian bluegrass	*Poa compressa 'Ruebens'*	Cool	Sod	2,500,000	0.5
Dural hard fescue	*Festuca ovina 'duriuscula'*	Cool	Bunch	565,000	1.0
Citation perennial ryegrass	*Lolium perenne 'Citation'*	Cool	Sod	247,000	3.0
Lincoln smooth brome	*Bromus inermis leyss 'Lincoln'*	Cool	Sod	130,000	3.0
Total					**7.5**

Temporary and Permanent Seeding (TS/PS) EC-2

Table TS/PS-2. Minimum Drill Seeding Rates for Perennial Grasses (cont.)

Common Name	Botanical Name	Growth Season[b]	Growth Form	Seeds/ Pound	Pounds of PLS/acre
Sandy Soil Seed Mix					
Blue grama	*Bouteloua gracilis*	Warm	Sod-forming bunchgrass	825,000	0.5
Camper little bluestem	*Schizachyrium scoparium 'Camper'*	Warm	Bunch	240,000	1.0
Prairie sandreed	*Calamovilfa longifolia*	Warm	Open sod	274,000	1.0
Sand dropseed	*Sporobolus cryptandrus*	Cool	Bunch	5,298,000	0.25
Vaughn sideoats grama	*Bouteloua curtipendula 'Vaughn'*	Warm	Sod	191,000	2.0
Arriba western wheatgrass	*Agropyron smithii 'Arriba'*	Cool	Sod	110,000	5.5
Total					**10.25**
Heavy Clay, Rocky Foothill Seed Mix					
Ephriam crested wheatgrass[d]	*Agropyron cristatum 'Ephriam'*	Cool	Sod	175,000	1.5
Oahe Intermediate wheatgrass	*Agropyron intermedium 'Oahe'*	Cool	Sod	115,000	5.5
Vaughn sideoats grama[e]	*Bouteloua curtipendula 'Vaughn'*	Warm	Sod	191,000	2.0
Lincoln smooth brome	*Bromus inermis leyss 'Lincoln'*	Cool	Sod	130,000	3.0
Arriba western wheatgrass	*Agropyron smithii 'Arriba'*	Cool	Sod	110,000	5.5
Total					**17.5**

[a] All of the above seeding mixes and rates are based on drill seeding followed by crimped straw mulch. These rates should be doubled if seed is broadcast and should be increased by 50 percent if the seeding is done using a Brillion Drill or is applied through hydraulic seeding. Hydraulic seeding may be substituted for drilling only where slopes are steeper than 3:1. If hydraulic seeding is used, hydraulic mulching should be done as a separate operation.

[b] See Table TS/PS-3 for seeding dates.

[c] If site is to be irrigated, the transition turf seed rates should be doubled.

[d] Crested wheatgrass should not be used on slopes steeper than 6H to 1V.

[e] Can substitute 0.5 lbs PLS of blue grama for the 2.0 lbs PLS of Vaughn sideoats grama.

EC-2 Temporary and Permanent Seeding (TS/PS)

Table TS/PS-3. Seeding Dates for Annual and Perennial Grasses

	Annual Grasses (Numbers in table reference species in Table TS/PS-1)		Perennial Grasses	
Seeding Dates	**Warm**	**Cool**	**Warm**	**Cool**
January 1–March 15			✓	✓
March 16–April 30	4	1,2,3	✓	✓
May 1–May 15	4		✓	
May 16–June 30	4,5,6,7			
July 1–July 15	5,6,7			
July 16–August 31				
September 1–September 30		8,9,10,11		
October 1–December 31			✓	✓

Mulch

Cover seeded areas with mulch or an appropriate rolled erosion control product to promote establishment of vegetation. Anchor mulch by crimping, netting or use of a non-toxic tackifier. See the Mulching BMP Fact Sheet for additional guidance.

Maintenance and Removal

Monitor and observe seeded areas to identify areas of poor growth or areas that fail to germinate. Reseed and mulch these areas, as needed.

An area that has been permanently seeded should have a good stand of vegetation within one growing season if irrigated and within three growing seasons without irrigation in Colorado. Reseed portions of the site that fail to germinate or remain bare after the first growing season.

Seeded areas may require irrigation, particularly during extended dry periods. Targeted weed control may also be necessary.

Protect seeded areas from construction equipment and vehicle access.

2N CIVIL
303.925.0544
www.2ncivil.com

PREPARED FOR:
BLACK FOREST, LLC
12740 BLACK FOREST ROAD
COLORADO SPRINGS, CO 80908

ESCD Details 1
CONSTRUCTION DOCUMENTS
BLACK FOREST OFFICE
COLORADO SPRINGS, COLORADO

DATE: 1-19-21
BY: TEW
REVISIONS:
1. EL PASO CNTY COMMENTS 1-7-21
2.
3.
4.

PROJECT NUMBER: 19015
ISSUED DATE: 12-03-2020
DESIGNED BY: TEW
REVIEWED BY: RCE

ESCD Details 1

J:\Projects\19\19015\dwg\Site Plan\8 ESCD Details 2.dwg 1/18/2021

BLACK FOREST OFFICE

N1/2 NE1/4 SE1/4 SE1/4 OF SECTION 07, TOWNSHIP 12 SOUTH, RANGE 65 WEST OF THE 6TH P.M., EL PASO COUNTY, COLORADO

SECTION A-A PROFILE
SCALE: (H) 1" = 20' (V) 1" = 4'
START STA: 0+00.00, END STA: 2+07.51

SECTION B-B PROFILE
SCALE: (H) 1" = 20' (V) 1" = 4'
START STA: 0+00.00, END STA: 0+80.77

Pay Item		Percent of Material Smaller Than Typical Stone[2]	Typical Stone Dimensions[3] (Inches)	Typical Stone Weight[4] (Pounds)
	Stone Size d50[1] (Inches)			
Riprap	9	70-100	15	160
		50-70	12	85
		35-50	9	35
		2-10	3	1.3

[1]d50 = nominal stone size
[2]based on typical rock mass
[3]equivalent spherical diameter
[4]based on a specific gravity = 2.5

POND MAINTENANCE ROAD DETAIL
N.T.S.

CLASSIFICATION FOR AGGREGATE BASE COURSE

Sieve Size	Mass Percent Passing Square Mesh Sieves						
	LL not greater than 35			LL not greater than 30			
	Class 1	Class 2	Class 3	Class 4	Class 5	Class 6	Class 7
150 mm (6")			100				
100 mm (4")		100					
75 mm (3")		95-100					
60 mm (2 ½")	100						
50 mm (2")	95-100			100			
37.5 mm (1 ½")				90-100	100		
25 mm (1")					95-100	100	100
19 mm (3/4")				50-90		95-100	
4.75 mm (#4)	30-65			30-50	30-70	30-65	
2.36 mm (#8)						25-55	20-85
75 µm (#200)	3-15	3-15	20 max	3-12	3-15	3-12	5-15
NOTE: Class 3 material shall consist of bank or pit run material.							

PIPE SIZE OR BOX HEIGHT	D	W*	L
18" – 24"	1'–0"	4'	15'
30" – 36"	1'–6"	6'	20'
42" – 48"	2'–0"	7'	24'
54" – 60"	2'–6"	8'	28'
66" – 72"	3'–0"	9'	32'

* IF OUTLET PIPE IS A BOX CULVERT WITH A WIDTH GREATER THAN W, THEN W = CULVERT WIDTH

LOW TAILWATER RIPRAP BASIN
N.T.S.

Section at Centerline

End View

PIPE DIA.	W	L	D
18"	2.50'	5.0'	18"
24"	3.00'	6.0'	18"
30"	4.00'	8.0'	18"

Concrete Flared End Section With Cutoff Wall

NOTES:
1. SOIL RIPRAP DETAILS ARE APPLICABLE TO SLOPED AREAS. REFER TO THE SITE PLAN ACTUAL LOCATION AND LIMITS.
2. MIX UNIFORM ALLY 65% RIPRAP BY VOLUME WITH 35% OF APPROVED SOIL BY VOLUME PRIOR TO PLACEMENT.
3. PLACE STONE-SOIL MIX TO RESULT IN SECURELY INTERLOCKED ROCK AT THE DESIGN THICKNESS AND GRADE. COMPACT AND LEVEL TO ELIMINATE ALL VOIDS AND ROCKS PROJECTING ABOVE DESIGN RIPRAP TOP GRADE.
4. CRIMP OR TACKIFY MULCH OR USE APPROVED HYDROMULCH AS CALLED FOR IN THE PLANS AND SPECIFICATIONS.

TYPICAL SECTION - SOIL RIPRAP WITH MULCH

STORM - POND OUTFALL PROFILE
SCALE: (H) 1" = 20' (V) 1" = 4'
START STA: 0+00.00, END STA: 0+49.44

STORM PROFILE
SCALE: (H) 1" = 20' (V) 1" = 4'
START STA: 0+00.00, END STA: 0+47.44

2N CIVIL
303.925.0544
www.2ncivil.com

PREPARED FOR:
BLACK FOREST, LLC
12740 BLACK FOREST ROAD
COLORADO SPRINGS, CO 80908

Pond Details
CONSTRUCTION DOCUMENTS
BLACK FOREST OFFICE
COLORADO SPRINGS, COLORADO

BY: TEW DATE: 1-19-21

REVISIONS:
1. EL PASO CNTY COMMENTS 1-7-21
2.
3.
4.

PROJECT NUMBER: 19015
ISSUED DATE: 12-03-2020
DESIGNED BY: TEW
REVIEWED BY: RCE

Pond Details

J:\Projects\19\19015\dwg\Drainage\Outlet Structure Details.dwg 1/18/2021

BLACK FOREST OFFICE

N1/2 NE1/4 SE1/4 SE1/4 OF SECTION 07, TOWNSHIP 12 SOUTH, RANGE 65 WEST OF THE 6TH P.M., EL PASO COUNTY, COLORADO

OUTLET STRUCTURE SECTION VIEW
NTS

PROFILE
NTS

SECTION A
NTS

ELEVATION

ORIFICE PLATE NOTES:

1. PROVIDE CONTINUOUS NEOPRENE GASKET MATERIAL BETWEEN THE ORIFICE PLATE AND CONCRETE.
2. BOLT PLATE TO CONCRETE 12" MAX. ON CENTER. SEE TABLE OS–2 FOR PLATE THICKNESS.

EURV AND WQCV TRASH RACKS:

1. WELL–SCREEN TRASH RACKS SHALL BE STAINLESS STEEL AND SHALL BE ATTACHED BY INTERMITTENT WELDS ALONG THE EDGE OF THE MOUNTING FRAME.
2. BAR GATE TRASH RACKS SHALL BE ALUMINUM AND SHALL BE BOLTED USING STAINLESS STEEL HARDWARE.
3. TRASH RACK OPEN AREAS ARE FOR SPECIFIED TRASH RACK MATERIALS. TOTAL TRASH RACK SIZE MAY NEED TO BE ADJUSTED FOR MATERIALS HAVING DIFFERENT OPEN AREA/GROSS AREA RATIO (R VALUE).
4. STRUCTURAL DESIGN OF TRASH RACKS SHALL BE BASED ON FULL HYDROSTATIC HEAD WITH ZERO HEAD DOWNSTREAM OF THE RACK.

OVERFLOW SAFETY GRATES:

1. ALL SAFETY GRATES SHALL BE MOUNTED USING STAINLESS STEEL HARDWARE AND PROVIDED WITH HINGED AND LOCKABLE OR BOLTABLE ACCESS PANELS.
2. SAFETY GRATES SHALL BE STAINLESS STEEL, ALUMINUM, OR STEEL. STEEL GRATES SHALL BE HOT DIP GALVANIZED AND MAY BE HOT POWDER COATED AFTER GALVANIZING.
3. SAFETY GRATES SHALL BE DESIGNED SUCH THAT THE DIAGONAL DIMENSION OF EACH OPENING IS SMALLER THAN THE DIAMETER OF THE OUTLET PIPE.
4. STRUCTURAL DESIGN OF SAFETY GRATES SHALL BE BASED ON FULL HYDROSTATIC HEAD WITH ZERO HEAD DOWNSTREAM OF THE RACK.

FIGURE OS–4 ORIFICE PLATE AND TRASH RACK DETAILS AND NOTES
NTS

SECTION B
NTS

SECTION C
NTS

R VALUE = (NET OPEN AREA)/(GROSS RACK AREA) = 0.60

SECTION D
NTS

FIGURE OS–5 TYPICAL OUTLET STRUCTURE WITH WELL SCREEN TRASH RACK

SECTION A–A
N.T.S.

SECTION B–B
N.T.S.

IMPACT BASIN
N.T.S.

TRICKLE CHANNEL

POND SIGNAGE
N.T.S.

(TO BE ATTACHED TO THE OUTLET BOX OR POSTED NEARBY)

EMERGENCY SPILLWAY
NTS

2N CIVIL
303.925.0544
www.2ncivil.com

PREPARED FOR:
BLACK FOREST, LLC
12740 BLACK FOREST ROAD
COLORADO SPRINGS, CO 80908

Outlet Structure Details
CONSTRUCTION DOCUMENTS
BLACK FOREST OFFICE
COLORADO SPRINGS, COLORADO

BY:	DATE:
TEW	1-19-21

REVISIONS:
1. EL PASO CNTY COMMENTS 1-7-21
2.
3.
4.

PROJECT NUMBER:	19015
ISSUED DATE:	12-03-2020
DESIGNED BY:	TEW
REVIEWED BY:	RCE

Outlet Structure Details

J:\Projects\19150\15dwg\Drainage\Outlet Structure Details.dwg 1/18/2021