



ORIGINAL PERMIT APPLICANT(S)

BLACK FOREST LLC

APPROVED WELL LOCATION

Water Division: 2 Water District: 10
Designated Basin: N/A
Management District: N/A
County: EL PASO
Parcel Name: N/A
Physical Address: 12740 BLACK FOREST ROAD COLORADO
SPRINGS, CO 80908

SE 1/4 SE 1/4 Section 7 Township 12.0 S Range 65.0 W Sixth P.M.

UTM COORDINATES (Meters, Zone: 13, NAD83)

Easting: 525861.7 Northing: 4318597.5

PERMIT TO REPLACE EXISTING WELL

ISSUANCE OF THIS PERMIT DOES NOT CONFER A WATER RIGHT
CONDITIONS OF APPROVAL

- 1) This well shall be used in such a way as to cause no material injury to existing water rights. The issuance of this permit does not ensure that no injury will occur to another vested water right or preclude another owner of a vested water right from seeking relief in a civil court action.
- 2) The construction of this well shall be in compliance with the Water Well Construction Rules 2 CCR 402-2, unless approval of a variance has been granted by the State Board of Examiners of Water Well Construction and Pump Installation Contractors in accordance with Rule 18.
- 3) Approved pursuant to CRS 37-92-602(3)(c) for the relocation of an existing well, permit no. 168912. The old well must be plugged in accordance with Rule 16 of the Water Well Construction Rules within ninety-one (91) days of completion of the new well. The enclosed Well Abandonment Report form must be completed and submitted to affirm that the old well was plugged.
- 4) Approved as the only well on a tract of land of 4.77 acres described as the N 1/2 of the NE 1/4 of the SE 1/4 of the SE 1/4 of Sec. 7, Twp. 12 S, Rng. 65 W, Sixth P.M., El Paso County.
- 5) The use of ground water from this well is limited to drinking and sanitary facilities as described in CRS 37-92-602(1)(c), for a commercial business. Water from this well shall not be used for lawn/landscape/greenhouse irrigation, domestic animal/livestock watering, or for any other purpose outside the business building structure(s).
- 6) The pumping rate of this well shall not exceed 15 GPM.
- 7) The annual amount of ground water to be withdrawn by this well shall not exceed 1/3 acre-foot (108,600 gallons).
- 8) The total depth of the well shall not exceed 690 feet, which corresponds to the base of the Dawson aquifer. At a minimum, plain casing shall be installed and grouted through all unconsolidated materials and shall extend a minimum of ten feet into the bedrock formation to prevent production from other zones.
- 9) The return flow from the use of this well must be through an individual waste water disposal system of the non-evaporative type where the water is returned to the same stream system in which the well is located.
- 10) A totalizing flow meter must be installed on this well and maintained in good working order. Permanent records of all diversions must be maintained by the well owner (recorded at least annually) and submitted to the Division Engineer upon request.
- 11) This well shall be constructed not more than 200 feet from the location specified on this permit.

NOTE: At the proposed well location, the Dawson aquifer is located at or near the ground surface and extends to a depth of approximately 690 feet. Wells completed in the Dawson aquifer must be constructed in accordance with Well Construction Rule 10.4.6 (2 CCR 402-2) for a Type II aquifer.

NOTE: This permit will expire on the expiration date unless the well is constructed by that date. A Well Construction and Yield Estimate Report (GWS-31) must be submitted to the Division of Water Resources to verify the well has been constructed. An extension of the expiration date may be available. Contact the DWR for additional information or refer to the extension request form (GWS-64) available at: <http://www.water.state.co.us>

WELL PERMIT NUMBER 168912--A

RECEIPT NUMBER 3695886



Date Issued: 12/23/2019

Issued By SHANNON PORTER

Expiration Date: 12/23/2021