



EL PASO COUNTY PLANNING & COMMUNITY DEVELOPMENT  
SIGN APPLICATION

SC-18-068

DATE: 01/08/2018

**Business**

Name: RHINO'S RANCH SALOON  
Address: 5853 Palmer Park Blvd.  
Colorado Springs, CO 80915

Zone: CR CAD-O  
Legal Description:  
LOT 1 POWERS CENTRE  
FIL NO 3

**Type of Sign**

Illuminated: YES  
Non-Illuminated: N/A  
Valuation: \$5,687.75

Storefront Length &/or  
Width: 87 FT

Proposed Sign Sq. Ft. 27.38

Existing Sign Sq. Ft. N/A

Total Sign Sq. Ft. 27.38

**Contractor Information**

Name: Sign Shop Illuminated

Address: 3505 E. Platte Ave.  
Colorado Springs, CO

Phone: 719.573.1567

Type of License: D5A

Contractor ID# 13325

**Vicinity Map**

Tax Schedule # 5406304050  
Please show major intersections.



**Elevation Drawing**

Indicate storefront length & placement of sign.



**Sign Plan**

(Please indicate dimensions and sign copy)

The location of the disconnect switch after installation shall comply with Article 600.6 (A) (1) of the National Electrical Code

LOGO SIGN MEASUREMENTS CALLED OUT IN RED  
SALOON SIGN MEASUREMENTS CALLED OUT IN GREEN  
OVERALL LENGTH CALLED OUT IN BLUE

LOGO: 13 SQFT  
SALOON: 14.38 SQFT

Property Frontage: 27.38  
Sqft: 27.38  
Storefront: 87  
Elevation: 18

**SIGN TYPE** Channel Letters  
**QUANTITY** 1  
**FACES** 7  
**MATERIAL SPECIFICATIONS**  
**FACES** Acrylic  
☒ Red  
☐  
☐  
**TRIM CAP** 3/4"  
☒ Black  
☐  
**RETURNS** 4" DEEP  
☒ Black  
☐  
**OVERLAY**  
☐  
☐  
☐  
**RACEWAYS** 8"  
☒ Painted to match Building  
☐

**Raceway Mount Detail**  
5" Deep channel letter  
1" Trimcap with screws  
3/16" acrylic face  
LED illumination  
Wall fasteners  
Class II supply wire  
Power supply installed in raceway  
.063 Aluminum Letter Backs  
4" raceway  
Disconnect Switch  
Weep holes

**WEST ELEVATION PROPOSED**  
TOTAL SQFT: 27.38

**SignShop Illuminated**  
Open Full Service Sign Company

**Client Information**  
Rhino's Ranch Saloon  
Gregory Roman  
719-229-7464  
garoman29@yahoo.com

**Job Location**  
5853 Palmer Park Blvd.  
Colorado Springs, CO

**CLIENT APPROVAL** Signed \_\_\_\_\_ Date \_\_\_\_\_  
**LANDLORD APPROVAL** Signed \_\_\_\_\_ Date \_\_\_\_\_

This design is the exclusive property of Sign Shop Illuminated, LLC and any reproduction or other use is strictly prohibited. All rights reserved.

led at site - Letters should be assembled and mounted as shown-Use only mounting hardware and transformer enclosures provided-Only UL Listed metallic conduit for HV wiring, EMT, flexible metal, etc.-Ground wire must be run for lengths longer than 100' Locate transformers inside, accessible to local inspectors. Suitable for dry/damp/wet conditions.

Page 1 of 1  
Drawing by JW  
Date November 15, 2018

Approved Date: \_\_\_\_\_ Resubmittal? Yes \_\_\_\_\_ No \_\_\_\_\_

Denied Date: \_\_\_\_\_

Comments: A bar is an allowed use in the CR zoning district.  
1.5 sq ft/frontage=130 sq ft allowed.

Fee of \$262.00 must accompany this Application. Additional signs at time of first Application are \$125.00. Make checks payable to El Paso County.