

Approved

by Jeff Rice

El Paso County Planning and Community Development
on behalf of Elizabeth Nijkamp, Engineering Review Manager

10/01/2021 12:00:10 PM



Geotechnical Pavement Section Design



Curtis Road and Davis Road

3050 Curtis Road

Peyton, Colorado

ProTeX Job No.: 8619

PCD File No. MS-19-006



1102 W Southern Ave, Ste 4 / Tempe, Arizona 85282-3102 / (o) 602-272-PTX1 (7891)

Dispatch 602-272-7890 / (f) 602-272-7892

www.protex-az.com

Curtis Road and Davis Road
3050 Curtis Road
Peyton, Colorado
ProTeX Job No.: 8619



January 13, 2019
(Revision 1, August 16, 2021 – Additional Roadway Surface Option)
(Revision 2, September 23, 2021 – Additional edits per Client/County request)

Home Run Restorations, Inc.

Re: **Geotechnical – Pavement Section Design**

Project: Curtis Road and Davis Road
3050 Curtis Road
Peyton, Colorado

ProTeX Job No.: 8619

Attention: Mr. Shawn Shaffer

At your request, ProTeX has completed a soil investigation for the subject project. The accompanying report includes field observations and laboratory testing supporting our conclusions and recommendations for the proposed development.

Respectfully submitted,
ProTeX - the PT Xperts, LLC



Date Expires: 10/31/2021
Thomas M. Perkins, P.E.

Curtis Road and Davis Road
3050 Curtis Road
Peyton, Colorado
ProTeX Job No.: 8619



TABLE OF CONTENTS

| | | |
|------------|---|----------|
| 1.0 | INTRODUCTION..... | 1 |
| 1.1 | Scope | 1 |
| 1.2 | Proposed Site Development..... | 1 |
| 1.3 | Terms and Conditions..... | 1 |
| 2.0 | FIELD AND LABORATORY TESTING | 1 |
| 2.1 | Geotechnical Site Reconnaissance | 1 |
| 2.2 | Field Investigation | 2 |
| 2.3 | Laboratory Testing..... | 2 |
| 2.4 | Potential for Soil Expansion (One-Dimensional Expansion Potential)..... | 3 |
| 3.0 | RECOMMENDATIONS | 3 |
| 3.1 | Pavement Section Recommendations..... | 3 |
| 3.1.1 | Projected Traffic..... | 3 |
| 3.1.2 | Pavement Design Analysis | 4 |
| 4.0 | CLOSURE | 5 |
| 4.1 | Limitations | 5 |
| 4.2 | Recommended Additional Services..... | 1 |

APPENDICES

Appendix A – Laboratory Test Results

R-Value
Grain Size Distribution Curve and Atterberg Limits

Appendix B – Site Information

Site Plan

Appendix C – Boring Logs

Test Pit Excavations



1.0 INTRODUCTION

1.1 Scope

ProTeX was retained by Home Restorations, Inc. to evaluate the subsurface soil conditions with respect to a proposed low volume rural roadway pavement section design for the project known as 3050 Curtis Road. The contents of this report include the findings from the field exploration and laboratory testing, with supporting recommendations for the proposed development.

1.2 Proposed Site Development

It is this firm's understanding that the proposed development will consist of:

- Four (4) individual residential home sites
- Paved section of road that provides access to the lots
- Rural gravel access to the lots

It is anticipated the proposed roadway(s) will have low volume traffic and light to moderate vehicle loads.

1.3 Terms and Conditions

This report was prepared for Home Restorations, Inc. The contents of this report may not be relied upon by any other party without the expressed written permission of ProTeX - the PT Xperts, LLC and the written permission of Home Restorations, Inc. The report presents site conditions at the time of the investigation and for the aforementioned proposed development. The report should be updated prior to construction if a maximum of one year has elapsed from the issued date.

2.0 FIELD AND LABORATORY TESTING

2.1 Geotechnical Site Reconnaissance

The site consists of approximately 36 acres of located at 3050 Curtis Road in Peyton, Colorado. At the time of the field site visit on December 17, 2018 the following site conditions were observed:

- Grading of the custom residential homes were in progress as well as rough grading of proposed rural access



2.2 Field Investigation

A total of 2 test holes (test holes TP1 and TP2) were completed within the proposed roadways alignment for the purpose of pavement section design. The soils were sampled at the anticipated depth of the proposed roadway. At each test hole location, the soils encountered were visually observed, classified, logged and representative samples were obtained where applicable. Refer to the site plan in Appendix B for approximate test hole locations.

2.3 Laboratory Testing

Subsequent to the field investigation, soil samples were submitted for laboratory testing. Tests were performed to determine the following:

- **Sieve Analysis and Atterberg Limits**- Used for formal classification of soils in general accordance with the Unified Soil Classification System (USCS) per ASTM Test Method D2487 and AASHTO Soil Classification System. Sieve analysis is performed in general accordance with AASHTO Test Methods T11 and T27. The Atterberg Limits were determined in general accordance with AASHTO Test Method T11 and T27.
- **Resistance Value (R-Value)** – The R-Value test procedure expresses a material’s resistance to deformation as a function of the ratio of the transmitted lateral pressure to applied vertical pressure in general accordance to ASTM D2844. Subgrade materials tested are assigned an R-Value for the purpose of pavement section design analysis.
- **Moisture Content** – The moisture content of the soil was tested in general accordance to AASHTO T 265.

Laboratory Test Summary

| Location | Depth (ft) | Plasticity Index | % Passing #200 | Moisture Content (%) | USCS Soil Classification | AASHTO Soil Classification | Tested R-Value |
|----------|------------|------------------|----------------|----------------------|--------------------------|----------------------------|----------------|
| TP1 | 1-3 | NP | 26 | 4.2 | SM | A-2-5 | 76 |
| TP1 | 8-10 | 6 | 30 | 5.1 | SC-SM | A-2-5 | - |
| TP2 | 1-3 | NP | 17 | 3.6 | SM | A-2-5 | - |
| TP2 | 3-5 | NP | 20 | 3.5 | SM | A-2-5 | - |

See Appendix A for a detailed compilation of the laboratory test results.

Curtis Road and Davis Road
3050 Curtis Road
Peyton, Colorado
ProTeX Job No.: 8619



2.4 Potential for Soil Expansion (One-Dimensional Expansion Potential)

The expansion potential (Swell) of the subgrade soils, sampled from the rural roadway, was not tested due to soil properties (Plasticity Index and Percent Passing the #200 Sieve) which are designated in the Section D.2.4. in the El Paso County Engineering Appendix D – Pavement Design Criteria and Report. **The plasticity index of soils evaluated as a part of this design did not exceed 10; therefore, mitigation measures such as stabilization or treatment of subgrade soils is not required.**

3.0 RECOMMENDATIONS

The recommendations contained herein are based on the findings of the field investigation, laboratory test results and local experience.

3.1 Pavement Section Recommendations

The pavement recommendations have been prepared in accordance with most current edition of El Paso County Engineering Appendix D – Pavement Design Criteria and Report (Revised 12/13/2016) Sections D.1 to D.5.

3.1.1 Projected Traffic

The projected traffic volumes/loads for pavement section design analysis, accounts for the year of the intended completion of the proposed development including construction traffic through build-out. The following anticipate Design ESAL for pavement section design and was anticipated based on the size and location of development and surrounding roadways. The design ESAL value for Local Roadways is designated in the Engineering Criteria Manual (ECM) Table D-2. Minimum Pavement Sections for El Paso County MuniCode (see below).

| Roadway Classifications | Design ESAL |
|--------------------------------------|--------------------|
| Paved Access Roadway for Custom Lots | 36, 500 |

Curtis Road and Davis Road
 3050 Curtis Road
 Peyton, Colorado
 ProTeX Job No.: 8619



3.1.2 Pavement Design Analysis

The design for the project were determined from surface soils properties within the proposed roadways, design parameters and structural coefficients provided in the El Paso County Engineering Design Criteria:

Low Volume Rural Custom Home Access Roadway:

| | |
|--|-------------|
| Analysis Period | 20 years |
| Change in Serviceability Factor | 2.0 |
| Seasonal Variation Factor (SVF) | 3.2 |
| *Design R-value | 76 |
| Resilient Modulus | 27,185 psi |
| Reliability | 75% |
| Combined Standard Error | 0.45 |
| Structural Coefficients | |
| Gravel | 0.18 |
| Hot Mix Asphalt | 0.44 |
| **Aggregate Base Course/Recycled Concrete | 0.11 |
| W ₁₈ - Equivalent Single Axle Load (ESAL) | 36,500 |
| Calculated SN (Structural Number) | 1.09 |

**Design R-value is based on actual tested R-values according to ASTM D2844*

***Materials must meet the requirements in Section D.5.5.I of El Paso County, Colorado - Engineering Criteria Manual.*

Low Volume Rural Asphaltic Concrete Roadway:

| Asphaltic Concrete Roadway for the Custom Home Lots | |
|---|-----------|
| Required Structural Number | 1.09 |
| Hot Mix Asphalt | 3 inches* |
| Aggregate Base Course/Recycled Concrete | 4 inches* |
| Actual Structural Number | 1.76 |

**Minimum allowable thickness per Table D-2 of El Paso County, Colorado - Engineering Criteria Manual.*

Low Volume Rural Gravel Roadway:

| Gravel Access Roadway for the Custom Home Lots | |
|--|-----------|
| Gravel for Gravel Roadway | 6 inches* |
| Processed/Compacted Native Subgrade | 6 inches |

**Gravel for Roadway must meet Requirements in Table D-7 of the El Paso County Engineering Criteria Manual*



El Paseo County Engineering Criteria Manual Table D-7. Gravel for Gravel Roads

| <i>Sieve Designation</i> | <i>Percent Passing by Weight</i> |
|---------------------------|----------------------------------|
| ¾" | 100 |
| #4 | 50-78 |
| #8 | 37-67 |
| #40 | 13-35 |
| #200 | 0-15 4-15 |
| Plastic Index (PI) | |
| | 4—12 |

Pavement materials and placement should conform to the County of El Paso, Colorado specifications. In no case, should pavement surfacing be placed on unstable wet subgrade. Care should be taken with regard to parkway grading, placement of landscape vegetation and irrigation systems to minimize moisture infiltration in subgrade soils below pavement sections.

4.0 CLOSURE

4.1 Limitations

The recommendations contained in this report are based on the assumption that the subsurface conditions do not deviate appreciably from those disclosed by the test holes. Should unusual material or conditions be encountered during construction, the ProTeX geotechnical engineer should be notified to make supplemental recommendations as deemed necessary. This report is issued with the understanding that it is the responsibility of the owner to see that its provisions are carried out or brought to the attention of those concerned. The scope of services for this project does not include any environmental assessment of the site or identification of contaminated or hazardous materials or conditions.

The findings of this report are considered valid as of the present date. However, changes in the conditions of the site can occur with the passage of time, whether due to natural events or to human activities on this or adjacent sites. In addition, changes in applicable or appropriate codes and standards may occur, whether they result from legislation or the broadening of knowledge. Accordingly, this report may become invalidated wholly or partially by changes outside our control. Therefore, this report is subject to review and revision as changed conditions are identified.

Curtis Road and Davis Road
3050 Curtis Road
Peyton, Colorado
ProTeX Job No.: 8619



4.2 Recommended Additional Services

The recommendations provided in this report are based on the assumption that a testing plan will be implemented with an adequate schedule of testing to ensure that the construction process meets the recommendations/specifications presented in this report. The testing and observation should be performed under the direction of the ProTeX Geotechnical Engineer/representative and should include, but not necessarily be limited to the following:

1. Approve and document that fill material used as engineered fill in pavement areas meets the specifications.
2. Monitor and test placement of fill soils in pavement locations to verify and document conformance with project specifications.

Appendix A

LABORATORY SERVICES REPORT

Report Number: 65151173.0043
Service Date: 01/04/19
Report Date: 01/09/19
Task:



4685 S Ash Ave, Ste H-4
Tempe, AZ 85282-6767
480-897-8200

Client

ProTeX
Attn: Jeff Ritter
1102 W. Southern Ave, Ste. 4
Tempe, AZ 85282

Project

ProTeX Protex Job # 3050 Curtis Rd.
In House - Terracon Tempe Lab
Tempe, AZ

Project No. 65151173

Material Description: Silty Sand

Sample Location: TP-1 @ 0'-3'


Lab Number: 2362

Sample Source: Job #3050 Curtis Rd

RESISTANCE R-VALUE AND EXPANSION PRESSURE OF COMPACTED SOILS (ASTM D2844)

| SPECIMEN I. D. | A | B | C |
|------------------------------|-------|-------|-------|
| Moisture Content | 11.4% | 10.5% | 9.7% |
| Compaction Pressure (psi) | 350 | 350 | 350 |
| Specimen Height (inches) | 2.51 | 2.50 | 2.52 |
| Dry Density (pcf) | 118.5 | 119.5 | 119.8 |
| Horiz. Pres. @ 1000lbs (psi) | 16.0 | 13.0 | 12.0 |
| Horiz. Pres. @ 2000lbs (psi) | 28.0 | 22.0 | 20.0 |
| Displacement | 4.35 | 4.25 | 4.13 |
| Expansion Pressure (psi) | 0.0 | 0.0 | 0.0 |
| Exudation Pressure (psi) | 212 | 428 | 796 |
| R Value | 73 | 79 | 81 |

R-Value:
76



Services:

Terracon Rep: Joseph Menezes

Reported To:

Contractor:

Report Distribution

(1) ProTeX, Emailed

(1) ProTeX, Engineering Department

Reviewed By:

Clifford Metz

Laboratory Manager

The tests were performed in general accordance with applicable ASTM, AASHTO, or DOT test methods. This report is exclusively for the use of the client indicated above and shall not be reproduced except in full without the written consent of our company. Test results transmitted herein are only applicable to the actual samples tested at the location(s) referenced and are not necessarily indicative of the properties of other apparently similar or identical materials.



ProTeX the PT Xperts LLC
 1102 W. Southern Ave., Ste. 4 Office: (602)-272-7891
 Tempe, AZ 85282 Fax: (602) 272-7892

Soils Summary

Client: Home Run Restorations, Inc.
 Project Name: Curtis Rd and Davis Rd
 Job Name: 3050 Curtis Rd
 Material: Geo samples - Native (On-site)
 Material Supplier: _____
 Sample Location: TP1 (1-3')

ProTeX Job No: 8619
 ProTeX Lab No: 190007 - Phoenix
 Date Received: 1/2/2019
 Sampled By: Tim C Pachak
 Date Sampled: 12/17/2018
 Submitted By: Spencer Drenth

| AASHTO T89/T90 | |
|------------------|----|
| Plasticity Index | |
| Liquid Limit | NV |
| Plastic Limit | NP |
| Plasticity Index | NP |

| Expansion Index, (EI) | Potential Expansion | Expansion Index |
|-----------------------|---------------------|-----------------|
| 0 - 20 | Very Low | |
| 21 - 51 | Low | |
| 52 - 90 | Medium | |
| 91 - 130 | High | |
| > 130 | Very High | |

| Percent Swell of Soil | |
|-----------------------|----|
| % Swell | NV |
| Notes: | |

| pH and Resistivity | |
|-----------------------|----|
| pH Reading: | NA |
| Resistivity (ohms-cm) | NA |

| Moisture Density (Proctor) | |
|----------------------------|----|
| Max. Dry Density | NV |
| Opt. Moisture % | NV |
| Corr. Max. Dry Density | NV |
| Corr. Opt. Moisture % | NV |
| % Rock | 0 |

Class: Silty sand
 Symbol: SM

* = out of specification

| AASHTO T11/T27 | | | |
|----------------|--------|-------|---|
| Sieve | % Pass | Specs | * |
| 1" | 100 | | |
| 1/2" | 100 | | |
| #4 | 100 | | |
| #10 | 98 | | |
| #40 | 75 | | |
| #100 | 41 | | |
| #200 | 26 | | |

Remarks:

Reviewed By:

Jerald W Grossarth



ProTeX the PT Xperts LLC
 1102 W. Southern Ave., Ste. 4 Office: (602)-272-7891
 Tempe, AZ 85282 Fax: (602) 272-7892

Soils Summary

Client: Home Run Restorations, Inc.
 Project Name: Curtis Rd and Davis Rd
 Job Name: 3050 Curtis Rd
 Material: Geo samples - Native (On-site)
 Material Supplier: _____
 Sample Location: TP1 (10')

ProTeX Job No: 8619
 ProTeX Lab No: 190008 - Phoenix
 Date Received: 1/2/2019
 Sampled By: Tim C Pachak
 Date Sampled: 12/17/2018
 Submitted By: _____

| AASHTO T89/T90 | |
|------------------|-----------|
| Plasticity Index | |
| Liquid Limit | 25 |
| Plastic Limit | 19 |
| Plasticity Index | 6 |

| Expansion Index, (EI) | Potential Expansion | Expansion Index |
|-----------------------|---------------------|-----------------|
| 0 - 20 | Very Low | |
| 21 - 51 | Low | |
| 52 - 90 | Medium | |
| 91 - 130 | High | |
| > 130 | Very High | |

| Percent Swell of Soil | |
|-----------------------|-----------|
| % Swell | NV |
| Notes: | |

| pH and Resistivity | |
|-----------------------|-----------|
| pH Reading: | NA |
| Resistivity (ohms-cm) | NA |

| Moisture Density (Proctor) | |
|----------------------------|-----------|
| Max. Dry Density | NV |
| Opt. Moisture % | NV |
| Corr. Max. Dry Density | NV |
| Corr. Opt. Moisture % | NV |
| % Rock | 1 |

Class: Silty, clayey sand

Symbol: SC-SM

* = out of specification

| AASHTO T11/T27 | | | |
|----------------|--------|-------|---|
| Sieve | % Pass | Specs | * |
| 1" | 100 | | |
| 1/2" | 100 | | |
| #4 | 99 | | |
| #10 | 97 | | |
| #40 | 73 | | |
| #100 | 43 | | |
| #200 | 30 | | |

Remarks:

Reviewed By:

Jerald W Grossarth



ProTeX the PT Xperts LLC
 1102 W. Southern Ave., Ste. 4 Office: (602)-272-7891
 Tempe, AZ 85282 Fax: (602) 272-7892

Soils Summary

Client: Home Run Restorations, Inc.
 Project Name: Curtis Rd and Davis Rd
 Job Name: 3050 Curtis Rd
 Material: Geo samples - Native (On-site)
 Material Supplier: _____
 Sample Location: TP2 (1-3')

ProTeX Job No: 8619
 ProTeX Lab No: 190009 - Phoenix
 Date Received: 1/2/2019
 Sampled By: Tim C Pachak
 Date Sampled: 12/17/2018
 Submitted By: _____

| AASHTO T89/T90 | |
|------------------|----|
| Plasticity Index | |
| Liquid Limit | NV |
| Plastic Limit | NP |
| Plasticity Index | NP |

| Expansion Index, (EI) | Potential Expansion | Expansion Index |
|-----------------------|---------------------|---|
| 0 - 20 | Very Low | |
| 21 - 51 | Low | EI = NA |
| 52 - 90 | Medium | |
| 91 - 130 | High | |
| > 130 | Very High | |

| Percent Swell of Soil | |
|-----------------------|----|
| % Swell | NV |
| Notes: | |

| pH and Resistivity | |
|-----------------------|----|
| pH Reading: | NA |
| Resistivity (ohms-cm) | NA |

| Moisture Density (Proctor) | |
|----------------------------|----|
| Max. Dry Density | NV |
| Opt. Moisture % | NV |
| Corr. Max. Dry Density | NV |
| Corr. Opt. Moisture % | NV |
| % Rock | 1 |

Class: Silty gravel
 Symbol: GM

* = out of specification

| AASHTO T11/T27 | | | |
|----------------|--------|-------|---|
| Sieve | % Pass | Specs | * |
| 1" | 100 | | |
| 1/2" | 100 | | |
| #4 | 99 | | |
| #10 | 96 | | |
| #40 | 76 | | |
| #100 | 32 | | |
| #200 | 17 | | |

Remarks:

Reviewed By:

Jerald W Grossarth



ProTeX the PT Xperts LLC
 1102 W. Southern Ave., Ste. 4 Office: (602)-272-7891
 Tempe, AZ 85282 Fax: (602) 272-7892

Soils Summary

Client: Home Run Restorations, Inc.
 Project Name: Curtis Rd and Davis Rd
 Job Name: 3050 Curtis Rd
 Material: Geo samples - Native (On-site)
 Material Supplier: _____
 Sample Location: TP2 (5')

ProTeX Job No: 8619
 ProTeX Lab No: 190010 - Phoenix
 Date Received: 1/2/2019
 Sampled By: Tim C Pachak
 Date Sampled: 12/17/2018
 Submitted By: _____

| AASHTO T89/T90 | |
|------------------|----|
| Plasticity Index | |
| Liquid Limit | NV |
| Plastic Limit | NP |
| Plasticity Index | NP |

| Expansion Index, (EI) | Potential Expansion | Expansion Index EI = NA |
|-----------------------|---------------------|--|
| 0 - 20 | Very Low | |
| 21 - 51 | Low | |
| 52 - 90 | Medium | |
| 91 - 130 | High | |
| > 130 | Very High | |

| Percent Swell of Soil | |
|-----------------------|----|
| % Swell | NV |
| Notes: | |

| pH and Resistivity | |
|-----------------------|----|
| pH Reading: | NA |
| Resistivity (ohms-cm) | NA |

| Moisture Density (Proctor) | |
|----------------------------|----|
| Max. Dry Density | NV |
| Opt. Moisture % | NV |
| Corr. Max. Dry Density | NV |
| Corr. Opt. Moisture % | NV |
| % Rock | 1 |

Class: Silty sand
 Symbol: SM

* = out of specification



| AASHTO T11/T27 | | | |
|----------------|--------|-------|---|
| Sieve | % Pass | Specs | * |
| 1" | 100 | | |
| 1/2" | 100 | | |
| #4 | 99 | | |
| #10 | 96 | | |
| #40 | 77 | | |
| #100 | 35 | | |
| #200 | 20 | | |

Remarks:


Reviewed By:

Jerald W Grossarth

Appendix B



Legend:



Site Plan

Scale: N.T.S.

Drawn by: KJN

Date: 09/30/2021

Curtis Road and Davis Road
 3050 Curtis Road
 El Paso County, Colorado



ProTeX Job No.: 8619

Appendix C



LOG OF BORING No. TP1

PROJECT: Curtis Road and David Road **PROJECT NO.:** 8619
CLIENT: Home Run Restorations, Inc.
PROJECT LOCATION: 3050 Curtis Road
LOCATION: See site map **ELEVATION:** _____
DRILLER: Onsite Contractor Backhoe **LOGGED BY:** TP
DRILLING METHOD: Backhoe **DATE:** 12/17/18
DEPTH TO - WATER> INITIAL: ∅ **AFTER 24 HOURS:** ∅ **CAVING>** C

This information pertains only to this boring and should not be interpreted as being indicative of the site.

| Depth (feet) | Description | Graphic | Sample No. | Blow Counts | % < #200 | TEST RESULTS | |
|--------------|---|---------|------------|-------------|----------|-------------------|--------------|
| | | | | | | Plastic Limit | Liquid Limit |
| | | | | | | Water Content - ● | |
| | | | | | | Penetration - ▨ | |
| | | | | | | 10 20 30 40 50 | |
| 0 | (SM) Silty Sand, non-plastic, brown, slightly damp | | 90007 | 26 | | | |
| 2.5 | | | | | | | |
| 5 | | | | | | | |
| 7.5 | | | | | | | |
| 8-10 | (SC-SM) Silty Clayey Sand, low plasticity, brown, slightly damp | | 90008 | 30 | | | |
| 10 | Boring terminated at 10 ft. | | | | | | |
| 12.5 | | | | | | | |
| 15 | | | | | | | |
| 17.5 | | | | | | | |

