

# **DRAINAGE LETTER REPORT**

**for**


**STRUTHERS RANCH POLARIS  
847 STRUTHERS RANCH ROAD  
LOTS 1-2, STRUTHERS RANCH SUBDIVISION FILING NO. 4**

**Prepared for:**

**Hammers Construction, Inc.**  
1411 Woolsey Heights  
Colorado Springs, CO 80915

August 10, 2022  
Revised October 21, 2022  
Revised February 21, 2023

**Prepared by:**



**19 E. Willamette Ave.  
Colorado Springs, CO 80903  
(719)-477-9429  
[www.jpsengr.com](http://www.jpsengr.com)**

**JPS Project No. 032203  
PCD Filing No. PPR2248**

**STRUTHERS RANCH POLARIS  
DRAINAGE LETTER REPORT  
TABLE OF CONTENTS**

	<u>PAGE</u>
DRAINAGE STATEMENT .....	i
I. INTRODUCTION .....	1
II. EXISTING / PROPOSED DRAINAGE CONDITIONS .....	2
III. DRAINAGE PLANNING FOUR STEP PROCESS.....	5
IV. FLOODPLAIN IMPACTS.....	5
V. STORMWATER DETENTION AND WATER QUALITY .....	6
VI. PUBLIC IMPROVEMENTS / DRAINAGE BASIN FEES .....	7
VII. SUMMARY .....	7

APPENDICES

APPENDIX A	Excerpts from Subdivision Drainage Report
APPENDIX B	Hydrologic Calculations
APPENDIX C	Hydraulic Calculations
APPENDIX D	Water Quality Pond Calculations
APPENDIX E	Water Quality Pond Cost Estimate
APPENDIX F	Figures
Figure FIRM	Floodplain Map
Sheet D1	Struthers Ranch Subdivision - Developed Drainage Plan
Sheet D1.1	Struthers Ranch Polaris - Developed Drainage Plan

DRAINAGE STATEMENT

Engineer's Statement:

The attached drainage plan and report were prepared under my direction and supervision and are correct to the best of my knowledge and belief. Said drainage report has been prepared according to the criteria established by the County for drainage reports and said report is in conformity with the master plan of the drainage basin. I accept responsibility for liability caused by negligent acts, errors or omissions on my part in preparing this report.

---

John P. Schwab, P.E. #29891

Developer's Statement:

I, the developer have read and will comply with all of the requirements specified in this drainage report and plan.

By:

---

Date

Hammers Construction, Inc.  
1411 Woolsey Heights, Colorado Springs, CO 80915

El Paso County's Statement

Filed in accordance with the requirements of the El Paso County Land Development Code, Drainage Criteria Manual, Volumes 1 and 2, and Engineering Criteria Manual as amended.

---

Joshua Palmer, P.E.  
County Engineer / ECM Administrator

Date

Conditions:

# I. INTRODUCTION

## A. Property Location and Description

Hammers Construction is planning to construct a new Polaris dealership on the vacant 2.94-acre property at the southeast corner of Struthers Road and Struthers Ranch Road in northern El Paso County, Colorado. The property is described as Lots 1 and 2, Struthers Ranch Subdivision Filing No. 4 (El Paso County Assessor’s Parcel Numbers 71363-03-010 and 71363-03-011).

The project consists of a new 12,000 square-foot, single-story Polaris dealership building with associated parking and site improvements. The property is bounded by Struthers Road on the southwest side and Struthers Ranch Road on the northwest side. Struthers Road is a fully improved, asphalt-paved arterial public street, and Struthers Ranch Road is a fully improved local public street. Existing platted residential lots are located along the northeast boundary of the parcel (Struthers Ranch Filing No. 2). The south boundary of the site adjoins vacant commercial properties (Lots 3 and 4, Struthers Ranch Subdivision Filing No. 4).

The property is zoned Planned Unit Development (PUD), and the proposed site development is fully consistent with the existing zoning of the site. Access to the site will be provided by the existing private driveway connection to Struthers Ranch Road along the north boundary of Lot 1.

The site is located in the Black Forest Creek Drainage Basin, and surface drainage from this site sheet flows southwesterly to an existing public storm sewer system along the west boundary of the property, flowing to the existing Struthers Ranch stormwater detention pond on the west side of Struthers Road.

This report is intended to meet the requirements of a site-specific “Letter Type” drainage report in accordance with El Paso County subdivision drainage criteria.

## B. Drainage Analysis Methods and Criteria

ITEM	DESCRIPTION	REFERENCE
Design Storm (initial/major)	5-year/100-year	CS/EPC DCM
Storm Runoff	Rational Method (Area<100acres)	CS/EPC DCM
Major Drainage Basin	Black Forest Creek	
Floodplain Impacts	Parcel is located outside any delineated FEMA floodplains	FIRM
Existing Downstream Facilities	Existing storm sewer system on east side of Struthers Road; Existing detention pond on west side of Struthers Road	

CS/EPC DCM = City of Colorado Springs & El Paso County Drainage Criteria Manual

## C. References

JPS Engineering, Inc., "Final Drainage Report for Struthers Ranch Filing No. 2," October 14, 2004 (approved by El Paso County 10/20/04).

JPS Engineering, Inc., "Drainage Letter Report for Struthers Ranch Subdivision Filing No. 4," February 22, 2006.

## II. EXISTING / PROPOSED DRAINAGE CONDITIONS

### Subdivision Drainage Report

Drainage planning for this site was previously master planned during original development of the Struthers Ranch Subdivision, as detailed in the "Final Drainage Report (FDR) for Struthers Ranch Filing No. 2" by JPS Engineering, dated October 14, 2004 (see excerpts in Appendix A). The project area at the southeast corner of Struthers Road and Struthers Ranch Road was identified as a future commercial development area in the original planning of the subdivision.

According to the original FDR, Basins D6A (3.0 acres) and D9A (3.18 acres) comprise the future commercial development areas on the south side of Struthers Ranch Road. The previously approved subdivision drainage planning assumed full commercial development within all of Basins D6A and D9A, with runoff coefficients of  $C_5 = 0.90$  and  $C_{100} = 0.90$ , and impervious areas of 95 percent for the entirety of these basins. According to the Rational Method calculations in the original subdivision drainage report, developed peak flows from Basin D6A were calculated as  $Q_5 = 14.0$  cfs and  $Q_{100} = 24.3$  cfs, and peak flows from Basin D9A were calculated as  $Q_5 = 14.9$  cfs and  $Q_{100} = 25.8$  cfs (see Appendix A).

As shown on the enclosed Struthers Ranch Subdivision Drainage Plan (Figure D1, Appendix F), the proposed Polaris development site lies entirely within Basin D6A as delineated in the approved "Final Drainage Report for Struthers Ranch Filing No. 2." The site slopes downward to the southwest, with average grades of 1-4 percent. On-site soils are classified by SCS as type 71, "Pring" series coarse sandy loam soils. These soils have moderately rapid permeability and slow to medium surface runoff characteristics. The soils are classified as hydrologic soils group B.

Developed drainage from this commercial site will sheet flow southwesterly to the existing storm sewer system along the east side of Struthers Road. Flows combine at the existing grated inlet on the east side of Struthers Road, where double 48-inch culverts convey developed flows across Struthers Road and into the existing detention pond. The previously approved drainage report for Struthers Ranch Filing No. 2 assumed full commercial development for this basin, which is consistent with the proposed site development. The existing detention pond was sized to account for fully developed flows from this commercial area.

The impervious area for the proposed Struthers Ranch Polaris development (delineated as Basin A within this report, which correlates with Basin D6A in the FDR) amounts to approximately 69 percent of the site (as tabulated on Sh. D1.1 and Appendix B), which is well below the impervious area of 95 percent assumed for full commercial development in the previously approved subdivision drainage report (see Appendix A).

Based on the previous construction of drainage improvements for the Struthers Ranch Subdivision, no significant impact on downstream drainage facilities is anticipated from this site development and replat. Proper erosion control measures will be required for development of the site, including silt fence along property boundaries to minimize off-site transport of construction sediment.

### **Existing Drainage Conditions**

As shown on the enclosed Drainage Plan (Figure D1.1, Appendix F), the site has been delineated as two on-site drainage basins. The project area (Lots 1-2, Struthers Ranch Filing No. 4) has been delineated as Basin A, and the future development area to the southeast (Lots 3-4, Struthers Ranch Filing No. 4) has been delineated as Basin B. The site is impacted by an off-site basin consisting of the rear sides of the adjoining single-family residential lots (platted as part of Struthers Ranch Filing No 2) along the southeast boundary of the site, which has been delineated as Basin OB1.

Existing drainage from Basin A sheet flows southwesterly across the property, with peak flows calculated as  $Q_5 = 0.8$  cfs and  $Q_{100} = 5.8$  cfs. Basin A flows to the existing ditch along the east side of Struthers Road, and the ditch flows are captured in the existing grated storm inlet identified as Design Point #1.

Existing drainage from off-site Basin OB1 (back sides of adjoining developed single-family residential lots along northeast boundary of project site) sheet flows southwesterly into Basin B, and Basin B flows southwesterly to the existing ditch along the east side of Struthers Road, ultimately flowing into the existing grated storm inlet at Design Point #1. Existing flows from Basins OB1 and B combine at Design Point #B1, with peak flows calculated as  $Q_5 = 1.9$  cfs and  $Q_{100} = 7.0$  cfs.

Existing flows from Basins A, OB1, and B combine at Design Point #1, with peak flows calculated as  $Q_5 = 2.5$  cfs and  $Q_{100} = 12.0$  cfs. A double 48-inch RCP storm sewer conveys the flow from the grated storm inlet southwesterly across Struthers Road into the existing regional Struthers Ranch Detention Pond.

### **Developed Drainage Plan**

Developed flows have been calculated based on the impervious areas associated with the proposed building and parking improvements. Surface drainage swales and a private storm sewer system will convey developed flows to the proposed Water Quality Pond A along the west boundary of the site. Site grades will slope to storm inlets and curb openings at selected locations, collecting surface drainage and conveying stormwater to

Water Quality Pond A. The proposed building pad will be graded with protective slopes to provide positive drainage away from the building, and the curb, gutter, drainage swales, and private storm sewer system will convey developed flows southwesterly into Water Quality Pond A.

The proposed Polaris site development on Lots 1-2 has been delineated as Basin A, which drains by sheet flow and curb and gutter to the proposed Stormwater Quality Detention Basin along the west boundary of the site. Private Storm Inlet A1 (Type 16) will intercept surface drainage from the north side of the Polaris site, and Private Storm Sewer A1 (18") will convey this flow into the on-site Water Quality Pond A. The balance of the Polaris site will flow by drainage swales and curb and gutter into the south side of Water Quality Pond A.

Developed peak flows at Design Point A are calculated as  $Q_5 = 8.9$  cfs and  $Q_{100} = 17.7$  cfs. Basin A generally correlates with "Basin D6A" in the Final Drainage Report for Struthers Ranch Filing No. 2 ( $Q_5 = 14.0$  cfs and  $Q_{100} = 24.3$  cfs).

The future commercial site development areas to the south in Lots 3-4 have been delineated as Basin B, which will generally drain northwesterly by sheet flow and curb and gutter to a future private storm sewer via a proposed 18" HDPE pipe conveying developed flows into Water Quality Pond A. Developed peak flows at Design Point B are calculated as  $Q_5 = 4.7$  cfs and  $Q_{100} = 9.0$  cfs. Basin B generally correlates with "Basin D9A" in the Final Drainage Report for Struthers Ranch Filing No. 2 ( $Q_5 = 14.9$  cfs and  $Q_{100} = 25.8$  cfs). Developed flows from off-site Basin OB1 will continue to combine with Basin B at Design Point #B1, with peak flows calculated as  $Q_5 = 5.9$  cfs and  $Q_{100} = 12.2$  cfs.

The 18" HDPE discharge pipe from Water Quality Pond A (along with overflows from the pond spillway) will drain into the existing grated storm inlet along the east side of Struthers Road, and the existing double 48-inch RCP storm sewer will continue to convey the flow from the grated storm inlet southwesterly across Struthers Road into the existing regional Struthers Ranch Detention Pond ("Detention Pond 11" per Black Forest Creek DBPS).

Developed flows from Basins A, OB1, and B combine at Design Point #1, with peak flows calculated as  $Q_5 = 11.9$  cfs and  $Q_{100} = 24.2$  cfs. As detailed in Appendix B, for comparison with the original Subdivision FDR, the total flows from Basins D6A and D9A (equivalent to Design Point #1) have been calculated as  $Q_5 = 23.2$  cfs and  $Q_{100} = 38.9$  cfs (significantly higher than the current developed flow calculations). As such, the developed flows are well below the previously master planned developed flows entering the regional detention pond.

Hydrologic and hydraulic calculations for the site are detailed in the appendices (Appendix B and C), and peak flows are identified on Figure D1.1 (Appendix F).

### **III. DRAINAGE PLANNING FOUR STEP PROCESS**

El Paso County Drainage Criteria require drainage planning to include a Four Step Process for receiving water protection that focuses on reducing runoff volumes, treating the water quality capture volume (WQCV), stabilizing drainageways, and implementing long-term source controls.

As stated in ECM Appendix I.7., the Four Step Process is applicable to all new and re-development projects with construction activities that disturb 1 acre or greater or that disturb less than 1 acre but are part of a larger common plan of development. The Four Step Process has been implemented as follows in the planning of this project:

#### Step 1: Employ Runoff Reduction Practices

- Extended Detention Basin: The majority of developed flows will be routed through the on-site detention basin, which will be grass-lined to encourage stormwater infiltration.

#### Step 2: Stabilize Drainageways

- There are no drainageways directly adjacent to this project site. Implementation of the on-site drainage improvements and detention basin will minimize downstream drainage impacts from this site.
- Drainage basin fees were previously paid during recording of the subdivision plat, and these fees provided the applicable cost contribution towards regional drainage improvements.

#### Step 3: Provide Water Quality Capture Volume (WQCV)

- EDB: The majority of the developed site will drain through an on-site Private Extended Detention Basin (EDB) along the west boundary of the property. The extended detention basin which will capture and slowly release the WQCV over an extended release period.

#### Step 4: Consider Need for Industrial and Commercial BMPs

- No industrial uses are proposed for this site.
- The commercial property owner will implement a Stormwater Management Plan including proper housekeeping practices and spill containment procedures.
- On-site drainage will be routed through the Extended Detention Basin (EDB) to minimize introduction of contaminants to the County's public drainage system.

### **IV. FLOODPLAIN IMPACTS**

According to the FEMA floodplain map for this area, El Paso County FIRM Panel No. 08041C0287G, dated December 7, 2018, the site is located beyond the limits of any delineated floodplains.



## V. STORMWATER DETENTION AND WATER QUALITY

Stormwater detention for this site is provided in the existing regional stormwater detention pond constructed during initial development of the Struthers Ranch Subdivision. The Struthers Ranch Homeowners Association is the owner of the existing Struthers Ranch Detention Pond located within Tract C, Struthers Ranch Filing No. 2. There currently appears to be a need for removal of excess vegetation within the pond to ensure proper operation of the detention facilities. The developer will need to coordinate with the HOA to ensure that the required maintenance is performed on the existing regional detention pond.

An on-site private Water Quality Pond will be constructed to meet stormwater quality improvements for this project site in accordance with current El Paso County drainage criteria.

As detailed in the detention pond calculations in Appendix D, the required Water Quality Capture Volume (WQCV) has been calculated as 0.13 acre-feet. The water quality capture volume has been calculated based on the actual impervious area of the proposed site development within Basin A (calculated as 69%), along with the typical single-family residential impervious area of 40% within the adjoining developed Basin OB1, and a conservative estimated impervious area of 95 percent for the anticipated future commercial development within Basin B (consistent with the original FDR).

The proposed Water Quality Basin has been designed utilizing the Denver Mile High Flood District's "MH-Detention\_v4.05" software package. Calculations and details for the proposed Water Quality Basin are enclosed in Appendix D, and design parameters for the Water Quality Basin are summarized as follows:

<b>Water Quality Basin</b>	<b>Tributary Drainage Basin</b>	<b>Tributary Area (ac)</b>	<b>Impervious Percentage</b>	<b>Min. WQCV (af)</b>	<b>Design Volume (af)</b>
A	A,OB1,B	5.62	68.1	0.13	0.22

The proposed on-site Water Quality Pond A provides a storage volume of 0.22 acre-feet, which meets the required WQCV volume.

The proposed water quality pond will include concrete forebays, trickle channels, and an outlet structure with a water quality orifice plate to maintain discharges below the allowable release rates. The pond outlet structure has been designed for a 40-hour release of the WQCV, and outlet structure sizing to maintain maximum allowable release rates from the pond. The water quality pond will have a grass-lined bottom to encourage infiltration of stormwater prior to discharging into the downstream public drainage system.

The new on-site Water Quality Basin will be privately owned and maintained by the property owner, and maintenance access will be provided from the southwest parking lot.

## **VI. PUBLIC IMPROVEMENTS / DRAINAGE BASIN FEES**

No public drainage improvements are required or proposed for this project. As detailed in Appendix E, the proposed private Water Quality Pond A has an estimated cost of approximately \$65,846.

The site lies completely within the Black Forest Creek Drainage Basin. Applicable drainage basin fees were paid at the time of original platting of Struthers Ranch Filing No. 2, so no drainage basin fees or bridge fees are applicable at this time.

## **VII. SUMMARY**

The developed drainage patterns for the proposed site development on Lots 1-2, Struthers Ranch Filing No. 4 will remain consistent with the established drainage plan for this subdivision. The grading and drainage plan for the proposed Polaris site development fully conforms to the approved drainage plan for Struthers Ranch Filings No. 2 and 4.

Developed flows from the site will drain through a Private Water Quality Pond at the southwest corner of the property prior to discharging to the existing downstream public drainage system. Stormwater detention is provided by the existing Struthers Ranch Detention Pond which was designed to accept fully developed flows from the commercial area encompassing this site (Lots 1-4, Struthers Ranch Filing No. 4). The proposed on-site Water Quality Pond will be constructed to meet current stormwater quality requirements. Construction and proper maintenance of the on-site drainage facilities and Extended Detention Basin, in conjunction with proper erosion control practices, will ensure that this developed site has no significant adverse drainage impact on downstream or surrounding areas.

**APPENDIX A**

**EXCERPTS FROM SUBDIVISION DRAINAGE REPORT**


**FINAL DRAINAGE REPORT**  
**for**  
**STRUTHERS RANCH FILING NO. 2**

**Prepared for:**

**WL Homes LLC**  
8610 Explorer Drive, Suite 300  
Colorado Springs, CO 80920

November 6, 2003  
Revised April 12, 2004  
Revised May 7, 2004  
Revised May 25, 2004  
Revised September 3, 2004  
Revised October 14, 2004

**Prepared by:**



19 E. Willamette Avenue  
Colorado Springs, CO 80903  
(719)-477-9429  
(719)-471-0766 FAX

**JPS Project No. 080006**

11 15 2004

11 29 04

## 2. Developed Drainage Conditions

The developed drainage basins and projected flows are shown in Figure D1, and preliminary hydrologic calculations are enclosed in Appendix B. The developed site has been divided into five major basins (A-E) and five design points (DP1-DP5), as shown on the enclosed Drainage Plan (Sheets D1 and D1.02). Hydrologic flow schematics and calculations are enclosed in Appendix B.

Struthers Ranch Filing No. 2 is located within parts of Basins C-F at the northwest corner of the site. The majority of developed areas ultimately flow to the proposed detention pond at Design Point No. 4. The internal road gutters of sub-basins D1-D10 will be graded to drain southwesterly through the interior road system. Storm inlets will be constructed in the interior roads as required to intercept developed flows exceeding the allowable street capacity. Storm sewer outfalls will be extended to the proposed detention pond.

To minimize the impacts of developed drainage from Struthers Ranch, flows from Basins C, D, and F will be routed through the proposed detention pond. Off-site Basins OC1 and OD1 will combine with flows from on-site Sub-basins D1-D10, C, E2, E3, and F at the proposed detention pond (Design Point #4), with developed flows of  $Q_5 = 66$  cfs and  $Q_{100} = 191$  cfs (SCS Method). The detention pond will discharge historic flows to the existing swale at the southerly site boundary, flowing into the existing 48-inch culvert crossing I-25. The proposed 48-inch RCP discharge pipe from the detention pond will be released to a riprap apron, flowing to an existing stable grass-lined swale across a parcel owned by the U.S Air Force Academy, ultimately crossing I-25 through the existing 48-inch CMP culvert.

The proposed site layout will significantly reduce the amount of developed flow reaching the existing 3.5'x2' culvert (Structure #11) at the westerly site boundary (Design Point #3). Flows from Sub-basin E4 ( $Q_5 = 1.9$  cfs and  $Q_{100} = 3.7$  cfs) represent the westerly side of the proposed Struthers Road draining to the existing culvert crossing I-25.

Basin E1 represents the small developed area at the northwest corner of the site, draining to the existing 4'x4' box culvert at Design Point #5. The proposed grading scheme for the commercial area north of Struthers Ranch Road will direct the majority of developed flows into Basin C, ultimately flowing to the proposed detention pond. As a result, developed flow impacts to the Jackson Creek Basin at the northwest corner of the site will be minimized. Estimated developed peak flows of  $Q_5 = 4.6$  cfs and  $Q_{100} = 8.9$  cfs at Design Point #5 remain within the capacity of the existing culvert.

### C. Comparison of Developed to Historic Discharges

Based on the hydrologic calculations in Appendix B, the total undetained developed flow from the site will exceed historic flow from the parcel. Projected increases in developed flows will be mitigated by routing flows through a proposed on-site stormwater detention pond. The comparison of developed to historic discharges at key design points is summarized as follows:



Design Point	Historic Flow			Developed Flow			Comparison of Developed to Historic Flow (Q <sub>5</sub> %/Q <sub>100</sub> %)
	Area (ac)	Q <sub>5</sub> (cfs)	Q <sub>100</sub> (cfs)	Area (ac)	Q <sub>5</sub> (cfs)	Q <sub>100</sub> (cfs)	
1 (SCS)	1,266	473	1,281	1,274	464	1,263	98% / 99% (decrease)
2	15.1	9.3	22.4	1.4	1.7	3.6	18% / 16% (decrease)
3	16.0	9.9	24.0	0.6	1.9	3.7	19% / 15% (decrease)
4 (SCS)	133.6	50	148	155.4	66	191	132% / 129% (increase)
5	6.8	8	9.2	4.0	4.6	8.9	121% / 99% (increase)

### D. Detention Ponds


The total developed storm runoff downstream of Struthers Ranch will be maintained at historic levels by routing flows through the proposed on-site detention pond located at the westerly boundary of the Struthers Ranch property (equivalent to "Detention Pond #11" as identified in the DBPS). The proposed detention facility will be sized to attenuate peak flows through the pond, based on the difference between outflow and inflow hydrographs. Flows from Basins C and D will be routed through the proposed detention pond at Design Point #4. The pond will be designed to "over-detain" to account for release of developed flows from Basins A and B, ensuring that the net discharge from the overall site will be maintained below historic levels.

As depicted on Sheet C1.02 (Appendix A), the proposed interim access connection from the I-25 Frontage Road to Struthers Road will bisect the pond, providing for a forebay at the upstream end of the pond. Once the interim access to the frontage road is abandoned, the maintenance access road will remain, and the forebay will continue to serve as a water quality enhancement feature. A detailed pond routing analysis utilizing the "Intelisolve Hydraflow" software package is enclosed in Appendix C1, resulting in the following pond design parameters:

Pond	Pond Inflow (Q <sub>5</sub> / Q <sub>100</sub> , cfs)	Pond Outflow (Q <sub>5</sub> / Q <sub>100</sub> , cfs)	Pond Volume (ac-ft)
DP4 ("Pond #11")	35 / 191	19.3 / 138.4	4.7



- NOTES**
1. DEVELOPMENT SHALL FOLLOW ALL REQUIREMENTS OF THE APPROVED HAZAT CONSERVATION PLAN (HCP) AND ASSOCIATED ENVIRONMENTAL PERMITS.
  2. PERMETER BASINS SHALL BE REQUIRED FOR ALL HOMES WITH BASEMENTS.



# STRUTHERS RANCH SUBDIVISION

## DEVELOPED DRAINAGE PLAN

No.	REVISION	BY	DATE
1	EPC COMMENTS	JPS	4/8/04
2	EPC COMMENTS	JPS	5/17/04
3	EPC COMMENTS	JPS	5/25/04
4	EPC COMMENTS	JPS	9/2/04
5	RE-SUBMIT TO EPC	JPS	9/30/04

NO.	DATE	DESCRIPTION
1	10/15/04	ISSUED FOR PERMITTING
2	10/15/04	ISSUED FOR PERMITTING
3	10/15/04	ISSUED FOR PERMITTING
4	10/15/04	ISSUED FOR PERMITTING
5	10/15/04	ISSUED FOR PERMITTING
6	10/15/04	ISSUED FOR PERMITTING
7	10/15/04	ISSUED FOR PERMITTING
8	10/15/04	ISSUED FOR PERMITTING
9	10/15/04	ISSUED FOR PERMITTING
10	10/15/04	ISSUED FOR PERMITTING
11	10/15/04	ISSUED FOR PERMITTING
12	10/15/04	ISSUED FOR PERMITTING
13	10/15/04	ISSUED FOR PERMITTING
14	10/15/04	ISSUED FOR PERMITTING
15	10/15/04	ISSUED FOR PERMITTING
16	10/15/04	ISSUED FOR PERMITTING
17	10/15/04	ISSUED FOR PERMITTING
18	10/15/04	ISSUED FOR PERMITTING
19	10/15/04	ISSUED FOR PERMITTING
20	10/15/04	ISSUED FOR PERMITTING
21	10/15/04	ISSUED FOR PERMITTING
22	10/15/04	ISSUED FOR PERMITTING
23	10/15/04	ISSUED FOR PERMITTING
24	10/15/04	ISSUED FOR PERMITTING
25	10/15/04	ISSUED FOR PERMITTING
26	10/15/04	ISSUED FOR PERMITTING
27	10/15/04	ISSUED FOR PERMITTING
28	10/15/04	ISSUED FOR PERMITTING
29	10/15/04	ISSUED FOR PERMITTING
30	10/15/04	ISSUED FOR PERMITTING
31	10/15/04	ISSUED FOR PERMITTING
32	10/15/04	ISSUED FOR PERMITTING
33	10/15/04	ISSUED FOR PERMITTING
34	10/15/04	ISSUED FOR PERMITTING
35	10/15/04	ISSUED FOR PERMITTING
36	10/15/04	ISSUED FOR PERMITTING
37	10/15/04	ISSUED FOR PERMITTING
38	10/15/04	ISSUED FOR PERMITTING
39	10/15/04	ISSUED FOR PERMITTING
40	10/15/04	ISSUED FOR PERMITTING
41	10/15/04	ISSUED FOR PERMITTING
42	10/15/04	ISSUED FOR PERMITTING
43	10/15/04	ISSUED FOR PERMITTING
44	10/15/04	ISSUED FOR PERMITTING
45	10/15/04	ISSUED FOR PERMITTING
46	10/15/04	ISSUED FOR PERMITTING
47	10/15/04	ISSUED FOR PERMITTING
48	10/15/04	ISSUED FOR PERMITTING
49	10/15/04	ISSUED FOR PERMITTING
50	10/15/04	ISSUED FOR PERMITTING
51	10/15/04	ISSUED FOR PERMITTING
52	10/15/04	ISSUED FOR PERMITTING
53	10/15/04	ISSUED FOR PERMITTING
54	10/15/04	ISSUED FOR PERMITTING
55	10/15/04	ISSUED FOR PERMITTING
56	10/15/04	ISSUED FOR PERMITTING
57	10/15/04	ISSUED FOR PERMITTING
58	10/15/04	ISSUED FOR PERMITTING
59	10/15/04	ISSUED FOR PERMITTING
60	10/15/04	ISSUED FOR PERMITTING
61	10/15/04	ISSUED FOR PERMITTING
62	10/15/04	ISSUED FOR PERMITTING
63	10/15/04	ISSUED FOR PERMITTING
64	10/15/04	ISSUED FOR PERMITTING
65	10/15/04	ISSUED FOR PERMITTING
66	10/15/04	ISSUED FOR PERMITTING
67	10/15/04	ISSUED FOR PERMITTING
68	10/15/04	ISSUED FOR PERMITTING
69	10/15/04	ISSUED FOR PERMITTING
70	10/15/04	ISSUED FOR PERMITTING
71	10/15/04	ISSUED FOR PERMITTING
72	10/15/04	ISSUED FOR PERMITTING
73	10/15/04	ISSUED FOR PERMITTING
74	10/15/04	ISSUED FOR PERMITTING
75	10/15/04	ISSUED FOR PERMITTING
76	10/15/04	ISSUED FOR PERMITTING
77	10/15/04	ISSUED FOR PERMITTING
78	10/15/04	ISSUED FOR PERMITTING
79	10/15/04	ISSUED FOR PERMITTING
80	10/15/04	ISSUED FOR PERMITTING
81	10/15/04	ISSUED FOR PERMITTING
82	10/15/04	ISSUED FOR PERMITTING
83	10/15/04	ISSUED FOR PERMITTING
84	10/15/04	ISSUED FOR PERMITTING
85	10/15/04	ISSUED FOR PERMITTING
86	10/15/04	ISSUED FOR PERMITTING
87	10/15/04	ISSUED FOR PERMITTING
88	10/15/04	ISSUED FOR PERMITTING
89	10/15/04	ISSUED FOR PERMITTING
90	10/15/04	ISSUED FOR PERMITTING
91	10/15/04	ISSUED FOR PERMITTING
92	10/15/04	ISSUED FOR PERMITTING
93	10/15/04	ISSUED FOR PERMITTING
94	10/15/04	ISSUED FOR PERMITTING
95	10/15/04	ISSUED FOR PERMITTING
96	10/15/04	ISSUED FOR PERMITTING
97	10/15/04	ISSUED FOR PERMITTING
98	10/15/04	ISSUED FOR PERMITTING
99	10/15/04	ISSUED FOR PERMITTING
100	10/15/04	ISSUED FOR PERMITTING

D1

**JPS ENGINEERING**  
 9 E. Mountain Ave.  
 Colorado Springs, CO 80903  
 TEL: 719-577-5829  
 FAX: 719-577-0088

TABLE 5-1

RECOMMENDED AVERAGE RUNOFF COEFFICIENTS AND PERCENT IMPERVIOUS

LAND USE OR SURFACE CHARACTERISTICS	PERCENT IMPERVIOUS	"C" FREQUENCY			
		10		100	
		A&B*	C&D*	A&B*	C&D*
<b>Business</b>					
Commercial Areas	95	0.90	0.90	0.90	0.90
Neighborhood Areas	70	0.75	0.75	0.80	0.80
<b>Residential</b>					
1/8 Acre or less	65	0.60	0.70	0.70	0.80
1/4 Acre	40	0.50	0.60	0.60	0.70
1/3 Acre	30	0.40	0.50	0.55	0.60
1/2 Acre	25	0.35	0.45	0.45	0.55
1 Acre	20	0.30	0.40	0.40	0.50
<b>Industrial</b>					
Light Areas	80	0.70	0.70	0.80	0.80
Heavy Areas	90	0.80	0.80	0.90	0.90
<b>Parks and Cemeteries</b>					
Park Areas	7	0.30	0.35	0.55	0.60
Playgrounds	13	0.30	0.35	0.60	0.65
Railroad Yard Areas	40	0.50	0.55	0.60	0.65
<b>Undeveloped Areas</b>					
Historic Flow Analysis- Greenbelts, Agricultural	2	0.15	0.25	0.20	0.30
Pasture/Meadow	0	0.25	0.30	0.35	0.45
Forest	0	0.10	0.15	0.15	0.20
Exposed Rock	100	0.90	0.90	0.95	0.95
Offsite Flow Analysis (when land use not defined)	45	0.55	0.60	0.65	0.70
<b>Streets</b>					
Paved	100	0.90	0.90	0.95	0.95
Gravel	80	0.80	0.80	0.85	0.85
<b>Drive and Walks</b>					
Drive and Walks	100	0.90	0.90	0.95	0.95
Roofs	90	0.90	0.90	0.95	0.95
Lawns	0	0.25	0.30	0.35	0.45

\* Hydrologic Soil Group

9/30/90

(EPC-DCM)



STRUTHERS RANCH  
COMPOSITE RUNOFF COEFFICIENTS

DEVELOPED CONDITIONS												
5-YEAR C VALUES												
BASIN	TOTAL AREA (AC)	SOIL TYPE	(AC)	SUB-AREA 1 DEVELOPMENT/ COVER	C	AREA (AC)	SUB-AREA 2 DEVELOPMENT/ COVER	C	(AC)	SUB-AREA 3 DEVELOPMENT/ COVER	C	WEIGHTED C VALUE
OA1	981	B	981	0.25-AC LOTS	0.5							0.500
OA2	240	B	240	0.25-AC LOTS	0.5							0.500
OA1,OA2	1221											0.500
B1	1.1	B	1.1	0.25-AC LOTS	0.5							0.500
A	38.5	B	38.5	OPEN SPACE	0.25							0.250
OA1,OA2,B1,A	1260.6											0.492
OB1	1.87	B	1.87	0.25-AC LOTS	0.5							0.500
B2	1.81	B	1.81	0.25-AC LOTS	0.5							0.500
B3	1.4	B	1.41	0.25-AC LOTS	0.5							0.500
B4	5.8	B	5.8	0.25-AC LOTS	0.5							0.500
OB1,B2-B4	10.9											0.500
B5	0.9	B	0.9	0.25-AC LOTS	0.5							0.500
OB1,B2-B5	11.8											0.500
B6	3.3	B	3.3	0.25-AC LOTS	0.5							0.500
OB1,B2-B6	15.1											0.500
OA1,OA2,A,B1-B6	1275.7											0.492
B7	0.83	B	0.83	0.25-AC LOTS	0.5							0.500
B8	0.52	B	0.52	0.25-AC LOTS	0.5							0.500
B7,B8	1.4											0.500
E4	0.6	B	0.34	PAVED	0.9	0.3	LANDSCAPE	0.25				0.618
OD1	98.57	B	98.57	5-AC LOTS	0.3							0.300
D1	0.46	B	0.46	MEADOW	0.25							0.250
OD1,D1	99.03											0.300

OD2	6.26	B	6.26	5-AC LOTS	0.3						0.300
D1C	3.23	B	1.5	0.25-AC LOTS	0.5	1.7	OPEN SPACE	0.25			0.366
OD2,D1C	9.49										0.322
D1A	3.00	B	0.8	0.25-AC LOTS	0.5	2.2	PARK / OS	0.25			0.317
OD2,D1C,D1A	12.49										0.321
D1B	0.19	B	0.19	ROADWAY	0.9						0.900
OD1,D1,D1A,D1B	111.71										0.303
D4	0.12	B	0.12	ROADWAY	0.9						0.900
OD1,D1,D1A,D1B,D4	111.83										0.304
D5	0.11	B	0.11	ROADWAY	0.9						0.900
OD1,D1,D1A,D1B,D4,D5	111.94										0.304
D6	0.32	B	0.318	ROADWAY	0.9						0.900
OD1,D1,D1A,D1B,D4-D6	112.26										0.306
OC1	2.21	B	2.21	5-AC LOTS	0.3						0.300
D2	3.60	B	3.6	0.25-AC LOTS	0.5						0.500
OC1,D2	5.81										0.424
E2A	0.39	B	0.3	PAVED	0.9	0.1	LANDSCAPE	0.25			0.750
D3	1.55	B	1.55	0.25-AC LOTS	0.5						0.500
C	4.75	B	4.75	COMMERCIAL	0.9						0.900
D3,C	6.30										0.802
OD1,OC1,C,E2A,D1-D6	124.76										0.338
E2	0.52	B	0.4	PAVED	0.9	0.1	LANDSCAPE	0.25			0.750
D6A	3.00	B	3	COMMERCIAL	0.9						0.900
OD1,OC1,C,D1-D6A	128.28										0.350
D7A	3.48	B	3.48	0.25-AC LOTS	0.5						0.500
D7	6.05	B	6.05	0.25-AC LOTS	0.5						0.500
D7A,D7	9.53										0.500
D8	3.72	B	3.72	0.25-AC LOTS	0.5						0.500
D7A,D7,D8	13.25										0.500
D9	1.20	B	1.2	0.25-AC LOTS	0.5						0.500
D7A-D9	14.45										0.500
E3A	0.12	B	0.12	MEDIAN	0.25						0.250
D10	4.80	B	4.8	0.25-AC LOTS	0.5						0.500
D7A-D10,E3A	19.37										0.498
D9A	3.18	B	3.18	COMMERCIAL	0.9						0.900
D7A-D10,E3A	22.55										0.555
E3	0.70	B	0.5	PAVED	0.9	0.2	LANDSCAPE	0.25			0.714
F	4.02	B	4.02	OPEN SPACE	0.25						0.250
OD1,C,D1-D10,E2-E3,F	155.55	B									0.379
OE1	2.47	B	2.47	5-AC LOTS	0.3						0.300
E1	1.5	B	1.5	COMMERCIAL	0.9						0.900
OE1,E1	4.0										0.527

STRUTHERS RANCH  
COMPOSITE RUNOFF COEFFICIENTS

DEVELOPED CONDITIONS												
100-YEAR C VALUES												
BASIN	TOTAL AREA (AC)	SOIL TYPE	(AC)	SUB-AREA 1 DEVELOPMENT/ COVER	C	AREA (AC)	SUB-AREA 2 DEVELOPMENT/ COVER	C	(AC)	SUB-AREA 3 DEVELOPMENT/ COVER	C	WEIGHTED C VALUE
OA1	981	B	981	0.25-AC LOTS	0.6							0.600
OA2	240	B	240	0.25-AC LOTS	0.6							0.600
OA1,OA2	1221											0.600
B1	1.1	B	1.1	0.25-AC LOTS	0.6							0.600
A	38.5	B	38.5	OPEN SPACE	0.35							0.350
OA1,OA2,B1,A	1260.6											0.592
OB1	1.87	B	1.87	0.25-AC LOTS	0.6							0.600
B2	1.81	B	1.81	0.25-AC LOTS	0.6							0.600
B3	1.4	B	1.41	0.25-AC LOTS	0.6							0.600
B4	5.8	B	5.8	0.25-AC LOTS	0.6							0.600
OB1,B2-B4	10.9											0.600
B5	0.9	B	0.9	0.25-AC LOTS	0.6							0.600
OB1,B2-B5	11.8											0.600
B6	3.3	B	3.3	0.25-AC LOTS	0.6							0.600
OB1,B2-B6	15.1											0.600
OA1,OA2,A,B1-B6	1275.7											0.592
B7	0.83	B	0.83	0.25-AC LOTS	0.6							0.600
B8	0.52	B	0.52	0.25-AC LOTS	0.6							0.600
B7,B8	1.4											0.600
E4	0.6	B	0.34	PAVED	0.95	0.3	LANDSCAPE	0.35				0.690
OD1	98.57	B	98.57	5-AC LOTS	0.4							0.400
D1	0.46	B	0.46	MEADOW	0.35							0.350
OD1,D1	99.03											0.400

OD2	6.26	B	6.26	5-AC LOTS	0.4						0.400
D1C	3.23	B	1.5	0.25-AC LOTS	0.6	1.7	OPEN SPACE	0.35			0.466
OD2,D1C	9.49										0.422
D1A	3.00	B	0.8	0.25-AC LOTS	0.6	2.2	PARK / OS	0.35			0.417
OD2,D1C,D1A	12.49										0.421
D1B	0.19	B	0.19	ROADWAY	0.95						0.950
OD1,D1,D1A,D1B	111.71										0.403
D4	0.12	B	0.12	ROADWAY	0.95						0.950
OD1,D1,D1A,D1B,D4	111.83										0.404
D5	0.11	B	0.11	ROADWAY	0.95						0.950
OD1,D1,D1A,D1B,D4,D5	111.94										0.404
D6	0.32	B	0.318	ROADWAY	0.95						0.950
OD1,D1,D1A,D1B,D4-D6	112.26										0.406
OC1	2.21	B	2.21	5-AC LOTS	0.4						0.400
D2	3.60	B	3.6	0.25-AC LOTS	0.6						0.600
OC1,D2	5.81										0.524
E2A	0.39	B	0.3	PAVED	0.95	0.1	LANDSCAPE	0.35			0.812
D3	1.55	B	1.55	0.25-AC LOTS	0.6						0.600
C	4.75	B	4.75	COMMERCIAL	0.9						0.900
D3,C	6.30										0.826
OD1,OC1,C,E2A,D1-D6	124.76										0.434
E2	0.52	B	0.4	PAVED	0.95	0.1	LANDSCAPE	0.35			0.812
D6A	3.00	B	3	COMMERCIAL	0.9						0.900
OD1,OC1,C,D1-D6A	128.28										0.443
D7A	3.48	B	3.48	0.25-AC LOTS	0.6						0.600
D7	6.05	B	6.05	0.25-AC LOTS	0.6						0.600
D7A,D7	9.53										0.600
D8	3.72	B	3.72	0.25-AC LOTS	0.6						0.600
D7A,D7,D8	13.25										0.600
D9	1.20	B	1.2	0.25-AC LOTS	0.6						0.600
D7A-D9	14.45										0.600
E3A	0.12	B	0.12	MEDIAN	0.35						0.350
D10	4.80	B	4.8	0.25-AC LOTS	0.6						0.600
D7A-D10,E3A	19.37										0.598
D9A	3.18	B	3.18	COMMERCIAL	0.9						0.900
D7A-D10,E3A	22.55										0.641
E3	0.70	B	0.5	PAVED	0.95	0.2	LANDSCAPE	0.35			0.779
F	4.02	B	4.02	OPEN SPACE	0.35						0.350
OD1,C,D1-D10,E2-E3,F	155.55	B									0.471
OE1	2.47	B	2.47	5-AC LOTS	0.4						0.400
E1	1.5	B	1.5	COMMERCIAL	0.9						0.900
OE1,E1	4.0										0.589

STRUTHERS RANCH  
RATIONAL METHOD - DRAINAGE CALCULATIONS

DEVELOPED FLOWS

BASIN	DESIGN POINT	AREA (AC)	C		OVERLAND LENGTH (FT)	SLOPE (%)	T <sub>co</sub> <sup>(1)</sup> (MIN)	CHANNEL LENGTH (FT)	CONVEYANCE COEFFICIENT K	SLOPE (%)	SCS <sup>(2)</sup> VELOCITY (FT/S)	T <sub>t</sub> <sup>(3)</sup> (MIN)	TOTAL T <sub>c</sub> <sup>(4)</sup> (MIN)	INTENSITY <sup>(5)</sup>			PEAK FLOW	
			5-YEAR <sup>(7)</sup>	100-YEAR <sup>(7)</sup>										5-YR (IN/HR)	100-YR (IN/HR)	Q5 <sup>(6)</sup> (CFS)	Q100 <sup>(6)</sup> (CFS)	
OA1		981.00	0.500	0.600	300	5.4	10.7	11900	1.50	5.4	3.49	56.9	67.6	1.50	2.65	735.75	1559.79	
OA2		240.00	0.500	0.600	300	5.5	10.6	620	1.50	5.5	3.52	2.9	13.5	3.60	6.10	432.00	878.40	
OA1, OA2	OA1	1221.00	0.500	0.600									67.6	1.50	2.65	915.75	1941.39	
B1	B1	1.10	0.500	0.600	250	12.8	7.3	0				0.0	7.3	4.50	7.60	2.48	5.02	
A		38.50	0.250	0.350	0		0.0	2730	1.50	3.2	2.68	17.0	17.0	3.20	5.50	30.80	74.11	
OA1, OA2, B1, A		1260.60	0.492	0.592									84.5	1.50	2.65	930.32	1977.63	
B2		1.81	0.500	0.600	150	5.3	7.6	450	2.00	4.9	4.43	1.7	9.3	4.10	7.10	3.71	7.71	
B3		1.41	0.500	0.600	0		0.0	700	2.00	3	3.46	3.4	3.4	5.20	9.00	3.67	7.61	
B4		5.89	0.500	0.600	0		0.0	1180	2.00	3.7	3.85	5.1	5.1	5.20	9.00	15.31	31.81	
OB1, B2, B3, B4	B3	9.11	0.500	0.600									12.7	3.70	6.20	16.85	33.89	
B5		0.90	0.500	0.600	0		0.0	1000	2.00	3.3	3.63	4.6	4.6	5.20	9.00	2.34	4.86	
OB1, B2, B5	B5	10.01	0.500	0.600									17.2	3.20	5.50	16.02	33.03	
B6	B6	3.30	0.500	0.600	0		0.0	2100	2.00	3.7	3.85	9.1	9.1	4.10	7.10	6.77	14.06	
OB1, B2, B6	B6A	13.31	0.500	0.600									17.2	3.20	5.50	21.30	43.92	
B6A	B6B															41.80	84.40	
OA1, OA2, A, B1, B6	1	1273.9	0.492	0.592									84.5	1.50	2.65	940.15	1998.51	
B7		0.83	0.500	0.600	150	4.0	8.3	0				0.0	8.3	4.25	7.50	1.76	3.74	
B8		0.52	0.500	0.600	850	5.5	17.8	0				0.0	17.8	3.10	5.20	0.81	1.62	
B7, B8	2	1.35	0.500	0.600									26.2	2.50	4.40	1.69	3.56	
E4	3	0.60	0.618	0.690	0		0.0	450	1.50	5.5	3.52	2.1	2.1	5.20	9.00	1.93	3.73	
OD1		98.57	0.300	0.400	1000	10.0	21.2	3300	1.50	3.9	2.96	18.6	39.7	1.90	3.40	56.18	134.06	
D1		0.46	0.250	0.350	0		0.0	180	1.50	2.5	2.37	1.3	1.3					
OD1, D1	D1	99.03	0.300	0.400									41.0	1.90	3.40	56.45	134.68	
OD2		6.26	0.300	0.400	1000	3.5	30.0	0				0.0	30.0	2.35	4.10	4.41	10.27	
D1C		3.23	0.366	0.466	0		0.0	700	2.00	3.4	3.69	3.2	3.2					
OD2, D1C	D1C	9.49	0.322	0.422									33.2	2.20	3.85	6.72	15.42	
D1A		3.00	0.317	0.417	0		0.0	370	2.00	2.7	3.29	1.9	1.9					
OD2, D1C, D1A	D1A	12.49	0.321	0.421									35.0	2.10	3.75	8.42	19.72	
D1B	D1B	0.19	0.900	0.950	0		0.0	420	2.00	1.6	2.53	2.8	2.8	5.20	9.00	0.89	1.62	
OD1, D1, D1A, D1B	D1A1	111.71	0.303	0.403									41.0	1.90	3.40	64.31	153.07	
D4	D4	0.12	0.900	0.950	0		0.0	700	2.00	1.56	2.50	4.7	4.7	5.20	9.00	0.56	1.03	
OD1, D1, D1A, D1B, D4	D4A	111.83	0.304	0.404									45.7	1.75	3.20	64.87	154.09	
D5	D5	0.11	0.900	0.950	0		0.0	250	2.00	3.27	3.62	1.2	1.2	5.20	9.00	0.51	0.94	
OD1, D1, D1A, D1B, D4, D5	D5A	111.94	0.304	0.404									46.8	1.70	3.15	65.39	155.03	
D6	D6	0.32	0.900	0.950	0		0.0	480	2.00	4.44	4.21	1.9	1.9	5.20	9.00	1.49	2.72	
OD1, D1, D1A, D1B, D4, D6	D6A1	112.26	0.306	0.406									48.7	1.70	3.00	66.88	157.75	

BASIN	DESIGN POINT	AREA (AC)	C		OVERLAND LENGTH (FT)	SLOPE (%)	T <sub>co</sub> <sup>(1)</sup> (MIN)	CHANNEL LENGTH (FT)	CONVEYANCE COEFFICIENT K	SLOPE (%)	SCS <sup>(2)</sup> VELOCITY (FT/S)	T <sub>t</sub> <sup>(3)</sup> (MIN)	TOTAL T <sub>c</sub> <sup>(4)</sup> (MIN)	INTENSITY <sup>(5)</sup>		PEAK FLOW	
			5-YEAR <sup>(7)</sup>	100-YEAR <sup>(7)</sup>										5-YR (IN/HR)	100-YR (IN/HR)	Q5 <sup>(6)</sup> (CFS)	Q100 <sup>(6)</sup> (CFS)
OC1		2.21	0.300	0.400	550	3.3	22.7					0.0	22.7	2.70	4.70	1.79	4.15
D2		3.60	0.500	0.600	0		0.0	600	2.00	3.6	3.79	2.6	2.6				
OC1,D2	D2	5.81	0.424	0.524									25.3	2.60	4.50	6.40	13.70
E2A	E2A	0.39	0.750	0.812	0		0.0	300	1.50	4	3.00	1.7	1.7	5.20	9.00	1.52	2.85
D3		1.55	0.500	0.600	0		0.0	580	2.00	4.3	4.15	2.3	2.3	5.20	9.00	4.03	8.37
C		4.75	0.900	0.900	0		0.0	750	2.00	3.3	3.63	3.4	3.4	5.20	9.00	22.23	38.48
D3,C	C	6.30	0.802	0.826									5.8	5.00	8.50	25.26	44.23
OD1,OC1,E2A,C,D1-D6	C1	124.76	0.338	0.434									48.7	1.70	3.00	71.69	162.43
F2		0.52	0.750	0.812	0		0.0	300	1.50	4	3.00	1.7	1.7	5.20	9.00	2.03	3.80
D6A	D6A	3.00	0.900	0.900	0		0.0	470	2.00	3.4	3.69	2.1	2.1	5.20	9.00	14.04	24.30
OD1,OC1,C,D1-D6A	D6A2	128.28	0.350	0.443									50.8	1.60	2.90	71.84	164.80
D7A	D7A	3.48	0.500	0.600	0		0.0	950	2.00	1.68	2.59	6.1	6.1	5.00	8.50	8.70	17.75
D7		6.05	0.500	0.600	0		0.0	1244	2.00	2.17	2.95	7.0	7.0	4.60	8.00	13.92	29.04
D7A,D7	D7	9.53	0.500	0.600									7.0	4.60	8.00	21.92	45.74
D8	D8	3.72	0.500	0.600	0		0.0	225	2.00	3.4	3.69	1.0	1.0	5.20	9.00	9.67	20.09
D7A-D8	D8A	13.25	0.500	0.600									8.1	4.40	7.50	29.15	59.63
D9	D9	1.20	0.500	0.600	0		0.0	210	2.00	3.4	3.69	0.9	0.9	5.20	9.00	3.12	6.48
D7A-D9	D9A	14.45	0.500	0.600									9.0	4.20	7.20	30.35	62.42
E3A	E3A	0.12	0.250	0.350	0		0.0	220	1.50	4.3	3.11	1.2	1.2	5.20	9.00	0.16	0.38
D10	D10	4.80	0.500	0.600	300	4.0	11.8	1820	2.00	3	3.46	8.8	20.5	2.95	5.05	7.08	14.54
D10A	D10A	0.23	0.500	0.600	0		0.0	200	1.50	0.5	1.06	3.1	3.1	5.20	9.00	0.60	1.24
D7A-D10,E3A	D10B	19.37	0.498	0.598									20.5	2.95	5.05	28.46	58.50
D9A	D9A	3.18	0.900	0.900	0		0.0	620	1.50	0.5	1.06	9.7	9.7	5.20	9.00	14.88	25.76
D7A-D10,E3A	D9B	22.55	0.555	0.641									30.3	2.30	4.05	28.79	58.54
E3	E3	0.70	0.714	0.779	0		0.0	620	1.50	0.8	1.34	7.7	7.7	4.40	7.50	2.20	4.09
F		4.02	0.250	0.350	0		0.0	570	1.50	1.0	1.50	6.3	6.3	5.00	8.50	5.03	11.96
OD1,OC1,C,D1-D10,E2-E3,F	4	155.55	0.379	0.471									50.8	1.60	2.90	94.32	212.46
OE1		2.47	0.300	0.400	850	2.8	29.8	0				0.0	29.8	2.35	4.10	1.74	4.05
E1		1.50	0.900	0.900	0		0.0	700	2.00	2.3	3.03	3.8	3.8	5.20	9.00	7.02	12.15
OE1,E1	5	3.97	0.527	0.589									33.6	2.20	3.80	4.60	8.89

1) OVERLAND FLOW T<sub>co</sub> = (1.87 \* (1.1 - RUNOFF COEFFICIENT) \* (OVERLAND FLOW LENGTH<sup>0.5</sup>) / (SLOPE<sup>0.333</sup>))

2) SCS VELOCITY = K \* ((SLOPE(%))<sup>0.5</sup>)

K = 0.70 FOR MEADOW / FOREST

K = 1.0 FOR BARE SOIL

K = 1.5 FOR GRASS CHANNEL

K = 2.0 FOR PAVEMENT

3) GUTTER/SWALE FLOW, TRAVEL TIME, T<sub>t</sub> = (CHANNEL LENGTH / SCS VELOCITY) / 60 SEC

4) T<sub>c</sub> = T<sub>co</sub> + T<sub>t</sub>

\*\*\* IF TOTAL TIME OF CONCENTRATION IS LESS THAN 5 MINUTES, THEN 5 MINUTES IS USED

5) INTENSITY BASED ON I-D-F CURVE IN EL PASO COUNTY DRAINAGE CRITERIA MANUAL

6) Q = CiA

7) WEIGHTED AVERAGE C VALUES FOR COMBINED BASINS

**APPENDIX B**  
**HYDROLOGIC CALCULATIONS**

**Table 6-6. Runoff Coefficients for Rational Method**  
(Source: UDFCD 2001)

Land Use or Surface Characteristics	Percent Impervious	Runoff Coefficients											
		2-year		5-year		10-year		25-year		50-year		100-year	
		HSG A&B	HSG C&D	HSG A&B	HSG C&D	HSG A&B	HSG C&D	HSG A&B	HSG C&D	HSG A&B	HSG C&D	HSG A&B	HSG C&D
Business													
Commercial Areas	95	0.79	0.80	0.81	0.82	0.83	0.84	0.85	0.87	0.87	0.88	0.88	0.89
Neighborhood Areas	70	0.45	0.49	0.49	0.53	0.53	0.57	0.58	0.62	0.60	0.65	0.62	0.68
Residential													
1/8 Acre or less	65	0.41	0.45	0.45	0.49	0.49	0.54	0.54	0.59	0.57	0.62	0.59	0.65
1/4 Acre	40	0.23	0.28	0.30	0.35	0.36	0.42	0.42	0.50	0.46	0.54	0.50	0.58
1/3 Acre	30	0.18	0.22	0.25	0.30	0.32	0.38	0.39	0.47	0.43	0.52	0.47	0.57
1/2 Acre	25	0.15	0.20	0.22	0.28	0.30	0.36	0.37	0.46	0.41	0.51	0.46	0.56
1 Acre	20	0.12	0.17	0.20	0.26	0.27	0.34	0.35	0.44	0.40	0.50	0.44	0.55
Industrial													
Light Areas	80	0.57	0.60	0.59	0.63	0.63	0.66	0.66	0.70	0.68	0.72	0.70	0.74
Heavy Areas	90	0.71	0.73	0.73	0.75	0.75	0.77	0.78	0.80	0.80	0.82	0.81	0.83
Parks and Cemeteries	7	0.05	0.09	0.12	0.19	0.20	0.29	0.30	0.40	0.34	0.46	0.39	0.52
Playgrounds	13	0.07	0.13	0.16	0.23	0.24	0.31	0.32	0.42	0.37	0.48	0.41	0.54
Railroad Yard Areas	40	0.23	0.28	0.30	0.35	0.36	0.42	0.42	0.50	0.46	0.54	0.50	0.58
Undeveloped Areas													
Historic Flow Analysis-- Greenbelts, Agriculture	2	0.03	0.05	0.09	0.16	0.17	0.26	0.26	0.38	0.31	0.45	0.36	0.51
Pasture/Meadow	0	0.02	0.04	0.08	0.15	0.15	0.25	0.25	0.37	0.30	0.44	0.35	0.50
Forest	0	0.02	0.04	0.08	0.15	0.15	0.25	0.25	0.37	0.30	0.44	0.35	0.50
Exposed Rock	100	0.89	0.89	0.90	0.90	0.92	0.92	0.94	0.94	0.95	0.95	0.96	0.96
Offsite Flow Analysis (when landuse is undefined)	45	0.26	0.31	0.32	0.37	0.38	0.44	0.44	0.51	0.48	0.55	0.51	0.59
Streets													
Paved	100	0.89	0.89	0.90	0.90	0.92	0.92	0.94	0.94	0.95	0.95	0.96	0.96
Gravel	80	0.57	0.60	0.59	0.63	0.63	0.66	0.66	0.70	0.68	0.72	0.70	0.74
Drive and Walks	100	0.89	0.89	0.90	0.90	0.92	0.92	0.94	0.94	0.95	0.95	0.96	0.96
Roofs	90	0.71	0.73	0.73	0.75	0.75	0.77	0.78	0.80	0.80	0.82	0.81	0.83
Lawns	0	0.02	0.04	0.08	0.15	0.15	0.25	0.25	0.37	0.30	0.44	0.35	0.50

### 3.2 Time of Concentration

One of the basic assumptions underlying the Rational Method is that runoff is a function of the average rainfall rate during the time required for water to flow from the hydraulically most remote part of the drainage area under consideration to the design point. However, in practice, the time of concentration can be an empirical value that results in reasonable and acceptable peak flow calculations.

For urban areas, the time of concentration ( $t_c$ ) consists of an initial time or overland flow time ( $t_i$ ) plus the travel time ( $t_r$ ) in the storm sewer, paved gutter, roadside drainage ditch, or drainage channel. For non-urban areas, the time of concentration consists of an overland flow time ( $t_i$ ) plus the time of travel in a concentrated form, such as a swale or drainageway. The travel portion ( $t_r$ ) of the time of concentration can be estimated from the hydraulic properties of the storm sewer, gutter, swale, ditch, or drainageway. Initial time, on the other hand, will vary with surface slope, depression storage, surface cover, antecedent rainfall, and infiltration capacity of the soil, as well as distance of surface flow. The time of concentration is represented by Equation 6-7 for both urban and non-urban areas.



$$t_c = t_i + t_t \quad (\text{Eq. 6-7})$$

Where:

$t_c$  = time of concentration (min)

$t_i$  = overland (initial) flow time (min)

$t_t$  = travel time in the ditch, channel, gutter, storm sewer, etc. (min)

### 3.2.1 Overland (Initial) Flow Time

The overland flow time,  $t_i$ , may be calculated using Equation 6-8.

$$t_i = \frac{0.395(1.1 - C_5)\sqrt{L}}{S^{0.33}} \quad (\text{Eq. 6-8})$$

Where:

$t_i$  = overland (initial) flow time (min)

$C_5$  = runoff coefficient for 5-year frequency (see Table 6-6)

$L$  = length of overland flow (300 ft maximum for non-urban land uses, 100 ft maximum for urban land uses)

$S$  = average basin slope (ft/ft)

Note that in some urban watersheds, the overland flow time may be very small because flows quickly concentrate and channelize.

### 3.2.2 Travel Time

For catchments with overland and channelized flow, the time of concentration needs to be considered in combination with the travel time,  $t_t$ , which is calculated using the hydraulic properties of the swale, ditch, or channel. For preliminary work, the overland travel time,  $t_t$ , can be estimated with the help of Figure 6-25 or Equation 6-9 (Guo 1999).

$$V = C_v S_w^{0.5} \quad (\text{Eq. 6-9})$$

Where:

$V$  = velocity (ft/s)

$C_v$  = conveyance coefficient (from Table 6-7)

$S_w$  = watercourse slope (ft/ft)

**Table 6-7. Conveyance Coefficient,  $C_v$** 

Type of Land Surface	$C_v$
Heavy meadow	2.5
Tillage/field	5
Riprap (not buried)*	6.5
Short pasture and lawns	7
Nearly bare ground	10
Grassed waterway	15
Paved areas and shallow paved swales	20

\* For buried riprap, select  $C_v$  value based on type of vegetative cover.

The travel time is calculated by dividing the flow distance (in feet) by the velocity calculated using Equation 6-9 and converting units to minutes.

The time of concentration ( $t_c$ ) is then the sum of the overland flow time ( $t_i$ ) and the travel time ( $t_t$ ) per Equation 6-7.

### 3.2.3 First Design Point Time of Concentration in Urban Catchments

Using this procedure, the time of concentration at the first design point (typically the first inlet in the system) in an urbanized catchment should not exceed the time of concentration calculated using Equation 6-10. The first design point is defined as the point where runoff first enters the storm sewer system.

$$t_c = \frac{L}{180} + 10 \quad (\text{Eq. 6-10})$$

Where:

$t_c$  = maximum time of concentration at the first design point in an urban watershed (min)

$L$  = waterway length (ft)

Equation 6-10 was developed using the rainfall-runoff data collected in the Denver region and, in essence, represents regional “calibration” of the Rational Method. Normally, Equation 6-10 will result in a lesser time of concentration at the first design point and will govern in an urbanized watershed. For subsequent design points, the time of concentration is calculated by accumulating the travel times in downstream drainageway reaches.


### 3.2.4 Minimum Time of Concentration

If the calculations result in a  $t_c$  of less than 10 minutes for undeveloped conditions, it is recommended that a minimum value of 10 minutes be used. The minimum  $t_c$  for urbanized areas is 5 minutes.

### 3.2.5 Post-Development Time of Concentration

As Equation 6-8 indicates, the time of concentration is a function of the 5-year runoff coefficient for a drainage basin. Typically, higher levels of imperviousness (higher 5-year runoff coefficients) correspond to shorter times of concentration, and lower levels of imperviousness correspond to longer times of

**Figure 6-5. Colorado Springs Rainfall Intensity Duration Frequency**



**IDF Equations**

$$I_{100} = -2.52 \ln(D) + 12.735$$

$$I_{50} = -2.25 \ln(D) + 11.375$$

$$I_{25} = -2.00 \ln(D) + 10.111$$

$$I_{10} = -1.75 \ln(D) + 8.847$$

$$I_5 = -1.50 \ln(D) + 7.583$$

$$I_2 = -1.19 \ln(D) + 6.035$$

Note: Values calculated by equations may not precisely duplicate values read from figure.

**STRUTHERS RANCH POLARIS  
COMPOSITE RUNOFF COEFFICIENTS**

<b>EXISTING CONDITIONS</b>											
<b>5-YEAR C VALUES</b>											
BASIN	TOTAL AREA (AC)	(AC)	SUB-AREA 1 DEVELOPMENT/ COVER	C	AREA (AC)	SUB-AREA 2 DEVELOPMENT/ COVER	C	(AC)	SUB-AREA 3 DEVELOPMENT/ COVER	C	WEIGHTED C VALUE
A	2.74	2.74	VACANT	0.08							0.080
OB1	1.47	1.47	SF RESIDENTIAL	0.3							0.300
B	1.41	1.41	VACANT	0.08							0.080
OB1,B	2.88										0.192
A,OB1,B	5.62										0.138
<b>100-YEAR C VALUES</b>											
BASIN	TOTAL AREA (AC)	(AC)	SUB-AREA 1 DEVELOPMENT/ COVER	C	AREA (AC)	SUB-AREA 2 DEVELOPMENT/ COVER	C	(AC)	SUB-AREA 3 DEVELOPMENT/ COVER	C	WEIGHTED C VALUE
A	2.74	2.74	VACANT	0.35							0.350
OB1	1.47	1.47	SF RESIDENTIAL	0.5							0.500
B	1.41	1.41	VACANT	0.35							0.350
OB1,B	2.88										0.427
A,OB1,B	5.62										0.389

**STRUTHERS RANCH POLARIS  
COMPOSITE RUNOFF COEFFICIENTS**

<b>DEVELOPED CONDITIONS</b>											
<b>5-YEAR C VALUES</b>											
BASIN	TOTAL AREA (AC)	(AC)	SUB-AREA 1 DEVELOPMENT/ COVER	C	AREA (AC)	SUB-AREA 2 DEVELOPMENT/ COVER	C	(AC)	SUB-AREA 3 DEVELOPMENT/ COVER	C	WEIGHTED C VALUE
A	2.74	1.90	PAVED/IMPERVIOUS	0.9	0.84	LANDSCAPED	0.08				0.649
OB1	1.47	1.47	SF RESIDENTIAL	0.3							0.300
B	1.41	1.34	PAVED/IMPERVIOUS	0.9	0.07	LANDSCAPED	0.08				0.859
OB1,B	2.88										0.574
A,OB1,B	5.62										0.610
<b>100-YEAR C VALUES</b>											
BASIN	TOTAL AREA (AC)	(AC)	SUB-AREA 1 DEVELOPMENT/ COVER	C	AREA (AC)	SUB-AREA 2 DEVELOPMENT/ COVER	C	(AC)	SUB-AREA 3 DEVELOPMENT/ COVER	C	WEIGHTED C VALUE
A	2.74	1.90	PAVED/IMPERVIOUS	0.96	0.84	LANDSCAPED	0.35				0.773
OB1	1.47	1.47	SF RESIDENTIAL	0.5							0.500
B	1.41	1.34	PAVED/IMPERVIOUS	0.96	0.07	LANDSCAPED	0.35				0.930
OB1,B	2.88										0.710
A,OB1,B	5.62										0.741

**STRUTHERS RANCH POLARIS  
RATIONAL METHOD**

**EXISTING CONDITIONS**

BASIN	DESIGN POINT	AREA (AC)	C		Overland Flow			Channel flow					TOTAL Tc <sup>(4)</sup> (MIN)	TOTAL Tc <sup>(4)</sup> (MIN)	INTENSITY <sup>(5)</sup>		PEAK FLOW	
			5-YEAR	100-YEAR	LENGTH (FT)	SLOPE (FT/FT)	Tco <sup>(1)</sup> (MIN)	CHANNEL LENGTH (FT)	CONVEYANCE COEFFICIENT C	SLOPE (FT/FT)	SCS <sup>(2)</sup> VELOCITY (FT/S)	Tt <sup>(3)</sup> (MIN)			5-YR (IN/HR)	100-YR (IN/HR)	Q5 <sup>(6)</sup> (CFS)	Q100 <sup>(6)</sup> (CFS)
			A	A	2.74	0.080	0.350	100	0.030	13.0	275	15			0.047	3.25	1.4	14.4
OB1	OB1	1.47	0.300	0.500	100	0.020	11.6					0.0	11.6	11.6	3.90	6.55	1.72	4.82
B	B	1.41	0.080	0.350	100	0.030	13.0	585	15	0.018	2.01	4.8	17.8	17.8	3.26	5.48	0.37	2.70
OB1,B	B1	2.88	0.192	0.427									16.5	16.5	3.38	5.67	1.87	6.98
Tt DP-B1 to DP1								225	15	0.036	2.85	1.3						
<b>A,OB1,B</b>	<b>1</b>	<b>5.62</b>	<b>0.138</b>	<b>0.389</b>									<b>17.8</b>	<b>17.8</b>	<b>3.27</b>	<b>5.48</b>	<b>2.53</b>	<b>11.98</b>

**DEVELOPED CONDITIONS**

BASIN	DESIGN POINT	AREA (AC)	C		Overland Flow			Channel flow					TOTAL Tc <sup>(4)</sup> (MIN)	TOTAL Tc <sup>(4)</sup> (MIN)	INTENSITY <sup>(5)</sup>		PEAK FLOW	
			5-YEAR	100-YEAR	LENGTH (FT)	SLOPE (FT/FT)	Tco <sup>(1)</sup> (MIN)	CHANNEL LENGTH (FT)	CONVEYANCE COEFFICIENT C	SLOPE (FT/FT)	SCS <sup>(2)</sup> VELOCITY (FT/S)	Tt <sup>(3)</sup> (MIN)			5-YR (IN/HR)	100-YR (IN/HR)	Q5 <sup>(6)</sup> (CFS)	Q100 <sup>(6)</sup> (CFS)
			A	A	2.74	0.649	0.773	60	0.083	3.2	490	20			0.027	3.29	2.5	5.6
OB1	OB1	1.47	0.300	0.500	100	0.020	11.6					0.0	11.6	11.6	3.90	6.55	1.72	4.82
B	B	1.41	0.859	0.930	100	0.030	3.1	500	20	0.02	2.83	2.9	6.0	6.0	4.89	8.22	5.93	10.78
OB1,B	B1	2.88	0.574	0.710									14.6	14.6	3.56	5.98	5.89	12.24
Tt DP-B1 to DP1								225	20	0.036	3.79	1.0						
<b>A,OB1,B</b>	<b>1</b>	<b>5.62</b>	<b>0.610</b>	<b>0.741</b>									<b>15.6</b>	<b>15.6</b>	<b>3.47</b>	<b>5.82</b>	<b>11.88</b>	<b>24.23</b>

**DEVELOPED CONDITIONS - COMPARISON WITH SUBDIVISION DRAINAGE REPORT ("FINAL DRAINAGE REPORT FOR STRUTHERS RANCH FILING NO. 2" BY JPS DATED 10/14/04)**

BASIN	DESIGN POINT	AREA (AC)	C		Overland Flow			Channel flow					TOTAL Tc <sup>(4)</sup> (MIN)	TOTAL Tc <sup>(4)</sup> (MIN)	INTENSITY <sup>(5)</sup>		PEAK FLOW	
			5-YEAR	100-YEAR	LENGTH (FT)	SLOPE (FT/FT)	Tco <sup>(1)</sup> (MIN)	CHANNEL LENGTH (FT)	CONVEYANCE COEFFICIENT C	SLOPE (FT/FT)	SCS <sup>(2)</sup> VELOCITY (FT/S)	Tt <sup>(3)</sup> (MIN)			5-YR (IN/HR)	100-YR (IN/HR)	Q5 <sup>(6)</sup> (CFS)	Q100 <sup>(6)</sup> (CFS)
			D6A	D6A	3.00	0.900	0.900			0.0	300	15			0.04	3.00	1.7	1.7
D9A	D9A	3.18	0.900	0.900			0.0	620	15	0.005	1.06	9.7	9.7	9.7	4.17	7.00	11.93	20.03
<b>D6A,D9A</b>	<b>1</b>	<b>6.18</b>	<b>0.900</b>	<b>0.900</b>									<b>9.7</b>	<b>9.7</b>	<b>4.17</b>	<b>7.00</b>	<b>23.18</b>	<b>38.92</b>

- 1) OVERLAND FLOW Tco = (0.395\*(1.1-RUNOFF COEFFICIENT)\*(OVERLAND FLOW LENGTH^0.5)/(SLOPE^0.333))
- 2) SCS VELOCITY = C \* ((SLOPE(FT/FT))^0.5)
  - C = 2.5 FOR HEAVY MEADOW
  - C = 5 FOR TILLAGE/FIELD
  - C = 7 FOR SHORT PASTURE AND LAWNS
  - C = 10 FOR NEARLY BARE GROUND
  - C = 15 FOR GRASSED WATERWAY
  - C = 20 FOR PAVED AREAS AND SHALLOW PAVED SWALES
- 3) MANNING'S CHANNEL TRAVEL TIME = LV (WHEN CHANNEL VELOCITY IS KNOWN)
- 4) Tc = Tco + Tt
- \*\*\* IF TOTAL TIME OF CONCENTRATION IS LESS THAN 5 MINUTES, THEN 5 MINUTES IS USED
- 5) INTENSITY BASED ON I-D-F EQUATIONS IN CITY OF COLORADO SPRINGS DRAINAGE CRITERIA MANUAL
  - I<sub>5</sub> = -1.5 \* ln(Tc) + 7.583
  - I<sub>100</sub> = -2.52 \* ln(Tc) + 12.735
- 6) Q = CiA

**APPENDIX C**  
**HYDRAULIC CALCULATIONS**

**STRUTHERS RANCH POLARIS  
STORM INLET SIZING SUMMARY**

INLET	BASIN FLOW			INLET FLOW			INLET CONDITION / TYPE	INLET SIZE (FT)	INLET CAPACITY (CFS)
	DP	Q5 FLOW (CFS)	Q100 FLOW (CFS)	INLET FLOW % OF BASIN	Q5 FLOW (CFS)	Q100 FLOW (CFS)			
A1	A	8.9	17.7	40	3.6	7.1	SUMP TYPE 16	SGL	8.7




**ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)**

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project:  
Inlet ID:

**Struthers Ranch Polaris - Inlet A1**  
**Inlet A1**



**Gutter Geometry (Enter data in the blue cells)**

Maximum Allowable Width for Spread Behind Curb  
 Side Slope Behind Curb (leave blank for no conveyance credit behind curb)  
 Manning's Roughness Behind Curb (typically between 0.012 and 0.020)  
 Height of Curb at Gutter Flow Line  
 Distance from Curb Face to Street Crown  
 Gutter Width  
 Street Transverse Slope  
 Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)  
 Street Longitudinal Slope - Enter 0 for sump condition  
 Manning's Roughness for Street Section (typically between 0.012 and 0.020)

$T_{BACK} = 2.0$  ft  
 $S_{BACK} = 0.020$  ft/ft  
 $n_{BACK} = 0.020$   
 $H_{CURB} = 6.00$  inches  
 $T_{CROWN} = 50.0$  ft  
 $W = 2.00$  ft  
 $S_x = 0.020$  ft/ft  
 $S_w = 0.083$  ft/ft  
 $S_o = 0.000$  ft/ft  
 $n_{STREET} = 0.016$

Max. Allowable Spread for Minor & Major Storm  
 Max. Allowable Depth at Gutter Flowline for Minor & Major Storm  
 Check boxes are not applicable in SUMP conditions

	Minor Storm	Major Storm	
$T_{MAX} =$	50.0	50.0	ft
$d_{MAX} =$	6.0	12.0	inches
	<input type="checkbox"/>	<input type="checkbox"/>	

**MINOR STORM** Allowable Capacity is based on Depth Criterion  
**MAJOR STORM** Allowable Capacity is based on Depth Criterion


$Q_{allow} =$ 

Minor Storm	Major Storm
SUMP	SUMP

 cfs

## INLET IN A SUMP OR SAG LOCATION

Version 4.05 Released March 2017



Design Information (Input)	MINOR	MAJOR	
Type of Inlet	Denver No. 16 Combination		
Local Depression (additional to continuous gutter depression 'a' from above)			
Number of Unit Inlets (Grate or Curb Opening)			
Water Depth at Flowline (outside of local depression)			
<b>Grate Information</b>			
Length of a Unit Grate			
Width of a Unit Grate			
Area Opening Ratio for a Grate (typical values 0.15-0.90)			
Clogging Factor for a Single Grate (typical value 0.50 - 0.70)			
Grate Weir Coefficient (typical value 2.15 - 3.60)			
Grate Orifice Coefficient (typical value 0.60 - 0.80)			
<b>Curb Opening Information</b>			
Length of a Unit Curb Opening			
Height of Vertical Curb Opening in Inches			
Height of Curb Orifice Throat in Inches			
Angle of Throat (see USDCM Figure ST-5)			
Side Width for Depression Pan (typically the gutter width of 2 feet)			
Clogging Factor for a Single Curb Opening (typical value 0.10)			
Curb Opening Weir Coefficient (typical value 2.3-3.7)			
Curb Opening Orifice Coefficient (typical value 0.60 - 0.70)			
<b>Low Head Performance Reduction (Calculated)</b>			
Depth for Grate Midwidth			
Depth for Curb Opening Weir Equation			
Combination Inlet Performance Reduction Factor for Long Inlets			
Curb Opening Performance Reduction Factor for Long Inlets			
Grated Inlet Performance Reduction Factor for Long Inlets			
<b>Total Inlet Interception Capacity (assumes clogged condition)</b>			
Inlet Capacity IS GOOD for Minor and Major Storms(>Q PEAK)			
	MINOR	MAJOR	
Type =	Denver No. 16 Combination		
$a_{local}$ =	2.00	2.00	inches
No =	1	1	
Ponding Depth =	6.0	12.0	inches
	MINOR	MAJOR	<input type="checkbox"/> Override Depths
$L_o (G)$ =	3.00	3.00	feet
$W_o$ =	1.73	1.73	feet
$A_{ratio}$ =	0.31	0.31	
$C_f (G)$ =	0.50	0.50	
$C_w (G)$ =	3.60	3.60	
$C_o (G)$ =	0.60	0.60	
	MINOR	MAJOR	
$L_o (C)$ =	3.00	3.00	feet
$H_{vert}$ =	6.50	6.50	inches
$H_{throat}$ =	5.25	5.25	inches
Theta =	0.00	0.00	degrees
$W_p$ =	2.00	2.00	feet
$C_f (C)$ =	0.10	0.10	
$C_w (C)$ =	3.70	3.70	
$C_o (C)$ =	0.66	0.66	
	MINOR	MAJOR	
$d_{grate}$ =	0.523	1.023	ft
$d_{curb}$ =	0.33	0.83	ft
$RF_{Combination}$ =	0.94	1.00	
$RF_{Curb}$ =	1.00	1.00	
$RF_{Grate}$ =	0.94	1.00	
	MINOR	MAJOR	
$Q_a$ =	3.9	8.7	cfs
$Q_{PEAK REQUIRED}$ =	3.6	7.1	cfs

**STRUTHERS RANCH POLARIS  
STORM SEWER SIZING SUMMARY**

PIPE FLOW				PIPE CAPACITY		
PIPE	DESIGN POINT	Q5 FLOW (CFS)	Q100 FLOW (CFS)	PIPE SIZE	MIN. PIPE SLOPE	PIPE CAPACITY (CFS)
A1	A1	3.6	7.1	18	1.0%	10.5

**ASSUMPTIONS:**

1. STORM DRAIN PIPE ASSUMED TO BE RCP OR HDPE

# Hydraulic Analysis Report

## Project Data

Project Title: Project - Polaris  
Designer: JPS  
Project Date: Monday, June 13, 2022  
Project Units: U.S. Customary Units  
Notes:

## Channel Analysis: SD-A1

Notes:

## Input Parameters

Channel Type: Circular  
Pipe Diameter: 1.5000 ft  
Longitudinal Slope: 0.0100 ft/ft  
Manning's n: 0.0130  
Depth: 1.5000 ft

## Result Parameters

Flow: 10.5043 cfs  
Area of Flow: 1.7671 ft<sup>2</sup>  
Wetted Perimeter: 4.7124 ft  
Hydraulic Radius: 0.3750 ft  
Average Velocity: 5.9442 ft/s  
Top Width: 0.0000 ft  
Froude Number: 0.0000  
Critical Depth: 1.2451 ft  
Critical Velocity: 6.6989 ft/s  
Critical Slope: 0.0098 ft/ft  
Critical Top Width: 1.13 ft  
Calculated Max Shear Stress: 0.9360 lb/ft<sup>2</sup>  
Calculated Avg Shear Stress: 0.2340 lb/ft<sup>2</sup>

## **APPENDIX D**

### **WATER QUALITY POND CALCULATIONS**


STRUTHERS RANCH POLARIS COMPOSITE IMPERVIOUS AREAS											
IMPERVIOUS AREAS											
BASIN	TOTAL AREA (AC)	(AC)	SUB-AREA 1 DEVELOPMENT/ COVER	PERCENT IMPERVIOUS	AREA (AC)	SUB-AREA 2 DEVELOPMENT/ COVER	PERCENT IMPERVIOUS	(AC)	SUB-AREA 3 DEVELOPMENT/ COVER	PERCENT IMPERVIOUS	WEIGHTED % IMP
A	2.74	1.90	PAVED/IMPERVIOUS	100	0.84	LANDSCAPED	0.00				69.343
OB1	1.47	1.47	SF RESIDENTIAL	40							40.000
B	1.41	1.34	PAVED/IMPERVIOUS	100	0.07	LANDSCAPED	0.00				95.000
OB1,B	2.88										66.927
A,OB1,B	5.62										68.105

# DETENTION BASIN STAGE-STORAGE TABLE BUILDER

MHFD-Detention, Version 4.05 (January 2022)

Project: **Struthers Ranch Polaris**

Basin ID: **Water Quality Pond A**



## Watershed Information

Selected BMP Type =	<b>EDB</b>
Watershed Area =	5.62 acres
Watershed Length =	825 ft
Watershed Length to Centroid =	400 ft
Watershed Slope =	0.024 ft/ft
Watershed Imperviousness =	68.10% percent
Percentage Hydrologic Soil Group A =	0.0% percent
Percentage Hydrologic Soil Group B =	100.0% percent
Percentage Hydrologic Soil Groups C/D =	0.0% percent
Target WQCV Drain Time =	40.0 hours
Location for 1-hr Rainfall Depths =	User Input

After providing required inputs above including 1-hour rainfall depths, click 'Run CUHP' to generate runoff hydrographs using the embedded Colorado Urban Hydrograph Procedure.

Water Quality Capture Volume (WQCV) =	0.125 acre-feet	Optional User Overrides	
Excess Urban Runoff Volume (EURV) =	0.419 acre-feet		
2-yr Runoff Volume (P1 = 1.19 in.) =	0.370 acre-feet	1.19	inches
5-yr Runoff Volume (P1 = 1.5 in.) =	0.500 acre-feet	1.50	inches
10-yr Runoff Volume (P1 = 1.75 in.) =	0.611 acre-feet	1.75	inches
25-yr Runoff Volume (P1 = 2 in.) =	0.743 acre-feet	2.00	inches
50-yr Runoff Volume (P1 = 2.25 in.) =	0.859 acre-feet	2.25	inches
100-yr Runoff Volume (P1 = 2.52 in.) =	0.998 acre-feet	2.52	inches
500-yr Runoff Volume (P1 = 3.14 in.) =	1.293 acre-feet	3.14	inches
Approximate 2-yr Detention Volume =	0.327 acre-feet		
Approximate 5-yr Detention Volume =	0.436 acre-feet		
Approximate 10-yr Detention Volume =	0.553 acre-feet		
Approximate 25-yr Detention Volume =	0.595 acre-feet		
Approximate 50-yr Detention Volume =	0.619 acre-feet		
Approximate 100-yr Detention Volume =	0.665 acre-feet		

## Define Zones and Basin Geometry

Zone 1 Volume (WQCV) =	0.125	acre-feet
Select Zone 2 Storage Volume (Optional) =		acre-feet
Select Zone 3 Storage Volume (Optional) =		acre-feet
Total Detention Basin Volume =	0.125	acre-feet

Total detention volume is less than 100-year volume.


Stage - Storage Description	Stage (ft)	Optional Override Stage (ft)	Length (ft)	Width (ft)	Area (ft <sup>2</sup> )	Optional Override Area (ft <sup>2</sup> )	Area (acre)	Volume (ft <sup>3</sup> )	Volume (ac-ft)
Top of Micropool	--	0.00	--	--	--	10	0.000		
Bot EL=6752.0	--	1.00	--	--	--	1,437	0.033	723	0.017
EL=6756.0	--	3.00	--	--	--	2,201	0.051	4,361	0.100
Top EL=6758.0	--	7.00	--	--	--	3,180	0.073	9,742	0.224
	--		--	--	--	4,160	0.096	17,082	0.392
	--		--	--	--				
	--		--	--	--				
	--		--	--	--				
	--		--	--	--				
	--		--	--	--				
	--		--	--	--				
	--		--	--	--				
	--		--	--	--				
	--		--	--	--				
	--		--	--	--				
	--		--	--	--				
	--		--	--	--				
	--		--	--	--				
	--		--	--	--				
	--		--	--	--				
	--		--	--	--				
	--		--	--	--				
	--		--	--	--				
	--		--	--	--				
	--		--	--	--				
	--		--	--	--				

SEE COMPOSITE IMPERVIOUS AREA CALCULATIONS ON PRECEDING PAGE (...WATER QUALITY POND A IS DESIGNED FOR THE COMBINED FLOW FROM DEVELOPED BASINS A, OB1, AND B)

# DETENTION BASIN OUTLET STRUCTURE DESIGN

MHFD-Detention, Version 4.05 (January 2022)

**Project:** Struthers Ranch Polaris  
**Basin ID:** Water Quality Pond A



**Example Zone Configuration (Retention Pond)**

	Estimated Stage (ft)	Estimated Volume (ac-ft)	Outlet Type
Zone 1 (WQCV)	3.47	0.125	Orifice Plate
Zone 2 (User)	3.47	0.000	Weir&Pipe (Restrict)
Zone 3			Not Utilized
<b>Total (all zones)</b>		<b>0.125</b>	

**User Input:** Orifice at Underdrain Outlet (typically used to drain WQCV in a Filtration BMP)

Underdrain Orifice Invert Depth =  ft (distance below the filtration media surface)  
 Underdrain Orifice Diameter =  inches

**Calculated Parameters for Underdrain**

Underdrain Orifice Area =  ft<sup>2</sup>  
 Underdrain Orifice Centroid =  feet

**User Input:** Orifice Plate with one or more orifices or Elliptical Slot Weir (typically used to drain WQCV and/or EURV in a sedimentation BMP)

Centroid of Lowest Orifice = <input type="text" value="0.00"/>	ft (relative to basin bottom at Stage = 0 ft)	WQ Orifice Area per Row = <input type="text" value="3.958E-03"/>	ft <sup>2</sup>
Depth at top of Zone using Orifice Plate = <input type="text" value="3.47"/>	ft (relative to basin bottom at Stage = 0 ft)	Elliptical Half-Width = <input type="text" value="N/A"/>	feet
Orifice Plate: Orifice Vertical Spacing = <input type="text" value="13.88"/>	inches	Elliptical Slot Centroid = <input type="text" value="N/A"/>	feet
Orifice Plate: Orifice Area per Row = <input type="text" value="0.57"/>	sq. inches (diameter = 13/16 inch)	Elliptical Slot Area = <input type="text" value="N/A"/>	ft <sup>2</sup>

should be 14.4" if spacing is 1.2ft as shown below. Shouldnt have a big impact on anything, but good to fix nonetheless.

**User Input:** Stage and Total Area of Each Orifice Row (numbered from lowest to highest)

	Row 1 (required)	Row 2 (optional)	Row 3 (optional)	Row 4 (optional)	Row 5 (optional)	Row 6 (optional)	Row 7 (optional)	Row 8 (optional)
Stage of Orifice Centroid (ft)	0.00	1.20	2.40					
Orifice Area (sq. inches)	0.57	0.57	0.57					
Stage of Orifice Centroid (ft)								
Orifice Area (sq. inches)								

**User Input:** Vertical Orifice (Circular or Rectangular)

Invert of Vertical Orifice = <input type="text" value="Not Selected"/>	<input type="text" value="Not Selected"/>	ft (relative to basin bottom at Stage = 0 ft)	Vertical Orifice Area = <input type="text" value="Not Selected"/>	ft <sup>2</sup>
Depth at top of Zone using Vertical Orifice = <input type="text" value="N/A"/>	<input type="text" value="N/A"/>	ft (relative to basin bottom at Stage = 0 ft)	Vertical Orifice Centroid = <input type="text" value="N/A"/>	feet
Vertical Orifice Diameter = <input type="text" value="N/A"/>	<input type="text" value="N/A"/>	inches		

**User Input:** Overflow Weir (Dropbox with Flat or Sloped Gate and Outlet Pipe OR Rectangular/Trapezoidal Weir and No Outlet Pipe)

Overflow Weir Front Edge Height, Ho = <input type="text" value="3.50"/>	<input type="text" value="N/A"/>	ft (relative to basin bottom at Stage = 0 ft)	Height of Gate Upper Edge, H <sub>1</sub> = <input type="text" value="3.50"/>	feet
Overflow Weir Front Edge Length = <input type="text" value="4.00"/>	<input type="text" value="N/A"/>	feet	Overflow Weir Slope Length = <input type="text" value="2.50"/>	feet
Overflow Weir Gate Slope = <input type="text" value="0.00"/>	<input type="text" value="N/A"/>	H:V	Gate Open Area / 100-yr Orifice Area = <input type="text" value="3.94"/>	
Horiz. Length of Weir Sides = <input type="text" value="2.50"/>	<input type="text" value="N/A"/>	feet	Overflow Gate Open Area w/o Debris = <input type="text" value="6.96"/>	ft <sup>2</sup>
Overflow Gate Type = <input type="text" value="Type C Gate"/>	<input type="text" value="N/A"/>		Overflow Gate Open Area w/ Debris = <input type="text" value="3.48"/>	ft <sup>2</sup>
Debris Clogging % = <input type="text" value="50%"/>	<input type="text" value="N/A"/>	%		

**User Input:** Outlet Pipe w/ Flow Restriction Plate (Circular Orifice, Restrictor Plate, or Rectangular Orifice)

Depth to Invert of Outlet Pipe = <input type="text" value="0.00"/>	<input type="text" value="N/A"/>	ft (distance below basin bottom at Stage = 0 ft)	Outlet Orifice Area = <input type="text" value="1.77"/>	ft <sup>2</sup>
Outlet Pipe Diameter = <input type="text" value="18.00"/>	<input type="text" value="N/A"/>	inches	Outlet Orifice Centroid = <input type="text" value="0.75"/>	feet
Restrictor Plate Height Above Pipe Invert = <input type="text" value="18.00"/>	<input type="text" value="N/A"/>	inches	Half-Central Angle of Restrictor Plate on Pipe = <input type="text" value="3.14"/>	radians

**User Input:** Emergency Spillway (Rectangular or Trapezoidal)

Spillway Invert Stage = <input type="text" value="5.50"/>	ft (relative to basin bottom at Stage = 0 ft)	Spillway Design Flow Depth = <input type="text" value="0.50"/>	feet
Spillway Crest Length = <input type="text" value="14.00"/>	feet	Stage at Top of Freeboard = <input type="text" value="7.00"/>	feet
Spillway End Slopes = <input type="text" value="4.00"/>	H:V	Basin Area at Top of Freeboard = <input type="text" value="0.10"/>	acres
Freeboard above Max Water Surface = <input type="text" value="1.00"/>	feet	Basin Volume at Top of Freeboard = <input type="text" value="0.39"/>	acre-ft

## Routed Hydrograph Results




*The user can override the default CUHP hydrographs and runoff volumes by entering new values in the Inflow Hydrographs table (Columns W through AF).*

	WQCV	EURV	2 Year	5 Year	10 Year	25 Year	50 Year	100 Year	500 Year
Design Storm Return Period =									
One-Hour Rainfall Depth (in) =	N/A	N/A	1.19	1.50	1.75	2.00	2.25	2.52	3.14
CUHP Runoff Volume (acre-ft) =	0.125	0.419	0.370	0.500	0.611	0.743	0.859	0.998	1.293
Inflow Hydrograph Volume (acre-ft) =	N/A	N/A	0.370	0.500	0.611	0.743	0.859	0.998	1.293
CUHP Predevelopment Peak Q (cfs) =	N/A	N/A	0.6	1.6	2.4	4.3	5.4	6.9	9.7
OPTIONAL Override Predevelopment Peak Q (cfs) =	N/A	N/A							
Predevelopment Unit Peak Flow, q (cfs/acre) =	N/A	N/A	0.10	0.29	0.43	0.77	0.96	1.23	1.72
Peak Inflow Q (cfs) =	N/A	N/A	6.3	8.5	10.0	12.5	14.4	17.0	21.9
Peak Outflow Q (cfs) =	0.1	34.6	4.5	7.1	9.5	12.8	14.2	16.3	18.2
Ratio Peak Outflow to Predevelopment Q =	N/A	N/A	N/A	4.4	3.9	3.0	2.6	2.3	1.9
Structure Controlling Flow	Plate	Overflow Weir 1	Overflow Weir 1	Overflow Weir 1	Overflow Weir 1	Overflow Weir 1	Overflow Weir 1	Outlet Plate 1	Outlet Plate 1
Max Velocity through Gate 1 (fps) =	N/A	1.03	0.62	1.0	1.4	1.8	2.0	2.3	2.6
Max Velocity through Gate 2 (fps) =	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Time to Drain 97% of Inflow Volume (hours) =	38	34	35	33	30	28	26	25	21
Time to Drain 99% of Inflow Volume (hours) =	41	39	41	40	39	38	37	36	34
Maximum Ponding Depth (ft) =	3.47	3.99	3.85	3.98	4.09	4.22	4.27	4.41	5.31
Area at Maximum Ponding Depth (acres) =	0.06	0.06	0.06	0.06	0.06	0.06	0.06	0.07	0.08
Maximum Volume Stored (acre-ft) =	0.125	0.156	0.147	0.155	0.161	0.169	0.173	0.182	0.246



# DETENTION BASIN OUTLET STRUCTURE DESIGN

*MHFD-Detention, Version 4.05 (January 2022)*



S-A-V-D Chart Axis Override	X-axis	Left Y-Axis	Right Y-Axis
minimum bound			
maximum bound			

# DETENTION BASIN OUTLET STRUCTURE DESIGN

Outflow Hydrograph Workbook Filename: \_\_\_\_\_

## Inflow Hydrographs

The user can override the calculated inflow hydrographs from this workbook with inflow hydrographs developed in a separate program.

Time Interval	SOURCE	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	
	TIME	WQCV [cfs]	EURV [cfs]	2 Year [cfs]	5 Year [cfs]	10 Year [cfs]	25 Year [cfs]	50 Year [cfs]	100 Year [cfs]	500 Year [cfs]	
5.00 min	0:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	0:05:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	0:10:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.08	0.01	0.26
	0:15:00	0.00	0.00	0.00	0.72	1.18	1.45	0.98	1.21	1.19	1.67
	0:20:00	0.00	0.00	0.00	2.48	3.23	3.87	2.38	2.76	2.96	3.90
	0:25:00	0.00	0.00	0.00	5.30	7.33	9.05	5.20	6.06	6.57	9.09
	0:30:00	0.00	0.00	0.00	6.26	8.45	10.02	11.61	13.52	15.09	19.59
	0:35:00	0.00	0.00	0.00	5.65	7.50	8.85	12.49	14.45	17.02	21.87
	0:40:00	0.00	0.00	0.00	4.92	6.40	7.56	11.73	13.53	15.83	20.30
	0:45:00	0.00	0.00	0.00	4.02	5.36	6.43	10.17	11.73	14.18	18.17
	0:50:00	0.00	0.00	0.00	3.31	4.52	5.33	8.93	10.29	12.36	15.82
	0:55:00	0.00	0.00	0.00	2.83	3.86	4.62	7.31	8.43	10.42	13.37
	1:00:00	0.00	0.00	0.00	2.50	3.38	4.12	6.23	7.20	9.16	11.76
	1:05:00	0.00	0.00	0.00	2.20	2.97	3.66	5.42	6.27	8.22	10.56
	1:10:00	0.00	0.00	0.00	1.80	2.57	3.23	4.48	5.19	6.57	8.48
	1:15:00	0.00	0.00	0.00	1.45	2.14	2.85	3.66	4.25	5.19	6.73
	1:20:00	0.00	0.00	0.00	1.21	1.78	2.43	2.85	3.30	3.82	4.95
	1:25:00	0.00	0.00	0.00	1.08	1.59	2.07	2.27	2.63	2.82	3.67
	1:30:00	0.00	0.00	0.00	1.01	1.49	1.83	1.85	2.13	2.22	2.89
	1:35:00	0.00	0.00	0.00	0.98	1.41	1.67	1.58	1.82	1.85	2.41
	1:40:00	0.00	0.00	0.00	0.96	1.26	1.55	1.40	1.61	1.60	2.08
	1:45:00	0.00	0.00	0.00	0.94	1.14	1.47	1.29	1.46	1.42	1.85
	1:50:00	0.00	0.00	0.00	0.93	1.06	1.41	1.21	1.37	1.30	1.70
	1:55:00	0.00	0.00	0.00	0.80	0.99	1.33	1.15	1.30	1.22	1.59
	2:00:00	0.00	0.00	0.00	0.70	0.92	1.19	1.12	1.26	1.18	1.53
	2:05:00	0.00	0.00	0.00	0.51	0.67	0.86	0.81	0.91	0.86	1.11
	2:10:00	0.00	0.00	0.00	0.37	0.48	0.61	0.58	0.65	0.62	0.80
	2:15:00	0.00	0.00	0.00	0.26	0.34	0.43	0.41	0.46	0.44	0.57
	2:20:00	0.00	0.00	0.00	0.18	0.23	0.30	0.29	0.32	0.31	0.40
	2:25:00	0.00	0.00	0.00	0.12	0.15	0.20	0.20	0.22	0.21	0.27
	2:30:00	0.00	0.00	0.00	0.08	0.10	0.14	0.13	0.15	0.14	0.19
	2:35:00	0.00	0.00	0.00	0.05	0.07	0.09	0.09	0.10	0.09	0.12
	2:40:00	0.00	0.00	0.00	0.02	0.04	0.05	0.05	0.06	0.05	0.07
	2:45:00	0.00	0.00	0.00	0.01	0.02	0.02	0.02	0.02	0.02	0.03
	2:50:00	0.00	0.00	0.00	0.00	0.00	0.00	0.01	0.01	0.01	0.01
	2:55:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:05:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:10:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:15:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:20:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:25:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:30:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:35:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:40:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:45:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:50:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:55:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
4:05:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
4:10:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
4:15:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
4:20:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
4:25:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
4:30:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
4:35:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
4:40:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
4:45:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
4:50:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
4:55:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
5:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
5:05:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
5:10:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
5:15:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
5:20:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
5:25:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
5:30:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
5:35:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
5:40:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
5:45:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
5:50:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
5:55:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
6:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	

**Design Procedure Form: Extended Detention Basin (EDB)**

UD-BMP (Version 3.07, March 2018)

Sheet 1 of 3

**Designer:** JPS  
**Company:** JPS  
**Date:** October 21, 2022  
**Project:** Struthers Ranch Polaris  
**Location:** Water Quality Pond A - Forebay A1

1. Basin Storage Volume

A) Effective Imperviousness of Tributary Area,  $I_a$

B) Tributary Area's Imperviousness Ratio ( $i = I_a / 100$ )

C) Contributing Watershed Area

D) For Watersheds Outside of the Denver Region, Depth of Average Runoff Producing Storm

E) Design Concept  
(Select EURV when also designing for flood control)

F) Design Volume (WQCV) Based on 40-hour Drain Time  
( $V_{DESIGN} = (1.0 * (0.91 * i^3 - 1.19 * i^2 + 0.78 * i) / 12 * Area)$ )

G) For Watersheds Outside of the Denver Region, Water Quality Capture Volume (WQCV) Design Volume  
( $V_{WQCV\ OTHER} = (d_s * V_{DESIGN} / 0.43)$ )

H) User Input of Water Quality Capture Volume (WQCV) Design Volume  
(Only if a different WQCV Design Volume is desired)

I) NRCS Hydrologic Soil Groups of Tributary Watershed  
 i) Percentage of Watershed consisting of Type A Soils  
 ii) Percentage of Watershed consisting of Type B Soils  
 iii) Percentage of Watershed consisting of Type C/D Soils

J) Excess Urban Runoff Volume (EURV) Design Volume  
 For HSG A:  $EURV_A = 1.68 * i^{1.28}$   
 For HSG B:  $EURV_B = 1.36 * i^{1.08}$   
 For HSG C/D:  $EURV_{C/D} = 1.20 * i^{1.08}$

K) User Input of Excess Urban Runoff Volume (EURV) Design Volume  
(Only if a different EURV Design Volume is desired)

$I_a =$   %  
 $i =$    
 Area =  ac  
 $d_s =$   in

Choose One  
 Water Quality Capture Volume (WQCV)  
 Excess Urban Runoff Volume (EURV)

$V_{DESIGN} =$   ac-ft  
 $V_{DESIGN\ OTHER} =$   ac-ft  
 $V_{DESIGN\ USER} =$   ac-ft

$HSG_A =$   %  
 $HSG_B =$   %  
 $HSG_{C/D} =$   %

$EURV_{DESIGN} =$   ac-ft  
 $EURV_{DESIGN\ USER} =$   ac-ft

2. Basin Shape: Length to Width Ratio  
(A basin length to width ratio of at least 2:1 will improve TSS reduction.)

L : W =  : 1

3. Basin Side Slopes

A) Basin Maximum Side Slopes  
(Horizontal distance per unit vertical, 4:1 or flatter preferred)

Z =  ft / ft  
**DIFFICULT TO MAINTAIN, INCREASE WHERE POSSIBLE**

4. Inlet

A) Describe means of providing energy dissipation at concentrated inflow locations:

Concrete Forebay

---



---



---

5. Forebay

A) Minimum Forebay Volume  
( $V_{MIN} =$   % of the WQCV)

B) Actual Forebay Volume

C) Forebay Depth  
( $D_F =$   inch maximum)

D) Forebay Discharge  
 i) Undetained 100-year Peak Discharge  
 ii) Forebay Discharge Design Flow  
( $Q_F = 0.02 * Q_{100}$ )

E) Forebay Discharge Design

F) Discharge Pipe Size (minimum 8-inches)

G) Rectangular Notch Width

$V_{MIN} =$   ac-ft  
 $V_F =$   ac-ft  
 $D_F =$   in  
 $Q_{100} =$   cfs  
 $Q_F =$   cfs

Choose One  
 Berm With Pipe  
 Wall with Rect. Notch  
 Wall with V-Notch Weir

Flow too small for berm w/ pipe

Calculated  $D_P =$   in

Calculated  $W_N =$   in

**Design Procedure Form: Extended Detention Basin (EDB)**

**Designer:** JPS  
**Company:** JPS  
**Date:** October 21, 2022  
**Project:** Struthers Ranch Polaris  
**Location:** Water Quality Pond A - Forebay A1

<p>6. Trickle Channel</p> <p>A) Type of Trickle Channel</p> <p>F) Slope of Trickle Channel</p>	<div style="border: 1px solid black; padding: 2px; margin-bottom: 10px;">             Choose One  <input checked="" type="radio"/> Concrete  <input type="radio"/> Soft Bottom         </div> <p>S = <input type="text" value="0.0050"/> ft / ft</p>
<p>7. Micropool and Outlet Structure</p> <p>A) Depth of Micropool (2.5-foot minimum)</p> <p>B) Surface Area of Micropool (10 ft<sup>2</sup> minimum)</p> <p>C) Outlet Type</p> <p>D) Smallest Dimension of Orifice Opening Based on Hydrograph Routing (Use UD-Detention)</p> <p>E) Total Outlet Area</p>	<p>D<sub>M</sub> = <input type="text" value="2.5"/> ft</p> <p>A<sub>M</sub> = <input type="text" value=""/> sq ft</p> <div style="border: 1px solid black; padding: 2px; margin-bottom: 10px;">             Choose One  <input checked="" type="radio"/> Orifice Plate  <input type="radio"/> Other (Describe):         </div> <hr/> <hr/> <p>D<sub>orifice</sub> = <input type="text" value="0.58"/> inches</p> <p>A<sub>orifice</sub> = <input type="text" value="1.74"/> square inches</p>
<p>8. Initial Surcharge Volume</p> <p>A) Depth of Initial Surcharge Volume (Minimum recommended depth is 4 inches)</p> <p>B) Minimum Initial Surcharge Volume (Minimum volume of 0.3% of the WQCV)</p> <p>C) Initial Surcharge Provided Above Micropool</p>	<p>D<sub>IS</sub> = <input type="text" value="6"/> in</p> <p>V<sub>IS</sub> = <input type="text" value=""/> cu ft</p> <p>V<sub>s</sub> = <input type="text" value=""/> cu ft</p>
<p>9. Trash Rack</p> <p>A) Water Quality Screen Open Area: <math>A_t = A_{ot} * 38.5 * (e^{-0.095D})</math></p> <p>B) Type of Screen (If specifying an alternative to the materials recommended in the USDCM, indicate "other" and enter the ratio of the total open are to the total screen are for the material specified.)</p> <p style="margin-left: 40px;">Other (Y/N): <input type="text" value="N"/></p> <p>C) Ratio of Total Open Area to Total Area (only for type 'Other')</p> <p>D) Total Water Quality Screen Area (based on screen type)</p> <p>E) Depth of Design Volume (EURV or WQCV) (Based on design concept chosen under 1E)</p> <p>F) Height of Water Quality Screen (H<sub>TR</sub>)</p> <p>G) Width of Water Quality Screen Opening (W<sub>opening</sub>) (Minimum of 12 inches is recommended)</p>	<p>A<sub>t</sub> = <input type="text" value="63"/> square inches</p> <div style="border: 1px solid black; padding: 2px; margin-bottom: 10px; width: fit-content;">             S.S. Well Screen with 60% Open Area         </div> <hr/> <hr/> <p>User Ratio = <input type="text" value=""/></p> <p>A<sub>total</sub> = <input type="text" value="106"/> sq. in.</p> <p>H = <input type="text" value="3.47"/> feet</p> <p>H<sub>TR</sub> = <input type="text" value="69.64"/> inches</p> <p>W<sub>opening</sub> = <input type="text" value="12.0"/> inches <span style="color: red; font-weight: bold;">VALUE LESS THAN RECOMMENDED MIN. WIDTH. WIDTH HAS BEEN SET TO 12 INCHES.</span></p>

**Design Procedure Form: Extended Detention Basin (EDB)**

Sheet 3 of 3

**Designer:** JPS  
**Company:** JPS  
**Date:** October 21, 2022  
**Project:** Struthers Ranch Polaris  
**Location:** Water Quality Pond A - Forebay A1

<p>10. Overflow Embankment</p> <p>A) Describe embankment protection for 100-year and greater overtopping:</p> <p>B) Slope of Overflow Embankment (Horizontal distance per unit vertical, 4:1 or flatter preferred)</p>	<p align="center"><u>Buried Riprap Spillway</u></p> <hr/> <p align="center">Ze = <span style="border: 1px solid black; padding: 2px;">4.00</span> ft / ft</p>
<p>11. Vegetation</p>	<div style="border: 1px solid black; padding: 5px; width: fit-content;"> <p align="center">Choose One</p> <p align="center"> <input type="radio"/> Irrigated  <input checked="" type="radio"/> Not Irrigated                 </p> </div>
<p>12. Access</p> <p>A) Describe Sediment Removal Procedures</p>	<p align="center"><u>Periodic inspection and removal as needed; Access ramp provided to pond bottom</u></p> <hr/> <hr/> <hr/>
<p>Notes: _____</p> <hr/> <hr/> <hr/>	

**Design Procedure Form: Extended Detention Basin (EDB)**

UD-BMP (Version 3.07, March 2018)

Sheet 1 of 3

**Designer:** JPS  
**Company:** JPS  
**Date:** October 21, 2022  
**Project:** Struthers Ranch Polaris  
**Location:** Water Quality Pond A - Forebay B1

1. Basin Storage Volume

A) Effective Imperviousness of Tributary Area,  $I_a$

B) Tributary Area's Imperviousness Ratio ( $i = I_a / 100$ )

C) Contributing Watershed Area

D) For Watersheds Outside of the Denver Region, Depth of Average Runoff Producing Storm

E) Design Concept  
(Select EURV when also designing for flood control)

F) Design Volume (WQCV) Based on 40-hour Drain Time  
( $V_{DESIGN} = (1.0 * (0.91 * i^3 - 1.19 * i^2 + 0.78 * i) / 12 * Area)$ )

G) For Watersheds Outside of the Denver Region, Water Quality Capture Volume (WQCV) Design Volume  
( $V_{WQCV\ OTHER} = (d_s * V_{DESIGN} / 0.43)$ )

H) User Input of Water Quality Capture Volume (WQCV) Design Volume  
(Only if a different WQCV Design Volume is desired)

I) NRCS Hydrologic Soil Groups of Tributary Watershed  
 i) Percentage of Watershed consisting of Type A Soils  
 ii) Percentage of Watershed consisting of Type B Soils  
 iii) Percentage of Watershed consisting of Type C/D Soils

J) Excess Urban Runoff Volume (EURV) Design Volume  
 For HSG A:  $EURV_A = 1.68 * i^{1.28}$   
 For HSG B:  $EURV_B = 1.36 * i^{1.08}$   
 For HSG C/D:  $EURV_{C/D} = 1.20 * i^{1.08}$

K) User Input of Excess Urban Runoff Volume (EURV) Design Volume  
(Only if a different EURV Design Volume is desired)

$I_a =$   %  
 $i =$    
 Area =  ac  
 $d_s =$   in

Choose One  
 Water Quality Capture Volume (WQCV)  
 Excess Urban Runoff Volume (EURV)

$V_{DESIGN} =$   ac-ft  
 $V_{DESIGN\ OTHER} =$   ac-ft  
 $V_{DESIGN\ USER} =$   ac-ft

$HSG_A =$   %  
 $HSG_B =$   %  
 $HSG_{C/D} =$   %

$EURV_{DESIGN} =$   ac-ft  
 $EURV_{DESIGN\ USER} =$   ac-ft

2. Basin Shape: Length to Width Ratio  
(A basin length to width ratio of at least 2:1 will improve TSS reduction.)

L : W =  : 1

3. Basin Side Slopes

A) Basin Maximum Side Slopes  
(Horizontal distance per unit vertical, 4:1 or flatter preferred)

Z =  ft / ft  
**DIFFICULT TO MAINTAIN, INCREASE WHERE POSSIBLE**

4. Inlet

A) Describe means of providing energy dissipation at concentrated inflow locations:

Concrete Forebay

---



---



---

5. Forebay

A) Minimum Forebay Volume  
( $V_{FMIN} =$   % of the WQCV)

B) Actual Forebay Volume

C) Forebay Depth  
( $D_F =$   inch maximum)

D) Forebay Discharge  
 i) Undetained 100-year Peak Discharge  
 ii) Forebay Discharge Design Flow  
( $Q_F = 0.02 * Q_{100}$ )

E) Forebay Discharge Design

F) Discharge Pipe Size (minimum 8-inches)

G) Rectangular Notch Width

$V_{FMIN} =$   ac-ft  
 $V_F =$   ac-ft  
 $D_F =$   in  
 $Q_{100} =$   cfs  
 $Q_F =$   cfs

Choose One  
 Berm With Pipe  
 Wall with Rect. Notch  
 Wall with V-Notch Weir

Flow too small for berm w/ pipe

Calculated  $D_P =$   in  
 Calculated  $W_N =$   in

**Design Procedure Form: Extended Detention Basin (EDB)**

**Designer:** JPS  
**Company:** JPS  
**Date:** October 21, 2022  
**Project:** Struthers Ranch Polaris  
**Location:** Water Quality Pond A - Forebay B1

<p>6. Trickle Channel</p> <p>A) Type of Trickle Channel</p> <p>F) Slope of Trickle Channel</p>	<div style="border: 1px solid black; padding: 2px; margin-bottom: 5px;">             Choose One  <input checked="" type="radio"/> Concrete  <input type="radio"/> Soft Bottom         </div> <p>S = <input style="width: 50px;" type="text" value="0.0050"/> ft / ft</p>
<p>7. Micropool and Outlet Structure</p> <p>A) Depth of Micropool (2.5-foot minimum)</p> <p>B) Surface Area of Micropool (10 ft<sup>2</sup> minimum)</p> <p>C) Outlet Type</p> <p>D) Smallest Dimension of Orifice Opening Based on Hydrograph Routing (Use UD-Detention)</p> <p>E) Total Outlet Area</p>	<p>D<sub>M</sub> = <input style="width: 50px;" type="text" value="2.5"/> ft</p> <p>A<sub>M</sub> = <input style="width: 50px;" type="text" value=""/> sq ft</p> <div style="border: 1px solid black; padding: 2px; margin-bottom: 5px;">             Choose One  <input checked="" type="radio"/> Orifice Plate  <input type="radio"/> Other (Describe):         </div> <hr/> <hr/> <p>D<sub>orifice</sub> = <input style="width: 50px;" type="text" value="0.58"/> inches</p> <p>A<sub>orifice</sub> = <input style="width: 50px;" type="text" value="1.74"/> square inches</p>
<p>8. Initial Surcharge Volume</p> <p>A) Depth of Initial Surcharge Volume (Minimum recommended depth is 4 inches)</p> <p>B) Minimum Initial Surcharge Volume (Minimum volume of 0.3% of the WQCV)</p> <p>C) Initial Surcharge Provided Above Micropool</p>	<p>D<sub>IS</sub> = <input style="width: 50px;" type="text" value="6"/> in</p> <p>V<sub>IS</sub> = <input style="width: 50px;" type="text" value=""/> cu ft</p> <p>V<sub>s</sub> = <input style="width: 50px;" type="text" value=""/> cu ft</p>
<p>9. Trash Rack</p> <p>A) Water Quality Screen Open Area: <math>A_t = A_{ot} * 38.5 * (e^{-0.095D})</math></p> <p>B) Type of Screen (If specifying an alternative to the materials recommended in the USDCM, indicate "other" and enter the ratio of the total open area to the total screen area for the material specified.)</p> <p style="margin-left: 40px;">Other (Y/N): <input style="width: 50px;" type="text" value="N"/></p> <p>C) Ratio of Total Open Area to Total Area (only for type 'Other')</p> <p>D) Total Water Quality Screen Area (based on screen type)</p> <p>E) Depth of Design Volume (EURV or WQCV) (Based on design concept chosen under 1E)</p> <p>F) Height of Water Quality Screen (H<sub>TR</sub>)</p> <p>G) Width of Water Quality Screen Opening (W<sub>opening</sub>) (Minimum of 12 inches is recommended)</p>	<p>A<sub>t</sub> = <input style="width: 50px;" type="text" value="63"/> square inches</p> <div style="border: 1px solid black; padding: 2px; margin-bottom: 5px; text-align: center;"> <i>S.S. Well Screen with 60% Open Area</i> </div> <hr/> <hr/> <p>User Ratio = <input style="width: 50px;" type="text" value=""/></p> <p>A<sub>total</sub> = <input style="width: 50px;" type="text" value="106"/> sq. in.</p> <p>H = <input style="width: 50px;" type="text" value="3.47"/> feet</p> <p>H<sub>TR</sub> = <input style="width: 50px;" type="text" value="69.64"/> inches</p> <p>W<sub>opening</sub> = <input style="width: 50px;" type="text" value="12.0"/> inches <span style="color: red; font-size: small;">VALUE LESS THAN RECOMMENDED MIN. WIDTH. WIDTH HAS BEEN SET TO 12 INCHES.</span></p>

Design Procedure Form: Extended Detention Basin (EDB)

Sheet 3 of 3

Designer: JPS  
Company: JPS  
Date: October 21, 2022  
Project: Struthers Ranch Polaris  
Location: Water Quality Pond A - Forebay B1

<p>10. Overflow Embankment</p> <p>A) Describe embankment protection for 100-year and greater overtopping:</p> <p>B) Slope of Overflow Embankment (Horizontal distance per unit vertical, 4:1 or flatter preferred)</p>	<p><u>Buried Riprap Spillway</u></p> <p>Ze = <u>4.00</u> ft / ft</p>
<p>11. Vegetation</p>	<p>Choose One</p> <p><input type="radio"/> Irrigated</p> <p><input checked="" type="radio"/> Not Irrigated</p>
<p>12. Access</p> <p>A) Describe Sediment Removal Procedures</p>	<p><u>Periodic inspection and removal as needed; Access ramp provided to pond bottom</u></p> <p>_____</p> <p>_____</p> <p>_____</p>
<p>Notes: _____</p> <p>_____</p> <p>_____</p>	



**APPENDIX E**

**WATER QUALITY POND COST ESTIMATE**

**STRUTHERS RANCH POLARIS  
 LOTS 1-2, STRUTHERS RANCH SUBDIVISION FILING NO. 4  
 ENGINEER'S COST ESTIMATE  
 DRAINAGE IMPROVEMENTS - WATER QUALITY POND**

Item No.	Description	Quantity	Unit	Unit Cost (\$\$)	Total Cost (\$\$)
<b>PRIVATE DRAINAGE FACILITIES (NON-REIMBURSABLE)</b>					
203	Detention Basin Earthwork	630	CY	\$22	\$13,860
301	Retaining Walls	1320	SF	\$25	\$33,000
301	Concrete Forebays (10'x8')	6.0	CY	\$300	\$1,800
301	Concrete Trickle Channels	1	LS	\$1,200	\$1,200
604	Detention Basin Outlet Structure / Buried Riprap Spillway	1	LS	\$10,000	\$10,000
<b>SUBTOTAL</b>					<b>\$59,860</b>
Engineering @ 10%					\$5,986
<b>TOTAL (NON-REIMBURSABLE)</b>					<b>\$65,846</b>
Note: This estimate does not include costs for street improvements and general civil costs (curb & gutter, crossspans, etc.)					

The cost estimate submitted herein is based on time-honored practices within the construction industry. As such the engineer does not control the cost of labor, materials, equipment or a contractor's method of determining prices and competitive bidding practices or market conditions. The estimate represents our best judgement as design professionals using current information available at the time of the preparation. The engineer cannot guarantee that proposals, bids and/or construction costs will not vary from this cost estimate.


**APPENDIX F**

**FIGURES**

# National Flood Hazard Layer FIRMMette



104°50'49"W 39°2'50"N



Basemap: USGS National Map: Orthoimagery: Data refreshed October, 2020

104°50'12"W 39°2'22"N

## Legend

SEE FIS REPORT FOR DETAILED LEGEND AND INDEX MAP FOR FIRM PANEL LAYOUT

SPECIAL FLOOD HAZARD AREAS		Without Base Flood Elevation (BFE) Zone A, V, A99
		With BFE or Depth Zone AE, AO, AH, VE, AR
		Regulatory Floodway
OTHER AREAS OF FLOOD HAZARD		0.2% Annual Chance Flood Hazard, Areas of 1% annual chance flood with average depth less than one foot or with drainage areas of less than one square mile Zone X
		Future Conditions 1% Annual Chance Flood Hazard Zone X
		Area with Reduced Flood Risk due to Levee. See Notes. Zone X
		Area with Flood Risk due to Levee Zone D
OTHER AREAS		NO SCREEN Area of Minimal Flood Hazard Zone X
		Effective LOMRs
GENERAL STRUCTURES		Area of Undetermined Flood Hazard Zone D
		Channel, Culvert, or Storm Sewer
OTHER FEATURES		Levee, Dike, or Floodwall
		20.2 Cross Sections with 1% Annual Chance Water Surface Elevation
MAP PANELS		17.5 Coastal Transect
		Base Flood Elevation Line (BFE)
		Limit of Study
		Jurisdiction Boundary
		Coastal Transect Baseline
		Profile Baseline
		Hydrographic Feature
		Digital Data Available
		No Digital Data Available
		Unmapped



The pin displayed on the map is an approximate point selected by the user and does not represent an authoritative property location.


This map complies with FEMA's standards for the use of digital flood maps if it is not void as described below. The basemap shown complies with FEMA's basemap accuracy standards.

The flood hazard information is derived directly from the authoritative NFHL web services provided by FEMA. This map was exported on **8/10/2022 at 5:04 PM** and does not reflect changes or amendments subsequent to this date and time. The NFHL and effective information may change or become superseded by new data over time.

This map image is void if the one or more of the following map elements do not appear: basemap imagery, flood zone labels, legend, scale bar, map creation date, community identifiers, FIRM panel number, and FIRM effective date. Map images for unmapped and unmodernized areas cannot be used for regulatory purposes.

**LEGEND**

- FILING LIMITS
- MAJOR BASIN BOUNDARY
- MINOR BASIN BOUNDARY
- 6520 --- EXISTING CONTOUR
- FLOWLINE
- ← PROPOSED FLOW DIRECTION ARROW
- PROPOSED DROP STRUCTURE
- ▲ DESIGN POINT
- ▲ Qs (cfs)
- ▲ Q100(cfs)
- BASIN DESIGNATION
- BASIN AREA (ACRES)





19 E. Willamette Ave.  
Colorado Springs, CO  
80903  
PH: 719-477-9429  
FAX: 719-471-0766

**STRUTHERS RANCH SUBDIVISION**

**DEVELOPED DRAINAGE PLAN**

NO.	REVISION	BY	DATE
1	EPC COMMENTS	JPS	4/8/04
2	EPC COMMENTS	JPS	5/7/04
3	EPC COMMENTS	JPS	5/25/04
4	EPC COMMENTS	JPS	9/2/04
5	RE-SUBMITTAL TO EPC	JPS	9/30/04



- NOTES:
- DEVELOPMENT SHALL FOLLOW ALL REQUIREMENTS OF THE APPROVED HABITAT CONSERVATION PLAN (HCP) AND ASSOCIATED ENVIRONMENTAL PERMITS.
  - PERIMETER DRAINS SHALL BE REQUIRED FOR ALL HOMES WITH BASEMENTS.

HORIZ. SCALE: 1"=200'	DRAWN: MJP
VERT. SCALE: N/A	DESIGNED: JPS
SURVEYED: PINNACLE	CHECKED: JPS
CREATED: 9/11/00	LAST MODIFIED: 10/15/04
PROJECT NO: 080006	MODIFIED BY: MJP
SHEET:	


**D1**

J:\\_p\projects\080006\struthers.dwg Oct 15, 2004 -- 12:12pm

NO.	BY	DATE	REVISION
A			
B			
C			
D			

**DEVELOPED  
DRAINAGE PLAN**

**STRUTHERS RANCH POLARIS  
LOTS 1-2, STRUTHERS RANCH SUBDIVISION FILING NO. 4**



**LEGEND**

- FEMA 100-YEAR FLOODWAY
- FEMA 100-YR FLOODPLAIN
- PROPERTY LINE
- - - DRAINAGE BASIN BOUNDARY
- - - EASEMENT LINE
- 6762 PROPOSED CONTOUR
- 6762 EXISTING CONTOUR
- × 49.0 PROPOSED SPOT ELEVATION (FLOWLINE)
- × 74.5 EXIST. SPOT ELEVATION
- 10% PROPOSED SLOPE
- TW TOP OF RETAINING WALL
- BW BOTTOM OF RETAINING WALL
- FLOWLINE
- FLOW DIRECTION ARROW
- △ DESIGN POINT
- BASIN DESIGNATION
- BASIN AREA (ACRES)

**IMPERVIOUS AREA CALCULATIONS:**

BASIN A SITE AREA = 2.74 AC.

SURFACE TYPE	AREA
SIDEWALK	7,215 SF
BUILDING	12,000 SF
ASPHALT PARKING	62,983 SF
<b>TOTAL IMPERVIOUS AREA</b>	<b>82,198 SF = 1.9 AC</b>


**= 69%**

**SUMMARY HYDROLOGY TABLE**

DESIGN POINT	Q5 (CFS)	Q100 (CFS)
A	8.9	17.7
B1	5.9	12.2
1	11.9	24.2

**DETENTION POND  
CONTOUR AREAS**

CONTOUR	AREA (SF)
6752	1,437 SF
6754	2,201 SF
6756	3,180 SF



PROPOSED RETAINING WALL  
PROTECT EXISTING ELECTRIC TRANSFORMER

MATCH INTO EXISTING SIDEWALK

CATHEDRAL ROCK CHURCH  
590 HWY 105 STE 190  
PARCEL NO: 71963-01-013  
ZONE: PUD  
USE: RELIGIOUS WORSHIP

EXISTING CURB & GUTTER  
MATCH INTO EXISTING SW SIDEWALK  
KEVIN P DICKSON  
14688 ALLEGIANCE DR  
PARCEL NO: 71963-03-001  
ZONE: PUD  
USE: SINGLE FAMILY RES.

STRUTHERS RANCH ROAD  
(60'-0" R.O.W.)

NEW ATTACHED 6'W SIDEWALK

MATCH INTO EXISTING CURB & GUTTER

PROTECT EXISTING FIBEROPTIC LINES

GEORGE E RUSSELL  
14678 ALLEGIANCE DR  
PARCEL NO: 71963-03-002  
ZONE: PUD  
USE: SINGLE FAMILY RES.

LOT 1  
76,122 SF  
FF=6765.0

PROPOSED BUILDING  
12,000 SF  
FF=6765.0

TRASH ENCLOSURE  
(2) 20 X 8 ROLL OFF DUMPSTER'S

4' CROSSSPAN  
FOUND 1-1/2" ALUMINUM CAP  
JR PLS 31161  
9' BELOW GROUND

EXISTING RIDGE

MARCUS GRAZES  
14688 ALLEGIANCE DR  
PARCEL NO: 71963-03-003  
ZONE: PUD  
USE: SINGLE FAMILY RES.

EXISTING 5'W SIDEWALK

STRUTHERS RANCH HOMEOWNERS  
PARCEL NO: 71963-03-001  
ZONE: PUD  
USE: SINGLE FAMILY RES.

PROPOSED RETAINING WALL  
PROPOSED TYPE 16 INLET AT W/18' SD INTO FOREBAY  
PROPOSED FOREBAY A1

4"W CONCRETE TRICKLE CHANNEL  
PROPOSED WATER QUALITY POND A  
BOTTOM EL-6752.0  
SPILLWAY-6756.5  
MIN. WQCV-0.13 AF  
DSN VOL- 0.22 AF

PROPOSED OUTLET STRUCTURE  
PROPOSED 37 LF 18" HDPE @ 0.5% SLOPE,  
CONNECT TO EXISTING INLET BOX

14"W BURIED RIPRAP SPILLWAY EL-6756.5

EXISTING STORM INLET  
GR EL-6756.48  
EX 30" INV IN (S)-6751.88  
EX 54" INV IN (N)-6750.36  
EX 2-42" INV OUT (W)-6750.15  
PR 18" INV IN (E)-6750.81

EXISTING DOUBLE 48" RCP STORM SEWER FLOWING INTO REGIONAL DETENTION BASIN II  
(OVERFLOW FROM WATER QUALITY POND WILL FLOW INTO EXISTING GRATED INLET & STORM SEWER TO REGIONAL DETENTION POND)

EXISTING 30" RCP CULVERT TO BE PLUGGED + ABANDONED  
PROPOSED 18" FES INV- 6752.86

PROPOSED CURB & GUTTER

ASPHALT

PROTECT EXISTING FIBEROPTIC LINES

RYAN W RESER  
14688 ALLEGIANCE DR  
PARCEL NO: 71963-03-004  
ZONE: PUD  
USE: SINGLE FAMILY RES.

FOUND PINK PLASTIC CAP  
ALC INC PLS 13487  
FLUSH WITH GROUND

LOT 4  
27,934 SF

CLARK FAMILY TRUST  
14680 STRUTHERS RD  
PARCEL NO: 71963-03-013  
ZONE: PUD  
USE: VACANT

FUTURE COMMERCIAL DEVELOPMENT AREA

LOT 3  
25,398 SF

CLARK FAMILY TRUST  
14680 STRUTHERS RD  
PARCEL NO: 71963-03-012  
ZONE: PUD  
USE: VACANT

FOUND 1-1/2" ALUMINUM CAP  
JR PLS 31161  
FLUSH WITH GROUND

STRUTHERS RANCH ROAD  
(120'-0" R.O.W.)

HORIZ. SCALE: 1"=30'	DRAWN: PV
VERT. SCALE: N/A	DESIGNED: JPS
SURVEYED: COMPASS	CHECKED: JPS
CREATED: 05/27/20	LAST MODIFIED: 02/20/23
PROJECT NO: 032203	MODIFIED BY: PV