

Architectural  
Structural  
Geotechnical



Materials Testing  
Forensic  
Civil/Planning

Job No. 188423

July 19, 2022

Aaron Atwood  
515 Struthers Loop  
Colorado Springs, Colorado

Re: Response to CGS Comments  
515 Struthers Loop  
Pair-A-Dise Subdivision, Filing No. 1  
El Paso County, Colorado

Dear Mr. Atwood,

RMG – Rocky Mountain Group (RMG) prepared the *Soils and Geology Study* (RMG Job No. 188423, dated April 8, 2022) for the proposed subdivision generally located southeast of the intersection of Struthers Road and Baptist Road. The report was reviewed by personnel of the Colorado Geological Survey (CGS). The CGS comments (dated May 4, 2022) were provided to us by Aaron Atwood on May 10, 2022.

The purpose of this letter is to provide RMG's response to the CGS comments. For clarity and ease of review we have “snipped” the CGS comments below, each followed by our response to that comment.

**CGS Comment:**

Submitted documents for the proposed subdivision (located 39.0533, -104.8367) include a Soils report (Geoquest, dated July 28, 2021) and a more recent Soils and Geology Study (RMG, April 8, 2022). Geoquest drilled two test borings. They do not measure the depth to groundwater in their borings, but they note high moisture content at 5 and 6 feet. Geoquest discusses the need for additional drainage during construction “...due to the high moisture content.” RMG does not perform further subsurface investigation or examine the evidence provided by Geoquest of shallow groundwater.

**RMG Response:**

CGS references “a Soils report” by Geoquest, dated July 28, 2021. However, there are two such reports pertinent to this site, one for the proposed northern lot (Geoquest’s Job #21-0795) and one for the proposed southern lot (Geoquest’s Job #21-0794). Geoquest reports 2 test borings per report, for a total of 4 test borings at this site. Geoquest does not report the occurrence of groundwater within any of the 4 test borings. Contrary to CGS’ statement in the snip above,

Geoquest also does not report high moisture content at 5 and 6 feet. Rather, they report high moisture content within the zone of soil logged by Geoquest as extending from a depth of either 5 or 6 feet to a depth of 15 feet in each of the borings. Geoquest does not clarify at what depth within those 9- to 10-foot zones of material the high moisture content was encountered.

“High moisture content” is not the same as (nor is it necessarily an indication of) shallow groundwater. Moisture content is the amount of water that is within a soil sample. All soil samples have a moisture content. Within most samples, that moisture content (whether low, moderate, or high) is “bound” (or entrapped) water; water that cannot easily be extracted by squeezing the soil. Water that can be extracted in such a manner, or water that is not entrapped, is considered “free” water. It’s common for soils to have moderate to high moisture content where no groundwater exists. The identification of high moisture content by Geoquest is not “evidence” of shallow groundwater.

Furthermore, of the two referenced reports by Geoquest, only one of them indicates the potential need for additional drainage and/or ballast rock, despite reporting similarly high moisture contents within the soil samples tested near the bottoms of the borings. It is unclear why Geoquest recommends additional drainage and/or ballast rock in one report but not in the other. However, it appears to be Geoquest’s opinion (and we concur) that the high moisture contents encountered do not pose a hazard to the proposed structures. Rather, they are a condition which can be readily mitigated with construction techniques commonly utilized in this region.

In response to CGS’ comments dated May 4, 2022, RMG performed two additional test borings at the site to measure the depth of groundwater (if present). The test borings were drilled to 20 feet and visually logged. The results of our groundwater observations are included in Section 6.9 of our revised Soils and Geology Study.

**CGS Comment:**

CGS recommends that before the approval of the subdivision, the County requires the Soil and Geology Study to be expanded to include evaluation and discussion of the shallow groundwater indicated in the Geoquest report. Additional borings may be necessary to adequately evaluate the site conditions as both of Geoquest’s borings are in the south end of the property and were not used to measure groundwater depths. The expanded report should include recommendations on mitigation of shallow groundwater, any additional problems associated with groundwater level fluctuations as well as any additional geologic conditions that may impose constraints on construction. CGS looks forward to reviewing additional analysis and recommendations when available.

**RMG Response:**

Additional discussions on groundwater (permanent and/or seasonal) are included in Section 6.9 of our revised Soils and Geology Study.

**CGS Comment:**

Additionally, CGS recommends a plat note be added that no basements or inhabitable below-grade areas are allowed unless groundwater monitoring (through the annual seasonal fluctuations) before construction demonstrates that below-grade areas can maintain 3-5 feet between the bottom of the foundation and the groundwater, or site grading indicates that it will mitigate the depth to groundwater.

**RMG Response:**

Additional discussions on groundwater (permanent and/or seasonal) and any proposed mitigations are included in Section 6.9 of our revised Soils and Geology Study. Based on the results of our investigation, it is our opinion that techniques that are commonly utilized throughout this region are suitable to address the conditions encountered on this site, and that no further requirements or limitations should be imposed.

**CGS Comment:**

As RMG states p. 11 "...conclusions and recommendations presented in this report are not intended for design and construction." Once individual home sites have been chosen, site-specific soils and foundation investigations will be necessary. These should include drilling, testing, and analysis for determining basement feasibility and designing foundations, floor systems, subsurface drainage, pavements, etc. CGS recommends a plat note be added stating site-specific soils and foundation investigations are required for any structures.

**RMG Response:**

CGS is correct that the conclusions and recommendations presented in the RMG report are not intended for design and construction purposes. The RMG report does not provide specific design recommendations. Rather, the RMG report reviews the site for suitability and compatibility with the proposed usage (in this case, two single-family residences, one per subdivided lot).

The two referenced Soils Reports completed by Geoquest, included in Appendix C, provide the recommendations for design and construction of the proposed foundations. As noted in the Geoquest reports, "*Also evaluated during the investigation were subsurface conditions which affect the depth of the foundation and subsequent loading design, such as ground water levels, soil types, and other factors which affect the bearing capacity of the soils. Design loadings are based on soils characteristics and represent the maximum permissible loads for these conditions.*" Geoquest performed two separate subsurface investigations (one for each proposed lot, with two borings each and associated testing and analysis) at the site, for the purpose of determining basement feasibility and designing foundations, subsurface drainage, etc. at the site. The investigations already performed by Geoquest meet the recommendations noted by CGS above, and thus no plat note is required.

**CGS Comment:**

Plat note 10 references the Geoquest report (July 28, 2021). CGS recommends that Plat Note 10 be updated to reference the date of RMG's updated report.

**RMG Response:**

RMG has requested Mr. Atwood have Plat note 10 updated to reference our amended report, dated July 19, 2022.

I hope this provides the information you have requested. Should you have questions, please feel free to contact our office.

Cordially,

RMG – Rocky Mountain Group



Kelli Zigler  
Project Geologist



Tony Munger, P.E.  
Geotechnical Project Manager

Architectural  
Structural  
Geotechnical



Materials Testing  
Forensic  
Civil/Planning

## SOILS AND GEOLOGY STUDY

**515 Struthers Loop  
Pair-A-Dise Subdivision Filing No. 1  
El Paso County, Colorado**

### PREPARED FOR:

**Aaron Atwood  
515 Struthers Loop  
Colorado Springs, CO 80921**

**JOB NO. 188423**

**April 8, 2022  
Amended July 19, 2022**

Respectfully Submitted,

RMG – Rocky Mountain Group

**Kelli Zigler  
Project Geologist**

Reviewed by,

RMG – Rocky Mountain Group

**Tony Munger, P.E.  
Geotechnical Project Manager**



---

## TABLE OF CONTENTS

---

1.0 GENERAL SITE AND PROJECT DESCRIPTION.....	4
1.1 Project Location .....	4
1.2 Existing and Proposed Land Use.....	4
1.3 Project Description .....	4
1.4 Previous Investigations.....	4
2.0 QUALIFICATIONS OF PREPARERS .....	5
3.0 STUDY OVERVIEW .....	5
3.1 Scope and Objective .....	5
3.2 Site Evaluation Techniques .....	6
3.3 Additional Documents.....	6
4.0 SITE CONDITIONS .....	6
4.1 Existing Site Conditions .....	6
4.2 Topography .....	7
4.3 Vegetation .....	7
4.4 Aerial Photographs and Remote-Sensing Imagery.....	7
5.0 FIELD INVESTIGATION AND LABORATORY TESTING .....	7
5.1 Drilling .....	7
5.2 Profile Pit Excavations .....	7
5.3 RMG Drilling .....	8
6.0 SOIL, GEOLOGY, AND ENGINEERING GEOLOGY .....	8
6.1 Subsurface Soil Conditions .....	8
6.2 Bedrock Conditions.....	8
6.3 U.S. Soil Conservation Service .....	8
6.4 General Geologic Conditions .....	9
6.5 Engineering Geology.....	9
6.6 Structural Features.....	9
6.7 Surficial (Unconsolidated) Deposits.....	9
6.8 Features of Special Significance .....	10
6.9 er and Groundwater .....	10
6.10 Flooding and Surface Drainage.....	11
7.0 ECONOMIC MINERAL RESOURCES.....	11
8.0 IDENTIFICATION AND MITIGATION OF POTENTIAL GEOLOGIC CONDITIONS .....	12
8.1 Compressible Soils .....	13
8.2 Expansive Soils .....	13
8.3 Faults and Seismicity.....	13
8.4 Radon.....	14
9.0 BEARING OF GEOLOGIC CONDITIONS UPON PROPOSED DEVELOPMENT .....	14
10.0 ADDITIONAL STUDIES .....	15
11.0 CONCLUSIONS .....	15
12.0 CLOSING.....	16

### FIGURES

Site Vicinity Map.....	1
Proposed Lot Layout Map .....	2
USGS Topo Map .....	3
USDA Soil Survey Map .....	4
Engineering Geology Map .....	5
FEMA Map .....	6
Perimeter Drain Detail .....	7
Underslab Drain Detail .....	8

Appendix A – Additional Reference Documents

Appendix B – Site Reconnaissance Photos

Appendix C – Site Investigation Reports Prepared by Geoquest, LLC.

# 1.0 GENERAL SITE AND PROJECT DESCRIPTION

---

## 1.1 Project Location

The project lies in the NW  $\frac{1}{4}$  of the NE  $\frac{1}{4}$  of Section 36, Township 11 South, Range 67 West of the 6<sup>th</sup> Principal Meridian in El Paso County, Colorado, and is generally located southeast of the intersection of Struthers Road and Baptist Road. The approximate location of the site is shown on the Site Vicinity Map, Figure 1.

## 1.2 Existing and Proposed Land Use

The site currently consists of one parcel (per the El Paso County Assessor's website) of approximately 5 acres:

- Schedule No. 7136002005, current land use is classified as a vacant residential lot

The current zoning is "RR-2.5" – *Residential Rural*. The parcel is currently undeveloped, vacant land. The future zoning designation is to remain "RR-2.5".

## 1.3 Project Description

It is our understanding that the property is to be subdivided into two lots of approximately 2.504 and 2.502 acres, respectively. Each new lot is to be developed with a new single-family residence, well, and on-site wastewater treatment system (OWTS). Lot 2 is to be accessed from Struthers Loop from an individual driveway and lot 1 is to be accessed from an access easement along the east side of lot 2. The Proposed Lot Layout Plan is presented in Figure 2.

## 1.4 Previous Investigations

Reports of previous geotechnical engineering/geologic investigations for this site were available for our review and are listed below:

1. *Soils Report for Aaron Atwood, Lot #38, (proposed Lot 1) Chaparral Hills Subdivision, 515 Struthers Loop, El Paso County, Colorado*, prepared by Geoquest, LLC, LLC, Job No. 21-0794, last dated July 28, 2021.
2. *Soils Report for Aaron Atwood, Lot #38, (proposed Lot 2) Chaparral Hills Subdivision, 515 Struthers Loop, El Paso County, Colorado*, prepared by Geoquest, LLC, LLC, Job No. 21-0795, last dated July 28, 2021.
3. *Profile Pit Evaluation for Aaron Atwood, Lot #38 (proposed Lot 1), Chaparral Hills Subdivision, 515 Struthers Loop, El Paso County, Colorado*, prepared by Geoquest, LLC, LLC, Job No. 21-0795, last dated July 16, 2021.
4. *Profile Pit Evaluation for Aaron Atwood, Lot #38, (proposed Lot 2) Chaparral Hills Subdivision, 515 Struthers Loop, El Paso County, Colorado*, prepared by Geoquest, LLC, LLC, Job No. 21-0794, last dated July 13, 2021.

## 2.0 QUALIFICATIONS OF PREPARERS

---

This Soils and Geology Study was prepared by a professional geologist as defined by Colorado Revised Statutes section 34-1-201(3) and by a qualified geotechnical engineer as defined by policy statement 15, "Engineering in Designated Natural Hazards Areas" of the Colorado State Board of Registration for Professional Engineers and Professional Land Surveyors. (Ord. 96-74; Ord. 01-42)

The principle investigators for this study are Kelli Zigler P.G., and Tony Munger, P.E. Ms. Zigler is a Professional Geologist as defined by State Statute (C.R.S 34-1-201) with over 21 years of experience in the geological and geotechnical engineering field. Ms. Kelli Zigler holds a B.S. in Geology from the University of Tulsa. Ms. Zigler has supervised and performed numerous geological and geotechnical field investigations throughout Colorado.

Tony Munger, P.E. is a licensed professional engineer with over 21 years of experience in the construction engineering (residential) field. Mr. Munger holds a B.S. in Architectural Engineering from the University of Wyoming

## 3.0 STUDY OVERVIEW

---

The purpose of this investigation is to characterize the general geotechnical, geologic site conditions, and on-site wastewater treatment system (OWTS) feasibility and present our opinions of the potential effect of these conditions on the proposed development within El Paso County, Colorado. As such, our services exclude evaluation of the environmental and/or human, health related work products or recommendations previously prepared, by others, for this project.

Revisions to the conclusions presented in this report may be issued based upon submission of the Development Plan. This study has been prepared in accordance with the requirements outlined in the El Paso County Land Development Code (LDC) specifically Chapter 8, last updated August 27, 2019. Applicable sections include 8.4.8 and 8.4.9, and the El Paso County Engineering Criteria Manual (ECM), specifically Appendix C last updated July 9, 2019.

### 3.1 Scope and Objective

The scope of this study is to include a physical reconnaissance of the site and a review of pertinent, publically available documents including, but not limited to, previous geologic and geotechnical reports, overhead and remote sensing imagery, published geology and/or hazard maps, design documents, etc.

The objectives of our study are to:

- Identify geologic conditions present on the site
- Analyze potential negative impacts of these conditions on the proposed site development
- Analyze potential negative impacts to surrounding properties and/or public services resulting from the proposed site development as it relates to existing geologic conditions
- Provide our opinion of suitable techniques that may be utilized to mitigate any potential negative impacts identified herein

This report presents the findings of the study performed by RMG-Rocky Mountain Group relating to the geologic conditions of the above-referenced site. Revisions and modifications to this report may be issued subsequently by RMG, based upon:

- Additional observations made during grading and construction which may indicate conditions that require re-evaluation of some of the criteria presented in this report
- Review of pertinent documents (development plans, plat maps, drainage reports/plans, etc.) not available at the time of this study
- Comments received from the governing jurisdiction and/or their consultants subsequent to submission of this document

### **3.2 Site Evaluation Techniques**

The information included in this report has been compiled from several sources, including:

- Field reconnaissance
- Geologic and topographic maps
- Review of selected publicly available, pertinent engineering reports
- Available aerial photographs
- Subsurface exploration
- Visual and tactile characterization of representative site soil and rock samples
- Geologic research and analysis
- Replat, Pair-A-Dise Subdivision, Filing No. 1, Project No. 61155, dated October 12, 2021, provided by MVE, Inc. Engineers and Surveyors

Geophysical investigations were not considered necessary for characterization of the site geology. Monitoring programs, which typically include instrumentation and/or observations for changes in groundwater, surface water flows, slope stability, subsidence, and similar conditions, are not known to exist and were not considered applicable for the scope of this report.

### **3.3 Additional Documents**

Additional documents reviewed during the performance of this study are included in Appendix A.

## **4.0 SITE CONDITIONS**

---

### **4.1 Existing Site Conditions**

The site is undeveloped. The site is generally located southeast of the intersection of Struthers Road and Baptist Road in El Paso County, Colorado and comprises approximately 5 acres. The site is currently zoned RR-2.5, residential rural and is to remain RR-2.5, in the future. Adjacent properties to the north, south, east, and west are zoned RR-2.5.

## 4.2 Topography

Based on our site reconnaissance on March 2, 2022 and USGS 2019 topographic map of the Monument Quadrangle, the site generally slopes down to the west with an overall elevation change of approximately 18 feet. A drainage channel runs through the site in the northwest corner, as shown in Figure 5, Engineering Geology Map. The water level in the drainage channel is anticipated to vary, depending upon local precipitation events.

## 4.3 Vegetation

The site vegetation primarily consists of native grasses, weeds, and other prairie-type vegetation. A dense stand of deciduous trees is located along the drainage channel in the northern portion of the site.

## 4.4 Aerial Photographs and Remote-Sensing Imagery

Personnel of RMG reviewed aerial photos available through Google Earth Pro dating back to 1999, Colorado Geological Survey (CGS) surficial geologic mapping, and historical photos by [historicaerials.com](http://historicaerials.com) dating back to 1947. Historically, the site has remained vacant, undeveloped land.

# 5.0 FIELD INVESTIGATION AND LABORATORY TESTING

---

The subsurface conditions below each lot were reportedly investigated by Geoquest, LLC (Geoquest) on July 5, 2021 as part of the two lot-specific *Soils Reports* and two lot-specific *Profile Pit Evaluation* reports referenced above and included in Appendix C. Geoquest indicates the performance of two test borings and two test pits on each new lot for the proposed single-family residences. According to Mr. Atwood, the test borings were performed within the locations of the proposed residences and the two test pits were performed near the desired OWTS locations.

Additionally, after the first round of CGS review comments were received via electronic mail from Mr. Atwood, RMG performed one additional test boring on each new lot located approximately between the two Geoquest test borings for the purpose of determining the relative depths to groundwater. The test borings were completed on June 2, 2022. Bulk samples were obtained at 5-foot intervals from both test borings. The samples were returned to the laboratory to obtain the moisture content from each sample. Additional lab testing was not considered necessary.

## 5.1 Geoquest Drilling

Two test borings were reportedly performed by Geoquest on each new lot to explore the subsurface soil conditions and provide recommendations for design and construction of the proposed foundations. The test borings were extended to depths of approximately 15 feet below the existing ground surface. The results of their investigations are presented in the referenced reports, attached and included in Appendix C. The approximate locations of the Geoquest test borings are presented on the Engineering Geology Map, Figure 5.

## 5.2 Geoquest Profile Pit Excavations

Two profile pits were performed by Geoquest on each new lot to explore the subsurface soils underlying the proposed on-site wastewater treatment systems. The number of test pits is in accordance with

Regulations of the El Paso County Board of Health, Chapter 8, On-site Wastewater Treatment Systems (OWTS) as required by 8.5.D.3.a.

The profile pits were located by Geoquest's client, Mr, Atwood. According to Geoquest's *Profile Pit Evaluation* reports (referenced above), all four profile pits were excavated to approximately 8 feet below the ground surface. The results of their investigations are presented in the referenced reports, attached and included in Appendix C. The approximate locations of the Geoquest profile pits are presented on the Engineering Geology Map, Figure 5.

### **5.3 RMG Drilling**

RMG performed two additional test borings to verify the depth of groundwater. The test borings were drilled to 20 feet and visually logged. The results of our investigation are presented in section 6.9.

## **6.0 SOIL, GEOLOGY, AND ENGINEERING GEOLOGY**

---

The site is located within the central portion of the Great Plains Physiographic Province. A major structural feature known as the Rampart Range Fault is located approximately 4 miles west of the site. The Rampart Range Fault marks the boundary between the Great Plains Physiographic Province and the Southern Rocky Mountain Province. The site exists within the southern portion of a large structural feature known as the Denver Basin. In general, the geology at the site consists of Louviers and Slocum alluvium composed of sand, silt, clay, and gravel with loamy colluvium that overlies the Dawson Formation.

### **6.1 Subsurface Soil Conditions**

Based on the Geoquest soils reports referenced above, the on-site soil on proposed lot 2 is anticipated to be silty sand with underlying clayey sand and the on-site soil on proposed lot 1 is anticipated to be silty sand with underlying low-plasticity clay.

### **6.2 Bedrock Conditions**

Bedrock (as defined by USDA) was not encountered in the profile pit excavations performed by Geoquest, LLC, LLC, LLC for the property. In general, the bedrock beneath the site is considered to be part of the Dawson formation. The Dawson formation is thick-bedded to massive, generally light colored arkose. The sandstones are poorly sorted with variable clay contents. The sandstone is generally permeable, well drained, and has good foundation support characteristics. The Dawson sandstone is generally not considered a limiting layer for OWTS.

### **6.3 U.S. Soil Conservation Service**

The USDA/NRCS soil survey identifies the site soils as:

- 68 – Peyton-Pring complex, 3 to 8 percent slopes. Properties of the complex include well drained soils, depth of the water table is anticipated to be greater than 80 inches, runoff is anticipated to be low, frequency of flooding and ponding is none, and landforms include hills.
- 93 – Tomah-Crowfoot complex, 8 to 15 percent slopes. Properties of the complex include well drained soils, depth of the water table is anticipated to be greater than 80 inches, runoff is anticipated

to be medium, frequency of flooding and ponding is none, and landforms include alluvial fans and hills.

The USDA Soil Survey Map is presented in Figure 4.

#### **6.4 General Geologic Conditions**

Based on our field observations and review of relevant geologic maps, we identified the geologic conditions (listed below) affecting the development, as shown on the Engineering Geology Map, Figure 5.

The site generally consists of alluvium and colluvium deposits of the Quaternary overlying the Dawson Arkose Formation of Tertiary age. Four geologic units were mapped at the site as:

- *ags* – Alluvial sand, silt, clay and gravel (Louviers and Slocum Alluviums, undivided; late middle Pleistocene)
- *cac* – Arkosic loamy colluvium and sheetwash alluvium (Holocene)
- *Tkda3* – Dawson Formation Facies Unit Three (Paleocene) – Unit consists of sub-equal amounts of thick and very thick-bedded, massive and cross-bedded, white, tan, and light-gray arkose and pebbly arkose; thin to thick beds of light-green to olive-gray clay-rich, fine- to medium-grained micaceous and feldspathic sandstone; and thin to thick beds of dark-gray to greenish-gray sandy claystone. Very thick-bedded, massive or cross-bedded, light-colored arkose beds in facies unit three resemble those in facies unit one but are finer grained and generally thinner. Facies unit three may have occasional thin, poorly developed, paleosols; reported coaly strata are not exposed at the surface. Unit is 500 to 600 feet thick in the area and thins towards the northwest as it interfingers with facies unit one and facies unit four.
- *SW* – Seasonally Wet Area

#### **6.5 Engineering Geology**

Two engineering geology units were mapped at the site as:

- *p Qs* – Slocum Alluvium
- *IA* – Stable alluvium, colluvium and bedrock on flat to gentle slopes (0-5%)

The map unit descriptions for these units are provided by Charles Robinson and Associates (1977).

#### **6.6 Structural Features**

Structural features such as schistosity, folds, zones of contortion or crushing, joints, shear zones or faults were not observed by RMG on the site or in the surrounding area.

#### **6.7 Surficial (Unconsolidated) Deposits**

Lake and pond sediments, swamp accumulations, sand dunes, marine terrace deposits, talus accumulations, creep, or slope wash were not observed on the site. Slump and slide debris were also not observed on the site.

## 6.8 Features of Special Significance

Features of special significance such as accelerated erosion, (advancing gully head, badlands, or cliff reentrants) were not observed on the property. Features indicating settlement or subsidence such as fissures, scarplets, and offset reference features were not observed on the study site or surrounding areas.

Features indicating creep, slump, or slide masses in bedrock and surficial deposits were not observed on the property.

## 6.9 Groundwater

The overall topography of the site slopes down to the northwest and west. It is anticipated the direction of surface water and groundwater is to flow in the same direction. Groundwater was not reported in the four test borings and four profile pits performed for the *Soils Reports* and *Profile Pit Evaluation* reports by Geoquest, LLC, referenced above. Groundwater was not encountered at the time of drilling in the two test borings performed by RMG, approximately 11 months after the original Geoquest test borings.

RMG performed three separate follow-up groundwater check observations to measure the groundwater levels within the two borings over a 5-week period. During the RMG follow-up groundwater checks, we also observed the Geoquest test borings and profile pits for groundwater. All four Geoquest test borings had caved to depths of approximately 10 to 11 feet and groundwater was not observed at any of the three follow-up site visits. Groundwater was also not observed in the four Geoquest profile pits during the three follow-up site visits. Below is a table summarizing our groundwater monitoring within the two RMG test borings at each of the three follow-up site visits:

<b>Lot #, TB (Relative Direction)</b>	<b>5-Day Groundwater (GW) Check 6/7/2022</b>
Lot 1, TB-1 (North)	GW @ 13.0 feet below ground surface
Lot 2, TB-2 (South)	No GW found - dry
<b>Lot #, TB (Relative Direction)</b>	<b>8-Day Groundwater Check 6/10/2022</b>
Lot 1, TB-1 (North)	GW @ 12.0 feet below ground surface
Lot 2, TB-2 (South)	No GW found - dry
<b>Lot #, TB (Relative Direction)</b>	<b>5-week Groundwater Check 7/7/2022</b>
Lot 1, TB-1 (North)	GW at 13.5 feet below ground surface: Total depth of boring 20'5"
Lot 2, TB-2 (South)	No GW – dry: Total depth of boring 20'2"

It should be noted that in granular soils and bedrock, some subsurface water conditions might be encountered due to the variability of the soil profile. Isolated sand and gravel layers within the soil, even those of limited

thickness and width, can convey subsurface water. Subsurface water may also flow atop the interface between the upper soils and the underlying bedrock. While not indicative of a "groundwater" condition, these occurrences of subsurface water migration can (especially in times of heavy rainfall or snowmelt) result in water migration into the excavation or (once construction is complete) the building envelope. Builders and planners should be cognizant of the potential for the occurrence of subsurface water conditions during on-site construction, and be prepared to evaluate and mitigate each individual occurrence as necessary.

The proposed foundations should penetrate sufficient depth to discourage the formation of frost/ice lenses beneath foundations. It is recommended that foundations extend to a depth of at least 2.5 feet below the finished grade for frost protection. A subsurface drain will be necessary to help prevent the intrusion of water into areas located below grade. A typical perimeter drain detail is presented in Figure 7. Additionally, an underslab drainage layer may also be recommended to help intercept groundwater before it enters the slab area should the groundwater levels rise. In general, if groundwater was encountered within 4 to 6 feet of the proposed basement slab elevation, an underslab drain should be anticipated. Careful attention should be paid to grade and discharge of the drain pipe. A typical underslab drain detail is presented in Figure 8.

If groundwater conditions are encountered at the time of foundation excavation result in either water flow into the excavation or destabilization of the foundation bearing soils, stabilization techniques should be implemented. Various stabilization methods can be employed and can be discussed at the time of construction. However, one potential method (consisting of the use of 1 to 2 feet of "ballast" rock) was proposed in the referenced Geoquest reports. Additional drainage measures (beyond those indicated herein) may also be required. Final recommendations for mitigation are to be determined based on the conditions encountered at the time of the excavation observation.

It must be understood that the recommended drainage systems are designed to intercept some types of subsurface moisture and not others. Therefore, the drains could operate properly and not mitigate all moisture problems relating to foundation performance or moisture intrusion into the basement area.

## **6.10 Flooding and Surface Drainage**

A natural drainage channel runs through the site in the northwest corner. The drainage channel was dry at the time of the site recon performed by RMG. The USGS Topo Map is presented in Figure 3.

Based on our review of the Federal Emergency Management Agency (FEMA) Community Panel No. 08041C0287G and the online ArcGIS El Paso County Risk Map, the site lies outside of a 100-year floodplain. The site is within the boundaries of Zone X. The FEMA Map is presented in Figure 6.

Zone X is defined by FEMA as an area of minimal flood hazard that is determined to be outside the Special Flood Hazard Area and higher than the elevation of the 0.2-percent-annual-chance (or 500-year) flood.

## **7.0 ECONOMIC MINERAL RESOURCES**

---

Under the provision of House Bill 1529, it was made a policy by the State of Colorado to preserve for extraction commercial mineral resources located in a populous county. Review of the *El Paso Aggregate Resource Evaluation Map, Master Plan for Mineral Extraction, Map 1* indicates the site is identified as Upland Deposits. The deposits are composed of sand, gravel with silt and clay. These deposits are remnants

of older streams deposited on topographic highs or bench like features. The tract is underlain primarily by the Dawson Arkose, a sedimentary formation of Tertiary age related to uplift and erosion of the Front Range.

According to the *Evaluation of Mineral and Mineral Fuel Potential of El Paso County State Mineral Lands*, the site is mapped within the Denver Basin Coal Region, the tract identifier is 41-02. However, the area of the site has been mapped "Poor" for coal resources. In this part of the Denver coal region, coal resources are locally present within the lower part of the Laramie Formation of Upper Cretaceous age. The area contains strata that may contain coal. This area is not prospective for metallic mineral resources. No oil and gas wells are drilled in the area, or within two miles of it. Alluvial deposits are commonly mined in the region for sand and gravel. There are no active or inactive gravel pits in the area, but there are several within a three mile radius of it. Alluvial deposits containing gravel and/or sand cover approximately 112 acres of tract 41-02. Assuming a mineable thickness of 15 feet, this represents 4.1 million tons of potentially useable resource. The quality of the resource has not been determined. In the vicinity of this area, the coal-bearing beds of the Laramie Formation lie at a depth of approximately 1,500 feet (Kirkham and Ladwig, 1979). It is possible that the tract contains coal resources at this depth. The coal seams in the Laramie Formation tend to be lenticular and discontinuous in comparison to areas currently being mined in western Colorado.

## 8.0 IDENTIFICATION AND MITIGATION OF POTENTIAL GEOLOGIC CONDITIONS

---

The El Paso County Engineering Criteria Manual recognizes and delineates the difference between geologic hazards and constraints. A *geologic hazard* is one of several types of adverse geologic conditions capable of causing significant damage or loss of property and life. Geologic hazards are defined in Section C.2.2 Sub-section E.1 of the ECM. A *geologic constraint* is one of several types of adverse geologic conditions capable of limiting or restricting construction on a particular site. Geologic constraints are defined in Section C.2.2 Sub-section E.2 of the ECM (1.15 Definitions of Specific Terms and Phrases). The following geologic constraints were considered in the preparation of this report. They are not anticipated to pose a significant risk to the proposed development:

- Avalanches
- Debris Flow-Fans/Mudslides
- Ground Subsidence and Abandoned Mining Activity
- Landslides
- Rockfall
- Flood Prone Area
- Groundwater Springs or Seeps
- Shallow Groundwater Tables
- Ponding water
- Steeply Dipping Bedrock
- Unstable or Potentially Unstable Slopes
- Scour, Erosion, Accelerated Erosion Along Creek Banks and Drainageways
- History of Landfill or Uncontrolled/Undocumented Fill Placement
- Valley Fill
- Downhill/Down-slope Creep
- Soil Slumps and Undercutting
- Corrosive Minerals

The following sections present the geologic conditions that have been identified on the property:

### **8.1 Compressible Soils**

Based on the Geoquest, LLC for the *Soils Reports* referenced above and our experience with similar materials in this area, the on-site soils generally possess low compressibility potential. If compressible materials are encountered in the excavations for the proposed residences, they can readily be mitigated with typical construction practices common to this region of El Paso County, Colorado.

It is unknown at this time whether the proposed single-family residences will have crawlspaces, basements, or a combination of both. Foundation design and construction are typically adjusted for collapsible soils.

#### Mitigation

Mitigation of compressible soils may include overexcavation and replacement with non-expansive structural fill. Drilled piers are not anticipated. Floor slabs bearing directly on compressible soils are expected to experience movement. Overexcavation and replacement with compacted non-expansive soils can be successful in reducing this slab movement.

The lot-specific subsurface soil investigation performed for each proposed structure should consider mitigation of compressible soils.

### **8.2 Expansive Soils**

Based on the Geoquest, LLC *Soils Reports* referenced above and our experience with similar materials in this area, the on-site soils generally possess low to moderate swell potential. The Dawson formation is known to have moderate to high swell potential in some locations. It is anticipated that expansive soils/bedrock may be encountered at depths that may affect residential foundations. If these materials are encountered in the excavations for the proposed residences, they can readily be mitigated with typical construction practices common to this region of El Paso County, Colorado.

#### Mitigation

Foundation design and construction are typically adjusted for expansive soils. Mitigation of expansive soils may include overexcavation and replacement with non-expansive structural fill. Drilled piers are not anticipated. Floor slabs bearing directly on expansive soils are expected to experience movement. Overexcavation and replacement with compacted non-expansive soils can be successful in reducing slab movement.

If expansive soils or bedrock are encountered during construction, mitigation of these expansive materials should follow the recommendations presented in a lot-specific subsurface soil investigation performed for each proposed structure.

### **8.3 Faults and Seismicity**

Based on review of the Earthquake and Late Cenozoic Fault and Fold Map Server provided by CGS located at <http://dnrwebmapgdev.state.co.us/CGSOnline/> and the recorded information dating back to November of 1900, Colorado Springs has not experienced a recorded earthquake with a magnitude greater than 1.6 during that period. The nearest recorded earthquakes over 1.6 occurred in December of 1995 in Manitou Springs, which experienced magnitudes ranging between 2.8 to 3.5. Additional earthquakes over 1.6 occurred between 1926 and 2001 in Woodland Park, which experienced magnitudes ranging from 2.7 to 3.3. Both

of these locations are located near the Ute Pass Fault, which is greater than 10 miles from the subject site. Earthquakes felt at this site will most likely result from minor shifting of the granite mass within the Pikes Peak Batholith, which includes pull from minor movements along faults found in the Denver basin. It is our opinion that ground motions resulting from minor earthquakes may affect structures (and the surrounding area) at this site if minor shifting were to occur.

#### Mitigation

The Pikes Peak Regional Building Code, 2017 Edition, indicates maximum considered earthquake spectral response accelerations of 0.213g for a short period ( $S_s$ ) and 0.059g for a 1-second period ( $S_1$ ). Based on the results of our experience with similar subsurface conditions, we recommend the site be classified as Site Class B, with average shear wave velocities ranging from 2,500 to 5,000 feet per second for the materials in the upper 100 feet.

### **8.4 Radon**

*"Radon Act 51 passed by Congress set the natural outdoor level of radon gas (0.4 pCi/L) as the target radon level for indoor radon levels".*

Northern El Paso County and the 80921 zip code in which the site is located, has an EPA assigned Radon Zone of 1. A radon Zone of 1 predicts an average indoor radon screening level greater than 0.4 pCi/L (picocuries per liter), which is above the recommended levels assigned by the EPA. *The EPA recommends [corrective measures](#) to reduce exposure to radon gas.*

All of the State of Colorado is considered EPA Zone 1 based on the information provided at [https://county-radon.info/CO/El\\_Paso.html](https://county-radon.info/CO/El_Paso.html). Elevated hazardous levels of radon from naturally occurring sources are not anticipated at this site.

#### Mitigation

Radon hazards are best mitigated at the building design and construction phases. Providing increased ventilation of basements, crawlspaces, creating slightly positive pressures within structures, and sealing of joints and cracks in the foundations and below-grade walls can help mitigate radon hazards. Passive radon mitigation systems are also available.

Passive and active mitigation procedures are commonly employed in this region to effectively reduce the buildup of radon gas. Measures that can be taken after the residence is enclosed during construction include installing a blower connected to the foundation drain and sealing the joints and cracks in concrete floors and foundation walls. If the occurrence of radon is a concern, it is recommended that the residence be tested after they are enclosed and commonly utilized techniques are in place to minimize the risk.

## **9.0 BEARING OF GEOLOGIC CONDITIONS UPON PROPOSED DEVELOPMENT**

---

Geologic hazards (as described in section 8 of this report) found to be present at this site include faults and seismicity and radon. Geologic conditions (as described in section 8 of this report) found to be present at this site include compressible soils and expansive soils. It is our opinion that the existing geologic and engineering conditions can be satisfactorily mitigated through proper engineering, design, and construction practices.

## 10.0 ADDITIONAL STUDIES

---

The findings, conclusions, and recommendations presented in this report were provided to evaluate the suitability of the site for future development. Unless indicated otherwise, the test borings, laboratory test results, conclusions and recommendations presented in this report are not intended for use for design and construction. Site-specific subsurface soil investigations have been completed by Geoquest, LLC, LLC, and are included in Appendix C. Additional studies are not anticipated.

## 11.0 CONCLUSIONS

---

Based upon our evaluation of the geologic conditions, it is our opinion that the proposed development is feasible. The geologic conditions identified are considered typical for the Front Range region of Colorado. Mitigation of geologic conditions is most effectively accomplished by avoidance. However, where avoidance is not a practical or acceptable alternative, geologic conditions should be mitigated by implementing appropriate planning, engineering, and suitable construction practices.

In addition to the previously identified mitigation alternatives, surface and subsurface drainage systems should be considered. Exterior, perimeter foundation drains should be installed around below-grade habitable or storage spaces. A typical perimeter drain detail is presented in Figure 7 and an underslab drain is presented in Figure 8. Surface water should be efficiently removed from the building area to prevent ponding and infiltration into the subsurface soil.

We believe the sandy clay loam will classify as Type A material and the sandy loam will classify as Type B material as defined by OSHA in 29 CFR Part 1926. OSHA requires that temporary excavations made in Type A and B materials be laid back at ratios no steeper than 3/4:1 (horizontal to vertical) and 1:1 (horizontal to vertical), respectively, unless the excavation is shored and braced. Excavations deeper than 20 feet, or when water is present, should always be braced or the slope designed by a professional engineer.

Long term cut slopes in the upper soil should be limited to no steeper than 3:1 (horizontal to vertical). Flatter slopes will likely be necessary should groundwater conditions occur. It is recommended that long term fill slopes be no steeper than 3:1 (horizontal to vertical).

Revisions and modifications to the conclusions and recommendations presented in this report may be issued subsequently by RMG based upon additional observations made during grading and construction, which may indicate conditions that require re-evaluation of some of the criteria presented in this report.

It is important for the Owner(s) of the property to read and understand this report, and to carefully familiarize themselves with the geologic hazards associated with construction in this area. This report only addresses the geologic constraints contained within the boundaries of the site referenced above.

The foundation systems for the proposed single-family residential structures and any retention/detention facilities should be designed and constructed based upon the recommendations developed in the site-specific subsurface soil investigation prepared by Geoquest, LLC included as Appendix C.

## 12.0 CLOSING


---

This report is for the exclusive purpose of providing geologic hazards information and preliminary geotechnical engineering recommendations. The scope of services did not include, either specifically or by implication, evaluation of wild fire hazards, environmental assessment of the site, or identification of contaminated or hazardous materials or conditions. Development of recommendations for the mitigation of environmentally related conditions, including but not limited to, biological or toxicological issues, are beyond the scope of this report. If the owner is concerned about the potential for such contamination or conditions, other studies should be undertaken.

This report has been prepared for **Aaron Atwood** in accordance with generally accepted geotechnical engineering and engineering geology practices. The conclusions and recommendations in this report are based in part upon data obtained from review of available topographic and geologic maps, review of available reports of previous studies conducted in the site vicinity, a site reconnaissance, and research of available published information, soil test borings, soil laboratory testing, and engineering analyses. The nature and extent of variations may not become evident until construction activities begin. If variations then become evident, RMG should be retained to re-evaluate the recommendations of this report, if necessary.

Our professional services were performed using that degree of care and skill ordinarily exercised, under similar circumstances, by geotechnical engineers and engineering geologists practicing in this or similar localities. RMG does not warrant the work of regulatory agencies or other third parties supplying information which may have been used during the preparation of this report. No warranty, express or implied, is made by the preparation of this report. Third parties reviewing this report should draw their own conclusions regarding site conditions and specific construction techniques to be used on this project.

## FIGURES



NOT TO SCALE

Architecture  
Structural  
Geotechnical



**Engineers / Architects**

SOUTHERN COLORADO OFFICE  
2910 AUSTIN BLUFFS PKWY, SUITE 100,  
COLORADO SPRINGS, CO 80918  
(719) 548-0600 ~ WWW.RMGENGINEERS.COM  
SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

Materials Testing  
Forensics  
Civil / Planning


## SITE VICINITY MAP

515 STRUTHERS LOOP  
PAIR-A-DISE SUBDIVISION FILING NO. 1  
EL PASO COUNTY, COLORADO  
AARON ATWOOD

JOB No. 188423

FIG No. 1

DATE 4-8-2022



**LEGEND**

- EXISTING BOUNDARY LINE
- - - - - EASEMENT LINE
- PROPOSED LOT LINE
- SET #5 REBAR W/ 1-1/2\"/>



NOT TO SCALE

Architecture  
Structural  
Geotechnical



**Engineers / Architects**

SOUTHERN COLORADO OFFICE  
2910 AUSTIN BLUFFS PKWY, SUITE 100,  
COLORADO SPRINGS, CO 80918  
(719) 548-0600 ~ WWW.RMGENGINEERS.COM  
SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

Materials Testing  
Forensics  
Civil / Planning


**PROPOSED LOT LAYOUT PLAN**

**515 STRUTHERS LOOP  
PAIR-A-DISE SUBDIVISION FILING NO. 1  
EL PASO COUNTY, COLORADO  
AARON ATWOOD**

**JOB No. 188423**

**FIG No. 2**

**DATE 4-8-2022**



NOT TO SCALE

Architecture  
Structural  
Geotechnical



**Engineers / Architects**

SOUTHERN COLORADO OFFICE  
2910 AUSTIN BLUFFS PKWY, SUITE 100,  
COLORADO SPRINGS, CO 80918

(719) 548-0600 ~ WWW.RMBENGINEERS.COM  
SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

Materials Testing  
Forensics  
Civil / Planning

**USGS TOPO MAP**

515 STRUTHERS LOOP  
PAIR-A-DISE SUBDIVISION FILING NO. 1  
EL PASO COUNTY, COLORADO  
AARON ATWOOD

JOB No. 188423

FIG No. 3

DATE 4-8-2022



68 - PEYTON-PRING COMPLEX, 3 TO 8 PERCENT SLOPES  
 93 - TOMAH-CROWFOOT COMPLEX, 8 TO 15 PERCENT SLOPES



NOT TO SCALE

Architecture  
 Structural  
 Geotechnical



**Engineers / Architects**

SOUTHERN COLORADO OFFICE  
 2910 AUSTIN BLUFFS PKWY, SUITE 100,  
 COLORADO SPRINGS, CO 80918

(719) 548-0600 ~ WWW.RMGENGINEERS.COM  
 SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

Materials Testing  
 Forensics  
 Civil / Planning

## USDA SOIL SURVEY MAP

515 STRUTHERS LOOP  
 PAIR-A-DISE SUBDIVISION FILING NO. 1  
 EL PASO COUNTY, COLORADO  
 AARON ATWOOD

JOB No. 188423

FIG No. 4

DATE 4-8-2022

Materials Testing  
 Foundation  
 Civil Planning



Engineers / Architects

SOUTHERN COLORADO OFFICE  
 2910 AUSTIN BLUFFS PKWY, SUITE 100,  
 COLORADO SPRINGS, CO 80918  
 (719) 548-0600 ~ WWW.RMGENGINEERS.COM  
 SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO


Architecture  
 Structural  
 Geotechnical

Geologic Conditions

ags - Alluvial sand, silt, clay and gravel (Louviers and Slocum Alluvium± late middle Pleistocene)  
 cac - Arkosic loamy colluvium and sheetwash alluvium (Holocene)  
 Tkda3 - Dawson Formation Facies Unit Three (Paleocene)  
 SW - Seasonally Wet Area

Engineering Conditions

p Qs - Slocum Alluvium  
 1A - Stable alluvium, colluvium and bedrock on flat to gentle slopes (0-5%)



- ⊗ DENOTES APPROXIMATE LOCATION OF RMG TEST BORINGS
- DENOTES APPROXIMATE LOCATION OF GEOQUEST'S TEST BORINGS PERFORMED FOR THE SITE SPECIFIC SOILS REPORTS
- ⊗ DENOTES APPROXIMATE LOCATION OF GEOQUEST'S PROFILE PITS PERFORMED FOR THE SITE SPECIFIC WASTEWATER REPORTS

  
 REFERENCE  
 NOT TO SCALE

515 STRUTHERS LOOP  
 PAIR-A-DISE SUBDIVISION  
 FILING NO. 1  
 EL PASO COUNTY, COLORADO  
 AARON ATWOOD

ENGINEER:	TFM
DRAWN BY:	KCR
CHECKED BY:	TFM
ISSUED:	4-8-2022
REVISED TO INCLUDE TEST BORING LOCATIONS	7-19-2202

ENGINEERING  
 GEOLOGY MAP

SHEET No.  
**FIG-5**

# National Flood Hazard Layer FIRMette



104°50'31"W 39°3'27"N



0 250 500 1,000 1,500 2,000 Feet 1:6,000  
 Basemap: USGS National Map: Orthoimagery: Data refreshed October, 2020

## Legend

SEE FIS REPORT FOR DETAILED LEGEND AND INDEX MAP FOR FIRM PANEL LAYOUT

SPECIAL FLOOD HAZARD AREAS		Without Base Flood Elevation (BFE) Zone A, V, A99
		With BFE or Depth Zone AE, AO, AH, VE, AR
		Regulatory Floodway
OTHER AREAS OF FLOOD HAZARD		0.2% Annual Chance Flood Hazard, Areas of 1% annual chance flood with average depth less than one foot or with drainage areas of less than one square mile Zone X
		Future conditions 1% Annual chance Flood Hazard Zone X
		Area with Reduced Flood Risk due to Levee. See Notes, Zone X
		Area with Flood Risk due to Levee Zone D
OTHER AREAS		NO SCREEN Area of Minimal Flood Hazard Zone X
		Effective LOMRs
		Area of Undetermined Flood Hazard Zone D
GENERAL STRUCTURES		Channel, culvert, or Storm Sewer
		Levee, Dike, or Floodwall
OTHER FEATURES		Cross Sections with 1% Annual Chance Water Surface Elevation
		Coastal Transect
		Base Flood Elevation Line (BFE)
		Limit of Study
		Jurisdiction Boundary
MAP PANELS		Digital Data Available
		No Digital Data Available
		Unmapped

The pin displayed on the map is an approximate point selected by the user and does not represent an authoritative property location.

This map complies with FEMA's standards for the use of digital flood maps if it is not void as described below. The basemap shown complies with FEMA's basemap accuracy standards.

The flood hazard information is derived directly from the authoritative NFHL web services provided by FEMA. This map was exported on 3/1/2022 at 5:26 PM and does not reflect changes or amendments subsequent to this date and time. The NFHL and effective information may change or become superseded by new data over time.

This map image is void if the one or more of the following map elements do not appear: basemap imagery, flood zone labels, legend, scale bar, map creation date, community identifiers, FIRM panel number, and FIRM effective date. Map images for unmapped and unmodernized areas cannot be used for regulatory purposes.



NOT TO SCALE

Architecture  
Structural  
Geotechnical

# RIMG

Engineers / Architects

SOUTHERN COLORADO OFFICE  
 2910 AUSTIN BLUFFS PKWY, SUITE 100,  
 COLORADO SPRINGS, CO 80918  
 (719) 548-0600 ~ WWW.RMGENGINEERS.COM  
 SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

Materials Testing  
Forensics  
Civil / Planning


## FEMA MAP

515 STRUTHERS LOOP  
 PAIR-A-DISE SUBDIVISION FILING NO. 1  
 EL PASO COUNTY, COLORADO  
 AARON ATWOOD

JOB No. 188423

FIG No. 6

DATE 4-8-2022



**GENERAL NOTES:**

1. BOTTOM OF DRAIN PIPE SHALL BE AT OR BELOW BOTTOM OF FOOTING AT ALL LOCATIONS
2. ALL DRAIN PIPE SHALL BE PERFORATED PLASTIC, WITH THE EXCEPTION OF THE DISCHARGE PORTION WHICH SHALL BE SOLID, NON-PERFORATED PIPE.
3. DRAIN PIPE SHALL HAVE POSITIVE FALL THROUGHOUT.
4. DRAIN PIPE SHALL BE PROVIDED WITH A FREE GRAVITY OUTFALL, IF POSSIBLE. IF A GRAVITY OUTFALL CANNOT BE ACHIEVED, THEN A SUMP PIT AND PUMP SHALL BE USED. THE OUTFALL SHOULD EXTEND PAST BACKFILL ZONES AND DISCHARGE TO A LOCATION THAT IS GRADED TO DIRECT WATER OFF-SITE.
5. ALL DRAIN COMPONENTS SHALL BE RATED/APPROVED BY THE MANUFACTURER FOR THE INSTALLED DEPTH AND APPLICATION
6. DRAIN SYSTEM, INCLUDING THE OUTFALL OF THE DRAIN, SHALL BE OBSERVED BY QUALIFIED PERSONNEL PRIOR TO BACKFILLING TO VERIFY INSTALLATION.
7. A VERTICAL SEGMENT OF PERFORATED DRAIN PIPE, CAPPED AT THE TOP, SHALL EXTEND TO FINISH GRADE WITHIN ALL WINDOW WELLS.

Architecture  
Structural  
Geotechnical



**Engineers / Architects**

SOUTHERN COLORADO OFFICE  
2910 AUSTIN BLUFFS PKWY, SUITE 100,  
COLORADO SPRINGS, CO 80918


(719) 548-0600 ~ WWW.RMGENGINEERS.COM

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

Materials Testing  
Forensics  
Civil / Planning

**PERIMETER DRAIN**

**FIG No. 7**



NON-WOVEN GEOTEXTILE (AS SHOWN) ACROSS BOTTOM OF BASEMENT - GEOTEXTILE TO MEET THE FOLLOWING REQUIREMENTS:  
 MAXIMUM APPARENT OPENING SIZE: US SIEVE #10  
 MINIMUM WATER FLOW RATE: 135 GAL/MIN/FT<sup>2</sup>  
 MINIMUM TRAPEZOIDAL TEAR STRENGTH: 40 lbs  
 MINIMUM CBR PUNCTURE STRENGTH: 250 lbs  
 MINIMUM GRAB TENSILE STRENGTH: 90 lbs

3' DIAMETER RIGID PERFORATED PIPE CONNECTED TO A SUITABLE GRAVITY OUTFALL SUCH AS AN UNDERDRAIN LOCATED IN THE UTILITY TRENCH IN THE STREET WITH A MIN. GRADE OF PIPE = 1.5%. IF A FREE GRAVITY OUTFALL CANNOT BE ACHIEVED, A SUMP PIT AND PUMP SHOULD BE PROVIDED.

**GENERAL NOTES:**

1. ALL DRAIN PIPE SHALL BE PERFORATED PLASTIC, WITH THE EXCEPTION OF THE DISCHARGE PORTION WHICH SHALL BE SOLID, NON-PERFORATED PIPE.
2. DRAIN PIPE SHALL HAVE POSITIVE FALL THROUGHOUT.
3. DRAIN PIPE SHALL BE PROVIDED WITH A FREE GRAVITY OUTFALL, IF POSSIBLE. IF A GRAVITY OUTFALL CANNOT BE ACHIEVED, THEN A SUMP PIT AND PUMP SHALL BE USED. THE OUTFALL SHOULD EXTEND PAST BACKFILL ZONES AND DISCHARGE TO A LOCATION THAT IS GRADED TO DIRECT WATER OFF-SITE.
4. ALL DRAIN COMPONENTS SHALL BE RATED/APPROVED BY THE MANUFACTURER FOR THE INSTALLED DEPTH AND APPLICATION
5. DRAIN SYSTEM, INCLUDING THE OUTFALL OF THE DRAIN, SHALL BE OBSERVED BY QUALIFIED PERSONNEL PRIOR TO BACKFILLING TO VERIFY INSTALLATION.

Architecture  
Structural  
Geotechnical



**Engineers / Architects**

SOUTHERN COLORADO OFFICE  
 2910 AUSTIN BLUFFS PKWY, SUITE 100,  
 COLORADO SPRINGS, CO 80918

(719) 548-0600 ~ WWW.RMGENGINEERS.COM  
 SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

Materials Testing  
Forensics  
Civil / Planning

**UNDERSLAB DRAIN**

**FIG No. 8**

# APPENDIX A

## Additional Reference Documents

1. *Replat Map, Pair-A-Dise Subdivision Filing No. 1, a re-plat of lot 38, Chaparral Hills, El Paso County, Colorado*, prepared by MVE, Inc. Engineers and Surveyors, last dated October 12, 2021.
2. *Soils Report for Aaron Atwood, Lot #38, Chaparral Hills Subdivision, 515 Struthers Loop, El Paso County, Colorado*, prepared by Geoquest, LLC, Job No. 21-0794, last dated July 30, 2021.
3. *Soils Report for Aaron Atwood, Lot #38, Chaparral Hills Subdivision, 515 Struthers Loop, El Paso County, Colorado*, prepared by Geoquest, LLC, Job No. 21-0795, last dated July 30, 2021.
4. *Flood Insurance Rate Map, El Paso County, Colorado and Unincorporated Areas, Community Panel No. 08041C0287G*, Federal Emergency Management Agency (FEMA), effective December 7, 2018.
5. *Surficial Geologic Map of the Denver 1-degree X 2-degree Quadrangle, Colorado. U.S. Geological Survey, Moore, D.W., Straub, A.W., Berry, M.E., Baker, M.L., and Brandt, T.R., MF-2388, 2001*
6. *Geologic Map of the Monument Quadrangle, El Paso County, Colorado*, Thorson, J.P., and Madole, R.F., Colorado Geological Survey, Open-File Report OF02-04, 2004.
7. *Environmental and Engineering Geologic Map for Land Use*, compiled by Dale M. Cochran, Charles S. Robinson & Associates, Inc., Golden, Colorado, 1977.
8. *Map of Potential Geologic Hazards and Surficial Deposits*, compiled by Dale M. Cochran, Charles S. Robinson & Associates, Inc., Golden, Colorado, 1977.
9. *Pikes Peak Regional Building Department*: <https://www.pprbd.org/>.
10. El Paso County Assessor Website  
<https://property.spatialest.com/co/elpaso/#/property/71360002005>  
Schedule No. 71360002005
11. *Colorado Geological Survey, USGS Geologic Map Viewer*:  
<http://coloradogeologicalsurvey.org/geologic-mapping/6347-2/>.
12. *Historical Aerials*: <https://www.historicaerials.com/viewer>, Images dated 1947, 1952, 1953, 1955, 1960, 1969, 1983, 1999, 2005, 2009, 2011, 2013, 2011, 2013, 2015, 2017, and 2019.
13. *USGS Historical Topographic Map Explorer*: <http://historicalmaps.arcgis.com/usgs/> El Paso County, Monument Quadrangle, 2019.
14. *Google Earth Pro*, Imagery dated 1999, 2003, 2004, 2005, 2006, 2011, 2015, 2017, 2019 and 2020.
15. Kirkham, R.M., and Ladwig, L.R., 1979, Coal resources of the Denver and Cheyenne basins, Colorado: Colorado Geological Survey Resource Series 5, 70 p., 5 plates
16. Keller, J.W., Phillips, R.C., and Morgan, Karen, 2002, Digital inventory of industrial mineral mines and mine permit locations in Colorado: Colorado Geological Survey Information Series IS-62, CD ROM.
17. Mason, G. T., and Arndt, R. E., 1996, Mineral resource data system (MRDS): U.S. Geological Survey Digital Data Series DDS-20 (CD-ROM).
18. *Evaluation of Mineral and Mineral Fuel Potential of El Paso County State Mineral Lands*
19. *The El Paso Aggregate Resource Evaluation Map, Master Plan for Mineral Extraction, Map 1*

**APPENDIX B**  
Site Reconnaissance Photos



Site access off of  
Struthers Loop  
Kyle Reamer-Staff  
Geologist-RMG

188423 - 515 Struthers Loop  
02 Mar 2022, 8:51:38 AM




SE boundary looking SE  
Kyle Reamer-Staff  
Geologist-RMG

188423 - 515 Struthers Loop  
02 Mar 2022, 8:52:14 AM



SE boundary looking North  
 Kyle Reamer-Staff  
 Geologist-RMG

188423 - 515 Struthers Loop  
 02 Mar 2022 8:52:46 AM



SE boundary looking West  
 Kyle Reamer-Staff  
 Geologist-RMG

188423 - 515 Struthers Loop  
 02 Mar 2022 8:53:06 AM



Telecommunications box in  
SE corner  
Kyle Reamer-Staff  
Geologist-RMG

188423 - 515 Struthers Loop  
02 Mar 2022, 8:54:18 AM




SW boundary looking north  
Kyle Reamer-Staff  
Geologist-RMG

188423 - 515 Struthers Loop  
02 Mar 2022, 8:56:16 AM



SE boundary looking South  
 Kyle Reamer-Staff  
 Geologist-RMG

188423 - 515 Struthers Loop  
 02 Mar 2022 8:53:25 AM



SE boundary looking  
 into property  
 Kyle Reamer-Staff  
 Geologist-RMG

188423 - 515 Struthers Loop  
 02 Mar 2022 8:53:42 AM




SW boundary looking east  
 Kyle Reamer-Staff  
 Geologist-RMG


188423 - 515 Struthers Loop  
 02 Mar 2022, 8:56:37 AM



SW boundary looking south  
 Kyle Reamer-Staff  
 Geologist-RMG

188423 - 515 Struthers Loop  
 02 Mar 2022, 8:56:52 AM





☉ 118°SE (T) ☉ 39°3'10"N, 104°50'13"W ±13ft ▲ 6902ft




Concrete sink SW boundary  
 Kyle Reamer-Staff  
 Geologist-RMG

188423 - 515 Struthers Loop  
 02 Mar 2022, 8:57:32 AM



☉ 248°W (T) ☉ 39°3'13"N, 104°50'9"W ±13ft ▲ 6921ft



Eastern boundary looking  
 into property  
 Kyle Reamer-Staff  
 Geologist-RMG

188423 - 515 Struthers Loop  
 02 Mar 2022, 9:00:18 AM



☉ 209°SW (T) ☉ 39°3'13"N, 104°50'9"W ±9ft ▲ 6925ft




Eastern boundary looking into property  
Kyle Reamer-Staff  
Geologist-RMG

188423 - 515 Struthers Loop  
02 Mar 2022 9:00:35 AM



☉ 320°NW (T) ☉ 39°3'13"N, 104°50'9"W ±9ft ▲ 6927ft




Eastern boundary looking into property  
Kyle Reamer-Staff  
Geologist-RMG

188423 - 515 Struthers Loop  
02 Mar 2022 9:00:40 AM


E 60 90 120 SE 150 180 S  
 119°SE (T) 39°3'15"N, 104°50'8"W ±13ft ▲ 6919ft



W 240 270 300 NW 330 0 N  
 302°NW (T) 39°3'15"N, 104°50'8"W ±9ft ▲ 6920ft







NE boundary looking south  
 Kyle Reamer-Staff  
 Geologist-RMG

188423 - 515 Struthers Loop  
 02 Mar 2022, 9:04:22 AM

NE boundary looking west  
 Kyle Reamer-Staff  
 Geologist-RMG

188423 - 515 Struthers Loop  
 02 Mar 2022, 9:04:31 AM



Shipping container near  
NE boundary  
Kyle Reamer-Staff  
Geologist-RMG

188423 - 515 Struthers Loop  
02 Mar 2022, 9:06:04 AM



Miscellaneous equipment near  
shipping container  
Kyle Reamer-Staff  
Geologist-RMG

188423 - 515 Struthers Loop  
02 Mar 2022, 9:06:36 AM



Wooded area along  
northern boundary  
Kyle Reamer-Staff  
Geologist-RMG

188423 - 515 Struthers Loop  
02 Mar 2022 9:07:29 AM




Wooded area along  
northern boundary  
Kyle Reamer-Staff  
Geologist-RMG

188423 - 515 Struthers Loop  
02 Mar 2022 9:07:44 AM



Northern boundary  
property fence  
Kyle Reamer-Staff  
Geologist-RMG

188423 - 515 Struthers Loop  
02 Mar 2022, 9:08:29 AM



Wetland type vegetation around  
NW boundary  
Kyle Reamer-Staff  
Geologist-RMG

188423 - 515 Struthers Loop  
02 Mar 2022, 9:11:26 AM




Remnants of 2021 Geoquest  
test pit on lot 1  
Kyle Reamer-Staff  
Geologist-RMG

188423 - 515 Struthers Loop  
02 Mar 2022, 9:12:26 AM

Geoquest Test pit from 2021  
Kyle Reamer-Staff  
Geologist-RMG

188423 - 515 Struthers Loop  
02 Mar 2022, 9:14:14 AM





Site overview from front  
of property  
Kyle Reamer-Staff  
Geologist-RMG

188423 - 515 Struthers Loop  
02 Mar 2022, 9:19:51 AM

Site overview from front  
of property  
Kyle Reamer-Staff  
Geologist-RMG

188423 - 515 Struthers Loop  
02 Mar 2022, 9:20:14 AM

## APPENDIX C

*Soils Reports for Aaron Atwood, Lot #38, Chaparral Hills Subdivision, 515 Struthers Loop, El Paso County, Colorado*, prepared by Geoquest, LLC, Job No. 21-0794 and 21-0795, last dated July 30, 2021.



6825 Silver Ponds Heights #101  
Colorado Springs, CO 80908  
(719) 481-4560

---

Aaron Atwood  
701 Airman Lane  
Colorado Springs, Colorado 80921

RE: Soil Test Receipt, 515 Struthers Loop, Geoquest #21-0794

To Whom It May Concern:

Thank you for choosing Geoquest, LLC to perform the Soils Report for the property at the above location.

The attached Soils Report provided by Geoquest, LLC, has been prepared in accordance with the standard of practice. This report does not address possible geologic hazards, environmental hazards, or drainage that exist on-site. There are specific requirements for the design and construction of the foundation of a structure at the location noted in the report. Some of these requirements are placed on the homeowner of the property and may be outside of the builders' control. **Accordingly, we are requiring both the builder and the homeowner to sign this letter indicating both parties have accepted a copy of the report, have read and understood the contents, and know they each have specific responsibilities. Failure to follow the recommendations and requirements of the report by any party can result in unsatisfactory performance of the foundation or building components. The Builder and Owner understand the risks, as noted in the Soils Report, and accept all risk, including movement of slabs.**

After the excavation has been completed an **Open Hole Observation is required** to be performed by the Soils Engineer. **After the Open Hole Observation is complete, the owner/builder should inform the Foundation Engineer of any changes to the soil conditions or allowable bearing. The Open Hole Observation is an additional cost.**

**Geoquest, LLC, will not provide any documentation for site inspections until we have received this letter with the required signatures.** If the property is being developed as a speculative investment and no homeowner has been contracted to purchase the property, you can indicate that under the homeowner signature line. Upon the sale of the property the builder understands that both this letter and a copy of the Soils Report shall be provided to the buyer, and a homeowner signed copy returned to Geoquest, LLC.

If you have any questions, feel free to contact us at (719) 481-4560.

Sincerely,

  
Charles E. Milligan, P.E.

Builder Representatives

Homeowner(s)

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_



6825 Silver Ponds Heights #101  
Colorado Springs, CO 80908  
(719) 481-4560

---

**SOILS REPORT**

**FOR**

**AARON ATWOOD**

**JOB #21-0794**

Lot #38,  
Chaparral Hills Subdivision,  
515 Struthers Loop,  
El Paso County,  
Colorado

Sincerely,

  
Charles E. Milligan, P.E.



**TABLE OF CONTENTS**

INTRODUCTION .....1

CONCLUSIONS .....1

GENERAL.....1

FIELD AND LABORATORY INVESTIGATION .....1

TOPOGRAPHY .....2

WEATHER .....2

DESIGN AND CONSTRUCTION CONSIDERATIONS .....2

RECOMMENDATION REMARKS .....3

COLD TEMPERATURE CONSIDERATIONS.....3

SURFACE DRAINAGE .....3

SUBSURFACE DRAINAGE .....4

REINFORCING .....4

FOOTING DESIGN .....4

CONSTRUCTION DETAILS.....4

MINIMUM MATERIALS SPECIFICATIONS .....4

OPEN HOLE OBSERVATION (added cost).....4

COMPACTION TESTING (added cost) .....5

MODIFIED PROCTOR DENSITY TESTING (added cost) .....5

FINAL OBSERVATIONS (added cost) .....5

LIMITATIONS .....5

APPENDIX .....6

## INTRODUCTION

The owners must be made aware of the contents of this report. If there are any questions or concerns regarding the information in this report, please contact Geoquest, LLC. It is the responsibility of the contractor on this project to make subsequent owners aware of the contents of this report. This is to ensure that the recommendations and requirements of the report, especially regarding the surface drainage, are acknowledged and followed. This report is prepared for **Aaron Atwood, owner, on Lot #38, Chaparral Hills Subdivision, 515 Struthers Loop, El Paso County, Colorado**. This report is prepared with the understanding that a single-family residence is planned for this site. The site does not have existing structures.

## CONCLUSIONS

The soil profile of this site has shallow unsuitable very low density material, to the depth of 5 feet. The excavation and the placement of the foundation components must penetrate the very low density silty sand (SM) in Test Hole #1 (TH-1). If this unsuitable material is encountered, it must be removed and replaced, compaction testing will be required, and a bearing of 1,000 pounds per square foot will be used. The over-excavated area shall extend to a minimum depth of 4 feet below the bottom of the foundation elevation and 4 feet laterally from the foundation. If the foundation will penetrate the unsuitable soil, then a soils bearing of 1,000 pounds per square foot should be used and 4 feet of lateral separation must be maintained.

A satisfactory foundation for this structure is a properly designed shallow foundation system consisting of foundation components resting directly on undisturbed materials. Foundation components resting directly on undisturbed low to moderate density materials shall be designed for a loading of not greater than **1,500 pounds per square foot**. Foundation components resting directly on undisturbed moderate density materials shall be designed for a loading of not greater than **2,000 pounds per square foot**. **Any design by any engineer is subject to revision based on the results of the open hole observation**. The compressibility of this material is low. This bearing capacity is calculated with a safety factor of three. The type of foundation configuration used depends on the building loads applied. The depth of foundation elements shall be determined by the foundation engineer but should be at least as deep as the minimum depth required by the governing building authority. **The laboratory testing revealed that the on-site soil is silty sand with underlying clayey sand (U.S.C.S. Classification Symbol SM, SC)**. The unit weight of equivalent fluid soil pressure of this material is **45 (SM) and 85 (SC) pounds per cubic foot**. **The native SC is not suitable and shall not be used as backfill material around the perimeter of the foundation**. The actual equivalent fluid soil pressure was not determined. The expected values are from ASCE 7-10, Table 3.2-1. **Foundation components should bear on soils of similar bearing capacity. Foundation components bearing on dissimilar soils should be avoided. The owners shall be made aware that movement will occur if surface or subsurface water is allowed to collect around the foundation wall.**

## GENERAL

The investigation was made to reveal important characteristics of the soils and of the site influencing the foundation design. Also evaluated during the investigation were subsurface conditions that affect the depth of the foundation and subsequent loading design, such as ground water levels, soil types, and other factors which affect the bearing capacity of the soils. Design loadings are based on soils characteristics and represent the maximum permissible loads for these conditions. The bearing capacity is calculated with a safety factor of three.

## FIELD AND LABORATORY INVESTIGATION

Two exploratory holes were drilled on July 5, 2021, at the locations shown on the enclosed site map. The location of these test holes was determined by Aaron Atwood. The test holes were drilled with a 3-inch diameter auger. At intervals anticipated to be the foundation depths, and as determined by the soils conditions, the drill tools were removed, and samples were taken by the use of a 2-inch split barrel sampler connected to a 140-pound drop-hammer. This hammer is dropped 30 inches to drive the penetration sampler into the soil (**ASTM D-1586**). The depths and descriptions of the materials encountered in each test boring at which the samples were taken are shown on the enclosed log sheets. All samples were classified both in the field and in the laboratory to evaluate the physical and mechanical properties of the materials encountered.

## TOPOGRAPHY

The topography of this site is that of an incline sloping down towards the southwest at 6%.

## WEATHER

The weather at the time of the soil examination consisted of clear skies with warm temperatures.

## DESIGN AND CONSTRUCTION CONSIDERATIONS

Slabs-on-grade may move and crack. Vertical slab movement of up to one and a half inches should be expected for native soils with low expansion potential. In some cases, vertical movement may exceed this range. If movement and associated damage to basement floors and finishes cannot be tolerated, a structural floor system should be installed. If compaction is not performed, settlement may occur causing cracking of foundation walls and floors. Soil located beneath concrete walls shall be compacted to at least 95% Modified Proctor density (**ASTM D-1557**). Soil located beneath concrete slabs shall be compacted to at least 85% Modified Proctor density. Special care is to be taken to re-compact the material above utility lines to a minimum of 85% Modified Proctor density. During construction, conditions that could cause settlement shall be eliminated. Interior non-bearing partition walls shall be constructed such that they do not transmit floor slab movement to the roof or overlying floor. The gap or void (1.5 inch min.) installed in these non-bearing partitions may require re-construction over the life of the structure to re-establish the gap or void to allow for vertical slab movement. Stairwells, doorways, and sheeted walls should be designed for this movement.

The following are general recommendations of on-grade slabs:

1. Slabs shall be placed on well-compacted, non-expansive materials, and all soft spots shall be thoroughly excavated and replaced with non-expansive fill materials as stated above.
2. Slabs shall be separated from all foundation walls, load bearing members, and utility lines.
3. At intervals not to exceed 12 feet in each direction, provide control joints to reduce problems with shrinkage and curling as recommended by the American Concrete Institute (**ACI 360R-10**). Moisten the ground beneath the slab prior to the placement of concrete.
4. All concrete placed must be cured properly as recommended by the American Concrete Institute (**ACI 360R-10**). Separate load bearing members from slabs, as discussed above. Care must be exercised to prevent excess moisture from entering the soil under the structure, both during and after construction.
5. Due to the exposure of exterior concrete to variations in moisture fluctuations, heaving and cracking of exterior slabs-on-grade should be expected. Placement of at least 3 feet of non-expansive fill beneath the slabs can help to reduce the impact of differential movement and cracking but may not eliminate movement. Exterior concrete shall slope away from the structure a minimum of 2% grade.
6. The clayey sand (SC) has been analyzed for its expansion and/or consolidation potential. Basement slabs, garage slabs, and all concrete floor slabs, however, exert a very low dead-load pressure on the soil. Since this soil contains at least a small amount of swell potential, slabs will crack and heave or settle if excess water is allowed to penetrate the sub-grade. For example, column openings to pads below the placed slab, if exposed to precipitation during construction, will conduct water to the sub-grade, possibly causing it to expand. Also, if the slab is placed with concrete too wet, expansion may occur. We recommend 3,000 psi concrete placed at a maximum slump of 4 inches.

## RECOMMENDATION REMARKS

The recommendations provided in this report are based upon the observed soil parameters, anticipated foundation loads, and accepted engineering procedures. The recommendations are intended to minimize differential movement resulting from the heaving of expansive soil or from the settlement induced by the application of loads. **It must be recognized that the foundation will undergo some movement on all soil types.** In addition, concrete floor slabs will move vertically, therefore, adherence to those recommendations which isolate floor slabs from columns, walls, partitions or other structural components is extremely important if damage to the superstructure is to be minimized.

Any subsequent owners should be apprised of the soil conditions and advised to maintain good practice in the future with regard to surface and subsurface drainage and partition framing, drywall and finish work above floor slabs.

Geoquest, LLC does not assure that the contractor and/or homeowner will comply with the recommendations provided in this report. Geoquest, LLC provides recommendations only and does not supervise, direct or control the implementation of the recommendations.

**Failure to follow the recommendation provided by Geoquest, LLC and follow observation requirements may jeopardize the construction project and Geoquest, LLC shall be absolved from any and all responsibility for any damages arising from the failure to obtain proper site observation and follow recommendations.**

## COLD TEMPERATURE CONSIDERATIONS

1. Concrete shall not be placed upon wet or frozen soil.
2. Concrete shall be protected from freezing until it has been allowed to cure for at least 7 days after placement in forms.
3. Snow or other frozen water shall not be allowed in the forms during placement of concrete.
4. Concrete shall be cured in forms for at least 72 hours.
5. Concrete shall be vibrated or rodded in forms to avoid segregation and cold joints.
6. The site shall be kept well drained at all times. Ponding of water should be avoided in the excavation area.

## SURFACE DRAINAGE

After construction of foundation walls, the backfill material shall be well compacted to 80% Modified Proctor density, to reduce future settlement. Any areas that settle after construction shall be filled to eliminate ponding of water adjacent to the foundation walls. **The finished grade shall have a positive slope away from the structure with an initial slope of 6 inch in the first 10 feet.** If a 10 foot zone is not possible on the upslope side of the structure, then a well-defined swale should be created a minimum of 5 feet from the foundation and sloped parallel with the wall at a 2% grade to intercept the surface water and carry it around and away from the structure. Homeowners shall maintain the surface grading and drainage installed by the builder to prevent water from being directed in the wrong direction. All downspouts shall have extensions that will remove runoff to the outside of the backfilled areas. Shrubs and plants requiring minimal watering shall be established in this area. Irrigated grass shall not be located within 5 feet of the foundation. Sprinklers shall not discharge water within 5 feet of the foundation. Irrigation should be limited to the minimum amount sufficient to maintain vegetation. Application of more water will increase the likelihood of floor slab and foundation movement.

All exterior grading and location of downspouts and their performance shall be inspected by Geoquest, LLC. **The native clayey sand (SC) material is not suitable and shall not be used as backfill material around the perimeter of the foundation.** If on-site soils are not suitable for the backfill, the backfill material shall consist of clean non-cohesive granular soils or road base material as described previously. Imported material is to be approved by Geoquest, LLC prior to placement. **We recommend imported granular backfill with a maximum unit weight of 45 pounds per cubic foot.** It is the responsibility of the contractor to schedule all inspections.

## **SUBSURFACE DRAINAGE**

Perimeter drains are required around all walls of the habitable or usable area portion of the structure that are below finished grade including all common wall(s) adjacent to the basement. Crawlspace are considered usable area. Walkout areas need not be drained unless specified at the time of the Open Hole Observation. The final determination of the necessity for perimeter drains will be made at the time of the Open Hole Observation. An Exterior Drain Detail is provided in this report. Drains should daylight away from the structure or discharge to a sump pump.

## **REINFORCING**

The concrete foundation walls shall be properly reinforced as per the specific design for this foundation by a **Colorado Registered Professional Engineer. Exact requirements are a function of the design of the structure. Questions concerning the specific design requirements shall be referred to the design engineer.**

## **FOOTING DESIGN**

The design for footings, pads, and/or piers for this structure is determined by applying the dead load and full live load to the foundation walls.

## **CONSTRUCTION DETAILS**

It is necessary with any soils investigation to assume that the materials from the test holes are representative of the materials in the area. On occasion variations in the subsurface materials do occur, therefore, should such variations become apparent during construction, the owner is advised to contact this office for a determination as to whether these variations will affect the design of the structure's foundation. If anomalies are observed during the excavation for the structure, this office should be contacted to determine whether the layers will adversely affect the design.

## **MINIMUM MATERIALS SPECIFICATIONS**

1. Minimum materials specifications of the concrete, reinforcing, etc., shall be determined by the Professional Foundation Design Engineer.
2. Compact beneath foundation walls a minimum of 95% Modified Proctor density to prevent settlement.
3. Compact all backfill material located around the perimeter of the foundation to a minimum of 80% Modified Proctor density.
4. Concrete shall be vibrated or rodded in forms to avoid segregation and cold joints.
5. The site shall be kept well drained at all times.

## **OPEN HOLE OBSERVATION (added cost)**

**If anyone other than Geoquest, LLC, performs the Open Hole Observation, that person/company assumes liability for the soils, and any possible changes to the foundation design.**

The owner, or a representative of the construction company shall contact **Geoquest, LLC** a minimum of **24 hours** prior to excavating for the foundation. An Open Hole Observation must be performed on each individual structure prior to the placement of concrete, and preferably prior to the placement of forms in the excavated area. **The failure to request or obtain an Open Hole Observation prior to the placement of foundation components may result in this Soils Report being declared null and void.** This is to ensure that soft areas, anomalies, etc., are not present in the foundation region. At the time of the open hole observation the **foundation type recommendations, maximum allowable bearing capacity may be revised** according to soil conditions found at that time. If revisions are made to the Soils Report due to the soil conditions of the excavation, **the Foundation Design Engineer must be notified of all revisions.**

### COMPACTION TESTING (added cost)

Geoquest, LLC shall perform compaction testing on any replaced material. Soil shall be compacted in maximum 6-inch lifts. Testing shall be performed at intervals not to exceed 24 inches (or as required by the design engineer). Modified Proctor Density must be provided to Geoquest, LLC prior to compaction testing, see below.

The owner, or a representative of the construction, shall contact Geoquest, LLC a **minimum of 24 hours prior to the time the compaction test is requested. The failure to properly compact and/or obtain proper compaction testing may result in this Soils Report being declared null and void.**

### MODIFIED PROCTOR DENSITY TESTING (added cost)

**Modified Proctor Density test must be provided to Geoquest, LLC prior to compaction testing.** If a Proctor cannot be provided, a Modified Proctor Density test must be completed prior to compaction testing. Two 5-gallon valid samples of the soil to be used, must be provided for testing, at least 2 weeks prior to the placement and compaction of the material.

**The failure to provide this data may result in this Soils Report being declared null and void.**

### FINAL OBSERVATIONS (added cost)

The owner, or a representative of the construction company, shall contact Geoquest, LLC at the time final grading and landscaping procedures are completed. This is to ensure that sprinkler systems are not installed adjacent to the structure and that only shrubs or plants that require minimal watering are established in this area. All exterior grading as well as the location of downspouts and their performance shall be inspected by Geoquest, LLC. Any additional landscaping or grading changes performed by subsequent contractors and/or owners shall be inspected and approved. It is the responsible of the contractor and/or owner to schedule all these inspections at the appropriate times. **The failure to obtain this inspection may result in this Soils Report being declared null and void.**

### LIMITATIONS

This report is issued based on the understanding that the owner or his representative will bring the information, data, and recommendations contained in this report to the attention of the project engineer and architect, in order that they may be incorporated into the plans for the structure. It is also the owner's responsibility to ensure that all contractors and sub-contractors carry out these recommendations during the construction phase.

This report was prepared in accordance with generally accepted professional geotechnical/engineering methods. However, Geoquest, LLC makes no other warranty, express or implied, as to the findings, data, specifications, or professional advice rendered hereunder. **Due to circumstances outside of Geoquest, LLC's control, including improper construction, failure to follow recommendations, and unforeseen events, the Limits of Liability extend only to fees rendered for the professional services provided.**

This report is considered valid as of the present date. The owner acknowledges, however, that changes in the conditions of the property might occur with the passage of time, such as those caused by natural effects or man-made changes, both on this land and on abutting properties. Further, changes in acceptable tolerances or standards might arise as the result of new legislative actions, new engineering advances, or the broadening of geotechnical knowledge. Thus, certain developments beyond our control may invalidate this report, in whole or in part.

This report and its recommendations do not apply to any other site than the one described herein and are predicated on the assumption that the soil conditions do not deviate from those described. In the event that any variations or undesirable conditions should be detected during the construction phase or if the proposed construction varies from that planned as of this report date, the owner shall immediately notify Geoquest, LLC in order that supplemental recommendations can be provided, if so required.

This report excludes possible environmental issues, geologic hazards, flooding, or any other natural or man-made hazards that affect this site. These are outside the scope of work, for this report.

## APPENDIX



# DRILL LOGS


JOB #: 21-0794	DEPTH (in ft.)	SYMBOL	SAMPLES	BLOW COUNT	WATER %	SOIL TYPE
TEST BORING NO.: TH-1						
DATE: 7/5/2021						
<u>0"-8" Topsoil</u>	0-2	X X X X				
<u>8"-5' Sand</u>	2-7					
Fine-coarse grained Very low density Low moisture content Low-moderate clay content Low-moderate plasticity Tan color	2			$\frac{5}{12''}$	4.7	
	4					
	6					
<u>5'- 15' Sand (SC)</u>	7-12					
Fine-coarse grained Moderate density High moisture content Moderate clay content Moderate plasticity Brown Grey color	8			$\frac{28}{12''}$	26.8	SC
	10					
	12					
	14					
	16					
	18					
	20					

JOB #: 21-0794	DEPTH (in ft.)	SYMBOL	SAMPLES	BLOW COUNT	WATER %	SOIL TYPE
TEST BORING NO.: TH-2						
DATE: 7/5/2021						
<u>0"-8" Topsoil</u>	0-2	X X X X				
<u>8"-6' Sand (SM)</u>	2-8					
Fine-coarse grained Low-moderate density Low moisture content Low-moderate clay content Low-moderate plasticity Tan color	2			$\frac{18}{12''}$	3.3	SM
	4					
	6					
<u>6'- 15' Sand</u>	7-12					
Fine-coarse grained Moderate density High moisture content Moderate clay content Moderate plasticity Brown Grey color	8			$\frac{26}{12''}$	24.2	
	10					
	12					
	14					
	16					
	18					
	20					

GEOQUEST LLC


**SITE MAP**

Lot 38  
Chaparral Hills  
515 Struthers Loop  
El Paso County  
Colorado  
Job #21-0794



0 50 100 150 200  
GRAPHIC SCALE IN FEET  
SCALE: 1" = 200'


# GEOQUEST LLC GRADATION TEST RESULTS



CLAY TO SILT	SAND	GRAVEL	
	FINE    MEDIUM    COARSE	FINE    COARSE	COBBLES

**CLASSIFICATION** SC  
 GRAVEL 2.7 %  
 SAND 57.4 %  
 FINES 39.9 %  
 SAMPLE # 1 HOLE # TH-1 DEPTH 12 FEET

NOTES: 26.8 % Moisture Content



CLAY TO SILT	SAND	GRAVEL	
	FINE    MEDIUM    COARSE	FINE    COARSE	COBBLES


**CLASSIFICATION** SM  
 GRAVEL 0.0 %  
 SAND 80.9 %  
 FINES 19.1 %  
 SAMPLE # 1 HOLE # TH-2 DEPTH 4 FEET

NOTES: 3.3 % Moisture Content


Job #: 21-0794 By: MJ 7/5/2021



## EXTERIOR DRAIN DETAIL



1. Gravel to be Not More Than 1-1/2" and Not Less Than 1/2" Diameter.
2. Perforated Pipe Diameter Varies With Expected Seepage. 3"  $\varnothing$  and 4"  $\varnothing$  are Most Common. ABS and PVC are Most Common Materials for Pipe. We approve the use of an "EZ Flow Drainage System" by Infiltrator. All specifications in this drain detail are still applicable.
3. Pipe to be Laid out in a Minimum Slope of 1" in 10'.
4. Gravity Outfall is Desired if Possible. Portion of Pipe in Area Not Drained Shall be Non-Perforated. Daylight Must be Maintained Clear of Debris in Order to Function Properly.
5. If Gravity Outfall is Not Possible, Provide a Sump With Operational Pump. Pump May Not Connect to Any Sanitary or Storm Sewer.
6. Soil Backfill Should be Compacted to at Least 80% of the Modified Proctor Density in the Upper Three Feet of Fill.
7. Filter Fabric to be Mirafi 140s or Approved Equivalent. Roofing Felt and Sheet Plastic are Not Acceptable.
8. Drain Pipe Shall be Laid Below Protected Area, as Shown in The Detail Above.
9. Mop Polyethylene Film to Wall Approximately One Foot Above Joint of Footing and Wall (Do Not Pull Plastic Tight) and Carry Beneath Gravel and Pipe.
10. The Polyethylene Film Shall be Continued to the Edge of the Excavation.



6825 Silver Ponds Heights #101  
Colorado Springs, CO 80908  
(719) 481-4560

Aaron Atwood  
701 Airman Lane  
Colorado Springs, Colorado 80921

RE: Soil Test Receipt, 515 Struthers Loop, Geoquest #21-0795

To Whom It May Concern:

Thank you for choosing Geoquest, LLC to perform the Soils Report for the property at the above location.

The attached Soils Report provided by Geoquest, LLC, has been prepared in accordance with the standard of practice. This report does not address possible geologic hazards, environmental hazards, or drainage that exist on-site. There are specific requirements for the design and construction of the foundation of a structure at the location noted in the report. Some of these requirements are placed on the homeowner of the property and may be outside of the builders' control. **Accordingly, we are requiring both the builder and the homeowner to sign this letter indicating both parties have accepted a copy of the report, have read and understood the contents, and know they each have specific responsibilities. Failure to follow the recommendations and requirements of the report by any party can result in unsatisfactory performance of the foundation or building components. The Builder and Owner understand the risks, as noted in the Soils Report, and accept all risk, including movement of slabs.**

After the excavation has been completed an **Open Hole Observation and Compaction Testing** are required to be performed by the Soils Engineer. **After the Final Compaction Test is complete, the owner/builder should inform the Foundation Engineer of any changes to the soil conditions or allowable bearing. The Open Hole Observation and Compaction Tests are an additional cost.**

**Geoquest, LLC, will not provide any documentation for site inspections until we have received this letter with the required signatures.** If the property is being developed as a speculative investment and no homeowner has been contracted to purchase the property, you can indicate that under the homeowner signature line. Upon the sale of the property the builder understands that both this letter and a copy of the Soils Report shall be provided to the buyer, and a homeowner signed copy returned to Geoquest, LLC.

If you have any questions, feel free to contact us at (719) 481-4560.

Sincerely,

  
Charles E. Milligan, P.E.

Builder Representatives

Homeowner(s)

\_\_\_\_\_  
  
\_\_\_\_\_

\_\_\_\_\_  
  
\_\_\_\_\_



6825 Silver Ponds Heights #101  
Colorado Springs, CO 80908  
(719) 481-4560

---

**SOILS REPORT**

**FOR**

**AARON ATWOOD**

**JOB #21-0795**

Lot #38,  
Chaparral Hills Subdivision,  
515 Struthers Loop,  
El Paso County,  
Colorado

Sincerely,

  
Charles E. Milligan, P.E.



**TABLE OF CONTENTS**

INTRODUCTION .....1

CONCLUSIONS .....1

GENERAL.....1

FIELD AND LABORATORY INVESTIGATION .....2

TOPOGRAPHY .....2

WEATHER .....2

DESIGN AND CONSTRUCTION CONSIDERATIONS .....2

RECOMMENDATION REMARKS .....3

COLD TEMPERATURE CONSIDERATIONS.....3

SURFACE DRAINAGE .....4

SUBSURFACE DRAINAGE .....4

REINFORCING .....4

FOOTING DESIGN .....4

CONSTRUCTION DETAILS.....4

MINIMUM MATERIALS SPECIFICATIONS.....5

OPEN HOLE OBSERVATION (added cost).....5

COMPACTION TESTING (added cost) .....5

MODIFIED PROCTOR DENSITY TESTING (added cost) .....5

FINAL OBSERVATIONS (added cost) .....5

LIMITATIONS .....6

APPENDIX .....7

## INTRODUCTION

The owners must be made aware of the contents of this report. If there are any questions or concerns regarding the information in this report, please call Geoquest, LLC. It is the responsibility of the contractor on this project to make subsequent homeowners aware of the contents of this report. This is to ensure that the recommendations and requirements of the report, especially regarding the surface drainage, are acknowledged and followed. This report is prepared for **Aaron Atwood, owner, on Lot #38, Chaparral Hills Subdivision, 515 Struthers Loop, El Paso County, Colorado**. This report is prepared with the understanding that a single-family residence is planned for this site. The site does not have existing structures.

## CONCLUSIONS

**Additional drainage will be required during construction due to the high moisture content. If the bottom of the excavation becomes unstable, the use of 1' to 2' of 4" to 8" ballast rock will be required.**

A satisfactory foundation for this structure is a properly designed shallow foundation system consisting of foundation components resting directly on over-excavated and replaced materials. This over-excavation and replaced materials scheme is necessary due to the low expansive on-site material. This over-excavation and replaced materials scheme will reduce, but not eliminate the potential for movement with moisture fluctuations in the unstable subgrade soils. Since those materials will remain in-place beneath the fill, a potential remains that moisture changes in these deeper unstable materials will cause some movement in the overlying fill and structure. **Vertical slab movement of up to three inches should be expected of soils of low expansion potential and for compacted structural fill after the removal of the expansive soils. In some cases, vertical movement may exceed this range. If movement and associated damage to basement floors and finishes cannot be tolerated, a structural floor system shall be installed.** This material has a swell potential of approximately **1.7% expansion potential with a dead load of 3,700 pounds per square foot (ASTM D-4546)**. **The over-excavated area shall extend to a minimum depth of 4 feet below the bottom of the foundation elevation and 4 feet laterally from the location of the foundation walls.** The material to be compacted in the excavation shall meet or exceed CDOT Class 5 or Class 6 Road Base per CDOT 2019 Standard Specifications Table 703-2. This material shall be compacted to a minimum of 95% of its Modified Proctor density (**ASTM D-1557**). **Modified Proctor testing (additional cost) will be required on a sample of the replacement material to be used for this over-excavation scheme. Two 5-gallon valid samples of the soil to be used, must be provided for testing (unless a previous proctor test can be provided) at least 2 weeks prior to the placement and compaction of the material.** The compressibility of the over-excavated and replaced material shall be taken to be low. A maximum allowable bearing capacity for the over-excavated and replaced material is a presumptive value of **1,500 pounds per square foot**. This bearing capacity is calculated with a safety factor of three. The type of foundation configuration used depends on the building loads applied. The depth of foundation elements shall be determined by the foundation engineer but should be at least as deep as the minimum depth required by the governing building authority. **The laboratory testing revealed that the on-site soil is silty sand with underlying low-plasticity clay (U.S.C.S. Classification Symbol SM, CL). The unit weight of equivalent fluid soil pressure of this material is 45 (SM) and 100 (CL) pounds per cubic foot. The native CL is not suitable and shall not be used as backfill material around the perimeter of the foundation.** The actual equivalent fluid soil pressure was not determined. The expected values are from ASCE 7-10, Table 3.2-1. **Foundation components should bear on soils of similar bearing capacity. Foundation components bearing on dissimilar soils should be avoided. The owners shall be made aware that movement will definitely occur if surface or subsurface water is allowed to collect around the foundation or in the over-excavated area.**

## GENERAL

The investigation was made to reveal important characteristics of the soils and of the site influencing the foundation design. Also evaluated during the investigation were subsurface conditions which affect the depth of the foundation and subsequent loading design, such as ground water levels, soil types, and other factors which affect the bearing capacity of the soils. Design loadings are based on soils characteristics and represent the maximum permissible loads for these conditions. The bearing capacity is calculated with a safety factor of three.

## FIELD AND LABORATORY INVESTIGATION

Two exploratory holes were drilled on July 5, 2021, at the locations shown on the enclosed site map. The location of these test holes was determined by Aaron Atwood. The test holes were drilled with a 3-inch diameter auger. At intervals anticipated to be the foundation depths, and as determined by the soils conditions, the drill tools were removed, and samples were taken by the use of a 2 inch "split barrel" sampler connected to a 140-pound drop-hammer. This hammer is dropped 30 inches to drive the penetration sampler into the soil (**ASTM D-1586**). The depths and descriptions of the materials encountered in each test boring at which the samples were taken are shown on the enclosed log sheets. All samples were classified both in the field and in the laboratory to evaluate the physical and mechanical properties of the materials encountered.

## TOPOGRAPHY

The topography of this site is that of an incline sloping down towards the west at 5%.

## WEATHER

The weather at the time of the soil examination consisted of clear skies with hot temperatures.

## DESIGN AND CONSTRUCTION CONSIDERATIONS

Slabs-on-grade may move and crack. Vertical slab movement of up to three inches should be expected for soils of low expansion potential and for compacted structural fill after removal of expansive soils. In some cases, vertical movement may exceed this range. If movement and associated damage to basement floors and finishes cannot be tolerated, a structural floor system shall be installed. The native materials encountered during the exploratory testing are not suitable for the support of residential construction. If compaction is not performed, settlement may occur causing cracking of foundation walls and floors. Personnel of Geoquest, LLC shall inspect the base of the over-excavation prior to any placement of any fill materials. All backfill material and over excavated and replaced material shall be properly tested by Geoquest, LLC at the time of installation of said material. Soil located beneath concrete walls shall be compacted to at least 95% Modified Proctor density (**ASTM D-1557**). Soil located beneath concrete slabs shall be compacted to at least 85% Modified Proctor density. Special care is to be taken to re-compact the material above utility lines to a minimum of 85% Modified Proctor density. During construction, conditions that could cause settlement shall be eliminated. Interior non-bearing partition walls shall be constructed such that they do not transmit floor slab movement to the roof or overlying floor. The gap or void (1.5-inch min.) installed in these non-bearing partitions may require re-construction over the life of the structure to re-establish the gap or void to allow for vertical slab movement. Stairwells, doorways, and sheeted walls should be designed for this movement.

The following are general recommendations of on-grade slabs:

1. Slabs shall be placed on a minimum of three feet of road base material and be tested to meet Modified Proctor density of 85%. All loose or soft spots shall be thoroughly excavated and replaced with non-expansive soil. **Up to 3 inches of movement of the slabs and exterior concrete can be expected.**
2. Slabs shall be separated from all foundation walls, load bearing members, and utility lines.
3. At intervals not to exceed 12 feet in each direction, provide control joints to reduce problems with shrinkage and curling as recommended by the American Concrete Institute (**ACI 360R-10**). Moisten the ground beneath the slab prior to the placement of concrete.

4. All concrete placed must be cured properly as recommended by the American Concrete Institute (**ACI 360R-10**). Separate load bearing members from slabs, as discussed above. Care must be exercised to prevent excess moisture from entering the soil under the structure, both during and after construction.
5. Due to the exposure of exterior concrete to variations in moisture fluctuations, heaving and cracking of exterior slabs-on-grade should be expected. Placement of at least 3 feet of non-expansive fill beneath the slabs can help to reduce the impact of differential movement and cracking but may not eliminate movement. Exterior concrete shall slope away from the structure a minimum of 2% grade.
6. **The low-plasticity clay (CL) has been tested for its expansion and/or consolidation potential. This material has a 1.7% expansion potential with a dead load of 3,700 pounds per square foot.** Basement slabs, garage slabs, and all concrete floor slabs, exert a very low dead-load pressure on the soil. Since this soil contains a small amount of swell potential, slabs will crack and heave or settle if excess water is allowed to penetrate the subgrade. For example, column openings to pads below the placed slab, if exposed to precipitation during construction, will conduct water to the subgrade, possibly causing it to expand. Also, if the slab is placed with concrete too wet, expansion may occur. We recommend 3,000 psi concrete placed at a maximum slump of 4 inches.

#### **RECOMMENDATION REMARKS**

The recommendations provided in this report are based upon the observed soil parameters, anticipated foundation loads and accepted engineering procedures. The recommendations are intended to minimize differential movement resulting from the heaving of expansive soil or from the settlement induced by the application of loads. **It must be recognized that the foundation will undergo some movement on all soil types.** In addition, concrete floor slabs will move vertically, therefore, adherence to those recommendations which isolate floor slabs from columns, walls, partitions or other structural components is extremely important, if damage to the superstructure is to be minimized. Any subsequent owners should be apprised of the soil conditions and advised to maintain good practice in the future with regard to surface and subsurface drainage and partition framing, drywall and finish work above floor slabs.

Geoquest, LLC does not assure that the contractor and/or homeowner will comply with the recommendations provided in this report. Geoquest, LLC provides recommendations only and does not supervise, direct or control the implementation of the recommendations.

**Failure to follow the recommendation provided by Geoquest, LLC and follow observation requirements may jeopardize the construction project and Geoquest, LLC shall be absolved from any and all responsibility for any damages arising from the failure to obtain proper site observation and follow recommendations.**

#### **COLD TEMPERATURE CONSIDERATIONS**

1. Concrete shall not be placed upon wet or frozen soil.
2. Concrete shall be protected from freezing until it has been allowed to cure for at least 7 days after placement in forms.
3. Snow or other frozen water shall not be allowed in the forms during placement of concrete.
4. Concrete shall be cured in forms for at least 72 hours.
5. Concrete shall be vibrated or rodded in forms to avoid segregation and cold joints.
6. The site shall be kept well drained at all times. Ponding of water should be avoided in the excavation area.

## **SURFACE DRAINAGE**

After construction of foundation walls, the backfill material shall be well compacted to 80% Modified Proctor density, to reduce future settlement. Any areas that settle after construction shall be filled to eliminate ponding of water adjacent to the foundation walls. **The finished grade shall have a positive slope away from the structure with an initial slope of 6 inch in the first 10 feet.** If a 10 foot zone is not possible on the upslope side of the structure, then a well-defined swale should be created a minimum of 5 feet from the foundation and sloped parallel with the wall at a 2% grade to intercept the surface water and carry it around and away from the structure. Homeowners shall maintain the surface grading and drainage installed by the builder to prevent water from being directed in the wrong direction. All downspouts shall have extensions that will remove runoff to the outside of the backfilled areas. Shrubs and plants requiring minimal watering shall be established in this area. Irrigated grass shall not be located within 5 feet of the foundation. Sprinklers shall not discharge water within 5 feet of the foundation. Irrigation should be limited to the minimum amount sufficient to maintain vegetation. Application of more water will increase the likelihood of floor slab and foundation movement.

All exterior grading and location of downspouts and their performance shall be inspected by Geoquest, LLC. **The native low-plasticity clay (CL) material is not suitable and shall not be used as backfill material around the perimeter of the foundation.** If on-site soils are not suitable for the backfill, the backfill material shall consist of clean non-cohesive granular soils or road base material as described previously. Imported material is to be approved by Geoquest, LLC prior to placement. **We recommend imported granular backfill with a maximum unit weight of 45 pounds per cubic foot.** It is the responsibility of the contractor to schedule all inspections.

## **SUBSURFACE DRAINAGE**

Perimeter drains are required around all walls of the habitable or usable area portion of the structure that are below finished grade including all common wall(s) adjacent to the basement. Crawlspace are considered usable area. Walkout areas need not be drained unless specified at the time of the Open Hole Observation. The final determination of the necessity for perimeter drains will be made at the time of the Open Hole Observation. An Exterior Drain Detail is provided in this report. Drains should daylight away from the structure or discharge to a sump pump.

## **REINFORCING**

The concrete foundation walls shall be properly reinforced as per the specific design for this foundation by a **Colorado Registered Professional Engineer. Exact requirements are a function of the design of the structure. Questions concerning the specific design requirements shall be referred to the design engineer.**

## **FOOTING DESIGN**

The design for footings, pads, and/or piers for this structure is determined by applying the dead load and full live load to the foundation walls.

## **CONSTRUCTION DETAILS**

It is necessary with any soils investigation to assume that the materials from the test holes are representative of the materials in the area. On occasion variations in the subsurface materials do occur, therefore, should such variations become apparent during construction, the owner is advised to contact this office for a determination as to whether these variations will affect the design of the structure's foundation. If anomalies are observed during the excavation for the structure, this office should be contacted to determine whether this may adversely affect the design.

## MINIMUM MATERIALS SPECIFICATIONS

1. Minimum materials specifications of the concrete, reinforcing, etc., shall be determined by the Professional Foundation Design Engineer.
2. Compact beneath foundation walls a minimum of 95% Modified Proctor density to prevent settlement.
3. Compact all backfill material located around the perimeter of the foundation to 80% Modified Proctor density.
4. Concrete shall be vibrated or rodded in forms to avoid segregation and cold joints.
5. The site shall be kept well drained at all times.

## OPEN HOLE OBSERVATION (added cost)

**If anyone other than Geoquest, LLC performs the Open Hole Observation and/or compaction testing, that person/company assumes liability for the soils, and any possible changes to the foundation design.**

The owner, or a representative of the construction company shall contact **Geoquest, LLC** a minimum of **24 hours** prior to excavating for the foundation. An Open Hole Observation must be performed on each individual structure prior to the placement of concrete, and preferably prior to the placement of forms in the excavated area. **The failure to request or obtain an Open Hole Observation prior to the placement of foundation components may result in this Soils Report being declared null and void.** This is to ensure that soft areas, anomalies, etc., are not present in the foundation region. At the time of the open hole observation the **foundation type recommendations, maximum allowable bearing capacity may be revised** according to soil conditions found at that time. If revisions are made to the Soils Report due to the soil conditions of the excavation, **the Foundation Design Engineer must be notified of all revisions.**

## COMPACTION TESTING (added cost)

Geoquest, LLC shall perform compaction testing on the replaced material. Soil shall be compacted in maximum 6-inch lifts. Testing shall be performed at intervals not to exceed 24 inches (or as required by the design engineer). Modified Proctor Density must be provided to Geoquest, LLC prior to compaction testing, see below.

The owner, or a representative of the construction, shall contact Geoquest, LLC a **minimum of 24 hours prior to the time the compaction test is requested. The failure to properly compact and/or obtain proper compaction testing may result in this Soils Report being declared null and void.**

## MODIFIED PROCTOR DENSITY TESTING (added cost)

**Modified Proctor Density test must be provided to Geoquest, LLC prior to compaction testing.** If a Proctor cannot be provided, a Modified Proctor Density test must be completed prior to compaction testing. Two 5-gallon valid samples of the soil to be used, must be provided for testing, at least 2 weeks prior to the placement and compaction of the material.

**The failure to provide this data may result in this Soils Report being declared null and void.**

## FINAL OBSERVATIONS (added cost)

The owner, or a representative of the construction company, shall contact Geoquest, LLC at the time final grading and landscaping procedures are completed. This is to ensure that sprinkler systems are not installed adjacent to the structure and that only shrubs or plants that require minimal watering are established in this area. All exterior grading as well as the location of downspouts and their performance shall be inspected by Geoquest, LLC. Any additional landscaping or grading changes performed by subsequent contractors and/or owners shall be inspected and approved. It is the responsible of the contractor and/or owner to schedule all these inspections at the appropriate times. **The failure to obtain this inspection may result in this Soils Report being declared null and void.**

## LIMITATIONS

This report is issued based on the understanding that the owner or his representative will bring the information, data, and recommendations contained in this report to the attention of the project engineer and architect, in order that they may be incorporated into the plans for the structure. It is also the owner's responsibility to ensure that all contractors and sub-contractors carry out these recommendations during the construction phase.

This report was prepared in accordance with generally accepted professional geotechnical/engineering methods. However, Geoquest, LLC makes no other warranty, express or implied, as to the findings, data, specifications, or professional advice rendered hereunder. **Due to circumstances outside of Geoquest, LLC's control, including improper construction, failure to follow recommendations, and unforeseen events, the Limits of Liability extend only to fees rendered for the professional services provided.**

This report is considered valid as of the present date. The owner acknowledges, however, that changes in the conditions of the property might occur with the passage of time, such as those caused by natural effects or man-made changes, both on this land and on abutting properties. Further, changes in acceptable tolerances or standards might arise as the result of new legislative actions, new engineering advances, or the broadening of geotechnical knowledge. Thus, certain developments beyond our control may invalidate this report, in whole or in part.

This report and its recommendations do not apply to any other site than the one described herein and are predicated on the assumption that the soil conditions do not deviate from those described. In the event that any variations or undesirable conditions should be detected during the construction phase or if the proposed construction varies from that planned as of this report date, the owner shall immediately notify Geoquest, LLC in order that supplemental recommendations can be provided, if so required.

This report excludes possible environmental issues, geologic hazards, flooding, or any other natural or man-made hazards that affect this site. These are outside the scope of work, for this report.

## APPENDIX



# DRILL LOGS


JOB #: 21-0795	DEPTH (in ft.)	SYMBOL	SAMPLES	BLOW COUNT	WATER %	SOIL TYPE
TEST BORING NO.: TH-1						
DATE: 7/5/2021						
<u>0"-6" Topsoil</u>	0-2	X				
<u>6"-5' Sand</u>	2-6					
Fine-coarse grained Very low density Low moisture content Low-moderate clay content Low-moderate plasticity Light Brown color	2					
	4			8 12"	3.3	
<u>5'- 15' Clay (CL)</u>	6-15					
Fine-medium grained Moderate density High moisture content Low-moderate sand content Moderate-high plasticity Brownish Grey color	8					
	10					
	12			25 12"	22.6	CL
	14					
	16					
	18					
	20					

JOB #: 21-0795	DEPTH (in ft.)	SYMBOL	SAMPLES	BLOW COUNT	WATER %	SOIL TYPE
TEST BORING NO.: TH-2						
DATE: 7/5/2021						
<u>0"-6" Topsoil</u>	0-2	X				
<u>6"-5' Sand (SM)</u>	2-6					
Fine-coarse grained Low density Low-moderate moisture content Low-moderate clay content Low-moderate plasticity Light Brown color	2					
	4			12 12"	6.5	SM
<u>5'- 15' Clay</u>	6-15					
Fine-medium grained Moderate density Moderate moisture content Low-moderate sand content Moderate-high plasticity Brownish Grey color	8					
	10					
	12					
	14			22 12"	11.8	
	16					
	18					
	20					

GEOQUEST LLC


**SITE MAP**

Lot 38  
Chaparral Hills  
515 Struthers Loop  
El Paso County  
Colorado  
Job #21-0795



0 50 100 150 200  
GRAPHIC SCALE IN FEET  
SCALE: 1" = 200'

# GEOQUEST LLC GRADATION TEST RESULTS



CLAY TO SILT	SAND	GRAVEL	
	FINE    MEDIUM    COARSE	FINE    COARSE	COBBLES

**CLASSIFICATION** CL

GRAVEL 7.6 %

SAND 40.9 %

FINES 51.5 %


NOTES: 22.6 % Moisture Content

LL = 38.5

PL = 24.1

PI = 14.4

SAMPLE # 1 HOLE # TH-1 DEPTH 12 FEET



CLAY TO SILT	SAND	GRAVEL	
	FINE    MEDIUM    COARSE	FINE    COARSE	COBBLES

**CLASSIFICATION** SM

GRAVEL 0.6 %

SAND 71.4 %

FINES 28.0 %


NOTES: 6.5 % Moisture Content

SAMPLE # 1 HOLE # TH-2 DEPTH 4 FEET

Job #: 21-0795 By: MJ 7/5/2021


GEOQUEST LLC  
SWELL-CONSOLIDATION TEST RESULTS

Job 21-0795 Soil Symbol: CL  
TH-1, 12' depth  
22.6 % native moisture  
24.7 % post test moisture  
1.7 % Expansion potential  
3700 psf force - Deadload





# EXTERIOR DRAIN DETAIL



1. Gravel to be Not More Than 1-1/2" and Not Less Than 1/2" Diameter.
2. Perforated Pipe Diameter Varies With Expected Seepage. 3"Ø and 4"Ø are Most Common. ABS and PVC are Most Common Materials for Pipe. We approve the use of an "EZ Flow Drainage System" by Infiltrator. All specifications in this drain detail are still applicable.
3. Pipe to be Laid out in a Minimum Slope of 1" in 10'.
4. Gravity Outfall is Desired if Possible. Portion of Pipe in Area Not Drained Shall be Non-Perforated. Daylight Must be Maintained Clear of Debris in Order to Function Properly.
5. If Gravity Outfall is Not Possible, Provide a Sump With Operational Pump. Pump May Not Connect to Any Sanitary or Storm Sewer.
6. Soil Backfill Should be Compacted to at Least 80% of the Modified Proctor Density in the Upper Three Feet of Fill.
7. Filter Fabric to be Mirafi 140s or Approved Equivalent. Roofing Felt and Sheet Plastic are Not Acceptable.
8. Drain Pipe Shall be Laid Below Protected Area, as Shown in The Detail Above.
9. Mop Polyethylene Film to Wall Approximately One Foot Above Joint of Footing and Wall (Do Not Pull Plastic Tight) and Carry Beneath Gravel and Pipe.
10. The Polyethylene Film Shall be Continued to the Edge of the Excavation.