



El Paso County MS4 Post Construction Detention / Water Quality Facility Documentation Form

This document **must be completed and submitted** with required attachments to the County for projects requiring a detention and/or a water quality facility. A separate completed form must be submitted for each facility.

Project name:

Owner name:

Location Address:

Latitude and Longitude:

Assessor's Parcel #: Section: Township: Range:

Expected Completion date:

Project acreage: Design Ponding Acres: Design Storm:

Design Engineer Email Address:

To ensure compliance with C.R.S. 37-92-602(8), the completed Stormwater Detention and Infiltration Design Data Sheet **must be attached**. The form can be found here: <https://maperture.digitaldataservices.com/gvh/?viewer=cswdif#> (click on Download SDI Design Data Sheet)

List all permanent water quality control measure(s) (EDBs, rain gardens, etc):

For all projects for which the constrained redevelopment sites standard is applied, provide an explanation of why it is not practicable to meet the full design standards.

Attach Operations and Maintenance (O&M) Plan describing the operation and maintenance procedures that ensure the long-term observation, maintenance, and operation of control measure(s), including routine inspection frequencies and maintenance activities. If multiple, different water quality control measures are used at the same location, a separate O & M Plan must be provided for each facility.

Attach Private Detention Basin / Stormwater Quality Best Management Practice Maintenance Agreement and Easement addressing maintenance of BMPs that shall be binding on all subsequent owners of the permanent BMPs.

Attachments:

Stormwater Detention and Infiltration Design Data Sheet
O & M Plan
Maintenance and Access Agreement

Review Engineer

EPC Project File No.

Stormwater Detention and Infiltration Design Data Sheet

Worksheet Protected

Stormwater Facility Name:

Facility Location & Jurisdiction:

User (Input) Watershed Characteristics

Watershed Slope =	0.020	ft/ft
Watershed Length-to-Width Ratio =	2.00	L:W
Watershed Area =	64.00	acres
Watershed Imperviousness =	13.0%	percent
percentage Hydrologic Soil Group A =	0.0%	percent
percentage Hydrologic Soil Group B =	100.0%	percent
percentage Hydrologic Soil Groups C/D =	0.0%	percent

User Input: Detention Basin Characteristics

WOCV Design Drain Time = 40.00 hours

[illegible]

After completing and printing this worksheet to a pdf, go to:
<https://maperture.digitaldataservices.com/gvh/?viewer=cswidf>
 create a new stormwater facility, and
 attach the pdf of this worksheet to that record.

Routed Hydrograph Results

Design Storm Return Period =	WQCV	2 Year	5 Year	10 Year	25 Year	50 Year	100 Year	
One-Hour Rainfall Depth =	0.53	1.19	1.50	1.75	2.00	2.25	2.52	in
Calculated Runoff Volume =	0.439	0.584	1.633	2.797	4.883	6.389	8.159	acre-ft
OPTIONAL Override Runoff Volume =								acre-ft
Inflow Hydrograph Volume =	0.439	0.584	1.632	2.797	4.883	6.384	8.156	acre-ft
Time to Drain 97% of Inflow Volume =	41	48	49	44	38	34	30	hours
Time to Drain 99% of Inflow Volume =	45	52	56	53	49	47	45	hours
Maximum Ponding Depth =	3.16	3.62	5.14	5.74	6.68	7.15	7.38	ft
Maximum Poned Area =	0.283	0.321	0.444	0.492	0.572	0.615	0.637	acres
Maximum Volume Stored =	0.411	0.549	1.130	1.414	1.910	2.194	2.331	acre-ft

Stormwater Detention and Infiltration Design Data Sheet

