



Prevent • Promote • Protect

Environmental Health Division  
1675 W. Garden of the Gods Road  
Suite 2044  
Colorado Springs, CO 80907  
(719) 578-3199 *phone*  
(719) 578-3188 *fax*  
[www.elpasocountyhealth.org](http://www.elpasocountyhealth.org)

### **Retreat @ TimberRidge, Filing No. 2, SF-21-21**

**Please accept the following comments from El Paso County Public Health (EPCPH) regarding the project referenced above:**

- **The 78.8-acre filing with 90 residential lots in total will have water and wastewater services provided through by couple different sources. There are 78 lots with water and wastewater services provided by the Sterling Ranch Metropolitan District #1 (SRMD#1). The remaining 12 lots are 2.5-acre+ in area and will be supplied water with individual private wells and wastewater by onsite wastewater treatment systems (OWTS).**
- **There is a finding for sufficiency in terms of water quality for the water services to the 78 urban lots by SRMD#1. SRMD#1 is assigned PWSID #CO0121724 by the Colorado Department of Public Health and Environment, Water Quality Control Division.**
- **There is a finding for sufficiency in terms of water quality for drinking water for Filing No. 2 based on the acceptable water quality sample results tested the following laboratories in February and March of 2017:**
  - **Colorado Analytical Laboratories, Inc.**
  - **Hazen Research, Inc.**
  - **Energy Laboratories**
- **Sterling Ranch Metropolitan District No. 1 has also agreed to provide wastewater service to the 78 urban residential lots. The 04April2019, JDS Hydro Water Resources and Wastewater Report for Sterling Ranch Service Area, reports there is sufficient capacity for the treatment of wastewater for the 78 urban residential lots. SRMD#1 has provided a Letter of Commitment dated 01April2021, to provide both water and wastewater treatment to the 78 urban residential lots.**
- **The Entech Engineering, Inc., Soil, Geology and Geologic Hazard Study dated 26April2021 for the twelve 2.5+ acre lots was reviewed for determining the suitability of the site for OWTS installations. The report indicated no ground water was encountered in the soil profile test pit excavations, or in the percolation tests profile borings. However, the report did show the soil in the area does have a fluctuating level of bedrock known as the Dawson Formation. This formation is common throughout the northeastern part of El Paso County, and OWTS installations are possible with proper engineering. The area also has a few low areas where seasonal high groundwater should be avoided when possible. Professional engineer designs are likely to be needed for OWTS's in this area.**

- Radon resistant construction building techniques/practices are encouraged in this area. The EPA has determined that Colorado, and specifically the El Paso County area, have higher radon levels than other areas of the country.
- Earthmoving activities greater than 25 acres require a Construction Activity Permit from the Colorado Department of Public Health and Environment, Air Pollution Control Division. Go to:  
<https://www.colorado.gov/pacific/cdphe/general-air-permits>
- The water quality basins must have mosquito control responsibilities included as a part of the construction design and the Timber Ridge Metropolitan District maintenance plan to help control mosquito breeding habitat and minimize the potential for West Nile Virus.

**Mike McCarthy**  
El Paso County Public Health  
[mikemccarthy@elpasoco.com](mailto:mikemccarthy@elpasoco.com)  
719-575-8602  
20June2021