



# Statistics

Description	Symbol	Avg	Max	Min	Max/Min	Avg/Min
PARKING LOT	✖	2.2 fc	6.0 fc	0.5 fc	12.0:1	4.4:1
SITE	+	0.4 fc	10.3 fc	0.0 fc	N/A	N/A

Symbol	Label	Image	Quantity	Manufacturer	Catalog Number	Description	Number Lamps	Lumens Per Lamp	Light Loss Factor	Wattage	Plot
	A		7	Lithonia Lighting	WDGE2 LED P2 40K 80CRI T3M	WDGE2 LED WITH P2 - PERFORMANCE PACKAGE, 4000K, 80CRI, TYPE 3 MEDIUM OPTIC	1	2062	1	18,9815	 Max: 1512cd
	B		2	Lithonia Lighting	WDGE3 LED P4 70CRI R3 40K	WDGE3 LED WITH P4 - PERFORMANCE PACKAGE, 4000K, 70CRI, TYPE 3 OPTIC	1	12166	1	87,8914	 Max: 8439cd
	C		1	Lithonia Lighting	DSX1 LED P4 30K 80CRI T4M	D-Series Size 1 Area Luminaire P4 Performance Package 3000K CCT 80 CRI Type 4 Medium	1	14174	1	247.88	 Max: 11339cd
	D		4	Lithonia Lighting	DSX1 LED P4 30K 80CRI T4M	D-Series Size 1 Area Luminaire P4 Performance Package 3000K CCT 80 CRI Type 4 Medium	1	14174	1	123.94	 Max: 11339cd
	E		0	Lithonia Lighting	DSX1 LED P4 30K 80CRI T4M	D-Series Size 1 Area Luminaire P4 Performance Package 3000K CCT 80 CRI Type 4 Medium	1	14174	1	247.88	 Max: 11339cd



Plan View  
Scale - 1" = 40ft

Designer  
Date  
03/15/2023  
Scale  
Not to Scale  
Drawing No.  
Summary