

2019 Financial Assurance Estimate Form (with pre-plat construction)

Updated: 7/16/2019

PROJECT INFORMATION	
Gardens at North Carefree	8/27/2019
Project Name	Date
PCD File No. SF195	

Description	Quantity	Units	Unit Cost	Total	(with Pre-Plat Construction) % Complete	Remaining
SECTION 1 - GRADING AND EROSION CONTROL (Construction and Permanent BMPs)						
* Earthwork						
less than 1,000; \$5,300 min		CY	\$ 8.00	= \$ -		
1,000-5,000; \$8,000 min		CY	\$ 6.00	= \$ -		
5,001-20,000; \$30,000 min	7,400	CY	\$ 5.00	= \$ 37,000.00		\$ 37,000.00
20,001-50,000; \$100,000 min		CY	\$ 3.50	= \$ -		
50,001-200,000; \$175,000 min		CY	\$ 2.50	= \$ -		
greater than 200,000; \$500,000 min		CY	\$ 2.00	= \$ -		
* Permanent Seeding (inc. noxious weed mgmt.)	2	AC	\$ 800.00	= \$ 1,200.00		\$ 1,200.00
* Mulching	1	AC	\$ 750.00	= \$ 750.00		\$ 750.00
* Permanent Erosion Control Blanket		SY	\$ 6.00	= \$ -		
* Permanent Pond/BMP Construction	1,610	CY	\$ 20.00	= \$ 32,200.00		\$ 32,200.00
* Permanent Pond/BMP (Spillway)	2	EA	\$ 12,000.00	= \$ 24,000.00		\$ 24,000.00
* Permanent Pond/BMP (Outlet Structure)	2	EA	\$ 4,000.00	= \$ 8,000.00		\$ 8,000.00
Safety Fence	1,825	LF	\$ 3.00	= \$ 5,475.00		\$ 5,475.00
Temporary Erosion Control Blanket		SY	\$ 3.00	= \$ -		
Vehicle Tracking Control	2	EA	\$ 2,370.00	= \$ 4,740.00		\$ 4,740.00
Silt Fence	1,400	LF	\$ 2.50	= \$ 2,750.00		\$ 2,750.00
Temporary Seeding	3	AC	\$ 628.00	= \$ 1,570.00		\$ 1,570.00
Temporary Mulch	3	AC	\$ 750.00	= \$ 1,875.00		\$ 1,875.00
Erosion Basins	12	EA	\$ 25.00	= \$ 300.00		\$ 300.00
Erosion Logs/Straw Waddle		LF	\$ 5.00	= \$ -		
Rock Check Dams		EA	\$ 500.00	= \$ -		
Inlet Protection	9	EA	\$ 167.00	= \$ 1,503.00		\$ 1,503.00
Sediment Basin	2	EA	\$ 1,762.00	= \$ 3,524.00		\$ 3,524.00
Concrete Washout Basin	1	EA	\$ 900.00	= \$ 900.00		\$ 900.00
<i>Insert items not listed but part of construction plans!</i>						
MAINTENANCE (35% of Construction BMPs)				\$ 6,006.70		\$ 6,006.70
Section 1 Subtotal				\$ 131,793.70		\$ 131,793.70

* Subject to defect warranty financial assurance. A minimum of 20% shall be retained until final acceptance (MAXIMUM OF 80% COMPLETE ALLOWED)

Description	Quantity	Units	Unit Cost	Total	(with Pre-Plat Construction) % Complete	Remaining
SECTION 2 - PUBLIC IMPROVEMENTS *						
ROADWAY IMPROVEMENTS						
Construction Traffic Control	1	LS		= \$ -		
Aggregate Base Course (135 lbs/cf)	2,392	Tons	\$ 28.00	= \$ 66,976.00		\$ 66,976.00
Aggregate Base Course (135 lbs/cf)		CY	\$ 50.00	= \$ -		
Asphalt Pavement (3" thick)		SY	\$ 14.00	= \$ -		
Asphalt Pavement (4" thick)		SY	\$ 19.00	= \$ -		
Asphalt Pavement (6" thick)		SY	\$ 23.00	= \$ -		
Asphalt Pavement (147 lbs/cf) <u>4</u> " thick	1,815	Tons	\$ 88.00	= \$ 159,720.00		\$ 159,720.00
Raised Median, Paved		SF	\$ 8.00	= \$ -		
Regulatory Sign/Advisory Sign	4	EA	\$ 300.00	= \$ 1,200.00		\$ 1,200.00
Guide/Street Name Sign	4	EA	\$ -	= \$ -		
Epoxy Pavement Marking	1,500	SF	\$ 13.00	= \$ 19,500.00		\$ 19,500.00
Thermoplastic Pavement Marking		SF	\$ 23.00	= \$ -		
Barricade - Type 3		EA	\$ 200.00	= \$ -		
Deliminator - Type 1		EA	\$ 24.00	= \$ -		
Curb and Gutter, Type A (6" Vertical)	800	LF	\$ 30.00	= \$ 24,000.00		\$ 24,000.00
Curb and Gutter, Type B (Median)		LF	\$ 30.00	= \$ -		
Curb and Gutter, Type C (Ramp)	3,600	LF	\$ 30.00	= \$ 108,000.00		\$ 108,000.00
4" Sidewalk (common areas only)	100	SY	\$ 48.00	= \$ 4,800.00		\$ 4,800.00
5' Sidewalk	2,201	SY	\$ 60.00	= \$ 132,060.00		\$ 132,060.00
6' Sidewalk		SY	\$ 72.00	= \$ -		
8' Sidewalk		SY	\$ 96.00	= \$ -		
Pedestrian Ramp	8	EA	\$ 1,150.00	= \$ 9,200.00		\$ 9,200.00
Cross Pan, local (8" thick, 6' wide to include return)	24	LF	\$ 61.00	= \$ 1,464.00		\$ 1,464.00
Cross Pan, collector (9" thick, 8' wide to include return)	36	LF	\$ 92.00	= \$ 3,312.00		\$ 3,312.00
Curb Chase		EA	\$ 1,480.00	= \$ -		
Guardrail Type 3 (W-Beam)		LF	\$ 48.00	= \$ -		
Guardrail Type 7 (Concrete)		LF	\$ 72.00	= \$ -		
Guardrail End Anchorage		EA	\$ 2,088.00	= \$ -		
Guardrail Impact Attenuator		EA	\$ 3,787.00	= \$ -		
Sound Barrier Fence (CMU block, 6' high)		LF	\$ 78.00	= \$ -		
Sound Barrier Fence (panels, 6' high)		LF	\$ 80.00	= \$ -		
Electrical Conduit, Size =		LF	\$ 16.00	= \$ -		
Traffic Signal, complete intersection		EA	\$ 425,000	= \$ -		
Section 2 Subtotal				\$ 606,700.00		\$ 606,700.00
Section 1 Subtotal				\$ 131,793.70		\$ 131,793.70
provide the cost of this item.						

include parallel pedestrian ramps also There should be a total of 15 ramps

cross pan is shown on both fallow In and running deer. Revise length

The CD's indicate approx. 253' of 18" RCP. Revise

Description	Quantity	Units	Unit Cost	Total	% Complete	(with Pre-Plat Construction) Remaining
<i>Insert items not listed but part of construction plans</i>						
STORM DRAIN IMPROVEMENTS						
Concrete Box Culvert (M Standard), Size (W x H)						
18" Reinforced Concrete Pipe	180	LF	\$ 65.00	\$ 11,700.00		\$ 11,700.00
24" Reinforced Concrete Pipe	28	LF	\$ 78.00	\$ 2,184.00		\$ 2,184.00
30" Reinforced Concrete Pipe	150	LF	\$ 97.00	\$ 14,550.00		\$ 14,550.00
36" Reinforced Concrete Pipe	23	LF	\$ 120.00	\$ 2,760.00		\$ 2,760.00
42" Reinforced Concrete Pipe	35	LF	\$ 160.00	\$ 5,600.00		\$ 5,600.00
48" Reinforced Concrete Pipe		LF	\$ 195.00			
54" Reinforced Concrete Pipe		LF	\$ 245.00			
60" Reinforced Concrete Pipe		LF	\$ 288.00			
66" Reinforced Concrete Pipe		LF	\$ 332.00			
72" Reinforced Concrete Pipe		LF	\$ 380.00			
18" Corrugated Steel Pipe		LF	\$ 84.00			
24" Corrugated Steel Pipe		LF	\$ 96.00			
30" Corrugated Steel Pipe		LF	\$ 122.00			
36" Corrugated Steel Pipe		LF	\$ 147.00			
42" Corrugated Steel Pipe		LF	\$ 168.00			
48" Corrugated Steel Pipe		LF	\$ 178.00			
54" Corrugated Steel Pipe		LF	\$ 260.00			
60" Corrugated Steel Pipe		LF	\$ 280.00			
66" Corrugated Steel Pipe		LF	\$ 340.00			
72" Corrugated Steel Pipe		LF	\$ 400.00			
78" Corrugated Steel Pipe		LF	\$ 460.00			
84" Corrugated Steel Pipe		LF	\$ 560.00			
Flared End Section (FES) RCP Size = 36" / 42"	2	EA	\$ 1,120.00	\$ 2,240.00		\$ 2,240.00
<small>(unit cost = 6x pipe unit cost)</small>						
Flared End Section (FES) CSP Size =						
<small>(unit cost = 6x pipe unit cost)</small>						
End Treatment- Headwall		EA				
End Treatment- Wingwall		EA				
End Treatment - Cutoff Wall		EA				
Curb Inlet (Type R) L=5', Depth < 5'	1	EA	\$ 5,542.00	\$ 5,542.00		\$ 5,542.00
Curb Inlet (Type R) L=5', 5' ≤ Depth < 10'		EA	\$ 1,188.00			
Curb Inlet (Type R) L=5', 10' ≤ Depth < 15'		EA	\$ 8,345.00			
Curb Inlet (Type R) L=10', Depth < 5'		EA	\$ 7,627.00			
Curb Inlet (Type R) L=10', 5' ≤ Depth < 10'	1	EA	\$ 7,861.00	\$ 7,861.00		\$ 7,861.00
Curb Inlet (Type R) L=10', 10' ≤ Depth < 15'		EA	\$ 9,841.00			
Curb Inlet (Type R) L=15', Depth < 5'		EA	\$ 9,918.00			
Curb Inlet (Type R) L=15', 5' ≤ Depth < 10'		EA	\$ 10,633.00			
Curb Inlet (Type R) L=15', 10' ≤ Depth < 15'		EA	\$ 11,627.00			
Curb Inlet (Type R) L=20', Depth < 5'		EA	\$ 10,570.00			
Curb Inlet (Type R) L=20', 5' ≤ Depth < 10'	4	EA	\$ 11,667.00	\$ 46,668.00		\$ 46,668.00
Curb Inlet (Type R) L=20', 10' ≤ Depth < 15'		EA	\$ 4,640.00			
Grated Inlet (Type C), Depth < 5'		EA	\$ 5,731.00			
Grated Inlet (Type D), Depth < 5'		EA	\$ 11,627.00			
Storm Sewer Manhole, Box Base		EA				
Storm Sewer Manhole, Slab Base		EA				
Geotextile (Erosion Control)		SY	\$ 6.00	\$ 6,395.00		\$ 6,395.00
Rip Rap, d50 size from 6" to 24"	20	Tons	\$ 80.00	\$ 1,600.00		\$ 1,600.00
Rip Rap, Grouded		Tons	\$ 95.00			
Drainage Channel Construction, Size (W x H)						
Drainage Channel Lining, Concrete	22	LF	\$ 570.00	\$ 12,540.00		\$ 12,540.00
Drainage Channel Lining, Rip Rap		CY	\$ 112.00			
Drainage Channel Lining, Grass		AC	\$ 1,468.00			
Drainage Channel Lining, Other Stabilization						
Section 2 Subtotal				\$ 649,872.00		\$ 649,872.00

Revise. It does not match the CD's and drainage report

There are 2 manholes

Insert items not listed but part of construction plans
 * - Subject to defect warranty financial assurance. A minimum of 20% shall be retained until final acceptance (MAXIMUM OF 80% COMPLETE ALLOWED)

PROJECT INFORMATION

Gardens at North Carefree
 Project Name

8/27/2019
 Date

SF195
 PCD File No.

Description	Quantity	Units	Unit Cost	Total	(with Pre-Plat Construction)	
					% Complete	Remaining

AS-BUILT PLANS (Public Improvements inc. Permanent WQCV BMPs)	LS		\$ 2,000.00	= \$ 2,000.00		\$ 2,000.00
POND/BMP CERTIFICATION (inc. elevations and volume calculations)	LS		\$ 1,500.00	= \$ 1,500.00		\$ 1,500.00

Total Construction Financial Assurance \$ 1,346,175.70
 (Sum of all section subtotals plus as-builts and pond/BMP certification)


Total Remaining Construction Financial Assurance (with Pre-Plat Construction) \$ 1,346,175.70
 (Sum of all section totals less credit for items complete plus as-builts and pond/BMP certification)

Total Defect Warranty Financial Assurance \$ 150,604.40
 (20% of all items identified as (*). To be collateralized at time of preliminary acceptance)

Approvals

I hereby certify that this is an accurate and complete representation of the information shown on the Grading and Erosion Control Plan and Construction Drawings associated with the Project.

Charles K. Cothran
 Engineer (P.E. Seal Required)
Mule Deer Investments
 Approved by Owner / Applicant




8/28/2019
 Date

Approved by El Paso County Engineer / ECM Administrator

Date


Markup Summary

Daniel Torres (6)




Subject: Callout
Page Label: 1
Author: Daniel Torres
Date: 9/25/2019 12:08:03 PM
Color: ■

provide the cost of this item.




Subject: Callout
Page Label: 1
Author: Daniel Torres
Date: 9/29/2019 2:21:53 PM
Color: ■

include parallel pedestrian ramps also. There should be a total of 15 ramps




Subject: Callout
Page Label: 1
Author: Daniel Torres
Date: 9/29/2019 2:40:03 PM
Color: ■

cross pan is shown on both fallow In and running deer. Revise length




Subject: Callout
Page Label: 2
Author: Daniel Torres
Date: 9/29/2019 2:47:33 PM
Color: ■

The CD's indicate approx. 253' of 18"RCP. Revise



Subject: Cloud+
Page Label: 2
Author: Daniel Torres
Date: 9/29/2019 2:51:15 PM
Color: ■

Revise. It does not match the CD's and drainage report



Subject: Callout
Page Label: 2
Author: Daniel Torres
Date: 9/29/2019 2:51:50 PM
Color: ■

There are 2 manholes