



**Planning and Community  
Development Department**  
2880 International Circle  
Colorado Springs, Colorado 80910  
Phone: 719.520.6300  
Fax: 719.520.6695  
Website: www.elpasoco.com

**DEVIATION REQUEST  
AND DECISION FORM**  
(Judge Orr Deviation)  
Updated: 6/26/2019

**PROJECT INFORMATION**

Project Name : Monument Ridge East  
Schedule No.(s) : 7102200013, 7102200006, 7102200010  
Legal Description : TRACT OF LAND IN N2 SEC 02-11-67 DESC AS FOLS, COM AT NE COR OF SD SEC, TH S 89<06'54" W 1320.00 FT, S 00<53'12" W 30.00 FT FOR POB, TH S 89<06'54" W 1834.51 FT TO PT ON ELY R/W LN OF I25, TH ALG SD R/W S 29<33'00" W 180.19 FT, S 89<05'00" W 500.00 FT, S 29<16'30" W 675.30 FT, S 06<43'00" W 36.92 FT, S 89<57'36" E 251.71 FT, S 06<43'00" W 337.98 FT, S 89<57'36" E 732.00 FT, TH N 14<12'38" E 887.45 FT, N 89<06'34" E 500.0 FT M/L, N 00<02'24" W 270.0 FT, S 89<06'54" W 650.0 FT M/L TO POB, EX PT DES AS FOLS: TR OF LAND IN NW4 SEC 2-11-67 DES AS FOLS: COM AT NE COR OF SD SEC 2, TH S 89<06'54" W ALG N LN OF SEC 2 A DIST OF 2879.42 FT, TH ON A DEFLECTION ANGLE TO THE L OF 90<00'00" 50.00 FT TO A PT 20.00 FT S OF EXISTING SLY R/W LN OF COUNTY LINE RD FOR POB, TH N 89<06'54" E 105.00 FT, S 13<48'06" W 130.00 FT, S 89<06'54" W 175.76 FT SLY OF S R/W LN OF SD RD A DIST OF 105.00 FT, N 13<48'06" E 130.00 FT TO POB, EX THAT PT CONV BY REC #210120918, EX THAT PT TO COUNTY CONV BY REC #214002145.  
TRACT OF LAND IN N2 SEC 02-11-67 DESC AS FOLS, COM AT NE COR OF SD SEC, TH S 89<06'54" W 1320.00 FT, S 00<53'12" W 30.00 FT, S 00<53'12" E 270.01 FT, S 89<06'34" W 1599.97 FT, S 14<12'38" W 887.45 FT FOR POB, TH CONT S 14<12'38" W 102.63 FT, S 86<45'14" W 350.00 FT, S 00<24'09" W 236.98 FT, N 89<57'36" W 649.40 FT TO A PT ON ELY R/W LN OF I25, TH N 06<43'00" E 696.96 FT, S 89<57'36" E 251.71 FT, S 06<43'00" W 337.98 FT, S 89<57'36" E 732.00 FT TO POB.  
THAT PART OF S2N2 LY ELY OF INTERSTATE 25 + WLY OF WOODCREST, NLY 15.00 AC M/L OF E2SW4 SEC 2-11-67, EX THAT PT CONV TO PLAT 12181 MISTY ACRES SUB FIL NO 1, EX THAT PT CONV TO PLAT 12182 MISTY ACRES SUB FIL NO 2

**APPLICANT INFORMATION**

Company : Monument Ridge East, LLC  
Name : Maria Larsen  
 Owner  Consultant  Contractor  
Mailing Address : 5050 List Drive  
Colorado Springs, CO 80919  
Phone Number : 719-291-2472  
Fax Number : N/A  
Email Address : nbt.nml@gmail.com

**ENGINEER INFORMATION**

Company : LSC Transportation Consultants, Inc.  
Name : Jeffrey C. Hodsdon Colorado P.E. Number : 31684  
Mailing Address : 2504 E. Pikes Peak Ave, Suite 304  
Colorado Springs, CO 80909  
Phone Number : 719-633-2868  
FAX Number : 719-633-5430  
Email Address : jeff@LSCtrans.com

OWNER, APPLICANT, AND ENGINEER DECLARATION

To the best of my knowledge, the information on this application and all additional or supplemental documentation is true, factual and complete. I am fully aware that any misrepresentation of any information on this application may be grounds for denial. I have familiarized myself with the rules, regulations and procedures with respect to preparing and filing this application. I also understand that an incorrect submittal will be cause to have the project removed from the agenda of the Planning Commission, Board of County Commissioners and/or Board of Adjustment or delay review until corrections are made, and that any approval of this application is based on the representations made in the application and may be revoked on any breach of representation or condition(s) of approval.

*Maana Larsen*  
Signature of owner (or authorized representative)

*11/11/2024*  
Date

Engineer's Seal, Signature  
And Date of Signature



**DEVIATION REQUEST** (Attach diagrams, figures, and other documentation to clarify request)

**Deviation No. 1** (Rev. 10-4-2024) A deviation from the standards of or in Sections 2.2.5.D. **2.3.2 and 2.3.7.B. Collector Access Standards** of the Engineering Criteria Manual (ECM) is requested.

Deviation request is to allow the proposed north access point location: Milky Way View to the planned extension of Misty Acres Boulevard. This deviation involves the intersection spacing of Milky Way View 395 feet to the north to the future County Line Road/Misty Acres Boulevard intersection.

Please refer to the attached Deviation Exhibits 1 and 2.

Identify the specific ECM standard which a deviation is requested:

**2.2.5.D. Collector Access Standards.** Collector roadways shall intersect another roadway (centerline to centerline) in accordance with the standards in Section 2.3.7. **On major collector roadways, the closest local roadway intersection to an arterial roadway shall be 660 feet (right-of-way line of arterial to centerline of local roadway).**

**2.3.2 (Design Standards by Function Classification),**  
Table 2-7. Roadway Design Standards for Urban Collectors and Locals  
Table 2-21. Entering Sight Distance

**2.3.7. Intersections:**  
B. Intersection Spacing and General Access Standards

Spacing of roads accessing an Urban Non-Residential Collector that will result in a full-movement intersection shall be 330 feet. The 330-foot standard is reflected in ECM Table 2-7, which bases the required access spacing on stopping sight distance on the major roadway with a design speed of 40 mph (ECM Table 2-17).

State the reason for the requested deviation:

The deviation is requested as the proposed intersection spacing between County Line Road and the proposed Milky Way View is less than the prescribed 660 feet along the future alignment of Misty Acres Boulevard.

Explain the proposed alternative and compare to the ECM standards (May provide applicable regional or national standards used as basis):

As the adjacent intersection to the north is an Arterial (County Line Road), the standard requires an intersection centerline spacing of 660 feet. Centerline spacing on Misty Acres Boulevard between County Line Road and the Milky Way View would be 395 feet (see Deviation Exhibit 1).

## LIMITS OF CONSIDERATION

(At least one of the conditions listed below must be met for this deviation request to be considered.)

- The ECM standard is inapplicable to the particular situation.
- Topography, right-of-way, or other geographical conditions or impediments impose an undue hardship and an equivalent alternative that can accomplish the same design objective is available and does not compromise public safety or accessibility.
- A change to a standard is required to address a specific design or construction problem, and if not modified, the standard will impose an undue hardship on the applicant with little or no material benefit to the public.

Provide justification:

- The proposed development west of the proposed Misty Acres Boulevard would offer limited access opportunity, and two access points are required for the area north and west of Misty Acres Boulevard and Monument Hill Road (realigned). The access opportunity is limited as 1) there would be no access to County Line Road to the north, 2) existing Monument Hill Road on the east side of the site will be removed with the creation of a new north terminus of Monument Hill Road to the south.
- The proposed alternative can accomplish the same design objective and would not compromise public safety or accessibility. The next section explains/justifies this.

## CRITERIA FOR APPROVAL

Per ECM section 5.8.7 the request for a deviation may be considered if the request is **not based exclusively on financial considerations**. The deviation must not be detrimental to public safety or surrounding property. The applicant must include supporting information demonstrating compliance with **all of the following criteria**:

The deviation will achieve the intended result with a comparable or superior design and quality of improvement.

- The proposed access alternative would result in a better design to provide better site circulation and private local streets with provide better traffic distribution. Two access points are required for this residential project with greater than 25 lots and will result in better traffic operations because multiple access points will provide motorists with options for ingress/egress.
- The intersection of Milky Way View has been placed 330 feet north the proposed Snowy Top Drive intersection to the south (meets the *ECM* standard).
- The proposed intersection would meet sight-distance criteria, considering site-specific conditions rather than only general criteria for the roadway classification (see Deviation Exhibit 2).
- This access would be a T intersection (to the west) with no street connection on the east side of Misty Acres Boulevard. As there would be no east leg of this intersection, a southbound left-turn lane on the north side of the Misty Acres Boulevard/Milky Way View intersection would not be needed. Therefore, the full distance between this intersection and County Line Road can be utilized for the northbound approach to the Misty Acres/County Line Road intersection – notably for queuing of northbound-to-westbound left turns. Also, since Misty Acres Boulevard will end at County Line Road, all but negligible northbound traffic will turn left or right at County Line Road.

The deviation will not adversely affect safety or operations.

### Entering Sight Distance

With a proposed design speed of 40 mph (35-mph posted speed limit) on Misty Acres Boulevard, the sight distance to the south at the proposed Milky Way View site-access location would be 665 feet. This exceeds the required 445-foot requirement for entering sight distance per *ECM* Table 2-21. The sight distance looking to the north from Milky Way View would have a sight distance of 345 feet. Although the general *ECM* standard by classification for a 40-mph design speed is 445 feet. Basically, all approaching southbound vehicles on Misty Acres Boulevard would be turning either left or right from County Line Road. Based on an approaching vehicle speed of about 25 mph, which is the estimated vehicle speed at the completion of a vehicle turn from County Line Road onto southbound Misty Acres Boulevard, the necessary/**required** (based on site-specific conditions) entering sight distance is 280 feet (also from Table 2-21, but for 25 mph). The plan-measured 345-foot distance would exceed this 280-foot distance. Please refer to Deviation Exhibit 2.

### Stopping Sight Distance Approaching an Intersection

The stopping sight distance to an access/intersection along Misty Acres Boulevard (to Milky Way View) from the north and south would meet the *ECM*-prescribed 305-foot stopping sight distance requirement (grade adjustment may apply, depending on the roadway grades shown on the plan & profile drawings for Misty Acres Boulevard).

### Vehicle Queuing

This access would be a T intersection (to the west) with no street connection on the east side of Misty Acres Boulevard. As there would be no east leg of this intersection, a southbound left-turn lane on the north side of the Misty Acres Boulevard/Milky Way View intersection would not be needed. Therefore, the full distance between this intersection and County Line Road can be utilized for the northbound approach to the Misty Acres/County Line Road intersection – notably for queuing of northbound-to-westbound left turns. The 2044 analysis indicates a 95<sup>th</sup>-percentile queue length of 128 feet, which can be accommodated with the proposed intersection spacing.

The deviation will not adversely affect safety or operations.

**Intersection Level of Service**

The proposed intersection would meet *ECM* criteria for level of service. Level of service is projected to be “B” for the eastbound approach for 2044.

**T-Intersection**

This access is proposed as a T-intersection rather than a four-leg intersection, which will have far fewer intersection conflict points than a four-leg, TWSC intersection.

The deviation will not adversely affect maintenance and its associated cost.

The spacing will not affect the maintenance cost as the spacing will not negatively affect the ability for snowplow and maintenance vehicles to perform roadway maintenance.

The deviation will not adversely affect aesthetic appearance.

Spacing will not affect the aesthetics, as the proposed intersection spacing meets the standard for local street intersection spacing along this classification of roadway (even though 660' is required to the north to an arterial roadway (County Line Road). Plus, the T-intersection configuration will be aesthetically more pleasing than a four-leg intersection.

The deviation meets the design intent and purpose of the *ECM* standards.

The proposed Milky Way View intersection site-access location, would meet the intent of *ECM* criteria, taking into account site-specific and plan-specific conditions and considering traffic-operations analysis results


The deviation meets the control measure requirements of Part I.E.3 and Part I.E.4 of the County's MS4 permit, as applicable.

Water quality will be provided. Construction of the roadways and development of the site will be required to meet the above sections of the MS4 permit. The spacing deviation requested in itself does not involve any disturbance.










Approximate Scale  
1" = 800'



Deviation Request from ECM 2.3.2 -- Design Standards by Function Classification

-  Existing roadway
-  Proposed roadway
-  Portion of proposed roadway for which deviation is requested
-  Intersection centerline spacing - 395' proposed, 660' required (Table 2-7)  
(660' to the first street intersection from an arterial intersection)
-  Site property boundary


Deviation No. 1 - Exhibit 1

# Intersection Spacing Along an Urban Major Collector

Monument Ridge East (LSC# S234450)







## Deviation Exhibit No 2

copy of Exhibit 1a

# Sight Distance - Milky Way View (North Access Intersection)

Monument Ridge East (LSC# S234450)

