

the table on the drainage plan identifies storm A through E and G. As the storm pipes are not shown on the drainage plan it is not clear what is proposed or what is existing. Please see comments on the drainage plan and identify the existing and proposed storm facilities.

September 19, 2022

Kevin Mastin
Executive Director
2880 International Circle, Suite 110
Colorado Springs, CO 80910

please discuss drainage fees. Provide a table showing the filing 1 fees that were offset & those paid (bridge fee), the total reimbursable amount per the DBPS and identify the fees that are due with this filing.

**RE: Drainage Letter Report Solace Apartments – Revision Request
El Paso County, CO**

identify that full spectrum detention EDB ponds and water quality are provided. Identify that the two ponds are currently being constructed (or have been) with filing 1.

Dear Mr. Mastin:

The attached Final Drainage Report, "Final Drainage Report for Solace Apartments Filing No. 1," was prepared by JR Engineering, LLC in November 2021. The report was for the "Solace of Colorado Springs SDP" (SF-20-032 / PPR-20-47 / CON-2165) development located in a portion of Section 7, Township 14 South, Range 65 West of the 6th P.M. El Paso County, Colorado. The report considered the development in two phases; Phase I included 234 multifamily units, and Phase II included 114 multifamily units combining for a total of 348 units. The following drainage letter is regarding the development of Solace Apartments Filing No. 2 (the "Project"), also referred to as Phase II.

The Final Drainage Report provides detention for both Phase I and Phase II in fully developed conditions. The Project's proposed onsite drainage system was designed to match the drainage patterns shown in the Final Drainage Report to prevent a re-study of the development. The Project is adding one storm main to connect to the storm proposed in Phase I. Drainage analysis as outlined in "City of Colorado Spring/El Paso County Drainage Criteria Manual" Volumes 1 and 2 (EPCDCM) was used to determine the hydrologic design of this main.

Attached are the Drainage Area Maps, SF-1, SF-2, and SF-3 forms, and the StormCAD which were used to design the additional storm main. We are requesting that the additional storm main can be included as a revision to the Final Drainage Report as the drainage patterns remain relatively the same and the HGL in the 100 year event remains within the pipe.

Provide a statement indicating that the proposed drainage is in conformance with the previously approved final drainage report and that no changes to the FSD ponds are required.

Sincerely,

Per the CD's ST-F storm pipe indicates that the HGL is not within the pipe. Be sure to specify water tight joints where pressure pipe conditions occur. Revise the statement accordingly.

Eric Gunderson, P.E.
Kimley-Horn
2 N. Nevada Ave, Suite 300
Colorado Springs, CO 80903

Provide a general property description of the site that comprises filing 2 and give general description of the proposed sub-basins. Indicate the total acreage in this filing.

Refer to DCMV1 Ch4 for drainage letter standards.



STANDARD FORM SF-1

RUNOFF COEFFICIENTS - IMPERVIOUS CALCULATION

Please make sure the project name matches the final plat title

PROJECT NAME: Cimarron Hills Phase II
 PROJECT NUMBER: 19614002
 CALCULATED BY: MVZ
 CHECKED BY: EJG

DATE: 9/13/2022

| SOIL: C | | ROOF AREA | STREET - PAVED AREA | LANDSCAPE AREA | GRAVEL AREA | TOTAL AREA (AC) | Cc(2) | Cc(5) | Cc(10) | Cc(100) | Imp % |
|-----------------------|--------------|----------------|--------------------------|---------------------|------------------|-----------------|-------------|-------------|-------------|-------------|------------|
| LAND USE: | | 0.71 | 0.89 | 0.02 | 0.57 | | | | | | |
| 2-YEAR COEFF. | | 0.73 | 0.90 | 0.08 | 0.59 | | | | | | |
| 5-YEAR COEFF. | | 0.75 | 0.92 | 0.15 | 0.63 | | | | | | |
| 10-YEAR COEFF. | | 0.81 | 0.96 | 0.35 | 0.70 | | | | | | |
| 100-YEAR COEFF. | | 0.90 | 100% | 0% | 80% | | | | | | |
| IMPERVIOUS % | | | | | | | | | | | |
| DESIGN BASIN | DESIGN POINT | ROOF AREA (AC) | STREET - PAVED AREA (AC) | LANDSCAPE AREA (AC) | GRAVEL AREA (AC) | TOTAL AREA (AC) | Cc(2) | Cc(5) | Cc(10) | Cc(100) | Imp % |
| MAIN | | | | | | | | | | | |
| F1 | B | 0.00 | 0.85 | 0.86 | 0.00 | 1.71 | 0.45 | 0.49 | 0.53 | 0.65 | 50% |
| F2 | B | 0.00 | 0.25 | 0.24 | 0.00 | 0.48 | 0.47 | 0.50 | 0.55 | 0.66 | 51% |
| | | 0.00 | 1.10 | 1.10 | 0.00 | 2.20 | 0.46 | 0.49 | 0.54 | 0.66 | 50% |
| BASIN SUBTOTAL | | 0% | 50% | 50% | 0% | 100% | | | | | |
| STORM A | | | | | | | | | | | |
| A1 | B | 0.00 | 0.02 | 0.18 | 0.00 | 0.21 | 0.12 | 0.18 | 0.24 | 0.42 | 12% |
| A2 | B | 0.00 | 0.00 | 0.05 | 0.00 | 0.05 | 0.02 | 0.08 | 0.15 | 0.35 | 0% |
| A3 | B | 0.12 | 0.00 | 0.00 | 0.00 | 0.12 | 0.71 | 0.73 | 0.75 | 0.81 | 90% |
| A4 | B | 0.00 | 0.00 | 0.04 | 0.00 | 0.04 | 0.02 | 0.08 | 0.15 | 0.35 | 0% |
| A5 | B | 0.12 | 0.00 | 0.00 | 0.00 | 0.12 | 0.71 | 0.73 | 0.75 | 0.81 | 90% |
| | | 0.23 | 0.02 | 0.27 | 0.00 | 0.53 | 0.36 | 0.40 | 0.45 | 0.58 | 44% |
| BASIN SUBTOTAL | | 44% | 5% | 51% | 0% | 100% | | | | | |
| STORM B | | | | | | | | | | | |
| B1 | B | 0.12 | 0.00 | 0.00 | 0.00 | 0.12 | 0.71 | 0.73 | 0.75 | 0.81 | 90% |
| B2 | B | 0.00 | 0.11 | 0.38 | 0.00 | 0.49 | 0.21 | 0.26 | 0.32 | 0.49 | 22% |
| B3 | B | 0.00 | 0.04 | 0.31 | 0.00 | 0.36 | 0.13 | 0.18 | 0.24 | 0.43 | 12% |
| B4 | B | 0.12 | 0.00 | 0.00 | 0.00 | 0.12 | 0.71 | 0.73 | 0.75 | 0.81 | 90% |
| | | 0.23 | 0.15 | 0.69 | 0.00 | 1.07 | 0.29 | 0.34 | 0.39 | 0.54 | 34% |
| BASIN SUBTOTAL | | 22% | 14% | 64% | 0% | 100% | | | | | |
| STORM C | | | | | | | | | | | |
| C1 | B | 0.12 | 0.00 | 0.00 | 0.00 | 0.12 | 0.71 | 0.73 | 0.75 | 0.81 | 90% |
| C2 | B | 0.12 | 0.00 | 0.00 | 0.00 | 0.12 | 0.71 | 0.73 | 0.75 | 0.81 | 90% |
| | | 0.23 | 0.00 | 0.00 | 0.00 | 0.23 | 0.71 | 0.73 | 0.75 | 0.81 | 90% |
| BASIN SUBTOTAL | | 100% | 0% | 0% | 0% | 100% | | | | | |
| STORM D | | | | | | | | | | | |
| D1 | A | 0.12 | 0.00 | 0.00 | 0.00 | 0.12 | 0.71 | 0.73 | 0.75 | 0.81 | 90% |
| D2 | A | 0.12 | 0.00 | 0.00 | 0.00 | 0.12 | 0.71 | 0.73 | 0.75 | 0.81 | 90% |
| D3 | A | 0.00 | 0.36 | 0.21 | 0.00 | 0.57 | 0.57 | 0.60 | 0.63 | 0.73 | 63% |
| | | 0.23 | 0.36 | 0.21 | 0.00 | 0.80 | 0.61 | 0.63 | 0.67 | 0.76 | 71% |
| BASIN SUBTOTAL | | 29% | 45% | 26% | 0% | 100% | | | | | |
| STORM E | | | | | | | | | | | |
| E1 | A | 0.12 | 0.00 | 0.00 | 0.00 | 0.12 | 0.71 | 0.73 | 0.75 | 0.81 | 90% |
| E2 | A | 0.00 | 0.02 | 0.14 | 0.00 | 0.16 | 0.14 | 0.19 | 0.25 | 0.43 | 14% |
| E3 | A | 0.12 | 0.00 | 0.00 | 0.00 | 0.12 | 0.71 | 0.73 | 0.75 | 0.81 | 90% |
| | | 0.23 | 0.02 | 0.14 | 0.00 | 0.39 | 0.48 | 0.51 | 0.55 | 0.66 | 59% |
| BASIN SUBTOTAL | | 59% | 6% | 35% | 0% | 100% | | | | | |
| STORM G | | | | | | | | | | | |
| G1 | A | 0.00 | 0.36 | 0.27 | 0.00 | 0.63 | 0.52 | 0.55 | 0.59 | 0.70 | 57% |
| | | 0.00 | 0.36 | 0.27 | 0.00 | 0.63 | 0.52 | 0.55 | 0.59 | 0.70 | 57% |
| BASIN SUBTOTAL | | 0% | 57% | 43% | 0% | 100% | | | | | |
| OFFSITE | | | | | | | | | | | |
| OFF1 | B | 0.00 | 0.02 | 0.95 | 0.00 | 0.97 | 0.04 | 0.10 | 0.16 | 0.36 | 2% |
| OFF2 | B | 0.00 | 0.01 | 0.11 | 0.00 | 0.12 | 0.08 | 0.14 | 0.21 | 0.40 | 7% |
| OFF3 | B | 0.00 | 0.02 | 0.29 | 0.00 | 0.31 | 0.08 | 0.13 | 0.20 | 0.39 | 6% |
| OFF4 | B | 0.00 | 0.00 | 0.27 | 0.00 | 0.27 | 0.02 | 0.08 | 0.15 | 0.35 | 0% |
| OFF5 | B | 0.00 | 0.00 | 0.22 | 0.00 | 0.22 | 0.02 | 0.08 | 0.15 | 0.35 | 0% |
| | | 0.00 | 0.05 | 1.84 | 0.00 | 1.89 | 0.04 | 0.10 | 0.17 | 0.37 | 2% |
| BASIN SUBTOTAL | | 0% | 2% | 98% | 0% | 100% | | | | | |
| DESIGN POINT B | | 0.70 | 1.28 | 2.06 | 0.00 | 4.03 | 0.41 | 0.45 | 0.50 | 0.62 | 47% |
| DESIGN POINT A | | 0.46 | 0.74 | 0.62 | 0.00 | 1.82 | 0.55 | 0.58 | 0.61 | 0.71 | 63% |
| OFFSITE FLOW | | 0.00 | 0.05 | 1.84 | 0.00 | 1.89 | 0.04 | 0.10 | 0.17 | 0.37 | 2% |
| TOTAL PROJECT | | 1.16 | 2.06 | 4.52 | 0.00 | 7.74 | 0.35 | 0.40 | 0.44 | 0.58 | 40% |

Cimarron Hills Phase II
100-YR
Conduit Table - Time: 0.00 hours

| Start Node | Invert (Start) (ft) | Stop Node | Invert (Stop) (ft) | Length (User Defined) (ft) | Slope (Calculated) (ft/ft) | Diameter (in) | Manning's n | Flow (cfs) | Velocity (ft/s) | Capacity (Full Flow) (cfs) |
|------------|---------------------|-----------|--------------------|----------------------------|----------------------------|---------------|-------------|------------|-----------------|----------------------------|
| CB-1 | 6,260.28 | CB-2 | 6,263.97 | 173.0 | -0.021 | 18.0 | 0.013 | 8.98 | 5.08 | 15.34 |
| O-1 | 6,259.59 | CB-1 | 6,260.28 | 69.5 | -0.010 | 18.0 | 0.013 | 23.05 | 13.04 | 10.47 |

Catch Basin Table - Time: 0.00 hours

| Elevation (Ground) (ft) | Elevation (Invert) (ft) | Flow (Additional Subsurface) (cfs) | Flow (Total Out) (cfs) | Hydraulic Grade Line (In) (ft) | Headloss Method | Headloss Coefficient (Standard) | Longitudinal Slope (Inlet) (ft/ft) | Inlet Location | Manning's n (Inlet) |
|-------------------------|-------------------------|------------------------------------|------------------------|--------------------------------|-----------------|---------------------------------|------------------------------------|----------------|---------------------|
| 6,266.00 | 6,260.28 | 14.07 | 23.05 | 6,265.22 | Absolute | 0.000 | 0.020 | On Grade | 0.013 |
| 6,267.68 | 6,263.97 | 8.98 | 8.98 | 6,266.48 | Absolute | 0.000 | 0.020 | On Grade | 0.013 |

Cimarron Hills Phase II
5-YR
Conduit Table - Time: 0.00 hours


| Start Node | Invert (Start) (ft) | Stop Node | Invert (Stop) (ft) | Length (User Defined) (ft) | Slope (Calculated) (ft/ft) | Diameter (in) | Manning's n | Flow (cfs) | Velocity (ft/s) | Capacity (Full Flow) (cfs) |
|------------|---------------------|-----------|--------------------|----------------------------|----------------------------|---------------|-------------|------------|-----------------|----------------------------|
| CB-1 | 6,260.28 | CB-2 | 6,263.97 | 173.0 | -0.021 | 18.0 | 0.013 | 3.46 | 7.01 | 15.34 |
| O-1 | 6,259.59 | CB-1 | 6,260.28 | 69.5 | -0.010 | 18.0 | 0.013 | 8.99 | 5.09 | 10.47 |

Catch Basin Table - Time: 0.00 hours

| Elevation (Ground) (ft) | Elevation (Invert) (ft) | Flow (Additional Subsurface) (cfs) | Flow (Total Out) (cfs) | Hydraulic Grade Line (In) (ft) | Headloss Method | Headloss Coefficient (Standard) | Longitudinal Slope (Inlet) (ft/ft) | Inlet Location | Manning's n (Inlet) |
|-------------------------|-------------------------|------------------------------------|------------------------|--------------------------------|-----------------|---------------------------------|------------------------------------|----------------|---------------------|
| 6,266.00 | 6,260.28 | 5.53 | 8.99 | 6,262.38 | Absolute | 0.000 | 0.020 | On Grade | 0.013 |
| 6,267.68 | 6,263.97 | 3.46 | 3.46 | 6,264.68 | Absolute | 0.000 | 0.020 | On Grade | 0.013 |


Profile Report

Engineering Profile - ST-F (Cimarron Hills Phase II.stsw)





Profile Report

Engineering Profile - ST-F (Cimarron Hills Phase II.stsw)



K:\COS_LA\196140002 - Cimarron Hills\Phase 2\Project Files\Eng\Drainage\Area Maps\196140002D_DMAP.dwg Zimmerman, Mitch 9/22/2022 11:52 AM




provide contour labels and drainage flow arrows

Please show the proposed storm pipes and the existing storm facilities where they will tie into and/or where runoff from this site will be conveyed to.

Identify the appropriate design points on the drainage plan.

FYI: Additional comments may be provided once all information is provided.



Kimley»Horn

PROJECT NAME: Cimarron Hills Phase II
 PROJECT NUMBER: 19614002
 CALCULATED BY: MVZ
 CHECKED BY: EIG

RATIONAL CALCULATIONS SUMMARY

| DESIGN POINT | TRIBUTARY BASINS | C2 | C100 | TRIBUTARY AREA (AC) | DIRECT FLOWS (CFS) | |
|-----------------------------|------------------|------|------|---------------------|--------------------|--------------|
| | | | | | Q5 | Q100 |
| MAIN | | | | | | |
| B | F1 | 0.45 | 0.65 | 1.71 | 3.46 | 8.43 |
| B | F2 | 0.47 | 0.66 | 0.48 | 1.07 | 2.58 |
| TOTAL | | | | | 2.20 | 11.00 |
| STORM A | | | | | | |
| B | A1 | 0.12 | 0.42 | 0.21 | 0.15 | 0.64 |
| B | A2 | 0.02 | 0.35 | 0.05 | 0.02 | 0.16 |
| B | A3 | 0.71 | 0.81 | 0.12 | 0.41 | 0.82 |
| B | A4 | 0.02 | 0.35 | 0.04 | 0.01 | 0.12 |
| B | A5 | 0.71 | 0.81 | 0.12 | 0.41 | 0.82 |
| TOTAL | | | | | 0.53 | 1.00 |
| STORM B | | | | | | |
| B | B1 | 0.71 | 0.81 | 0.12 | 0.41 | 0.83 |
| B | B2 | 0.21 | 0.49 | 0.49 | 0.48 | 1.62 |
| B | B3 | 0.13 | 0.43 | 0.36 | 0.24 | 1.03 |
| B | B4 | 0.71 | 0.81 | 0.12 | 0.41 | 0.83 |
| TOTAL | | | | | 1.07 | 4.32 |
| STORM C | | | | | | |
| B | C1 | 0.71 | 0.81 | 0.12 | 0.41 | 0.83 |
| B | C2 | 0.71 | 0.81 | 0.12 | 0.41 | 0.83 |
| TOTAL | | | | | 0.23 | 1.66 |
| STORM D | | | | | | |
| A | D1 | 0.71 | 0.81 | 0.12 | 0.56 | 1.13 |
| A | D2 | 0.71 | 0.81 | 0.12 | 0.56 | 1.13 |
| A | D3 | 0.57 | 0.73 | 0.57 | 2.27 | 5.08 |
| TOTAL | | | | | 0.80 | 7.35 |
| STORM E | | | | | | |
| A | E1 | 0.71 | 0.81 | 0.12 | 0.57 | 1.14 |
| A | E2 | 0.14 | 0.43 | 0.16 | 0.21 | 0.85 |
| A | E3 | 0.71 | 0.81 | 0.12 | 0.57 | 1.14 |
| TOTAL | | | | | 0.39 | 3.13 |
| STORM G | | | | | | |
| A | G1 | 0.52 | 0.70 | 0.63 | 2.29 | 5.30 |
| TOTAL | | | | | 0.63 | 5.30 |
| OFFSITE | | | | | | |
| C | OFF1 | 0.04 | 0.36 | 0.97 | 0.62 | 4.25 |
| B | OFF2 | 0.08 | 0.40 | 0.12 | 0.11 | 0.58 |
| A | OFF3 | 0.08 | 0.39 | 0.31 | 0.27 | 1.47 |
| A | OFF4 | 0.02 | 0.35 | 0.27 | 0.14 | 1.13 |
| C | OFF5 | 0.02 | 0.35 | 0.22 | 0.12 | 0.95 |
| TOTAL | | | | | 1.89 | 8.39 |
| STORM C | | | | | | |
| DESIGN POINT A TOTAL | | | | | 2.40 | 13.08 |
| DESIGN POINT B TOTAL | | | | | 4.15 | 20.12 |
| TOTAL SITE | | | | | 7.74 | 38.41 |

make sure the title matches what is shown on the final plat document i.e. Solace Apartments Filing No. 2



Kimley»Horn
 2022 KIMLEY-HORN AND ASSOCIATES, INC.
 2 North Nevada Avenue, Suite 300
 Colorado Springs, Colorado 80903 (719) 453-0180

DESIGNED BY: MVZ
 DRAWN BY: MVZ/RES
 CHECKED BY: EUG
 DATE: 09/19/2022

CIMARRON HILLS - PHASE 2
 CONSTRUCTION DOCUMENTS
 DRAINAGE AREA MAP - PROPOSED SUBBASINS

NO. _____ BY _____ DATE _____
 REVISION _____

PRELIMINARY
 FOR REVIEW ONLY
 NOT FOR CONSTRUCTION
 Kimley»Horn
 Kimley-Horn and Associates, Inc.

PROJECT NO. 09668009
 SHEET EXH

**FINAL DRAINAGE REPORT
FOR
SOLACE APARTMENTS FILING NO. 1**

**Prepared For:
CS Powers and Galley, LLC
510 S Neil St
Champaign, IL 61820
(734) 216-2577**

**November 11, 2021
Project No. 25174.00**


**Prepared By:
JR Engineering, LLC
5475 Tech Center Drive
Colorado Springs, CO 80919
719-593-2593**

**PCD File No. PPR-20-047
PCD File No. SF2032**

**Final Drainage Report
Solace Apartments Filing No. 1**

ENGINEER'S STATEMENT:

The attached drainage plan and report were prepared under my direction and supervision and are correct to the best of my knowledge and belief. Said drainage report has been prepared according to the criteria established by El Paso County for drainage reports and said report is in conformity with the master plan of the drainage basin. I accept responsibility for any liability caused by any negligent acts, errors, or omissions on my part in preparing this report.


Mike Bramlett, Colorado P.E. # 32314
For and On Behalf of JR Engineering, LLC



Date


11/11/21

DEVELOPER'S STATEMENT:

I, the developer, have read and will comply with all of the requirements specified in this drainage report and plan.

Business Name: CS Powers and Galley, LLC

By:

 11/12/2021

Title:

MEMBER

Address:

510 S Neil St
Champaign, IL 61820

El Paso County:

Filed in accordance with the requirements of the El Paso County Land Development Code, Drainage Criteria Manual, Volumes 1 and 2 and Engineering Criteria Manual, as amended.

APPROVED
Engineering Department


11/30/2021 11:05:30 AM

dsdnijkamp

EPC Planning & Community
Development Department

Jennifer Irvine, P.E.
County Engineer/ ECM Administrator

Conditions:



CONTENTS

| | |
|--|-----------|
| PURPOSE | 1 |
| GENERAL LOCATION AND DESCRIPTION | 1 |
| LOCATION | 1 |
| DESCRIPTION OF PROPERTY | 2 |
| FLOODPLAIN STATEMENT | 2 |
| DRAINAGE BASINS AND SUB-BASINS | 2 |
| EXISTING MAJOR BASIN DESCRIPTIONS..... | 2 |
| EXISTING SUB-BASIN DRAINAGE | 3 |
| PROPOSED SUB-BASIN DRAINAGE..... | 5 |
| EXISTING MAJOR DRAINAGEWAY – SAND CREEK | 13 |
| DRAINAGE DESIGN CRITERIA | 13 |
| DEVELOPMENT CRITERIA REFERENCE | 13 |
| HYDROLOGIC CRITERIA | 13 |
| HYDRAULIC CRITERIA | 14 |
| DRAINAGE FACILITY DESIGN | 14 |
| GENERAL CONCEPT | 14 |
| SPECIFIC DETAILS | 14 |
| <i>Four Step Process to Minimize Adverse Impacts of Urbanization</i> | 14 |
| <i>Water Quality</i> | 15 |
| <i>Erosion Control Plan</i> | 16 |
| <i>Operation & Maintenance</i> | 16 |
| <i>Drainage & Bridge Fees</i> | 16 |
| <i>Construction Cost Opinion</i> | 17 |
| SUMMARY | 18 |
| REFERENCES: | 20 |

APPENDICES

- A. Figures and Exhibits
- B. Hydrologic/Hydraulic Calculations
- C. Detention and Water Quality Calculations
- D. Reference Materials
- E. Drainage Maps



PURPOSE

This document is the Final Drainage report for the Solace Apartments. The purpose of this report is to:

1. Identify on-site and off-site drainage patterns.
2. Design storm water facilities to collect and convey storm runoff from the proposed development to appropriate discharge and/or detention locations.
3. Design water quality and detention facilities to control discharge release rates to below historic.
4. Demonstrate compliance with surrounding major drainage basin planning studies, master development drainage plans and flood insurance studies.

GENERAL LOCATION AND DESCRIPTION

Location

The proposed Solace Apartments, known as “Solace” from herein, is a parcel of land located in Section 7, Township 14 South, Range 65 West of the 6th Principal Meridian in El Paso County, Colorado. Solace is a 28.83 acre, urban, multifamily-development and is comprised of 16 apartment dwellings and associated infrastructure. Solace will be split into two phases for construction, lot 1 (phase 1) contains most of the site with lot 2 (phase 2) containing the northern most section of the development. See appendix A for a site plan exhibit showing the Solace phasing. Solace is bound by existing industrial developments to the North and vacant land to the West. Galley Road bounds the property to the south and existing light industrial businesses to the east. A vicinity map of the area is presented in Appendix A.

Currently, there is one major Drainageway that runs along Solace: Sand Creek (Center Tributary) Drainageway. This Drainageway was analyzed, both hydrologically and hydraulically, in the following reports:

- Sand Creek Drainage Basin Planning Study (KEC), January 1993.
- Flood Insurance Study– El Paso County, Colorado & Incorporated Areas Vol 7 of 8, December 2018.
- Sand Creek – Center Tributary Channel Analysis Report for Solace Apartments (JR), June 2020
- LOMR- Case No. 05-08-0368P Federal Emergency Management Agency, May 23, 2007.

The impact of this Drainageway and planning studies on the proposed development will be discussed later in the report.

Description of Property

Solace is currently unoccupied and undeveloped. The existing ground cover is sparse vegetation and open space, typical of a Colorado rolling range land condition. In general, Solace slopes from northwest to southeast.

Per an NRCS web soil survey of the area, Solace is made up of Type B soils with a very small percentage of Type A in the northwest corner of the property. This Type B soil is a Blendon sandy loam. This soil type has a moderate infiltration rate when thoroughly wet. It also consists of moderately deep or deep, moderately well drained or well drained soil. A soil survey map has been presented in Appendix A.

Floodplain Statement

Based on the FEMA FIRM Maps number 08041C0751G and 08041C0752G, dated December 7, 2018, a portion of the existing drainageway lies within Zone AE and Zone X. Zone AE is defined as area subject to inundation by the 1-percent-annual-chance flood event. Zone X is defined as area outside the Special Flood Hazard Area (SFHA) and higher than the elevation of the 0.2-percent-annual-chance (or 500-year) flood. The FIRM Maps have been presented in Appendix A.

DRAINAGE BASINS AND SUB-BASINS

Existing Major Basin Descriptions

Solace lies within Sand Creek Drainage Basin based on the “*Sand Creek Drainage Basin Planning Study*” prepared by Kiowa Engineering in January 1993.

The Sand Creek Drainage Basin covers approximately 54 square miles in unincorporated El Paso County, CO. The Sand Creek Drainage Basin is tributary to Fountain Creek. In its existing condition, the basin is comprised of rolling rangeland with fair to good vegetative cover associated with Colorado’s semi-arid climate. The natural Drainageway within the site limits is typically deep and narrow with a well-defined flow path in most areas. Anticipated land use for the basin includes multifamily residential and open space.

As part of its drainage research, JR Engineering reviewed the following drainage studies, reports and LOMRs:

- Sand Creek Drainage Basin Planning Study prepared by Kiowa Engineering Corporation in January 1993.
- Flood Insurance Study– El Paso County, Colorado, & Incorporated Areas Vol 7, December 2018.
- LOMR- Case No. 05-08-0368P Federal Emergency Management Agency, May 23, 2007.
- Sand Creek – Center Tributary Channel Analysis Report for Solace Apartments (JR), June 2020

Final Drainage Report
Solace Apartments Filing No. 1

- Preliminary Drainage Report For Solace Apartments (JR), September 3, 2020

The *Sand Creek Drainage Basin Planning Study* was used to establish a stormwater management plan for the existing and future stormwater infrastructure needs within the Sand Creek Drainage Basin. Based on provided drainage maps and analysis, in its existing condition, the Sand Creek Center Tributary Drainageway contains a 100-year flow of 820-1100 cfs along Solace's east property line. The major Sand Creek Drainageway conveys the stormwater south along the eastern property line where it ultimately outfalls into the Fountain Creek. JR Engineering has performed checks on these flow rates to verify their validity. Basin calculations show that the 820-1100 cfs are still valid for this existing condition.

FEMA prepared a revised FIS for El Paso County Colorado, Volume 7 of 8, dated December 7, 2018. The effective floodplain for the site is shown on the FIRM 08041C0752G, revised to reflect LOMR, dated December 7, 2018. The study area of the FIS where the Sand Creek Drainageway crosses Galley Road, was found to overtop the culverts and flow onto the road. According to the FIS, this crossing has a 10% annual chance of flooding and is located in Zone AE of the FIRM. The *Sand Creek Drainage Basin LOMR* was executed on May 23, 2007. The LOMR revised the flood zone or the area south of Galley Road. See FIRM Map Panel 08041C0752G for limits of LOMR study and revised flood zones, presented in Appendix D.

Existing Sub-basin Drainage

On-site, existing basin drainage patterns are generally from northwest to southeast by way of on-site swales. Existing on-site areas flow directly into the Sand Creek Drainageway. For this development, the existing onsite drainage has been broken into Basin A and Basin B. All existing basins that are offsite are represented by Basin OS. All basin delineation for the existing condition can be found in the existing drainage map located in Appendix E.

Basin A contains a total of 23.98 acres and is broken down into three sub-basins: A1, A2, and A3. This basin represents a majority of the proposed development and is comprised solely of undeveloped land. Flows from this basin are tributary to the Sand Creek Center Tributary Drainageway in the existing condition.

Sub-basin A1 ($Q_5=3.1$ cfs, $Q_{100}=21.0$ cfs) is 14.75 acres of undeveloped land, and represents the easternmost portion of the site that is adjacent to the Sand Creek Center Tributary Drainageway. Storm runoff from this sub-basin flows southeast, via overland flow, directly into the Sand Creek Center Tributary Drainageway at Design Point 1.

Sub-basin A2 ($Q_5=0.9$ cfs, $Q_{100}=6.2$ cfs) is 3.79 acres and represents the undeveloped land in the center of the development. Storm runoff from this sub-basin flows south (Design Point 2), via overland flow, directly onto Galley Road. From here, flows are conveyed east in the existing curb and gutter into the Sand Creek Center Tributary Drainageway.

Final Drainage Report
Solace Apartments Filing No. 1

Sub-basin A3 ($Q_5=1.4$ cfs, $Q_{100}=9.5$ cfs) is 5.44 Acres and represents the undeveloped land on the southern property line of the development. Storm runoff from this sub basin flows south (Design Point 3), via overland flow, directly onto Galley Road. From here, flows are conveyed east via the existing curb and gutter to the Sand Creek Center Tributary Drainageway.

Sub-basin B1 ($Q_5=1.3$ cfs, $Q_{100}=9.0$ cfs) Sub-basin B1 consists of 4.84 acres of undeveloped land that drains overland to the southwest (Design Point 4) and offsite where it ultimately outfalls into an existing retention pond on the northeast corner of the intersection of Galley Road and Powers Blvd. This basin represents the westernmost portion of the site.

Basin OS consists of Sub-Basins OS1-OS2 combining for a total of 26.66 acres. This basin represents the developed land located to the north of the proposed development's property line, where the site ties in to Paonia Street. These sub-basins are primarily light industrial sites, and stormwater runoff is conveyed via overland flow and local roads.

Sub-basin OS1 ($Q_5=36.7$ cfs, $Q_{100}=73.1$ cfs) consists of the existing Paonia Street and the existing light industrial properties located just north of the site. In the existing condition, a portion of runoff from this sub-basin is captured by an existing concrete line channel along the north boundary of the site. The remaining runoff flows south onsite into the second drainageway where it ultimately outfalls into Sand Creek Center Tributary Drainageway at Galley Road. In the proposed condition, the runoff will be captured by the existing concrete channel and a proposed overflow channel at the north property line (Design Point 5 in the existing condition and Design Point 43 in the proposed condition) to prevent any offsite flows from entering the property. Once this existing flow has been captured, the runoff will be conveyed directly into the existing Sand Creek Center Tributary Drainageway at Design Point 1.1. Capturing this flow and draining it directly into the Sand Creek Center Tributary Drainageway will cause a slight change in the existing drainage patterns. A portion of this flow will no longer enter the existing second drainageway along the proposed Paonia Street alignment. Instead, this entire flow will enter the Sand Creek Center Tributary Drainageway near the north property line at Design Point 1.1. In order to accommodate this change, combination of rip rap and concrete lining shall be utilized in the overflow channel to prevent channel erosion. The Sand Creek Drainageway channel shall be modified to give the drainageway adequate capacity to contain the 100 year water surface and protect against erosive velocities in the channel. A typical cross section of the channel can also be found on the Channel Improvement Plans in Appendix E, for further detail of channel improvements see the JR Engineering Sand Creek Center Tributary Channel Improvements Letter. Channel analysis and weir calculations can be found in the *Sand Creek – Center Tributary Channel Analysis Report for Solace Apartments*, prepared by JR Engineering in May 2020.

Sub-basin OS2 ($Q_5=21.3$ cfs, $Q_{100}=42.5$ cfs) consists of the existing Ainsworth Street and the existing light industrial properties located just east of Ainsworth Street. Runoff from this sub-basin is captured by an existing swale along N. Powers Boulevard. The Solace Apartment site has a 5' berm that is proposed along the northern property line. This berm will prevent any drainage from this

Final Drainage Report
Solace Apartments Filing No. 1

basin to reach the site, and will utilize an onsite conveyance swale located at the toe of the berm to convey the flow to the western property line (Design Point 6 in the existing condition and Design Point 44 in the proposed condition). This proposed berm will slightly modify the existing drainage patterns, as it will prevent offsite flows from entering the northwestern corner of the site. To route flows offsite, an 18" depth swale with a 2' bottom is present at the bottom of the berm which will route flows to the west and outfall into the CDOT right-of-way located to the west of the site. According to UDFCD Chapter 8, figure 8-22, protection for this swale shall be Type VL riprap, see appendix B for this table.

Flows within the Sand Creek Drainageway are represented by Design Points 1.0-1.3 in the existing condition, and Design Points 5.0-5.3 in the proposed condition. Flows for these design points were taken directly from modeling data used by FEMA for the determination of the flood plain extents shown in FEMA FIRM 08041C0752G. These flows were used in the development of the HEC-RAS model to show the 100-year capacity of the drainageway in its proposed condition. Design Point 1.0 in the existing condition and 5.0 in the proposed condition ($Q_{100}=820$ cfs) represents the flows in the drainageway prior to entering the site boundary. Design Point 1.1 in the existing condition and 5.1 in the proposed condition ($Q_{100}=820$ cfs) represents the flow in the drainageway after the flows from Basin OS1 enter the channel. Design Point 1.2 in the existing condition and 5.2 in the proposed condition ($Q_{100}=1037$ cfs) represents the area where flows enter the drainageway from developments and roads located to the east of the site. Design Point 1.3 in the existing condition and 5.3 in the proposed condition ($Q_{100}=1100$ cfs) represents the flows at the Galley Road crossing. This flow was used to analyze the overtopping of Galley Road and the existing weir structure on the south side of the road.

Proposed Sub-basin Drainage

The proposed Solace basin delineation is as follows;

Sub-basin A1 ($Q_5=1.7$ cfs, $Q_{100}=3.3$ cfs) contains a total of 0.50 acres. This basin represents the north eastern portion of the proposed Phase 1 development. This basin is primarily multi-family residential and minor open space. Stormwater runoff from this basin is conveyed via private streets, where it is captured via a series of on-grade and sump inlets (Design Point 4). Runoff from this sub-basin ultimately outfalls into the proposed onsite Pond A. From the detention pond, the treated flows are then released directly into the Sand Creek Center Tributary Drainageway below historic rates at Design Point 5.2.

Sub-basin A2 ($Q_5=1.6$ cfs, $Q_{100}=3.1$ cfs) contains a total of 0.47 acres. This basin represents the eastern portion of the proposed along the Phase 1 development phase line. This basin is primarily multi-family residential and minor open space. Stormwater runoff from this basin is conveyed via private streets, where it is captured via a series of on-grade and sump inlets (Design Point 5). Runoff from this sub-basin ultimately outfalls into the proposed onsite Pond A. From the detention pond, the treated flows are then released directly into the Sand Creek Center Tributary Drainageway below historic rates at Design Point 5.2.

Final Drainage Report
Solace Apartments Filing No. 1

Sub-basin A3 ($Q_5=1.6$ cfs, $Q_{100}=3.1$ cfs) contains a total of 0.45 acres. This basin represents the center portion of the proposed development along the Phase 1 development phase line. This basin is primarily parking lot with garages and minor open space. Stormwater runoff from this basin is conveyed via private streets, where it is captured by an area inlet (Design Point 6). Runoff from this sub-basin ultimately outfalls into the proposed onsite Pond A. From the detention pond, the treated flows are then released directly into the Sand Creek Center Tributary Drainageway below historic rates at Design Point 5.2.

Sub-basin A4 ($Q_5=0.6$ cfs, $Q_{100}=1.0$ cfs) contains a total of 0.15 acres. This basin represents a northern half of a proposed building and is comprised solely of proposed roof. Stormwater runoff from this basin is captured by proposed roof drains and conveyed to the proposed storm sewer infrastructure (Design Point 2.1). Runoff from this sub-basin ultimately outfalls into the proposed onsite Pond A. From the detention pond, the treated flows are then released directly into the Sand Creek Center Tributary Drainageway below historic rates at Design Point 5.2.

Sub-basin A5 ($Q_5=0.5$ cfs, $Q_{100}=1.0$ cfs) contains a total of 0.13 acres. This basin represents a northern half of a proposed building and is comprised solely of proposed roof. Stormwater runoff from this basin is captured by proposed roof drains and conveyed to the proposed storm sewer infrastructure (Design Point 2.3). Runoff from this sub-basin ultimately outfalls into the proposed onsite Pond A. From the detention pond, the treated flows are then released directly into the Sand Creek Center Tributary Drainageway below historic rates at Design Point 5.2.

Sub-basin A6 ($Q_5=3.2$ cfs, $Q_{100}=7.0$ cfs) contains a total of 1.51 acres. This basin represents the central portion of the proposed Phase 1 development. This basin is primarily multi-family residential and minor open space. Stormwater runoff from this basin is conveyed via private streets, where it is captured by a sump inlet (Design Point 10). Runoff from this sub-basin ultimately outfalls into the proposed onsite Pond A. From the detention pond, the treated flows are then released directly into the Sand Creek Center Tributary Drainageway below historic rates at Design Point 5.2.

Sub-basin A7 ($Q_5=1.0$ cfs, $Q_{100}=2.4$ cfs) contains a total of 0.58 acres. This basin represents the northwestern portion of Paonia Street and minor open. This basin is primarily minor open space with some asphalt paving and concrete sidewalks. Stormwater runoff from this basin is conveyed via curb & gutter, where it is captured by an on-grade inlet (Design Point 11). Runoff from this sub-basin ultimately outfalls into the proposed onsite Pond A. From the detention pond, the treated flows are then released directly into the Sand Creek Center Tributary Drainageway below historic rates at Design Point 5.2.

Sub-basin A8 ($Q_5=0.8$ cfs, $Q_{100}=1.7$ cfs) contains a total of 0.30 acres. This basin represents the northeastern portion of Paonia Street. Half of this sub-basin is comprised of asphalt paving, while the second half is open space. Stormwater runoff from this basin is conveyed via curb & gutter, where it is captured by an on-grade inlet (Design Point 12). Runoff from this sub-basin ultimately

Final Drainage Report
Solace Apartments Filing No. 1

outfalls into the proposed onsite Pond A. From the detention pond, the treated flows are then released directly into the Sand Creek Center Tributary Drainageway below historic rates at Design Point 5.2.

Sub-basin A9 ($Q_5=0.4$ cfs, $Q_{100}=2.9$ cfs) contains a total of 1.33 acres. This basin represents the northeastern portion of the development. This basin is primarily open space and Pond A. Stormwater runoff from this basin is conveyed via overland flow, where it is captured by Pond A (Design Point 6A). From the detention pond, the treated flows are then released directly into the Sand Creek Center Tributary Drainageway below historic rates at Design Point 5.2.

Sub-basin B1 ($Q_5=1.6$ cfs, $Q_{100}=2.8$ cfs) contains a total of 0.37 acres. This basin represents the western portion of the proposed Phase 1 development along the phase line. This basin is primarily parking lot and minor open space. Stormwater runoff from this basin is conveyed via private streets, where it is captured by an on-grade inlet (Design Point 14). Runoff from this sub-basin, ultimately outfalls into the proposed onsite Pond B. From the detention pond, the treated flows are then released directly into the Sand Creek Center Tributary Drainageway below historic rates at Design Point 5.3.

Sub-basin B2 ($Q_5=1.4$ cfs, $Q_{100}=2.7$ cfs) contains a total of 0.35 acres. This basin represents a small western portion of the proposed Phase 1 development along the phase line. This basin is primarily parking lot and minor open space. Stormwater runoff from this basin is conveyed via private streets, where it is captured by an area inlet (Design Point 15). Runoff from this sub-basin ultimately outfalls into the proposed onsite Pond B. From the detention pond, the treated flows are then released directly into the Sand Creek Center Tributary Drainageway below historic rates at Design Point 5.3

Sub-basin B3 ($Q_5=1.2$ cfs, $Q_{100}=2.4$ cfs) contains a total of 0.35 acres. This basin represents the northwestern portion of the proposed Phase 1 development along the phase line. This basin is primarily parking lot and minor open space. Stormwater runoff from this basin is conveyed via private streets, where it is captured by an area inlet (Design Point 16). Runoff from this sub-basin ultimately outfalls into the proposed onsite Pond B. From the detention pond, the treated flows are then released directly into the Sand Creek Center Tributary Drainageway below historic rates at Design Point 5.3

Sub-basin B4 ($Q_5=0.1$ cfs, $Q_{100}=0.2$ cfs) contains a total of 0.03 acres. This basin represents a western portion of a proposed building and is comprised solely of proposed roof. Stormwater runoff from this basin is captured by proposed roof drains and conveyed to the proposed storm sewer infrastructure (Design Point 3.2). Runoff from this sub-basin ultimately outfalls into the proposed onsite Pond B. From the detention pond, the treated flows are then released directly into the Sand Creek Center Tributary Drainageway below historic rates at Design Point 5.3.

Sub-basin B5 ($Q_5=1.0$ cfs, $Q_{100}=1.8$ cfs) contains a total of 0.26 acres. This basin represents a eastern portion of a proposed building and a small western portion of an adjacent building. This sub-basin is comprised solely of proposed roof. Stormwater runoff from this basin is captured by proposed roof drains and conveyed to the proposed storm sewer infrastructure (Design Point 3.3).

Final Drainage Report
Solace Apartments Filing No. 1

Runoff from this sub-basin ultimately outfalls into the proposed onsite Pond B. From the detention pond, the treated flows are then released directly into the Sand Creek Center Tributary Drainageway below historic rates at Design Point 5.3.

Sub-basin B6 ($Q_5=1.9$ cfs, $Q_{100}=4.1$ cfs) contains a total of 0.73 acres. This basin represents the western drive aisle of the proposed Phase 1 development. This basin is primarily parking lot with garages and minor open space. Stormwater runoff from this basin is conveyed via private streets, where it is captured by an area inlet (Design Point 19). Runoff from this sub-basin ultimately outfalls into the proposed onsite Pond B. From the detention pond, the treated flows are then released directly into the Sand Creek Center Tributary Drainageway below historic rates at Design Point 5.3.

Sub-basin B7 ($Q_5=0.8$ cfs, $Q_{100}=2.0$ cfs) contains a total of 0.47 acres. This basin represents a proposed building and open space in the center of the development. This sub-basin is comprised primarily of proposed roof and open space. Stormwater runoff from this basin is captured by proposed roof and area drains. Runoff is then conveyed to the proposed storm sewer infrastructure (Design Point 3.5). Runoff from this sub-basin ultimately outfalls into the proposed onsite Pond B. From the detention pond, the treated flows are then released directly into the Sand Creek Center Tributary Drainageway below historic rates at Design Point 5.3.

Sub-basin B8 ($Q_5=0.9$ cfs, $Q_{100}=1.7$ cfs) contains a total of 0.25 acres. This basin represents an eastern portion of a proposed building and a small western portion of an adjacent building. This sub-basin is comprised solely of proposed roof. Stormwater runoff from this basin is captured by proposed roof drains and conveyed to the proposed storm sewer infrastructure (Design Point 3.6). Runoff from this sub-basin ultimately outfalls into the proposed onsite Pond B. From the detention pond, the treated flows are then released directly into the Sand Creek Center Tributary Drainageway below historic rates at Design Point 5.3.

Sub-basin B9 ($Q_5=0.7$ cfs, $Q_{100}=1.3$ cfs) contains a total of 0.19 acres. This basin represents a eastern portion of a proposed building and is comprised solely of proposed roof. Stormwater runoff from this basin is captured by proposed roof drains and conveyed to the proposed storm sewer infrastructure (Design Point 3.7). Runoff from this sub-basin ultimately outfalls into the proposed onsite Pond B. From the detention pond, the treated flows are then released directly into the Sand Creek Center Tributary Drainageway below historic rates at Design Point 5.3.

Sub-basin B10 ($Q_5=1.0$ cfs, $Q_{100}=2.2$ cfs) contains a total of 0.38 acres. This basin represents the clubhouse parking area and open space. This basin is primarily parking lot with open space. Stormwater runoff from this basin is conveyed curb and gutter, where it is captured by an on-grade inlet (Design Point 23). Runoff from this sub-basin ultimately outfalls into the proposed onsite Pond B. From the detention pond, the treated flows are then released directly into the Sand Creek Center Tributary Drainageway below historic rates at Design Point 5.3.

Final Drainage Report
Solace Apartments Filing No. 1

Sub-basin B11 ($Q_5=1.0$ cfs, $Q_{100}=2.6$ cfs) contains a total of 0.74 acres. This basin represents a proposed building and open space in the center of the development. This sub-basin is comprised primarily of proposed roof and open space. Stormwater runoff from this basin is captured by proposed roof and area drains. Runoff is then conveyed to the proposed storm sewer infrastructure (Design Point 4.0). Runoff from this sub-basin ultimately outfalls into the proposed onsite Pond B. From the detention pond, the treated flows are then released directly into the Sand Creek Center Tributary Drainageway below historic rates at Design Point 5.3.

Sub-basin B12 ($Q_5=2.7$ cfs, $Q_{100}=5.6$ cfs) contains a total of 1.08 acres. This basin represents the drive aisle just west of the clubhouse of the Phase 1 development. This basin is primarily parking lot with garages and minor open space. Stormwater runoff from this basin is conveyed via private streets, where it is captured by a sump inlet (Design Point 27). Runoff from this sub-basin ultimately outfalls into the proposed onsite Pond B. From the detention pond, the treated flows are then released directly into the Sand Creek Center Tributary Drainageway below historic rates at Design Point 5.3.

Sub-basin B13 ($Q_5=1.5$ cfs, $Q_{100}=3.2$ cfs) contains a total of 0.48 acres. This basin represents the drive aisle and open space in the center of Basin B. This basin is primarily parking lot with open space. Stormwater runoff from this basin is conveyed via private streets, where it is captured by an area inlet (Design Point 25). Runoff from this sub-basin ultimately outfalls into the proposed onsite Pond B. From the detention pond, the treated flows are then released directly into the Sand Creek Center Tributary Drainageway below historic rates at Design Point 5.3.

Sub-basin B13A ($Q_5=0.5$ cfs, $Q_{100}=1.6$ cfs) contains a total of 0.58 acres. This basin represents a northern portion of a proposed building and the southern portion of another, the middle portion of the basin is comprised of minor open space. Stormwater runoff from this basin is captured by proposed roof and area drains. Runoff is then conveyed to the proposed storm sewer infrastructure (Design Point 3.9). Runoff from this sub-basin ultimately outfalls into the proposed onsite Pond B. From the detention pond, the treated flows are then released directly into the Sand Creek Center Tributary Drainageway below historic rates at Design Point 5.3.

Sub-basin B14 ($Q_5=1.3$ cfs, $Q_{100}=2.6$ cfs) contains a total of 0.49 acres. This basin represents the western portion of the clubhouse and associated parking and drive aisle. This basin is primarily roof, parking lot, and open space. Stormwater runoff from this basin is conveyed via private streets, where it is captured by a sump inlet (Design Point 28). Runoff from this sub-basin ultimately outfalls into the proposed onsite Pond B. From the detention pond, the treated flows are then released directly into the Sand Creek Center Tributary Drainageway below historic rates at Design Point 5.3.

Sub-basin B15 ($Q_5=0.9$ cfs, $Q_{100}=1.8$ cfs) contains a total of 0.27 acres. This basin represents the eastern portion of the clubhouse and associated parking and drive aisle. This basin is primarily roof, parking lot, and open space. Stormwater runoff from this basin is conveyed via private streets, where it is captured by a sump inlet (Design Point 30). Runoff from this sub-basin ultimately outfalls into

Final Drainage Report
Solace Apartments Filing No. 1

the proposed onsite Pond B. From the detention pond, the treated flows are then released directly into the Sand Creek Center Tributary Drainageway below historic rates at Design Point 5.3.

Sub-basin B16 ($Q_5=0.4$ cfs, $Q_{100}=0.8$ cfs) contains a total of 0.15 acres. This basin represents a southern portion of a proposed building and a small open space area. Stormwater runoff from this basin is captured by proposed roof drains and an area inlet. Runoff is then conveyed to the proposed storm sewer infrastructure (Design Point 4.3). Runoff from this sub-basin ultimately outfalls into the proposed onsite Pond B. From the detention pond, the treated flows are then released directly into the Sand Creek Center Tributary Drainageway below historic rates at Design Point 5.3.

Sub-basin B17 ($Q_5=1.8$ cfs, $Q_{100}=4.5$ cfs) contains a total of 0.99 acres. This basin represents the northwestern portion of Paonia Street within Basin B. This basin is primarily road paving and open space. Stormwater runoff from this basin is conveyed via curb & gutter, where it is captured by an on-grade inlet (Design Point 31). Runoff from this sub-basin ultimately outfalls into the proposed onsite Pond B. From the detention pond, the treated flows are then released directly into the Sand Creek Center Tributary Drainageway below historic rates at Design Point 5.3

Sub-basin B18 ($Q_5=1.1$ cfs, $Q_{100}=2.4$ cfs) contains a total of 0.47 acres. This basin represents the northeastern portion of Paonia Street within Basin B. This basin is primarily road paving and minor open space. Stormwater runoff from this basin is conveyed via curb & gutter, where it is captured by an on-grade inlet (Design Point 32). Runoff from this sub-basin ultimately outfalls into the proposed onsite Pond B. From the detention pond, the treated flows are then released directly into the Sand Creek Center Tributary Drainageway below historic rates at Design Point 5.3

Sub-basin B19 ($Q_5=2.1$ cfs, $Q_{100}=5.7$ cfs) contains a total of 1.92 acres. This basin represents the southern half of the clubhouse and patio area, along with the southwestern portion of Paonia Street within Basin B. This basin is primarily road paving, open space, and roof. Stormwater runoff from this basin is conveyed via overland flow and curb & gutter, where it is captured by an on-grade inlet (Design Point 33). Runoff from this sub-basin ultimately outfalls into the proposed onsite Pond B. From the detention pond, the treated flows are then released directly into the Sand Creek Center Tributary Drainageway below historic rates at Design Point 5.3

Sub-basin B20 ($Q_5=0.6$ cfs, $Q_{100}=1.4$ cfs) contains a total of 0.26 acres. This basin represents the southeastern portion of Paonia Street within Basin B. This basin is primarily road paving and minor open space. Stormwater runoff from this basin is conveyed via curb & gutter, where it is captured by an on-grade inlet (Design Point 34). Runoff from this sub-basin ultimately outfalls into the proposed onsite Pond B. From the detention pond, the treated flows are then released directly into the Sand Creek Center Tributary Drainageway below historic rates at Design Point 5.3

Sub-basin B21 ($Q_5=0.5$ cfs, $Q_{100}=3.6$ cfs) contains a total of 2.46 acres. This basin represents the northeastern portion of the development. This basin is primarily open space and Pond B. Stormwater runoff from this basin is conveyed via overland flow, where it is captured by Pond B

Final Drainage Report
Solace Apartments Filing No. 1

(Design Point 37). From the detention pond, the treated flows are then released directly into the Sand Creek Center Tributary Drainageway below historic rates at Design Point 5.3

Sub-Basin C1 ($Q_5=0.8$ cfs, $Q_{100}=2.2$ cfs) contains a total of 0.74 acres. This basin represents the southernmost portion of the proposed development. This basin is primarily proposed roadway and minor open space. Stormwater runoff from this basin is conveyed via proposed curb and gutter to a proposed crossspan (Design Point 40) at the intersection of Paonia Street and Galley Road. Runoff is then conveyed east by the existing curb and gutter in Galley Road to the Sand Creek Center Tributary Drainageway, per historic conditions.

Sub-Basin C2 ($Q_5=0.3$ cfs, $Q_{100}=2.3$ cfs) contains a total of 0.80 acres. This basin represents the westernmost portion of the proposed Phase 1 development. This basin is solely comprised of open space. Stormwater runoff from this basin follows historic drainage patterns and sheet flows offsite (Design Point 41).

Sub-Basin D1 ($Q_5=0.7$ cfs, $Q_{100}=2.6$ cfs) contains a total of 0.95 acres and represents the northern most portion of Paonia Street and the site. This basin is comprised primarily of proposed roadway and open space. Runoff from this basin is conveyed via emergency overflow channel to the Sand Creek Center Tributary Drainageway (Design Point 42) per historic conditions. See the *Sand Creek-Center Tributary Channel Analysis Report for Solace Apartments*, prepared by JR Engineering October 15th, 2020 for overflow channel details.

Sub-Basin F1 ($Q_5=2.2$ cfs, $Q_{100}=4.7$ cfs) contains a total of 0.92 acres and represents the northwestern most portion of the Pond A tributary. This basin is comprised primarily of future parking areas, open space, and a future building. Runoff from this basin will be captured by future storm sewer infrastructure (Design Point 1). The proposed storm sewer infrastructure for the Phase 1 improvements have been sized to account for the future flows from this sub-basin. The future flows have also been analyzed in the Storm CAD model to ensure ultimate build out conditions have been accounted for. Runoff from this sub-basin will ultimately outfall into the proposed onsite Pond A. The proposed Pond A has also been sized to account for these future flows. From the detention pond, the treated flows are then released directly into the Sand Creek Center Tributary Drainageway below historic rates at Design Point 5.2.

Sub-Basin F2 ($Q_5=0.5$ cfs, $Q_{100}=1.0$ cfs) contains a total of 0.14 acres and represents the future parking spaces along the drive aisle of the northernmost site access location. This basin is comprised solely of future parking. Runoff from this basin will be captured by the existing storm sewer infrastructure (Design Point 4). The proposed storm sewer infrastructure for the Phase 1 improvements have been sized to account for the future flows from this sub-basin. The future flows have also been analyzed in the Storm CAD model to ensure ultimate build out conditions have been accounted for. Runoff from this sub-basin will ultimately outfall into the proposed onsite Pond A. The proposed Pond A has also been sized to account for these future flows. From the detention pond,

Final Drainage Report
Solace Apartments Filing No. 1

the treated flows are then released directly into the Sand Creek Center Tributary Drainageway below historic rates at Design Point 5.2.

Sub-Basin F3 ($Q_5=2.1$ cfs, $Q_{100}=4.4$ cfs) contains a total of 0.73 acres and represents the eastern portion of the future parking spaces along the north property line of the site. This basin is comprised primarily of future parking and open space. Runoff from this basin will be captured by future storm sewer infrastructure (Design Point 3). The proposed storm sewer infrastructure for the Phase 1 improvements have been sized to account for the future flows from this sub-basin. The future flows have also been analyzed in the Storm CAD model to ensure ultimate build out conditions have been accounted for. Runoff from this sub-basin will ultimately outfall into the proposed onsite Pond A. The proposed Pond A has also been sized to account for these future flows. From the detention pond, the treated flows are then released directly into the Sand Creek Center Tributary Drainageway below historic rates at Design Point 5.2.

Sub-Basin F4 ($Q_5=0.8$ cfs, $Q_{100}=2.3$ cfs) contains a total of 0.68 acres and represents a portion of the Phase 2 improvements located in the center of the site. This basin is comprised primarily of future open space and a future building. Runoff from this basin will be captured by future storm sewer infrastructure (Design Point 7). The proposed storm sewer infrastructure for the Phase 1 improvements have been sized to account for the future flows from this sub-basin. The future flows have also been analyzed in the Storm CAD model to ensure ultimate build out conditions have been accounted for. Runoff from this sub-basin will ultimately outfall into the proposed onsite Pond A. The proposed Pond A has also been sized to account for these future flows. From the detention pond, the treated flows are then released directly into the Sand Creek Center Tributary Drainageway below historic rates at Design Point 5.2.

Sub-Basin F5 ($Q_5=5.7$ cfs, $Q_{100}=14.7$ cfs) contains a total of 3.88 acres and represents the western portion of the future parking spaces along the north property line of the site, the future buildings on the northwest portion of the site, and the open space associated with these improvements. This basin is comprised primarily of future parking, future buildings, and open space. Runoff from this basin will be captured by future storm sewer infrastructure (Design Point 3.0). The proposed storm sewer infrastructure for the Phase 1 improvements have been sized to account for the future flows from this sub-basin. The future flows have also been analyzed in the Storm CAD model to ensure ultimate build out conditions have been accounted for. Runoff from this sub-basin will ultimately outfall into the proposed onsite Pond B. The proposed Pond B has also been sized to account for these future flows. From the detention pond, the treated flows are then released directly into the Sand Creek Center Tributary Drainageway below historic rates at Design Point 5.3.

Sub-Basin F6 ($Q_5=0.2$ cfs, $Q_{100}=1.0$ cfs) contains a total of 0.35 acres. This basin represents the westernmost portion of the proposed Phase 1 development. This basin is solely comprised of open space. Stormwater runoff from this basin follows historic drainage patterns and sheet flows offsite (Design Point 41).

Final Drainage Report Solace Apartments Filing No. 1

Sub-Basin F7 ($Q_5=0.2$ cfs, $Q_{100}=1.5$ cfs) contains a total of 0.53 acres. This basin represents the westernmost portion of the proposed Phase 1 development. This basin is solely comprised of open space. Stormwater runoff from this basin follows historic drainage patterns and sheet flows offsite (Design Point 41).

All calculations and stormwater routing can be found in Appendix B.

Existing Major Drainageway – Sand Creek

The Sand Creek channel conveys an existing 820-1100 cfs along the sites eastern property line. In order to maintain the drainage patterns on the site, 2 detention ponds have been proposed to release developed flows, at or below historic rates. Based on the results of the *Sand Creek – Center Tributary Channel Analysis Report for Solace Apartments*, prepared by JR Engineering in May 2020, the existing channel sections will need protection from erosion as a result of the Solace development. This report analyzed the existing conditions to ensure that the Sand Creek channel is stable and velocities do not exceed allowable limits. Based on the results of this report, it was found that the channel in its current conditions is inadequate, as velocities in the channel exceeded allowable limits and overtopping occurs at the Galley Road. The report recommended several improvements to ensure channel stability, including channel lining such as riprap or concrete to protect from the high velocities, widening the channel to increase capacity and decrease velocity & adding check/ drop structures to reduce velocities. The report also indicates that improvements will be necessary to address the overtopping at the Galley Road crossing. An existing overflow structure is currently in place to convey any overtopping flows, but does not have adequate capacity. Analysis of the proposed improvements to the channel can be found in the *Sand Creek Center Tributary Channel Improvements Letter*. Channel hydraulic analysis sheets are presented in Appendix B of the aforementioned report and Channel Plans for the proposed improvements can be found in Appendix E. A drainage map for the Solace site can be found in Appendix E.

DRAINAGE DESIGN CRITERIA

Development Criteria Reference

Storm drainage analysis and design criteria for the project were taken from the “*City of Colorado Spring/El Paso County Drainage Criteria Manual*” Volumes 1 and 2 (EPCDCM), dated October 12, 1994, the “*Urban Storm Drainage Criteria Manual*” Volumes 1 - 3 (USDCM) and Chapter 6 and Section 3.2.1 of Chapter 13 of the “*Colorado Springs Drainage Criteria Manual (CCSDCM)*”, dated May 2014, as adopted by El Paso County.

Hydrologic Criteria

All hydrologic data was obtained from the “*El Paso Drainage Criteria Manual*” Volumes 1 and 2, and the “*Urban Drainage and Flood Control District Urban Storm Drainage Criteria Manual*” Volumes 1, 2, and 3. Onsite drainage improvements were designed based on the 5 year (minor) storm event and the 100-year (major) storm event. Rational Method calculations were prepared, in accordance with

Final Drainage Report
Solace Apartments Filing No. 1

Chapter 6, Section 3.0 of the EPCDCM, for the sub-basins that directly impact the sizing of the proposed storm sewer outfalls. Rational method calculations are presented in Appendix B.

Mile High Flood District's MHFD-Detention, Version 4.03 workbook was used for pond sizing. Required detention volumes and allowable release rates were designed per USDCM and CCS/EPCDCM. Pond sizing spreadsheets are presented in Appendix C.

Hydraulic Criteria

GeoHECRAS was used as the primary analysis method for the site in the *Sand Creek – Center Tributary Channel Analysis Report for Solace Apartments* and the *Sand Creek Center Tributary Channel Improvements Letter*. GeoHECRAS was used to model existing flows within the Sand Creek Drainageway in its existing and proposed conditions. This model was used to verify flood plains and analyze any overtopping that may occur within the project site. The 100-year water surface profiles for the model were analyzed from the north property line of the site to the area just south of the Galley Road Crossing.

Using StormCAD V8i, a modeling program for stormwater drainage, the hydraulic grade lines and energy grade lines were determined for the storm sewer network. Manhole and pipe losses for the model were obtained from the *Urban Storm Drainage Criteria Manual*, Mile High Flood District. Model results for the project site have been included in Appendix B.

DRAINAGE FACILITY DESIGN

General Concept

The proposed stormwater conveyance system was designed to convey the developed Solace runoff to two proposed full spectrum water quality and detention ponds via private storm sewer. The proposed pond bottoms are approximately 1.5 feet higher than the existing channel bottom. This allows adequate drainage from the ponds to outfall into the channel without the need for backflow prevention measures. The proposed ponds were also designed to release at less than historic rates to minimize adverse impacts downstream. Treated water will outfall directly into the Sand Creek Drainageway, where it will eventually outfall into Fountain Creek. The current site will be constructed in 2 phases. Both of the proposed ponds will be designed and constructed with the Phase 1 improvements along with the storm sewer within Paonia Street. Proposed drainage maps are presented in Appendix E, showing locations of the pond and channel outfall locations and improvements.

Specific Details

Four Step Process to Minimize Adverse Impacts of Urbanization

In accordance with the El Paso County Drainage Criteria Manual Volume 2, this site has implemented the four step process to minimize adverse impacts of urbanization. The four step

Final Drainage Report
Solace Apartments Filing No. 1

process includes reducing runoff volumes, stabilizing drainageways, treating the water quality capture volume (WQCV), and consider the need for Industrial Commercial BMP's.

Step 1, Reducing Runoff Volumes: The development of the project site is a proposed multi-family development with open spaces and lawn areas interspersed within the development which helps disconnect impervious areas and reduce runoff volumes.

Step 2, Stabilize Drainageways: Solace utilizes private storm sewer throughout the project site. This private storm sewer directs the on-site development flows to the multiple detention ponds within the project that release at or below historic rates into the Sand Creek Drainageway. Sand Creek (Center Tributary) Drainageway is stabilized downstream of the development, however additional stabilization measures shall be implemented to prevent any negative impacts to the drainageway. Drop structures have been added in order to reduce the slope of the channel. The channel shall also utilize concrete paving to avoid any erosion of the channel along the site.

Step 3, Provide WQCV: Runoff from this development is treated through capture and slow release of the WQCV in multiple full spectrum water quality and detention ponds that are designed per current El Paso County drainage criteria for Extended Detention Basins (EDB). These ponds will facilitate pollutant removal for the site, while also reducing peak stormwater rates into the Sand Creek Drainageway.

Step 4, Consider the need for Industrial and Commercial BMP's: No industrial or commercial uses are proposed within this development. However, a site specific storm water quality and erosion control plan and narrative have been prepared in conjunction with this final drainage report. Site specific temporary source control BMPs as well as permanent BMP's are detailed in this plan and narrative to protect receiving waters.

Water Quality

In accordance with Section 13.3.2.1 of the CCS/EPCDCM, full spectrum water quality and detention are provided for all developed basins. Outlet structure release rates shall be limited to less than historic rates to minimize adverse impacts to downstream stormwater facilities. Complete pond and outlet structure designs can be found in the appendix C. See Table 3 below for the proposed pond parameters.

Table 3: Pond Summary

| Tributary Sub-Basin | Pond Name | Tributary Acres | Comp. % Imperv. | WQ Volume (ac-ft) | Total Detention Volume (ac-ft) | Provided Volume (ac-ft) |
|----------------------------|------------------|------------------------|------------------------|--------------------------|---------------------------------------|--------------------------------|
| A | POND A | 7.89 | 49.43 | 0.135 | 0.732 | 1.292 |
| B | POND B | 17.50 | 40.6 | 0.264 | 1.412 | 2.659 |

**Final Drainage Report
Solace Apartments Filing No. 1**

Per Section I.7.1.B.7 of the ECM – Stormwater Quality Policy and Procedures, sites with land disturbance to undeveloped land (land with no human-made structures such as buildings or pavement) that will remain undeveloped after the site, may be excluded from the water quality requirements set for in Section 1.7. Per this section, we respectfully request that Basins C2, F6, and F7 be excluded from permanent stormwater quality management. Due to existing topography and design constraints, Basins C1 and D1 could not be captured and routed to a permanent full spectrum water quality and detention pond. Per Section I.7.1.C.1 of the ECM – Stormwater Quality Policy and Procedures, the County may exclude up to 20%, not to exceed 1 acre, of the applicable development site, from the WQCV standard. Basin C1 & D1 contain approximately 0.32 acres of pavement, equal to approximately 1.11% of the total development site. Per this section, we respectfully request that Basin C1 & D1 be excluded from the permanent stormwater quality management.

Erosion Control Plan

The El Paso County Drainage Criteria Manual specifies an Erosion Control Plan and associated cost estimate must be submitted with each Final Drainage Report. The Erosion Control Plan for Solace has been submitted with this report.

Operation & Maintenance

In order to ensure the function and effectiveness of the stormwater infrastructure, maintenance activities such as inspection, routine maintenance, restorative maintenance, rehabilitation and repair, are required. All proposed drainage structures within the any platted County ROW will be owned and maintained by El Paso County. All proposed drainage structures within the property or tracts will be owned and maintained by the property owner. Vegetation in the natural and improved portions of Sand Creek Drainageway is the responsibility of El Paso County. This includes all mowing, seeding and weed control activities. An Inspection & Maintenance Plan has been submitted concurrently with this report that details the required maintenance activities and intervals to ensure proper function of all stormwater infrastructure in the future. The full spectrum detention ponds will be owned & maintained by the property owner.

Drainage & Bridge Fees

The site lies within the Sand Creek Drainage Basin.

| 2021 DRAINAGE AND BRIDGE FEES – Solace Apartments | | | | |
|--|-------------------------------------|-----------------------------------|----------------------------|--------------------------|
| Impervious Acres (ac) | Drainage Fee (Per Imp. Acre) | Bridge Fee (Per Imp. Acre) | Solace Drainage Fee | Solace Bridge Fee |
| 11.67 | \$20,387 | \$8,339 | \$237,916 | \$97,316 |

The Solace development will receive full credit for any channel improvements indicated in the Sand Creek DBPS. From the Sand Creek DBPS, the channel improvements estimated for this reach of the tributary was estimated to be \$323,500. The table regarding these costs can be found in the Appendix. From the *Sand Creek (Center Tributary) Channel Analysis*, by JR Engineering, the estimated channel improvements will cost \$554,950. Per the Sand Creek Drainage Basin Planning Study, the Center Tributary has proposed crossing improvements at Terminal Avenue and Omaha

Final Drainage Report
Solace Apartments Filing No. 1

Boulevard. Both of these crossing were estimated to be \$72,000. Crossing improvements were also proposed at W. Frontage Road for \$106,200, US 24 Bypass for \$211,500, E. Frontage Road for \$84,600, Bijou Street for \$84,600, Platte Avenue for \$169,200, & Galley Road for \$90,000. These estimates provide costs for the storm sewer required to replace the existing infrastructure at these locations. The Galley Road crossing estimate reflects upsizing the existing culverts to 5’x 8’ concrete box structures. These estimates can be found in Appendix D. Based on these estimated costs, it is presumed that no drainage basin fees will be necessary.

Construction Cost Opinion

El Paso County specifies a cost estimate of proposed drainage facility improvements be submitted with the Final Drainage Report. A construction cost opinion for both public and private drainage improvements have been provided below. Please note that the following cost estimate does not include channel improvements.

| PUBLIC DRAINAGE FACILITIES | | | | |
|-----------------------------------|--------------------------|-------------|-------------------|----------------------|
| Item | Quantity | Unit | Unit Price | Extended Cost |
| 18" RCP | 93 | LF | \$65.00 | \$6,045.00 |
| 24" RCP | 41 | LF | \$78.00 | \$3,198.00 |
| 36" RCP | 188 | LF | \$120.00 | \$22,560.00 |
| 42" RCP | 31 | LF | \$160.00 | \$4,960.00 |
| 5' Type R Inlet | 2 | EA | \$6,200.00 | \$12,400.00 |
| 10' Type R Inlet | 4 | EA | \$7,600.00 | \$30,400.00 |
| 15' Type R Inlet | 2 | EA | \$12,000.00 | \$24,000.00 |
| Storm Sewer Manhole (Box Base) | 2 | EA | \$11,627.00 | \$23,254.00 |
| | | | Sub-Total | \$126,817.00 |
| | 10% Eng. And Contingency | | | \$12,681.70 |
| | | | Grand Total | \$139,498.70 |

Final Drainage Report
Solace Apartments Filing No. 1

| PRIVATE DRAINAGE FACILITIES | | | | |
|------------------------------------|-----------------|-------------|--------------------------|----------------------|
| Item | Quantity | Unit | Unit Price | Extended Cost |
| 18" RCP | 1,254 | LF | \$65.00 | \$81,510.00 |
| 24" RCP | 763 | LF | \$78.00 | \$59,514.00 |
| 30" RCP | 464 | LF | \$97.00 | \$45,008.00 |
| 36" RCP | 327 | LF | \$120.00 | \$39,240.00 |
| 42" RCP | 44 | LF | \$160.00 | \$7,040.00 |
| 18" FES | 2 | EA | \$390.00 | \$780.00 |
| 24" FES | 1 | EA | \$468.00 | \$468.00 |
| 5' Type R Inlet | 8 | EA | \$6,159.00 | \$49,274.00 |
| Type 13 Valley Inlet | 7 | EA | \$4,640.00 | \$32,480.00 |
| Storm Sewer Manhole (Slab Base) | 18 | EA | \$6,395.00 | \$115,110.00 |
| Storm Sewer Manhole (Box Base) | 3 | EA | \$11,627.00 | \$34,881.00 |
| Pond Grading | 3,682 | CY | \$20.00 | \$73,640.00 |
| Pond Spillway | 2 | EA | \$7,500.00 | \$15,000.00 |
| Pond Outlet Structure | 2 | EA | \$25,000.00 | \$50,000.00 |
| Pond Forebay | 4 | EA | \$12,000.00 | \$48,000.00 |
| 2' Concrete Trickle Channel | 728 | LF | \$75.00 | \$54,600.00 |
| Maintenance Trail (Asphalt) | 2486 | SY | \$90.00 | \$223,740.00 |
| Rip Rap | 198 | CY | \$112.00 | \$22,176.00 |
| | | | Sub-Total | \$952,461.00 |
| | | | 10% Eng. And Contingency | \$95,246.10 |
| | | | Grand Total | \$1,047,707.10 |

SUMMARY

The proposed development remains consistent with pre-development drainage conditions with the construction of the recommended drainage improvements, including storm sewer, detention ponds and existing drainageways. The proposed development will not adversely affect the offsite major drainageways or surrounding development. In order to safely convey flows through the Sand Creek Drainageway, channel improvements will be necessary to ensure channel stability and prevent channel degradation. Concrete paving will be required to armor the channel and stabilize the slopes during a major storm event. These improvements will ensure the drainageway functions properly as

Final Drainage Report
Solace Apartments Filing No. 1


a primary drainage conveyance system for the Solace Apartments. These improvements to the Sand Creek Center Tributary Drainageway are discussed in the *Sand Creek Center Tributary Channel Improvements Letter*. This report meets the latest El Paso County Drainage Criteria requirements for this site.

REFERENCES:

1. El Paso County Drainage Criteria Manual Volume 1, El Paso County, CO, 1994.
2. Urban Storm Drainage Criteria Manual Volumes 1-3, Mile High Flood District, Latest Revisions.
3. Flood Insurance Study- El Paso County, Colorado & Incorporated Areas Vol 7 of 8, Federal Emergency Management Agency, December 7, 2018.
4. Sand Creek Drainage Basin Planning Study, Kiowa Engineering, January 1993.
5. Sand Creek Drainage Basin LOMR, Federal Emergency Management Agency, May 23, 2007.
6. Sand Creek - Center Tributary Channel Analysis Report for Solace Apartments, JR Engineering, May, 2020
7. Preliminary Drainage Report for Solace Apartments, JR Engineering, September 3, 2020
8. El Paso County Engineering Criteria Manual, El Paso County, Latest Revision (2020)
9. City of Colorado Springs Design Criteria Manual Volume 1, City of Colorado Springs, Latest Revision (2014)

APPENDIX A
FIGURES AND EXHIBITS

X:\2510000.all\2517400\Drawings\Blocks\Vicinity Map - Drainage.dwg, 8.5x11 Portrait, 12/17/2019 11:14:34 AM, PhillipsJ



SITE



ORIGINAL SCALE: 1" = 500'


VICINITY MAP
 SOLACE APARTMENTS
 JOB NO. 15504.03
 4/27/2018




J-R ENGINEERING
 A Westrian Company

Centennial 303-740-9393 • Colorado Springs 719-593-2593
 Fort Collins 970-491-9888 • www.jrengineering.com

Hydrologic Soil Group—El Paso County Area, Colorado



Map Scale: 1:15,300 if printed on A landscape (11" x 8.5") sheet.




Map projection: Web Mercator Corner coordinates: WGS84 Edge tics: UTM Zone 13N WGS84



MAP LEGEND

Area of Interest (AOI)









 Area of Interest (AOI)

Soils

Soil Rating Polygons





-  A
-  A/D
-  B
-  B/D
-  C
-  C/D
-  D
-  Not rated or not available

Soil Rating Lines

-  A
-  A/D
-  B
-  B/D
-  C
-  C/D
-  D
-  Not rated or not available

Soil Rating Points



-  A
-  A/D
-  B
-  B/D

-  C
-  C/D
-  D
-  Not rated or not available


Water Features

 Streams and Canals

Transportation

-  Rails
-  Interstate Highways
-  US Routes
-  Major Roads
-  Local Roads

Background

 Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
 Web Soil Survey URL:
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: El Paso County Area, Colorado
 Survey Area Data: Version 17, Sep 13, 2019

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Aug 19, 2018—Sep 23, 2018

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Hydrologic Soil Group

| Map unit symbol | Map unit name | Rating | Acres in AOI | Percent of AOI |
|------------------------------------|--|--------|----------------|----------------|
| 8 | Blakeland loamy sand, 1 to 9 percent slopes | A | 373.7 | 35.4% |
| 10 | Blendon sandy loam, 0 to 3 percent slopes | B | 321.4 | 30.5% |
| 11 | Bresser sandy loam, cool, 0 to 3 percent slopes | B | 31.9 | 3.0% |
| 12 | Bresser sandy loam, cool, 3 to 5 percent slopes | B | 69.8 | 6.6% |
| 13 | Bresser sandy loam, cool, 5 to 9 percent slopes | B | 41.4 | 3.9% |
| 28 | Ellicott loamy coarse sand, 0 to 5 percent slopes | A | 96.1 | 9.1% |
| 56 | Nelson-Tassel fine sandy loams, 3 to 18 percent slopes | B | 3.7 | 0.3% |
| 70 | Pits, gravel | A | 10.3 | 1.0% |
| 94 | Travessilla-Rock outcrop complex, 8 to 90 percent slopes | D | 51.5 | 4.9% |
| 95 | Truckton loamy sand, 1 to 9 percent slopes | A | 35.7 | 3.4% |
| 96 | Truckton sandy loam, 0 to 3 percent slopes | A | 19.7 | 1.9% |
| Totals for Area of Interest | | | 1,055.2 | 100.0% |

Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

Rating Options


Aggregation Method: Dominant Condition

Component Percent Cutoff: None Specified

Tie-break Rule: Higher

S
P
R
I
N
G
S

E
D



1370000 FT

38° 50' 37.50"

104° 43' 7.50"

5'25"000m E

JOINS PANEL 0754



MAP SCALE 1" = 500'



PANEL 0752G

FIRM
FLOOD INSURANCE RATE MAP
EL PASO COUNTY,
COLORADO
AND INCORPORATED AREAS

PANEL 752 OF 1300
 (SEE MAP INDEX FOR FIRM PANEL LAYOUT)

CONTAINS:

| COMMUNITY | NUMBER | PANEL | SUFFIX |
|---------------------------|--------|-------|--------|
| COLORADO SPRINGS, CITY OF | 080060 | 0752 | G |
| EL PASO COUNTY | 080059 | 0752 | G |

Notice to User: The Map Number shown below should be used when placing map orders; the Community Number shown above should be used on insurance applications for the subject community.

MAP NUMBER
08041C0752G

MAP REVISED
DECEMBER 7, 2018

Federal Emergency Management Agency



NATIONAL FLOOD INSURANCE PROGRAM

This is an official copy of a portion of the above referenced flood map. It was extracted using F-MIT On-Line. This map does not reflect changes or amendments which may have been made subsequent to the date on the title block. For the latest product information about National Flood Insurance Program flood maps check the FEMA Flood Map Store at www.msc.fema.gov

NOTES TO USERS

This map is for use in administering the National Flood Insurance Program. It does not necessarily identify all areas subject to flooding, particularly from local drainage sources of small size. The community map repository should be consulted for possible updated or additional flood hazard information.

To obtain more detailed information in areas where **Base Flood Elevations (BFEs)** and/or **floodways** have been determined, users are encouraged to consult the Flood Profiles and Floodway Data and/or Summary of Stillwater Elevations tables contained within the Flood Insurance Study (FIS) report that accompanies this FIRM. Users should be aware that BFEs shown on the FIRM represent rounded whole-foot elevations. These BFEs are intended for flood insurance rating purposes only and should not be used as the sole source of flood elevation information. Accordingly, flood elevation data presented in the FIS report should be utilized in conjunction with the FIRM for purposes of construction and/or floodplain management.

Coastal Base Flood Elevations shown on this map apply only landward of 0.0' North American Vertical Datum of 1988 (NAVD88). Users of this FIRM should be aware that coastal flood elevations are also provided in the Summary of Stillwater Elevations table in the Flood Insurance Study report for this jurisdiction. Elevations shown in the Summary of Stillwater Elevations table should be used for construction and/or floodplain management purposes when they are higher than the elevations shown on this FIRM.

Boundaries of the **floodways** were computed at cross sections and interpolated between cross sections. The floodways were based on hydraulic considerations with regard to requirements of the National Flood Insurance Program. Floodway widths and other pertinent floodway data are provided in the Flood Insurance Study report for this jurisdiction.

Certain areas not in Special Flood Hazard Areas may be protected by **flood control structures**. Refer to section 2.4 "Flood Protection Measures" of the Flood Insurance Study report for information on flood control structures for this jurisdiction.

The **projection** used in the preparation of this map was Universal Transverse Mercator (UTM) zone 13. The **horizontal datum** was NAD83, GRS80 spheroid. Differences in datum, spheroid, projection or UTM zones zones used in the production of FIRMs for adjacent jurisdictions may result in slight positional differences in map features across jurisdiction boundaries. These differences do not affect the accuracy of this FIRM.

Flood elevations on this map are referenced to the **North American Vertical Datum of 1988 (NAVD88)**. These flood elevations must be compared to structure and ground elevations referenced to the same **vertical datum**. For information regarding conversion between the National Geodetic Vertical Datum of 1929 and the North American Vertical Datum of 1988, visit the National Geodetic Survey website at <http://www.ngs.noaa.gov/> or contact the National Geodetic Survey at the following address:

NGS Information Services
 NOAA, NINGS12
 National Geodetic Survey
 SSMC-3, #9202
 1315 East-West Highway
 Silver Spring, MD 20910-3282

To obtain current elevation, description, and/or location information for **bench marks** shown on this map, please contact the Information Services Branch of the National Geodetic Survey at (301) 713-3242 or visit its website at <http://www.ngs.noaa.gov/>.

Base Map information shown on this FIRM was provided in digital format by El Paso County, Colorado Springs Utilities, City of Fountain, Bureau of Land Management, National Oceanic and Atmospheric Administration, United States Geological Survey, and Anderson Consulting Engineers, Inc. These data are current as of 2006.

This map reflects more detailed and up-to-date **stream channel configurations and floodplain delineations** than those shown on the previous FIRM for this jurisdiction. The floodplains and floodways that were transferred from the previous FIRM may have been adjusted to conform to these new stream channel configurations. As a result, the Flood Profiles and Floodway Data tables in the Flood Insurance Study Report (which contains authoritative hydraulic data) may reflect stream channel distances that differ from what is shown on this map. The profile baselines depicted on this map represent the hydraulic modeling baselines that match the flood profiles and Floodway Data Tables if applicable, in the FIS report. As a result, the profile baselines may deviate significantly from the new base map channel representation and may appear outside of the floodplain.

Corporate limits shown on this map are based on the best data available at the time of publication. Because changes due to annexations or de-annexations may have occurred after this map was published, map users should contact appropriate community officials to verify current corporate limit locations.

Please refer to the separately printed **Map Index** for an overview map of the county showing the layout of map panels; community map repository addresses; and a Listing of Communities table containing National Flood Insurance Program dates for each community as well as a listing of the panels on which each community is located.


Contact **FEMA Map Service Center (MSC)** via the FEMA Map Information eXchange (FIMIX) 1-877-336-2627 for information on available products associated with this FIRM. Available products may include previously issued Letters of Map Change, a Flood Insurance Study Report, and/or digital versions of this map. The MSC may also be reached by Fax at 1-800-358-9620 and its website at <http://www.msc.fema.gov/>.

If you have **questions about this map** or questions concerning the National Flood Insurance Program in general, please call 1-877-FEMA MAP (1-877-336-2627) or visit the FEMA website at <http://www.fema.gov/business/nfp>.


El Paso County Vertical Datum Offset Table

| Flooding Source | Vertical Datum Offset (ft) |
|---|----------------------------|
| REFER TO SECTION 3.3 OF THE EL PASO COUNTY FLOOD INSURANCE STUDY FOR STREAM BY STREAM VERTICAL DATUM CONVERSION INFORMATION | |


Panel Location Map



This Digital Flood Insurance Rate Map (DFIRM) was produced through a Cooperating Technical Partner (CTP) agreement between the State of Colorado Water Conservation Board (CWCB) and the Federal Emergency Management Agency (FEMA).



Additional Flood Hazard information and resources are available from local communities and the Colorado Water Conservation Board.



LEGEND

SPECIAL FLOOD HAZARD AREAS (SFHAS) SUBJECT TO INUNDATION BY THE 1% ANNUAL CHANCE FLOOD

The 1% annual chance flood (100-year flood), also known as the base flood, is the flood that has a 1% chance of being equalled or exceeded in any given year. The Special Flood Hazard Area is the area subject to flooding by the 1% annual chance flood. Areas of Special Flood Hazard include Zones A, AE, AH, AO, AR, A99, V, and VE. The Base Flood Elevation is the water-surface elevation of the 1% annual chance flood.

- ZONE A** No Base Flood Elevations determined.
- ZONE AE** Base Flood Elevations determined.
- ZONE AH** Flood depths of 1 to 3 feet (usually areas of ponding); Base Flood Elevations determined.
- ZONE AO** Flood depths of 1 to 3 feet (usually sheet flow on sloping terrain); average depths determined. For areas of alluvial fan flooding, velocities also determined.
- ZONE AR** Special Flood Hazard Area Formerly protected from the 1% annual chance flood by a flood control system that was subsequently decommissioned. Zone AR indicates that the former flood control system is being restored to provide protection from the 1% annual chance or greater flood.
- ZONE A99** Area to be protected from 1% annual chance flood by a Federal flood protection system under construction; no Base Flood Elevations determined.
- ZONE V** Coastal flood zone with velocity hazard (wave action); no Base Flood Elevations determined.
- ZONE VE** Coastal flood zone with velocity hazard (wave action); Base Flood Elevations determined.

FLOODWAY AREAS IN ZONE AE

The floodway is the channel of a stream plus any adjacent floodplain areas that must be kept free of encroachment so that the 1% annual chance flood can be carried without substantial increases in flood heights.

OTHER FLOOD AREAS

ZONE X Areas of 0.2% annual chance flood; areas of 1% annual chance flood with average depths of less than 1 foot, or with drainage areas less than 1 square mile, and areas protected by levees from 1% annual chance flood.

OTHER AREAS

ZONE X Areas determined to be outside the 0.2% annual chance floodplain.

ZONE D Areas in which flood hazards are undetermined, but possible.

COASTAL BARRIER RESOURCES SYSTEM (CBRS) AREAS

OTHERWISE PROTECTED AREAS (OPAs)

CBRS areas and OPAs are normally located within or adjacent to Special Flood Hazard Areas.

- Floodplain boundary
- Floodway boundary
- Zone D Boundary
- CBRS and OPA boundary

Boundary dividing Special Flood Hazard Areas of different Base Flood Elevations, flood depths or flood velocities.

513 Base Flood Elevation line and value; elevation in feet* (EL 987)

Base Flood Elevation value where uniform within zone; elevation in feet* (EL 987)

* Referenced to the North American Vertical Datum of 1988 (NAVD 88)

A-A Cross section line

23-23 Transsect line

97° 07' 30.00" Geographic coordinates referenced to the North American Datum of 1983 (NAD 83)

4750000N 1000-meter Universal Transverse Mercator grid ticks, zone 13

6000000 FT 5000-foot grid ticks; Colorado State Plane coordinate system, central zone (FIPSZONE 0902), Lambert Conformal Conic Projection

DX5510 Bench mark (see explanation in Notes to Users section of this FIRM panel)

M1.5 River Mile

MAP REPOSITORIES Refer to Map Repositories list on Map Index

EFFECTIVE DATE OF COUNTYWIDE FLOOD INSURANCE RATE MAP MARCH 17, 1997

EFFECTIVE DATE(S) OF REVISION(S) TO THIS PANEL DECEMBER 7, 2018 - to update corporate limits, to change Base Flood Elevations and Special Flood Hazard Areas, to update map format, to add roads and road names, and to incorporate previously issued Letters of Map Revision.

For community map revision history prior to countywide mapping, refer to the Community Map History Table located in the Flood Insurance Study report for this jurisdiction.

To determine if flood insurance is available in this community, contact your insurance agent or call the National Flood Insurance Program at 1-800-638-6620.

MAP SCALE 1" = 500'

250 0 500 1000 FEET

150 0 150 300 METERS

NFP

PANEL 0751G

FIRM

FLOOD INSURANCE RATE MAP

EL PASO COUNTY, COLORADO AND INCORPORATED AREAS

PANEL 751 OF 1300

(SEE MAP INDEX FOR FIRM PANEL LAYOUT)

CONTAINS:

| COMMUNITY | NUMBER | PANEL | SUFFIX |
|---------------------------|--------|-------|--------|
| COLORADO SPRINGS, CITY OF | 08060 | 0751 | G |
| EL PASO COUNTY | 08059 | 0751 | G |

Notice to User: The Map Number shown below should be used when placing map orders. The Community Number shown above should be used on insurance applications for the subject community.

MAP NUMBER 08041C0751G

MAP REVISED DECEMBER 7, 2018

Federal Emergency Management Agency

APPENDIX B

HYDROLOGIC/ HYDRAULIC CALCULATIONS

COMPOSITE % IMPERVIOUS & COMPOSITE RUNOFF COEFFICIENT CALCULATIONS

Subdivision: Solace (Existing Condition)
 Location: El Paso County

Project Name: Solace Apartments
 Project No.: 25174.00
 Calculated By: JBP
 Checked By: _____
 Date: 6/29/20

| Basin ID | Total Area (ac) | Streets (100% Impervious) | | | | Roofs (90% Impervious) | | | | Light Industrial (80% Impervious) | | | | Undeveloped (2% Impervious) | | | | Basins Total Weighted C | | Basins Total Weighted % Imp. |
|-----------------|-----------------|---------------------------|------------------|-----------|-----------------|------------------------|------------------|-----------|-----------------|-----------------------------------|------------------|-----------|-----------------|-----------------------------|------------------|-----------|-----------------|-------------------------|------------------|------------------------------|
| | | C ₅ | C ₁₀₀ | Area (ac) | Weighted % Imp. | C ₅ | C ₁₀₀ | Area (ac) | Weighted % Imp. | C ₅ | C ₁₀₀ | Area (ac) | Weighted % Imp. | C ₅ | C ₁₀₀ | Area (ac) | Weighted % Imp. | C ₅ | C ₁₀₀ | |
| A1 | 14.75 | 0.90 | 0.96 | 0.00 | 0.0% | 0.73 | 0.81 | 0.00 | 0.0% | 0.59 | 0.70 | 0.00 | 0.0% | 0.09 | 0.36 | 14.75 | 2.0% | 0.09 | 0.36 | 2.0% |
| A2 | 3.79 | 0.90 | 0.96 | 0.00 | 0.0% | 0.73 | 0.81 | 0.00 | 0.0% | 0.59 | 0.70 | 0.00 | 0.0% | 0.09 | 0.36 | 3.79 | 2.0% | 0.09 | 0.36 | 2.0% |
| A3 | 5.44 | 0.90 | 0.96 | 0.00 | 0.0% | 0.73 | 0.81 | 0.00 | 0.0% | 0.59 | 0.70 | 0.00 | 0.0% | 0.09 | 0.36 | 5.44 | 2.0% | 0.09 | 0.36 | 2.0% |
| B1 | 4.84 | 0.90 | 0.96 | 0.00 | 0.0% | 0.73 | 0.81 | 0.00 | 0.0% | 0.59 | 0.70 | 0.00 | 0.0% | 0.09 | 0.36 | 4.84 | 2.0% | 0.09 | 0.36 | 2.0% |
| OS1 | 17.73 | 0.90 | 0.96 | 0.00 | 0.0% | 0.73 | 0.81 | 0.00 | 0.0% | 0.59 | 0.70 | 17.73 | 80.0% | 0.09 | 0.36 | 0.00 | 2.0% | 0.59 | 0.70 | 80.0% |
| OS2 | 8.93 | 0.90 | 0.96 | 0.00 | 0.0% | 0.73 | 0.81 | 0.00 | 0.0% | 0.73 | 0.81 | 8.93 | 90.0% | 0.09 | 0.36 | 0.00 | 2.0% | 0.73 | 0.81 | 90.0% |
| | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | |
| TOTAL (A1-B1) | 28.82 | | | | | | | | | | | | | | | | | | | 2.0% |
| TOTAL (OS1-OS3) | 26.66 | | | | | | | | | | | | | | | | | | | 83.3% |
| TOTAL | 55.48 | | | | | | | | | | | | | | | | | | | 41.1% |

STANDARD FORM SF-2 TIME OF CONCENTRATION

Subdivision: Solace (Existing Condition)
Location: El Paso County

Project Name: Solace Apartments
Project No.: 25174.00
Calculated By: JBP
Checked By:
Date: 6/29/20

| SUB-BASIN DATA | | | | | | INITIAL/OVERLAND (T _i) | | | TRAVEL TIME (T _t) | | | | | t _c CHECK (URBANIZED BASINS) | | | FINAL | |
|----------------|-----------|------------------------|----------------|----------------|------------------|------------------------------------|--------------------|----------------------|-------------------------------|--------------------|------|-------------|----------------------|---|-------------------|--------------------------------|----------------------|--|
| BASIN ID | D.A. (ac) | Hydrologic Soils Group | Impervious (%) | C ₅ | C ₁₀₀ | L (ft) | S _o (%) | t _i (min) | L _t (ft) | S _t (%) | K | VEL. (ft/s) | t _t (min) | COMP. t _c (min) | TOTAL LENGTH (ft) | Urbanized t _c (min) | t _c (min) | |
| A1 | 14.75 | B | 2% | 0.09 | 0.36 | 100 | 2.4% | 13.7 | 1119 | 2.0% | 7.0 | 1.0 | 18.8 | 32.5 | 1219.0 | 39.9 | 32.5 | |
| A2 | 3.79 | B | 2% | 0.09 | 0.36 | 100 | 2.0% | 14.5 | 611 | 1.8% | 7.0 | 0.9 | 10.8 | 25.4 | 711.0 | 33.8 | 25.4 | |
| A3 | 5.44 | B | 2% | 0.09 | 0.36 | 100 | 1.8% | 15.0 | 444 | 1.9% | 7.0 | 1.0 | 7.7 | 22.7 | 544.0 | 31.4 | 22.7 | |
| B1 | 4.84 | B | 2% | 0.09 | 0.36 | 100 | 3.0% | 12.7 | 351 | 1.2% | 7.0 | 0.8 | 7.6 | 20.3 | 451.0 | 31.4 | 20.3 | |
| OS1 | 17.73 | B | 80% | 0.59 | 0.70 | 100 | 1.9% | 7.5 | 1236 | 1.8% | 20.0 | 2.7 | 7.7 | 15.1 | 1336.0 | 20.0 | 15.1 | |
| OS2 | 8.93 | B | 90% | 0.73 | 0.81 | 100 | 2.1% | 5.2 | 415 | 1.9% | 15.0 | 2.1 | 3.3 | 8.6 | 515.0 | 13.0 | 8.6 | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |

NOTES:

$$t_c = t_i + t_t$$

Where:

- t_c = computed time of concentration (minutes)
- t_i = overland (initial) flow time (minutes)
- t_t = channelized flow time (minutes).

$$t_t = \frac{L_t}{60K\sqrt{S_o}} = \frac{L_t}{60V_t}$$

Where:

- t_t = channelized flow time (travel time, min)
- L_t = waterway length (ft)
- S_o = waterway slope (ft/ft)
- V_t = travel time velocity (ft/sec) = K√S_o
- K = NRCS conveyance factor (see Table 6-2).

Equation 6-2
$$t_i = \frac{0.395(1.1 - C_2)\sqrt{L_i}}{S_o^{0.333}}$$

Where:

- t_i = overland (initial) flow time (minutes)
- C₂ = runoff coefficient for 5-year frequency (from Table 6-4)
- L_i = length of overland flow (ft)
- S_o = average slope along the overland flow path (ft/ft).

Equation 6-4
$$t_c = (26 - 17i) + \frac{L_t}{60(14i + 9)\sqrt{S_t}}$$

Where:

- t_c = minimum time of concentration for first design point when less than t_c from Equation 6-1.
- L_t = length of channelized flow path (ft)
- i = imperviousness (expressed as a decimal)
- S_t = slope of the channelized flow path (ft/ft).

Equation 6-3

Equation 6-5

Table 6-2. NRCS Conveyance factors, K

| Type of Land Surface | Conveyance Factor, K |
|--------------------------------------|----------------------|
| Heavy meadow | 2.5 |
| Tillage/field | 5 |
| Short pasture and lawns | 7 |
| Nearly bare ground | 10 |
| Grassed waterway | 15 |
| Paved areas and shallow paved swales | 20 |

Use a minimum t_c value of 5 minutes for urbanized areas and a minimum t_c value of 10 minutes for areas that are not considered urban. Use minimum values even when calculations result in a lesser time of concentration.

STANDARD FORM SF-3
STORM DRAINAGE SYSTEM DESIGN
(RATIONAL METHOD PROCEDURE)

Subdivision: Solace (Existing Condition)
Location: El Paso County
Design Storm: 5-Year

Project Name: Solace Apartments
Project No.: 25174.00
Calculated By: JBP
Checked By:
Date: 6/29/20

| STREET | Design Point | DIRECT RUNOFF | | | | | | | TOTAL RUNOFF | | | | STREET/SWALE | | | PIPE | | | | TRAVEL TIME | | | REMARKS | |
|--------|--------------|---------------|-----------|---------------|----------------------|----------|-----------|---------|----------------------|----------|-----------|---------|---------------------------------|----------|-----------|-------------------------|----------|-----------|--------------------|-------------|----------------|----------------------|--|--|
| | | Basin ID | Area (Ac) | Runoff Coeff. | t _c (min) | C*A (Ac) | I (in/hr) | Q (cfs) | t _c (min) | C*A (ac) | I (in/hr) | Q (cfs) | Q _{street/swale} (cfs) | C*A (ac) | Slope (%) | Q _{pipe} (cfs) | C*A (ac) | Slope (%) | Pipe Size (inches) | Length (ft) | Velocity (fps) | t _t (min) | | |
| | 1 | A1 | 14.75 | 0.09 | 32.5 | 1.33 | 2.36 | 3.1 | | | | | 3.1 | 1.33 | 0.7 | | | | | | | | | Surface runoff from existing basin A1, Surface flow into Sand Creek Drainageway at DP 1 |
| | 2 | A2 | 3.79 | 0.09 | 25.4 | 0.34 | 2.73 | 0.9 | | | | | 0.9 | 0.34 | 2.0 | | | | | | | | | Surface runoff from Basin A2 Surface flow offsite to the south at DP 2 |
| | 3 | A3 | 5.44 | 0.09 | 22.7 | 0.49 | 2.90 | 1.4 | | | | | 1.4 | 0.49 | 2.5 | | | | | | | | | Surface runoff from Basin A3 Surface flow offsite to the south at DP 3 |
| | 4 | B1 | 4.84 | 0.09 | 20.3 | 0.44 | 3.07 | 1.3 | | | | | 1.3 | 0.44 | 1.0 | | | | | | | | | Surface runoff from Basin B1 Surface flow offsite to the southwest at DP 4 |
| | 5 | OS1 | 17.73 | 0.59 | 15.1 | 10.46 | 3.51 | 36.7 | | | | | 36.7 | 10.46 | 1.78 | | | | | 200 | 2.0 | 1.7 | Surface runoff from Basin OS1, captured by existing concrete channel at DP 5 Channel conveyance to Sand Creek at DP 1.1 | |
| | 6 | OS2 | 8.93 | 0.73 | 8.6 | 6.52 | 4.36 | 28.4 | | | | | 28.4 | 6.52 | 3.2 | | | | | 147 | 2.7 | 0.9 | Surface runoff from Basin OS2 diverted to swale west of site at DP 6 | |
| | 1.0 | - | - | - | - | - | - | - | | | | | | | | | | | | | | | 5-Year Flows were not analyzed as part of the Sand Creek Drainage Basin Planning Study. | |
| | 1.1 | - | - | - | - | - | - | - | | | | | | | | | | | | | | | 5-Year Flows were not analyzed as part of the Sand Creek Drainage Basin Planning Study. | |
| | 1.2 | - | - | - | - | - | - | - | | | | | | | | | | | | | | | 5-Year Flows were not analyzed as part of the Sand Creek Drainage Basin Planning Study. | |
| | 1.3 | - | - | - | - | - | - | - | | | | | | | | | | | | | | | 5-Year Flows were not analyzed as part of the Sand Creek Drainage Basin Planning Study. | |
| | 1.4 | - | - | - | - | - | - | - | | | | | | | | | | | | | | | 5-Year Flows were not analyzed as part of the LOMR for Sand Creek Center Tributary. | |
| | 1.5 | - | - | - | - | - | - | - | | | | | | | | | | | | | | | 5-Year Flows were not analyzed as part of the Sand Creek Drainage Basin Planning Study. | |
| | 1.6 | - | - | - | - | - | - | - | | | | | | | | | | | | | | | 5-Year Flows were not analyzed as part of the Sand Creek Drainage Basin Planning Study. | |

Notes:
Street and Pipe C*A values are determined by Q/i using the catchment's intensity value.
All pipes are private and RCP unless otherwise noted. Pipe size shown in table column.

STANDARD FORM SF-3
STORM DRAINAGE SYSTEM DESIGN
(RATIONAL METHOD PROCEDURE)

Subdivision: Solace (Existing Condition)
Location: El Paso County
Design Storm: 100-Year

Project Name: Solace Apartments
Project No.: 25174.00
Calculated By: JBP
Checked By:
Date: 6/29/20

| Description | Design Point | DIRECT RUNOFF | | | | | | | TOTAL RUNOFF | | | | STREET/SWALE | | | PIPE | | | | TRAVEL TIME | | | REMARKS | |
|-------------|--------------|---------------|-----------|---------------|----------------------|----------|-----------|---------|----------------------|----------|-----------|---------|---------------------------------|----------|-----------|-------------------------|----------|-----------|--------------------|-------------|----------------|----------------------|---|--|
| | | Basin ID | Area (ac) | Runoff Coeff. | t _c (min) | C*A (ac) | i (in/hr) | Q (cfs) | t _c (min) | C*A (ac) | i (in/hr) | Q (cfs) | Q _{street/swale} (cfs) | C*A (ac) | Slope (%) | Q _{pipe} (cfs) | C*A (ac) | Slope (%) | Pipe Size (inches) | Length (ft) | Velocity (fps) | t _t (min) | | |
| | 1 | A1 | 14.75 | 0.36 | 32.5 | 5.31 | 3.96 | 21.0 | | | | 21.0 | 5.31 | 0.7 | | | | | | | | | | Surface runoff from existing basin A1, Surface flow into Sand Creek Drainageway at DP 1 |
| | 2 | A2 | 3.79 | 0.36 | 25.4 | 1.36 | 4.59 | 6.2 | | | | 6.2 | 1.36 | 2.0 | | | | | | | | | | Surface runoff from Basin A2 Surface flow offsite to the south at DP 2 |
| | 3 | A3 | 5.44 | 0.36 | 22.7 | 1.96 | 4.87 | 9.5 | | | | 9.5 | 1.96 | 2.5 | | | | | | | | | | Surface runoff from Basin A3 Surface flow offsite to the south at DP 3 |
| | 4 | B1 | 4.84 | 0.36 | 20.3 | 1.74 | 5.15 | 9.0 | | | | 9.0 | 1.74 | 1.0 | | | | | | | | | | Surface runoff from Basin B1 Surface flow offsite to the southwest at DP 4 |
| | 5 | OS1 | 17.73 | 0.70 | 15.1 | 12.41 | 5.89 | 73.1 | | | 573.1 | 573.1 | | 1.78 | | | | | 200 | 2.0 | 1.7 | | Surface runoff from Basin OS1 & DP 1.4, captured by existing concrete channel at DP 5 Street conveyance to DP 5, flow split to DP 1.5 & DP 1.6 | |
| | 6 | OS2 | 8.93 | 0.81 | 8.6 | 7.23 | 7.32 | 52.9 | | | | 52.9 | 7.23 | 3.2 | | | | | 147 | 2.7 | 0.9 | | Surface runoff from Basin OS2 diverted to swale west of site at DP 6 | |
| | 1.0 | - | - | - | - | - | - | 820.0 | | | | 820.0 | | | | | | | | | | | | Flow taken directly from the Sand Creek Drainage Basin Planning Study |
| | 1.1 | - | - | - | - | - | - | 820.0 | | | | 820.0 | | | | | | | | | | | | Flow taken directly from the Sand Creek Drainage Basin Planning Study |
| | 1.2 | - | - | - | - | - | - | 1037.0 | | | | 1037.0 | | | | | | | | | | | | Flow taken directly from the Sand Creek Drainage Basin Planning Study |
| | 1.3 | - | - | - | - | - | - | 1100.0 | | | | 1100.0 | | | | | | | | | | | | Flow taken directly from the Sand Creek Drainage Basin Planning Study |
| | 1.4 | - | - | - | - | - | - | 500.0 | | | | 500.0 | | | | | | | | | | | | Flow taken directly from the LOMR for Sand Creek Center Tributary Street conveyance to DP 5 |
| | 1.5 | | | | | | | | | | 244.0 | 244.0 | | | | | | | | | | | | Second Draiangeway Channel conveyance to Sand Creek at DP 1 |
| | 1.6 | | | | | | | | | | 42.1 | 42.1 | | | | | | | | | | | | Existing Concrete Channel Channel conveyance to Sand Creek at DP 1.1 |

Notes:
Street and Pipe C*A values are determined by Q/i using the catchment's intensity value.
All pipes are private and RCP unless otherwise noted. Pipe size shown in table column.

COMPOSITE % IMPERVIOUS & COMPOSITE RUNOFF COEFFICIENT CALCULATIONS

Subdivision: Solace
 Location: El Paso County

Project Name: Solace Apartments
 Project No.: 25174.00
 Calculated By: AAM
 Checked By: _____
 Date: 3/12/21

| Basin ID | Total Area (ac) | Streets (100% Impervious) | | | | Roofs (90% Impervious) | | | | Light Industrial (80% Impervious) | | | | Lawns (0% Impervious) | | | | Basins Total Weighted C | | Basins Total Weighted % Imp. |
|----------|-----------------|---------------------------|------------------|-----------|-----------------|------------------------|------------------|-----------|-----------------|-----------------------------------|------------------|-----------|-----------------|-----------------------|------------------|-----------|-----------------|-------------------------|------------------|------------------------------|
| | | C ₅ | C ₁₀₀ | Area (ac) | Weighted % Imp. | C ₅ | C ₁₀₀ | Area (ac) | Weighted % Imp. | C ₅ | C ₁₀₀ | Area (ac) | Weighted % Imp. | C ₅ | C ₁₀₀ | Area (ac) | Weighted % Imp. | C ₅ | C ₁₀₀ | |
| A1 | 0.50 | 0.90 | 0.96 | 0.29 | 58.0% | 0.73 | 0.81 | 0.11 | 19.8% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 0.10 | 0.0% | 0.70 | 0.81 | 77.8% |
| A2 | 0.47 | 0.90 | 0.96 | 0.36 | 76.6% | 0.73 | 0.81 | 0.00 | 0.0% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 0.11 | 0.0% | 0.71 | 0.82 | 76.6% |
| A3 | 0.45 | 0.90 | 0.96 | 0.35 | 77.8% | 0.73 | 0.81 | 0.00 | 0.0% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 0.10 | 0.0% | 0.72 | 0.82 | 77.8% |
| A4 | 0.15 | 0.90 | 0.96 | 0.00 | 0.0% | 0.73 | 0.81 | 0.15 | 90.0% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 0.00 | 0.0% | 0.73 | 0.81 | 90.0% |
| A5 | 0.13 | 0.90 | 0.96 | 0.00 | 0.0% | 0.73 | 0.81 | 0.13 | 90.0% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 0.00 | 0.0% | 0.73 | 0.81 | 90.0% |
| A6 | 1.51 | 0.90 | 0.96 | 0.53 | 35.1% | 0.73 | 0.81 | 0.38 | 22.6% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 0.60 | 0.0% | 0.53 | 0.68 | 57.7% |
| A7 | 0.58 | 0.90 | 0.96 | 0.24 | 41.4% | 0.73 | 0.81 | 0.00 | 0.0% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 0.34 | 0.0% | 0.42 | 0.60 | 41.4% |
| A8 | 0.30 | 0.90 | 0.96 | 0.16 | 53.3% | 0.73 | 0.81 | 0.00 | 0.0% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 0.14 | 0.0% | 0.52 | 0.68 | 53.3% |
| A9 | 1.33 | 0.90 | 0.96 | 0.00 | 0.0% | 0.73 | 0.81 | 0.00 | 0.0% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 1.33 | 0.0% | 0.08 | 0.35 | 0.0% |
| B1 | 0.37 | 0.90 | 0.96 | 0.29 | 78.4% | 0.73 | 0.81 | 0.00 | 0.0% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 0.08 | 0.0% | 0.72 | 0.83 | 78.4% |
| B2 | 0.35 | 0.90 | 0.96 | 0.33 | 94.3% | 0.73 | 0.81 | 0.00 | 0.0% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 0.02 | 0.0% | 0.85 | 0.93 | 94.3% |
| B3 | 0.35 | 0.90 | 0.96 | 0.25 | 71.4% | 0.73 | 0.81 | 0.00 | 0.0% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 0.10 | 0.0% | 0.67 | 0.79 | 71.4% |
| B4 | 0.03 | 0.90 | 0.96 | 0.00 | 0.0% | 0.73 | 0.81 | 0.03 | 90.0% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 0.00 | 0.0% | 0.73 | 0.81 | 90.0% |
| B5 | 0.26 | 0.90 | 0.96 | 0.00 | 0.0% | 0.73 | 0.81 | 0.26 | 90.0% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 0.00 | 0.0% | 0.73 | 0.81 | 90.0% |
| B6 | 0.73 | 0.90 | 0.96 | 0.43 | 58.9% | 0.73 | 0.81 | 0.00 | 0.0% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 0.30 | 0.0% | 0.56 | 0.71 | 58.9% |
| B7 | 0.47 | 0.90 | 0.96 | 0.00 | 0.0% | 0.73 | 0.81 | 0.21 | 40.2% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 0.26 | 0.0% | 0.37 | 0.56 | 40.2% |
| B8 | 0.25 | 0.90 | 0.96 | 0.00 | 0.0% | 0.73 | 0.81 | 0.25 | 90.0% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 0.00 | 0.0% | 0.73 | 0.81 | 90.0% |
| B9 | 0.19 | 0.90 | 0.96 | 0.00 | 0.0% | 0.73 | 0.81 | 0.19 | 90.0% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 0.00 | 0.0% | 0.73 | 0.81 | 90.0% |
| B10 | 0.38 | 0.90 | 0.96 | 0.21 | 55.3% | 0.73 | 0.81 | 0.00 | 0.0% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 0.17 | 0.0% | 0.53 | 0.69 | 55.3% |
| B11 | 0.74 | 0.90 | 0.96 | 0.00 | 0.0% | 0.73 | 0.81 | 0.29 | 35.3% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 0.45 | 0.0% | 0.33 | 0.53 | 35.3% |
| B12 | 1.08 | 0.90 | 0.96 | 0.66 | 61.1% | 0.73 | 0.81 | 0.00 | 0.0% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 0.42 | 0.0% | 0.58 | 0.72 | 61.1% |
| B13 | 0.58 | 0.90 | 0.96 | 0.33 | 56.9% | 0.73 | 0.81 | 0.00 | 0.0% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 0.25 | 0.0% | 0.55 | 0.70 | 56.9% |
| B13A | 0.48 | 0.90 | 0.96 | 0.00 | 0.0% | 0.73 | 0.81 | 0.11 | 20.6% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 0.37 | 0.0% | 0.23 | 0.46 | 20.6% |
| B14 | 0.49 | 0.90 | 0.96 | 0.29 | 59.2% | 0.73 | 0.81 | 0.05 | 9.2% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 0.15 | 0.0% | 0.63 | 0.76 | 68.4% |
| B15 | 0.27 | 0.90 | 0.96 | 0.19 | 70.4% | 0.73 | 0.81 | 0.02 | 6.7% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 0.06 | 0.0% | 0.71 | 0.81 | 77.0% |
| B16 | 0.15 | 0.90 | 0.96 | 0.00 | 0.0% | 0.73 | 0.81 | 0.11 | 66.0% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 0.04 | 0.0% | 0.56 | 0.69 | 66.0% |
| B17 | 0.99 | 0.90 | 0.96 | 0.40 | 40.4% | 0.73 | 0.81 | 0.01 | 0.9% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 0.58 | 0.0% | 0.42 | 0.60 | 41.3% |
| B18 | 0.47 | 0.90 | 0.96 | 0.24 | 51.1% | 0.73 | 0.81 | 0.00 | 0.0% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 0.23 | 0.0% | 0.50 | 0.66 | 51.1% |

| Basin ID | Total Area (ac) | Streets (100% Impervious) | | | | Roofs (90% Impervious) | | | | Light Industrial (80% Impervious) | | | | Lawns (0% Impervious) | | | | Basins Total Weighted C | | Basins Total Weighted % Imp. |
|-----------------|-----------------|---------------------------|------------------|-----------|-----------------|------------------------|------------------|-----------|-----------------|-----------------------------------|------------------|-----------|-----------------|-----------------------|------------------|-----------|-----------------|-------------------------|------------------|------------------------------|
| | | C ₅ | C ₁₀₀ | Area (ac) | Weighted % Imp. | C ₅ | C ₁₀₀ | Area (ac) | Weighted % Imp. | C ₅ | C ₁₀₀ | Area (ac) | Weighted % Imp. | C ₅ | C ₁₀₀ | Area (ac) | Weighted % Imp. | C ₅ | C ₁₀₀ | |
| B19 | 1.92 | 0.90 | 0.96 | 0.44 | 22.9% | 0.73 | 0.81 | 0.16 | 7.5% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 1.32 | 0.0% | 0.32 | 0.53 | 30.4% |
| B20 | 0.26 | 0.90 | 0.96 | 0.13 | 50.0% | 0.73 | 0.81 | 0.00 | 0.0% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 0.13 | 0.0% | 0.49 | 0.66 | 50.0% |
| B21 | 2.46 | 0.90 | 0.96 | 0.00 | 0.0% | 0.73 | 0.81 | 0.00 | 0.0% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 2.46 | 0.0% | 0.08 | 0.35 | 0.0% |
| C1 | 0.74 | 0.90 | 0.96 | 0.19 | 25.7% | 0.73 | 0.81 | 0.00 | 0.0% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 0.55 | 0.0% | 0.29 | 0.51 | 25.7% |
| C2 | 0.80 | 0.90 | 0.96 | 0.00 | 0.0% | 0.73 | 0.81 | 0.00 | 0.0% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 0.80 | 0.0% | 0.08 | 0.35 | 0.0% |
| D1 | 0.95 | 0.90 | 0.96 | 0.13 | 13.7% | 0.73 | 0.81 | 0.00 | 0.0% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 0.82 | 0.0% | 0.19 | 0.43 | 13.7% |
| F1 | 0.92 | 0.90 | 0.96 | 0.33 | 35.9% | 0.73 | 0.81 | 0.21 | 20.5% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 0.38 | 0.0% | 0.52 | 0.67 | 56.4% |
| F2 | 0.14 | 0.90 | 0.96 | 0.11 | 78.6% | 0.73 | 0.81 | 0.00 | 0.0% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 0.03 | 0.0% | 0.72 | 0.83 | 78.6% |
| F3 | 0.73 | 0.90 | 0.96 | 0.44 | 60.3% | 0.73 | 0.81 | 0.00 | 0.0% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 0.29 | 0.0% | 0.57 | 0.72 | 60.3% |
| F4 | 0.68 | 0.90 | 0.96 | 0.02 | 2.9% | 0.73 | 0.81 | 0.21 | 27.8% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 0.45 | 0.0% | 0.30 | 0.51 | 30.7% |
| F5 | 3.88 | 0.90 | 0.96 | 0.79 | 20.4% | 0.73 | 0.81 | 0.66 | 15.3% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 2.43 | 0.0% | 0.36 | 0.55 | 35.7% |
| F6 | 0.35 | 0.90 | 0.96 | 0.00 | 0.0% | 0.73 | 0.81 | 0.00 | 0.0% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 0.35 | 0.0% | 0.08 | 0.35 | 0.0% |
| F7 | 0.53 | 0.90 | 0.96 | 0.00 | 0.0% | 0.73 | 0.81 | 0.00 | 0.0% | 0.59 | 0.70 | 0.00 | 0.0% | 0.08 | 0.35 | 0.53 | 0.0% | 0.08 | 0.35 | 0.0% |
| OS1 | 17.73 | 0.90 | 0.96 | 0.00 | 0.0% | 0.73 | 0.81 | 0.00 | 0.0% | 0.59 | 0.70 | 17.73 | 80.0% | 0.08 | 0.35 | 0.00 | 0.0% | 0.59 | 0.70 | 80.0% |
| OS2 | 8.93 | 0.90 | 0.96 | 0.00 | 0.0% | 0.73 | 0.81 | 0.00 | 0.0% | 0.59 | 0.70 | 8.93 | 90.0% | 0.08 | 0.35 | 0.00 | 0.0% | 0.59 | 0.70 | 90.0% |
| TOTAL (A1-D1) | 21.18 | | | | | | | | | | | | | | | | | | | 40.9% |
| TOTAL (F1-F7) | 7.23 | | | | | | | | | | | | | | | | | | | 36.8% |
| TOTAL (OS1-OS2) | 26.66 | | | | | | | | | | | | | | | | | | | 83.3% |
| TOTAL | 55.07 | | | | | | | | | | | | | | | | | | | 60.9% |

STANDARD FORM SF-2 TIME OF CONCENTRATION

Subdivision: Solace
Location: El Paso County

Project Name: Solace Apartments
Project No.: 25174.00
Calculated By: AAM
Checked By: _____
Date: 3/12/21

| SUB-BASIN | | | | | | INITIAL/OVERLAND | | | TRAVEL TIME | | | | | t _c CHECK | | | FINAL |
|-----------|-----------|------------------------|----------------|----------------|------------------|-------------------|--------------------|----------------------|---------------------|--------------------|------|-------------|----------------------|----------------------------|-------------------|--------------------------------|-------|
| DATA | | | | | | (T _i) | | | (T _t) | | | | | (URBANIZED BASINS) | | | |
| BASIN ID | D.A. (ac) | Hydrologic Soils Group | Impervious (%) | C ₅ | C ₁₀₀ | L (ft) | S _o (%) | t _i (min) | L _t (ft) | S _t (%) | K | VEL. (ft/s) | t _t (min) | COMP. t _c (min) | TOTAL LENGTH (ft) | Urbanized t _c (min) | |
| A1 | 0.50 | B | 78% | 0.70 | 0.81 | 48 | 2.0% | 4.0 | 212 | 1.1% | 20.0 | 2.1 | 1.7 | 5.7 | 260.0 | 14.5 | 5.7 |
| A2 | 0.47 | B | 77% | 0.71 | 0.82 | 78 | 2.5% | 4.6 | 207 | 1.2% | 20.0 | 2.2 | 1.6 | 6.2 | 285.0 | 14.6 | 6.2 |
| A3 | 0.45 | B | 78% | 0.72 | 0.82 | 54 | 1.3% | 4.7 | 185 | 1.5% | 20.0 | 2.4 | 1.3 | 5.9 | 239.0 | 14.0 | 5.9 |
| A4 | 0.15 | B | 90% | 0.73 | 0.81 | 20 | 1.0% | 3.0 | 120 | 1.0% | 20.0 | 2.0 | 1.0 | 4.0 | 140.0 | 11.6 | 5.0 |
| A5 | 0.13 | B | 90% | 0.73 | 0.81 | 20 | 1.0% | 3.0 | 120 | 1.0% | 20.0 | 2.0 | 1.0 | 4.0 | 140.0 | 11.6 | 5.0 |
| A6 | 1.51 | B | 58% | 0.53 | 0.68 | 110 | 1.9% | 8.8 | 217 | 1.2% | 20.0 | 2.1 | 1.7 | 10.5 | 327.0 | 18.2 | 10.5 |
| A7 | 0.58 | B | 41% | 0.42 | 0.60 | 86 | 2.2% | 8.8 | 261 | 1.5% | 20.0 | 2.4 | 1.8 | 10.6 | 347.0 | 21.4 | 10.6 |
| A8 | 0.30 | B | 53% | 0.52 | 0.68 | 20 | 2.0% | 3.7 | 316 | 1.5% | 20.0 | 2.4 | 2.2 | 5.9 | 336.0 | 19.5 | 5.9 |
| A9 | 1.33 | B | 0% | 0.08 | 0.35 | 152 | 7.0% | 11.9 | 194 | 1.3% | 15.0 | 1.7 | 1.9 | 13.9 | 346.0 | 29.2 | 13.9 |
| B1 | 0.37 | B | 78% | 0.72 | 0.83 | 56 | 2.3% | 3.9 | 171 | 1.3% | 20.0 | 2.3 | 1.3 | 5.1 | 227.0 | 13.9 | 5.1 |
| B2 | 0.35 | B | 94% | 0.85 | 0.93 | 44 | 1.9% | 2.4 | 215 | 1.9% | 20.0 | 2.8 | 1.3 | 3.7 | 259.0 | 11.1 | 5.0 |
| B3 | 0.35 | B | 71% | 0.67 | 0.79 | 33 | 2.3% | 3.4 | 140 | 1.0% | 20.0 | 2.0 | 1.2 | 4.6 | 173.0 | 15.1 | 5.0 |
| B4 | 0.03 | B | 90% | 0.73 | 0.81 | 20 | 1.0% | 3.0 | 40 | 1.0% | 20.0 | 2.0 | 0.3 | 3.3 | 60.0 | 11.0 | 5.0 |
| B5 | 0.26 | B | 90% | 0.73 | 0.81 | 20 | 1.0% | 3.0 | 120 | 1.0% | 20.0 | 2.0 | 1.0 | 4.0 | 140.0 | 11.6 | 5.0 |
| B6 | 0.73 | B | 59% | 0.56 | 0.71 | 70 | 3.6% | 5.3 | 222 | 1.2% | 20.0 | 2.1 | 1.7 | 7.1 | 292.0 | 18.0 | 7.1 |
| B7 | 0.47 | B | 40% | 0.37 | 0.56 | 88 | 7.3% | 6.4 | 54 | 1.0% | 15.0 | 1.5 | 0.6 | 7.0 | 142.0 | 19.8 | 7.0 |
| B8 | 0.25 | B | 90% | 0.73 | 0.81 | 20 | 1.0% | 3.0 | 120 | 1.0% | 20.0 | 2.0 | 1.0 | 4.0 | 140.0 | 11.6 | 5.0 |
| B9 | 0.19 | B | 90% | 0.73 | 0.81 | 20 | 1.0% | 3.0 | 120 | 1.0% | 20.0 | 2.0 | 1.0 | 4.0 | 140.0 | 11.6 | 5.0 |
| B10 | 0.38 | B | 55% | 0.53 | 0.69 | 43 | 3.2% | 4.6 | 111 | 1.9% | 20.0 | 2.8 | 0.7 | 5.2 | 154.0 | 17.4 | 5.2 |
| B11 | 0.74 | B | 35% | 0.33 | 0.53 | 140 | 5.0% | 9.6 | 130 | 1.0% | 15.0 | 1.5 | 1.4 | 11.1 | 270.0 | 21.6 | 11.1 |
| B12 | 1.08 | B | 61% | 0.58 | 0.72 | 71 | 2.3% | 6.0 | 418 | 1.2% | 20.0 | 2.1 | 3.2 | 9.2 | 489.0 | 19.3 | 9.2 |
| B13 | 0.58 | B | 57% | 0.55 | 0.70 | 87 | 4.9% | 5.5 | 192 | 3.4% | 20.0 | 3.7 | 0.9 | 6.4 | 279.0 | 17.4 | 6.4 |
| B13A | 0.48 | B | 21% | 0.23 | 0.46 | 60 | 3.9% | 7.8 | 197 | 1.0% | 20.0 | 2.0 | 1.6 | 9.4 | 257.0 | 25.3 | 9.4 |
| B14 | 0.49 | B | 68% | 0.63 | 0.76 | 195 | 2.1% | 9.2 | 23 | 1.0% | 20.0 | 2.0 | 0.2 | 9.4 | 218.0 | 14.6 | 9.4 |
| B15 | 0.27 | B | 77% | 0.71 | 0.81 | 117 | 2.5% | 5.7 | 6 | 1.0% | 20.0 | 2.0 | 0.1 | 5.7 | 123.0 | 13.0 | 5.7 |
| B16 | 0.15 | B | 66% | 0.56 | 0.69 | 20 | 1.0% | 4.4 | 120 | 1.0% | 20.0 | 2.0 | 1.0 | 5.4 | 140.0 | 15.9 | 5.4 |
| B17 | 0.99 | B | 41% | 0.42 | 0.60 | 32 | 3.0% | 4.8 | 494 | 1.5% | 20.0 | 2.4 | 3.4 | 8.2 | 526.0 | 23.5 | 8.2 |
| B18 | 0.47 | B | 51% | 0.50 | 0.66 | 20 | 2.0% | 3.9 | 494 | 1.5% | 20.0 | 2.4 | 3.4 | 7.2 | 514.0 | 21.5 | 7.2 |
| B19 | 1.92 | B | 30% | 0.32 | 0.53 | 250 | 3.0% | 15.5 | 178 | 1.0% | 20.0 | 2.0 | 1.5 | 16.9 | 428.0 | 23.1 | 16.9 |
| B20 | 0.26 | B | 50% | 0.49 | 0.66 | 20 | 2.0% | 3.9 | 280 | 1.0% | 20.0 | 2.0 | 2.3 | 6.3 | 300.0 | 20.4 | 6.3 |

STANDARD FORM SF-2 TIME OF CONCENTRATION

Subdivision: Solace
Location: El Paso County

Project Name: Solace Apartments
Project No.: 25174.00
Calculated By: AAM
Checked By: _____
Date: 3/12/21

| SUB-BASIN | | | | | | INITIAL/OVERLAND | | | TRAVEL TIME | | | | | t _c CHECK | | | FINAL |
|-----------|-----------|------------------------|----------------|----------------|------------------|-------------------|--------------------|----------------------|---------------------|--------------------|------|-------------|----------------------|----------------------------|-------------------|--------------------------------|----------------------|
| DATA | | | | | | (T _i) | | | (T _t) | | | | | (URBANIZED BASINS) | | | |
| BASIN ID | D.A. (ac) | Hydrologic Soils Group | Impervious (%) | C ₅ | C ₁₀₀ | L (ft) | S _o (%) | t _i (min) | L _t (ft) | S _t (%) | K | VEL. (ft/s) | t _t (min) | COMP. t _c (min) | TOTAL LENGTH (ft) | Urbanized t _c (min) | t _c (min) |
| B21 | 2.46 | B | 0% | 0.08 | 0.35 | 250 | 2.5% | 21.5 | 736 | 1.0% | 15.0 | 1.5 | 8.2 | 29.7 | 986.0 | 39.6 | 29.7 |
| C1 | 0.74 | B | 26% | 0.29 | 0.51 | 153 | 2.0% | 14.4 | 95 | 1.8% | 20.0 | 2.7 | 0.6 | 15.0 | 248.0 | 22.6 | 15.0 |
| C2 | 0.80 | B | 0% | 0.08 | 0.35 | 30 | 5.0% | 5.9 | 30 | 5.0% | 7.0 | 1.6 | 0.3 | 6.3 | 60.0 | 26.2 | 6.3 |
| D1 | 0.95 | B | 14% | 0.19 | 0.43 | 83 | 2.0% | 11.9 | 155 | 3.3% | 15.0 | 2.7 | 0.9 | 12.8 | 238.0 | 25.0 | 12.8 |
| F1 | 0.92 | B | 56% | 0.52 | 0.67 | 112 | 5.5% | 6.3 | 196 | 1.8% | 20.0 | 2.7 | 1.2 | 7.5 | 308.0 | 17.9 | 7.5 |
| F2 | 0.14 | B | 79% | 0.72 | 0.83 | 30 | 4.0% | 2.4 | 257 | 1.1% | 20.0 | 2.1 | 2.1 | 4.4 | 287.0 | 14.7 | 5.0 |
| F3 | 0.73 | B | 60% | 0.57 | 0.72 | 66 | 13.5% | 3.3 | 331 | 1.5% | 20.0 | 2.4 | 2.3 | 5.5 | 397.0 | 18.3 | 5.5 |
| F4 | 0.68 | B | 31% | 0.30 | 0.51 | 173 | 6.0% | 10.5 | 97 | 1.0% | 20.0 | 2.0 | 0.8 | 11.3 | 270.0 | 22.0 | 11.3 |
| F5 | 3.88 | B | 36% | 0.36 | 0.55 | 115 | 5.0% | 8.5 | 283 | 1.7% | 20.0 | 2.6 | 1.8 | 10.3 | 398.0 | 22.5 | 10.3 |
| F6 | 0.35 | B | 0% | 0.08 | 0.35 | 30 | 8.0% | 5.1 | 30 | 8.0% | 7.0 | 2.0 | 0.3 | 5.3 | 60.0 | 26.2 | 5.3 |
| F7 | 0.53 | B | 0% | 0.08 | 0.35 | 20 | 25.0% | 2.8 | 516 | 2.0% | 15.0 | 2.1 | 4.1 | 6.9 | 536.0 | 32.8 | 6.9 |
| OS1 | 17.73 | B | 80% | 0.59 | 0.70 | 100 | 1.9% | 7.5 | 1236 | 1.8% | 20.0 | 2.7 | 7.7 | 15.1 | 1336.0 | 20.0 | 15.1 |
| OS2 | 8.93 | B | 90% | 0.59 | 0.70 | 100 | 2.1% | 7.2 | 425 | 1.9% | 15.0 | 2.1 | 3.4 | 10.6 | 525.0 | 13.1 | 10.6 |

NOTES:

$$t_c = t_i + t_t$$

Where:

- t_c = computed time of concentration (minutes)
- t_i = overland (initial) flow time (minutes)
- t_t = channelized flow time (minutes).

$$t_t = \frac{L_t}{60K\sqrt{S_o}} = \frac{L_t}{60V_t}$$

Where:

- t_t = channelized flow time (travel time, min)
- L_t = waterway length (ft)
- S_o = waterway slope (ft/ft)
- V_t = travel time velocity (ft/sec) = K√S_o
- K = NRCS conveyance factor (see Table 6-2).

Equation 6-2

$$t_i = \frac{0.395(1.1 - C_5)\sqrt{L_i}}{S_o^{0.33}}$$

Where:

- t_i = overland (initial) flow time (minutes)
- C₅ = runoff coefficient for 5-year frequency (from Table 6-4)
- L_i = length of overland flow (ft)
- S_o = average slope along the overland flow path (ft/ft).

Equation 6-4

$$t_t = (26 - 17t) + \frac{L_t}{60(14i + 9)\sqrt{S_t}}$$

Where:

- t_t = minimum time of concentration for first design point when less than t_t from Equation 6-1.
- L_t = length of channelized flow path (ft)
- i = imperviousness (expressed as a decimal)
- S_t = slope of the channelized flow path (ft/ft).

Equation 6-3

Table 6-2. NRCS Conveyance factors, K

| Type of Land Surface | Conveyance Factor, K |
|--------------------------------------|----------------------|
| Heavy meadow | 2.5 |
| Tillage/field | 5 |
| Short pasture and lawns | 7 |
| Nearly bare ground | 10 |
| Grassed waterway | 15 |
| Paved areas and shallow paved swales | 20 |

Use a minimum t_c value of 5 minutes for urbanized areas and a minimum t_t value of 10 minutes for areas that are not considered urban. Use minimum values even when calculations result in a lesser time of concentration.

STANDARD FORM SF-3
STORM DRAINAGE SYSTEM DESIGN
(RATIONAL METHOD PROCEDURE)

ubdivision: Solace
 Location: El Paso County
 sign Storm: 5-Year

Project Name: Solace Apartments
 Project No.: 25174.00
 Calculated By: AAM
 Checked By:
 Date: 3/12/21

| STREET | Design Point | DIRECT RUNOFF | | | | | | | TOTAL RUNOFF | | | | STREET/SWALE | | | PIPE | | | | TRAVEL TIME | | | REMARKS |
|--------|--------------|---------------|-----------|---------------|----------------------|----------|-----------|---------|----------------------|----------|-----------|---------|---------------------------------|----------|-----------|-------------------------|----------|-----------|--------------------|-------------|----------------|---|---------|
| | | Basin ID | Area (Ac) | Runoff Coeff. | t _c (min) | C*A (Ac) | I (in/hr) | Q (cfs) | t _c (min) | C*A (ac) | I (in/hr) | Q (cfs) | Q _{street/swale} (cfs) | C*A (ac) | Slope (%) | Q _{pipe} (cfs) | C*A (ac) | Slope (%) | Pipe Size (inches) | Length (ft) | Velocity (fps) | t _c (min) | |
| | 1 | F1 | 0.92 | 0.52 | 7.5 | 0.48 | 4.56 | 2.2 | | | | | | | 2.2 | 0.48 | 1.0 | 18 | 320 | 4.6 | 1.2 | Future on-grade inlet Future pipe conveyance to DP 1.0 | |
| | 2 | F2 | 0.14 | 0.72 | 5.0 | 0.10 | 5.17 | 0.5 | | | | 0.5 | 0.10 | 2.18 | | | | | 33 | 3.0 | 0.2 | Future overland flow to DP 4 Infrastructure to South Detention Pond at DP 2 | |
| | 3 | F3 | 0.73 | 0.57 | 5.5 | 0.42 | 5.02 | 2.1 | | | | | | | 2.1 | 0.42 | 1.9 | 18 | 64 | 5.8 | 0.2 | Future sump inlet Future pipe conveyance to DP 1.0 | |
| | 4 | A1 | 0.50 | 0.70 | 5.7 | 0.35 | 4.97 | 1.7 | | | | 0.1 | 0.03 | 1.5 | 1.6 | 0.32 | 1.5 | 18 | 300 | 1.8 | 2.7 | On-grade inlet, Carryover flow to DP 11 Piped to DP 1.0 | |
| | 1.0 | | | | | | | | 8.7 | 1.32 | 4.35 | 5.7 | | | 5.7 | 1.32 | 2.1 | 36 | 221 | 7.4 | 0.5 | Sum of DP 1, DP 2, DP 3, & DP 4 Piped to DP 4P | |
| | 4P | | | | | | | | 8.7 | 1.32 | 4.35 | 5.7 | 5.7 | 1.32 | 0.5 | | | | 185 | 1.1 | 2.9 | Pond A Forebay Trickle channel conveyance to DP 6P | |
| | 5 | A2 | 0.47 | 0.71 | 6.2 | 0.33 | 4.85 | 1.6 | | | | 0.6 | 0.12 | 1.2 | 1.0 | 0.21 | 2.0 | 18 | 290 | 1.6 | 2.9 | No. 16-valley inlet, Carryover flow to DP 10 Piped to DP 2.2 | |
| | 6 | A3 | 0.45 | 0.72 | 5.9 | 0.32 | 4.92 | 1.6 | | | | 0.6 | 0.12 | 1.5 | 1.0 | 0.20 | 1.0 | 18 | 321 | 1.8 | 2.9 | No. 16-valley inlet, Carryover flow to DP 10 Piped to DP 2.0 | |
| | 7 | F4 | 0.68 | 0.30 | 11.3 | 0.21 | 3.95 | 0.8 | | | | | | | 0.8 | 0.21 | 1.0 | 15 | 27 | 3.5 | 0.1 | Future roof drains and area inlets Future pipe conveyance to DP 2.0 | |
| | 2.0 | | | | | | | | 11.4 | 0.41 | 3.93 | 1.6 | | | 1.6 | 0.41 | 1.0 | 18 | 14 | 4.3 | 0.1 | Sum of DP 6 & DP 7 Piped to DP 2.1 | |
| | 8 | A4 | 0.15 | 0.73 | 5.0 | 0.11 | 5.17 | 0.6 | | | | | | | 0.6 | 0.11 | 1.0 | 15 | 105 | 3.1 | 0.6 | Roof drains Piped to DP 2.1 | |
| | 2.1 | | | | | | | | 11.4 | 0.52 | 3.93 | 2.1 | | | 2.1 | 0.52 | 1.0 | 18 | 101 | 4.6 | 0.4 | Sum of DP 8 & DP 2.0 Piped to DP 2.2 | |
| | 2.2 | | | | | | | | 11.8 | 0.73 | 3.88 | 2.8 | | | 2.8 | 0.73 | 1.0 | 24 | 105 | 4.9 | 0.4 | Sum of DP 5 & DP 2.1 Piped to DP 2.3 | |
| | 9 | A5 | 0.13 | 0.73 | 5.0 | 0.09 | 5.17 | 0.5 | | | | | | | 0.5 | 0.09 | 1.0 | 15 | 7 | 3.0 | 0.0 | Roof drains Piped to DP 2.3 | |
| | 2.3 | | | | | | | | 12.2 | 0.82 | 3.83 | 3.1 | | | 3.1 | 0.82 | 1.3 | 24 | 114 | 5.4 | 0.4 | Sum of DP 9 & DP 2.2 Piped to DP 2.4 | |
| | 10 | A6 | 1.51 | 0.53 | 10.5 | 0.80 | 4.06 | 3.2 | 10.5 | 1.04 | 4.06 | 4.2 | | | 4.2 | 1.04 | 1.3 | 24 | 0 | 6.0 | 0.0 | Sump Inlet, Sum of Carryover flows from DP 5, DP 6, and Sub-Basin A6 Piped to DP 2.4 | |
| | 2.4 | | | | | | | | 12.5 | 1.86 | 3.79 | 7.1 | | | 7.1 | 1.86 | 2.0 | 30 | 31 | 8.0 | 0.1 | Sum of DP 9 & DP 2.2 Piped to DP 2.5 | |
| | 11 | A7 | 0.58 | 0.42 | 10.6 | 0.24 | 4.05 | 1.0 | 10.6 | 0.27 | 4.05 | 1.1 | | | 1.1 | 0.27 | 2.0 | 30 | 0 | 4.5 | 0.0 | On-grade Inlet, Sum of carryover from DP 4 and Sub-Basin A7 Piped to DP 2.5 | |
| | 2.5 | | | | | | | | 12.6 | 2.13 | 3.78 | 8.1 | | | 8.1 | 2.13 | 2.0 | 36 | 44 | 8.0 | 0.1 | Sum of DP 11 & DP 2.4 Piped to DP 2.6 | |
| | 12 | A8 | 0.30 | 0.52 | 5.9 | 0.16 | 4.92 | 0.8 | | | | | | | 0.8 | 0.16 | 2.0 | 30 | 0 | 4.0 | 0.0 | On-grade inlet Piped to DP 2.6 | |
| | 2.6 | | | | | | | | 12.7 | 2.29 | 3.77 | 8.6 | | | 8.6 | 2.29 | 2.4 | 36 | 55 | 8.8 | 0.1 | Sum of DP 12 & DP 2.5 Piped to DP 5P | |
| | 5P | | | | | | | | 12.7 | 2.29 | 3.77 | 8.6 | 8.6 | 2.29 | 0.5 | | | | 45 | 1.1 | 0.7 | Pond A Forebay Trickle channel conveyance to DP 6P | |
| | 6P | A9 | 1.33 | 0.08 | 13.9 | 0.11 | 3.64 | 0.4 | | | | 0.4 | 0.11 | 2.18 | | | | | | | | Overland Flow Pond Conveyance to DP 6P | |
| | 6P | | | | | | | | 13.9 | 3.72 | 3.64 | 13.5 | | | | | | | | | | Pond outlet Structure Release detained flows into Sandcreek Drainageway | |
| | 13 | F5 | 3.88 | 0.36 | 10.3 | 0.82 | 4.09 | 3.4 | | | | 3.4 | 0.82 | 1.2 | | | | | 170 | 1.3 | 2.2 | Future Phase 2 developed flows minus roof drains and future area inlet flows Pan conveyance to DP 14 | |

STANDARD FORM SF-3
STORM DRAINAGE SYSTEM DESIGN
(RATIONAL METHOD PROCEDURE)

ubdivision: Solace
 Location: El Paso County
 sign Storm: 5-Year

Project Name: Solace Apartments
 Project No.: 25174.00
 Calculated By: AAM
 Checked By:
 Date: 3/12/21

| STREET | Design Point | DIRECT RUNOFF | | | | | | | TOTAL RUNOFF | | | | STREET/SWALE | | | PIPE | | | | TRAVEL TIME | | | REMARKS |
|--------|--------------|---------------|-----------|---------------|----------------------|----------|-----------|---------|----------------------|----------|-----------|---------|---------------------------------|----------|-----------|-------------------------|----------|-----------|--------------------|-------------|----------------|----------------------|--|
| | | Basin ID | Area (Ac) | Runoff Coeff. | t _c (min) | C*A (Ac) | I (in/hr) | Q (cfs) | t _c (min) | C*A (ac) | I (in/hr) | Q (cfs) | Q _{street/swale} (cfs) | C*A (ac) | Slope (%) | Q _{pipe} (cfs) | C*A (ac) | Slope (%) | Pipe Size (inches) | Length (ft) | Velocity (fps) | t _c (min) | |
| | 14 | B1 | 0.37 | 0.72 | 5.1 | 0.27 | 5.13 | 1.4 | 12.4 | 1.09 | 3.80 | 4.1 | 2.4 | 0.64 | 1.1 | 1.7 | 0.45 | 1.0 | 18 | 89 | 1.6 | 0.9 | Sum of carryover flows from DP 13 and Sub-Basin B1, No. 16-valley inlet, Carryover flow to DP 16 Piped to DP 3.0 |
| | 3.0 | | | | | | | | 12.4 | 1.68 | 3.80 | 6.4 | | | | 6.4 | 1.68 | 1.0 | 18 | 89 | 6.2 | 0.2 | Flows captured by No. 16-Valley inlet and future building and area drains connecting directly to inlet. Piped to DP 3.1 |
| | 15 | B2 | 0.35 | 0.85 | 5.0 | 0.30 | 5.17 | 1.6 | | | | | | | | 1.6 | 0.30 | 2.0 | 18 | 75 | 5.4 | 0.2 | On-grade inlet Piped to DP 3.1 |
| | 16 | B3 | 0.35 | 0.67 | 5.0 | 0.23 | 5.17 | 1.2 | 13.4 | 0.87 | 3.69 | 3.2 | | | | 3.2 | 0.87 | 1.0 | 18 | 0 | 5.2 | 0.0 | Sum of carryover flow from DP 14 and Sub-Basin B3, On-grade inlet. Carryover flow to DP 19 Piped to DP 3.1 |
| | 3.1 | | | | | | | | 13.4 | 2.85 | 3.69 | 10.5 | | | | 10.5 | 2.85 | 0.5 | 30 | 30 | 5.4 | 0.1 | Sum of DP 14, DP 15 & DP 16 Piped to DP 3.2 |
| | 17 | B4 | 0.03 | 0.73 | 5.0 | 0.02 | 5.17 | 0.1 | | | | | | | | 0.1 | 0.02 | 1.0 | 8 | 40 | 1.9 | 0.3 | Roof drains Piped to DP 3.2 |
| | 3.2 | | | | | | | | 13.5 | 2.87 | 3.68 | 10.6 | | | | 10.6 | 2.87 | 0.5 | 30 | 163 | 5.4 | 0.5 | Sum of DP 17 & DP 3.1 Piped to DP 3.3 |
| | 18 | B5 | 0.26 | 0.73 | 5.0 | 0.19 | 5.17 | 1.0 | | | | | | | | 1.0 | 0.19 | 1.0 | 8 | 40 | 3.8 | 0.2 | Roof drains Piped to DP 3.3 |
| | 3.3 | | | | | | | | 14.0 | 3.06 | 3.63 | 11.1 | | | | 11.1 | 3.06 | 1.9 | 30 | 75 | 8.8 | 0.1 | Sum of DP 18 & DP 3.2 Piped to DP 3.4 |
| | 19 | B6 | 0.73 | 0.56 | 7.1 | 0.41 | 4.65 | 1.9 | | | | | 0.8 | 0.17 | 1.1 | 1.1 | 0.24 | 1.0 | 18 | 445 | 1.6 | 4.7 | No. 16-valley inlet, Carryover flow to DP 27 Piped to DP 3.4 |
| | 3.4 | | | | | | | | 14.1 | 3.29 | 3.61 | 11.9 | | | | 11.9 | 3.29 | 1.0 | 30 | 29 | 7.2 | 0.1 | Sum of DP 19 & DP 3.3 Piped to DP 3.5 |
| | 20 | B7 | 0.47 | 0.37 | 7.0 | 0.17 | 4.66 | 0.8 | | | | | | | | 0.8 | 0.17 | 1.0 | 15 | 60 | 3.5 | 0.3 | Roof drains Piped to DP 3.5 |
| | 3.5 | | | | | | | | 14.2 | 3.46 | 3.60 | 12.5 | | | | 12.5 | 3.46 | 0.5 | 30 | 143 | 5.7 | 0.4 | Sum of DP 20 & DP 3.4 Piped to DP 3.6 |
| | 21 | B8 | 0.25 | 0.73 | 5.0 | 0.18 | 5.17 | 0.9 | | | | | | | | 0.9 | 0.18 | 1.0 | 15 | 10 | 3.6 | 0.0 | Roof drains Piped to DP 3.6 |
| | 3.6 | | | | | | | | 14.6 | 3.64 | 3.56 | 13.0 | | | | 13.0 | 3.64 | 0.5 | 30 | 191 | 5.8 | 0.6 | Sum of DP 21 & DP 3.5 Piped to DP 3.7 |
| | 22 | B9 | 0.19 | 0.73 | 5.0 | 0.14 | 5.17 | 0.7 | | | | | | | | 0.7 | 0.14 | 1.0 | 15 | 15 | 3.4 | 0.1 | Roof drains Piped to DP 3.7 |
| | 3.7 | | | | | | | | 15.2 | 3.78 | 3.50 | 13.3 | | | | 13.3 | 3.78 | 0.5 | 30 | 101 | 5.8 | 0.3 | Sum of DP 22 & DP 3.6 Piped to DP 3.8 |
| | 23 | B10 | 0.38 | 0.53 | 5.2 | 0.20 | 5.10 | 1.0 | | | | | | | | 1.0 | 0.20 | 2.0 | 18 | 15 | 4.7 | 0.1 | Sump Inlet Piped to DP 3.8 |
| | 3.8 | | | | | | | | 15.5 | 3.98 | 3.48 | 13.8 | | | | 13.8 | 3.98 | 0.5 | 36 | 46 | 5.8 | 0.1 | Sum of DP 23 & DP 3.7 Piped to DP 4.2 |
| | 24 | B13A | 0.48 | 0.23 | 9.4 | 0.11 | 4.22 | 0.5 | | | | | | | | 0.5 | 0.11 | 1.0 | 15 | 47 | 3.0 | 0.3 | Roof drains Piped to DP 3.9 |
| | 25 | B13 | 0.58 | 0.55 | 6.4 | 0.32 | 4.80 | 1.5 | | | | | 0.6 | 0.13 | 3.0 | 0.9 | 0.19 | 2.0 | 18 | 40 | 2.6 | 0.3 | No. 16-valley inlet, Carryover flow to DP 28 Piped to DP 3.9 |
| | 3.9 | | | | | | | | 9.7 | 0.30 | 4.18 | 1.2 | | | | 1.2 | 0.30 | 2.0 | 18 | 41 | 4.9 | 0.1 | Sum of DP 24 & DP 25 Piped to DP 4.1 |
| | 26 | B11 | 0.74 | 0.33 | 11.1 | 0.25 | 3.98 | 1.0 | | | | | | | | 1.0 | 0.25 | 1.0 | 15 | 39 | 3.7 | 0.2 | Roof drains Piped to DP 4.0 |
| | 27 | B12 | 1.08 | 0.58 | 9.2 | 0.63 | 4.25 | 2.7 | 11.8 | 0.80 | 3.89 | 3.1 | | | | 3.1 | 0.80 | 1.0 | 18 | 0 | 5.2 | 0.0 | Sump Inlet, sum of carryover from DP 19 and Sub-Basin B12 Piped to DP 4.0 |
| | 4.0 | | | | | | | | 11.8 | 1.05 | 3.89 | 4.1 | | | | 4.1 | 1.05 | 1.0 | 18 | 32 | 5.6 | 0.1 | Sum of DP 26 & DP 27 Piped to DP 4.1 |
| | 28 | B14 | 0.49 | 0.63 | 9.4 | 0.31 | 4.22 | 1.3 | 9.4 | 0.44 | 4.22 | 1.9 | | | | 1.9 | 0.44 | 1.2 | 18 | 12 | 4.8 | 0.0 | Sump Inlet, sum of carryover from DP 25 & Sub-Basin B14 Piped to DP 4.1 |

STANDARD FORM SF-3
STORM DRAINAGE SYSTEM DESIGN
(RATIONAL METHOD PROCEDURE)

ubdivision: Solace
 Location: El Paso County
 sign Storm: 5-Year

Project Name: Solace Apartments
 Project No.: 25174.00
 Calculated By: AAM
 Checked By:
 Date: 3/12/21

| STREET | Design Point | DIRECT RUNOFF | | | | | | | TOTAL RUNOFF | | | | STREET/SWALE | | | PIPE | | | | TRAVEL TIME | | | REMARKS |
|--------|--------------|---------------|-----------|---------------|----------------------|----------|-----------|---------|----------------------|----------|-----------|---------|---------------------------------|----------|-----------|-------------------------|----------|-----------|--------------------|-------------|----------------|--|---------|
| | | Basin ID | Area (Ac) | Runoff Coeff. | t _c (min) | C*A (Ac) | I (in/hr) | Q (cfs) | t _c (min) | C*A (ac) | I (in/hr) | Q (cfs) | Q _{street/swale} (cfs) | C*A (ac) | Slope (%) | Q _{pipe} (cfs) | C*A (ac) | Slope (%) | Pipe Size (inches) | Length (ft) | Velocity (fps) | t _r (min) | |
| | 4.1 | | | | | | | 11.9 | 1.79 | 3.87 | 6.9 | | | | 6.9 | 1.79 | 1.0 | 24 | 44 | 6.3 | 0.1 | Sum of DP 28, DP 3.9, & DP 4.0 Piped to DP 4.2 | |
| | 4.2 | | | | | | | 15.6 | 5.78 | 3.46 | 20.0 | | | | 20.0 | 5.78 | 0.5 | 36 | 158 | 6.4 | 0.4 | Sum of DP 3.8 & DP 4.1 Piped to DP 4.4 | |
| | 29 | B16 | 0.15 | 0.56 | 5.4 | 0.08 | 5.06 | 0.4 | | | | | | | 0.4 | 0.08 | 1.0 | 15 | 47 | 2.8 | 0.3 | Roof drains Piped to DP 4.3 | |
| | 30 | B15 | 0.27 | 0.71 | 5.7 | 0.19 | 4.96 | 0.9 | | | | | | | 0.9 | 0.19 | 2.0 | 18 | 0 | 4.6 | 0.0 | Sump Inlet Piped to DP 4.3 | |
| | 4.3 | | | | | | | 5.7 | 0.27 | 4.96 | 1.3 | | | | 1.3 | 0.27 | 2.0 | 18 | 34 | 5.1 | 0.1 | Sum of DP 29 & DP 30 Piped to DP 4.4 | |
| | 4.4 | | | | | | | 16.0 | 6.05 | 3.42 | 20.7 | | | | 20.7 | 6.05 | 0.8 | 36 | 311 | 7.7 | 0.7 | Sum of DP 4.2 & DP 4.3 Piped to DP 4.5 | |
| | 31 | B17 | 0.99 | 0.42 | 8.2 | 0.41 | 4.43 | 1.8 | | | | | | | 1.8 | 0.41 | 2.0 | 18 | 13 | 5.6 | 0.0 | On-grade inlet Piped to DP 4.5 | |
| | 4.5 | | | | | | | 16.7 | 6.46 | 3.36 | 21.7 | | | | 21.7 | 6.46 | 0.5 | 42 | 32 | 6.5 | 0.1 | Sum of DP 31 & DP 4.4 Piped to DP 2.6 | |
| | 32 | B18 | 0.47 | 0.50 | 7.2 | 0.23 | 4.62 | 1.1 | | | | | | | 1.1 | 0.23 | 0.5 | 42 | 0 | 2.7 | 0.0 | On-grade inlet Piped to DP 4.6 | |
| | 4.6 | | | | | | | 16.8 | 6.69 | 3.35 | 22.4 | | | | 22.4 | 6.69 | 0.5 | 42 | 52 | 6.6 | 0.1 | Sum of DP 32 & DP 4.5 Piped to DP 35 | |
| | 35 | | | | | | | 16.8 | 6.7 | 3.35 | 22.4 | 22.4 | 6.69 | 0.5 | | | | | 336 | 1.1 | 5.3 | Pond B forebay Trickle channel conveyance to DP 37 | |
| | 33 | B19 | 1.92 | 0.32 | 16.9 | 0.62 | 3.34 | 2.1 | | | | | | | 2.1 | 0.62 | 1.0 | 18 | 55 | 4.5 | 0.2 | On-grade Inlet Piped to DP 4.7 | |
| | 34 | B20 | 0.26 | 0.49 | 6.3 | 0.13 | 4.83 | 0.6 | | | | | | | 0.6 | 0.13 | 1.0 | 24 | 0 | 3.1 | 0.0 | On-grade Inlet Piped to DP 4.7 | |
| | 4.7 | | | | | | | 17.1 | 0.75 | 3.32 | 2.5 | | | | 2.5 | 0.75 | 1.0 | 24 | 52 | 4.7 | 0.2 | Sum of DP 33 & DP 34 Piped to DP 2.6 | |
| | 36 | | | | | | | 17.1 | 0.8 | 3.32 | 2.5 | 2.5 | 0.75 | 0.5 | | | | | 106 | 1.1 | 1.7 | Pond B forebay Trickle channel conveyance to DP 37 | |
| | 37 | B21 | 2.46 | 0.08 | 29.7 | 0.20 | 2.50 | 0.5 | | | | 0.5 | 0.20 | 2.18 | | | | | | | | Overland Flow Pond Conveyance to DP 37 | |
| | 37 | | | | | | | 22.0 | 7.64 | 2.94 | 22.5 | | | | | | | | | | | Pond outlet Structure Release detained flows into Sandcreek Drainageway | |
| | 38 | F6 | 0.35 | 0.08 | 5.3 | 0.03 | 5.07 | 0.2 | | | | 0.2 | 0.03 | 5.0 | | | | | 0 | 4.5 | 0.0 | Future overland flow Sheet flow offsite per historic condition | |
| | 39 | F7 | 0.53 | 0.08 | 6.9 | 0.04 | 4.69 | 0.2 | | | | 0.2 | 0.04 | 2.0 | | | | | 0 | 2.8 | 0.0 | Future overland flow Existing swale conveyance offsite per historic condition | |
| | 40 | C1 | 0.74 | 0.29 | 15.0 | 0.22 | 3.52 | 0.8 | | | | 0.8 | 0.22 | 1.0 | | | | | 183 | 2.0 | 1.5 | Future overland flow to DP 40 Existing swale conveyance offsite per historic condition | |
| | 41 | C2 | 0.80 | 0.08 | 6.3 | 0.06 | 4.83 | 0.3 | | | | 0.3 | 0.06 | 4.57 | | | | | 0 | 4.3 | 0.0 | Overland flow Sheet flow offsite per historic condition | |
| | 42 | D1 | 0.95 | 0.19 | 12.8 | 0.18 | 3.76 | 0.7 | | | | 0.7 | 0.18 | 3.3 | | | | | 0 | 3.6 | 0.0 | Overland flow Overflow channel to the Sandcreek Drainageway | |
| | 43 | OS1 | 17.73 | 0.59 | 15.1 | 10.46 | 3.51 | 36.7 | | | | 36.7 | 10.46 | 3.2 | | | | | 225 | 3.6 | 1.0 | Surface runoff from Basin OS1, captured by existing channel and proposed overflow channel at DP 43 Channel conveyance to Sand Creek at DP 5.1 | |
| | 44 | OS2 | 8.93 | 0.59 | 10.6 | 5.27 | 4.04 | 21.3 | | | | 21.3 | 5.27 | 3.2 | | | | | 147 | 2.7 | 0.9 | Surface runoff from Basin OS2 Diverted to swale west of site at DP 44 | |
| | 5.0 | - | - | - | - | - | - | | | | | | | | | | | | | | | 5-Year Flows were not analyzed as part of the Sand Creek Drainage Basin Planning Study. | |
| | 5.1 | - | - | - | - | - | - | | | | | | | | | | | | | | | 5-Year Flows were not analyzed as part of the Sand Creek Drainage Basin Planning Study. | |

STANDARD FORM SF-3
STORM DRAINAGE SYSTEM DESIGN
(RATIONAL METHOD PROCEDURE)

Subdivision: Solace
 Location: El Paso County
 Design Storm: 5-Year

Project Name: Solace Apartments
 Project No.: 25174.00
 Calculated By: AAM
 Checked By:
 Date: 3/12/21

| STREET | Design Point | DIRECT RUNOFF | | | | | | | TOTAL RUNOFF | | | | STREET/SWALE | | | PIPE | | | TRAVEL TIME | | | REMARKS | |
|--------|--------------|---------------|-----------|---------------|-------------|----------|-----------|---------|--------------|----------|-----------|---------|--------------------------|----------|-----------|------------------|----------|-----------|--------------------|-------------|----------------|---------|---|
| | | Basin ID | Area (Ac) | Runoff Coeff. | t_c (min) | C*A (Ac) | I (in/hr) | Q (cfs) | t_c (min) | C*A (ac) | I (in/hr) | Q (cfs) | $Q_{street/swale}$ (cfs) | C*A (ac) | Slope (%) | Q_{pipe} (cfs) | C*A (ac) | Slope (%) | Pipe Size (inches) | Length (ft) | Velocity (fps) | | t_r (min) |
| | 5.2 | - | - | - | - | - | - | | | | | | | | | | | | | | | | 5-Year Flows were not analyzed as part of the Sand Creek Drainage Basin Planning Study. |
| | 5.3 | - | - | - | - | - | - | | | | | | | | | | | | | | | | 5-Year Flows were not analyzed as part of the Sand Creek Drainage Basin Planning Study. |

Notes:
 Street and Pipe C*A values are determined by Q/I using the catchment's intensity value.
 All pipes are private and RCP unless otherwise noted. Pipe size shown in table column.

STANDARD FORM SF-3
STORM DRAINAGE SYSTEM DESIGN
(RATIONAL METHOD PROCEDURE)

Subdivision: Solace
 Location: El Paso County
 Design Storm: 100-Year

Project Name: Solace Apartments
 Project No.: 25174.00
 Calculated By: AAM
 Checked By:
 Date: 3/12/21

| Description | Design Point | DIRECT RUNOFF | | | | | | | TOTAL RUNOFF | | | | STREET/SWALE | | | PIPE | | | TRAVEL TIME | | | REMARKS | |
|-------------|--------------|---------------|-----------|---------------|----------------------|----------|-----------|---------|----------------------|----------|-----------|---------|---------------------------------|----------|-----------|-------------------------|----------|-----------|--------------------|-------------|----------------|--|---|
| | | Basin ID | Area (ac) | Runoff Coeff. | t _c (min) | C*A (ac) | I (in/hr) | Q (cfs) | t _c (min) | C*A (ac) | I (in/hr) | Q (cfs) | Q _{street/swale} (cfs) | C*A (ac) | Slope (%) | Q _{pipe} (cfs) | C*A (ac) | Slope (%) | Pipe Size (Inches) | Length (ft) | Velocity (fps) | | t _t (min) |
| | 1 | F1 | 0.92 | 0.67 | 7.5 | 0.62 | 7.66 | 4.7 | | | | | | | 4.7 | 0.62 | 1.0 | 18 | 320 | 5.8 | 0.9 | Future on-grade inlet Future pipe conveyance to DP 1.0 | |
| | 2 | F2 | 0.14 | 0.83 | 5.0 | 0.12 | 8.68 | 1.0 | | | | 1.0 | 0.12 | 2.18 | | | | | 33 | 3.0 | 0.2 | Future overland flow to DP 4 Infrastructure to South Detention Pond at DP 2 | |
| | 3 | F3 | 0.73 | 0.72 | 5.5 | 0.52 | 8.43 | 4.4 | | | | | | | 4.4 | 0.52 | 1.9 | 18 | 64 | 7.1 | 0.2 | Future sump inlet Future pipe conveyance to DP 1.0 | |
| | 4 | A1 | 0.50 | 0.81 | 5.7 | 0.40 | 8.35 | 3.3 | | | | 1.0 | 0.12 | 1.5 | 2.3 | 0.28 | 1.5 | 18 | 300 | 1.8 | 2.7 | On-grade inlet, Carryover flow to DP 11 Piped to DP 1.0 | |
| | 1.0 | | | | | | | 8.4 | 1.54 | 7.36 | 11.3 | | | | 11.3 | 1.54 | 2.1 | 36 | 221 | 9.0 | 0.4 | Sum of DP 1, DP 2, DP 3, & DP 4 Piped to DP 4P | |
| | 4P | | | | | | | 8.4 | 1.54 | 7.36 | 11.3 | 11.3 | 1.54 | 0.5 | | | | | 185 | 1.1 | 2.9 | Pond A Forebay Trickle channel conveyance to DP 6P | |
| | 5 | A2 | 0.47 | 0.82 | 6.2 | 0.38 | 8.14 | 3.1 | | | | 1.6 | 0.20 | 1.2 | 1.5 | 0.18 | 2.0 | 18 | 290 | 1.6 | 2.9 | No. 16-valley inlet, Carryover flow to DP 10 Piped to DP 2.2 | |
| | 6 | A3 | 0.45 | 0.82 | 5.9 | 0.37 | 8.26 | 3.1 | | | | 1.6 | 0.19 | 1.5 | 1.5 | 0.18 | 1.0 | 18 | 321 | 1.8 | 2.9 | No. 16-valley inlet, Carryover flow to DP 10 Piped to DP 2.0 | |
| | 7 | F4 | 0.68 | 0.51 | 11.3 | 0.35 | 6.63 | 2.3 | | | | | | | 2.3 | 0.35 | 1.0 | 15 | 27 | 4.8 | 0.1 | Future roof drains and area inlets Future pipe conveyance to DP 2.0 | |
| | 2.0 | | | | | | | 11.4 | 0.53 | 6.61 | 3.5 | | | | 3.5 | 0.53 | 1.0 | 18 | 14 | 5.3 | 0.0 | Sum of DP 6 & DP 7 Piped to DP 2.1 | |
| | 8 | A4 | 0.15 | 0.81 | 5.0 | 0.12 | 8.68 | 1.0 | | | | | | | 1.0 | 0.12 | 1.0 | 15 | 105 | 3.9 | 0.5 | Roof drains Piped to DP 2.1 | |
| | 2.1 | | | | | | | 11.4 | 0.65 | 6.60 | 4.3 | | | | 4.3 | 0.65 | 1.0 | 18 | 101 | 5.6 | 0.3 | Sum of DP 8 & DP 2.0 Piped to DP 2.2 | |
| | 2.2 | | | | | | | 11.7 | 0.84 | 6.54 | 5.5 | | | | 5.5 | 0.84 | 1.0 | 24 | 105 | 5.9 | 0.3 | Sum of DP 5 & DP 2.1 Piped to DP 2.3 | |
| | 9 | A5 | 0.13 | 0.81 | 5.0 | 0.11 | 8.68 | 1.0 | | | | | | | 1.0 | 0.11 | 1.0 | 15 | 7 | 3.7 | 0.0 | Roof drains Piped to DP 2.3 | |
| | 2.3 | | | | | | | 12.0 | 0.95 | 6.47 | 6.1 | | | | 6.1 | 0.95 | 1.3 | 24 | 114 | 6.6 | 0.3 | Sum of DP 9 & DP 2.2 Piped to DP 2.4 | |
| | 10 | A6 | 1.51 | 0.68 | 10.5 | 1.03 | 6.82 | 7.0 | 10.5 | 1.41 | 6.82 | 9.6 | | | 9.6 | 1.41 | 1.3 | 24 | 0 | 7.6 | 0.0 | Sump Inlet, Sum of Carryover flows from DP 5, DP 6, and Sub-Basin A6 Piped to DP 2.4 | |
| | 2.4 | | | | | | | 12.3 | 2.36 | 6.41 | 15.1 | | | | 15.1 | 2.36 | 2.0 | 30 | 31 | 9.8 | 0.1 | Sum of DP 9 & DP 2.2 Piped to DP 2.5 | |
| | 11 | A7 | 0.58 | 0.60 | 10.6 | 0.35 | 6.79 | 2.4 | 10.6 | 0.47 | 6.79 | 3.2 | | | 3.2 | 0.47 | 2.0 | 30 | 0 | 6.4 | 0.0 | On-grade Inlet, Sum of carryover from DP 4 and Sub-Basin A7 Piped to DP 2.5 | |
| | 2.5 | | | | | | | 12.3 | 2.83 | 6.40 | 18.2 | | | | 18.2 | 2.83 | 2.0 | 36 | 44 | 10.2 | 0.1 | Sum of DP 11 & DP 2.4 Piped to DP 2.6 | |
| | 12 | A8 | 0.30 | 0.68 | 5.9 | 0.20 | 8.27 | 1.7 | | | | | | | 1.7 | 0.20 | 2.0 | 30 | 0 | 5.2 | 0.0 | On-grade inlet Piped to DP 2.6 | |
| | 2.6 | | | | | | | 12.4 | 3.03 | 6.39 | 19.4 | | | | 19.4 | 3.03 | 2.4 | 36 | 55 | 11.2 | 0.1 | Sum of DP 12 & DP 2.5 Piped to DP 5P | |
| | 5P | | | | | | | 12.4 | 3.03 | 6.39 | 19.4 | 19.4 | 3.03 | 0.5 | | | | | 45 | 1.1 | 0.7 | Pond A Forebay Trickle channel conveyance to DP 6P | |
| | 6P | A9 | 1.33 | 0.35 | 13.9 | 0.47 | 6.11 | 2.9 | | | | 2.9 | 0.47 | 2.18 | | | | | | | | Overland Flow Pond Conveyance to DP 6P | |
| | 6P | | | | | | | 13.9 | 5.04 | 6.11 | 30.8 | | | | | | | | | | | Pond outlet Structure Release detained flows into Sandcreek Drainageway | |
| | 13 | F5 | 2.00 | 0.59 | 9.7 | 1.18 | 7.00 | 8.3 | | | | 8.3 | 1.18 | 1.2 | | | | | 170 | 1.3 | 2.2 | Future Phase 2 developed flows minus roof drains and future area inlet flows Pan conveyance to DP 14 | |
| | 14 | B1 | 0.37 | 0.83 | 5.1 | 0.31 | 8.61 | 2.7 | 11.9 | 1.49 | 6.50 | 9.7 | 7.0 | 1.07 | 1.1 | 2.7 | 0.42 | 1.0 | 18 | 89 | 1.6 | 0.9 | Sum of carryover flows from DP 13 and Sub-Basin B1, No. 16-valley inlet, Carryover flow to DP 16 Piped to DP 3.0 |
| | 3.0 | | | | | | | 11.9 | 1.40 | 6.50 | 9.1 | | | | 9.1 | 1.40 | 1.0 | 18 | 89 | 6.7 | 0.2 | Flows captured by No. 16-Valley inlet and future building and area drains connecting directly to inlet. Piped to DP 3.1 | |

STANDARD FORM SF-3
STORM DRAINAGE SYSTEM DESIGN
(RATIONAL METHOD PROCEDURE)

Subdivision: Solace
 Location: El Paso County
 Design Storm: 100-Year

Project Name: Solace Apartments
 Project No.: 25174.00
 Calculated By: AAM
 Checked By:
 Date: 3/12/21

| Description | Design Point | DIRECT RUNOFF | | | | | | | TOTAL RUNOFF | | | | STREET/SWALE | | | PIPE | | | TRAVEL TIME | | | REMARKS | |
|-------------|--------------|---------------|-----------|---------------|----------------------|----------|-----------|---------|----------------------|----------|-----------|---------|---------------------------------|----------|-----------|-------------------------|----------|-----------|--------------------|-------------|----------------|--|---|
| | | Basin ID | Area (ac) | Runoff Coeff. | t _c (min) | C*A (ac) | I (in/hr) | Q (cfs) | t _c (min) | C*A (ac) | I (in/hr) | Q (cfs) | Q _{street/swale} (cfs) | C*A (ac) | Slope (%) | Q _{pipe} (cfs) | C*A (ac) | Slope (%) | Pipe Size (inches) | Length (ft) | Velocity (fps) | | t _t (min) |
| | 15 | B2 | 0.35 | 0.93 | 5.0 | 0.32 | 8.68 | 2.8 | | | | | | | 2.8 | 0.32 | 2.0 | 18 | 75 | 6.4 | 0.2 | On-grade inlet Piped to DP 3.1 | |
| | 16 | B3 | 0.35 | 0.79 | 5.0 | 0.28 | 8.68 | 2.4 | 12.8 | 1.35 | 6.31 | 8.5 | 0.3 | 0.05 | 1.1 | 8.2 | 1.30 | 1.0 | 18 | 89 | 1.6 | 0.9 | Sum of carryover flow from DP 14 and Sub-Basin B3, On-grade inlet. Carryover flow to DP 19 Piped to DP 3.1 |
| | 3.1 | | | | | | | | 12.8 | 3.02 | 6.31 | 19.0 | | | 19.0 | 3.02 | 0.5 | 30 | 30 | 6.3 | 0.1 | Sum of DP 14, DP 15 & DP 16 Piped to DP 3.2 | |
| | 17 | B4 | 0.03 | 0.81 | 5.0 | 0.02 | 8.68 | 0.2 | | | | | | | 0.2 | 0.02 | 1.0 | 8 | 40 | 2.3 | 0.3 | Roof drains Piped to DP 3.2 | |
| | 3.2 | | | | | | | | 12.9 | 3.04 | 6.29 | 19.1 | | | 19.1 | 3.04 | 0.5 | 30 | 163 | 6.3 | 0.4 | Sum of DP 17 & DP 3.1 Piped to DP 3.3 | |
| | 18 | B5 | 0.26 | 0.81 | 5.0 | 0.21 | 8.68 | 1.8 | | | | | | | 1.8 | 0.21 | 1.0 | 8 | 40 | 5.2 | 0.1 | Roof drains Piped to DP 3.3 | |
| | 3.3 | | | | | | | | 13.3 | 3.25 | 6.21 | 20.2 | | | 20.2 | 3.25 | 1.9 | 30 | 75 | 10.4 | 0.1 | Sum of DP 18 & DP 3.2 Piped to DP 3.4 | |
| | 19 | B6 | 0.73 | 0.71 | 7.1 | 0.52 | 7.81 | 4.1 | 8.0 | 0.57 | 7.50 | 4.3 | 2.5 | 0.33 | 1.1 | 1.8 | 0.24 | 1.0 | 18 | 445 | 1.6 | 4.7 | No. 16-valley inlet, Carryover flow to DP 27 Piped to DP 3.4 |
| | 3.4 | | | | | | | | 13.5 | 3.49 | 6.19 | 21.6 | | | 21.6 | 3.49 | 1.0 | 30 | 29 | 8.5 | 0.1 | Sum of DP 19 & DP 3.3 Piped to DP 3.5 | |
| | 20 | B7 | 0.47 | 0.56 | 7.0 | 0.26 | 7.83 | 2.0 | | | | | | | 2.0 | 0.26 | 1.0 | 15 | 60 | 4.6 | 0.2 | Roof drains Piped to DP 3.5 | |
| | 3.5 | | | | | | | | 13.5 | 3.75 | 6.17 | 23.2 | | | 23.2 | 3.75 | 0.5 | 30 | 143 | 6.6 | 0.4 | Sum of DP 20 & DP 3.4 Piped to DP 3.6 | |
| | 21 | B8 | 0.25 | 0.81 | 5.0 | 0.20 | 8.68 | 1.7 | | | | | | | 1.7 | 0.20 | 1.0 | 15 | 10 | 4.4 | 0.0 | Roof drains Piped to DP 3.6 | |
| | 3.6 | | | | | | | | 13.9 | 3.95 | 6.11 | 24.1 | | | 24.1 | 3.95 | 0.5 | 30 | 191 | 6.6 | 0.5 | Sum of DP 21 & DP 3.5 Piped to DP 3.7 | |
| | 22 | B9 | 0.19 | 0.81 | 5.0 | 0.15 | 8.68 | 1.3 | | | | | | | 1.3 | 0.15 | 1.0 | 15 | 15 | 4.0 | 0.1 | Roof drains Piped to DP 3.7 | |
| | 3.7 | | | | | | | | 14.4 | 4.10 | 6.02 | 24.7 | | | 24.7 | 4.10 | 0.5 | 30 | 101 | 6.7 | 0.3 | Sum of DP 22 & DP 3.6 Piped to DP 3.8 | |
| | 23 | B10 | 0.38 | 0.69 | 5.2 | 0.26 | 8.56 | 2.2 | | | | | | | 2.2 | 0.26 | 2.0 | 18 | 15 | 5.9 | 0.0 | Sump Inlet Piped to DP 3.8 | |
| | 3.8 | | | | | | | | 14.6 | 4.36 | 5.98 | 26.1 | | | 26.1 | 4.36 | 0.5 | 36 | 46 | 6.9 | 0.1 | Sum of DP 23 & DP 3.7 Piped to DP 4.2 | |
| | 24 | B13A | 0.48 | 0.46 | 9.4 | 0.22 | 7.08 | 1.6 | | | | | | | 1.6 | 0.22 | 1.0 | 15 | 47 | 4.3 | 0.2 | Roof drains Piped to DP 3.9 | |
| | 25 | B13 | 0.58 | 0.70 | 6.4 | 0.40 | 8.06 | 3.2 | | | | | 1.7 | 0.21 | 3.0 | 1.5 | 0.19 | 2.0 | 18 | 40 | 2.6 | 0.3 | No. 16-valley inlet, Carryover flow to DP 28 Piped to DP 3.9 |
| | 3.9 | | | | | | | | 9.6 | 0.41 | 7.04 | 2.9 | | | 2.9 | 0.41 | 2.0 | 18 | 41 | 6.4 | 0.1 | Sum of DP 24 & DP 25 Piped to DP 4.1 | |
| | 26 | B11 | 0.74 | 0.53 | 11.1 | 0.39 | 6.68 | 2.6 | | | | | | | 2.6 | 0.39 | 1.0 | 15 | 39 | 4.9 | 0.1 | Roof drains Piped to DP 4.0 | |
| | 27 | B12 | 1.08 | 0.72 | 9.2 | 0.78 | 7.13 | 5.6 | 12.7 | 1.11 | 6.33 | 7.1 | | | 7.1 | 1.11 | 1.0 | 18 | 0 | 6.4 | 0.0 | Sump Inlet, sum of carryover from DP 19 and Sub-Basin B12 Piped to DP 4.0 | |
| | 4.0 | | | | | | | | 12.7 | 1.50 | 6.33 | 9.5 | | | 9.5 | 1.50 | 1.0 | 18 | 32 | 6.7 | 0.1 | Sum of DP 26 & DP 27 Piped to DP 4.1 | |
| | 28 | B14 | 0.49 | 0.76 | 9.4 | 0.37 | 7.08 | 2.6 | 9.4 | 0.58 | 7.08 | 4.1 | | | 4.1 | 0.58 | 1.2 | 18 | 12 | 5.9 | 0.0 | Sump Inlet, sum of carryover from DP 25 & Sub-Basin B14 Piped to DP 4.1 | |
| | 4.1 | | | | | | | | 12.8 | 2.49 | 6.31 | 15.7 | | | 15.7 | 2.49 | 1.0 | 24 | 44 | 7.8 | 0.1 | Sum of DP 28, DP 3.9, & DP 4.0 Piped to DP 4.2 | |
| | 4.2 | | | | | | | | 14.7 | 6.85 | 5.96 | 40.8 | | | 40.8 | 6.85 | 0.5 | 36 | 158 | 7.5 | 0.4 | Sum of DP 3.8 & DP 4.1 Piped to DP 4.4 | |
| | 29 | B16 | 0.15 | 0.69 | 5.4 | 0.10 | 8.49 | 0.8 | | | | | | | 0.8 | 0.10 | 1.0 | 15 | 47 | 3.6 | 0.2 | Roof drains Piped to DP 4.3 | |

STANDARD FORM SF-3
STORM DRAINAGE SYSTEM DESIGN
(RATIONAL METHOD PROCEDURE)

Subdivision: Solace
 Location: El Paso County
 Design Storm: 100-Year

Project Name: Solace Apartments
 Project No.: 25174.00
 Calculated By: AAM
 Checked By:
 Date: 3/12/21

| Description | Design Point | DIRECT RUNOFF | | | | | | | TOTAL RUNOFF | | | | STREET/SWALE | | | PIPE | | | TRAVEL TIME | | | REMARKS |
|-------------|--------------|---------------|-----------|---------------|----------------------|----------|-----------|---------|----------------------|----------|-----------|---------|---------------------------------|----------|-----------|-------------------------|----------|-----------|--------------------|-------------|----------------|--|
| | | Basin ID | Area (ac) | Runoff Coeff. | t _c (min) | C*A (ac) | I (in/hr) | Q (cfs) | t _c (min) | C*A (ac) | I (in/hr) | Q (cfs) | Q _{street/swale} (cfs) | C*A (ac) | Slope (%) | Q _{pipe} (cfs) | C*A (ac) | Slope (%) | Pipe Size (Inches) | Length (ft) | Velocity (fps) | |
| | 30 | B15 | 0.27 | 0.81 | 5.7 | 0.22 | 8.33 | 1.8 | | | | | | | 1.8 | 0.22 | 2.0 | 18 | 0 | 5.6 | 0.0 | Sump Inlet Piped to DP 4.3 |
| | 4.3 | | | | | | | | 5.7 | 0.32 | 8.33 | 2.7 | | | 2.7 | 0.32 | 2.0 | 18 | 34 | 6.4 | 0.1 | Sum of DP 29 & DP 30 Piped to DP 4.4 |
| | 4.4 | | | | | | | | 15.1 | 7.17 | 5.90 | 42.3 | | | 42.3 | 7.17 | 0.8 | 36 | 311 | 9.1 | 0.6 | Sum of DP 4.2 & DP 4.3 Piped to DP 4.5 |
| | 31 | B17 | 0.99 | 0.60 | 8.2 | 0.60 | 7.43 | 4.5 | | | | 0.2 | 0.02 | 1.0 | 4.3 | 0.58 | 2.0 | 18 | 292 | 1.5 | 3.2 | On-grade inlet, carryover flow to DP 33 Piped to DP 4.5 |
| | 4.5 | | | | | | | | 15.6 | 7.75 | 5.81 | 45.0 | | | 45.0 | 7.75 | 0.5 | 42 | 32 | 7.8 | 0.1 | Sum of DP 31 & DP 4.4 Piped to DP 2.6 |
| | 32 | B18 | 0.47 | 0.66 | 7.2 | 0.31 | 7.75 | 2.4 | | | | | | | 2.4 | 0.31 | 0.5 | 42 | 0 | 3.4 | 0.0 | On-grade inlet Piped to DP 4.6 |
| | 4.6 | | | | | | | | 15.7 | 8.06 | 5.80 | 46.7 | | | 46.7 | 8.06 | 0.5 | 42 | 52 | 7.9 | 0.1 | Sum of DP 32 & DP 4.5 Piped to DP 35 |
| | 35 | | | | | | | | 15.7 | 8.1 | 5.8 | 46.7 | 46.7 | 8.06 | 0.5 | | | | 336 | 1.1 | 5.3 | Pond B forebay Trickle channel conveyance to DP 37 |
| | 33 | B19 | 1.92 | 0.53 | 16.9 | 1.01 | 5.60 | 5.7 | 16.9 | 1.03 | 5.60 | 5.8 | | | 5.8 | 1.03 | 1.0 | 18 | 55 | 6.0 | 0.2 | Sum of carryover from DP 31 and Sub-basin B19, On-grade Inlet Piped to DP 4.7 |
| | 34 | B20 | 0.26 | 0.66 | 6.3 | 0.17 | 8.12 | 1.4 | | | | | | | 1.4 | 0.17 | 1.0 | 24 | 0 | 3.9 | 0.0 | On-grade Inlet Piped to DP 4.7 |
| | 4.7 | | | | | | | | 17.1 | 1.20 | 5.58 | 6.7 | | | 6.7 | 1.20 | 1.0 | 24 | 52 | 6.2 | 0.1 | Sum of DP 33 & DP 34 Piped to DP 2.6 |
| | 36 | | | | | | | | 17.1 | 1.2 | 5.6 | 6.7 | 6.7 | 1.20 | 0.5 | | | | 106 | 1.1 | 1.7 | Pond B forebay Trickle channel conveyance to DP 37 |
| | 37 | B21 | 2.46 | 0.35 | 29.7 | 0.86 | 4.19 | 3.6 | | | | 3.6 | 0.86 | 2.18 | | | | | | | | Overland Flow Pond Conveyance to DP 37 |
| | 37 | | | | | | | | 21.0 | 10.12 | 5.06 | 51.3 | | | | | | | | | | Pond outlet Structure Release detained flows into Sandcreek Drainageway |
| | 38 | F6 | 0.35 | 0.35 | 5.3 | 0.12 | 8.52 | 1.0 | | | | 1.0 | 0.12 | 5.0 | | | | | 0 | 4.5 | 0.0 | Future overland flow Sheet flow offsite per historic condition |
| | 39 | F7 | 0.53 | 0.35 | 6.9 | 0.19 | 7.87 | 1.5 | | | | 1.5 | 0.19 | 2.0 | | | | | 0 | 2.8 | 0.0 | Future overland flow Existing swale conveyance offsite per historic condition |
| | 40 | C1 | 0.74 | 0.51 | 15.0 | 0.37 | 5.91 | 2.2 | | | | 2.2 | 0.37 | 1.0 | | | | | 183 | 2.0 | 1.5 | Future overland flow to DP 40 Existing swale conveyance offsite per historic condition |
| | 41 | C2 | 0.80 | 0.35 | 6.3 | 0.28 | 8.12 | 2.3 | | | | 2.3 | 0.28 | 4.57 | | | | | 0 | 4.3 | 0.0 | Overland flow Sheet flow offsite per historic condition |
| | 42 | D1 | 0.95 | 0.43 | 12.8 | 0.41 | 6.31 | 2.6 | | | | 2.6 | 0.41 | 3.3 | | | | | 0 | 3.6 | 0.0 | Overland flow Overflow channel to the Sandcreek Drainageway |
| | 43 | OS1 | 17.73 | 0.70 | 15.1 | 12.41 | 5.89 | 73.1 | | | | 73.1 | 12.41 | 3.2 | | | | | 225 | 3.6 | 1.0 | Surface runoff from Basin OS1, captured by existing channel and proposed overflow channel at DP 43 Channel conveyance to Sand Creek at DP 5.1 |
| | 44 | OS2 | 8.93 | 0.70 | 10.6 | 6.25 | 6.78 | 42.4 | | | | 42.4 | 6.25 | 3.2 | | | | | 147 | 2.7 | 0.9 | Surface runoff from Basin OS2 Diverted to swale west of site at DP 44 |
| | 5.0 | - | - | - | - | - | - | 820.0 | | | | 820.0 | | | | | | | | | | Flow taken directly from the Sand Creek Drainage Basin Planning Study |
| | 5.1 | - | - | - | - | - | - | 820.0 | | | | 820.0 | | | | | | | | | | Flow taken directly from the Sand Creek Drainage Basin Planning Study |
| | 5.2 | - | - | - | - | - | - | 1037.0 | | | | 1037.0 | | | | | | | | | | Flow taken directly from the Sand Creek Drainage Basin Planning Study |
| | 5.3 | - | - | - | - | - | - | 1100.0 | | | | 1100.0 | | | | | | | | | | Flow taken directly from the Sand Creek Drainage Basin Planning Study |

Notes:
 Street and Pipe C*A values are determined by Q/I using the catchment's intensity value.
 All pipes are private and RCP unless otherwise noted. Pipe size shown in table column.

Scenario: 5 year
Current Time Step: 0.000 h
Conduit FlexTable: Combined Pipe/Node Report

| Upstream Structure | Label | Flow (cfs) | Diameter (in) | Slope (Calculated) (ft/ft) | Invert (Start) (ft) | Invert (Stop) (ft) | Elevation Ground (Start) (ft) | Elevation Ground (Stop) (ft) | Hydraulic Grade Line (In) (ft) | Hydraulic Grade Line (Out) (ft) | Energy Grade Line (In) (ft) | Energy Grade Line (Out) (ft) | Velocity (ft/s) | Upstream Structure Headloss Coefficient | Length (User Defined) (ft) |
|--------------------------|---------------------|------------|---------------|----------------------------|---------------------|--------------------|-------------------------------|------------------------------|--------------------------------|---------------------------------|-----------------------------|------------------------------|-----------------|---|----------------------------|
| DP09-2 | CO-1 | 2.10 | 12.0 | 0.010 | 6,263.75 | 6,263.66 | 6,267.82 | 6,268.25 | 6,264.37 | 6,264.34 | 6,264.63 | 6,264.55 | 4.76 | 1.000 | 8.8 |
| DP09-1 | CO-2 | 2.10 | 12.0 | 0.010 | 6,263.46 | 6,262.84 | 6,268.25 | 6,267.71 | 6,264.08 | 6,263.91 | 6,264.34 | 6,264.02 | 4.71 | 1.000 | 62.5 |
| DP01-2 | P01-1 | 22.40 | 42.0 | 0.005 | 6,246.24 | 6,245.98 | 6,252.97 | 6,249.87 | 6,247.69 | 6,247.33 | 6,248.24 | 6,248.00 | 6.55 | 0.050 | 52.0 |
| DP01-11 | P01-10 | 11.90 | 30.0 | 0.010 | 6,255.56 | 6,253.84 | 6,262.02 | 6,260.91 | 6,256.72 | 6,255.06 | 6,257.16 | 6,255.45 | 7.24 | 1.020 | 171.7 |
| DP01-12 | P01-11 | 11.10 | 24.0 | 0.010 | 6,256.81 | 6,256.06 | 6,264.38 | 6,262.02 | 6,258.00 | 6,257.05 | 6,258.50 | 6,257.85 | 7.18 | 0.050 | 74.6 |
| DP01-13 | P01-12 | 10.60 | 24.0 | 0.010 | 6,258.65 | 6,257.01 | 6,265.62 | 6,264.38 | 6,259.82 | 6,257.97 | 6,260.30 | 6,258.75 | 7.09 | 0.640 | 163.6 |
| DP01-14 | P01-13 | 10.50 | 24.0 | 0.010 | 6,259.07 | 6,258.85 | 6,265.81 | 6,265.62 | 6,260.23 | 6,260.13 | 6,260.71 | 6,260.51 | 7.09 | 1.020 | 21.8 |
| DP01-15 | P01-14 | 9.60 | 18.0 | 0.010 | 6,259.32 | 6,259.20 | 6,265.70 | 6,265.81 | 6,260.82 | 6,260.72 | 6,261.28 | 6,261.18 | 6.74 | 0.050 | 11.8 |
| DP01-16 | P01-15 | 6.40 | 18.0 | 0.010 | 6,260.28 | 6,259.59 | 6,265.15 | 6,265.70 | 6,261.26 | 6,260.84 | 6,261.69 | 6,261.10 | 6.23 | 0.000 | 69.2 |
| DP01-3 | P01-2 | 21.70 | 42.0 | 0.005 | 6,246.60 | 6,246.44 | 6,252.79 | 6,252.97 | 6,248.03 | 6,247.78 | 6,248.57 | 6,248.42 | 6.48 | 1.020 | 32.2 |
| DP01-4 | P01-3 | 20.70 | 36.0 | 0.007 | 6,248.21 | 6,246.80 | 6,255.53 | 6,252.79 | 6,249.67 | 6,248.58 | 6,250.24 | 6,248.93 | 7.49 | 1.320 | 188.4 |
| DP01-5 | P01-4 | 20.70 | 36.0 | 0.005 | 6,249.02 | 6,248.41 | 6,257.20 | 6,255.53 | 6,250.48 | 6,250.42 | 6,251.05 | 6,250.69 | 6.44 | 1.020 | 122.5 |
| DP01-6 | P01-5 | 20.00 | 36.0 | 0.005 | 6,250.01 | 6,249.22 | 6,257.99 | 6,257.20 | 6,251.45 | 6,251.06 | 6,252.00 | 6,251.36 | 6.40 | 1.020 | 158.1 |
| DP01-7 | P01-6 | 13.80 | 36.0 | 0.010 | 6,250.87 | 6,250.41 | 6,258.31 | 6,257.99 | 6,252.05 | 6,252.01 | 6,252.49 | 6,252.21 | 7.44 | 1.020 | 46.0 |
| DP01-8 | P01-7 | 13.30 | 30.0 | 0.005 | 6,251.88 | 6,251.37 | 6,259.77 | 6,258.31 | 6,253.11 | 6,252.56 | 6,253.59 | 6,253.08 | 5.80 | 0.400 | 101.1 |
| DP01-9 | P01-8 | 13.00 | 30.0 | 0.005 | 6,252.23 | 6,252.08 | 6,258.40 | 6,259.77 | 6,253.44 | 6,253.30 | 6,253.91 | 6,253.76 | 5.75 | 0.400 | 30.0 |
| DP01-10 | P01-9 | 13.00 | 30.0 | 0.008 | 6,253.64 | 6,252.43 | 6,260.91 | 6,258.40 | 6,254.85 | 6,253.48 | 6,255.32 | 6,254.17 | 6.68 | 0.450 | 161.0 |
| DP02-2 | P02-1 | 8.60 | 24.0 | 0.030 | 6,255.29 | 6,253.65 | 6,262.08 | 6,256.99 | 6,256.34 | 6,254.31 | 6,256.75 | 6,255.72 | 9.98 | 0.050 | 54.9 |
| DP02-3 | P02-2 | 8.10 | 24.0 | 0.010 | 6,256.39 | 6,256.94 | 6,262.08 | 6,262.08 | 6,257.40 | 6,256.78 | 6,257.80 | 6,257.43 | 6.64 | 0.050 | 44.3 |
| DP02-4 | P02-3 | 7.10 | 18.0 | 0.010 | 6,257.20 | 6,256.89 | 6,262.72 | 6,262.08 | 6,258.23 | 6,257.81 | 6,258.70 | 6,258.42 | 6.36 | 0.100 | 31.2 |
| DP02-5 | P02-4 | 3.10 | 18.0 | 0.010 | 6,258.54 | 6,257.40 | 6,264.18 | 6,262.72 | 6,259.21 | 6,258.28 | 6,259.47 | 6,258.41 | 5.18 | 0.100 | 113.6 |
| DP02-6 | P02-5 | 2.80 | 18.0 | 0.010 | 6,259.78 | 6,258.74 | 6,266.02 | 6,264.18 | 6,260.42 | 6,259.27 | 6,260.66 | 6,259.66 | 5.02 | 0.520 | 104.5 |
| DP02-7 | P02-6 | 2.10 | 18.0 | 0.010 | 6,260.42 | 6,259.98 | 6,265.64 | 6,266.02 | 6,260.97 | 6,260.54 | 6,261.17 | 6,260.73 | 4.66 | 0.400 | 43.6 |
| DP02-8 | P02-7 | 2.10 | 18.0 | 0.010 | 6,261.19 | 6,260.62 | 6,267.06 | 6,265.64 | 6,261.74 | 6,261.07 | 6,261.94 | 6,261.41 | 4.65 | 0.050 | 56.6 |
| DP02-9 | P02-8 | 1.60 | 18.0 | 0.010 | 6,261.55 | 6,261.39 | 6,266.82 | 6,267.06 | 6,262.02 | 6,261.79 | 6,262.20 | 6,262.07 | 4.30 | 0.000 | 15.9 |
| DP03-2 | P03-1 | 4.30 | 18.0 | 0.031 | 6,259.72 | 6,255.40 | 6,267.19 | 6,258.76 | 6,260.52 | 6,255.89 | 6,260.83 | 6,257.03 | 8.58 | 0.400 | 137.2 |
| DP03-3 | P03-2 | 4.30 | 18.0 | 0.010 | 6,261.36 | 6,260.52 | 6,266.61 | 6,267.19 | 6,262.16 | 6,261.19 | 6,262.47 | 6,261.68 | 5.64 | 1.520 | 84.2 |
| DP03-4 | P03-3(1) | 2.20 | 18.0 | 0.010 | 6,264.44 | 6,262.84 | 6,269.46 | 6,267.71 | 6,265.00 | 6,263.91 | 6,265.21 | 6,263.95 | 4.70 | 0.050 | 160.0 |
| MH-5 | P03-3(2) | 4.30 | 18.0 | 0.010 | 6,262.64 | 6,261.56 | 6,267.71 | 6,266.61 | 6,263.44 | 6,262.64 | 6,263.75 | 6,262.79 | 5.72 | 1.500 | 104.2 |
| DP03-5 | P03-4 | 2.20 | 18.0 | 0.010 | 6,265.17 | 6,264.64 | 6,270.32 | 6,269.46 | 6,265.73 | 6,265.11 | 6,265.94 | 6,265.45 | 4.69 | 0.000 | 53.3 |
| DP04-1 | P04-1 | 6.90 | 24.0 | 0.010 | 6,251.65 | 6,251.21 | 6,256.47 | 6,257.99 | 6,252.58 | 6,251.98 | 6,252.94 | 6,252.58 | 6.32 | 1.520 | 44.0 |
| DP04-2 | P04-2 | 1.20 | 18.0 | 0.010 | 6,252.26 | 6,251.85 | 6,257.41 | 6,256.47 | 6,253.13 | 6,253.13 | 6,253.15 | 6,253.14 | 3.95 | 0.000 | 41.0 |
| DP05-1 | P05-1 | 1.60 | 18.0 | 0.015 | 6,261.02 | 6,260.02 | 6,265.37 | 6,265.81 | 6,261.50 | 6,260.72 | 6,261.67 | 6,260.78 | 4.95 | 0.400 | 66.9 |
| DP05-2 | P05-2 | 1.60 | 18.0 | 0.020 | 6,261.70 | 6,261.22 | 6,266.72 | 6,265.37 | 6,262.18 | 6,261.56 | 6,262.35 | 6,262.00 | 5.49 | 0.000 | 24.1 |
| DP06-1 | P06-1 | 4.10 | 18.0 | 0.020 | 6,252.49 | 6,251.85 | 6,257.48 | 6,256.47 | 6,253.27 | 6,253.13 | 6,253.57 | 6,253.23 | 7.18 | 0.000 | 32.0 |
| DP07-1 | P07-1 | 1.90 | 18.0 | 0.020 | 6,252.09 | 6,251.85 | 6,256.68 | 6,256.47 | 6,253.12 | 6,253.13 | 6,253.15 | 6,253.15 | 5.76 | 0.000 | 12.1 |
| DP08-1 | P08-01 | 1.00 | 18.0 | 0.020 | 6,261.57 | 6,260.91 | 6,266.14 | 6,266.02 | 6,261.94 | 6,261.17 | 6,262.08 | 6,261.53 | 4.79 | 0.000 | 33.0 |
| DP10-1 | P10-1 | 0.00 | 18.0 | 0.050 | 6,261.97 | 6,261.60 | 6,266.90 | 6,266.61 | 6,262.64 | 6,262.64 | 6,262.64 | 6,262.64 | 0.00 | 0.000 | 7.4 |
| DP11-2 | P11-1 | 2.50 | 18.0 | 0.007 | 6,245.02 | 6,244.65 | 6,250.01 | 6,246.66 | 6,245.75 | 6,245.77 | 6,245.88 | 6,245.82 | 4.38 | 0.050 | 49.8 |
| DP11-3 | P11-2 | 2.10 | 18.0 | 0.008 | 6,245.65 | 6,245.22 | 6,249.80 | 6,250.01 | 6,246.20 | 6,245.70 | 6,246.40 | 6,245.99 | 4.26 | 0.000 | 54.4 |
| DP12-1 | P12-1 | 1.80 | 18.0 | 0.020 | 6,248.05 | 6,247.80 | 6,252.95 | 6,252.79 | 6,248.55 | 6,248.58 | 6,248.74 | 6,248.64 | 5.68 | 0.000 | 12.6 |
| DP13-1 | P13-1 | 1.30 | 18.0 | 0.040 | 6,251.86 | 6,250.52 | 6,256.31 | 6,257.20 | 6,252.29 | 6,251.06 | 6,252.44 | 6,251.14 | 6.59 | 0.000 | 33.6 |
| DP14-1 | P14-1 | 1.00 | 18.0 | 0.040 | 6,252.89 | 6,252.37 | 6,257.83 | 6,258.31 | 6,253.26 | 6,252.60 | 6,253.40 | 6,253.11 | 6.12 | 0.000 | 12.9 |
| DP15-1 | P15-1 | 1.10 | 18.0 | 0.067 | 6,257.43 | 6,256.56 | 6,261.74 | 6,262.02 | 6,257.82 | 6,257.17 | 6,257.96 | 6,257.21 | 7.52 | 0.000 | 13.0 |
| Structure - (81) (STORM) | Pipe - (66) (STORM) | 2.70 | 36.0 | 0.010 | 6,243.00 | 6,242.44 | 6,247.85 | 6,245.78 | 6,243.51 | 6,242.85 | 6,243.69 | 6,243.18 | 4.61 | 0.000 | 56.3 |
| Structure - (93) (STORM) | Pipe - (75) (STORM) | 1.30 | 36.0 | 0.010 | 6,250.10 | 6,249.18 | 6,257.50 | 6,252.53 | 6,250.45 | 6,249.47 | 6,250.57 | 6,249.68 | 3.71 | 0.000 | 92.0 |


X:\2510000.all\2517400\StormCAD\Solace.stsw

Scenario: 100 year
Current Time Step: 0.000 h
Conduit FlexTable: Combined Pipe/Node Report


| Upstream Structure | Label | Flow (cfs) | Diameter (in) | Slope (Calculated) (ft/ft) | Invert (Start) (ft) | Invert (Stop) (ft) | Elevation Ground (Start) (ft) | Elevation Ground (Stop) (ft) | Hydraulic Grade Line (In) (ft) | Hydraulic Grade Line (Out) (ft) | Energy Grade Line (In) (ft) | Energy Grade Line (Out) (ft) | Velocity (ft/s) | Upstream Structure Headloss Coefficient | Length (User Defined) (ft) |
|--------------------------|---------------------|------------|---------------|----------------------------|---------------------|--------------------|-------------------------------|------------------------------|--------------------------------|---------------------------------|-----------------------------|------------------------------|-----------------|---|----------------------------|
| DP09-2 | CO-1 | 4.40 | 12.0 | 0.010 | 6,263.75 | 6,263.66 | 6,267.82 | 6,268.25 | 6,268.76 | 6,266.62 | 6,267.25 | 6,267.11 | 5.60 | 1.000 | 8.8 |
| DP09-1 | CO-2 | 4.40 | 12.0 | 0.010 | 6,263.46 | 6,262.84 | 6,268.25 | 6,267.71 | 6,266.14 | 6,265.18 | 6,266.62 | 6,265.67 | 5.60 | 1.000 | 62.5 |
| DP01-2 | P01-1 | 46.70 | 42.0 | 0.005 | 6,246.24 | 6,245.98 | 6,252.97 | 6,249.87 | 6,248.37 | 6,248.05 | 6,249.27 | 6,249.02 | 7.89 | 0.050 | 52.0 |
| DP01-11 | P01-10 | 21.60 | 30.0 | 0.010 | 6,255.56 | 6,253.84 | 6,262.02 | 6,260.91 | 6,257.14 | 6,255.65 | 6,257.82 | 6,256.15 | 8.47 | 1.020 | 171.7 |
| DP01-12 | P01-11 | 20.20 | 24.0 | 0.010 | 6,256.81 | 6,256.06 | 6,264.38 | 6,262.02 | 6,258.42 | 6,257.83 | 6,259.28 | 6,258.56 | 8.16 | 0.050 | 74.6 |
| DP01-13 | P01-12 | 19.10 | 24.0 | 0.010 | 6,258.65 | 6,257.01 | 6,265.62 | 6,264.38 | 6,260.22 | 6,258.42 | 6,261.03 | 6,259.43 | 8.08 | 0.640 | 163.6 |
| DP01-14 | P01-13 | 19.00 | 24.0 | 0.010 | 6,259.07 | 6,258.85 | 6,265.81 | 6,265.62 | 6,260.79 | 6,260.74 | 6,261.47 | 6,261.33 | 8.10 | 1.020 | 21.8 |
| DP01-15 | P01-14 | 17.30 | 18.0 | 0.010 | 6,259.32 | 6,259.20 | 6,265.70 | 6,265.81 | 6,261.80 | 6,261.48 | 6,263.29 | 6,262.97 | 9.79 | 0.050 | 11.8 |
| DP01-16 | P01-15 | 9.10 | 18.0 | 0.010 | 6,260.28 | 6,259.59 | 6,265.15 | 6,265.70 | 6,262.40 | 6,261.88 | 6,262.81 | 6,262.29 | 5.15 | 0.000 | 69.2 |
| DP01-3 | P01-2 | 45.00 | 42.0 | 0.005 | 6,246.60 | 6,246.44 | 6,252.79 | 6,252.97 | 6,248.69 | 6,248.47 | 6,249.57 | 6,249.41 | 7.81 | 1.020 | 32.2 |
| DP01-4 | P01-3 | 42.30 | 36.0 | 0.007 | 6,248.21 | 6,246.80 | 6,255.53 | 6,252.79 | 6,250.33 | 6,249.58 | 6,251.31 | 6,250.18 | 8.92 | 1.320 | 188.4 |
| DP01-5 | P01-4 | 42.30 | 36.0 | 0.005 | 6,249.02 | 6,248.41 | 6,257.20 | 6,255.53 | 6,252.11 | 6,251.62 | 6,252.67 | 6,252.17 | 5.98 | 1.020 | 122.5 |
| DP01-6 | P01-5 | 40.80 | 36.0 | 0.005 | 6,250.01 | 6,249.22 | 6,257.99 | 6,257.20 | 6,253.27 | 6,252.68 | 6,253.79 | 6,253.20 | 5.77 | 1.020 | 158.1 |
| DP01-7 | P01-6 | 26.10 | 36.0 | 0.010 | 6,250.87 | 6,250.41 | 6,258.31 | 6,257.99 | 6,253.87 | 6,253.80 | 6,254.08 | 6,254.01 | 8.86 | 1.020 | 46.0 |
| DP01-8 | P01-7 | 24.70 | 30.0 | 0.005 | 6,251.88 | 6,251.37 | 6,259.77 | 6,258.31 | 6,254.45 | 6,254.08 | 6,254.84 | 6,254.48 | 5.03 | 0.400 | 101.1 |
| DP01-9 | P01-8 | 24.10 | 30.0 | 0.005 | 6,252.23 | 6,252.08 | 6,258.40 | 6,259.77 | 6,254.71 | 6,254.61 | 6,255.08 | 6,254.98 | 6.61 | 0.400 | 30.0 |
| DP01-10 | P01-9 | 24.10 | 30.0 | 0.008 | 6,253.64 | 6,252.43 | 6,260.91 | 6,258.40 | 6,255.31 | 6,254.86 | 6,256.05 | 6,255.24 | 7.78 | 0.450 | 161.0 |
| DP02-2 | P02-1 | 19.40 | 24.0 | 0.030 | 6,255.29 | 6,253.65 | 6,262.08 | 6,256.99 | 6,256.87 | 6,255.46 | 6,257.70 | 6,256.11 | 12.42 | 0.050 | 54.9 |
| DP02-3 | P02-2 | 18.20 | 24.0 | 0.010 | 6,256.39 | 6,255.94 | 6,262.08 | 6,262.08 | 6,257.93 | 6,257.31 | 6,258.69 | 6,258.29 | 8.06 | 0.050 | 44.3 |
| DP02-4 | P02-3 | 15.10 | 18.0 | 0.010 | 6,257.20 | 6,256.89 | 6,262.72 | 6,262.08 | 6,259.00 | 6,258.30 | 6,260.13 | 6,259.49 | 8.54 | 0.100 | 31.2 |
| DP02-5 | P02-4 | 6.10 | 18.0 | 0.010 | 6,258.54 | 6,257.40 | 6,264.18 | 6,262.72 | 6,259.49 | 6,259.11 | 6,259.91 | 6,259.30 | 6.18 | 0.100 | 113.6 |
| DP02-6 | P02-5 | 5.50 | 18.0 | 0.010 | 6,259.78 | 6,258.74 | 6,266.02 | 6,264.18 | 6,260.68 | 6,259.51 | 6,261.06 | 6,260.07 | 6.00 | 0.520 | 104.5 |
| DP02-7 | P02-6 | 4.30 | 18.0 | 0.010 | 6,260.42 | 6,259.98 | 6,265.64 | 6,266.02 | 6,261.22 | 6,260.88 | 6,261.53 | 6,261.12 | 5.66 | 0.400 | 43.6 |
| DP02-8 | P02-7 | 4.30 | 18.0 | 0.010 | 6,261.19 | 6,260.62 | 6,267.06 | 6,265.64 | 6,261.98 | 6,261.29 | 6,262.30 | 6,261.79 | 5.66 | 0.050 | 56.6 |
| DP02-9 | P02-8 | 3.50 | 18.0 | 0.010 | 6,261.55 | 6,261.39 | 6,266.82 | 6,267.06 | 6,262.26 | 6,262.00 | 6,262.54 | 6,262.42 | 5.36 | 0.000 | 15.9 |
| DP03-2 | P03-1 | 11.30 | 18.0 | 0.031 | 6,259.72 | 6,255.40 | 6,267.19 | 6,258.76 | 6,261.00 | 6,256.24 | 6,261.77 | 6,258.14 | 11.05 | 0.400 | 137.2 |
| DP03-3 | P03-2 | 11.30 | 18.0 | 0.010 | 6,261.36 | 6,260.52 | 6,266.61 | 6,267.19 | 6,262.74 | 6,261.80 | 6,263.43 | 6,262.57 | 6.39 | 1.520 | 84.2 |
| DP03-4 | P03-3(1) | 4.70 | 18.0 | 0.010 | 6,264.44 | 6,262.84 | 6,269.46 | 6,267.71 | 6,265.37 | 6,265.18 | 6,265.63 | 6,265.29 | 5.78 | 0.050 | 160.0 |
| MH-5 | P03-3(2) | 9.10 | 18.0 | 0.010 | 6,262.64 | 6,261.56 | 6,267.71 | 6,266.61 | 6,264.56 | 6,263.78 | 6,264.98 | 6,264.19 | 5.15 | 1.500 | 104.2 |
| DP03-5 | P03-4 | 4.70 | 18.0 | 0.010 | 6,265.17 | 6,264.64 | 6,270.32 | 6,269.46 | 6,266.00 | 6,265.34 | 6,266.34 | 6,265.86 | 5.77 | 0.000 | 53.3 |
| DP04-1 | P04-1 | 15.70 | 24.0 | 0.010 | 6,251.65 | 6,251.21 | 6,256.47 | 6,257.99 | 6,254.01 | 6,253.80 | 6,254.40 | 6,254.19 | 5.00 | 1.520 | 44.0 |
| DP04-2 | P04-2 | 2.90 | 18.0 | 0.010 | 6,252.26 | 6,251.85 | 6,257.41 | 6,256.47 | 6,254.63 | 6,254.60 | 6,254.67 | 6,254.64 | 1.64 | 0.000 | 41.0 |
| DP05-1 | P05-1 | 2.80 | 18.0 | 0.015 | 6,261.02 | 6,260.02 | 6,265.37 | 6,265.81 | 6,261.66 | 6,261.48 | 6,261.90 | 6,261.52 | 5.81 | 0.400 | 66.9 |
| DP05-2 | P05-2 | 2.80 | 18.0 | 0.020 | 6,261.70 | 6,261.22 | 6,266.72 | 6,265.37 | 6,262.33 | 6,261.68 | 6,262.58 | 6,262.26 | 6.44 | 0.000 | 24.1 |
| DP06-1 | P06-1 | 9.50 | 18.0 | 0.020 | 6,252.49 | 6,251.85 | 6,257.48 | 6,256.47 | 6,254.86 | 6,254.60 | 6,255.31 | 6,255.05 | 5.38 | 0.000 | 32.0 |
| DP07-1 | P07-1 | 4.10 | 18.0 | 0.020 | 6,252.09 | 6,251.85 | 6,256.68 | 6,256.47 | 6,254.62 | 6,254.60 | 6,254.70 | 6,254.68 | 2.32 | 0.000 | 12.1 |
| DP08-1 | P08-01 | 1.50 | 18.0 | 0.020 | 6,261.57 | 6,260.91 | 6,266.14 | 6,266.02 | 6,262.03 | 6,261.23 | 6,262.20 | 6,261.68 | 5.39 | 0.000 | 33.0 |
| DP10-1 | P10-1 | 2.30 | 18.0 | 0.050 | 6,261.97 | 6,261.60 | 6,266.90 | 6,266.61 | 6,263.79 | 6,263.78 | 6,263.81 | 6,263.81 | 1.30 | 0.000 | 7.4 |
| DP11-2 | P11-1 | 6.70 | 18.0 | 0.007 | 6,245.02 | 6,244.65 | 6,250.01 | 6,246.66 | 6,248.16 | 6,247.96 | 6,248.39 | 6,248.18 | 3.79 | 0.050 | 49.8 |
| DP11-3 | P11-2 | 5.80 | 18.0 | 0.008 | 6,245.65 | 6,245.22 | 6,249.80 | 6,250.01 | 6,248.34 | 6,248.17 | 6,248.51 | 6,248.34 | 3.28 | 0.000 | 54.4 |
| DP12-1 | P12-1 | 4.30 | 18.0 | 0.020 | 6,248.05 | 6,247.80 | 6,252.95 | 6,252.79 | 6,249.60 | 6,249.58 | 6,249.70 | 6,249.68 | 2.43 | 0.000 | 12.6 |
| DP13-1 | P13-1 | 2.70 | 18.0 | 0.040 | 6,251.86 | 6,250.52 | 6,256.31 | 6,257.20 | 6,252.58 | 6,252.68 | 6,252.74 | 6,252.71 | 8.16 | 0.000 | 33.6 |
| DP14-1 | P14-1 | 2.20 | 18.0 | 0.040 | 6,252.89 | 6,252.37 | 6,257.83 | 6,258.31 | 6,254.08 | 6,254.08 | 6,254.11 | 6,254.11 | 7.72 | 0.000 | 12.9 |
| DP15-1 | P15-1 | 1.80 | 18.0 | 0.067 | 6,257.43 | 6,256.56 | 6,261.74 | 6,262.02 | 6,257.93 | 6,257.83 | 6,258.12 | 6,257.85 | 8.71 | 0.000 | 13.0 |
| Structure - (81) (STORM) | Pipe - (66) (STORM) | 3.30 | 36.0 | 0.010 | 6,243.00 | 6,242.44 | 6,247.85 | 6,245.78 | 6,248.73 | 6,248.73 | 6,248.73 | 6,248.73 | 0.47 | 0.000 | 56.3 |
| Structure - (93) (STORM) | Pipe - (75) (STORM) | 3.20 | 36.0 | 0.010 | 6,250.10 | 6,249.18 | 6,257.50 | 6,252.53 | 6,254.22 | 6,254.22 | 6,254.23 | 6,254.22 | 0.45 | 0.000 | 92.0 |

X:\2510000.all\2517400\StormCAD\Solace.stsw


Scenario: 5 year




Scenario: 5 year




Scenario: 5 year



Scenario: 5 year



Scenario: 5 year




ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project:
Inlet ID:

Solace Apartments
A1



Gutter Geometry (Enter data in the blue cells)

Maximum Allowable Width for Spread Behind Curb
 Side Slope Behind Curb (leave blank for no conveyance credit behind curb)
 Manning's Roughness Behind Curb (typically between 0.012 and 0.020)
 Height of Curb at Gutter Flow Line
 Distance from Curb Face to Street Crown
 Gutter Width
 Street Transverse Slope
 Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)
 Street Longitudinal Slope - Enter 0 for sump condition
 Manning's Roughness for Street Section (typically between 0.012 and 0.020)

$T_{BACK} = 5.0$ ft
 $S_{BACK} = 0.020$ ft/ft
 $n_{BACK} = 0.016$
 $H_{CURB} = 6.00$ inches
 $T_{CROWN} = 24.0$ ft
 $W = 2.00$ ft
 $S_X = 0.025$ ft/ft
 $S_W = 0.083$ ft/ft
 $S_0 = 0.010$ ft/ft
 $n_{STREET} = 0.016$

Max. Allowable Spread for Minor & Major Storm
 Max. Allowable Depth at Gutter Flowline for Minor & Major Storm
 Allow Flow Depth at Street Crown (leave blank for no)

| | Minor Storm | Major Storm | |
|-------------|--------------------------|--------------------------|-------------|
| $T_{MAX} =$ | 24.0 | 24.0 | ft |
| $d_{MAX} =$ | 6.0 | 12.0 | inches |
| | <input type="checkbox"/> | <input type="checkbox"/> | check = yes |


MINOR STORM Allowable Capacity is based on Depth Criterion
MAJOR STORM Allowable Capacity is based on Spread Criterion

| | Minor Storm | Major Storm | |
|---------------|-------------|-------------|-----|
| $Q_{allow} =$ | 11.9 | 39.5 | cfs |

Minor storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'
Major storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'

INLET ON A CONTINUOUS GRADE

Version 4.06 Released August 2018




| Design Information (Input) | MINOR | MAJOR | |
|---|--------------------------|-------|--------|
| Type of Inlet | CDOT Type R Curb Opening | | |
| Local Depression (additional to continuous gutter depression 'a') | 3.0 | 3.0 | inches |
| Total Number of Units in the Inlet (Grate or Curb Opening) | 1 | 1 | |
| Length of a Single Unit Inlet (Grate or Curb Opening) | 5.00 | 5.00 | ft |
| Width of a Unit Grate (cannot be greater than W, Gutter Width) | N/A | N/A | ft |
| Clogging Factor for a Single Unit Grate (typical min. value = 0.5) | N/A | N/A | |
| Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.1) | 0.10 | 0.10 | |
| Street Hydraulics: OK - Q < Allowable Street Capacity | | | |
| Total Inlet Interception Capacity | 1.6 | 2.3 | cfs |
| Total Inlet Carry-Over Flow (flow bypassing inlet) | 0.1 | 1.0 | cfs |
| Capture Percentage = Q_i/Q_o = | 93 | 71 | % |

ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project:
Inlet ID:


Solace Apartments
A2



| Gutter Geometry (Enter data in the blue cells) | | | | | | | |
|--|---|-------------|-------------|--|--------------------|--------|--------|
| Maximum Allowable Width for Spread Behind Curb | $T_{BACK} = 4.0$ ft | | | | | | |
| Side Slope Behind Curb (leave blank for no conveyance credit behind curb) | $S_{BACK} = 0.020$ ft/ft | | | | | | |
| Manning's Roughness Behind Curb (typically between 0.012 and 0.020) | $n_{BACK} = 0.016$ | | | | | | |
| Height of Curb at Gutter Flow Line | $H_{CURB} = 6.00$ inches | | | | | | |
| Distance from Curb Face to Street Crown | $T_{CROWN} = 18.0$ ft | | | | | | |
| Gutter Width | $W = 2.00$ ft | | | | | | |
| Street Transverse Slope | $S_X = 0.020$ ft/ft | | | | | | |
| Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft) | $S_W = 0.083$ ft/ft | | | | | | |
| Street Longitudinal Slope - Enter 0 for sump condition | $S_O = 0.012$ ft/ft | | | | | | |
| Manning's Roughness for Street Section (typically between 0.012 and 0.020) | $n_{STREET} = 0.016$ | | | | | | |
| Max. Allowable Spread for Minor & Major Storm | <table style="width: 100%; border: none;"> <tr> <td style="width: 50%; text-align: center;">Minor Storm</td> <td style="width: 50%; text-align: center;">Major Storm</td> <td style="width: 10%;"></td> </tr> <tr> <td style="text-align: center;">$T_{MAX} = 18.0$</td> <td style="text-align: center;">18.0</td> <td style="text-align: right;">ft</td> </tr> </table> | Minor Storm | Major Storm | | $T_{MAX} = 18.0$ | 18.0 | ft |
| Minor Storm | Major Storm | | | | | | |
| $T_{MAX} = 18.0$ | 18.0 | ft | | | | | |
| Max. Allowable Depth at Gutter Flowline for Minor & Major Storm | <table style="width: 100%; border: none;"> <tr> <td style="width: 50%; text-align: center;">Minor Storm</td> <td style="width: 50%; text-align: center;">Major Storm</td> <td style="width: 10%;"></td> </tr> <tr> <td style="text-align: center;">$d_{MAX} = 6.0$</td> <td style="text-align: center;">12.0</td> <td style="text-align: right;">inches</td> </tr> </table> | Minor Storm | Major Storm | | $d_{MAX} = 6.0$ | 12.0 | inches |
| Minor Storm | Major Storm | | | | | | |
| $d_{MAX} = 6.0$ | 12.0 | inches | | | | | |
| Allow Flow Depth at Street Crown (leave blank for no) | <input type="checkbox"/> <input type="checkbox"/> check = yes | | | | | | |
| MINOR STORM Allowable Capacity is based on Spread Criterion | | | | | | | |
| MAJOR STORM Allowable Capacity is based on Spread Criterion | | | | | | | |
| Minor storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management' | | | | | | | |
| Major storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management' | | | | | | | |
| | <table style="width: 100%; border: none;"> <tr> <td style="width: 50%; text-align: center;">Minor Storm</td> <td style="width: 50%; text-align: center;">Major Storm</td> <td style="width: 10%;"></td> </tr> <tr> <td style="text-align: center;">$Q_{allow} = 13.7$</td> <td style="text-align: center;">13.7</td> <td style="text-align: right;">cfs</td> </tr> </table> | Minor Storm | Major Storm | | $Q_{allow} = 13.7$ | 13.7 | cfs |
| Minor Storm | Major Storm | | | | | | |
| $Q_{allow} = 13.7$ | 13.7 | cfs | | | | | |

INLET ON A CONTINUOUS GRADE

Version 4.06 Released August 2018




| Design Information (Input) | MINOR | MAJOR | |
|---|----------------------------|-------|--------|
| Type of Inlet | Denver No. 16 Valley Grate | | |
| Local Depression (additional to continuous gutter depression 'a') | 2.0 | 2.0 | inches |
| Total Number of Units in the Inlet (Grate or Curb Opening) | 1 | 1 | |
| Length of a Single Unit Inlet (Grate or Curb Opening) | 3.00 | 3.00 | ft |
| Width of a Unit Grate (cannot be greater than W, Gutter Width) | 1.73 | 1.73 | ft |
| Clogging Factor for a Single Unit Grate (typical min. value = 0.5) | 0.50 | 0.50 | |
| Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.1) | N/A | N/A | |
| Street Hydraulics: OK - Q < Allowable Street Capacity | | | |
| Total Inlet Interception Capacity | 1.0 | 1.5 | cfs |
| Total Inlet Carry-Over Flow (flow bypassing inlet) | 0.6 | 1.6 | cfs |
| Capture Percentage = Q_i/Q_o = | 63 | 48 | % |

ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project:
Inlet ID:

Solace Apartments
A3



Gutter Geometry (Enter data in the blue cells)

Maximum Allowable Width for Spread Behind Curb
 Side Slope Behind Curb (leave blank for no conveyance credit behind curb)
 Manning's Roughness Behind Curb (typically between 0.012 and 0.020)
 Height of Curb at Gutter Flow Line
 Distance from Curb Face to Street Crown
 Gutter Width
 Street Transverse Slope
 Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)
 Street Longitudinal Slope - Enter 0 for sump condition
 Manning's Roughness for Street Section (typically between 0.012 and 0.020)

$T_{BACK} = 4.0$ ft
 $S_{BACK} = 0.020$ ft/ft
 $n_{BACK} = 0.016$
 $H_{CURB} = 6.00$ inches
 $T_{CROWN} = 18.0$ ft
 $W = 2.00$ ft
 $S_x = 0.020$ ft/ft
 $S_w = 0.083$ ft/ft
 $S_o = 0.020$ ft/ft
 $n_{STREET} = 0.016$

Max. Allowable Spread for Minor & Major Storm
 Max. Allowable Depth at Gutter Flowline for Minor & Major Storm
 Allow Flow Depth at Street Crown (leave blank for no)

| | Minor Storm | Major Storm | |
|-------------|--------------------------|--------------------------|-------------|
| $T_{MAX} =$ | 18.0 | 18.0 | ft |
| $d_{MAX} =$ | 6.0 | 12.0 | inches |
| | <input type="checkbox"/> | <input type="checkbox"/> | check = yes |


MINOR STORM Allowable Capacity is based on Spread Criterion
MAJOR STORM Allowable Capacity is based on Spread Criterion

| | Minor Storm | Major Storm | |
|---------------|-------------|-------------|-----|
| $Q_{allow} =$ | 17.7 | 17.7 | cfs |

Minor storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'
Major storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'

INLET ON A CONTINUOUS GRADE

Version 4.06 Released August 2018




| Design Information (Input) | MINOR | MAJOR | |
|---|----------------------------|-------|--------|
| Type of Inlet | Denver No. 16 Valley Grate | | |
| Local Depression (additional to continuous gutter depression 'a') | 2.0 | 2.0 | inches |
| Total Number of Units in the Inlet (Grate or Curb Opening) | 1 | 1 | |
| Length of a Single Unit Inlet (Grate or Curb Opening) | 3.00 | 3.00 | ft |
| Width of a Unit Grate (cannot be greater than W, Gutter Width) | 1.73 | 1.73 | ft |
| Clogging Factor for a Single Unit Grate (typical min. value = 0.5) | 0.50 | 0.50 | |
| Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.1) | N/A | N/A | |
| Street Hydraulics: OK - Q < Allowable Street Capacity | | | |
| Total Inlet Interception Capacity | 1.0 | 1.5 | cfs |
| Total Inlet Carry-Over Flow (flow bypassing inlet) | 0.6 | 1.6 | cfs |
| Capture Percentage = Q_i/Q_o = | 63 | 48 | % |

ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project:
Inlet ID:

Solace Apartments
A6



Gutter Geometry (Enter data in the blue cells)

Maximum Allowable Width for Spread Behind Curb
 Side Slope Behind Curb (leave blank for no conveyance credit behind curb)
 Manning's Roughness Behind Curb (typically between 0.012 and 0.020)
 Height of Curb at Gutter Flow Line
 Distance from Curb Face to Street Crown
 Gutter Width
 Street Transverse Slope
 Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)
 Street Longitudinal Slope - Enter 0 for sump condition
 Manning's Roughness for Street Section (typically between 0.012 and 0.020)

$T_{BACK} = 2.0$ ft
 $S_{BACK} = 0.020$ ft/ft
 $n_{BACK} = 0.016$

$H_{CURB} = 6.00$ inches
 $T_{CROWN} = 18.0$ ft
 $W = 2.00$ ft
 $S_x = 0.020$ ft/ft
 $S_w = 0.083$ ft/ft
 $S_o = 0.000$ ft/ft
 $n_{STREET} = 0.016$

Max. Allowable Spread for Minor & Major Storm
 Max. Allowable Depth at Gutter Flowline for Minor & Major Storm
 Check boxes are not applicable in SUMP conditions

| | Minor Storm | Major Storm | |
|-------------|--------------------------|--------------------------|--------|
| $T_{MAX} =$ | 18.0 | 18.0 | ft |
| $d_{MAX} =$ | 6.0 | 12.0 | inches |
| | <input type="checkbox"/> | <input type="checkbox"/> | |


MINOR STORM Allowable Capacity is based on Depth Criterion
MAJOR STORM Allowable Capacity is based on Depth Criterion

$Q_{allow} =$

| Minor Storm | Major Storm | |
|-------------|-------------|-----|
| SUMP | SUMP | cfs |

INLET IN A SUMP OR SAG LOCATION

Version 4.06 Released August 2018



| Design Information (Input) | MINOR | MAJOR | |
|--|--------------------------|-------|---|
| Type of Inlet | CDOT Type R Curb Opening | | |
| Local Depression (additional to continuous gutter depression 'a' from above) | 3.00 | 3.00 | inches |
| Number of Unit Inlets (Grate or Curb Opening) | 1 | 1 | |
| Water Depth at Flowline (outside of local depression) | 4.7 | 6.4 | inches |
| Grate Information | MINOR | MAJOR | <input checked="" type="checkbox"/> Override Depths |
| Length of a Unit Grate | N/A | N/A | feet |
| Width of a Unit Grate | N/A | N/A | feet |
| Area Opening Ratio for a Grate (typical values 0.15-0.90) | N/A | N/A | |
| Clogging Factor for a Single Grate (typical value 0.50 - 0.70) | N/A | N/A | |
| Grate Weir Coefficient (typical value 2.15 - 3.60) | N/A | N/A | |
| Grate Orifice Coefficient (typical value 0.60 - 0.80) | N/A | N/A | |
| Curb Opening Information | MINOR | MAJOR | |
| Length of a Unit Curb Opening | 10.00 | 10.00 | feet |
| Height of Vertical Curb Opening in Inches | 6.00 | 6.00 | inches |
| Height of Curb Orifice Throat in Inches | 6.00 | 6.00 | inches |
| Angle of Throat (see USDCM Figure ST-5) | 63.40 | 63.40 | degrees |
| Side Width for Depression Pan (typically the gutter width of 2 feet) | 2.00 | 2.00 | feet |
| Clogging Factor for a Single Curb Opening (typical value 0.10) | 0.10 | 0.10 | |
| Curb Opening Weir Coefficient (typical value 2.3-3.7) | 3.60 | 3.60 | |
| Curb Opening Orifice Coefficient (typical value 0.60 - 0.70) | 0.67 | 0.67 | |
| Low Head Performance Reduction (Calculated) | MINOR | MAJOR | |
| Depth for Grate Midwidth | N/A | N/A | ft |
| Depth for Curb Opening Weir Equation | 0.23 | 0.37 | ft |
| Combination Inlet Performance Reduction Factor for Long Inlets | 0.45 | 0.61 | |
| Curb Opening Performance Reduction Factor for Long Inlets | 0.85 | 0.96 | |
| Grated Inlet Performance Reduction Factor for Long Inlets | N/A | N/A | |
| Total Inlet Interception Capacity (assumes clogged condition) | MINOR | MAJOR | |
| Q_a | 4.3 | 10.0 | cfs |
| Q_{PEAK REQUIRED} | 4.2 | 9.6 | cfs |


Inlet Capacity IS GOOD for Minor and Major Storms(>Q PEAK)

ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project:
Inlet ID:


Solace Apartments
A7



| Gutter Geometry (Enter data in the blue cells) | | | | | | | | | |
|--|--|-------------|-------------|-------------|--|-------------|------|------|--------|
| Maximum Allowable Width for Spread Behind Curb | $T_{BACK} = 20.0$ ft | | | | | | | | |
| Side Slope Behind Curb (leave blank for no conveyance credit behind curb) | $S_{BACK} = 0.020$ ft/ft | | | | | | | | |
| Manning's Roughness Behind Curb (typically between 0.012 and 0.020) | $n_{BACK} = 0.016$ | | | | | | | | |
| Height of Curb at Gutter Flow Line | $H_{CURB} = 6.00$ inches | | | | | | | | |
| Distance from Curb Face to Street Crown | $T_{CROWN} = 20.0$ ft | | | | | | | | |
| Gutter Width | $W = 2.00$ ft | | | | | | | | |
| Street Transverse Slope | $S_X = 0.020$ ft/ft | | | | | | | | |
| Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft) | $S_W = 0.083$ ft/ft | | | | | | | | |
| Street Longitudinal Slope - Enter 0 for sump condition | $S_O = 0.015$ ft/ft | | | | | | | | |
| Manning's Roughness for Street Section (typically between 0.012 and 0.020) | $n_{STREET} = 0.016$ | | | | | | | | |
| Max. Allowable Spread for Minor & Major Storm | <table style="width: 100%; border: none;"> <tr> <td style="width: 50%;"></td> <td style="width: 25%; text-align: center;">Minor Storm</td> <td style="width: 25%; text-align: center;">Major Storm</td> <td style="width: 10%;"></td> </tr> <tr> <td>$T_{MAX} =$</td> <td style="border: 1px solid black; text-align: center;">20.0</td> <td style="border: 1px solid black; text-align: center;">20.0</td> <td style="border: none;">ft</td> </tr> </table> | | Minor Storm | Major Storm | | $T_{MAX} =$ | 20.0 | 20.0 | ft |
| | Minor Storm | Major Storm | | | | | | | |
| $T_{MAX} =$ | 20.0 | 20.0 | ft | | | | | | |
| Max. Allowable Depth at Gutter Flowline for Minor & Major Storm | <table style="width: 100%; border: none;"> <tr> <td style="width: 50%;"></td> <td style="width: 25%; text-align: center;">Minor Storm</td> <td style="width: 25%; text-align: center;">Major Storm</td> <td style="width: 10%;"></td> </tr> <tr> <td>$d_{MAX} =$</td> <td style="border: 1px solid black; text-align: center;">6.0</td> <td style="border: 1px solid black; text-align: center;">12.0</td> <td style="border: none;">inches</td> </tr> </table> | | Minor Storm | Major Storm | | $d_{MAX} =$ | 6.0 | 12.0 | inches |
| | Minor Storm | Major Storm | | | | | | | |
| $d_{MAX} =$ | 6.0 | 12.0 | inches | | | | | | |
| Allow Flow Depth at Street Crown (leave blank for no) | <input type="checkbox"/> <input type="checkbox"/> check = yes | | | | | | | | |
| MINOR STORM Allowable Capacity is based on Depth Criterion | | | | | | | | | |
| MAJOR STORM Allowable Capacity is based on Spread Criterion | | | | | | | | | |
| $Q_{allow} =$ | | | | | | | | | |
| <table style="width: 100%; border: none;"> <tr> <td style="width: 50%;"></td> <td style="width: 25%; text-align: center;">Minor Storm</td> <td style="width: 25%; text-align: center;">Major Storm</td> <td style="width: 10%;"></td> </tr> <tr> <td></td> <td style="border: 1px solid black; text-align: center;">16.9</td> <td style="border: 1px solid black; text-align: center;">20.0</td> <td style="border: none;">cfs</td> </tr> </table> | | | Minor Storm | Major Storm | | | 16.9 | 20.0 | cfs |
| | Minor Storm | Major Storm | | | | | | | |
| | 16.9 | 20.0 | cfs | | | | | | |
| Minor storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management' | | | | | | | | | |
| Major storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management' | | | | | | | | | |

INLET ON A CONTINUOUS GRADE

Version 4.06 Released August 2018




| Design Information (Input) | MINOR | MAJOR | |
|---|--------------------------|-------|--------|
| Type of Inlet | CDOT Type R Curb Opening | | |
| Local Depression (additional to continuous gutter depression 'a') | 3.0 | 3.0 | inches |
| Total Number of Units in the Inlet (Grate or Curb Opening) | 1 | 1 | |
| Length of a Single Unit Inlet (Grate or Curb Opening) | 10.00 | 10.00 | ft |
| Width of a Unit Grate (cannot be greater than W, Gutter Width) | N/A | N/A | ft |
| Clogging Factor for a Single Unit Grate (typical min. value = 0.5) | N/A | N/A | |
| Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.1) | 0.10 | 0.10 | |
| Street Hydraulics: OK - Q < Allowable Street Capacity | | | |
| Total Inlet Interception Capacity | 1.1 | 3.2 | cfs |
| Total Inlet Carry-Over Flow (flow bypassing inlet) | 0.0 | 0.0 | cfs |
| Capture Percentage = Q_i/Q_o = | 100 | 100 | % |

ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project:
Inlet ID:

Solace Apartments
A8



Gutter Geometry (Enter data in the blue cells)

Maximum Allowable Width for Spread Behind Curb
Side Slope Behind Curb (leave blank for no conveyance credit behind curb)
Manning's Roughness Behind Curb (typically between 0.012 and 0.020)

$T_{BACK} = 20.0$ ft
 $S_{BACK} = 0.020$ ft/ft
 $n_{BACK} = 0.016$

Height of Curb at Gutter Flow Line
Distance from Curb Face to Street Crown
Gutter Width
Street Transverse Slope
Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)
Street Longitudinal Slope - Enter 0 for sump condition
Manning's Roughness for Street Section (typically between 0.012 and 0.020)

$H_{CURB} = 6.00$ inches
 $T_{CROWN} = 20.0$ ft
 $W = 2.00$ ft
 $S_x = 0.020$ ft/ft
 $S_w = 0.083$ ft/ft
 $S_o = 0.015$ ft/ft
 $n_{STREET} = 0.016$

Max. Allowable Spread for Minor & Major Storm
Max. Allowable Depth at Gutter Flowline for Minor & Major Storm
Allow Flow Depth at Street Crown (leave blank for no)

| | Minor Storm | Major Storm | |
|-------------|-------------|-------------|--------|
| $T_{MAX} =$ | 20.0 | 20.0 | ft |
| $d_{MAX} =$ | 6.0 | 12.0 | inches |

check = yes


MINOR STORM Allowable Capacity is based on Depth Criterion
MAJOR STORM Allowable Capacity is based on Spread Criterion

| | Minor Storm | Major Storm | |
|---------------|-------------|-------------|-----|
| $Q_{allow} =$ | 16.9 | 20.0 | cfs |

Minor storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'
Major storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'

INLET ON A CONTINUOUS GRADE

Version 4.06 Released August 2018




| Design Information (Input) | MINOR | | MAJOR | |
|---|---------------------------------|---------|--------|--|
| Type of Inlet | Type = CDOT Type R Curb Opening | | | |
| Local Depression (additional to continuous gutter depression 'a') | $a_{LOCAL} = 3.0$ | 3.0 | inches | |
| Total Number of Units in the Inlet (Grate or Curb Opening) | $No = 1$ | 1 | | |
| Length of a Single Unit Inlet (Grate or Curb Opening) | $L_o = 10.00$ | 10.00 | ft | |
| Width of a Unit Grate (cannot be greater than W, Gutter Width) | $W_o = N/A$ | N/A | ft | |
| Clogging Factor for a Single Unit Grate (typical min. value = 0.5) | $C_{r-G} = N/A$ | N/A | | |
| Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.1) | $C_{r-C} = 0.10$ | 0.10 | | |
| Street Hydraulics: OK - Q < Allowable Street Capacity | | | | |
| Total Inlet Interception Capacity | $Q = 0.8$ | 1.7 | cfs | |
| Total Inlet Carry-Over Flow (flow bypassing inlet) | $Q_b = 0.0$ | 0.0 | cfs | |
| Capture Percentage = $Q_r/Q_b =$ | $C\% = 100$ | 100 | % | |

ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project:
Inlet ID:


Solace Apartments
B1



| Gutter Geometry (Enter data in the blue cells) | | | | | | | |
|--|---|-------------|-------------|--|------|------|--------|
| Maximum Allowable Width for Spread Behind Curb | $T_{BACK} = 4.0$ ft | | | | | | |
| Side Slope Behind Curb (leave blank for no conveyance credit behind curb) | $S_{BACK} = 0.020$ ft/ft | | | | | | |
| Manning's Roughness Behind Curb (typically between 0.012 and 0.020) | $n_{BACK} = 0.016$ | | | | | | |
| Height of Curb at Gutter Flow Line | $H_{CURB} = 6.00$ inches | | | | | | |
| Distance from Curb Face to Street Crown | $T_{CROWN} = 18.0$ ft | | | | | | |
| Gutter Width | $W = 2.00$ ft | | | | | | |
| Street Transverse Slope | $S_x = 0.020$ ft/ft | | | | | | |
| Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft) | $S_w = 0.083$ ft/ft | | | | | | |
| Street Longitudinal Slope - Enter 0 for sump condition | $S_o = 0.013$ ft/ft | | | | | | |
| Manning's Roughness for Street Section (typically between 0.012 and 0.020) | $n_{STREET} = 0.016$ | | | | | | |
| Max. Allowable Spread for Minor & Major Storm | <table border="1" style="display: inline-table; border-collapse: collapse;"> <tr> <th style="width: 50%;">Minor Storm</th> <th style="width: 50%;">Major Storm</th> <th style="width: 10%;"></th> </tr> <tr> <td style="text-align: center;">18.0</td> <td style="text-align: center;">18.0</td> <td style="text-align: right;">ft</td> </tr> </table> | Minor Storm | Major Storm | | 18.0 | 18.0 | ft |
| Minor Storm | Major Storm | | | | | | |
| 18.0 | 18.0 | ft | | | | | |
| Max. Allowable Depth at Gutter Flowline for Minor & Major Storm | <table border="1" style="display: inline-table; border-collapse: collapse;"> <tr> <th style="width: 50%;">Minor Storm</th> <th style="width: 50%;">Major Storm</th> <th style="width: 10%;"></th> </tr> <tr> <td style="text-align: center;">6.0</td> <td style="text-align: center;">12.0</td> <td style="text-align: right;">inches</td> </tr> </table> | Minor Storm | Major Storm | | 6.0 | 12.0 | inches |
| Minor Storm | Major Storm | | | | | | |
| 6.0 | 12.0 | inches | | | | | |
| Allow Flow Depth at Street Crown (leave blank for no) | <input type="checkbox"/> <input type="checkbox"/> check = yes | | | | | | |
| MINOR STORM Allowable Capacity is based on Spread Criterion | | | | | | | |
| MAJOR STORM Allowable Capacity is based on Spread Criterion | | | | | | | |
| Minor storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management' | | | | | | | |
| Major storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management' | | | | | | | |
| $Q_{allow} =$ | <table border="1" style="display: inline-table; border-collapse: collapse;"> <tr> <th style="width: 50%;">Minor Storm</th> <th style="width: 50%;">Major Storm</th> <th style="width: 10%;"></th> </tr> <tr> <td style="text-align: center;">14.3</td> <td style="text-align: center;">14.3</td> <td style="text-align: right;">cfs</td> </tr> </table> | Minor Storm | Major Storm | | 14.3 | 14.3 | cfs |
| Minor Storm | Major Storm | | | | | | |
| 14.3 | 14.3 | cfs | | | | | |

INLET ON A CONTINUOUS GRADE

Version 4.06 Released August 2018




| Design Information (Input) | MINOR | MAJOR | |
|---|----------------------------|-------|--------|
| Type of Inlet | Denver No. 16 Valley Grate | | |
| Local Depression (additional to continuous gutter depression 'a') | 2.0 | 2.0 | inches |
| Total Number of Units in the Inlet (Grate or Curb Opening) | 1 | 1 | |
| Length of a Single Unit Inlet (Grate or Curb Opening) | 3.00 | 3.00 | ft |
| Width of a Unit Grate (cannot be greater than W, Gutter Width) | 1.73 | 1.73 | ft |
| Clogging Factor for a Single Unit Grate (typical min. value = 0.5) | 0.50 | 0.50 | |
| Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.1) | N/A | N/A | |
| Street Hydraulics: OK - Q < Allowable Street Capacity | | | |
| Total Inlet Interception Capacity | 1.7 | 2.7 | cfs |
| Total Inlet Carry-Over Flow (flow bypassing inlet) | 2.4 | 7.0 | cfs |
| Capture Percentage = Q_i/Q_o = | 42 | 28 | % |

ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project:
Inlet ID:

Solace Apartments
B2



Gutter Geometry (Enter data in the blue cells)

Maximum Allowable Width for Spread Behind Curb
 Side Slope Behind Curb (leave blank for no conveyance credit behind curb)
 Manning's Roughness Behind Curb (typically between 0.012 and 0.020)
 Height of Curb at Gutter Flow Line
 Distance from Curb Face to Street Crown
 Gutter Width
 Street Transverse Slope
 Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)
 Street Longitudinal Slope - Enter 0 for sump condition
 Manning's Roughness for Street Section (typically between 0.012 and 0.020)

$T_{BACK} = 4.0$ ft
 $S_{BACK} = 0.020$ ft/ft
 $n_{BACK} = 0.016$
 $H_{CURB} = 6.00$ inches
 $T_{CROWN} = 24.0$ ft
 $W = 2.00$ ft
 $S_x = 0.025$ ft/ft
 $S_w = 0.083$ ft/ft
 $S_o = 0.028$ ft/ft
 $n_{STREET} = 0.016$

Max. Allowable Spread for Minor & Major Storm
 Max. Allowable Depth at Gutter Flowline for Minor & Major Storm
 Allow Flow Depth at Street Crown (leave blank for no)

| | Minor Storm | Major Storm | |
|-------------|--------------------------|--------------------------|-------------|
| $T_{MAX} =$ | 24.0 | 24.0 | ft |
| $d_{MAX} =$ | 6.0 | 12.0 | inches |
| | <input type="checkbox"/> | <input type="checkbox"/> | check = yes |


MINOR STORM Allowable Capacity is based on Depth Criterion
MAJOR STORM Allowable Capacity is based on Spread Criterion

| | Minor Storm | Major Storm | |
|---------------|-------------|-------------|-----|
| $Q_{allow} =$ | 15.7 | 65.7 | cfs |

Minor storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'
Major storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'

INLET ON A CONTINUOUS GRADE

Version 4.06 Released August 2018




| Design Information (Input) | MINOR | MAJOR | |
|---|--------------------------|-------|--------|
| Type of Inlet | CDOT Type R Curb Opening | | |
| Local Depression (additional to continuous gutter depression 'a') | 3.0 | 3.0 | inches |
| Total Number of Units in the Inlet (Grate or Curb Opening) | 1 | 1 | |
| Length of a Single Unit Inlet (Grate or Curb Opening) | 10.00 | 10.00 | ft |
| Width of a Unit Grate (cannot be greater than W, Gutter Width) | N/A | N/A | ft |
| Clogging Factor for a Single Unit Grate (typical min. value = 0.5) | N/A | N/A | |
| Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.1) | 0.10 | 0.10 | |
| Street Hydraulics: OK - Q < Allowable Street Capacity | | | |
| Total Inlet Interception Capacity | 1.6 | 2.8 | cfs |
| Total Inlet Carry-Over Flow (flow bypassing inlet) | 0.0 | 0.0 | cfs |
| Capture Percentage = Q_i/Q_o = | 100 | 100 | % |

ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project:
Inlet ID:

Solace Apartments
B3



Gutter Geometry (Enter data in the blue cells)

Maximum Allowable Width for Spread Behind Curb
Side Slope Behind Curb (leave blank for no conveyance credit behind curb)
Manning's Roughness Behind Curb (typically between 0.012 and 0.020)

$T_{BACK} = 4.0$ ft
 $S_{BACK} = 0.020$ ft/ft
 $n_{BACK} = 0.016$

Height of Curb at Gutter Flow Line
Distance from Curb Face to Street Crown
Gutter Width
Street Transverse Slope
Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)
Street Longitudinal Slope - Enter 0 for sump condition
Manning's Roughness for Street Section (typically between 0.012 and 0.020)

$H_{CURB} = 6.00$ inches
 $T_{CROWN} = 24.0$ ft
 $W = 2.00$ ft
 $S_x = 0.020$ ft/ft
 $S_w = 0.083$ ft/ft
 $S_o = 0.013$ ft/ft
 $n_{STREET} = 0.016$

Max. Allowable Spread for Minor & Major Storm
Max. Allowable Depth at Gutter Flowline for Minor & Major Storm
Allow Flow Depth at Street Crown (leave blank for no)

| | Minor Storm | Major Storm | |
|-------------|--------------------------|--------------------------|-------------|
| $T_{MAX} =$ | 24.0 | 24.0 | ft |
| $d_{MAX} =$ | 6.0 | 12.0 | inches |
| | <input type="checkbox"/> | <input type="checkbox"/> | check = yes |


MINOR STORM Allowable Capacity is based on Depth Criterion
MAJOR STORM Allowable Capacity is based on Spread Criterion

| | Minor Storm | Major Storm | |
|---------------|-------------|-------------|-----|
| $Q_{allow} =$ | 15.7 | 30.1 | cfs |

Minor storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'
Major storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'

INLET ON A CONTINUOUS GRADE

Version 4.06 Released August 2018




| Design Information (Input) | MINOR | MAJOR | |
|---|--------------------------|-------|--------|
| Type of Inlet | CDOT Type R Curb Opening | | |
| Local Depression (additional to continuous gutter depression 'a') | 3.0 | 3.0 | inches |
| Total Number of Units in the Inlet (Grate or Curb Opening) | 1 | 1 | |
| Length of a Single Unit Inlet (Grate or Curb Opening) | 15.00 | 15.00 | ft |
| Width of a Unit Grate (cannot be greater than W, Gutter Width) | N/A | N/A | ft |
| Clogging Factor for a Single Unit Grate (typical min. value = 0.5) | N/A | N/A | |
| Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.1) | 0.10 | 0.10 | |
| Street Hydraulics: OK - Q < Allowable Street Capacity | | | |
| Total Inlet Interception Capacity | 3.2 | 8.2 | cfs |
| Total Inlet Carry-Over Flow (flow bypassing inlet) | 0.0 | 0.3 | cfs |
| Capture Percentage = Q_i/Q_o = | 100 | 96 | % |

ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project:
Inlet ID:

Solace Apartments
B6



Gutter Geometry (Enter data in the blue cells)

Maximum Allowable Width for Spread Behind Curb
Side Slope Behind Curb (leave blank for no conveyance credit behind curb)
Manning's Roughness Behind Curb (typically between 0.012 and 0.020)

$T_{BACK} = 4.0$ ft
 $S_{BACK} = 0.020$ ft/ft
 $n_{BACK} = 0.016$

Height of Curb at Gutter Flow Line
Distance from Curb Face to Street Crown
Gutter Width
Street Transverse Slope
Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)
Street Longitudinal Slope - Enter 0 for sump condition
Manning's Roughness for Street Section (typically between 0.012 and 0.020)

$H_{CURB} = 6.00$ inches
 $T_{CROWN} = 18.0$ ft
 $W = 2.00$ ft
 $S_x = 0.020$ ft/ft
 $S_w = 0.083$ ft/ft
 $S_o = 0.012$ ft/ft
 $n_{STREET} = 0.016$

Max. Allowable Spread for Minor & Major Storm
Max. Allowable Depth at Gutter Flowline for Minor & Major Storm
Allow Flow Depth at Street Crown (leave blank for no)

| | Minor Storm | Major Storm | |
|-------------|-------------|-------------|--------|
| $T_{MAX} =$ | 18.0 | 18.0 | ft |
| $d_{MAX} =$ | 6.0 | 12.0 | inches |

check = yes


MINOR STORM Allowable Capacity is based on Spread Criterion
MAJOR STORM Allowable Capacity is based on Spread Criterion

| | Minor Storm | Major Storm | |
|---------------|-------------|-------------|-----|
| $Q_{allow} =$ | 13.7 | 13.7 | cfs |

Minor storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'
Major storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'

INLET ON A CONTINUOUS GRADE

Version 4.06 Released August 2018




| Design Information (Input) | MINOR | MAJOR | |
|---|----------------------------|-------|--------|
| Type of Inlet | Denver No. 16 Valley Grate | | |
| Local Depression (additional to continuous gutter depression 'a') | 2.0 | 2.0 | inches |
| Total Number of Units in the Inlet (Grate or Curb Opening) | 1 | 1 | |
| Length of a Single Unit Inlet (Grate or Curb Opening) | 3.00 | 3.00 | ft |
| Width of a Unit Grate (cannot be greater than W, Gutter Width) | 1.73 | 1.73 | ft |
| Clogging Factor for a Single Unit Grate (typical min. value = 0.5) | 0.50 | 0.50 | |
| Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.1) | N/A | N/A | |
| Street Hydraulics: OK - Q < Allowable Street Capacity | | | |
| Total Inlet Interception Capacity | 1.1 | 1.8 | cfs |
| Total Inlet Carry-Over Flow (flow bypassing inlet) | 0.8 | 2.5 | cfs |
| Capture Percentage = Q_i/Q_b = | 59 | 42 | % |

ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project:
Inlet ID:

**Solace Apartments
B10**



Gutter Geometry (Enter data in the blue cells)

Maximum Allowable Width for Spread Behind Curb
 Side Slope Behind Curb (leave blank for no conveyance credit behind curb)
 Manning's Roughness Behind Curb (typically between 0.012 and 0.020)
 Height of Curb at Gutter Flow Line
 Distance from Curb Face to Street Crown
 Gutter Width
 Street Transverse Slope
 Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)
 Street Longitudinal Slope - Enter 0 for sump condition
 Manning's Roughness for Street Section (typically between 0.012 and 0.020)

$T_{BACK} = 4.0$ ft
 $S_{BACK} = 0.020$ ft/ft
 $n_{BACK} = 0.016$

$H_{CURB} = 6.00$ inches
 $T_{CROWN} = 24.0$ ft
 $W = 2.00$ ft
 $S_x = 0.030$ ft/ft
 $S_w = 0.083$ ft/ft
 $S_o = 0.000$ ft/ft
 $n_{STREET} = 0.016$

Max. Allowable Spread for Minor & Major Storm
 Max. Allowable Depth at Gutter Flowline for Minor & Major Storm
 Check boxes are not applicable in SUMP conditions

| | Minor Storm | Major Storm | |
|-------------|--------------------------|--------------------------|--------|
| $T_{MAX} =$ | 24.0 | 24.0 | ft |
| $d_{MAX} =$ | 6.0 | 12.0 | inches |
| | <input type="checkbox"/> | <input type="checkbox"/> | |


MINOR STORM Allowable Capacity is based on Depth Criterion
MAJOR STORM Allowable Capacity is based on Depth Criterion

$Q_{allow} =$

| Minor Storm | Major Storm | |
|-------------|-------------|-----|
| SUMP | SUMP | cfs |

INLET IN A SUMP OR SAG LOCATION

Version 4.06 Released August 2018




| Design Information (Input) | MINOR | MAJOR | |
|--|--------------------------|-------|---|
| Type of Inlet | CDOT Type R Curb Opening | | |
| Local Depression (additional to continuous gutter depression 'a' from above) | 3.00 | 3.00 | inches |
| Number of Unit Inlets (Grate or Curb Opening) | 1 | 1 | |
| Water Depth at Flowline (outside of local depression) | 3.5 | 4.2 | inches |
| Grate Information | MINOR | MAJOR | <input checked="" type="checkbox"/> Override Depths |
| Length of a Unit Grate | N/A | N/A | feet |
| Width of a Unit Grate | N/A | N/A | feet |
| Area Opening Ratio for a Grate (typical values 0.15-0.90) | N/A | N/A | |
| Clogging Factor for a Single Grate (typical value 0.50 - 0.70) | N/A | N/A | |
| Grate Weir Coefficient (typical value 2.15 - 3.60) | N/A | N/A | |
| Grate Orifice Coefficient (typical value 0.60 - 0.80) | N/A | N/A | |
| Curb Opening Information | MINOR | MAJOR | |
| Length of a Unit Curb Opening | 5.00 | 5.00 | feet |
| Height of Vertical Curb Opening in Inches | 6.00 | 6.00 | inches |
| Height of Curb Orifice Throat in Inches | 6.00 | 6.00 | inches |
| Angle of Throat (see USDCM Figure ST-5) | 63.40 | 63.40 | degrees |
| Side Width for Depression Pan (typically the gutter width of 2 feet) | 2.00 | 2.00 | feet |
| Clogging Factor for a Single Curb Opening (typical value 0.10) | 0.10 | 0.10 | |
| Curb Opening Weir Coefficient (typical value 2.3-3.7) | 3.60 | 3.60 | |
| Curb Opening Orifice Coefficient (typical value 0.60 - 0.70) | 0.67 | 0.67 | |
| Low Head Performance Reduction (Calculated) | MINOR | MAJOR | |
| Depth for Grate Midwidth | N/A | N/A | ft |
| Depth for Curb Opening Weir Equation | 0.13 | 0.19 | ft |
| Combination Inlet Performance Reduction Factor for Long Inlets | 0.45 | 0.54 | |
| Curb Opening Performance Reduction Factor for Long Inlets | 0.99 | 1.00 | |
| Grated Inlet Performance Reduction Factor for Long Inlets | N/A | N/A | |
| Total Inlet Interception Capacity (assumes clogged condition) | MINOR | MAJOR | |
| Inlet Capacity IS GOOD for Minor and Major Storms(>Q PEAK) | 1.2 | 2.3 | cfs |
| Q PEAK REQUIRED = | 1.0 | 2.2 | cfs |

ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project:
Inlet ID:

**Solace Apartments
B13**



Gutter Geometry (Enter data in the blue cells)

Maximum Allowable Width for Spread Behind Curb
Side Slope Behind Curb (leave blank for no conveyance credit behind curb)
Manning's Roughness Behind Curb (typically between 0.012 and 0.020)

$T_{BACK} = 4.0$ ft
 $S_{BACK} = 0.020$ ft/ft
 $n_{BACK} = 0.016$

Height of Curb at Gutter Flow Line
Distance from Curb Face to Street Crown
Gutter Width

$H_{CURB} = 6.00$ inches
 $T_{CROWN} = 18.0$ ft
 $W = 2.00$ ft

Street Transverse Slope
Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)
Street Longitudinal Slope - Enter 0 for sump condition
Manning's Roughness for Street Section (typically between 0.012 and 0.020)

$S_X = 0.020$ ft/ft
 $S_W = 0.083$ ft/ft
 $S_O = 0.034$ ft/ft
 $n_{STREET} = 0.016$

Max. Allowable Spread for Minor & Major Storm
Max. Allowable Depth at Gutter Flowline for Minor & Major Storm
Allow Flow Depth at Street Crown (leave blank for no)

| | Minor Storm | Major Storm | |
|-------------|-------------|-------------|--------|
| $T_{MAX} =$ | 18.0 | 18.0 | ft |
| $d_{MAX} =$ | 6.0 | 12.0 | inches |

check = yes


MINOR STORM Allowable Capacity is based on Depth Criterion
MAJOR STORM Allowable Capacity is based on Spread Criterion

| | Minor Storm | Major Storm | |
|---------------|-------------|-------------|-----|
| $Q_{allow} =$ | 17.1 | 23.1 | cfs |

Minor storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'
Major storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'

INLET ON A CONTINUOUS GRADE

Version 4.06 Released August 2018




| Design Information (Input) | MINOR | MAJOR | |
|---|----------------------------|-------|--------|
| Type of Inlet | Denver No. 16 Valley Grate | | |
| Local Depression (additional to continuous gutter depression 'a') | 2.0 | 2.0 | inches |
| Total Number of Units in the Inlet (Grate or Curb Opening) | 1 | 1 | |
| Length of a Single Unit Inlet (Grate or Curb Opening) | 3.00 | 3.00 | ft |
| Width of a Unit Grate (cannot be greater than W, Gutter Width) | 1.73 | 1.73 | ft |
| Clogging Factor for a Single Unit Grate (typical min. value = 0.5) | 0.50 | 0.50 | |
| Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.1) | N/A | N/A | |
| Street Hydraulics: OK - Q < Allowable Street Capacity | | | |
| Total Inlet Interception Capacity | 0.9 | 1.5 | cfs |
| Total Inlet Carry-Over Flow (flow bypassing inlet) | 0.6 | 1.7 | cfs |
| Capture Percentage = Q_i/Q_o = | 62 | 46 | % |

ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project:
Inlet ID:

Solace Apartments
B12



Gutter Geometry (Enter data in the blue cells)

Maximum Allowable Width for Spread Behind Curb
 Side Slope Behind Curb (leave blank for no conveyance credit behind curb)
 Manning's Roughness Behind Curb (typically between 0.012 and 0.020)
 Height of Curb at Gutter Flow Line
 Distance from Curb Face to Street Crown
 Gutter Width
 Street Transverse Slope
 Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)
 Street Longitudinal Slope - Enter 0 for sump condition
 Manning's Roughness for Street Section (typically between 0.012 and 0.020)

$T_{BACK} = 4.0$ ft
 $S_{BACK} = 0.020$ ft/ft
 $n_{BACK} = 0.016$

$H_{CURB} = 6.00$ inches
 $T_{CROWN} = 18.0$ ft
 $W = 2.00$ ft
 $S_x = 0.030$ ft/ft
 $S_w = 0.083$ ft/ft
 $S_o = 0.000$ ft/ft
 $n_{STREET} = 0.016$

Max. Allowable Spread for Minor & Major Storm
 Max. Allowable Depth at Gutter Flowline for Minor & Major Storm
 Check boxes are not applicable in SUMP conditions

| | Minor Storm | Major Storm | |
|-------------|--------------------------|--------------------------|--------|
| $T_{MAX} =$ | 18.0 | 18.0 | ft |
| $d_{MAX} =$ | 6.0 | 12.0 | inches |
| | <input type="checkbox"/> | <input type="checkbox"/> | |


MINOR STORM Allowable Capacity is based on Depth Criterion
MAJOR STORM Allowable Capacity is based on Depth Criterion

$Q_{allow} =$

| Minor Storm | Major Storm | |
|-------------|-------------|-----|
| SUMP | SUMP | cfs |

INLET IN A SUMP OR SAG LOCATION

Version 4.06 Released August 2018




| Design Information (Input) | MINOR | MAJOR | |
|--|--------------------------|-------|---|
| Type of Inlet | CDOT Type R Curb Opening | | |
| Local Depression (additional to continuous gutter depression 'a' from above) | 3.00 | 3.00 | inches |
| Number of Unit Inlets (Grate or Curb Opening) | 1 | 1 | |
| Water Depth at Flowline (outside of local depression) | 4.8 | 6.8 | inches |
| Grate Information | MINOR | MAJOR | <input checked="" type="checkbox"/> Override Depths |
| Length of a Unit Grate | N/A | N/A | feet |
| Width of a Unit Grate | N/A | N/A | feet |
| Area Opening Ratio for a Grate (typical values 0.15-0.90) | N/A | N/A | |
| Clogging Factor for a Single Grate (typical value 0.50 - 0.70) | N/A | N/A | |
| Grate Weir Coefficient (typical value 2.15 - 3.60) | N/A | N/A | |
| Grate Orifice Coefficient (typical value 0.60 - 0.80) | N/A | N/A | |
| Curb Opening Information | MINOR | MAJOR | |
| Length of a Unit Curb Opening | 5.00 | 5.00 | feet |
| Height of Vertical Curb Opening in Inches | 6.00 | 6.00 | inches |
| Height of Curb Orifice Throat in Inches | 6.00 | 6.00 | inches |
| Angle of Throat (see USDCM Figure ST-5) | 63.40 | 63.40 | degrees |
| Side Width for Depression Pan (typically the gutter width of 2 feet) | 2.00 | 2.00 | feet |
| Clogging Factor for a Single Curb Opening (typical value 0.10) | 0.10 | 0.10 | |
| Curb Opening Weir Coefficient (typical value 2.3-3.7) | 3.60 | 3.60 | |
| Curb Opening Orifice Coefficient (typical value 0.60 - 0.70) | 0.67 | 0.67 | |
| Low Head Performance Reduction (Calculated) | MINOR | MAJOR | |
| Depth for Grate Midwidth | N/A | N/A | ft |
| Depth for Curb Opening Weir Equation | 0.23 | 0.40 | ft |
| Combination Inlet Performance Reduction Factor for Long Inlets | 0.62 | 0.88 | |
| Curb Opening Performance Reduction Factor for Long Inlets | 1.00 | 1.00 | |
| Grated Inlet Performance Reduction Factor for Long Inlets | N/A | N/A | |
| Total Inlet Interception Capacity (assumes clogged condition) | MINOR | MAJOR | |
| Inlet Capacity IS GOOD for Minor and Major Storms(>Q PEAK) | 3.2 | 7.2 | cfs |
| Q PEAK REQUIRED = | 3.1 | 7.1 | cfs |

ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project:
Inlet ID:

Solace Apartments
B14



Gutter Geometry (Enter data in the blue cells)

Maximum Allowable Width for Spread Behind Curb
 Side Slope Behind Curb (leave blank for no conveyance credit behind curb)
 Manning's Roughness Behind Curb (typically between 0.012 and 0.020)
 Height of Curb at Gutter Flow Line
 Distance from Curb Face to Street Crown
 Gutter Width
 Street Transverse Slope
 Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)
 Street Longitudinal Slope - Enter 0 for sump condition
 Manning's Roughness for Street Section (typically between 0.012 and 0.020)

$T_{BACK} = 4.0$ ft
 $S_{BACK} = 0.020$ ft/ft
 $n_{BACK} = 0.016$

$H_{CURB} = 6.00$ inches
 $T_{CROWN} = 18.0$ ft
 $W = 2.00$ ft
 $S_X = 0.027$ ft/ft
 $S_W = 0.083$ ft/ft
 $S_0 = 0.000$ ft/ft
 $n_{STREET} = 0.016$

Max. Allowable Spread for Minor & Major Storm
 Max. Allowable Depth at Gutter Flowline for Minor & Major Storm
 Check boxes are not applicable in SUMP conditions

| | Minor Storm | Major Storm | |
|-------------|--------------------------|--------------------------|--------|
| $T_{MAX} =$ | 18.0 | 18.0 | ft |
| $d_{MAX} =$ | 6.0 | 12.0 | inches |
| | <input type="checkbox"/> | <input type="checkbox"/> | |


MINOR STORM Allowable Capacity is based on Depth Criterion
MAJOR STORM Allowable Capacity is based on Depth Criterion

$Q_{allow} =$

| Minor Storm | Major Storm | |
|-------------|-------------|-----|
| SUMP | SUMP | cfs |

INLET IN A SUMP OR SAG LOCATION

Version 4.06 Released August 2018




| Design Information (Input) | MINOR | MAJOR | |
|--|--------------------------|-------|---|
| Type of Inlet | CDOT Type R Curb Opening | | |
| Local Depression (additional to continuous gutter depression 'a' from above) | 3.00 | 3.00 | inches |
| Number of Unit Inlets (Grate or Curb Opening) | 1 | 1 | |
| Water Depth at Flowline (outside of local depression) | 4.7 | 5.4 | inches |
| Grate Information | MINOR | MAJOR | <input checked="" type="checkbox"/> Override Depths |
| Length of a Unit Grate | N/A | N/A | feet |
| Width of a Unit Grate | N/A | N/A | feet |
| Area Opening Ratio for a Grate (typical values 0.15-0.90) | N/A | N/A | |
| Clogging Factor for a Single Grate (typical value 0.50 - 0.70) | N/A | N/A | |
| Grate Weir Coefficient (typical value 2.15 - 3.60) | N/A | N/A | |
| Grate Orifice Coefficient (typical value 0.60 - 0.80) | N/A | N/A | |
| Curb Opening Information | MINOR | MAJOR | |
| Length of a Unit Curb Opening | 5.00 | 5.00 | feet |
| Height of Vertical Curb Opening in Inches | 6.00 | 6.00 | inches |
| Height of Curb Orifice Throat in Inches | 6.00 | 6.00 | inches |
| Angle of Throat (see USDCM Figure ST-5) | 63.40 | 63.40 | degrees |
| Side Width for Depression Pan (typically the gutter width of 2 feet) | 2.00 | 2.00 | feet |
| Clogging Factor for a Single Curb Opening (typical value 0.10) | 0.10 | 0.10 | |
| Curb Opening Weir Coefficient (typical value 2.3-3.7) | 3.60 | 3.60 | |
| Curb Opening Orifice Coefficient (typical value 0.60 - 0.70) | 0.67 | 0.67 | |
| Low Head Performance Reduction (Calculated) | MINOR | MAJOR | |
| Depth for Grate Midwidth | N/A | N/A | ft |
| Depth for Curb Opening Weir Equation | 0.23 | 0.28 | ft |
| Combination Inlet Performance Reduction Factor for Long Inlets | 0.61 | 0.69 | |
| Curb Opening Performance Reduction Factor for Long Inlets | 1.00 | 1.00 | |
| Grated Inlet Performance Reduction Factor for Long Inlets | N/A | N/A | |
| Total Inlet Interception Capacity (assumes clogged condition) | MINOR | MAJOR | |
| Inlet Capacity IS GOOD for Minor and Major Storms(>Q PEAK) | 3.1 | 4.2 | cfs |
| Q PEAK REQUIRED = | 1.9 | 4.1 | cfs |

ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project:
Inlet ID:

Solace Apartments
B15



Gutter Geometry (Enter data in the blue cells)

Maximum Allowable Width for Spread Behind Curb
 Side Slope Behind Curb (leave blank for no conveyance credit behind curb)
 Manning's Roughness Behind Curb (typically between 0.012 and 0.020)
 Height of Curb at Gutter Flow Line
 Distance from Curb Face to Street Crown
 Gutter Width
 Street Transverse Slope
 Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)
 Street Longitudinal Slope - Enter 0 for sump condition
 Manning's Roughness for Street Section (typically between 0.012 and 0.020)

$T_{BACK} = 4.0$ ft
 $S_{BACK} = 0.020$ ft/ft
 $n_{BACK} = 0.016$

$H_{CURB} = 6.00$ inches
 $T_{CROWN} = 18.0$ ft
 $W = 2.00$ ft
 $S_X = 0.020$ ft/ft
 $S_W = 0.083$ ft/ft
 $S_O = 0.000$ ft/ft
 $n_{STREET} = 0.016$

Max. Allowable Spread for Minor & Major Storm
 Max. Allowable Depth at Gutter Flowline for Minor & Major Storm
 Check boxes are not applicable in SUMP conditions

| | Minor Storm | Major Storm | |
|-------------|--------------------------|--------------------------|--------|
| $T_{MAX} =$ | 18.0 | 18.0 | ft |
| $d_{MAX} =$ | 6.0 | 12.0 | inches |
| | <input type="checkbox"/> | <input type="checkbox"/> | |


MINOR STORM Allowable Capacity is based on Depth Criterion
MAJOR STORM Allowable Capacity is based on Depth Criterion

$Q_{allow} =$

| Minor Storm | Major Storm | |
|-------------|-------------|-----|
| SUMP | SUMP | cfs |

INLET IN A SUMP OR SAG LOCATION

Version 4.06 Released August 2018




| Design Information (Input) | MINOR | MAJOR | |
|--|----------------------------|--------|---|
| Type of Inlet | Denver No. 16 Valley Grate | | |
| Local Depression (additional to continuous gutter depression 'a' from above) | $a_{local} = 2.00$ | 2.00 | inches |
| Number of Unit Inlets (Grate or Curb Opening) | No = 2 | 2 | |
| Water Depth at Flowline (outside of local depression) | Ponding Depth = 3.2 | 4.3 | inches |
| Grate Information | MINOR | MAJOR | <input checked="" type="checkbox"/> Override Depths |
| Length of a Unit Grate | $L_g (G) = 3.00$ | 3.00 | feet |
| Width of a Unit Grate | $W_o = 1.73$ | 1.73 | feet |
| Area Opening Ratio for a Grate (typical values 0.15-0.90) | $A_{ratio} = 0.31$ | 0.31 | |
| Clogging Factor for a Single Grate (typical value 0.50 - 0.70) | $C_l (G) = 0.50$ | 0.50 | |
| Grate Weir Coefficient (typical value 2.15 - 3.60) | $C_w (G) = 3.60$ | 3.60 | |
| Grate Orifice Coefficient (typical value 0.60 - 0.80) | $C_o (G) = 0.60$ | 0.60 | |
| Curb Opening Information | MINOR | MAJOR | |
| Length of a Unit Curb Opening | $L_c (C) = N/A$ | N/A | feet |
| Height of Vertical Curb Opening in Inches | $H_{vert} = N/A$ | N/A | inches |
| Height of Curb Orifice Throat in Inches | $H_{throat} = N/A$ | N/A | inches |
| Angle of Throat (see USDCM Figure ST-5) | $\theta = N/A$ | N/A | degrees |
| Side Width for Depression Pan (typically the gutter width of 2 feet) | $W_p = N/A$ | N/A | feet |
| Clogging Factor for a Single Curb Opening (typical value 0.10) | $C_l (C) = N/A$ | N/A | |
| Curb Opening Weir Coefficient (typical value 2.3-3.7) | $C_w (C) = N/A$ | N/A | |
| Curb Opening Orifice Coefficient (typical value 0.60 - 0.70) | $C_o (C) = N/A$ | N/A | |
| Low Head Performance Reduction (Calculated) | MINOR | MAJOR | |
| Depth for Grate Midwidth | $d_{grate} = 0.294$ | 0.381 | ft |
| Depth for Curb Opening Weir Equation | $d_{curb} = N/A$ | N/A | ft |
| Combination Inlet Performance Reduction Factor for Long Inlets | $RF_{combination} = N/A$ | N/A | |
| Curb Opening Performance Reduction Factor for Long Inlets | $RF_{curb} = N/A$ | N/A | |
| Grated Inlet Performance Reduction Factor for Long Inlets | $RF_{grate} = 0.38$ | 0.51 | |
| Total Inlet Interception Capacity (assumes clogged condition) | MINOR | MAJOR | |
| Inlet Capacity IS GOOD for Minor and Major Storms(>Q PEAK) | $Q_a = 0.9$ | 1.8 | cfs |
| $Q_{PEAK REQUIRED} =$ | 0.9 | 1.8 | cfs |

ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project:
Inlet ID:

Solace Apartments
B17



Gutter Geometry (Enter data in the blue cells)

Maximum Allowable Width for Spread Behind Curb
 Side Slope Behind Curb (leave blank for no conveyance credit behind curb)
 Manning's Roughness Behind Curb (typically between 0.012 and 0.020)
 Height of Curb at Gutter Flow Line
 Distance from Curb Face to Street Crown
 Gutter Width
 Street Transverse Slope
 Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)
 Street Longitudinal Slope - Enter 0 for sump condition
 Manning's Roughness for Street Section (typically between 0.012 and 0.020)

$T_{BACK} = 20.0$ ft
 $S_{BACK} = 0.020$ ft/ft
 $n_{BACK} = 0.016$
 $H_{CURB} = 6.00$ inches
 $T_{CROWN} = 20.0$ ft
 $W = 2.00$ ft
 $S_x = 0.020$ ft/ft
 $S_w = 0.083$ ft/ft
 $S_o = 0.015$ ft/ft
 $n_{STREET} = 0.016$

Max. Allowable Spread for Minor & Major Storm
 Max. Allowable Depth at Gutter Flowline for Minor & Major Storm
 Allow Flow Depth at Street Crown (leave blank for no)

| | Minor Storm | Major Storm | |
|-------------|--------------------------|--------------------------|-------------|
| $T_{MAX} =$ | 20.0 | 20.0 | ft |
| $d_{MAX} =$ | 6.0 | 12.0 | inches |
| | <input type="checkbox"/> | <input type="checkbox"/> | check = yes |


MINOR STORM Allowable Capacity is based on Depth Criterion
MAJOR STORM Allowable Capacity is based on Spread Criterion

| | Minor Storm | Major Storm | |
|---------------|-------------|-------------|-----|
| $Q_{allow} =$ | 16.9 | 20.0 | cfs |

Minor storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'
Major storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'

INLET ON A CONTINUOUS GRADE

Version 4.06 Released August 2018




| Design Information (Input) | MINOR | MAJOR | |
|---|--------------------------|-------|--------|
| Type of Inlet | CDOT Type R Curb Opening | | |
| Local Depression (additional to continuous gutter depression 'a') | 3.0 | 3.0 | inches |
| Total Number of Units in the Inlet (Grate or Curb Opening) | 1 | 1 | |
| Length of a Single Unit Inlet (Grate or Curb Opening) | 10.00 | 10.00 | ft |
| Width of a Unit Grate (cannot be greater than W, Gutter Width) | N/A | N/A | ft |
| Clogging Factor for a Single Unit Grate (typical min. value = 0.5) | N/A | N/A | |
| Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.1) | 0.10 | 0.10 | |
| Street Hydraulics: OK - Q < Allowable Street Capacity | | | |
| Total Inlet Interception Capacity | 1.8 | 4.3 | cfs |
| Total Inlet Carry-Over Flow (flow bypassing inlet) | 0.0 | 0.2 | cfs |
| Capture Percentage = Q_i/Q_o = | 100 | 96 | % |

ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project:
Inlet ID:

Solace Apartments
B18



Gutter Geometry (Enter data in the blue cells)

Maximum Allowable Width for Spread Behind Curb
 Side Slope Behind Curb (leave blank for no conveyance credit behind curb)
 Manning's Roughness Behind Curb (typically between 0.012 and 0.020)
 Height of Curb at Gutter Flow Line
 Distance from Curb Face to Street Crown
 Gutter Width
 Street Transverse Slope
 Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)
 Street Longitudinal Slope - Enter 0 for sump condition
 Manning's Roughness for Street Section (typically between 0.012 and 0.020)

$T_{BACK} = 20.0$ ft
 $S_{BACK} = 0.020$ ft/ft
 $n_{BACK} = 0.016$
 $H_{CURB} = 6.00$ inches
 $T_{CROWN} = 20.0$ ft
 $W = 2.00$ ft
 $S_X = 0.020$ ft/ft
 $S_W = 0.083$ ft/ft
 $S_0 = 0.015$ ft/ft
 $n_{STREET} = 0.016$

Max. Allowable Spread for Minor & Major Storm
 Max. Allowable Depth at Gutter Flowline for Minor & Major Storm
 Allow Flow Depth at Street Crown (leave blank for no)

| | Minor Storm | Major Storm | |
|-------------|--------------------------|--------------------------|-------------|
| $T_{MAX} =$ | 20.0 | 20.0 | ft |
| $d_{MAX} =$ | 6.0 | 12.0 | inches |
| | <input type="checkbox"/> | <input type="checkbox"/> | check = yes |


MINOR STORM Allowable Capacity is based on Depth Criterion
MAJOR STORM Allowable Capacity is based on Spread Criterion

| | Minor Storm | Major Storm | |
|---------------|-------------|-------------|-----|
| $Q_{allow} =$ | 16.9 | 20.0 | cfs |

Minor storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'
Major storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'

INLET ON A CONTINUOUS GRADE

Version 4.06 Released August 2018




| Design Information (Input) | MINOR | MAJOR | |
|---|--------------------------|-------|--------|
| Type of Inlet | CDOT Type R Curb Opening | | |
| Local Depression (additional to continuous gutter depression 'a') | 3.0 | 3.0 | inches |
| Total Number of Units in the Inlet (Grate or Curb Opening) | 1 | 1 | |
| Length of a Single Unit Inlet (Grate or Curb Opening) | 10.00 | 10.00 | ft |
| Width of a Unit Grate (cannot be greater than W, Gutter Width) | N/A | N/A | ft |
| Clogging Factor for a Single Unit Grate (typical min. value = 0.5) | N/A | N/A | |
| Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.1) | 0.10 | 0.10 | |
| Street Hydraulics: OK - Q < Allowable Street Capacity | | | |
| Total Inlet Interception Capacity | 1.1 | 2.4 | cfs |
| Total Inlet Carry-Over Flow (flow bypassing inlet) | 0.0 | 0.0 | cfs |
| Capture Percentage = Q_i/Q_o = | 100 | 100 | % |

ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project:
Inlet ID:

Solace Apartments
B19



Gutter Geometry (Enter data in the blue cells)

Maximum Allowable Width for Spread Behind Curb
 Side Slope Behind Curb (leave blank for no conveyance credit behind curb)
 Manning's Roughness Behind Curb (typically between 0.012 and 0.020)
 Height of Curb at Gutter Flow Line
 Distance from Curb Face to Street Crown
 Gutter Width
 Street Transverse Slope
 Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)
 Street Longitudinal Slope - Enter 0 for sump condition
 Manning's Roughness for Street Section (typically between 0.012 and 0.020)

$T_{BACK} = 20.0$ ft
 $S_{BACK} = 0.020$ ft/ft
 $n_{BACK} = 0.016$
 $H_{CURB} = 6.00$ inches
 $T_{CROWN} = 20.0$ ft
 $W = 2.00$ ft
 $S_X = 0.020$ ft/ft
 $S_W = 0.083$ ft/ft
 $S_0 = 0.010$ ft/ft
 $n_{STREET} = 0.016$

Max. Allowable Spread for Minor & Major Storm
 Max. Allowable Depth at Gutter Flowline for Minor & Major Storm
 Allow Flow Depth at Street Crown (leave blank for no)

| | Minor Storm | Major Storm | |
|-------------|--------------------------|--------------------------|-------------|
| $T_{MAX} =$ | 20.0 | 20.0 | ft |
| $d_{MAX} =$ | 6.0 | 12.0 | inches |
| | <input type="checkbox"/> | <input type="checkbox"/> | check = yes |


MINOR STORM Allowable Capacity is based on Depth Criterion
MAJOR STORM Allowable Capacity is based on Spread Criterion

| | Minor Storm | Major Storm | |
|---------------|-------------|-------------|-----|
| $Q_{allow} =$ | 13.8 | 16.3 | cfs |

Minor storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'
Major storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'

INLET ON A CONTINUOUS GRADE

Version 4.06 Released August 2018




| Design Information (Input) | MINOR | MAJOR | |
|---|--------------------------|-------|--------|
| Type of Inlet | CDOT Type R Curb Opening | | |
| Local Depression (additional to continuous gutter depression 'a') | 3.0 | 3.0 | inches |
| Total Number of Units in the Inlet (Grate or Curb Opening) | 1 | 1 | |
| Length of a Single Unit Inlet (Grate or Curb Opening) | 15.00 | 15.00 | ft |
| Width of a Unit Grate (cannot be greater than W, Gutter Width) | N/A | N/A | ft |
| Clogging Factor for a Single Unit Grate (typical min. value = 0.5) | N/A | N/A | |
| Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.1) | 0.10 | 0.10 | |
| Street Hydraulics: OK - Q < Allowable Street Capacity | | | |
| Total Inlet Interception Capacity | 2.1 | 5.8 | cfs |
| Total Inlet Carry-Over Flow (flow bypassing inlet) | 0.0 | 0.0 | cfs |
| Capture Percentage = Q_i/Q_o = | 100 | 100 | % |

ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project:
Inlet ID:

Solace Apartments
B20



Gutter Geometry (Enter data in the blue cells)

Maximum Allowable Width for Spread Behind Curb
Side Slope Behind Curb (leave blank for no conveyance credit behind curb)
Manning's Roughness Behind Curb (typically between 0.012 and 0.020)

$T_{BACK} = 20.0$ ft
 $S_{BACK} = 0.020$ ft/ft
 $n_{BACK} = 0.016$

Height of Curb at Gutter Flow Line
Distance from Curb Face to Street Crown
Gutter Width
Street Transverse Slope
Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)
Street Longitudinal Slope - Enter 0 for sump condition
Manning's Roughness for Street Section (typically between 0.012 and 0.020)

$H_{CURB} = 6.00$ inches
 $T_{CROWN} = 20.0$ ft
 $W = 2.00$ ft
 $S_X = 0.020$ ft/ft
 $S_W = 0.083$ ft/ft
 $S_0 = 1.000$ ft/ft
 $n_{STREET} = 0.016$

Max. Allowable Spread for Minor & Major Storm
Max. Allowable Depth at Gutter Flowline for Minor & Major Storm
Allow Flow Depth at Street Crown (leave blank for no)

| | Minor Storm | Major Storm | |
|-------------|-------------|-------------|--------|
| $T_{MAX} =$ | 20.0 | 20.0 | ft |
| $d_{MAX} =$ | 6.0 | 12.0 | inches |

check = yes


MINOR STORM Allowable Capacity is based on Depth Criterion
MAJOR STORM Allowable Capacity is based on Depth Criterion

| | Minor Storm | Major Storm | |
|---------------|-------------|-------------|-----|
| $Q_{allow} =$ | 6.2 | 46.5 | cfs |

Minor storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'
Major storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'

INLET ON A CONTINUOUS GRADE

Version 4.06 Released August 2018



| Design Information (Input) | MINOR | MAJOR | |
|---|--------------------------|-------|--------|
| Type of Inlet | CDOT Type R Curb Opening | | |
| Local Depression (additional to continuous gutter depression 'a') | 3.0 | 3.0 | inches |
| Total Number of Units in the Inlet (Grate or Curb Opening) | 1 | 1 | |
| Length of a Single Unit Inlet (Grate or Curb Opening) | 10.00 | 10.00 | ft |
| Width of a Unit Grate (cannot be greater than W, Gutter Width) | N/A | N/A | ft |
| Clogging Factor for a Single Unit Grate (typical min. value = 0.5) | N/A | N/A | |
| Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.1) | 0.10 | 0.10 | |
| Street Hydraulics: OK - Q < Allowable Street Capacity | | | |
| Total Inlet Interception Capacity | 0.6 | 1.4 | cfs |
| Total Inlet Carry-Over Flow (flow bypassing inlet) | 0.0 | 0.0 | cfs |
| Capture Percentage = Q_i/Q_o = | 100 | 100 | % |






Figure 8-22. Swale stability chart; 2- to 4-foot bottom width and side slopes between 5:1 and 10:1
 (Note: Riprap classifications refer to gradation for riprap used in soil riprap or void-filled riprap. See Figure 8-34 for gradations.) (Source: Muller Engineering Company)

APPENDIX C

WATER QUALITY AND DETENTION CALCULATIONS

DETENTION BASIN STAGE-STORAGE TABLE BUILDER


MHFD-Detention, Version 4.03 (May 2020)



DETENTION BASIN OUTLET STRUCTURE DESIGN

MHFD-Detention, Version 4.03 (May 2020)

Project: Solace Apartments
Basin ID: Pond A



Example Zone Configuration (Retention Pond)

| | Estimated Stage (ft) | Estimated Volume (ac-ft) | Outlet Type |
|--------------------------|----------------------|--------------------------|----------------------|
| Zone 1 (WQCV) | 2.49 | 0.135 | Orifice Plate |
| Zone 2 (EURV) | 3.77 | 0.282 | Circular Orifice |
| Zone 3 (100-year) | 4.70 | 0.315 | Weir&Pipe (Restrict) |
| Total (all zones) | | 0.732 | |

User Input: Orifice at Underdrain Outlet (typically used to drain WQCV in a Filtration BMP)

Underdrain Orifice Invert Depth = ft (distance below the filtration media surface)
Underdrain Orifice Diameter = inches

Calculated Parameters for Underdrain
Underdrain Orifice Area = ft²
Underdrain Orifice Centroid = feet

User Input: Orifice Plate with one or more orifices or Elliptical Slot Weir (typically used to drain WQCV and/or EURV in a sedimentation BMP)

Invert of Lowest Orifice = ft (relative to basin bottom at Stage = 0 ft)
Depth at top of Zone using Orifice Plate = ft (relative to basin bottom at Stage = 0 ft)
Orifice Plate: Orifice Vertical Spacing = inches
Orifice Plate: Orifice Area per Row = sq. inches (diameter = 3/4 inch)

Calculated Parameters for Plate
WQ Orifice Area per Row = ft²
Elliptical Half-Width = feet
Elliptical Slot Centroid = feet
Elliptical Slot Area = ft²

User Input: Stage and Total Area of Each Orifice Row (numbered from lowest to highest)

| | Row 1 (required) | Row 2 (optional) | Row 3 (optional) | Row 4 (optional) | Row 5 (optional) | Row 6 (optional) | Row 7 (optional) | Row 8 (optional) |
|--------------------------------|------------------|------------------|------------------|------------------|------------------|------------------|------------------|------------------|
| Stage of Orifice Centroid (ft) | 0.00 | 0.70 | 1.40 | 2.10 | | | | |
| Orifice Area (sq. inches) | 0.45 | 0.45 | 0.45 | 0.45 | | | | |

| | Row 9 (optional) | Row 10 (optional) | Row 11 (optional) | Row 12 (optional) | Row 13 (optional) | Row 14 (optional) | Row 15 (optional) | Row 16 (optional) |
|--------------------------------|------------------|-------------------|-------------------|-------------------|-------------------|-------------------|-------------------|-------------------|
| Stage of Orifice Centroid (ft) | | | | | | | | |
| Orifice Area (sq. inches) | | | | | | | | |

User Input: Vertical Orifice (Circular or Rectangular)

| | Zone 2 Circular | Not Selected | |
|---|-----------------|--------------|---|
| Invert of Vertical Orifice = | 2.49 | N/A | ft (relative to basin bottom at Stage = 0 ft) |
| Depth at top of Zone using Vertical Orifice = | 3.77 | N/A | ft (relative to basin bottom at Stage = 0 ft) |
| Vertical Orifice Diameter = | 0.38 | N/A | inches |

Calculated Parameters for Vertical Orifice

| | Zone 2 Circular | Not Selected | |
|-----------------------------|-----------------|--------------|-----------------|
| Vertical Orifice Area = | 0.00 | N/A | ft ² |
| Vertical Orifice Centroid = | 0.02 | N/A | feet |

User Input: Overflow Weir (Dropbox with Flat or Sloped Gate and Outlet Pipe OR Rectangular/Trapezoidal Weir (and No Outlet Pipe))

| | Zone 3 Weir | Not Selected | |
|---------------------------------------|-------------|--------------|---|
| Overflow Weir Front Edge Height, Ho = | 3.77 | N/A | ft (relative to basin bottom at Stage = 0 ft) |
| Overflow Weir Front Edge Length = | 4.00 | N/A | feet |
| Overflow Weir Gate Slope = | 0.00 | N/A | H:V |
| Horiz. Length of Weir Sides = | 3.00 | N/A | feet |
| Overflow Gate Open Area % = | 70% | N/A | %, gate open area/total area |
| Debris Clogging % = | 50% | N/A | % |

Calculated Parameters for Overflow Weir

| | Zone 3 Weir | Not Selected | |
|---|-------------|--------------|-----------------|
| Height of Gate Upper Edge, H _i = | 3.77 | N/A | feet |
| Overflow Weir Slope Length = | 3.00 | N/A | feet |
| Gate Open Area / 100-yr Orifice Area = | 28.73 | N/A | |
| Overflow Gate Open Area w/o Debris = | 8.40 | N/A | ft ² |
| Overflow Gate Open Area w/ Debris = | 4.20 | N/A | ft ² |

User Input: Outlet Pipe w/ Flow Restriction Plate (Circular Orifice, Restrictor Plate, or Rectangular Orifice)

| | Zone 3 Restrictor | Not Selected | |
|---|-------------------|--------------|--|
| Depth to Invert of Outlet Pipe = | 0.00 | N/A | ft (distance below basin bottom at Stage = 0 ft) |
| Outlet Pipe Diameter = | 18.00 | N/A | inches |
| Restrictor Plate Height Above Pipe Invert = | 4.00 | | inches |

Calculated Parameters for Outlet Pipe w/ Flow Restriction Plate

| | Zone 3 Restrictor | Not Selected | |
|--|-------------------|--------------|-----------------|
| Outlet Orifice Area = | 0.29 | N/A | ft ² |
| Outlet Orifice Centroid = | 0.20 | N/A | feet |
| Half-Central Angle of Restrictor Plate on Pipe = | 0.98 | N/A | radians |

User Input: Emergency Spillway (Rectangular or Trapezoidal)

| Spillway Invert Stage = | 5.47 | ft (relative to basin bottom at Stage = 0 ft) | |
|-------------------------------------|-------|---|--|
| Spillway Crest Length = | 40.00 | feet | |
| Spillway End Slopes = | 10.00 | H:V | |
| Freeboard above Max Water Surface = | 1.00 | feet | |

Calculated Parameters for Spillway

| Spillway Design Flow Depth = | 0.31 | feet |
|------------------------------------|------|---------|
| Stage at Top of Freeboard = | 6.78 | feet |
| Basin Area at Top of Freeboard = | 0.48 | acres |
| Basin Volume at Top of Freeboard = | 1.29 | acre-ft |




Routed Hydrograph Results

The user can override the default CUHP hydrographs and runoff volumes by entering new values in the Inflow Hydrographs table (Columns W through AF).

| | WQCV | EURV | 2 Year | 5 Year | 10 Year | 25 Year | 50 Year | 100 Year | 500 Year |
|---|-------|-----------------|--------------------|-----------------|----------------|----------------|----------------|----------------|----------|
| Design Storm Return Period | N/A | N/A | 1.19 | 1.50 | 1.75 | 2.00 | 2.26 | 2.52 | 3.14 |
| One-Hour Rainfall Depth (in) | N/A | N/A | 1.19 | 1.50 | 1.75 | 2.00 | 2.26 | 2.52 | 3.14 |
| CUHP Runoff Volume (acre-ft) | 0.135 | 0.417 | 0.382 | 0.546 | 0.691 | 0.887 | 1.052 | 1.247 | 1.654 |
| Inflow Hydrograph Volume (acre-ft) | N/A | N/A | 0.382 | 0.546 | 0.691 | 0.887 | 1.052 | 1.247 | 1.654 |
| CUHP Predevelopment Peak Q (cfs) | N/A | N/A | 0.9 | 2.7 | 4.0 | 7.2 | 9.1 | 11.2 | 15.7 |
| OPTIONAL Override Predevelopment Peak Q (cfs) | N/A | N/A | | | | | | | |
| Predevelopment Unit Peak Flow, q (cfs/acre) | N/A | N/A | 0.12 | 0.34 | 0.51 | 0.91 | 1.15 | 1.42 | 1.99 |
| Peak Inflow Q (cfs) | N/A | N/A | 6.7 | 9.8 | 12.0 | 15.6 | 18.5 | 22.1 | 28.9 |
| Peak Outflow Q (cfs) | 0.1 | 0.1 | 0.1 | 1.3 | 2.7 | 2.9 | 3.0 | 3.2 | 12.0 |
| Ratio Peak Outflow to Predevelopment Q | N/A | N/A | N/A | 0.5 | 0.7 | 0.4 | 0.3 | 0.3 | 0.8 |
| Structure Controlling Flow | Plate | Overflow Weir 1 | Vertical Orifice 1 | Overflow Weir 1 | Outlet Plate 1 | Outlet Plate 1 | Outlet Plate 1 | Outlet Plate 1 | Spillway |
| Max Velocity through Gate 1 (fps) | N/A | N/A | N/A | 0.1 | 0.3 | 0.3 | 0.3 | 0.4 | 0.4 |
| Max Velocity through Gate 2 (fps) | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A |
| Time to Drain 97% of Inflow Volume (hours) | 37 | 70 | 67 | 72 | 70 | 68 | 67 | 66 | 63 |
| Time to Drain 99% of Inflow Volume (hours) | 40 | 76 | 72 | 78 | 77 | 76 | 76 | 75 | 74 |
| Maximum Ponding Depth (ft) | 2.49 | 3.77 | 3.58 | 3.89 | 4.01 | 4.46 | 4.80 | 5.26 | 5.64 |
| Area at Maximum Ponding Depth (acres) | 0.15 | 0.29 | 0.27 | 0.31 | 0.32 | 0.36 | 0.39 | 0.42 | 0.45 |
| Maximum Volume Stored (acre-ft) | 0.135 | 0.417 | 0.364 | 0.450 | 0.491 | 0.641 | 0.768 | 0.954 | 1.125 |

DETENTION BASIN OUTLET STRUCTURE DESIGN

MHFD-Detention, Version 4.00 (December 2019)



S-A-V-D Chart Axis Override

| | X-axis | Left Y-Axis | Right Y-Axis |
|---------------|--------|-------------|--------------|
| minimum bound | | | |
| maximum bound | | | |

DETENTION BASIN OUTLET STRUCTURE DESIGN

Outflow Hydrograph Workbook Filename: _____

Inflow Hydrographs

The user can override the calculated inflow hydrographs from this workbook with inflow hydrographs developed in a separate program.

| Time Interval | SOURCE | CUHP | CUHP | CUHP | CUHP | CUHP | CUHP | CUHP | CUHP | CUHP |
|---------------|---------|------------|------------|--------------|--------------|---------------|---------------|---------------|----------------|----------------|
| | TIME | WQCV [cfs] | EURV [cfs] | 2 Year [cfs] | 5 Year [cfs] | 10 Year [cfs] | 25 Year [cfs] | 50 Year [cfs] | 100 Year [cfs] | 500 Year [cfs] |
| 5.00 min | 0:00:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 0:05:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 0:10:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.08 | 0.01 | 0.24 |
| | 0:15:00 | 0.00 | 0.00 | 0.66 | 1.08 | 1.34 | 0.90 | 1.12 | 1.10 | 1.55 |
| | 0:20:00 | 0.00 | 0.00 | 2.29 | 2.99 | 3.69 | 2.21 | 2.58 | 2.76 | 3.72 |
| | 0:25:00 | 0.00 | 0.00 | 5.25 | 7.86 | 10.25 | 5.16 | 6.14 | 6.79 | 10.27 |
| | 0:30:00 | 0.00 | 0.00 | 6.66 | 9.76 | 11.95 | 14.01 | 16.83 | 18.97 | 25.29 |
| | 0:35:00 | 0.00 | 0.00 | 6.09 | 8.72 | 10.62 | 15.64 | 18.54 | 22.08 | 28.92 |
| | 0:40:00 | 0.00 | 0.00 | 5.30 | 7.42 | 9.07 | 14.86 | 17.52 | 20.71 | 27.03 |
| | 0:45:00 | 0.00 | 0.00 | 4.33 | 6.18 | 7.70 | 12.90 | 15.22 | 18.61 | 24.26 |
| | 0:50:00 | 0.00 | 0.00 | 3.56 | 5.17 | 6.33 | 11.37 | 13.40 | 16.27 | 21.18 |
| | 0:55:00 | 0.00 | 0.00 | 3.00 | 4.33 | 5.39 | 9.24 | 10.91 | 13.68 | 17.88 |
| | 1:00:00 | 0.00 | 0.00 | 2.63 | 3.76 | 4.77 | 7.76 | 9.21 | 11.94 | 15.65 |
| | 1:05:00 | 0.00 | 0.00 | 2.32 | 3.29 | 4.23 | 6.71 | 7.99 | 10.71 | 14.07 |
| | 1:10:00 | 0.00 | 0.00 | 1.90 | 2.84 | 3.72 | 5.49 | 6.56 | 8.51 | 11.25 |
| | 1:15:00 | 0.00 | 0.00 | 1.52 | 2.33 | 3.25 | 4.44 | 5.31 | 6.64 | 8.87 |
| | 1:20:00 | 0.00 | 0.00 | 1.22 | 1.86 | 2.66 | 3.38 | 4.03 | 4.82 | 6.43 |
| | 1:25:00 | 0.00 | 0.00 | 1.05 | 1.60 | 2.19 | 2.55 | 3.05 | 3.40 | 4.58 |
| | 1:30:00 | 0.00 | 0.00 | 0.98 | 1.47 | 1.90 | 1.99 | 2.37 | 2.55 | 3.46 |
| | 1:35:00 | 0.00 | 0.00 | 0.93 | 1.39 | 1.70 | 1.65 | 1.95 | 2.04 | 2.77 |
| | 1:40:00 | 0.00 | 0.00 | 0.91 | 1.23 | 1.56 | 1.42 | 1.67 | 1.70 | 2.30 |
| | 1:45:00 | 0.00 | 0.00 | 0.89 | 1.11 | 1.47 | 1.27 | 1.49 | 1.46 | 1.99 |
| | 1:50:00 | 0.00 | 0.00 | 0.88 | 1.02 | 1.40 | 1.18 | 1.36 | 1.30 | 1.76 |
| | 1:55:00 | 0.00 | 0.00 | 0.76 | 0.96 | 1.30 | 1.11 | 1.28 | 1.19 | 1.61 |
| | 2:00:00 | 0.00 | 0.00 | 0.67 | 0.88 | 1.16 | 1.07 | 1.22 | 1.13 | 1.53 |
| | 2:05:00 | 0.00 | 0.00 | 0.49 | 0.64 | 0.84 | 0.78 | 0.89 | 0.82 | 1.11 |
| | 2:10:00 | 0.00 | 0.00 | 0.36 | 0.46 | 0.60 | 0.56 | 0.64 | 0.59 | 0.80 |
| | 2:15:00 | 0.00 | 0.00 | 0.26 | 0.33 | 0.43 | 0.40 | 0.45 | 0.43 | 0.57 |
| | 2:20:00 | 0.00 | 0.00 | 0.18 | 0.23 | 0.30 | 0.28 | 0.32 | 0.30 | 0.40 |
| | 2:25:00 | 0.00 | 0.00 | 0.12 | 0.15 | 0.21 | 0.19 | 0.22 | 0.21 | 0.28 |
| | 2:30:00 | 0.00 | 0.00 | 0.08 | 0.10 | 0.14 | 0.13 | 0.15 | 0.14 | 0.19 |
| | 2:35:00 | 0.00 | 0.00 | 0.05 | 0.07 | 0.09 | 0.09 | 0.10 | 0.09 | 0.13 |
| | 2:40:00 | 0.00 | 0.00 | 0.03 | 0.04 | 0.05 | 0.05 | 0.06 | 0.05 | 0.07 |
| | 2:45:00 | 0.00 | 0.00 | 0.01 | 0.02 | 0.02 | 0.03 | 0.03 | 0.03 | 0.03 |
| | 2:50:00 | 0.00 | 0.00 | 0.00 | 0.01 | 0.01 | 0.01 | 0.01 | 0.01 | 0.01 |
| | 2:55:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 3:00:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 3:05:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 3:10:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 3:15:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 3:20:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 3:25:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 3:30:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 3:35:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 3:40:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 3:45:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 3:50:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 3:55:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 4:00:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 4:05:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 4:10:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 4:15:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 4:20:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 4:25:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 4:30:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 4:35:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 4:40:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 4:45:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 4:50:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 4:55:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 5:00:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 5:05:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 5:10:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 5:15:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 5:20:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 5:25:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 5:30:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 5:35:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 5:40:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 5:45:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 5:50:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 5:55:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 6:00:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |

Detention Pond A North Forebay Calculations

| | | | |
|---------------------------------------|--------|-------|--|
| 100 YR Discharge | 11.3 | CFS | |
| WQCV Storage | 0.135 | AC-FT | |
| Forebay Volume (2% pf WQCV) | 0.0027 | AC-FT | |
| Forebay Release Volume (2% of 100 YR) | 0.226 | CFS | |

Weir Report

Hydraflow Express Extension for Autodesk® Civil 3D® by Autodesk, Inc.

Friday, Nov 6 2020

Pond A North Forebay Calculations

Rectangular Weir


Crest = Sharp
 Bottom Length (ft) = 0.25
 Total Depth (ft) = 1.25

Highlighted

Depth (ft) = 0.42
 Q (cfs) = 0.230
 Area (sqft) = 0.11
 Velocity (ft/s) = 2.17
 Top Width (ft) = 0.25

Calculations

Weir Coeff. Cw = 3.33
 Compute by: Known Q
 Known Q (cfs) = 0.23



Detention Pond A South Forebay Calculations

| | | |
|---------------------------------------|--------|-------|
| 100 YR Discharge | 19.4 | CFS |
| WQCV Storage | 0.135 | AC-FT |
| Forebay Volume (2% pf WQCV) | 0.0027 | AC-FT |
| Forebay Release Volume (2% of 100 YR) | 0.388 | CFS |

Weir Report

Hydraflow Express Extension for Autodesk® Civil 3D® by Autodesk, Inc.

Friday, Nov 6 2020

Pond A South Forebay Calculations

Rectangular Weir


Crest = Sharp
 Bottom Length (ft) = 0.25
 Total Depth (ft) = 1.25

Highlighted

Depth (ft) = 0.60
 Q (cfs) = 0.388
 Area (sqft) = 0.15
 Velocity (ft/s) = 2.58
 Top Width (ft) = 0.25

Calculations

Weir Coeff. Cw = 3.33
 Compute by: Known Q
 Known Q (cfs) = 0.39



Channel Report

Pond A Trickle Channel

Rectangular

Bottom Width (ft) = 2.00

Total Depth (ft) = 0.50

Invert Elev (ft) = 1.00

Slope (%) = 1.00

N-Value = 0.013

Calculations

Compute by: Known Q

Known Q (cfs) = 0.61

Highlighted

Depth (ft) = 0.12

Q (cfs) = 0.610

Area (sqft) = 0.24


Velocity (ft/s) = 2.54

Wetted Perim (ft) = 2.24

Crit Depth, Y_c (ft) = 0.15

Top Width (ft) = 2.00

EGL (ft) = 0.22



Channel Report

Pond A Spillway

Trapezoidal


Bottom Width (ft) = 40.00
Side Slopes (z:1) = 10.00, 10.00
Total Depth (ft) = 1.44
Invert Elev (ft) = 1.00
Slope (%) = 0.20
N-Value = 0.020

Highlighted

Depth (ft) = 0.41
Q (cfs) = 30.80
Area (sqft) = 18.08
Velocity (ft/s) = 1.70
Wetted Perim (ft) = 48.24
Crit Depth, Yc (ft) = 0.26
Top Width (ft) = 48.20
EGL (ft) = 0.46



Calculations

Compute by: Known Q
Known Q (cfs) = 30.80



DETENTION BASIN STAGE-STORAGE TABLE BUILDER

MHFD-Detention, Version 4.03 (May 2020)




DETENTION BASIN OUTLET STRUCTURE DESIGN

MHFD-Detention, Version 4.03 (May 2020)

Project: Solace Apartments

Basin ID: Pond B



Example Zone Configuration (Retention Pond)

| | Estimated Stage (ft) | Estimated Volume (ac-ft) | Outlet Type |
|--------------------------|----------------------|--------------------------|----------------------|
| Zone 1 (WQCV) | 2.60 | 0.264 | Orifice Plate |
| Zone 2 (EURV) | 3.63 | 0.482 | Circular Orifice |
| Zone 3 (100-year) | 4.68 | 0.666 | Weir&Pipe (Restrict) |
| Total (all zones) | | 1.412 | |

User Input: Orifice at Underdrain Outlet (typically used to drain WQCV in a Filtration BMP)

| | | |
|-----------------------------------|-----|--|
| Underdrain Orifice Invert Depth = | N/A | ft (distance below the filtration media surface) |
| Underdrain Orifice Diameter = | N/A | inches |

| | | |
|--------------------------------------|-----|-----------------|
| Calculated Parameters for Underdrain | | |
| Underdrain Orifice Area = | N/A | ft ² |
| Underdrain Orifice Centroid = | N/A | feet |

User Input: Orifice Plate with one or more orifices or Elliptical Slot Weir (typically used to drain WQCV and/or EURV in a sedimentation BMP)

| | | |
|--|------|---|
| Invert of Lowest Orifice = | 0.00 | ft (relative to basin bottom at Stage = 0 ft) |
| Depth at top of Zone using Orifice Plate = | 2.60 | ft (relative to basin bottom at Stage = 0 ft) |
| Orifice Plate: Orifice Vertical Spacing = | 6.00 | inches |
| Orifice Plate: Orifice Area per Row = | N/A | inches |

| | | |
|---------------------------------|-----|-----------------|
| Calculated Parameters for Plate | | |
| WQ Orifice Area per Row = | N/A | ft ² |
| Elliptical Half-Width = | N/A | feet |
| Elliptical Slot Centroid = | N/A | feet |
| Elliptical Slot Area = | N/A | ft ² |

User Input: Stage and Total Area of Each Orifice Row (numbered from lowest to highest)

| | Row 1 (required) | Row 2 (optional) | Row 3 (optional) | Row 4 (optional) | Row 5 (optional) | Row 6 (optional) | Row 7 (optional) | Row 8 (optional) |
|--------------------------------|------------------|------------------|------------------|------------------|------------------|------------------|------------------|------------------|
| Stage of Orifice Centroid (ft) | 0.00 | 0.50 | 1.00 | 1.50 | 2.00 | | | |
| Orifice Area (sq. inches) | 0.56 | 0.56 | 0.56 | 0.52 | 0.52 | | | |

| | Row 9 (optional) | Row 10 (optional) | Row 11 (optional) | Row 12 (optional) | Row 13 (optional) | Row 14 (optional) | Row 15 (optional) | Row 16 (optional) |
|--------------------------------|------------------|-------------------|-------------------|-------------------|-------------------|-------------------|-------------------|-------------------|
| Stage of Orifice Centroid (ft) | | | | | | | | |
| Orifice Area (sq. inches) | | | | | | | | |

User Input: Vertical Orifice (Circular or Rectangular)

| | Zone 2 Circular | Not Selected | |
|---|-----------------|--------------|---|
| Invert of Vertical Orifice = | 2.60 | N/A | ft (relative to basin bottom at Stage = 0 ft) |
| Depth at top of Zone using Vertical Orifice = | 3.63 | N/A | ft (relative to basin bottom at Stage = 0 ft) |
| Vertical Orifice Diameter = | 1.50 | N/A | inches |

| | | |
|--|------|-----|
| Calculated Parameters for Vertical Orifice | | |
| Vertical Orifice Area = | 0.01 | N/A |
| Vertical Orifice Centroid = | 0.06 | N/A |

User Input: Overflow Weir (Dropbox with Flat or Sloped Gate and Outlet Pipe OR Rectangular/Trapezoidal Weir (and No Outlet Pipe))

| | Zone 3 Weir | Not Selected | |
|---------------------------------------|-------------|--------------|---|
| Overflow Weir Front Edge Height, Ho = | 3.63 | N/A | ft (relative to basin bottom at Stage = 0 ft) |
| Overflow Weir Front Edge Length = | 4.00 | N/A | feet |
| Overflow Weir Gate Slope = | 0.00 | N/A | H:V |
| Horiz. Length of Weir Sides = | 3.00 | N/A | feet |
| Overflow Gate Open Area % = | 70% | N/A | %, gate open area/total area |
| Debris Clogging % = | 50% | N/A | % |

| | | |
|---|-------|-----|
| Calculated Parameters for Overflow Weir | | |
| Height of Gate Upper Edge, H ₁ = | 3.63 | N/A |
| Overflow Weir Slope Length = | 3.00 | N/A |
| Gate Open Area / 100-yr Orifice Area = | 28.73 | N/A |
| Overflow Gate Open Area w/o Debris = | 8.40 | N/A |
| Overflow Gate Open Area w/ Debris = | 4.20 | N/A |

User Input: Outlet Pipe w/ Flow Restriction Plate (Circular Orifice, Restrictor Plate, or Rectangular Orifice)

| | Zone 3 Restrictor | Not Selected | |
|---|-------------------|--------------|--|
| Depth to Invert of Outlet Pipe = | 0.00 | N/A | ft (distance below basin bottom at Stage = 0 ft) |
| Outlet Pipe Diameter = | 18.00 | N/A | inches |
| Restrictor Plate Height Above Pipe Invert = | 4.00 | | inches |

| | | |
|---|------|-----|
| Calculated Parameters for Outlet Pipe w/ Flow Restriction Plate | | |
| Outlet Orifice Area = | 0.29 | N/A |
| Outlet Orifice Centroid = | 0.20 | N/A |
| Half-Central Angle of Restrictor Plate on Pipe = | 0.98 | N/A |

User Input: Emergency Spillway (Rectangular or Trapezoidal)

| | | |
|-------------------------------------|-------|---|
| Spillway Invert Stage = | 6.10 | ft (relative to basin bottom at Stage = 0 ft) |
| Spillway Crest Length = | 50.00 | feet |
| Spillway End Slopes = | 10.00 | H:V |
| Freeboard above Max Water Surface = | 1.00 | feet |

| | | |
|------------------------------------|------|---------|
| Calculated Parameters for Spillway | | |
| Spillway Design Flow Depth = | 0.34 | feet |
| Stage at Top of Freeboard = | 7.44 | feet |
| Basin Area at Top of Freeboard = | 0.87 | acres |
| Basin Volume at Top of Freeboard = | 2.66 | acre-ft |




Routed Hydrograph Results

The user can override the default CUHP hydrographs and runoff volumes by entering new values in the Inflow Hydrographs table (Columns W through AF).

| | WQCV | EURV | 2 Year | 5 Year | 10 Year | 25 Year | 50 Year | 100 Year | 500 Year |
|---|-------|-----------------|--------------------|----------------|----------------|----------------|----------------|----------------|----------|
| Design Storm Return Period | | | | | | | | | |
| One-Hour Rainfall Depth (in) | N/A | N/A | 1.19 | 1.50 | 1.75 | 2.00 | 2.26 | 2.52 | 3.14 |
| CUHP Runoff Volume (acre-ft) | 0.264 | 0.746 | 0.729 | 1.088 | 1.408 | 1.872 | 2.246 | 2.702 | 3.634 |
| Inflow Hydrograph Volume (acre-ft) | N/A | N/A | 0.729 | 1.088 | 1.408 | 1.872 | 2.246 | 2.702 | 3.634 |
| CUHP Predevelopment Peak Q (cfs) | N/A | N/A | 1.4 | 4.0 | 6.1 | 11.3 | 14.3 | 18.2 | 25.4 |
| OPTIONAL Override Predevelopment Peak Q (cfs) | N/A | N/A | | | | | | | |
| Predevelopment Unit Peak Flow, q (cfs/acre) | N/A | N/A | 0.08 | 0.23 | 0.35 | 0.64 | 0.82 | 1.04 | 1.45 |
| Peak Inflow Q (cfs) | N/A | N/A | 8.4 | 12.8 | 16.1 | 23.1 | 27.6 | 32.7 | 43.5 |
| Peak Outflow Q (cfs) | 0.1 | 0.2 | 0.2 | 2.7 | 2.8 | 3.0 | 3.2 | 3.3 | 15.8 |
| Ratio Peak Outflow to Predevelopment Q | N/A | N/A | N/A | 0.7 | 0.5 | 0.3 | 0.2 | 0.2 | 0.6 |
| Structure Controlling Flow | Plate | Overflow Weir 1 | Vertical Orifice 1 | Outlet Plate 1 | Outlet Plate 1 | Outlet Plate 1 | Outlet Plate 1 | Outlet Plate 1 | Spillway |
| Max Velocity through Gate 1 (fps) | N/A | N/A | N/A | 0.3 | 0.3 | 0.3 | 0.3 | 0.4 | 0.4 |
| Max Velocity through Gate 2 (fps) | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A |
| Time to Drain 97% of Inflow Volume (hours) | 38 | 70 | 69 | 72 | 71 | 70 | 69 | 68 | 65 |
| Time to Drain 99% of Inflow Volume (hours) | 40 | 74 | 74 | 77 | 77 | 78 | 78 | 79 | 77 |
| Maximum Ponding Depth (ft) | 2.60 | 3.63 | 3.52 | 3.85 | 4.19 | 4.79 | 5.25 | 5.83 | 6.29 |
| Area at Maximum Ponding Depth (acres) | 0.35 | 0.57 | 0.55 | 0.60 | 0.64 | 0.70 | 0.73 | 0.75 | 0.86 |
| Maximum Volume Stored (acre-ft) | 0.266 | 0.750 | 0.689 | 0.873 | 1.091 | 1.494 | 1.824 | 2.253 | 2.616 |

DETENTION BASIN OUTLET STRUCTURE DESIGN

MHFD-Detention, Version 4.00 (December 2019)



S-A-V-D Chart Axis Override

| | X-axis | Left Y-Axis | Right Y-Axis |
|---------------|--------|-------------|--------------|
| minimum bound | | | |
| maximum bound | | | |

DETENTION BASIN OUTLET STRUCTURE DESIGN

Outflow Hydrograph Workbook Filename: _____

Inflow Hydrographs

The user can override the calculated inflow hydrographs from this workbook with inflow hydrographs developed in a separate program.

| Time Interval | SOURCE | WQCV [cfs] | EURV [cfs] | 2 Year [cfs] | 5 Year [cfs] | 10 Year [cfs] | 25 Year [cfs] | 50 Year [cfs] | 100 Year [cfs] | 500 Year [cfs] |
|---------------|---------|------------|------------|--------------|--------------|---------------|---------------|---------------|----------------|----------------|
| 5.00 min | 0:00:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 0:05:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 0:10:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.07 | 0.01 | 0.22 |
| | 0:15:00 | 0.00 | 0.00 | 0.60 | 0.98 | 1.22 | 0.82 | 1.04 | 1.00 | 1.47 |
| | 0:20:00 | 0.00 | 0.00 | 2.20 | 2.93 | 3.70 | 2.19 | 2.59 | 2.74 | 3.81 |
| | 0:25:00 | 0.00 | 0.00 | 5.52 | 8.65 | 11.64 | 5.47 | 6.59 | 7.37 | 11.75 |
| | 0:30:00 | 0.00 | 0.00 | 8.06 | 12.47 | 15.81 | 16.67 | 20.33 | 23.06 | 31.64 |
| | 0:35:00 | 0.00 | 0.00 | 8.44 | 12.83 | 16.12 | 21.61 | 26.01 | 30.90 | 41.39 |
| | 0:40:00 | 0.00 | 0.00 | 8.09 | 12.06 | 15.12 | 23.06 | 27.59 | 32.73 | 43.47 |
| | 0:45:00 | 0.00 | 0.00 | 7.34 | 11.00 | 14.00 | 21.99 | 26.27 | 31.95 | 42.38 |
| | 0:50:00 | 0.00 | 0.00 | 6.67 | 10.11 | 12.76 | 20.97 | 25.04 | 30.40 | 40.28 |
| | 0:55:00 | 0.00 | 0.00 | 6.11 | 9.24 | 11.75 | 19.06 | 22.79 | 28.22 | 37.47 |
| | 1:00:00 | 0.00 | 0.00 | 5.66 | 8.51 | 10.92 | 17.44 | 20.92 | 26.44 | 35.17 |
| | 1:05:00 | 0.00 | 0.00 | 5.24 | 7.83 | 10.14 | 16.03 | 19.28 | 24.94 | 33.21 |
| | 1:10:00 | 0.00 | 0.00 | 4.70 | 7.16 | 9.37 | 14.37 | 17.31 | 22.17 | 29.63 |
| | 1:15:00 | 0.00 | 0.00 | 4.19 | 6.44 | 8.65 | 12.75 | 15.38 | 19.40 | 26.05 |
| | 1:20:00 | 0.00 | 0.00 | 3.77 | 5.78 | 7.87 | 11.09 | 13.38 | 16.57 | 22.30 |
| | 1:25:00 | 0.00 | 0.00 | 3.46 | 5.31 | 7.15 | 9.78 | 11.80 | 14.33 | 19.34 |
| | 1:30:00 | 0.00 | 0.00 | 3.24 | 4.94 | 6.52 | 8.69 | 10.47 | 12.60 | 17.01 |
| | 1:35:00 | 0.00 | 0.00 | 3.03 | 4.60 | 5.96 | 7.78 | 9.36 | 11.17 | 15.07 |
| | 1:40:00 | 0.00 | 0.00 | 2.84 | 4.18 | 5.45 | 6.97 | 8.36 | 9.89 | 13.34 |
| | 1:45:00 | 0.00 | 0.00 | 2.65 | 3.78 | 4.96 | 6.23 | 7.45 | 8.73 | 11.76 |
| | 1:50:00 | 0.00 | 0.00 | 2.47 | 3.38 | 4.49 | 5.54 | 6.60 | 7.64 | 10.28 |
| | 1:55:00 | 0.00 | 0.00 | 2.18 | 3.00 | 3.99 | 4.87 | 5.78 | 6.61 | 8.88 |
| | 2:00:00 | 0.00 | 0.00 | 1.89 | 2.61 | 3.44 | 4.22 | 4.99 | 5.64 | 7.57 |
| | 2:05:00 | 0.00 | 0.00 | 1.52 | 2.09 | 2.75 | 3.37 | 3.97 | 4.47 | 5.98 |
| | 2:10:00 | 0.00 | 0.00 | 1.19 | 1.61 | 2.13 | 2.56 | 3.01 | 3.36 | 4.49 |
| | 2:15:00 | 0.00 | 0.00 | 0.94 | 1.27 | 1.71 | 1.89 | 2.22 | 2.45 | 3.32 |
| | 2:20:00 | 0.00 | 0.00 | 0.76 | 1.04 | 1.40 | 1.45 | 1.70 | 1.84 | 2.52 |
| | 2:25:00 | 0.00 | 0.00 | 0.63 | 0.85 | 1.15 | 1.13 | 1.33 | 1.40 | 1.93 |
| | 2:30:00 | 0.00 | 0.00 | 0.52 | 0.70 | 0.94 | 0.89 | 1.04 | 1.07 | 1.48 |
| | 2:35:00 | 0.00 | 0.00 | 0.42 | 0.57 | 0.77 | 0.70 | 0.82 | 0.81 | 1.12 |
| | 2:40:00 | 0.00 | 0.00 | 0.35 | 0.46 | 0.61 | 0.55 | 0.64 | 0.60 | 0.84 |
| | 2:45:00 | 0.00 | 0.00 | 0.28 | 0.37 | 0.48 | 0.43 | 0.50 | 0.45 | 0.62 |
| | 2:50:00 | 0.00 | 0.00 | 0.23 | 0.29 | 0.38 | 0.33 | 0.38 | 0.34 | 0.47 |
| | 2:55:00 | 0.00 | 0.00 | 0.18 | 0.23 | 0.30 | 0.26 | 0.30 | 0.27 | 0.37 |
| | 3:00:00 | 0.00 | 0.00 | 0.15 | 0.18 | 0.23 | 0.21 | 0.24 | 0.22 | 0.30 |
| | 3:05:00 | 0.00 | 0.00 | 0.12 | 0.14 | 0.18 | 0.16 | 0.19 | 0.17 | 0.24 |
| | 3:10:00 | 0.00 | 0.00 | 0.09 | 0.11 | 0.14 | 0.13 | 0.14 | 0.13 | 0.18 |
| | 3:15:00 | 0.00 | 0.00 | 0.06 | 0.08 | 0.10 | 0.09 | 0.11 | 0.10 | 0.13 |
| | 3:20:00 | 0.00 | 0.00 | 0.04 | 0.05 | 0.07 | 0.07 | 0.07 | 0.07 | 0.09 |
| | 3:25:00 | 0.00 | 0.00 | 0.03 | 0.04 | 0.05 | 0.04 | 0.05 | 0.04 | 0.06 |
| | 3:30:00 | 0.00 | 0.00 | 0.02 | 0.02 | 0.03 | 0.03 | 0.03 | 0.03 | 0.03 |
| | 3:35:00 | 0.00 | 0.00 | 0.01 | 0.01 | 0.01 | 0.01 | 0.01 | 0.01 | 0.02 |
| | 3:40:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 3:45:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 3:50:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 3:55:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 4:00:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 4:05:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 4:10:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 4:15:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 4:20:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 4:25:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 4:30:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 4:35:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 4:40:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 4:45:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 4:50:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 4:55:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 5:00:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 5:05:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 5:10:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 5:15:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 5:20:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 5:25:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 5:30:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 5:35:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 5:40:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 5:45:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 5:50:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 5:55:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| 6:00:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | |

Detention Pond B South Forebay Calculations

| | | |
|---------------------------------------|---------|-------|
| 100 YR Discharge | 6.7 | CFS |
| WQCV Storage | 0.264 | AC-FT |
| Forebay Volume (2% pf WQCV) | 0.00528 | AC-FT |
| Forebay Release Volume (2% of 100 YR) | 0.134 | CFS |

Weir Report

Hydraflow Express Extension for Autodesk® Civil 3D® by Autodesk, Inc.

Wednesday, Nov 25 2020

Pond B South Forebay Calculations

Rectangular Weir


| | |
|--------------------|---------|
| Crest | = Sharp |
| Bottom Length (ft) | = 0.25 |
| Total Depth (ft) | = 1.25 |

Highlighted

| | |
|-----------------|---------|
| Depth (ft) | = 0.30 |
| Q (cfs) | = 0.134 |
| Area (sqft) | = 0.07 |
| Velocity (ft/s) | = 1.81 |
| Top Width (ft) | = 0.25 |

Calculations

| | |
|----------------|---------|
| Weir Coeff. Cw | = 3.33 |
| Compute by: | Known Q |
| Known Q (cfs) | = 0.13 |



Detention Pond B North Forebay Calculations

| | | |
|---------------------------------------|---------|-------|
| 100 YR Discharge | 46.7 | CFS |
| WQCV Storage | 0.264 | AC-FT |
| Forebay Volume (2% pf WQCV) | 0.00528 | AC-FT |
| Forebay Release Volume (2% of 100 YR) | 0.934 | CFS |

Weir Report

Hydraflow Express Extension for Autodesk® Civil 3D® by Autodesk, Inc.

Wednesday, Nov 25 2020

Pond B North Forebay Calculations

Rectangular Weir


Crest = Sharp
 Bottom Length (ft) = 0.25
 Total Depth (ft) = 1.25

Highlighted

Depth (ft) = 1.08
 Q (cfs) = 0.930
 Area (sqft) = 0.27
 Velocity (ft/s) = 3.46
 Top Width (ft) = 0.25

Calculations

Weir Coeff. Cw = 3.33
 Compute by: Known Q
 Known Q (cfs) = 0.93



Channel Report

Pond B Trickle Channel

Rectangular

Bottom Width (ft) = 2.00

Total Depth (ft) = 0.50

Invert Elev (ft) = 1.00

Slope (%) = 1.00

N-Value = 0.013

Calculations

Compute by: Known Q

Known Q (cfs) = 1.06

Highlighted

Depth (ft) = 0.17

Q (cfs) = 1.060

Area (sqft) = 0.34


Velocity (ft/s) = 3.12

Wetted Perim (ft) = 2.34

Crit Depth, Yc (ft) = 0.21

Top Width (ft) = 2.00

EGL (ft) = 0.32



Channel Report

Pond B Spillway

Trapezoidal


Bottom Width (ft) = 50.00
Side Slopes (z:1) = 10.00, 10.00
Total Depth (ft) = 1.50
Invert Elev (ft) = 1.00
Slope (%) = 0.20
N-Value = 0.020

Highlighted

Depth (ft) = 0.49
Q (cfs) = 51.30
Area (sqft) = 26.90
Velocity (ft/s) = 1.91
Wetted Perim (ft) = 59.85
Crit Depth, Y_c (ft) = 0.32
Top Width (ft) = 59.80
EGL (ft) = 0.55

Calculations

Compute by: Known Q
Known Q (cfs) = 51.30



APPENDIX D
REFERENCE MATERIALS



Federal Emergency Management Agency

Washington, D.C. 20472

JAN 30 2007

CERTIFIED MAIL
RETURN RECEIPT REQUESTED

The Honorable Sallie Clark
Chair, El Paso County
Board of Commissioners
27 East Vermijo Avenue
Colorado Springs, CO 80903

IN REPLY REFER TO:

Case No.: 05-08-0368P
Community Name: El Paso County, CO
Community No.: 080059
Effective Date of
This Revision: **MAY 23 2007**

Dear Ms. Clark:

The Flood Insurance Study report and Flood Insurance Rate Map for your community have been revised by this Letter of Map Revision (LOMR). Please use the enclosed annotated map panel(s) revised by this LOMR for floodplain management purposes and for all flood insurance policies and renewals issued in your community.

Additional documents are enclosed which provide information regarding this LOMR. Please see the List of Enclosures below to determine which documents are included. Other attachments specific to this request may be included as referenced in the Determination Document. If you have any questions regarding floodplain management regulations for your community or the National Flood Insurance Program (NFIP) in general, please contact the Consultation Coordination Officer for your community. If you have any technical questions regarding this LOMR, please contact the Director, Federal Insurance and Mitigation Division of the Department of Homeland Security's Federal Emergency Management Agency (FEMA) in Denver, Colorado, at (303) 235-4830, or the FEMA Map Assistance Center toll free at 1-877-336-2627 (1-877-FEMA MAP). Additional information about the NFIP is available on our website at <http://www.fema.gov/nfip>.

Sincerely,

Patrick, F. Sacbibit, P.E., CFM, Project Engineer
Engineering Management Section
Mitigation Division

For: William R. Blanton Jr., CFM, Chief
Engineering Management Section
Mitigation Division

List of Enclosures:

Letter of Map Revision Determination Document
Annotated Flood Insurance Rate Map
Annotated Flood Insurance Study Report

cc: The Honorable Lionel Rivera
Mayor, City of Colorado Springs

Regional Floodplain Administrator
Pikes Peak Regional Building Department

J. F. Sato and Associates, Inc.

Engineering and Surveying, Inc.



Federal Emergency Management Agency

Washington, D.C. 20472

LETTER OF MAP REVISION DETERMINATION DOCUMENT

| COMMUNITY AND REVISION INFORMATION | | PROJECT DESCRIPTION | BASIS OF REQUEST |
|------------------------------------|--|--|---|
| COMMUNITY | El Paso County Colorado (Unincorporated Areas) | CHANNELIZATION CULVERT | FLOODWAY HYDRAULIC ANALYSIS NEW TOPOGRAPHIC DATA BASEMAP CHANGES |
| | COMMUNITY NO.: 080059 | | |
| IDENTIFIER | Sand Creek Center Tributary and East Fork LOMR | APPROXIMATE LATITUDE & LONGITUDE: 38.846, -104.720 SOURCE: USGS QUADRANGLE DATUM: NAD 27 | |
| ANNOTATED MAPPING ENCLOSURES | | ANNOTATED STUDY ENCLOSURES | |
| TYPE: FIRM* | NO.: 08041C0752 F DATE: March 17, 1997 | DATE OF EFFECTIVE FLOOD INSURANCE STUDY: August 23, 1999 | |
| TYPE: FIRM | NO.: 08041C0753 F DATE: March 17, 1997 | PROFILE(S): 206P | |
| TYPE: FIRM | NO.: 08041C0754 F DATE: March 17, 1997 | FLOODWAY DATA TABLE: 5 | |

Enclosures reflect changes to flooding sources affected by this revision.

* FIRM - Flood Insurance Rate Map; ** FBFM - Flood Boundary and Floodway Map; *** FHBM - Flood Hazard Boundary Map

FLOODING SOURCE(S) & REVISED REACH(ES)

Sand Creek Center Tributary – from approximately 1,350 feet upstream of East Frontage Road to just upstream of Galley Road

SUMMARY OF REVISIONS

| Flooding Source | Effective Flooding | Revised Flooding | Increases | Decreases |
|-----------------------------|--------------------|------------------|-----------|-----------|
| Sand Creek Center Tributary | Zone AE | Zone AE | YES | YES |
| | Floodway | Floodway | YES | YES |
| | BFES* | BFES | NONE | YES |
| | Zone X (shaded) | Zone X (shaded) | YES | YES |

* BFES - Base Flood Elevations

DETERMINATION

This document provides the determination from the Department of Homeland Security's Federal Emergency Management Agency (FEMA) regarding a request for a Letter of Map Revision (LOMR) for the area described above. Using the information submitted, we have determined that a revision to the flood hazards depicted in the Flood Insurance Study (FIS) report and/or National Flood Insurance Program (NFIP) map is warranted. This document revises the effective NFIP map, as indicated in the attached documentation. Please use the enclosed annotated map panels revised by this LOMR for floodplain management purposes and for all flood insurance policies and renewals in your community.

This determination is based on the flood data presently available. The enclosed documents provide additional information regarding this determination. If you have any questions about this document, please contact the FEMA Map Assistance Center toll free at 1-877-336-2627 (1-877-FEMA MAP) or by letter addressed to the LOMR Depot, 3601 Eisenhower Avenue, Alexandria, VA 22304. Additional information about the NFIP is available on our website at <http://www.fema.gov/nfip>.

Patrick F. Sacbibit, P.E., CFM, Project Engineer
Engineering Management Section
Mitigation Division



Federal Emergency Management Agency
Washington, D.C. 20472

**LETTER OF MAP REVISION
DETERMINATION DOCUMENT (CONTINUED)**

OTHER COMMUNITIES AFFECTED BY THIS REVISION

CID Number: 080060 **Name:** City of Colorado Springs, Colorado

AFFECTED MAP PANELS

TYPE: FIRM NO.: 08041C0753 F DATE: March 17, 1997
TYPE: FIRM NO.: 08041C0754 F DATE: March 17, 1997

AFFECTED PORTIONS OF THE FLOOD INSURANCE STUDY REPORT

DATE OF EFFECTIVE FLOOD INSURANCE STUDY: August 23, 1999
PROFILE(S): 205P, 206P, 209P, and 210P
FLOODWAY DATA TABLE: 5

This determination is based on the flood data presently available. The enclosed documents provide additional information regarding this determination. If you have any questions about this document, please contact the FEMA Map Assistance Center toll free at 1-877-336-2627 (1-877-FEMA MAP) or by letter addressed to the LOMR Depot, 3601 Eisenhower Avenue, Alexandria, VA 22304. Additional Information about the NFIP is available on our website at <http://www.fema.gov/nfip>.

Patrick F. Sacbbit, P.E., CFM, Project Engineer
Engineering Management Section
Mitigation Division



Federal Emergency Management Agency

Washington, D.C. 20472

LETTER OF MAP REVISION DETERMINATION DOCUMENT (CONTINUED)

COMMUNITY INFORMATION

APPLICABLE NFIP REGULATIONS/COMMUNITY OBLIGATION

We have made this determination pursuant to Section 206 of the Flood Disaster Protection Act of 1973 (P.L. 93-234) and in accordance with the National Flood Insurance Act of 1968, as amended (Title XIII of the Housing and Urban Development Act of 1968, P.L. 90-448), 42 U.S.C. 4001-4128, and 44 CFR Part 65. Pursuant to Section 1361 of the National Flood Insurance Act of 1968, as amended, communities participating in the NFIP are required to adopt and enforce floodplain management regulations that meet or exceed NFIP criteria. These criteria, including adoption of the FIS report and FIRM, and the modifications made by this LOMR, are the minimum requirements for continued NFIP participation and do not supersede more stringent State/Commonwealth or local requirements to which the regulations apply.

We provide the floodway designation to your community as a tool to regulate floodplain development. Therefore, the floodway revision we have described in this letter, while acceptable to us, must also be acceptable to your community and adopted by appropriate community action, as specified in Paragraph 60.3(d) of the NFIP regulations.

NFIP regulations Subparagraph 60.3(b)(7) requires communities to ensure that the flood-carrying capacity within the altered or relocated portion of any watercourse is maintained. This provision is incorporated into your community's existing floodplain management ordinances; therefore, responsibility for maintenance of the altered or relocated watercourse, including any related appurtenances such as bridges, culverts, and other drainage structures, rests with your community. We may request that your community submit a description and schedule of maintenance activities necessary to ensure this requirement.

COMMUNITY REMINDERS

We based this determination on the 1-percent-annual-chance flood discharges computed in the FIS for your community without considering subsequent changes in watershed characteristics that could increase flood discharges. Future development of projects upstream could cause increased flood discharges, which could cause increased flood hazards. A comprehensive restudy of your community's flood hazards would consider the cumulative effects of development on flood discharges subsequent to the publication of the FIS report for your community and could, therefore, establish greater flood hazards in this area.

Your community must regulate all proposed floodplain development and ensure that permits required by Federal and/or State/Commonwealth law have been obtained. State/Commonwealth or community officials, based on knowledge of local conditions and in the interest of safety, may set higher standards for construction or may limit development in floodplain areas. If your State/Commonwealth or community has adopted more restrictive or comprehensive floodplain management criteria, those criteria take precedence over the minimum NFIP requirements.

We will not print and distribute this LOMR to primary users, such as local insurance agents or mortgage lenders; instead, the community will serve as a repository for the new data. We encourage you to disseminate the information in this LOMR by preparing a news release for publication in your community's newspaper that describes the revision and explains how your community will provide the data and help interpret the NFIP maps. In that way, interested persons, such as property owners, insurance agents, and mortgage lenders, can benefit from the information.

This determination is based on the flood data presently available. The enclosed documents provide additional information regarding this determination. If you have any questions about this document, please contact the FEMA Map Assistance Center toll free at 1-877-336-2627 (1-877-FEMA MAP) or by letter addressed to the LOMR Depot, 3601 Eisenhower Avenue, Alexandria, VA 22304. Additional information about the NFIP is available on our website at <http://www.fema.gov/nfip>.

A handwritten signature in black ink, appearing to read "P. Sacbibit".

Patrick F. Sacbibit, P.E., CFM, Project Engineer
Engineering Management Section
Mitigation Division



Federal Emergency Management Agency
Washington, D.C. 20472

**LETTER OF MAP REVISION
DETERMINATION DOCUMENT (CONTINUED)**

We have designated a Consultation Coordination Officer (CCO) to assist your community. The CCO will be the primary liaison between your community and FEMA. For information regarding your CCO, please contact:

Ms. Jeanine D. Petterson
Director, Federal Insurance and Mitigation Division
Federal Emergency Management Agency, Region VIII
Denver Federal Center, Building 710
P.O. Box 25267
Denver, CO 80225-0267
(303) 235-4830

STATUS OF THE COMMUNITY NFIP MAPS

We will not physically revise and republish the FIRM and FIS report for your community to reflect the modifications made by this LOMR at this time. When changes to the previously cited FIRM panel(s) and FIS report warrant physical revision and republication in the future, we will incorporate the modifications made by this LOMR at that time.

This determination is based on the flood data presently available. The enclosed documents provide additional information regarding this determination. If you have any questions about this document, please contact the FEMA Map Assistance Center toll free at 1-877-336-2627 (1-877-FEMA MAP) or by letter addressed to the LOMR Depot, 3601 Eisenhower Avenue, Alexandria, VA 22304. Additional information about the NFIP is available on our website at <http://www.fema.gov/nfip>.

A handwritten signature in black ink, appearing to read "P. Sacbibit".

Patrick F. Sacbibit, P.E., CFM, Project Engineer
Engineering Management Section
Mitigation Division



Federal Emergency Management Agency
Washington, D.C. 20472

LETTER OF MAP REVISION
DETERMINATION DOCUMENT (CONTINUED)

PUBLIC NOTIFICATION OF REVISION

PUBLIC NOTIFICATION

| FLOODING SOURCE | LOCATION OF REFERENCED ELEVATION | BFE (FEET NGVD 29) | | MAP PANEL NUMBER(S) |
|-----------------------------|---|--------------------|---------|---------------------|
| | | EFFECTIVE | REVISED | |
| Sand Creek Center Tributary | Approximately 1,350 feet upstream of East Frontage Road | 6,170 | 6,165 | 08041C0753 F |
| | Just downstream of Terminal Avenue | 6,216 | 6,213 | 08041C0754 F |

Within 90 days of the second publication in the local newspaper, a citizen may request that we reconsider this determination. Any request for reconsideration must be based on scientific or technical data. Therefore, this letter will be effective only after the 90-day appeal period has elapsed and we have resolved any appeals that we receive during this appeal period. Until this LOMR is effective, the revised BFEs presented in this LOMR may be changed.

A notice of changes will be published in the *Federal Register*. This information also will be published in your local newspaper on or about the dates listed below.

LOCAL NEWSPAPER Name: *El Paso County News*
 Dates: 02/14/2007 02/21/2007

This determination is based on the flood data presently available. The enclosed documents provide additional information regarding this determination. If you have any questions about this document, please contact the FEMA Map Assistance Center toll free at 1-877-336-2627 (1-877-FEMA MAP) or by letter addressed to the LOMR Depot, 3601 Eisenhower Avenue, Alexandria, VA 22304. Additional information about the NFIP is available on our website at <http://www.fema.gov/nfip>.

Patrick F. Sacbibit, P.E., CFM, Project Engineer
Engineering Management Section
Mitigation Division

CHANGES ARE MADE IN DETERMINATIONS OF BASE FLOOD ELEVATIONS FOR THE CITY OF COLORADO SPRINGS AND THE UNINCORPORATED AREAS OF EL PASO COUNTY, COLORADO, UNDER THE NATIONAL FLOOD INSURANCE PROGRAM

On March 17, 1997, the Department of Homeland Security's Federal Emergency Management Agency identified Special Flood Hazard Areas (SFHAs) in the City of Colorado Springs and in the unincorporated areas of El Paso County, Colorado, through issuance of a Flood Insurance Rate Map (FIRM). The Mitigation Division has determined that modification of the elevations of the flood having a 1-percent chance of being equaled or exceeded in any given year (base flood) for certain locations in these communities is appropriate. The modified Base Flood Elevations (BFEs) revise the FIRM for the communities.

The changes are being made pursuant to Section 206 of the Flood Disaster Protection Act of 1973 (Public Law 93-234) and are in accordance with the National Flood Insurance Act of 1968, as amended (Title XIII of the Housing and Urban Development Act of 1968, Public Law 90-448), 42 U.S.C. 4001-4128, and 44 CFR Part 65.

A hydraulic analysis was performed to incorporate new topographic data for Sand Creek Center Tributary from just upstream of Airport Road to just upstream of Galley Road and for Sand Creek East Fork from approximately 970 feet downstream of Powers Boulevard to just downstream of Stewart Avenue. This has resulted in a revised delineation of the regulatory floodway, increases and decreases in SFHA width, and increased and decreased BFEs for both aforementioned flooding sources. The table below indicates existing and modified BFEs for selected locations along the affected lengths of the flooding source(s) cited above.

| Location | Existing BFE (feet)* | Modified BFE (feet)* |
|--|-------------------------|-------------------------|
| Sand Creek Center Tributary: | | |
| ¹ Approximately 150 feet upstream of Airport Road | 6,109 | 6,108 |
| ¹ Approximately 1,250 feet upstream of East Frontage Road | 6,168 | 6,164 |
| ² Approximately 1,350 feet upstream of East Frontage Road | 6,170 | 6,165 |
| ² Just downstream of Terminal Avenue | 6,216 | 6,213 |
| Sand Creek East Fork: | | |
| ¹ Approximately 810 feet downstream of Powers Boulevard | 6,099 | 6,096 |
| ¹ Approximately 140 feet downstream of Stewart Avenue | 6,206 | 6,205 |

*National Geodetic Vertical Datum, rounded to nearest whole foot

¹City of Colorado Springs

²Unincorporated areas of El Paso County

Under the above-mentioned Acts of 1968 and 1973, the Mitigation Division must develop criteria for floodplain management. To participate in the National Flood Insurance Program (NFIP), the community must use the modified BFEs to administer the floodplain management measures of the NFIP. These modified BFEs will also be used to calculate the appropriate flood insurance premium rates for new buildings and their contents and for the second layer of insurance on existing buildings and contents.

Upon the second publication of notice of these changes in this newspaper, any person has 90 days in which he or she can request, through the Chief Executive Officer of the community, that the Mitigation Division reconsider the determination. Any request for reconsideration must be based on knowledge of

changed conditions or new scientific or technical data. All interested parties are on notice that until the 90-day period elapses, the Mitigation Division's determination to modify the BFEs may itself be changed.

Any person having knowledge or wishing to comment on these changes should immediately notify:

The Honorable Sallie Clark
Chair, El Paso County
Board of Commissioners
27 East Vermijo Avenue
Colorado Springs, CO 80903

OR

The Honorable Lionel Rivera
Mayor, City of Colorado Springs
P.O. Box 1575
Colorado Springs, CO 80901

| FLOODING SOURCE | | FLOODWAY | | | BASE FLOOD WATER SURFACE ELEVATION | | | INCREASE |
|----------------------|-----------------------|--------------|-------------------------|---------------------------------|------------------------------------|------------------|---------------|----------|
| CROSS SECTION | DISTANCE ¹ | WIDTH (FEET) | SECTION AREA (SQ. FEET) | MEAN VELOCITY (FEET PER SECOND) | REGULATORY | WITHOUT FLOODWAY | WITH FLOODWAY | |
| | | | | | FEET (NGVD) | | | |
| Sand Creek East Fork | 1,100 | 100 | 455 | 11.9 | 6,038.7 | 6,038.7 | 6,038.7 | 0.0 |
| | 2,400 | 100 | 446 | 12.2 | 6,054.3 | 6,054.3 | 6,054.3 | 0.0 |
| | 3,330 | 100 | 450 | 12.0 | 6,069.9 | 6,069.9 | 6,069.9 | 0.0 |
| | 4,240 | 100 | 449 | 12.1 | 6,085.1 | 6,085.1 | 6,085.1 | 0.0 |
| | 4,870 | 102 | 446 | 12.0 | 6,095.1 | 6,095.1 | 6,095.1 | 0.0 |
| | 6,188 | 70 | 489 | 10.9 | 6,118.5 | 6,118.5 | 6,118.5 | 0.0 |
| | 7,403 | 71 | 396 | 13.5 | 6,136.0 | 6,136.0 | 6,136.0 | 0.0 |
| | 7,931 | 148 | 507 | 10.5 | 6,158.8 | 6,158.8 | 6,158.8 | 0.0 |
| | 8,943 | 98 | 444 | 12.0 | 6,169.0 | 6,169.0 | 6,169.0 | 0.0 |
| | 9,666 | 86 | 423 | 12.6 | 6,177.0 | 6,177.0 | 6,177.0 | 0.0 |
| | 10,721 | 81 | 415 | 12.8 | 6,193.3 | 6,193.3 | 6,193.3 | 0.0 |
| | 11,347 | 166 | 526 | 10.1 | 6,207.3 | 6,207.3 | 6,207.3 | 0.0 |
| | 11,375 | 173 | 632 | 8.4 | 6,207.9 | 6,207.9 | 6,207.9 | 0.0 |
| | 12,610 | 367 | 699 | 7.6 | 6,228.8 | 6,228.8 | 6,228.8 | 0.1 |
| | 13,720 | 188 | 570 | 10.0 | 6,241.7 | 6,241.7 | 6,241.7 | 0.0 |
| | 14,805 | 125 | 479 | 11.1 | 6,257.9 | 6,257.9 | 6,257.9 | 0.0 |
| | 14,885 | 125 | 601 | 8.9 | 6,259.9 | 6,259.9 | 6,259.9 | 1.0 |
| | 15,850 | 228 | 582 | 9.2 | 6,268.7 | 6,268.7 | 6,268.7 | 0.0 |
| | 16,325 | 300 | 678 | 7.9 | 6,277.3 | 6,277.3 | 6,277.3 | 0.2 |
| | 16,995 | 321 | 690 | 7.7 | 6,291.4 | 6,291.4 | 6,292.0 | 0.6 |
| | 17,065 | 326 | 667 | 8.0 | 6,291.4 | 6,291.4 | 6,292.1 | 0.7 |
| | 17,915 | 388 | 1,598 | 3.3 | 6,293.4 | 6,293.4 | 6,294.0 | 0.6 |
| | 18,995 | 367 | 683 | 7.8 | 6,307.2 | 6,307.2 | 6,307.6 | 0.4 |
| | 20,525 | 413 | 706 | 7.5 | 6,326.4 | 6,326.4 | 6,327.1 | 0.7 |
| | 22,125 | 255 | 620 | 8.6 | 6,348.7 | 6,348.7 | 6,348.8 | 0.1 |
| | 23,105 | 397 | 706 | 7.6 | 6,359.9 | 6,359.9 | 6,359.9 | 0.0 |
| 24,835 | 431 | 705 | 7.4 | 6,383.7 | 6,383.7 | 6,383.7 | 0.0 | |
| 26,505 | 353 | 667 | 7.8 | 6,401.0 | 6,401.0 | 6,401.5 | 0.5 | |

Revised Data

Revised by LOMR dated OCT 07 2004

¹ Feet above confluence with Sand Creek

FEDERAL EMERGENCY MANAGEMENT AGENCY
EL PASO COUNTY, CO
AND INCORPORATED AREAS

FLOODWAY DATA

SAND CREEK EAST FORK


TABLE 5

| FLOODING SOURCE | | FLOODWAY | | | | BASE FLOOD WATER SURFACE ELEVATION | | |
|-----------------------------|-----------------------|--------------|----------------------------|---------------------------------|------------|------------------------------------|---------------------------|----------|
| CROSS SECTION | DISTANCE ¹ | WIDTH (FEET) | SECTION AREA (SQUARE FEET) | MEAN VELOCITY (FEET PER SECOND) | REGULATORY | WITHOUT FLOODWAY FEET (NGVD) | WITH FLOODWAY FEET (NGVD) | INCREASE |
| Sand Creek Center Tributary | | | | | | | | |
| A | 940 | 40 | 92 | 8.6 | 6,106.5 | 6,106.5 | 6,106.5 | 0.0 |
| B | 990 | 40 | 118 | 6.7 | 6,107.2 | 6,107.2 | 6,107.2 | 0.0 |
| C | 2,238 | 91 | 120 | 6.6 | 6,120.2 | 6,120.2 | 6,120.2 | 0.0 |
| D | 3,948 | 46 | 95 | 8.0 | 6,138.3 | 6,138.3 | 6,138.3 | 0.0 |
| E | 4,547 | 170 | 159 | 4.8 | 6,147.4 | 6,147.4 | 6,147.4 | 0.0 |
| F | 5,539 | 52 | 97 | 7.8 | 6,156.8 | 6,156.8 | 6,156.8 | 0.0 |
| G | 7,191 | 63 | 104 | 7.3 | 6,176.2 | 6,176.2 | 6,176.2 | 0.0 |
| H | 7,940 | 52 | 00 | 7.8 | 6,189.6 | 6,189.6 | 6,189.6 | 0.0 |
| I | 8,527 | 40 | | 7.8 | 6,197.6 | 6,197.6 | 6,197.6 | 0.0 |
| J | 9,366 | 17 | 42 | 9.0 | 6,213.4 | 6,213.4 | 6,213.4 | 0.0 |
| K | 10,055 | 232 | 278 | 4.0 | 6,221.9 | 6,221.9 | 6,221.9 | 0.0 |
| L | 10,627 | 539 | 469 | 2.4 | 6,230.6 | 6,230.6 | 6,230.6 | 0.0 |
| M | 11,321 | 31 | 79 | 9.1 | 6,241.1 | 6,241.1 | 6,241.1 | 0.0 |
| N | 11,648 | 60 | 99 | 7.3 | 6,244.6 | 6,244.6 | 6,244.6 | 0.8 |
| O | 12,840 | 29 | 85 | 9.6 | 6,253.8 | 6,253.8 | 6,253.8 | 0.0 |
| P | 13,730 | 27 | 83 | 9.9 | 6,273.6 | 6,273.6 | 6,273.6 | 0.0 |
| Q | 14,592 | 26 | 68 | 9.3 | 6,299.7 | 6,299.7 | 6,299.7 | 0.0 |
| R | 14,670 | 40 | 61 | 6.9 | 6,304.2 | 6,304.2 | 6,305.2 | 1.0 |
| S | 15,050 | 20 | 63 | 10.1 | 6,307.6 | 6,307.6 | 6,308.1 | 0.5 |
| T | 15,460 | 25 | 68 | 9.5 | 6,310.8 | 6,310.8 | 6,311.4 | 0.6 |
| U | 15,750 | 20 | 41 | 7.8 | 6,319.6 | 6,319.6 | 6,319.6 | 0.0 |
| V | 16,670 | 20 | 39 | 8.1 | 6,346.0 | 6,346.0 | 6,346.0 | 0.0 |

Flow rate = 792 cfs


Flow rate = 822 cfs

¹ Feet Above confluence with Sand Creek East Fork




38°50'37"

104°43'07"



EL PASO COUNTY
UNINCORPORATED AREAS
080059



APPROXIMATE SCALE IN FEET



NATIONAL FLOOD INSURANCE PROGRAM

FIRM
FLOOD INSURANCE RATE MAP

EL PASO COUNTY,
COLORADO AND
UNINCORPORATED AREAS

PANEL 752 OF 1300
(SEE MAP INDEX FOR PANELS NOT PRINTED)

CONTAINS:
COMMUNITY NUMBER PANEL SHEET
COLORADO SPRINGS, CITY OF 080059 0752 F
EL PASO COUNTY UNINCORPORATED AREAS 080059 0752 F



Federal Emergency Management Agency




MAP NUMBER
08041C0752 F
EFFECTIVE DATE:
MARCH 17, 1997

MAY 29 2007

JOINS PANEL 0754


**EL PASO COUNTY
UNINCORPORATED AREAS
080059**

Legend

-  1% annual chance (100-Year) Floodplain
-  1% annual chance (100-Year) Floodway
-  0.2% annual chance (500-Year) Floodplain



APPROXIMATE SCALE IN FEET



NATIONAL FLOOD INSURANCE PROGRAM

**FIRM
FLOOD INSURANCE RATE MAP**

**EL PASO COUNTY,
COLORADO
AND INCORPORATED AREAS**

**PANEL 753 OF 1300
(SEE MAP INDEX FOR PANELS NOT PRINTED)**

CONTAINS:
COMMUNITY NUMBER PANEL SUFFIX


| | | | |
|---|--------|------|---|
| COLORADO SPRINGS, CITY OF | 080060 | 0753 | F |
| EL PASO COUNTY, UNINCORPORATED AREAS | 080059 | 0753 | F |

REVISED TO
REFLECT LOMR
EFFECTIVE MAY 23 2007

MAP NUMBER
08041C0753 F

EFFECTIVE DATE:
MARCH 17, 1997

Federal Emergency Management Agency






JOINS PANEL 0754

R66W
R65W

104°43'07"
38°50'37"

JOINS PANEL 0752

EL PASO COUNTY UNINCORPORATED AREAS 080059

- Legend
-  1% annual chance (100-Year) Floodplain
 -  1% annual chance (100-Year) Floodway
 -  0.2% annual chance (500-Year) Floodplain



APPROXIMATE SCALE IN FEET
500 0 500

NATIONAL FLOOD INSURANCE PROGRAM

FIRM FLOOD INSURANCE RATE MAP

EL PASO COUNTY,
COLORADO
AND INCORPORATED AREAS

PANEL 754 OF 1300
(SEE MAP INDEX FOR PANELS NOT PRINTED)

CONTAINS:
COMMUNITY NUMBER PANEL SUFFIX


COLORADO SPRINGS, CITY OF 080060 0754 F
EL PASO COUNTY, UNINCORPORATED AREAS 080059 0754 F

REVISED TO
REFLECT LOMR
EFFECTIVE MAY 23 2007

MAP NUMBER
08041C0754 F
EFFECTIVE DATE:
MARCH 17, 1997



Federal Emergency Management Agency



NOTE: MAP AREA SHOWN ON
THIS PANEL IS LOCATED
WITHIN TOWNSHIP 14 SOUTH,
RANGE 65 WEST.

AREA REVISED
BY LOMR DATED OCTOBER 7, 2004

CITY OF COLORADO SPRINGS
080060


JOINS PANEL 0753

19

SAND CREEK DRAINAGE BASIN PLANNING STUDY

PRELIMINARY DESIGN REPORT

CITY OF COLORADO SPRINGS, EL PASO COUNTY, COLORADO



PREPARED FOR:

City of Colorado Springs
Department of Comprehensive Planning, Development and Finance
Engineering Division
30 S. Nevada
Colorado Springs, Colorado 80903

PREPARED BY:

Kowa Engineering Corporation
1011 North Weber
Colorado Springs, CO 80903

SAND CREEK
DRAINAGE BASIN PLANNING STUDY
PRELIMINARY DESIGN REPORT

Prepared for:

City of Colorado Springs
Department of Comprehensive Planning, Development And Finance
Engineering Division - MAIL CODE 435
P.O. Box 1575
Colorado Springs, CO 80901-1575

Prepared by:

Kiowa Engineering Corporation
1001 North Weber #200
Colorado Springs, CO 80903

KIOWA Project No. 90.04.09
R185

JANUARY 1993
Revised APRIL 1993
Revised FEBRUARY 1995
Revised APRIL 1995
Revised OCTOBER 1995
Revised March 1996

TABLE OF CONTENTS

| | | | |
|--|------|------------------------|----|
| | Page | Conclusions | |
| LIST OF TABLES | ii | | 34 |
| LIST OF FIGURES | iii | | |
| RESOLUTION OF ADOPTION AND ENGINEER'S STATEMENT | iv | | |
| I. INTRODUCTION | | | |
| Authorization | 1 | | 51 |
| Purpose and Scope | 1 | | 51 |
| Summary of Data Obtained | 1 | | 52 |
| Mapping and Surveying | 2 | | 52 |
| Project Coordination | 2 | | 53 |
| Acknowledgements | 3 | | 53 |
| II. STUDY AREA DESCRIPTION | | | |
| Basin Description | 4 | | 53 |
| Climate | 4 | | 53 |
| Soils and Geology | 4 | | 54 |
| Property Ownership and Impervious Land Densities | 4 | | 54 |
| Park Land and Open Space | 5 | | 54 |
| III. HYDROLOGIC ANALYSIS | | | |
| Runoff Model | 8 | | 58 |
| Basin Characteristics | 8 | | 58 |
| Previous Studies | 8 | | 59 |
| Impervious Land Density | 8 | | |
| Design Rainfall | 9 | | |
| Hydrologic Modeling | 9 | | |
| Results | 9 | | |
| IV. HYDRAULIC ANALYSIS AND FLOOD PLAIN DESCRIPTION | | | |
| Reach Delineation | 18 | | |
| Flood History | 18 | | |
| Hydraulic Structure Inventory | 19 | | |
| Flood Plains | 19 | | |
| V. EVALUATION OF CONCEPTUAL ALTERNATIVES | | | |
| Introduction | 31 | | |
| Evaluation Parameters | 31 | | |
| Environmental Review of Mainstem Sand Creek Basin | 31 | | |
| Environmental Review for the East Fork Sand Creek Drainage Basin | 32 | | |
| Summary of Drainageway Habitat Zones | 33 | | |
| Preliminary Matrix of Conceptual Alternatives | 33 | | |
| Drainageway System Alternatives | 33 | | |
| VI. DEVELOPMENT OF ALTERNATIVES AND RECOMMENDED PLAN | | | |
| Channel Alternatives | 38 | | |
| Impact Upon Habitat | 39 | | |
| Development of Recommended Plan | 40 | | |
| Discussion of Recommended Plan | 40 | | |
| VII. PRELIMINARY DESIGN | | | |
| Criteria | 51 | | |
| Hydrology | 51 | | |
| Channels | 51 | | |
| Drop Structures and Check Structures | 52 | | |
| Detention | 52 | | |
| Water Quality | 52 | | |
| Trails | 53 | | |
| Maintenance and Revegetation | 53 | | |
| Right-of-Way | 53 | | |
| Roadway Bridge and Culvert Replacements | 53 | | |
| Erosion and Sedimentation Control | 54 | | |
| General | 54 | | |
| VIII. PLAN IMPLEMENTATION | | | |
| General | 58 | | |
| Cost Estimate | 58 | | |
| Unplanted Acreage | 58 | | |
| Drainage and Bridge Fee Calculations | 59 | | |
| APPENDIX A: | | Project Correspondence | |
| PRELIMINARY DESIGN DRAWINGS, PLAN, PROFILES AND DETAILS | | | |

LIST OF TABLES

| | <u>Page</u> | <u>Page</u> | |
|--------------|--|---|-------|
| Table III-1 | Percent Impervious Values | 10 | |
| Table III-2 | Summary of Peak Discharges - 24-Hour Duration Storm, Baseline Conditions | 10 | |
| Table IV-1 | Summary of Hydraulic Structures - Crossings | 20-25 | |
| Table IV-2 | Summary of Hydraulic Structures - Channels | 26-29 | |
| Table V-1 | Summary of Wildlife Habitat Acreages | 35 | |
| Table VI-1 | Matrix of Channel Alternatives | 43 | |
| Table VI-2 | Evaluation of Conceptual Channel Alternatives Floodplain Preservation | 44 | |
| Table VI-3 | Evaluation of Conceptual Channel Alternatives Channelization | 45 | |
| Table VI-4 | Evaluation of Conceptual Channel Alternatives Selective Drainageway Improvements | 46 | |
| Table VI-5 | Evaluation of Conceptual Channel Alternatives West Fork Sand Creek | 47 | |
| Table VI-6 | Evaluation of Conceptual Channel Alternatives Center Tributary Sand Creek | 48 | |
| Table VI-7 | Matrix of Recommended Channel Alternatives | 49 | |
| Table VII-1 | Summary of Peak Discharges Selected Detention Alternative | 55 | |
| Table VII-2 | Regional Detention Basin Water Quality Storage Requirements | 56 | |
| Table VIII-1 | Unit Construction Costs | 60 | |
| Table VIII-2 | Drainageway Conveyance Cost Estimate | 61-71 | |
| Table VIII-3 | Tributary Drainageway Conveyance Cost Estimate | 72-75 | |
| Table VIII-4 | Roadway Culvert Crossing Cost Estimate | 76-79 | |
| | Table VIII-5 | Detention Basin Cost Estimate | 80-81 |
| | Table VIII-6 | Miscellaneous Drainageway Cost Estimate | 82 |
| | Table VIII-7 | Bridge Crossing Cost Estimate | 83-84 |
| | Table VIII-8 | Drainage Basin Fee Estimation | 85 |
| | Table VIII-9 | City Bridge Fee Calculation | 86 |
| | Table VIII-10 | County Bridge Fee Calculation | 86 |
| | Table VIII-11 | Regional Detention Basin Land Fee Calculation | 87 |
| | Table VIII-12 | Regional Detention Basin Capital Cost Fee Calculation | 87 |

LIST OF FIGURES

| | <u>Page</u> |
|--|-------------|
| Figure II-1 | 5 |
| Vicinity Map | |
| Figure II-2 | 6 |
| Hydrologic Soils Map | |
| Figure II-3 | 7 |
| Proposed Land Use | |
| Figure III-1 | 11 |
| Regional Sub-Basins | |
| Figure III-2 | 12 |
| Flood Discharge Profile - Mainstem Sand Creek | |
| Figure III-3 | 13 |
| Flood Discharge Profile - Center Tributary Sand Creek | |
| Figure III-4 | 14 |
| Flood Discharge Profile - West Fork Sand Creek | |
| Figure III-5 | 15 |
| Flood Discharge Profile - East Fork Sand Creek | |
| Figure III-6 | 16 |
| Flood Discharge Profile - East Fork Sub-tributary | |
| Figure III-7 | 17 |
| Flood Discharge Profile - East and West Bierstadt Creeks | |
| Figure IV-1 | 30 |
| Reach Delineations | |
| Figure V-1 | 36 |
| Detention Basin Alternatives, Sand Creek | |
| Figure V-2 | 37 |
| Detention Basin Alternatives, East Fork Sand Creek | |
| Figure VI-1 | 50 |
| Channel Alternatives, East Fork Sand Creek | |
| Figure VII-1 | 57 |
| Water Quality Pond Capture Volumes | |

Resolution No. 189-95

A RESOLUTION ADOPTING THE SAND CREEK DRAINAGE BASIN PLANNING STUDY AND ESTABLISHING A DRAINAGE FEE, A DETENTION POND CAPITAL FEE, A DETENTION POND LAND FEE, AND AN ARTERIAL BRIDGE FEE FOR THE BASIN.

WHEREAS, the City Engineering Division of the City of Colorado Springs Department of Planning and Development has reviewed the Sand Creek Drainage Basin Planning Study as prepared by Kiowa Engineering Corporation, Colorado Springs, Colorado dated November 2, 1995, and

WHEREAS, the City/County Drainage Board has recommended approval of the above study at their November 2, 1995, meeting;

WHEREAS, the Sand Creek Drainage Basin includes unplatted land within the City limits;

NOW THEREFORE, BE IT RESOLVED by the City Council of the City of Colorado Springs:


Section 1. That the Sand Creek Drainage Basin Planning Study, dated November 1995, by Kiowa Engineering Corporation is adopted for use. City Engineering will utilize that study to assist in evaluating subdivision drainage reports.

Section 2. That a Sand Creek Drainage Basin Fee be established as \$4,895/acre, that a Sand Creek Detention Pond Capital Fee be established as \$1,213/acre, that a Sand Creek Detention Pond Land Fee be established as \$167/acre, and that a Sand Creek Arterial Bridge Fee be established as \$323/acre, as part of.

Dated at Colorado Springs, Colorado, this _____ 28th _____ day of _____ November _____, 1995.


Mayor



ATTEST:


City Clerk

ENGINEER'S STATEMENT:

The attached SAND CREEK DRAINAGE BASIN PLANNING STUDY report was prepared under my direction and supervision and are correct to the best of my knowledge and belief. Said drainage report has been prepared according to the criteria established by the City for drainage reports. I accept responsibility for any liability caused by any negligent acts, errors and omissions on my part in preparing this report.

Kiowa Engineering Corporation, 1011 North Weber St., Suite 200, Colorado Springs, CO 80903



Registered Engineer No. 10530
Date: 7/26/96

I. INTRODUCTION

Authorization

The preliminary design of the drainageway and roadway crossing facilities within the Sand Creek Drainage Basin was authorized under the terms of Agreement Number 90-85 between the City of Colorado Springs (City) and Kiowa Engineering Corporation. The agreement was approved by the Colorado Springs City Council, April 10, 1990. Subsequent to this agreement, a change order to the contract to allow for the inclusion of technical information contained in the draft East Fork Sand Creek Drainage Basin Planning Study was approved July, 1993.

Purpose and Scope

The purpose of the study is to identify feasible stormwater management plans to satisfy the existing and future needs within the Sand Creek Drainage Basin. The Sand Creek basin is to be referred to throughout this study and is inclusive of the Sand Creek mainstem and East Fork Sand Creek watersheds. The specific scope of work for this study included the following tasks:

1. Meet with the City to: insure compliance with the services required by this agreement, obtain existing data and general information from participating entities, solicit desires of participating entities and other interested agencies or groups in order to develop alternate plans, procure current information relative to development plans in the basin, procure information relative to right-of-way limitations, proposed stormwater projects, potential hazards due to flooding, and avoid duplication of effort whenever possible by utilizing existing information available from other agencies.
2. Contact the City, County, individuals, and other agencies who have knowledge and/or interest in the study area.
3. Utilize City policies and criteria and applicable information wherever possible.
4. Perform hydraulic and hydrologic analyses within the study area.
5. Identify environmental setting of basin.
6. Identify existing and potential drainage and/or flooding problems.
7. Develop improvement alternatives to reduce existing and potential flooding problems, and to mitigate the impact of stormwater runoff upon environmentally significant areas along the drainageway(s).
8. Examine the operation and maintenance aspects of feasible alternatives.

9. Conduct an economic analysis of each alternative.
10. Recommend and prepare a preliminary design for a selected alternative plan.
11. Develop drainage and bridge fees for the basin.
12. Prepare a written report discussing all items examined in the study.
13. Conduct presentations to public and private entities in order to define project goals, and to involve agencies with specific interest to help define feasible alternatives.

Summary of Data Obtained

Listed below are the technical reports collected for the review as part of preparing this study:

1. Soil Survey for El Paso County, Colorado, dated June 1981.
2. "City of Colorado Springs/El Paso County Drainage Criteria Manual", prepared by City of Colorado Springs, El Paso County, and HDR Infrastructure, Inc., dated May 1987.
3. "Flood Insurance Studies for Colorado Springs, and El Paso County, Colorado", prepared by the Federal Emergency Management Agency (FEMA), revised 1989.
4. Flood Insurance Restudy, Hydrology Report and Hydrologic Analyses, prepared by RCI, Inc., 1989.
5. Sand Creek Drainage Basin Planning Study prepared by Simons, Li & Associates, Inc., dated July, 1985.
6. Flood Hazard Analysis, Sand Creek, City of Colorado Springs and El Paso County, Colorado, prepared by the Soil Conservation Service, dated December, 1973.
7. Banning-Lewis Ranch Master Drainage Plan, prepared by MSM Consultants, Inc., dated June 1981.
8. Sand Creek Drainage Basin Study, prepared by United Planning and Engineering Company, October, 1977.
9. Draft East Fork Sand Creek Drainage Basin Planning Study, prepared by Kiowa Engineering Corporation, January, 1989.
10. Drainage Basin Inventory, Sand Creek Drainage Basin, prepared by Oliver E. Watts, P.E., June 1990.

In addition to the above listed reports there were a number of drainage study reports, sketch plans, preliminary and final design drawings, land use and zoning maps, development

plans, and existing drainage facility maps that were collected from the City, County, and other local agencies.

Reports which were prepared previous to the preliminary design report include the "Sand Creek Drainage Basin Planning Study Hydrology Report," and the "Sand Creek Drainage Basin Planning Study Development of Alternatives Report." These reports were prepared as part of the overall planning effort and have been referred to throughout this report. The Hydrology Report summarized peak flow data for existing and future basin development conditions without improvements in the basin, and established the base line hydrologic conditions from which the alternative planning then proceeded. The Development of Alternatives report evaluated the various combinations of drainageway improvements for the basin, taking into account environmental, cost, construction, right-of-way, maintenance and implementation factors for each feasible alternate plan. These reports are on file with the City Engineering Division, as well as technical addenda for each report. Both of these reports covered only the mainstem of the Sand Creek Basin. The similar information prepared for the draft East Fork Sand Creek Drainage Basin Planning Study has been summarized in this preliminary design report.

Mapping and Surveying

Mapping used in the planning effort for the mainstem of Sand Creek consisted of USGS 7-1/2 minute quadrangles, and 2-foot contour interval, 1-inch to 200-foot scale planimetric topographic maps. For the area of the basin north of Woodmen Road, aerial topographic mapping was compiled in May 1990. For the balance of the basin, the City of Colorado Springs Department of Public Utilities provided topographic mapping compiled from aerial photographs dated 1989. This mapping has been prepared as part of the Facility Inventory Management System (FIMS). The aerial topographic mapping was used in the drainage inventory, hydrologic/hydraulic analyses, and in the alternative planning phases of this project. All topographic mapping was based upon USGS vertical datum.

For the East Fork Sand Creek basin, mapping from the FIMS office and two-foot contour interval topography prepared in 1987 for the Banning-Lewis Ranch property were used in the preparation of the preliminary design. Where topographic mapping was not available, USGS quadrangle maps were used.

Stream cross-section data was obtained from the aerial mapping described above. These sections were verified against the cross-sections compiled in the 1986 City of Colorado Springs Flood Insurance Study (FIS), wherever possible.

Drainageway site inspections were conducted throughout the study area, and photographs were taken documenting the key drainage features.

The following general conditions have been placed upon the use of the FIMS topographic mapping:

-- Use of these products is restricted to the project for which the FIMS products are provided.

-- Only the body content found within the headline of the borrowed maps may appear in any report/publication developed for your study. Also, the labeling that appears on any photographs provided shall not appear in any such report/publication.

-- All FIMS' products provided to contractors involved in the subject study shall be retrieved by your department upon conclusion of the study and either returned to FIMS or destroyed.

-- The report(s) developed in which the FIMS' products are used shall include the following disclaimer statement:

"The maps and photographs included in this report were developed for purposes of the Colorado Springs Department of Utilities and are for internal use only. The Colorado Springs Department of Utilities makes no warranty, expressed or implied, as to the completeness, accuracy, or content of such products or any reproductions thereof. Any other use is not recommended and occurs at the risk of the user; such user is solely responsible and/or liable for the use of such products.

Original maps and photographs are the property of the Colorado Springs Department of Utilities. All rights are reserved. These maps and photographs or any associated record may not, wholly or in part, be reproduced, stored, or transmitted in any form or by any means, electronic, mechanical, photocopying, or otherwise, without the express prior written permission of the Colorado Springs Department of Utilities.

Regardless of the existence of purpoed copies of these official maps and photographs which may from time to time be made or published, there is only one set of official maps and photographs, which are those kept and maintained by the Colorado Springs Department of Utilities."

Project Coordination

Throughout the course of the study, meetings were held with representatives of City, County, State, and Federal agencies with an interest in drainageway planning in general. The primary reason for the coordination effort was to obtain technical information and to identify concerns with regard to the development of drainageway facilities within the basin. During the course of preparing the Development of Alternatives report, the planning constraints and concepts were discussed with the agencies and interested individuals and their input used to refine the feasible alternatives and to eventually identify a recommended drainageway plan for further design evaluation. The complete mailing list and project correspondence is contained in Appendix A of this report.

Coordination with a similar list of agencies and individuals was conducted during the preparation of the draft East Fork Sand Creek Drainage Basin Planning study. This study was authorized and conducted for Artes Properties, Inc. Meetings with state and federal agencies, the City and the County were involved in a series of meetings during the development of the alternative planning concepts and the preliminary design for the East Fork Sand Creek basin.

Acknowledgements

During the preparation of the study, several government agencies and interested individuals were routinely involved in the coordination activities. Representatives from the Colorado Division of Wildlife, U.S. Army Corps of Engineers (COE), and various City Departments provided valuable commentary during the development of the alternative plans. A listing of the individuals and agencies routinely coordinated with during the study has been presented below:

| <u>Name</u> | <u>Agency</u> |
|-----------------|--|
| Alan Morrice | El Paso County Department of Public Works |
| John Fisher | El Paso County Land Use Department |
| Sue Johnson | El Paso County Parks Department |
| Rick O'Connor | El Paso County Planning Department |
| Hugh King | City of Colorado Springs Street Division |
| Gary Haynes | City Engineering Division |
| Bruce Thorson | City Engineering Division |
| Ken Sampley | City Engineering Division |
| Steve Jacobsen | City Engineering Division |
| Christine Lytle | City Engineering Division |
| Bruce Goforth | Colorado Division of Wildlife |
| Dan Bunting | Regional Building Department |
| Sarah Fowler | Environmental Protection Agency |
| John Liou | Federal Emergency Management Agency |
| Dave Frick | RCI, Inc., Fort Collins, Colorado |
| Bill Noonan | U.S. Fish and Wildlife |
| Anita Culp | U.S. Army Corps of Engineers |
| John Maynard | Aiken/Audobon Society |
| John Covert | Palmer Foundation |
| Peter Kernikump | City Planning Department |
| Jim Rees | Department of Planning and Development |
| Fred Mais | City Parks and Recreation |
| Diana Medina | City of Colorado Springs |
| Dan Tippie | Department of Public Utilities Gas Division |
| Russ Nicklin | City of Colorado Springs |
| Wes Tyson | Department of Public Utilities Wastewater Division |
| | Department of Public Utilities Water Division |
| | City Attorney's Office |

II. STUDY AREA DESCRIPTION

The Sand Creek drainage basin is a left-bank tributary to the Fountain Creek lying in the west-central portions of El Paso County. Sand Creek's drainage area at Fountain Creek is approximately 54 square miles of which approximately 18.8 square miles are inside the City of Colorado Springs corporate limits. The basin is divided into five major sub-basins, the Sand Creek mainstem, the East Fork Sand Creek, the Central Tributary to East Fork, the West Fork, and the East Fork Subtributary. Figure II-1 shows the location of the Sand Creek basin.

Basin Description

The Sand Creek basin covers a total of 54 square miles in unincorporated El Paso County and Colorado Springs, Colorado. Of this total, approximately 28 square miles is encompassed by the Sand Creek basin, and 26 square miles for the East Fork Sand Creek basin. The basin trends in generally a south to southwesterly direction, entering the Fountain Creek approximately two miles upstream of the Academy Boulevard bridge over Fountain Creek. Two main tributaries drain the basin, those being the mainstem of Sand Creek and East Fork Sand Creek. Development presence is most evident along the mainstem. At this time, approximately 25 percent of the basin is developed. This alternative evaluation focuses upon the Sand Creek basin only.

The maximum basin elevation is approximately 7,620 feet above mean sea level, and falls to approximately 5,790 feet at the confluence with Fountain Creek. The headwaters of the basin originate in the conifer covered areas of The Black Forest. The middle eastern portions of the basin are typified by rolling range land with fair to good vegetative cover associated with semi-arid climates.

Climate

This area of El Paso County can be described, in general as high plains, with total precipitation amounts typical of a semi-arid region. Winters are generally cold and dry. Precipitation ranges from 14 to 16 inches per year, with the majority of this precipitation occurring in spring and summer in the form of rainfall. Thunderstorms are common during the summer months, and are typified by quick-moving low pressure cells which draw moisture from the Gulf of Mexico into the region. Average temperatures range from about 30°F in the winter

to 75° in the summer. The relative humidity ranges from about 25 percent in the summer to 45 percent in the winter.

Soils and Geology

Soils within the Sand Creek basin vary between soil types A through D, as identified by the U. S. Department of Agriculture, Soil Conservation Service. The predominant soil groupings are in the Truckton and Bresser soil associations. The soils consist of deep, well drained soils that formed in alluvium and residuum, derived from sedimentary rock. The soils have high to moderate infiltration rates, and are extremely susceptible to wind and water erosion where poor vegetation cover exists. In undeveloped areas, the predominance of Type A and B soils give this basin a lower runoff per unit area as compared to basins with soils dominated by Types C and D. Presented on Figure II-2 is the Hydrologic Soil distribution map for the Sand Creek basin.

Property Ownership and Impervious Land Densities

Property ownership along the major drainageway within the Sand Creek basin vary from public to private. Along the developed reaches, drainage right-of-ways and greenbelts have been dedicated during the development of the adjacent residential and commercial land. Where development has not occurred, the drainageways remain under private ownership with no delineated drainage right-of-way or easements. There are several public parks which abut the mainstem of Sand Creek. Roadway and utility easements abutting or crossing the major drainageways occur most frequently in the developed portions of the basin.


Land use information for the existing and future conditions were reviewed as part of the planning effort. This information is used in the hydrologic analysis to predict runoff rates and volumes for the purposes of facility evaluation. The identification of land uses abutting the drainageways is also useful in the identification of feasible plans for stabilization and aesthetic treatment of the creek. Presented on Figure II-3 is the proposed land use map used in the evaluation of impervious land densities discussed in the hydrologic section of this report. Figure II-3 is not intended to reflect the future zoning or land use policies of the City or the County.


The land use information within the Banning-Lewis Ranch property was obtained from Aries Properties during the time the draft East Fork Sand Creek Drainage Basin Planning Study was being prepared. The land use information was again reviewed with the City of Colorado Springs Department of Planning and was found to be appropriate for use in the estimation of hydrology for the East Fork Basin. The location of future arterial streets and roadways within

the Banning Lewis property were obtained from the Banning-Lewis Ranch master plan. The location of roadways offsite from the Banning Lewis-Ranch were obtained from the El Paso County Major Transportation Plan dated 1988.

Park Land and Open Space


An inventory of park land and public open space was prepared. Many times, the combination of the drainageway and adjacent park lands can be used to visually extend the limits of a park or open space. The drainageway can also act to link parks and other land uses within the basin if multiple use trails are incorporated into the channel section(s). The Sand Creek drainageway has been identified as a major trail corridor within the City of Colorado Springs Trails Plan. Park land designated within the Banning-Lewis Ranch master plan were taken into account during the siting of stormwater facilities within the Banning-Lewis property.





LEGEND

- HYDROLOGIC SOIL GROUP A
- ▨ HYDROLOGIC SOIL GROUP B
- ▤ HYDROLOGIC SOIL GROUP C
- ▥ HYDROLOGIC SOIL GROUP D





LEGEND

- MULTI-FAMILY RESIDENTIAL
- SINGLE FAMILY RESIDENTIAL
- LARGE LOT RESIDENTIAL
- OFFICE / RETAIL / COMMERCIAL
- INDUSTRIAL
- INSTITUTIONAL
- OPEN SPACE / PARK
- AGRICULTURAL / RANCHETTE (5 ac+)

THIS DRAWING IS A MASTER PLANNING SHEET REPRESENTING PRELIMINARY AND CONCEPTUAL ENGINEERING. IT SHOULD NOT BE USED FOR CONSTRUCTION PURPOSES.

| CHANNEL IMPROVEMENTS | | CHANNEL TYPE |
|----------------------|-------------------|----------------------------------|
| SEGMENT NO. | BOTTOM WIDTH (FT) | |
| 145 | 16 | 100-YEAR CONC. CHANNEL, 4' DEPTH |
| 146-1 | 10 | |
| 146-2 | N/A | EXISTING CHANNEL TO REMAIN |

FOR PROFILE SEE SHEETS CTP-2 AND CTP-3





Kiowa Engineering Corporation
 419 W. Blou Street
 Colorado Springs, Colorado
 80905-1308


**SAND CREEK DRAINAGE
 BASIN PLANNING STUDY
 PRELIMINARY DESIGN PLANS**

Project No. 90-04-09
 Date: 9/7/92
 Designer: EAW
 Checker: DMW
 Rev: 1/1/92

CT-7



| | | | | |
|---|---|--|---|--------------|
| Kiowa Engineering Corporation DESIGNED BY: _____ DATE: _____ DRAWN BY: _____ DATE: 7/92 REVISIONS: _____ DATE: _____ | SAND CREEK DRAINAGE BASIN PLANNING STUDY PRELIMINARY DESIGN PROFILES | CITY OF COLORADO SPRINGS EL PASO COUNTY, COLORADO | CENTER TRIBUTARY SAND CREEK Station 12+50 to 71+50 | CTP-1 |
| | | | | |



DESIGNED BY: _____ DATE: _____
 DRAWN BY: _____ DATE: 7/92
 REVISIONS: _____ DATE: _____



Kiowa Engineering Corporation

SAND CREEK DRAINAGE BASIN PLANNING STUDY
 PRELIMINARY DESIGN PROFILES

CITY OF COLORADO SPRINGS
 EL PASO COUNTY, COLORADO

CENTER TRIBUTARY SAND CREEK
 Station 71+50 to 130+50

CTP-2



| | | | | |
|---|---|--|---|-------|
| DESIGNED BY DATE 7/32 CHECKED BY DATE 7/32 REVISIONS DATE | SAND CREEK DRAINAGE BASIN PLANNING STUDY PRELIMINARY DESIGN PROFILES | CITY OF COLORADO SPRINGS EL PASO COUNTY, COLORADO | CENTER TRIBUTARY SAND CREEK Station 130+50 to 144+50 | CTP-3 |
| | | | | |

TABLE VIII-4: SAND CREEK DRAINAGE BASIN PLANNING STUDY
ROADWAY CULVERT CROSSING COST ESTIMATE

| SAND CREEK BASINS | | | | | | | | | |
|----------------------|--------------|---------------------|----------------|--------|------|-----------|------------|-------------------------|------------|
| ROADWAY | REACH NUMBER | DRAINAGEWAY SEGMENT | CROSSING TYPE | LENGTH | UNIT | UNIT COST | TOTAL COST | TOTAL REIMBURSABLE COST | TOTAL COST |
| BANNING-LEWIS PRKW | SC-8 | 186 | 6'Hx10'W CBC | 120 | LF | \$390 | \$46,800 | \$46,800 | \$46,800 |
| ARROYO LANE | SC-9 | 171 | 6'Hx12'W CBC | 80 | LF | \$510 | \$40,800 | \$0 | \$40,800 |
| VOLLMER ROAD | SC-8 | 169 | 60-INCH CMP | 80 | LF | \$120 | \$9,600 | \$0 | \$9,600 |
| " | SC-9 | 173 | " | 80 | LF | \$120 | \$9,600 | \$0 | \$9,600 |
| BURGESS ROAD | SC-9 | 176 | 42-INCH CMP | 80 | LF | \$75 | \$6,000 | \$0 | \$6,000 |
| " | SC-9 | 178 | 2-42-INCH CMP | 80 | LF | \$150 | \$12,000 | \$0 | \$12,000 |
| CENTER TRIBUTARY | | | | | | | | | |
| TERMINAL AVENUE | CT-2 | 144 | 4-5'Hx8'W CBC | 60 | LF | \$1,200 | \$72,000 | \$0 | \$72,000 |
| OMAHA BOULEVARD | CT-2 | 146-2 | 3-4'Hx9'W CBC | 80 | LF | \$900 | \$72,000 | \$0 | \$72,000 |
| WEST FORK SAND CREEK | | | | | | | | | |
| WOOTEN ROAD | WF-1 | 153 | 2-4'Hx6'W CBC | 100 | LF | \$480 | \$48,000 | \$0 | \$48,000 |
| EDISON AVENUE | WF-1 | 153 | 2-4'Hx6'W CBC | 60 | LF | \$240 | \$14,400 | \$0 | \$14,400 |
| PALMER PARK BLVD. | WF-1 | 154-2 | 2-4'Hx10'W CBC | 80 | LF | \$540 | \$43,200 | \$0 | \$43,200 |
| CHICAGO RIVER | WF-1 | 165-1 | 4'Hx8'W CBC | 220 | LF | \$270 | \$59,400 | \$0 | \$59,400 |
| HALF MOON DRIVE | WF-1 | 165-2 | 4'Hx6'W CBC | 60 | LF | \$240 | \$14,400 | \$0 | \$14,400 |

TOTAL CULVERT CONSTRUCTION COSTS, SAND CREEK \$1,902,600 \$1,111,000

Table VIII-7:
SAND CREEK DRAINAGE BASIN PLANNING STUDY
BRIDGE CROSSING COST ESTIMATE
SAND CREEK DRAINAGE BASINS

| ROADWAY | REACH NUMBER | DRAINAGEWAY SEGMENT | CROSSING TYPE | JURISDICTION CITY | COUNTY | SIZE | UNIT | UNIT COST | TOTAL COST COUNTY | TOTAL COST CITY |
|-----------------------|--------------|---------------------|-----------------------|-------------------|--------|-------|------|-----------|-------------------|-----------------|
| SAND CREEK | | | | | | | | | | |
| CHELTON ROAD | SC-1 | 115 | 210' TWO-SPAN BRIDGE | X | | 16800 | SF | \$80 | \$0 | \$1,344,000 |
| STEFSON HILLS BLVD. | SC-6 | 130 | 3-8'Hx10'W CBC | X | | 200 | LF | \$1,110 | \$0 | \$222,000 |
| JEREMIAH SMITH RD. | SC-6 | 137 | 3-8'Hx10'W CBC | X | | 60 | LF | \$1,110 | \$0 | \$66,600 |
| PETERSON ROAD | SC-6 | 141 | 80' CLEAR SPAN BRIDGE | X | | 6400 | SF | \$80 | \$0 | \$512,000 |
| DUBLIN BOULEVARD | SC-7 | 141 | 80' CLEAR SPAN BRIDGE | X | | 6400 | SF | \$80 | \$0 | \$512,000 |
| MARKSHEEL ROAD | SC-8 | 151 | 3-10'Hx10'W CBC | X | | 80 | LF | \$1,260 | \$100,800 | \$0 |
| RESEARCH PARKWAY | SC-8 | 163 | 4-8'Hx10'W CBC | X | | 80 | LF | \$1,560 | \$124,800 | \$0 |
| BANNING-LEWIS PKWY | SC-8 | 187 | 4-8'Hx10'W CBC | X | | 80 | LF | \$1,560 | \$124,800 | \$0 |
| CENTER TRIBUTARY | | | | | | | | | | |
| W. FRONTAGE ROAD | CT-1 | 142 | 3-6'Hx16'W CBC | X | | 60 | LF | \$1,770 | \$106,200 | \$0 |
| US 24 BYPASS | CT-1 | 142 | 3-6'Hx16'W CBC | X | | 150 | LF | \$1,410 | \$211,500 | \$0 |
| E. FRONTAGE RD, US 24 | CT-1 | 142 | 3-6'Hx16'W CBC | X | | 60 | LF | \$1,410 | \$84,600 | \$0 |
| BIOU STREET, US 24 | CT-1 | 142 | 3-6'Hx16'W CBC | X | | 60 | LF | \$1,410 | \$84,600 | \$0 |
| PLATIE AVENUE, US 24 | CT-2 | 142 | 3-6'Hx16'W CBC | X | | 120 | LF | \$1,410 | \$169,200 | \$0 |
| GALLEY ROAD | CT-4 | 144 | 3-5'Hx8'W CBC | X | | 100 | LF | \$900 | \$90,000 | \$0 |
| WEST FORK SAND CREEK | | | | | | | | | | |
| GALLEY ROAD | WF-2 | 155 | 54' CLEAR SPAN BRIDGE | X | | 5130 | SF | \$80 | \$0 | \$410,400 |
| PALMER PARK BLVD. | WF-2 | 156 | 54' CLEAR SPAN BRIDGE | X | | 5130 | SF | \$80 | \$0 | \$410,400 |
| CONSTITUTION AVE. | WF-3 | 159 | 40' CLEAR SPAN BRIDGE | X | | 3200 | SF | \$80 | \$0 | \$256,000 |
| MAIZELAND ROAD | WF-3 | 170 | 30' CLEAR SPAN BRIDGE | X | | 2400 | SF | \$80 | \$0 | \$192,000 |
| SO. CAREFREE | WF-3 | 170 | 2-6'Hx15'W CBC | X | | 80 | LF | \$1,200 | \$96,000 | \$0 |


TOTAL BRIDGE CONSTRUCTION COSTS, SAND CREEK \$1,096,500 \$4,021,400

FLOOD INSURANCE STUDY



EL PASO COUNTY, COLORADO, AND INCORPORATED AREAS

El Paso County



| COMMUNITY NAME | COMMUNITY NUMBER |
|--|---------------------|
| CALHAN, TOWN OF | 080192 |
| COLORADO SPRINGS, CITY OF | 080060 |
| EL PASO COUNTY (UNINCORPORATED AREAS) | 080059 |
| FOUNTAIN, CITY OF | 080061 |
| GREEN MOUNTAIN FALLS, TOWN OF | 080062 |
| MANITOU SPRINGS, CITY OF | 080063 |
| MONUMENT, TOWN OF | 080064 |
| PALMER LAKE, TOWN OF | 080065 |
| RAMAH, TOWN OF | 080066 |

Revised: December 7, 2018



Federal Emergency Management Agency

FLOOD INSURANCE STUDY NUMBER
08041CV007A

NOTICE TO
FLOOD INSURANCE STUDY USERS

Communities participating in the National Flood Insurance Program have established repositories of flood hazard data for floodplain management and flood insurance purposes. This Flood Insurance Study (FIS) report may not contain all data available within the repository. It is advisable to contact the community repository for any additional data.

Part or all of this FIS report may be revised and republished at any time. In addition, part of this FIS report may be revised by the Letter of Map Revision process, which does not involve republication or redistribution of the FIS report. It is, therefore, the responsibility of the user to consult with community officials and to check the community repository to obtain the most current FIS report components.


This FIS report was revised on December 7, 2018. Users should refer to Section 10.0, Revisions Description, for further information. Section 10.0 is intended to present the most up-to-date information for specific portions of this FIS report. Therefore, users of this report should be aware that the information presented in Section 10.0 superseded information in Sections 1.0 through 9.0 of this FIS report.

Initial Countywide FIS Report Effective Date: March 17, 1997

First Revised Countywide FIS Report Effective Date: August 23, 1999 - to add base flood elevations, to add special flood hazard areas, and to change special flood hazard areas.

Second Revised Countywide FIS Report Effective Date: December 7, 2018 - to update corporate limits, to change Base Flood Elevations and Special Flood Hazard Areas, to update map format, to add roads and road names, and to incorporate previously issued Letters of Map Revision.

FLOOD PROFILES



**SAND CREEK - CENTER TRIBUTARY
CHANNEL ANALYSIS REPORT
FOR
SOLACE APARTMENTS**

**Prepared For:
Jackson Dearborn Partners
404 S. Wells Street, Suite 400
Chicago, IL 60607
(734) 216-2577**

**June 30, 2020
Project No. 25174.00**

**Prepared By:
JR Engineering, LLC
5475 Tech Center Drive
Colorado Springs, CO 80919
719-593-2593**

PCD File NO. SP201

CONTENTS

| | |
|---|----------|
| OVERVIEW | 3 |
| GENERAL LOCATION AND DESCRIPTION | 3 |
| LOCATION..... | 3 |
| DESCRIPTION OF PROPERTY | 3 |
| FLOODPLAIN STATEMENT..... | 3 |
| PREVIOUS SAND CREEK STUDIES | 3 |
| DRAINAGE DESIGN CRITERIA | 7 |
| DEVELOPMENT CRITERIA REFERENCE | 7 |
| HYDROLOGIC CRITERIA..... | 8 |
| HYDRAULIC CRITERIA..... | 8 |
| SUMMARY | 8 |
| REFERENCES: | 9 |

APPENDICES

- A. Figures and Exhibits
- B. Hydraulic Calculations
- C. Reference Material

OVERVIEW

This report was prepared to provide design information for the existing Sand Creek -Center Tributary Drainageway as part of the Solace Apartment development. This document is the Channel Analysis report for the Solace Apartments. The Sand Creek-Center Tributary Drainageway has been studied as part of a Flood Insurance Study (FIS) for El Paso County Colorado, Volume 7 of 8, revised December 7, 2018 and Sand Creek Drainage Basin Planning Study, dated January 1993. Existing flow rates from the Sand Creek Planning Study were used as the basis for the design of the existing channel condition.

GENERAL LOCATION AND DESCRIPTION

Location

The proposed Solace Apartments, known as “Solace” from herein, is a parcel of land located in Section 7, Township 14 South, Range 65 West of the 6th Principal Meridian in El Paso County, Colorado. Solace is a 28.99 acre, urban, multifamily-development and is comprised of 16 apartment buildings and associated infrastructure. Solace is bound by existing industrial developments to the North and vacant land to the West. Galley Road bounds the property to the south and existing light industrial businesses to the east. A vicinity map of the area is presented in Appendix A.

Description of Property

Solace is currently unoccupied and undeveloped. The existing ground cover is sparse vegetation and open space, typical of a Colorado rolling range land condition. In general, Solace slopes from northwest to southeast. The existing conditions of the Sand Creek -Center Tributary Drainageway on the site are heavily wooded for the length of the channel throughout the Solace site.

Per an NRCS web soil survey of the area, Solace is made up of Type B soils with a very small percentage of Type A in the northwest corner of the property. This Type B soil is a blendon sandy loam. This soil type has a moderate infiltration rate when thoroughly wet. It also consists of moderately deep or deep, moderately well drained or well drained soil. A soil survey map has been presented in Appendix A.

Floodplain Statement

Based on the FEMA FIRM Map numbers 08041C0751G & 08041C0752G, dated December 7, 2018, a portion of the existing drainageway lies within Zone AE and Zone X. Zone AE is defined as area subject to inundation by the 1-percent-annual-chance flood event and is a flood hazard area. Zone X is defined as area outside the Special Flood Hazard Area (SFHA) and higher than the elevation of the 0.2-percent-annual-chance (or 500-year) flood. The FIRM Map has been presented in Appendix A. Currently a portion of the Solace site lies within Zone AE at the extension of Paonia Street to Galley Road, as seen in FEMA FIRM Map number 08041C0752G.

PREVIOUS SAND CREEK STUDIES

Solace lies within Sand Creek Drainage Basin based on the “*Sand Creek Drainage Basin Planning Study*” prepared by Kiowa Engineering in January 1993.

The Sand Creek Drainage Basin covers approximately 54 square miles in unincorporated El Paso County, CO. The Sand Creek Drainage Basin is tributary to Fountain Creek. In its existing condition, the basin is comprised of developed land with the exception of the Solace Parcel which is comprised of rolling rangeland with fair to good vegetative cover associated with Colorado’s semi-arid climate. The natural Drainageway within the site limits is typically deep and narrow with a well-defined flow path in most areas. Anticipated land use for the Solace parcel includes multifamily residential and open space.

As part of its drainage research, JR Engineering reviewed the following drainage studies, reports and LOMRs:

- Sand Creek Drainage Basin Planning Study prepared by Kiowa Engineering Corporation in January 1993.
- Flood Insurance Study– El Paso County, Colorado & Incorporated Areas Vol 7 of 8, December 2018.
- LOMR- Case No. 05-08-0368P Federal Emergency Management Agency, May 23, 2007.

The *Sand Creek Drainage Basin Planning Study* was used to establish a stormwater management plan for the existing and future stormwater infrastructure needs within the Sand Creek Drainage Basin. The *Sand Creek Drainage Basin Planning Study* conducted a hydrologic analysis using a runoff model named the Soil Conservation Service (SCS) Computer Program for the Project Formulation Hydrology (TR20). Based on provided drainage maps and analysis, in its existing condition, the Sand Creek-Center Tributary Drainageway contains a 100-year flow of 720 cfs at upstream station 1053 then jumps to 960 cfs at station 1030 in Sand Creek along Solace’s east property line. The flow then changes again at station 1014, to a value of 956 cfs, where the flow from the secondary drainageway on Paonia Street converges with the Sand Creek Drainageway, this flow was based on JR Engineering analysis. These flows were used in the model as they were depicted as being the flows present in the project section of the Sand Creek Tributary Drainageway as called out in *Sand Creek Drainage Basin Planning Study*. The major Sand Creek-Center Tributary Drainageway conveys the stormwater south along the eastern property line where it ultimately outfalls into the Fountain Creek. JR Engineering also performed a hydrologic analysis to determine the flows in the Sand Creek-Center Tributary Drainageway and arrived at similar results to those shown in the *Sand Creek Drainage Basin Planning Study*, thus verifying the validity of these flows. These basin calculations show that the 720-960 cfs, based on the *Sand Creek Drainage Basin Planning Study*, are still valid for this existing condition, a summary table of the flows in the Sand Creek Drainageway based on various studies can be found below.

| SOLACE APARTMENTS | | |
|---|------------------------------|------------|
| Sand Creek Center Tributary Flow Summary Table | | |
| Report/Study | Location | Flow (cfs) |
| <i>Sand Creek DBPS, Kiowa Engineering, Rev. March 1996, Table III-2</i> | DP 45, @ Galley Rd. Crossing | 1,340 |
| <i>Sand Creek DBPS, Kiowa Engineering, Rev. March 1996, CTP-2</i> | @ STA 125+00 | 960 |
| <i>Sand Creek DBPS, Kiowa Engineering, Rev. March 1996, CTP-2</i> | @ STA 132+30 | 720 |
| <i>Flood Insurance Study, El Paso County, Rev. December 7, 2018</i> | Section N, @ Galley Road | 723 |
| <i>JR Engineering October 2019</i> | @ Galley Road | 956 |

FEMA prepared a revised FIS for El Paso County Colorado, Volume 7 of 8, dated December 7, 2018. The effective floodplain for the site is shown on the FIRM 08041C0752G, revised to reflect LOMR, dated May 23, 2007. The study area of the FIS where the Sand Creek Drainageway crosses Galley Road, was found to overtop the culverts and flow onto the road. According to the FIS, this crossing has a 10% annual chance of flooding and is located in Zone AE of the FIRM. This location is a Special Flood Hazard Area (SFHA) inundated by the 100-year flood, Zone AE (base flood elevations determined). The *Sand Creek Drainage Basin LOMR* was executed on May 23, 2007. The LOMR revised the flood zone on the area south of Galley Road. See FIRM Map Panel 08041C0752G for limits of LOMR study and revised flood zones, presented in Appendix C.

To the west of the Sand Creek-Center Tributary Drainageway is a secondary Drainageway that captures the flow coming from the west side of Paonia Street. This drainage way is located at the proposed extension of Paonia Street to meet Galley Road. The flows created by the secondary drainageway and the development north of the site will be captured on the Solace site, and transported to the Sand Creek-Center Tributary Drainageway. According to *Sand Creek Drainage Basin LOMR*, the flow present in this secondary drainageway in a 1-percent-annual-chance flood event is 213 cfs. This was calculated by use of the LOMR maps, and evaluating the difference in flow as the Sand Creek Center Tributary Drainageway splits as it crosses Omaha Boulevard. Section R of the FEMA Map Panel 08041C0752G, shows the split as the flow present in the channel drops to 421 cfs from 634 cfs at section S just upstream. The difference in these flows is 213 cfs this flow is assumed to overtop the road at Omaha Boulevard crossing structure, and travel west to Paonia Street and is routed south in the Sand Creek Center Tributary onto the Solace site. A calculation of the flows present in Paonia was also conducted by Galloway Engineering in the *Preliminary Drainage Report and Floodplain Certification for Powers Center Point*, dated October 1st, 2007. This report used a similar methodology in calculating the flows; however this analysis was made using LOMR data from 1997 with higher flows thus resulting in a calculated flow of 500 cfs. To be conservative, JR Engineering's design will be based on the 500 cfs specified, rather than the 213 cfs calculated. Additional information has been requested via FEMA FIS data request. When this additional data

can be obtained, a proposed channel improvements report including both main channel and overflow improvements will be updated to reflect the latest available information. At the current point in time, all available published data has been exhausted to prove a reduced flow rate in the overflow channel (Paonia Street).

Just north of the Solace site on Paonia Street a concrete channel exists that diverts a portion of the flows present in Paonia Street back into the Sand Creek-Center Tributary Drainageway. However the size of this channel will not convey all flows present in Paonia, therefore improvements are necessary to mitigate the offsite flows. Potential options to mitigate these flows are discussed below. Each possible alternative has been preliminarily evaluated to ensure feasibility in mitigating the secondary drainageway currently existing in Paonia Street.

The first conceptual option would be to have future Paonia Street continue to maintain an existing super elevation that will direct all flows present on Paonia towards the east side of the road. GIS contours indicate this super elevation exists, as well as confirmation stated by the Galloway Engineering Preliminary Drainage Report. The curb and gutter along the east side of Paonia will be omitted to create a 110 ft weir that will route flows back to the existing Sand Creek-Center Tributary Drainageway. The 110 ft weir would reduce into a 40 ft wide channel as it approaches the existing channel at a 45 degree angle. Flow calculations for this overflow design can be found in Appendix B, along with flow capacity calculations for existing Paonia Street & existing concrete channel north of the site.

A second conceptual option would be to create a low point in Paonia shortly after crossing south onto the subject property, thus creating a sump condition. The sump inlets would capture minor runoff and pipe it to the main channel, while a larger event would behave in a similar manner to the above scenario, routing via the same overflow weir and channel back to the main Sand Creek-Center Tributary Channel. The alternative profile for this scenario can be found in Appendix B, as well as on the preliminary Paonia Street Improvement plans.

Finally, a third option would be to widen the existing concrete channel at the property line to increase capacity enough to accept all flows from the overflow channel.

The first option has been presented in the drainage maps and preliminary plans associated with this report; however no alternative has been definitively selected at this time. One alternative or a combination of these alternatives may be utilized at time of final design to safely and efficiently route the Paonia Street overflow channel back to the main channel near the northern site boundary.

Channel Deficiencies

The *Sand Creek Drainage Basin Planning Study* performed a hydraulic analysis of the Sand Creek-Center Tributary Drainageway between Galley Road and Paonia Street, and an analysis of the crossing structure for Sand Creek at Galley Road. For the crossing structure at Galley Road they determined that the existing crossing structures were inadequate for the demands of the Drainageway

and would require improvements to expand the capacity of these structures. These results can be seen in Table IV-1 Summary of Hydraulic Structures – Crossings: Sand Creek Drainage Basin Planning Study shown below. The Study proposed improvements to the existing crossing structures by replacing them with 3-8’Wx 5’H Concrete Box Culverts.

| LOCATION | REACH # | SIZE | TYPE | CAPACITY | CAPACITY | COMMENTS |
|--------------------|---------|-----------|-----------------|------------|------------|--|
| | | | | EXISTING | FUTURE (1) | |
| Airport Road | CT-1 | 5-6'x8' | BOX CULVERT | ADEQUATE | ADEQUATE | |
| Pikes Peak Ave. | CT-1 | NONE | | INADEQUATE | INADEQUATE | POWERS BLVD. OVERTOPPED FREQUENTLY BETWEEN BIJOU ST. AND PIKES PEAK AVE. |
| Powers Blvd. | CT-1 | VARIOUS | METAL PIPE | INADEQUATE | INADEQUATE | |
| Platte Ave (US 24) | CT-1 | 8'x4' | BOX CULVERT | INADEQUATE | INADEQUATE | APPROACH CHANNEL IN NEED OF REALIGNMENT |
| Terminal Avenue | CT-2 | 2-4'x8' | BOX CULVERT | INADEQUATE | INADEQUATE | |
| Galley Road | CT-2 | 3-42'x72" | METAL ARCH PIPE | INADEQUATE | INADEQUATE | |
| Omaha Boulevard | CT-2 | 2-36'x57" | METAL ARCH PIPE | INADEQUATE | INADEQUATE | |

The study also found the existing channel for the Sand Creek-Center Tributary Drainageway between Galley Road and Paonia Street to be inadequate for the given flow rate. The report says that the existing channel has limited maintenance access, leading to the channel degrading and being filled with obstructions. Those findings can be seen in Table IV-2 Summary of Hydraulic Structures – Channels: Sand Creek Drainage Basin Planning Study. The *Sand Creek Drainage Basin Planning Study* recommended improvements to the existing channel by lining the channel with concrete.

| LOCATION FROM / TO | REACH # | DIMENSIONS | | | TYPE | CAPACITY (1) | | COMMENTS |
|--------------------------------------|---------|------------|--------|-------|---|--------------|-------|---|
| | | TW | SS | DEPTH | | ADO | INADO | |
| | | (ft) | (ft) | (ft) | | | | |
| CENTER TRIBUTARY | | | | | | | | |
| East Fork Sand Creek to Airport Road | CT-1 | 45 | 2:1 | 6 | Riprap lined trapezoidal channel | X | X | Riprap has failed or is non-existent along some portions of this segment of the Center Tributary |
| Pikes Peak to Bijou St. | CT-1 | | | N/A | Rubble lined ditches along Powers Blvd. | | | Flow passes over and along Powers Blvd. street section on a frequent basis. Road closures common. |
| Bijou St. to Platte Ave. | CT-1 | | | N/A | Unlined, natural. | | | Overbanks vegetated, channel dry with sand invert, no vegetation. Channel eroded at outlet of US24 culvert. |
| Platte Ave. to Terminal Ave. | CT-2 | 15-25 | 1:1 | 4-6 | Trapezoidal concrete lined. | X | | Channel has adequate capacity. |
| Terminal Avenue to Galley Road | CT-2 | 21 | 1:1 | 5 | Trapezoidal concrete lined. | X | | Channel has adequate capacity. |
| Galley Road to Paonia Ct. (ext) | CT-2 | 30-40 | varies | 4-5 | Unimproved segment. | | X | Channel is degraded and filled with debris. Poor maintenance access. |
| Paonia Ct. to Omaha Blvd. | CT-2 | 21 | 1:1 | 5 | Trapezoidal concrete lined channel. | X | | Maintenance access poor. Debris and trash in channel. |

The GeoHecRas model results completed with this report contain similar findings to those in the drainage basin planning study. This model was based on the existing channel conditions; a model will be created for the sites proposed conditions in the final drainage report. Average velocities of 10-12 fps for a majority of the channel reach exceed allowable limits for an unprotected channel. The current Galley road crossing structures lack of capacity also leads to overtopping of the road during these events. This report confirms that both this Sand Creek channel reach and Galley Road crossing structures are inadequate for the 100-yr storm event.

Channel Improvement Recommendations

The *Sand Creek Drainage Basin Planning Study (DBPS)* concluded that the Sand Creek-Center Tributary Drainageway channel, in its current state, is inadequate to handle the historical flows tributary to the channel. This report falls in line, indicating that improvements shall be made to the channel in order to provide adequate capacity and prevent erosion. In the DBPS improvements are also designated for the crossing structures at Galley Road to provide adequate capacity and prevent overtopping of the road. Upon further investigation, this report found that overtopping of Galley Road appears to be addressed via the overflow structure and associate downstream bank protections shown in Figure 1. This weir was analyzed to determine the effectiveness to safely pass overtopping flows. From the HEC-RAS model, it was determined that approximately 581 cfs overtops the roadway during a 100-year event. The weir in its current configuration could only adequately pass approximately 40 cfs of this flow. On the north side of the Galley road crossing, there is a section of roadway without curb & gutter; this allows the water transported along the north half of galley road to directly flow into the Sand Creek Center Tributary Drainageway. A picture of this curb opening is shown below in figure 2.



Figure 1: Existing Drainage Structures at Galley Road (Viewed from South)



Figure 2: Curb Opening on North Half of the Galley Road Crossing (Looking to the North)

This analysis notes existing overtopping, further discussion with the county engineer to discuss potential solutions is recommended. One possible solution is that the existing culverts be replaced to prevent overtopping at Galley Road by upsizing to a larger culvert(s). Ultimately, culvert

improvements will be necessary when the County deems the historic overtopping of Galley Road above acceptable tolerance. Currently, no adjacent structures are impacted by this overtopping. Weir calculations can be found in the appendix.

Based upon the findings to the *Sand Creek Drainage Basin Planning Study* and the conforming GeoHecRas modeling contained in this report, potential recommended channel improvements include:

- Widening of the channel west bank to reduce flow depth, thus corresponding velocities
- Lining portions of the channel with riprap or other protective surfaces
- Adding check structures and potentially drop structures to reduce channel grade, a conceptual profile can be seen in Appendix A.
- Replacing existing culverts at Galley Road to prevent roadway overtopping

Stable slopes of 1% were chosen for the channel based on stable slope specified by The *Sand Creek Drainage Basin Planning Study (DBPS.)*

CONCEPT COST ESTIMATE

Below is Conceptual Cost Estimate for the proposed channel improvements to the Sand Creek-Center Tributary Drainageway.

Table 3: Cost Opinion-Public Reimbursable

| PUBLIC DRAINAGE FACILITIES | | | | |
|-----------------------------------|-----------------|-------------|--------------------------|----------------------|
| Item | Quantity | Unit | Unit Price | Extended Cost |
| Clearing & Grubbing | 2 | AC | \$5,000.00 | \$10,000.00 |
| Channel Widening Earthwork (Cut) | 7000 | CY | \$3.00 | \$21,000.00 |
| Riprap Lining (Type M) | 5100 | CY | \$85.00 | \$433,500.00 |
| Drop Structures | 2 | EA | \$20,000.00 | \$40,000.00 |
| | | | Sub-Total | \$504,500.00 |
| | | | 10% Eng. And Contingency | \$50,450.00 |
| | | | Grand Total | \$554,950.00 |

DRAINAGE DESIGN CRITERIA

Development Criteria Reference

Storm drainage analysis techniques were taken from the “*City of Colorado Spring/El Paso County Drainage Criteria Manual*” Volumes 1 and 2 (EPCDCM), dated October 12, 1994, the “*Urban Storm Drainage Criteria Manual*” Volumes 1 - 3 (USDCM) and Chapter 6 and Section 3.2.1 of Chapter 13 of the “*Colorado Springs Drainage Criteria Manual (CCSDCM)*, dated May 2014, as adopted by El Paso County.

Hydrologic Criteria

The hydrologic analysis for this project is based on the *Sand Creek Drainage Basin Planning Study*. The flow rates for the 100-yr storm event were taken from sheets CTP-2 & CTP-3 of this study. The Baseline Flows from the *Sand Creek Drainage Basin Planning Study* are included in Appendix C.

Hydraulic Criteria

GeoHecRas was used as the primary analysis method for the site. GeoHecRas was used to model existing flows within the Sand Creek-Center Tributary Drainageway. This model was used to verify flood plains and analyze any overtopping that may occur within the project site. The 100-year water surface profiles for the model were analyzed from the north property line of the site to the area 100 feet south of the Galley Road Crossing. Hydraulic computations for the models are contained in Appendix B. In the model the value for the roughness coefficient (n) were based upon those shown in Table 12-2 of the City of Colorado Springs Drainage Criteria Manual, Volume 1. The manning's roughness coefficient for the sides of the channel was evaluated as $n = 0.05$, as the channel sides are most closely categorized as sluggish reaches with weeds, the minimum value of n was taken. For the bottom of the channel a manning's roughness coefficient value of $n = 0.025$, as the existing channel bottom being very clear and free of plants or other debris, the minimum value of n was taken. Table 12-2 highlights the manning values used for the model. The channel was analyzed as a winding channel in the GeoHecRas model.

Table 12-2. Roughness Coefficients

| Channel Description | Roughness Coefficient (n) | | |
|--|---------------------------|---------|---------|
| | Minimum | Typical | Maximum |
| Natural Streams (top width at flood stage <100 feet | | | |
| 1. Streams on Plain | | | |
| a. Clean, straight, full stage, no rifts or deep pools | 0.025 | 0.030 | 0.033 |
| b. Same as above, but more stones and weeds | 0.030 | 0.035 | 0.040 |
| c. Clean, winding, some pools and shoals | 0.033 | 0.040 | 0.045 |
| d. Same as above, but some weeds and stones | 0.035 | 0.045 | 0.050 |
| e. Same as above, lower stages, more ineffective slopes and sections | 0.040 | 0.048 | 0.055 |
| f. Same as c, but more stones | 0.045 | 0.050 | 0.060 |
| g. Sluggish reaches, weedy, deep pools | 0.050 | 0.070 | 0.080 |
| h. Very weedy reaches, deep pools, or floodways with heavy stand of timber and underbrush | 0.075 | 0.100 | 0.150 |
| 2. Mountain Streams, no vegetation in channel, banks usually steep, trees and brush along banks submerged at high stages | | | |
| a. Bottom: gravels, cobbles, and few boulders | See Jarrett's equation* | | |
| b. Bottom: cobbles with large boulders | See Jarrett's equation* | | |

The flows in the channel, upstream and downstream of the Solace site, were determined using the sheet CTP-2 of the *Sand Creek Drainage Basin Planning Study*, with the flow 720 cfs being used at the upstream end of the channel till river station 1031 where the flow changes to 960 cfs, and once again at the Galley Road crossing to 1340 cfs. These can be seen in the GeoHecRas output table. Geometry of the channel and the crossing structure at Galley Road was determined from survey

conducted by JR Engineering's internal survey department. The Galley road crossing structure was modeled in the GeoHecRas model; its geometric parameters were determined using survey obtained data to the crossing. The sizes of the 48" CMP culverts in the crossing were also determined from survey data.

SUMMARY

This analysis of the Sand Creek-Center Tributary Drainageway remains consistent with previous studies. Velocities in the drainageway are of concern and require channel improvements, such as widening and riprap lining to ensure the Sand Creek Drainageway remains stable during a 100-yr event. This report meets the latest El Paso County Drainage Criteria requirements for this site. The results of JR Engineering's GeoHecRas model for the channel appear accurate as the water surface elevations of the channel matchup very closely to the elevations called out in the FEMA FIS along the channel. The overtopping elevation at Galley Road shown in the model matches the elevation shown in the FEMA floodplain map of 6249, showing that the GeoHecRas model results are valid.

REFERENCES:


1. El Paso County Drainage Criteria Manual Volume 1, El Paso County, CO, 1994.
2. Urban Storm Drainage Criteria Manual, Urban Drainage and Flood Control District, Latest Revision.
3. Flood Insurance Study- El Paso County, Colorado & Incorporated Areas Vol 7 of 8, Federal Emergency Management Agency, December 7, 2018.
4. Sand Creek Drainage Basin Planning Study, Kiowa Engineering, January 1993.
5. Sand Creek Drainage Basin LOMR, Federal Emergency Management Agency, May 23, 2007.
6. Preliminary Drainage Report and Floodplain Certification for Powers Center Point, Galloway Engineering, October 2007.

HEC-RAS Plan: Default Scenario River: Channel 01 Reach: CH01 Profile: Sand Creek

| Reach | River Sta | Profile | Q Total (cfs) | Min Ch El (ft) | W.S. Elev (ft) | Crit W.S. (ft) | E.G. Elev (ft) | E.G. Slope (ft/ft) | Vel Chnl (ft/s) | Flow Area (sq ft) | Top Width (ft) | Froude # Chl |
|-------|-----------|------------|------------------|-------------------|-------------------|-------------------|-------------------|-----------------------|--------------------|----------------------|-------------------|--------------|
| CH01 | 1053 | Sand Creek | 760.00 | 6265.00 | 6269.26 | 6269.26 | 6270.04 | 0.003762 | 8.51 | 179.27 | 110.42 | 0.77 |
| CH01 | 1052 | Sand Creek | 760.00 | 6258.00 | 6262.11 | 6262.11 | 6263.78 | 0.005804 | 10.49 | 77.83 | 25.50 | 0.96 |
| CH01 | 1051 | Sand Creek | 760.00 | 6257.00 | 6261.64 | 6261.64 | 6263.29 | 0.006883 | 10.30 | 74.47 | 24.12 | 0.98 |
| CH01 | 1050 | Sand Creek | 760.00 | 6257.00 | 6261.55 | 6261.55 | 6263.17 | 0.005614 | 10.36 | 81.50 | 27.77 | 0.96 |
| CH01 | 1049 | Sand Creek | 760.00 | 6257.00 | 6260.93 | 6260.93 | 6262.50 | 0.005917 | 10.15 | 80.51 | 28.71 | 0.97 |
| CH01 | 1048 | Sand Creek | 760.00 | 6255.00 | 6259.52 | 6259.52 | 6261.19 | 0.005730 | 10.51 | 80.21 | 27.19 | 0.97 |
| CH01 | 1047 | Sand Creek | 760.00 | 6254.00 | 6258.20 | 6258.20 | 6259.83 | 0.006013 | 10.34 | 79.30 | 27.50 | 0.98 |
| CH01 | 1046 | Sand Creek | 760.00 | 6253.00 | 6257.62 | 6257.33 | 6258.86 | 0.004369 | 9.10 | 93.85 | 32.59 | 0.85 |
| CH01 | 1045 | Sand Creek | 760.00 | 6253.00 | 6257.94 | | 6258.62 | 0.002044 | 6.71 | 123.65 | 36.54 | 0.59 |
| CH01 | 1044 | Sand Creek | 760.00 | 6252.00 | 6258.04 | | 6258.47 | 0.000942 | 5.39 | 158.77 | 38.15 | 0.42 |
| CH01 | 1043 | Sand Creek | 760.00 | 6252.00 | 6258.17 | | 6258.40 | 0.000450 | 3.84 | 219.34 | 49.10 | 0.29 |
| CH01 | 1042 | Sand Creek | 760.00 | 6252.00 | 6258.25 | | 6258.35 | 0.000192 | 2.60 | 333.13 | 72.33 | 0.19 |
| CH01 | 1041 | Sand Creek | 760.00 | 6251.00 | 6258.15 | 6254.86 | 6258.33 | 0.000342 | 3.46 | 250.00 | 54.53 | 0.26 |
| CH01 | 1040 | Sand Creek | 760.00 | 6251.00 | 6257.48 | | 6258.25 | 0.001509 | 7.34 | 129.48 | 31.17 | 0.53 |
| CH01 | 1039 | Sand Creek | 720.00 | 6250.00 | 6256.03 | 6256.03 | 6258.09 | 0.005145 | 12.17 | 78.63 | 22.88 | 0.93 |
| CH01 | 1038 | Sand Creek | 720.00 | 6250.00 | 6254.65 | 6254.65 | 6256.48 | 0.005632 | 11.04 | 74.30 | 23.99 | 0.96 |
| CH01 | 1037 | Sand Creek | 720.00 | 6249.00 | 6254.26 | 6254.26 | 6256.12 | 0.005266 | 11.39 | 78.61 | 25.24 | 0.94 |
| CH01 | 1036 | Sand Creek | 720.00 | 6249.00 | 6254.18 | 6253.87 | 6255.67 | 0.004153 | 10.16 | 86.85 | 27.64 | 0.84 |
| CH01 | 1035 | Sand Creek | 720.00 | 6248.00 | 6254.49 | | 6255.37 | 0.001997 | 8.12 | 123.42 | 33.33 | 0.60 |
| CH01 | 1034 | Sand Creek | 720.00 | 6248.00 | 6253.87 | 6253.37 | 6255.23 | 0.003530 | 9.97 | 96.29 | 27.50 | 0.78 |
| CH01 | 1033 | Sand Creek | 720.00 | 6248.00 | 6253.90 | 6253.27 | 6255.15 | 0.003218 | 9.54 | 100.27 | 28.48 | 0.75 |
| CH01 | 1032 | Sand Creek | 720.00 | 6248.00 | 6254.02 | 6252.85 | 6254.99 | 0.002212 | 8.21 | 107.83 | 28.30 | 0.63 |
| CH01 | 1031 | Sand Creek | 720.00 | 6247.00 | 6252.93 | 6252.93 | 6254.82 | 0.005902 | 11.67 | 81.05 | 24.65 | 0.92 |
| CH01 | 1030 | Sand Creek | 960.00 | 6247.00 | 6253.53 | | 6254.38 | 0.001956 | 8.14 | 169.51 | 45.64 | 0.61 |
| CH01 | 1029 | Sand Creek | 960.00 | 6247.00 | 6253.61 | | 6254.29 | 0.001452 | 7.08 | 180.40 | 43.93 | 0.52 |
| CH01 | 1028 | Sand Creek | 960.00 | 6247.00 | 6253.63 | 6251.57 | 6254.24 | 0.001217 | 6.58 | 184.56 | 43.62 | 0.48 |
| CH01 | 1027 | Sand Creek | 960.00 | 6247.00 | 6253.56 | | 6254.17 | 0.001232 | 7.01 | 201.11 | 46.32 | 0.50 |
| CH01 | 1026 | Sand Creek | 960.00 | 6247.00 | 6253.62 | | 6254.11 | 0.000969 | 5.82 | 199.63 | 47.17 | 0.43 |
| CH01 | 1025 | Sand Creek | 960.00 | 6247.00 | 6253.70 | 6250.88 | 6254.05 | 0.000644 | 4.85 | 227.01 | 48.43 | 0.35 |
| CH01 | 1024 | Sand Creek | 960.00 | 6246.00 | 6253.67 | 6250.42 | 6254.02 | 0.000576 | 4.98 | 235.21 | 46.35 | 0.34 |
| CH01 | 1023 | Sand Creek | 960.00 | 6246.00 | 6253.62 | 6250.47 | 6254.01 | 0.000626 | 5.21 | 225.63 | 43.80 | 0.35 |
| CH01 | 1022 | Sand Creek | 960.00 | 6246.00 | 6253.61 | | 6254.00 | 0.000607 | 5.19 | 221.85 | 41.91 | 0.35 |
| CH01 | 1021 | Sand Creek | 960.00 | 6246.00 | 6253.17 | | 6253.94 | 0.001350 | 7.37 | 164.92 | 36.16 | 0.51 |
| CH01 | 1020 | Sand Creek | 960.00 | 6246.00 | 6252.32 | 6251.61 | 6253.82 | 0.003159 | 10.30 | 118.91 | 30.63 | 0.76 |
| CH01 | 1019 | Sand Creek | 960.00 | 6246.00 | 6252.49 | 6251.34 | 6253.62 | 0.002313 | 9.03 | 140.23 | 36.35 | 0.66 |
| CH01 | 1018 | Sand Creek | 960.00 | 6246.00 | 6251.44 | 6251.44 | 6253.45 | 0.004819 | 12.21 | 109.12 | 31.63 | 0.94 |
| CH01 | 1017 | Sand Creek | 960.00 | 6245.00 | 6251.26 | 6250.03 | 6252.37 | 0.002324 | 8.73 | 133.16 | 32.49 | 0.65 |
| CH01 | 1016 | Sand Creek | 960.00 | 6245.00 | 6250.14 | 6250.14 | 6252.15 | 0.005299 | 11.66 | 96.28 | 28.21 | 0.95 |
| CH01 | 1015 | Sand Creek | 960.00 | 6244.00 | 6250.38 | 6248.09 | 6250.77 | 0.000839 | 5.11 | 215.92 | 53.82 | 0.39 |
| CH01 | 1014 | Sand Creek | 956.00 | 6244.00 | 6250.35 | 6248.71 | 6250.72 | 0.000950 | 5.78 | 370.06 | 207.76 | 0.42 |
| CH01 | 1013 | Sand Creek | 956.00 | 6244.00 | 6249.89 | 6249.89 | 6250.66 | 0.001931 | 8.21 | 274.84 | 196.01 | 0.61 |
| CH01 | 1012 | Sand Creek | 956.00 | 6244.00 | 6248.95 | 6248.95 | 6251.16 | 0.005865 | 12.67 | 104.90 | 38.16 | 1.02 |
| CH01 | 1011 | Sand Creek | 956.00 | 6244.00 | 6249.28 | 6249.28 | 6250.05 | 0.002387 | 8.46 | 279.17 | 203.66 | 0.66 |
| CH01 | 1010 | Sand Creek | 956.00 | 6244.00 | 6249.16 | 6249.16 | 6249.97 | 0.002504 | 8.54 | 254.79 | 169.44 | 0.67 |
| CH01 | 1009 | Sand Creek | 956.00 | 6242.00 | 6249.14 | 6247.90 | 6249.85 | 0.001612 | 7.93 | 276.71 | 166.57 | 0.55 |
| CH01 | 1008 | Sand Creek | 956.00 | 6242.00 | 6247.80 | 6247.80 | 6249.73 | 0.004748 | 11.73 | 106.54 | 31.47 | 0.91 |
| CH01 | 1007 | Sand Creek | 956.00 | 6242.00 | 6248.22 | 6247.39 | 6249.22 | 0.002263 | 9.17 | 222.13 | 127.82 | 0.66 |
| CH01 | 1006 | Sand Creek | 956.00 | 6242.00 | 6248.59 | 6247.92 | 6249.01 | 0.001105 | 6.67 | 368.21 | 181.76 | 0.46 |
| CH01 | 1005 | Sand Creek | 956.00 | 6242.00 | 6248.64 | 6246.43 | 6248.97 | 0.000738 | 5.28 | 352.19 | 168.51 | 0.38 |
| CH01 | 1004 | Sand Creek | 956.00 | 6242.00 | 6248.76 | 6245.39 | 6248.91 | 0.000242 | 3.31 | 399.38 | 160.30 | 0.22 |
| CH01 | 1003.56 | | Culvert | | | | | | | | | |
| CH01 | 1003 | Sand Creek | 956.00 | 6239.00 | 6244.43 | 6242.22 | 6244.82 | 0.000233 | 4.99 | 191.73 | 160.51 | 0.40 |
| CH01 | 1002 | Sand Creek | 956.00 | 6240.00 | 6243.32 | 6243.32 | 6244.68 | 0.001891 | 9.35 | 102.20 | 38.15 | 1.01 |
| CH01 | 1001 | Sand Creek | 956.00 | 6239.00 | 6242.61 | 6242.61 | 6244.01 | 0.001806 | 9.51 | 100.52 | 34.95 | 0.99 |
| CH01 | 1000 | Sand Creek | 956.00 | 6239.00 | 6242.44 | 6242.44 | 6243.85 | 0.001879 | 9.55 | 100.10 | 35.71 | 1.01 |

HEC-RAS Model Plan: Default Scenario 5/1/2020


Channel 01 CH01



| Legend | |
|-----------------|--|
| EG Sand Creek | (Green dashed line) |
| WS Sand Creek | (Blue solid line) |
| Crit Sand Creek | (Red dashed line with plus markers) |
| Ground | (Black solid line with square markers) |
| Left Levee | (Cyan shaded area) |
| Right Levee | (Cyan shaded area) |


HEC-RAS Model Plan: Default Scenario 5/1/2020

RS = 1053




HEC-RAS Model Plan: Default Scenario 5/1/2020

RS = 1052




HEC-RAS Model Plan: Default Scenario 5/1/2020


RS = 1051




HEC-RAS Model Plan: Default Scenario 5/1/2020

RS = 1050







HEC-RAS Model Plan: Default Scenario 5/1/2020
RS = 1045




HEC-RAS Model Plan: Default Scenario 5/1/2020
RS = 1044








HEC-RAS Model Plan: Default Scenario 5/1/2020
RS = 1043




HEC-RAS Model Plan: Default Scenario 5/1/2020
RS = 1042












HEC-RAS Model Plan: Default Scenario 5/1/2020
RS = 1029




HEC-RAS Model Plan: Default Scenario 5/1/2020
RS = 1028




HEC-RAS Model Plan: Default Scenario 5/1/2020
RS = 1027




HEC-RAS Model Plan: Default Scenario 5/1/2020
RS = 1026




HEC-RAS Model Plan: Default Scenario 5/1/2020
RS = 1025




HEC-RAS Model Plan: Default Scenario 5/1/2020
RS = 1024



HEC-RAS Model Plan: Default Scenario 5/1/2020
RS = 1023




HEC-RAS Model Plan: Default Scenario 5/1/2020
RS = 1022




HEC-RAS Model Plan: Default Scenario 5/1/2020

RS = 1021




HEC-RAS Model Plan: Default Scenario 5/1/2020

RS = 1020




HEC-RAS Model Plan: Default Scenario 5/1/2020





RS = 1019




HEC-RAS Model Plan: Default Scenario 5/1/2020

RS = 1018







HEC-RAS Model Plan: Default Scenario 5/1/2020
RS = 1013




HEC-RAS Model Plan: Default Scenario 5/1/2020
RS = 1012




HEC-RAS Model Plan: Default Scenario 5/1/2020
RS = 1011




HEC-RAS Model Plan: Default Scenario 5/1/2020
RS = 1010




HEC-RAS Model Plan: Default Scenario 5/1/2020
RS = 1009




HEC-RAS Model Plan: Default Scenario 5/1/2020
RS = 1008











HEC-RAS Model Plan: Default Scenario 5/1/2020
RS = 1007



HEC-RAS Model Plan: Default Scenario 5/1/2020
RS = 1006







Worksheet for Rectangular Weir - 4' Openings (10)

Project Description


Solve For Discharge

Input Data


| | | | |
|------------------------|---|------|----|
| Headwater Elevation | | 0.50 | ft |
| Crest Elevation | | 0.00 | ft |
| Tailwater Elevation | | 0.00 | ft |
| Weir Coefficient | | 3.10 | US |
| Crest Length | | 4.00 | ft |
| Number Of Contractions | 0 | | |

Results


| | | | |
|------------------------------|--|------|--------------------|
| Discharge | | 4.38 | ft ³ /s |
| Headwater Height Above Crest | | 0.50 | ft |
| Tailwater Height Above Crest | | 0.00 | ft |
| Flow Area | | 2.00 | ft ² |
| Velocity | | 2.19 | ft/s |
| Wetted Perimeter | | 5.00 | ft |
| Top Width | | 4.00 | ft |



36" RCP TOEWALL FOOTING ELEVATION VIEW
SCALE: 1" = 5'



BAFFLE BOULDER DETAIL
SCALE: NTS




TOEWALL FOOTING PROFILE
SCALE: 1" = 5'

ENERGY DISSIPATION
STRUCTURE
SOLACE APARTMENTS
JOB NO. 25174.00
5/1/20
SHEET 1 OF 1



Centennial 303-740-9393 • Colorado Springs 719-593-2593
Fort Collins 970-491-9888 • www.jrengineering.com

X:\2510000\all\2517400\Drawings\Presentation\Energy Dissipation.dwg, 11x17 Landscape, 4/28/2020 9:10:08 AM, McmullanA




A = END HEIGHT OF FLARED END SECTION OR AS SPECIFIED BY THE ENGINEER.

ELEVATION VIEW

NOTES:

1. IT IS THE DESIGN ENGINEER'S RESPONSIBILITY TO EVALUATE THE SITE CONDITIONS AND PROVIDE FINAL DESIGN OF BOULDER SIZES AND PLACEMENT, HEADWALL, FOOTING, REINFORCING STEEL AND FILLING OF VOIDS WITH GROUT OR ROCK.

2. INSTALL JOINT FASTENERS TO JOINT IMMEDIATELY UPSTREAM OF OUTLET. LOCATE AT 10-O'CLOCK AND 2-O'CLOCK. TRIM THREAD FLUSH WITH INTERIOR BOLTS.




B = 2D₅₀ OF DOWNSTREAM RIPRAP AND 3' MIN.

PROFILE

TOEWALL DESIGN TABLE

| PIPE SIZE | LENGTH, MIN. |
|-----------|--------------|
| 18" | 7'-0" |
| 24" | 8'-0" |
| 30" | 10'-0" |
| 36" | 12'-0" |
| 42" | 12'-6" |
| 48" | 13'-0" |
| 54" | 13'-6" |
| 60" | 14'-0" |
| 66" | 14'-6" |
| 72" | 15'-0" |

Figure 9-30. Flared end section (FES) headwall concept



LOMA LOMA

6264 Ft

6259 Ft

6254 Ft

6249 Ft

6236 Ft

6232 Ft

Paonia Ct

Valley St

Seneca Rd

Seneca Rd

Atoka Dr

Nokomis Dr

Atoka Dr

Wakita Dr

Galley Ct

Ford St

Valley St

N Powers Blvd

21

Galley Rd

141



Channel Report

Ex. Concrete Channel

Trapezoidal


Bottom Width (ft) = 3.50
Side Slopes (z:1) = 1.33, 1.53
Total Depth (ft) = 1.75
Invert Elev (ft) = 6267.00
Slope (%) = 1.41
N-Value = 0.013

Highlighted

Depth (ft) = 0.88
Q (cfs) = 42.08
Area (sqft) = 4.19
Velocity (ft/s) = 10.05
Wetted Perim (ft) = 6.57
Crit Depth, Yc (ft) = 1.37
Top Width (ft) = 6.02
EGL (ft) = 2.45

Calculations

Compute by: Known Depth
Known Depth (ft) = 0.88



Weir Report

Paonia Street Weir

Compound Weir

Crest = Sharp
Bottom Length (ft) = 115.00
Total Depth (ft) = 1.25
Length, x (ft) = 80.00
Depth, a (ft) = 0.50

Highlighted

Depth (ft) = 1.24
Q (cfs) = 439.00
Area (sqft) = 125.10
Velocity (ft/s) = 3.51
Top Width (ft) = 115.00

Calculations

Weir Coeff. Cw = 3.33
Compute by: Known Q
Known Q (cfs) = 439.00



Channel Report

Overflow Channel

Trapezoidal


Bottom Width (ft) = 115.00
Side Slopes (z:1) = 6.80, 6.80
Total Depth (ft) = 0.65
Invert Elev (ft) = 6265.66
Slope (%) = 1.68
N-Value = 0.017

Highlighted

Depth (ft) = 0.52
Q (cfs) = 439.00
Area (sqft) = 61.64
Velocity (ft/s) = 7.12
Wetted Perim (ft) = 122.15
Crit Depth, Yc (ft) = 0.65
Top Width (ft) = 122.07
EGL (ft) = 1.31

Calculations

Compute by: Known Q
Known Q (cfs) = 439.00



Channel Report

Paonia Street Ex.

User-defined

Invert Elev (ft) = 6271.04
Slope (%) = 1.00
N-Value = 0.016

Highlighted


Depth (ft) = 1.27
Q (cfs) = 500.00
Area (sqft) = 66.09
Velocity (ft/s) = 7.57
Wetted Perim (ft) = 89.48
Crit Depth, Yc (ft) = 1.56
Top Width (ft) = 89.43
EGL (ft) = 2.16

Calculations

Compute by: Known Q
Known Q (cfs) = 500.00

(Sta, El, n)-(Sta, El, n)...

(0.00, 6273.30)-(48.06, 6271.58, 0.016)-(86.95, 6271.04, 0.016)-(95.27, 6271.26, 0.016)-(99.33, 6271.58, 0.016)-(135.09, 6273.05, 0.016)





To: El Paso County Engineering Division
From: Mike Bramlett, PE
Date: August 27, 2021
Subject: Sand Creek Center Tributary Channel Improvements

The purpose of this letter is to provide design information for the existing conditions of the Sand Creek Center Tributary Drainageway, located east of the Solace Apartments site. This letter will also discuss the proposed improvements for the channel, design methodology, and the modeling results. For further information on the previous evaluation of the channel in its existing conditions and conceptual design, see the *Sand Creek – Center Tributary Channel Analyses Report for Solace Apartments* by JR Engineering. For further information concerning drainage for the Solace Apartments Site, see the *Final Drainage Report for Solace Apartments*, by JR Engineering.

Project General Discussion

The Sand Creek Center Tributary Channel is located in Section 7, Township 14 South, Range 65 West of the 6th Principal Meridian in El Paso County, Colorado. The site is part of the Solace Apartments project and is located on the eastern edge of the project. As part of the proposed improvements for the Solace Apartments Project, this reach of the Sand Creek Center Tributary will also be improved. The sections upstream and downstream of the site have already undergone improvements, and the channel in its current state shows extensive flooding in a 100 year event. In addition to improvements to the Sand Creek Center Tributary Channel, the channels secondary drainageway located to the west of the channel in Paonia Street will also be improved with an overflow channel that will direct flow present in the secondary drainageway into the main channel and avoid further flooding of the Paonia Street extension into the Solace Apartments site.

Channel Flows

Evaluation of the flows present in the Sand Creek Center Tributary and its secondary drainageway were discussed in detail in the *Sand Creek – Center Tributary Channel Analysis for Solace Apartments* by JR Engineering. Since the initial analysis of the channel took place, JR Engineering was able to acquire the modeling data used by FEMA for determination of flood plain modeling shown in FEMA FIRM 08041C0752G. JR Engineering assumes FEMA's flows to be accurate, and thus utilized these as the basis for our model. The main channel contains 820 cfs of flow and the secondary channel contains 217 cfs. The flow in the main channel then jumps up to 1,037 cfs at the convergence of the secondary drainageway. The convergence of these flows occurs just upstream of the Galley Road crossing, where existing topography directs the secondary drainageway into the main channel. Downstream an existing channel coming from nearby Valley Road (east)

converges with the main channel; we then utilized FEMA's 1,100 cfs to model the remaining portion of the channel.

Existing Channel Conditions

In its existing conditions the Sand Creek Center Tributary Channel along the Solace site consists of a natural channel overgrown with trees and bushes along the sides of the channel with the bottom being relatively clean and free of obstacles. The 1,350 LF reach of the Sand Creek Center Tributary Channel located incorporated with the Solace site is undeveloped, as compared to the majority of channels in the basin which have had some improvement. Downstream and upstream sections of the Sand Creek Center Tributary Channel are concrete lined. The secondary Drainageway located in Paonia Street flows south from Omaha Blvd to the Solace Apartments site where flow splits between an existing concrete channel running east to the main Sand Creek Center Tributary Channel, and a swale flowing south where it eventually rejoins the main channel at the Galley Road crossing. It is anticipated that the concrete channel will divert 42 cfs from the 217cfs present in the secondary drainageway, with 175 cfs flowing south down the existing swale. There is also an existing channel coming from Valley Road to the east. This channel intersects the main channel approximate halfway between the north and south limits of the site, adding 63 cfs to the main channel, as discussed in the Channel Flows section above. In its existing conditions, the Sand Creek Center Tributary Channel FEMA firm panel 08041C0752G, depicts 100 year flooding extending into the adjacent properties to the east and onto Paonia Street improvements to the west. The existing channel currently overtops the Galley Road crossing; primarily due to the capacity of the culverts at the crossing rather than the channel's current conditions.

Proposed Channel Improvements

As determined by the Sand Creek Drainage Basin Planning Study (DBPS) & and JR Engineering Sand Creek – Center Tributary Channel Analysis for Solace Apartments, this section of the Sand Creek Center Tributary will require improvements to ensure adequate capacity in the channel and protection against erosive velocities. In order to be consistent with improvements already made in the surrounding area and to align with the recommendations made by the DBPS, JR Engineering is proposing concrete lining of the channel along the Solace site, along with widening of the existing channel and modification to the channel alignment in this area. JR Engineering is also proposing the addition of a USBR Type III Stilling Basin and 10 foot sloped concrete drop in the channel, in order to force a hydraulic jump in the channel and reduce velocities present in the channel while still matching existing grades for the majority of channel alignment. The design methodology of the sloped drop and USBR Type III Stilling Basin are based on the design procedure for Stilling Basins presented in the Federal Highway Administrations Hydraulic Engineering Circular No. 14, Chapter 8. Calculation for stilling basin and accessories sizing can be found in the Appendix of this letter. The proposed channel section shall be a trapezoidal channel section with a 10' bottom width, with a minimum channel depth of 6.5' and side slopes varying from 3:1 to 2:1 along the channel's alignment. The channel shall be lined with concrete for a depth of 4.5' to protect the channel from the erosive velocities present in the channel, with an average depth of flow in a 100 year event for the proposed channel being approximately 4' this will provide a minimum freeboard of 2' from the top of the channel to the 100 year water surface, adhering to the DCM Volume 1 for minimum freeboard of 1.4'. The concrete section shall typically be a 6" thick concrete apron for the channel, with sections of the section of channel located within the sloped drop and stilling basin being a 12"

thick concrete apron. In accordance with the DBPS the channel shall be designed with a stable slope of 1% for the majority of the channel. For further details please see the Channel Improvement Plans included in the Appendix of this letter. In order to reduce the velocities present in the channel and avoid excessively steep slopes for extended portions of the channel's alignment, a 100' long sloped drop structure, with a total vertical drop of 10', will be placed at the upstream end of the channel. At the base of the drop will be a USBR Type III Stilling Basin that will include chute blocks, baffle blocks and a sill wall to decrease the velocity of the water coming down the sloped drop and force a hydraulic jump. This basin will also include a low flow channel through the sill wall located at the end of the stilling basin to allow water movement through the structure at lower flows and prevent ponding of water in the structure. Further detail for the sloped drop and stilling basin can be found in the channel improvement plans shown in the Appendix.

Paonia Street Secondary Drainageway Improvements

Part of the Sand Creek Center Tributary Improvements also includes the addition of a diversion channel that will direct flows present in the Paonia Street Secondary Drainageway into the main channel. This diversion will be known as the Overflow Channel for the remainder of this letter. Just north of the Overflow Channel, the existing Paonia Street is partially supered in existing conditions routing all flows present in the street to the east side. With major flows present in the existing Paonia Street present on the east side of the road, the Overflow channel will act as a large opening weir and divert flows to the main channel. The Overflow Channel shall be a concrete and riprapped lined channel with varying widths and depths that will convey the flows present in Paonia Street into the main channel. The diversion channel shall be concrete from the edge of Paonia to the right-of-way, after which it will become a riprap trapezoidal channel section with a typical bottom width of 20' and a depth of 2'-3'. The channel will run east from Paonia until it intersects with the proposed Sand Creek Center Tributary Channel alignment, where it will outfall just upstream of the proposed sloped drop in the channel. Just south of the diversion channel opening along Paonia Street will be two 15' type R inlets, that will be used to capture nuisance flows in the curb & gutter and also any flow that may bypass the diversion channel. These inlets are a redundant and not intended to capture any flows present in Paonia as the Overflow Channel is sized and designed to capture all flows present in Paonia; each inlet has a total intercept capacity of 17cfs for a total of 34cfs combined. These inlets will directly outfall into the main channel and will not be detained by any of the onsite detention ponds. For further detail on the diversion channel please see the channel improvement plans, and for detail on the type R inlets see the exert of the Solace Construction Drawings, both shown in the Appendix of this letter.

Modeling Results

The proposed conditions of the channel and its second Drainageway were modeled using GeoHecRas to determine the extents of the 100 year floodplain for the site. Flow rates from the model were used based on those discussed in the Channel Flows section and Existing Conditions section of this letter. The model was run with downstream boundary conditions for each reach using critical depths, and the entirety of the model was ran using steady flow conditions. The model was contains four separate reaches, with the main reach modeling the proposed alignment and conditions for the Sand Creek Center Tributary Channel. The other reaches modeling the Paonia Street Overflow Channel, the existing concrete overflow channel at Paonia and an existing channel that runs east to west from Valley Street and intersects the Sand Creek Center Tributary Channel, each reach

intersection were modeled using the energy equation. The model used Manning's values (n) of 0.013 for the concrete lining, 0.033 for the riprap of the overflow channel, and 0.03 for the any location outside of the concrete or riprap extents as they were determined to be most similar to a grassed area with some weeds. The results of the GeoHecRas model show that the proposed improvements to the channel substantially reduce the extents of the flood plain in the channel and contain the 100 year flood plain within the concrete extents of the channel. The results also show a maximum velocity in the channel of 10.32 ft/s in a 100 year event, showing that the concrete lining of the channel will provide sufficient protection from erosive velocities present in the channel. The GeoHecRas model for the proposed conditions also shows overtopping of the channel crossing at Galley Road, which is consistent with the flood data presented by the FEMA FIRM 08041C0752G. Flooding of the roadway is due to the insufficient capacity of the culvert crossing in this area, with the current configuration of three 48" CMP culverts only providing 365 cfs of capacity of the 1,100 cfs flow at the crossing. Flooding of the Galley Road Crossing could be alleviated by upsizing of the culvert(s), these improvements will be necessary when the County deems the historic overtopping of Galley Road to be above acceptable tolerance. *The channel improvements did not result in any change to existing overtopping of Galley Road as this is due to insufficient capacity of the culverts at this crossing, which will ultimately be addressed at a later date.* Further details on the model results can be found in the Appendix.

Summary

The analysis of the proposed improvements of the Sand Creek Center Tributary Drainageway and its secondary drainageway located in Paonia Street show significant reduction of the flood plain extents, with it now being contained within the channel extents and no longer extensively flooding properties adjacent the proposed Solace Apartment Site. The proposed diversion channel also redirects flow that would otherwise flood the proposed extension of Paonia Street back into the channel, thus alleviating the risk of the roadway flooding in a 100 year event.

Please contact me should you have any questions or concerns regarding this letter at 303-740-9393.

Sincerely,
JR ENGINEERING, LLC



Mike Bramlett, PE
JR Engineering

SOLACE APARTMENTS - SAND CREEK CENTER TRIBUTARY


A PORTION OF SECTION 7, TOWNSHIP 14 SOUTH, RANGE 65 WEST OF THE 6TH P.M.

EL PASO COUNTY, COLORADO

CHANNEL IMPROVEMENTS

ABBREVIATIONS

| | | | | | |
|-------|---------------------------------------|------|----------------------------------|-------|---|
| AC | ACRE | FDP | FINAL DEVELOPMENT PLAN | PL | PROPERTY LINE |
| AD | ALGEBRAIC DIFFERENCE | FDR | FINAL DRAINAGE REPORT | PR | PROPOSED |
| AH | AHEAD | FES | FLARED END SECTION | PRC | POINT OF REVERSE CURVATURE |
| ARCH | ARCHITECT | FG | FINISHED GRADE | PT | POINT OF TANGENCY |
| ASCE | AMERICAN SOCIETY OF CIVIL ENGINEERS | FH | FIRE HYDRANT | PV | PLUG VALVE |
| ASSY | ASSEMBLY | FL | FLOWLINE | PVC | POLYVINYL CHLORIDE |
| AVE | AVENUE | FO | FILING | R | RADIUS |
| BB | BOX BASE | FO | FIBER OPTIC CABLE | RCP | REINFORCED CONCRETE PIPE |
| BK | BACK | GB | GRADE BREAK | RD | ROAD |
| BNDY | BOUNDARY | GE | GAS EASEMENT | ROW | RIGHT OF WAY |
| BOP | BOTTOM OF PIPE | GIS | GEOGRAPHIC INFORMATION SYSTEM | RT | RIGHT |
| BOV | BLOW OFF VALVE | GL | GAS LINE | S | SOUTH |
| BFV | BUTTERFLY VALVE | GPS | GLOBAL POSITIONING SYSTEM | STE | STEEL |
| BLVD | BOULEVARD | GV | GATE VALVE | SAN | SANITARY SEWER |
| BW | BOTTOM OF WALL | HC | HANDICAP | SF | SQUARE FEET |
| C&G | CURB & GUTTER | HDC | HIGH DEFLECTION COUPLING | ST | STREET |
| CATV | CABLE TELEVISION | HDPE | HIGH DENSITY POLYETHYLENE | STA | STATION |
| CB | CATCH BASIN | HGL | HYDRAULIC GRADE LINE | STM | STORM SEWER |
| CBC | CONCRETE BOX CULVERT | HOA | HOME OWNERS ASSOCIATION | SV | SQUARE YARD |
| CDOT | COLORADO DEPARTMENT OF TRANSPORTATION | HP | HIGH POINT | SY-IN | SQUARE YARD INCH |
| CDS | CUL-DE-SAC | I | INLET | TB | THRUST BLOCK |
| CFS | CUBIC FEET PER SECOND | IE | IRRIGATION EASEMENT | TBC | TOP BACK OF CURB |
| CL | CENTER LINE | INT | INTERSECTION | TBW | TOP BACK OF WALK |
| CLOMR | CONDITIONAL LETTER OF MAP REVISION | INV | INVERT | TEL | TELEPHONE |
| CLR | CLEAR | IRR | IRRIGATION | TOA | TOP OF ASPHALT |
| CMP | CORRUGATED METAL PIPE | KB | KICK (THRUST) BLOCK | TOB | TOP OF BOX |
| CO | CLEAN OUT | LE | LANDSCAPE EASEMENT | TOC | TOP OF CURB OR CONCRETE |
| CONC | CONCRETE | LF | LINEAR FEET | TOF | TOP OF FOUNDATION |
| CR | CIRCLE | LN | LANE | TOP | TOP OF PIPE |
| CSP | CORRUGATED STEEL PIPE | LOMR | LETTER OF MAP REVISION | TW | TOP OF WALL |
| CT | COURT | LP | LOW POINT | TYP | TYPICAL |
| CTRB | CONCRETE THRUST REDUCER BLOCK | LS | LUMP SUM | UDFCD | URBAN DRAINAGE AND FLOOD CONTROL DISTRICT |
| CY | CUBIC YARD | LT | LEFT | UE | UTILITY EASEMENT |
| DBPS | DRAINAGE BASIN PLANNING STUDY | LT | LEFT | U&DE | UTILITY & DRAINAGE EASEMENT |
| DE | DRAINAGE EASEMENT | MAX | MAXIMUM | UGE | UNDERGROUND ELECTRIC |
| DIA | DIAMETER | MDDP | MASTER DEVELOPMENT DRAINAGE PLAN | VCP | VITRIFIED CLAY PIPE |
| DIP | DUCTILE IRON PIPE | MH | MANHOLE | VPC | VERTICAL POINT OF CURVATURE |
| DR | DRIVE | MIN | MINIMUM | VPI | VERTICAL POINT OF INTERSECTION |
| DRC | DESIGN REVIEW COMMITTEE | N | NORTH | VPT | VERTICAL POINT OF TANGENCY |
| DU | DWELLING UNITS | NRCP | NON-REINFORCED CONCRETE PIPE | VTC | VEHICLE TRACKING CONTROL |
| E | EAST | ODP | OFFICIAL DEVELOPMENT PLAN | W | WEST |
| EA | EACH | OHE | OVERHEAD ELECTRIC | WL | WATER LINE |
| EGL | ENERGY GRADE LINE | OHU | OVERHEAD UTILITY | WM | WATER MAIN |
| EL | ELEVATION | PC | POINT OF CURVATURE | WRD | WATER RESOURCES DEPARTMENT |
| ELEC | ELECTRIC | PCC | POINT OF COMPOUND CURVATURE | WS | WATER SURFACE |
| EOA | EDGE OF ASPHALT | PCR | POINT OF CURB RETURN | WSE | WATER SURFACE ELEVATION |
| ESMT | EASEMENT | PDP | PRELIMINARY DEVELOPMENT PLAN | WTR | WATER |
| EST | ESTIMATE | PE | PROFESSIONAL ENGINEER | YR | YEAR |
| EX | EXISTING | PI | POINT OF INTERSECTION | | |
| | | PKWY | PARKWAY | | |



VICINITY MAP
SCALE: 1" = 300'

SHEET INDEX

| | |
|-------|----------------------------------|
| 1 | COVER SHEET |
| 2 | GENERAL NOTES |
| 3 | SITE AND DEMO PLAN |
| 4-6 | CHANNEL PLAN AND PROFILES |
| 7 | CHANNEL DETAILS |
| 8 | DROP STRUCTURES PLAN AND PROFILE |
| 9 | DROP STRUCTURE DETAIL SHEETS |
| 10 | PAONIA STREET OVERFLOW PLAN |
| TOTAL | 10 |

BASIS OF BEARINGS

THE EASTERLY LINE OF LOT 2, POWERS & GALLEY PLAZA FILING NO. 1 RECORDED IN PLAT BOOK A-4 AT PAGE 30, SAID LINE BEING MONUMENTED BY A 1-1/4" YELLOW PLASTIC CAP STAMPED "LS 22106" AT THE SOUTH END AND A 1" O.D. PIPE AT THE NORTH END, SAID LINE BEARING N00°27'47"E AS SHOWN ON SAID PLAT.

BENCHMARK

FIMS MONUMENT FB81, BEING MONUMENTED BY A 3-1/4" ALUMINUM CAP IN RANGE BOX WITH NO TOP, LOCATED 900 FEET EAST OF THE INTERSECTION OF E. PLATTE AVENUE AND VALLEY STREET, APPROXIMATELY 80 FEET NORTH OF THE CENTERLINE OF E. PLATTE AVENUE. SAID MONUMENT HAVING A PUBLISHED ELEVATION OF 6275.86 FEET, NAVD88.

THE LOCATIONS OF EXISTING ABOVE GROUND AND UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. THE CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE CAUSED BY HIS FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL ABOVE GROUND AND UNDERGROUND UTILITIES.

APPLICANT/OWNER

JACKSON DEARBORN PARTNERS
404 S. WELLS ST.
SUITE 400
CHICAGO, IL 60607
P~734.216.2577

CIVIL ENGINEER

JR ENGINEERING
5475 TECH CENTER DR
SUITE 235
COLORADO SPRINGS, CO 80919
CONTACT: MIKE BRAMLETT
C~719.659.7679

PLANNER

N.E.S. INC.
619 N. CASCADE AVE
SUITE 200
COLORADO SPRINGS, CO 80903
CONTACT: TAMARA BAXTER
P~719.471.0073

GEOTECHNICAL ENGINEER

CTL THOMPSON, INC
5170 MARK DABLING BLVD
COLORADO SPRINGS, CO 80918
P~719.528.8300



Know what's below.
Call before you dig.

OWNER/DEVELOPER STATEMENT

I, THE OWNER/DEVELOPER HAVE READ AND WILL COMPLY WITH ALL OF THE REQUIREMENTS SPECIFIED IN THESE DETAILED PLANS AND SPECIFICATIONS.

DANE OLMSTEAD

DATE

JACKSON DEARBORN PARTNERS
404 S. WELLS STREET, SUITE 400
CHICAGO, IL 60607

EL PASO COUNTY STATEMENT

COUNTY PLAN REVIEW IS PROVIDED ONLY FOR GENERAL CONFORMANCE WITH COUNTY DESIGN CRITERIA. THE COUNTY IS NOT RESPONSIBLE FOR THE ACCURACY AND ADEQUACY OF THE DESIGN, DIMENSIONS, AND/OR ELEVATIONS WHICH SHALL BE CONFIRMED AT THE JOB SITE. THE COUNTY THROUGH THE APPROVAL OF THIS DOCUMENT ASSUMES NO RESPONSIBILITY FOR COMPLETENESS AND/OR ACCURACY OF THIS DOCUMENT.

FILED IN ACCORDANCE WITH THE REQUIREMENTS OF THE EL PASO COUNTY LAND DEVELOPMENT CODE, DRAINAGE CRITERIA MANUAL VOLUMES 1 AND 2, AND ENGINEERING CRITERIA MANUAL AS AMENDED.

IN ACCORDANCE WITH ECM SECTION 1.12, THESE CONSTRUCTION DOCUMENTS WILL BE VALID FOR CONSTRUCTION FOR A PERIOD OF 2 YEARS FROM THE DATE SIGNED BY THE EL PASO COUNTY ENGINEER. IF CONSTRUCTION HAS NOT STARTED WITHIN THOSE 2 YEARS, THE PLANS WILL NEED TO BE RESUBMITTED FOR APPROVAL, INCLUDING PAYMENT OF REVIEW FEES AT THE PLANNING AND COMMUNITY DEVELOPMENT DIRECTORS DISCRETION.

JENNIFER IRVINE, P.E.

DATE


COUNTY ENGINEER/ECM ADMINISTRATOR

ENGINEER'S STATEMENT

STANDARD DETAILS SHOWN WERE REVIEWED ONLY AS TO THEIR APPLICATION ON THIS PROJECT

MIKE A. BRAMLETT, P.E.
COLORADO P.E. 32314
FOR AND ON BEHALF OF JR ENGINEERING

DATE



UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE APPROPRIATE REVIEWING AGENCIES, OR ENGINEERING APPROVES THEIR USE, THESE DRAWINGS ARE DESIGNATED BY WRITTEN AUTHORIZATION.

PREPARED FOR
JACKSON DEARBORN PARTNERS
404 S. WELLS ST.
SUITE 400
CHICAGO, ILL 60607
OFFICE PHONE
(734) 216-2577

J-R ENGINEERING
A Westman Company
Central 303-740-9888 • Colorado Springs 719-583-2583
Fort Collins 970-491-9888 • www.jrengineering.com

| No. | REVISION | BY | DATE |
|-----|----------|----|------|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

| H-SCALE | V-SCALE | DATE | DESIGNED BY | DRAWN BY | CHECKED BY |
|---------|---------|----------|-------------|----------|------------|
| 1"=300' | N/A | 11/16/20 | JBP | JBP | |

SAND CREEK CENTER TRIBUTARY
COVER SHEET
SHEET 1 OF 10
JOB NO. 25174.00

LAYER LINETYPE LEGEND

Table with 3 columns: Linetype, EXISTING, PROPOSED. Lists various utility and construction lines like MATCH LINE, SECTION LINE, BOUNDARY LINE, etc.

UTILITIES LEGEND

Table with 3 columns: Utility Type, EXISTING, PROPOSED. Lists categories like STORM SEWER, SANITARY SEWER, WATER LINE, GAS LINE, and DRY UTILITIES with their respective symbols.

MONUMENTATION LEGEND

Table with 2 columns: Monument Type, Symbol. Lists types like ALUMINUM CAP - FOUND, BRASS CAP - FOUND, BENCHMARK - FOUND, etc.

DRAINAGE REPORT PLANS

Table with 2 columns: Drainage Report Plan Name, Symbol. Lists plans like BASIN DESIGNATION (NO COEFFICIENT), BASIN DESIGNATION (1 COEFFICIENT), etc.

LANDSCAPE LEGEND

Table with 3 columns: Landscape Element, EXISTING, PROPOSED. Lists elements like TREE - CONIFEROUS, TREE - DECIDUOUS, SHRUB/BUSH, etc.

STANDARD NOTES FOR EL PASO COUNTY CONSTRUCTION PLANS

- 1. ALL DRAINAGE AND ROADWAY CONSTRUCTION SHALL MEET THE STANDARDS AND SPECIFICATIONS OF THE CITY OF COLORADO SPRINGS/EL PASO COUNTY DRAINAGE CRITERIA MANUAL, VOLUMES 1 AND 2, AND THE EL PASO COUNTY ENGINEERING CRITERIA MANUAL.
2. CONTRACTOR SHALL BE RESPONSIBLE FOR THE NOTIFICATION AND FIELD NOTIFICATION OF ALL EXISTING UTILITIES...
3. CONTRACTOR SHALL KEEP A COPY OF THESE APPROVED PLANS...
4. NOTWITHSTANDING ANYTHING DEPICTED IN THESE PLANS...
5. IT IS THE DESIGN ENGINEER'S RESPONSIBILITY TO ACCURATELY SHOW EXISTING CONDITIONS...
6. CONTRACTOR SHALL SCHEDULE A PRE-CONSTRUCTION MEETING WITH EL PASO COUNTY PLANNING AND COMMUNITY DEVELOPMENT INSPECTIONS...
7. IT IS THE CONTRACTOR'S RESPONSIBILITY TO UNDERSTAND THE REQUIREMENTS OF ALL JURISDICTIONAL AGENCIES...
8. CONTRACTOR SHALL NOT DEVIATE FROM THE PLANS WITHOUT FIRST OBTAINING WRITTEN APPROVAL...
9. ALL STORM DRAIN PIPE SHALL BE CLASS III RCP UNLESS OTHERWISE NOTED...
10. CONTRACTOR SHALL COORDINATE GEOTECHNICAL TESTING PER ECM STANDARDS...
11. ALL CONSTRUCTION TRAFFIC MUST ENTER/EXIT THE SITE AT APPROVED CONSTRUCTION ACCESS POINTS.
12. SIGHT VISIBILITY TRIANGLES ARE IDENTIFIED IN THE PLANS SHALL BE PROVIDED AT ALL INTERSECTIONS...
13. SIGNING AND STRIPING SHALL COMPLY WITH EL PASO COUNTY DEPARTMENT OF PUBLIC WORKS AND MUTCD CRITERIA.
14. CONTRACTOR SHALL OBTAIN ANY PERMITS REQUIRED BY EL PASO COUNTY DEPARTMENT OF PUBLIC WORKS...
15. THE LIMITS OF CONSTRUCTION SHALL REMAIN WITHIN THE PROPERTY LINE UNLESS OTHERWISE NOTED...



Know what's below. Call before you dig.

ENGINEER'S STATEMENT

STANDARD DETAILS SHOWN WERE REVIEWED ONLY AS TO THEIR APPLICATION ON THIS PROJECT



MIKE A. BRAMLETT, P.E.
COLORADO P.E. 32314
FOR AND ON BEHALF OF JR ENGINEERING, LLC

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE APPROPRIATE REVIEWING AGENCIES, OR ENGINEERING APPROVES THEIR USE, THESE DRAWINGS ARE DESIGNATED BY WRITTEN AUTHORIZATION.



PREPARED FOR JACKSON DEARBORN PARTNERS
404 S. WELLS ST.
SUITE 400
CHICAGO, ILL. 60607
OFFICE PHONE (734) 216-2577

J.R. ENGINEERING
A Westman Company
Central 303-740-9888 • Colorado Springs 719-583-2583
Fort Collins 970-491-9888 • www.jrengineering.com

Table with columns: No., REVISION, BY, DATE. Revision table for the drawing.

Table with columns: H-SCALE, V-SCALE, DATE, DESIGNED BY, DRAWN BY, CHECKED BY. Project details table.


SAND CREEK CENTER TRIBUTARY
GENERAL NOTES



UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE APPROPRIATE REVIEWING AGENCIES, OR ENGINEERING APPROVES THEIR USE, THESE DRAWINGS ARE DESIGNATED BY WRITTEN AUTHORIZATION.
 PREPARED FOR
JACKSON DEARBORN PARTNERS
 404 S. WELLS ST.
 SUITE 400
 CHICAGO, ILL. 60607
 OFFICE PHONE (734) 216-2577

J.R. ENGINEERING
 A Westman Company
 Centennial 303-740-9888 • Colorado Springs 719-583-2583
 Fort Collins 970-491-9888 • www.jrengineering.com

| BY | DATE | No. | REVISION |
|----|------|-----|----------|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |




811
 Know what's below.
 Call before you dig.


ORIGINAL SCALE: 1" = 50'

ENGINEER'S STATEMENT
 STANDARD DETAILS SHOWN WERE REVIEWED ONLY AS TO THEIR APPLICATION ON THIS PROJECT
 MIKE A. BRAMLETT, P.E.
 COLORADO P.E. 32314
 FOR AND ON BEHALF OF JR ENGINEERING, LOCAL ENGINEER

SAND CREEK CENTER TRIBUTARY SITE AND DEMO PLAN
 SHEET 3 OF 10
 JOB NO. 25174.00




**SAND CREEK-CENTER TRIBUTARY CHANNEL PROFILE (4)
STA 11+00.00 TO 16+50.00**



FENCING NOTES

- FENCING SHALL BE PROVIDED ALONG THE EXTENTS OF THE CHANNEL, EXCEPT FOR AT LOCATIONS OF MAINTENANCE ACCESS.
- FENCING SHALL CONFORM TO THE LANDSCAPING PLANS FOR SOLACE OF COLORADO SPRINGS SP-20-001, BY NES.



LEGEND

- PROPOSED MAJOR CONTOURS (solid line with elevation 6100)
- EXISTING MAJOR CONTOUR (dashed line with elevation 6100)
- LIMITS OF GRADING (dotted line)
- 6" THICK CONCRETE CHANNEL LINING (stippled pattern)
- 12" THICK CONCRETE CHANNEL LINING (cross-hatched pattern)


CHANNEL PROFILE LEGEND

| | |
|--|----------------|
| | PROPOSED GRADE |
| | EXISTING GRADE |

ENGINEER'S STATEMENT

STANDARD DETAILS SHOWN WERE REVIEWED ONLY AS TO THEIR APPLICATION ON THIS PROJECT

MIKE A. BRAMLETT, P.E.
COLORADO P.E. 32314
FOR AND ON BEHALF OF JR ENGINEERING



UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE APPROPRIATE REVIEWING AGENCIES, JR ENGINEERING APPROVES THEIR USES DESIGNATED BY WRITTEN AUTHORIZATION.

PREPARED FOR
JACKSON DEARBORN PARTNERS
404 S. WELLS ST.
SUITE 400
CHICAGO, ILL. 60607
OFFICE PHONE (734) 216-2577



J.R. ENGINEERING
A Westman Company
Central 303-740-9888 • Colorado Springs 719-583-2583
Fort Collins 970-491-9888 • www.jrengineering.com

| BY | DATE | REVISION |
|----|------|----------|
| | | |
| | | |

H-SCALE 1"=20'
V-SCALE 1"=2'
DATE 11/16/20
DESIGNED BY JBP
DRAWN BY JBP
CHECKED BY

SAND CREEK CENTER TRIBUTARY CHANNEL PLAN AND PROFILES






SHEET 4 OF 10
JOB NO. 25174.00



**SAND CREEK-CENTER TRIBUTARY CHANNEL PROFILE (3)
STA 6+00.00 TO 11+00.00**

FENCING NOTES

- FENCING SHALL BE PROVIDED ALONG THE EXTENTS OF THE CHANNEL, EXCEPT FOR AT LOCATIONS OF MAINTENANCE ACCESS.
- FENCING SHALL CONFORM TO THE LANDSCAPING PLANS FOR SOLACE APARTMENTS, COLORADO SPRINGS SP-20-001, BY NES.



ENGINEER'S STATEMENT
STANDARD DETAILS SHOWN WERE REVIEWED ONLY AS TO THEIR APPLICATION ON THIS PROJECT

MIKE A. BRAMLETT, P.E.
COLORADO P.E. 32314
FOR AND ON BEHALF OF JR ENGINEERING

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE AGENCIES, OR ENGINEERING APPROVES THEIR USE, THESE DRAWINGS ARE DESIGNATED BY WRITTEN AUTHORIZATION.

PREPARED FOR
JACKSON DEARBORN PARTNERS
404 S. WELLS ST.
SUITE 400
CHICAGO, ILL. 60607
OFFICE PHONE (734) 216-2577



J.R. ENGINEERING
A Westman Company
Central 303-740-9383 • Colorado Springs 719-583-2583
Fort Collins 970-491-9888 • www.jrengineering.com

| BY | DATE | NO. | REVISION |
|----|------|-----|----------|
| | | | |



H-SCALE 1"=20'
V-SCALE 1"=2'
DATE 11/16/20
DESIGNED BY JBP
DRAWN BY JBP
CHECKED BY

SAND CREEK CENTER TRIBUTARY CHANNEL PLAN AND PROFILES



SHEET 5 OF 10
JOB NO. 25174.00



**SAND CREEK-CENTER TRIBUTARY CHANNEL PROFILE
STA 0+00.00 TO 6+00.00**




- FENCING NOTES**
- FENCING SHALL BE PROVIDED ALONG THE EXTENTS OF THE CHANNEL, EXCEPT FOR AT LOCATIONS OF MAINTENANCE ACCESS.
 - FENCING SHALL CONFORM TO THE LANDSCAPING PLANS FOR SOLACE OF COLORADO SPRINGS SP-20-001, BY NES.




ENGINEER'S STATEMENT
STANDARD DETAILS SHOWN WERE REVIEWED ONLY AS TO THEIR APPLICATION ON THIS PROJECT

MIKE A. BRAMLETT, P.E.
COLORADO P.E. 32314
FOR AND ON BEHALF OF JR ENGINEERING


| | |
|---|---|
| PREPARED FOR JACKSON DEARBORN PARTNERS 404 S. WELLS ST. SUITE 400 CHICAGO, ILL. 60607 OFFICE PHONE (734) 216-2577 | UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE APPROPRIATE REVIEWING AGENCIES, JR ENGINEERING APPROVES THEIR USE. REVISES DESIGNATED BY WRITTEN AUTHORIZATION. |
| | |
| BY DATE | No. REVISION |
| H-SCALE 1"=20' V-SCALE 1"=2' DATE 11/16/20 DESIGNED BY JBP DRAWN BY JBP CHECKED BY | SAND CREEK CENTER TRIBUTARY CHANNEL PLAN AND PROFILES |
| SHEET 6 OF 10 JOB NO. 25174.00 | 811 Know what's below. Call before you dig. |




TYPICAL CONCRETE CHANNEL SECTION
SCALE: N.T.S.




SLOPE CHANGE AT CHANNEL PAVING SLAB
SCALE: N.T.S.




CUTOFF/APRON TOE WALL
SCALE: N.T.S.




EXPANSION JOINT




DOWELED TRANSVERSE CONSTRUCTION OR CONTRACTION JOINT
(TRANSVERSE WEAKENED PLANE JOINT)




LONGITUDINAL CONTRACTION JOINT
(LONGITUDINAL WEAKENED PLANE JOINT)




LONGITUDINAL CONSTRUCTION JOINT
* USE ONLY IF T ≥ 8 IN.
FORM ONLY FEMALE KEYWAY




LONGITUDINAL CONSTRUCTION JOINT
** USE ONLY IF T < 8 IN.



LONGITUDINAL CONSTRUCTION JOINT
A KEYWAY IS ALLOWED TO FACILITATE USE OF BENT TIE BARS OR APPROVED TWO PIECE CONNECTORS



SEAL AT CONSTRUCTION JOINT



SAWED JOINT
*** USE T/4 WHEN T < 8 IN.

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE APPROPRIATE REVIEWING AGENCIES, OR ENGINEERING APPROVES THEIR USE, THESE DRAWINGS ARE DESIGNATED BY WRITTEN AUTHORIZATION.

PREPARED FOR
JACKSON DEARBORN PARTNERS
404 S. WELLS ST.
SUITE 400
CHICAGO, ILL. 60607
OFFICE PHONE (734) 216-2577

J.R. ENGINEERING
A Westman Company
Central 303-740-9888 • Colorado Springs 719-583-2583
Fort Collins 970-491-9888 • www.jrengineering.com

| BY | DATE |
|----|------|
| | |
| | |
| | |
| | |
| | |



| No. | REVISION |
|-----|----------|
| | |
| | |
| | |
| | |

| H-SCALE | N/A | V-SCALE | N/A | DATE | DESIGNED BY | DRAWN BY | CHECKED BY |
|---------|-----|---------|-----|----------|-------------|----------|------------|
| | | | | 11/16/20 | JBP | JBP | |



SAND CREEK CENTER TRIBUTARY CHANNEL DETAILS
SHEET 7 OF 10
JOB NO. 25174.00



ENGINEER'S STATEMENT
STANDARD DETAILS SHOWN WERE REVIEWED ONLY AS TO THEIR APPLICATION ON THIS PROJECT
MIKE A. BRAMLETT, P.E.
COLORADO P.E. 32314
FOR AND ON BEHALF OF JR ENGINEERING, LOCAL ENGINEER
DATE



**DROP 1 PROFILE
STA 13+00.00 TO 14+65.00**



ENGINEER'S STATEMENT
STANDARD DETAILS SHOWN WERE REVIEWED ONLY AS TO THEIR APPLICATION ON THIS PROJECT

MIKE A. BRAMLETT, P.E.
COLORADO P.E. 32314
FOR AND ON BEHALF OF JR ENGINEERING, LOCAL ENGINEER

UNLESS SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE AGENCIES, OR ENGINEERING APPROVES THEIR USE, DESIGNATED BY WRITTEN AUTHORIZATION.

PREPARED FOR
JACKSON DEARBORN PARTNERS
404 S. WELLS ST.
SUITE 400
CHICAGO, ILL. 60607
OFFICE PHONE (734) 216-2577

J.R. ENGINEERING
A Westman Company


Central 303-740-9888 • Colorado Springs 719-583-2583
Fort Collins 970-491-9888 • www.jrengineering.com

| No. | REVISION | BY | DATE |
|-----|----------|----|------|
| | | | |
| | | | |
| | | | |
| | | | |

| H-SCALE | V-SCALE | DATE | DESIGNED BY | DRAWN BY | CHECKED BY |
|---------|---------|----------|-------------|----------|------------|
| 1"=6' | 1"=6' | 11/16/20 | JBP | JBP | JBP |

SAND CREEK CENTER TRIBUTARY
DROP STRUCTURES PLAN AND PROFILE

SHEET 8 OF 10
JOB NO. 25174.00



UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE APPROPRIATE REVIEWING AGENCIES, JR ENGINEERING APPROVES THEIR USE AS DESIGNED BY WRITTEN AUTHORIZATION.

PREPARED FOR
JACKSON DEARBORN PARTNERS
 404 S. WELLS ST.
 SUITE 400
 CHICAGO, ILL. 60607
 OFFICE PHONE (734) 216-2577

J.R. ENGINEERING
 A Westman Company
 Centennial 303-740-9888 • Colorado Springs 719-583-2583
 Fort Collins 970-491-9888 • www.jrengineering.com

| BY | DATE |
|----|------|
| | |
| | |
| | |
| | |
| | |
| | |

| No. | REVISION | H-SCALE | N/A | V-SCALE | N/A | DATE | DESIGNED BY | DRAWN BY | CHECKED BY |
|-----|----------|---------|-----|---------|-----|----------|-------------|----------|------------|
| | | | | | | 11/16/20 | JBP | JBP | |

SAND CREEK CENTER
 TRIBUTARY
 DROP STRUCTURE DETAIL
 SHEETS

SHEET 9 OF 10
 JOB NO. 25174.00




Know what's below.
 Call before you dig.


ENGINEER'S STATEMENT

STANDARD DETAILS SHOWN WERE REVIEWED ONLY AS TO THEIR APPLICATION ON THIS PROJECT





MIKE A. BRAMLETT, P.E.
 COLORADO P.E. 32314



FOR AND ON BEHALF OF JR ENGINEERING, INC.



AREA PART OF
PAONIA STREET IMPROVEMENTS
SEE PAONIA STREET CONSTRUCTION
DRAWINGS FOR FURTHER DETAIL



ENGINEER'S STATEMENT
 PREPARED UNDER MY DIRECT SUPERVISION AND ON BEHALF OF JR
 ENGINEERING
Mike Bramlett
 MIKE A. BRAMLETT, P.E.
 COLORADO P.E. 32314
 FOR AND ON BEHALF OF JR ENGINEERING, LOCAL ENGINEERING PROFESSIONAL CORPORATION
 DATE 7/14/21


| | |
|---|---|
| SAND CREEK CENTER TRIBUTARY PAONIA STREET OVERFLOW PLAN | SHEET 10 OF 10 JOB NO. 25174.00 |
| | H-SCALE 1"=10' V-SCALE N/A DATE 11/16/20 DESIGNED BY JBP DRAWN BY JBP CHECKED BY |
| No. REVISION BY DATE | PREPARED FOR JACKSON DEARBORN PARTNERS 404 S. WELLS ST. SUITE 400 CHICAGO, ILL. 60607 OFFICE PHONE (734) 216-2577 |
| J.R. ENGINEERING A Westman Company Centennial 300-740-9888 • Colorado Springs 719-588-2583 Fort Collins 970-491-9888 • www.jrengineering.com | UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE APPROPRIATE REVIEWING AGENCIES, JR ENGINEERING APPROVES THEIR USE DESIGNATED BY WRITTEN AUTHORIZATION. |

TABLE VIII-2: SAND CREEK DRAINAGE BASIN PLANNING STUDY
CONT'D DRAINAGEWAY CONVEYANCE COST ESTIMATE
CENTER TRIBUTARY SAND CREEK

| SEGMENT NUMBER | REACH NUMBER | SEGMENT LENGTH (FT) | IMPROVEMENT TYPE | IMPROVEMENT LENGTH (FT) | UNIT COST (\$/LF) | NUMBER OF GRADE CONTROLS | LENGTH OF GRADE CONTROL (FT) | TOTAL REIMBURSABLE COSTS | TOTAL COST |
|--|--------------|---------------------|-----------------------|-------------------------|-------------------|--------------------------|------------------------------|--------------------------|-------------|
| 141 | CT-1 | 2600 | EX. RIPRAP TO REMAIN | 1500 | 195 | 5 | 400 | \$338,500 | \$338,500 |
| 142 | " | 4100 | 100-YR RIPRAP (1) | 1300 | 195 | 10 | 600 | \$322,500 | \$322,500 |
| 143 | " | 2300 | 100-YR RIPRAP (1) | 2300 | 195 | 8 | 480 | \$0 | \$503,700 |
| 144 | CT-2 | 2800 | EX. CHANNEL TO REMAIN | 200 | 195 | 0 | 0 | \$39,000 | \$39,000 |
| 145 | " | 720 | 100-YEAR CONCRETE | 720 | 195 | 2 | 100 | \$151,900 | \$151,900 |
| 146-1 | " | 680 | " | 680 | 195 | 0 | 0 | \$132,600 | \$132,600 |
| 146-2 | " | 1300 | EX. CHANNEL TO REMAIN | 1200 | 0 | 0 | 0 | \$0 | \$0 |
| TOTAL CENTER TRIBUTARY SAND CREEK DRAINAGEWAYS | | | | | | | | \$984,500 | \$1,488,200 |

(1) A PORTION OF THESE IMPROVEMENTS TO BE CONSTRUCTED AS PART OF THE US 24 BYPASS PROJECT, PHASE II.

APPENDIX E
DRAINAGE MAPS & PLANS



DESIGN POINT SUMMARY TABLE


| DP | OS | Q100 |
|-----|-------|--------|
| | Total | Total |
| 1 | 3.1 | 21.0 |
| 2 | 0.9 | 6.2 |
| 3 | 1.4 | 9.5 |
| 4 | 1.3 | 9.0 |
| 5 | 36.7 | 573.1 |
| 6 | 28.4 | 52.9 |
| 1.0 | - | 820.0 |
| 1.1 | - | 820.0 |
| 1.2 | - | 1037.0 |
| 1.3 | - | 1100.0 |
| 1.4 | - | 500.0 |
| 1.5 | - | 244.0 |
| 1.6 | - | 42.1 |

BASIN SUMMARY TABLE

| Tributary Sub-basin | Area (acres) | Percent Impervious | C _s | C ₁₀₀ | t _c (min) | Q _s (cfs) | Q ₁₀₀ (cfs) |
|---------------------|--------------|--------------------|----------------|------------------|----------------------|----------------------|------------------------|
| A1 | 14.75 | 2% | 0.09 | 0.36 | 32.5 | 3.1 | 21.0 |
| A2 | 3.79 | 2% | 0.09 | 0.36 | 25.4 | 0.9 | 6.2 |
| A3 | 5.44 | 2% | 0.09 | 0.36 | 22.7 | 1.4 | 9.5 |
| B1 | 4.84 | 2% | 0.09 | 0.36 | 20.3 | 1.3 | 9.0 |
| OS1 | 17.73 | 80% | 0.59 | 0.70 | 15.1 | 36.7 | 73.1 |
| OS2 | 8.93 | 90% | 0.73 | 0.81 | 8.6 | 28.4 | 52.9 |

LEGEND:

- EXISTING MAJOR CONTOUR
- EXISTING MINOR CONTOUR
- DRAINAGE BASIN
- A = BASIN DESIGNATION
B = AREA IN ACRES
C = PERCENT IMPERVIOUS
- DESIGN POINT
- HIGH POINT
- LOW POINT
- EXISTING DRAINAGE ARROW




EXISTING DRAINAGE MAP
SOLACE AT CIMARRON HILLS
JOB NO. 25174.00
3/12/21
SHEET 1 OF 1



Centennial 303-740-9393 • Colorado Springs 719-593-2593
Fort Collins 970-491-9888 • www.jrengineering.com

SEE SHEET 3



DESIGN POINT

| DP | OS | Q100 |
|-------|-------|--------|
| Total | Total | Total |
| 1 | 2.2 | 4.7 |
| 2 | 0.5 | 1.0 |
| 3 | 2.1 | 4.4 |
| 4 | 1.7 | 3.3 |
| 5 | 1.6 | 3.1 |
| 6 | 1.6 | 3.1 |
| 7 | 0.8 | 2.3 |
| 8 | 0.6 | 1.0 |
| 9 | 0.5 | 1.0 |
| 10 | 4.2 | 9.6 |
| 11 | 1.1 | 3.2 |
| 12 | 0.8 | 1.7 |
| 13 | 3.4 | 8.3 |
| 14 | 4.1 | 9.7 |
| 15 | 1.6 | 2.8 |
| 16 | 3.2 | 8.5 |
| 17 | 0.1 | 0.2 |
| 18 | 1.0 | 1.8 |
| 19 | 1.9 | 4.3 |
| 20 | 0.8 | 2.0 |
| 21 | 0.9 | 1.7 |
| 22 | 0.7 | 1.3 |
| 23 | 1.0 | 2.2 |
| 24 | 0.5 | 1.6 |
| 25 | 1.5 | 3.2 |
| 26 | 1.0 | 2.6 |
| 27 | 3.1 | 7.1 |
| 28 | 1.9 | 4.1 |
| 29 | 0.4 | 0.8 |
| 30 | 0.9 | 1.8 |
| 31 | 1.8 | 4.5 |
| 32 | 1.1 | 2.4 |
| 33 | 2.1 | 5.8 |
| 34 | 0.6 | 1.4 |
| 35 | 22.4 | 46.7 |
| 36 | 2.5 | 6.7 |
| 37 | 22.5 | 3.6 |
| 38 | 0.2 | 1.0 |
| 39 | 0.2 | 1.5 |
| 40 | 0.8 | 2.2 |
| 41 | 0.3 | 2.3 |
| 42 | 0.5 | 1.9 |
| 43 | 36.7 | 73.1 |
| 44 | 21.3 | 42.4 |
| 4P | 5.7 | 11.3 |
| 5P | 8.6 | 19.4 |
| 6P | 13.5 | 30.8 |
| 1.0 | 5.7 | 11.3 |
| 2.0 | 1.6 | 3.5 |
| 2.1 | 2.1 | 4.3 |
| 2.2 | 2.8 | 5.5 |
| 2.3 | 3.1 | 6.1 |
| 2.4 | 7.1 | 15.1 |
| 2.5 | 8.1 | 18.2 |
| 2.6 | 8.6 | 19.4 |
| 3.0 | 6.4 | 9.1 |
| 3.1 | 10.5 | 19.0 |
| 3.2 | 10.6 | 19.1 |
| 3.3 | 11.1 | 20.2 |
| 3.4 | 11.9 | 21.6 |
| 3.5 | 12.5 | 23.2 |
| 3.6 | 13.0 | 24.1 |
| 3.7 | 13.3 | 24.7 |
| 3.8 | 13.8 | 26.1 |
| 3.9 | 1.2 | 2.9 |
| 4.0 | 4.1 | 9.5 |
| 4.1 | 6.9 | 15.7 |
| 4.2 | 20.0 | 40.8 |
| 4.3 | 1.3 | 2.7 |
| 4.4 | 20.7 | 42.3 |
| 4.5 | 21.7 | 45.0 |
| 4.6 | 22.4 | 46.7 |
| 4.7 | 2.5 | 6.7 |
| 5.0 | - | 820.0 |
| 5.1 | - | 820.0 |
| 5.2 | - | 1037.0 |
| 5.3 | - | 1100.0 |

BASIN SUMMARY TABLE

| Tributary Sub-basin | Area (acres) | Percent Impervious | C _s | C ₁₀₀ | t _c (min) | Q _s (cfs) | Q ₁₀₀ (cfs) |
|---------------------|--------------|--------------------|----------------|------------------|----------------------|----------------------|------------------------|
| A1 | 0.50 | 78% | 0.70 | 0.81 | 5.7 | 1.7 | 3.3 |
| A2 | 0.47 | 77% | 0.71 | 0.82 | 6.2 | 1.6 | 3.1 |
| A3 | 0.45 | 78% | 0.72 | 0.82 | 5.9 | 1.6 | 3.1 |
| A4 | 0.15 | 90% | 0.73 | 0.81 | 5.0 | 0.6 | 1.0 |
| A5 | 0.13 | 90% | 0.73 | 0.81 | 5.0 | 0.5 | 1.0 |
| A6 | 1.51 | 58% | 0.53 | 0.68 | 10.5 | 3.2 | 7.0 |
| A7 | 0.58 | 41% | 0.42 | 0.60 | 10.6 | 1.0 | 2.4 |
| A8 | 0.30 | 53% | 0.52 | 0.68 | 5.9 | 0.8 | 1.7 |
| A9 | 1.33 | 0% | 0.08 | 0.35 | 13.9 | 0.4 | 2.9 |
| B1 | 0.37 | 78% | 0.72 | 0.83 | 5.1 | 1.4 | 2.7 |
| B2 | 0.35 | 94% | 0.85 | 0.93 | 5.0 | 1.6 | 2.8 |
| B3 | 0.35 | 71% | 0.67 | 0.79 | 5.0 | 1.2 | 2.4 |
| B4 | 0.03 | 90% | 0.73 | 0.81 | 5.0 | 0.1 | 0.2 |
| B5 | 0.26 | 90% | 0.73 | 0.81 | 5.0 | 1.0 | 1.8 |
| B6 | 0.73 | 59% | 0.56 | 0.71 | 7.1 | 1.9 | 4.1 |
| B7 | 0.47 | 40% | 0.37 | 0.56 | 7.0 | 0.8 | 2.0 |
| B8 | 0.25 | 90% | 0.73 | 0.81 | 5.0 | 0.9 | 1.7 |
| B9 | 0.19 | 90% | 0.73 | 0.81 | 5.0 | 0.7 | 1.3 |
| B10 | 0.38 | 55% | 0.53 | 0.69 | 5.2 | 1.0 | 2.2 |
| B11 | 0.74 | 35% | 0.33 | 0.53 | 11.1 | 1.0 | 2.6 |
| B12 | 1.08 | 61% | 0.58 | 0.72 | 9.2 | 2.7 | 5.6 |
| B13 | 0.58 | 57% | 0.55 | 0.70 | 6.4 | 1.5 | 3.2 |
| B13A | 0.48 | 21% | 0.23 | 0.46 | 9.4 | 0.5 | 1.6 |
| B14 | 0.49 | 68% | 0.63 | 0.76 | 9.4 | 1.3 | 2.6 |
| B15 | 0.27 | 77% | 0.71 | 0.81 | 5.7 | 0.9 | 1.8 |
| B16 | 0.15 | 66% | 0.56 | 0.69 | 5.4 | 0.4 | 0.8 |
| B17 | 0.99 | 41% | 0.42 | 0.60 | 8.2 | 1.8 | 4.5 |
| B18 | 0.47 | 51% | 0.50 | 0.66 | 7.2 | 1.1 | 2.4 |
| B19 | 1.92 | 30% | 0.32 | 0.53 | 16.9 | 2.1 | 5.7 |
| B20 | 0.26 | 50% | 0.49 | 0.66 | 6.3 | 0.6 | 1.4 |
| B21 | 2.46 | 0% | 0.08 | 0.35 | 29.7 | 0.5 | 3.6 |
| C1 | 0.74 | 26% | 0.29 | 0.51 | 15.0 | 0.8 | 2.2 |
| C2 | 0.80 | 0% | 0.08 | 0.35 | 6.3 | 0.3 | 2.3 |
| D1 | 0.95 | 14% | 0.19 | 0.43 | 12.8 | 0.7 | 2.6 |
| F1 | 0.92 | 56% | 0.52 | 0.67 | 7.5 | 2.2 | 4.7 |
| F2 | 0.14 | 79% | 0.72 | 0.83 | 5.0 | 0.5 | 1.0 |
| F3 | 0.73 | 60% | 0.57 | 0.72 | 5.5 | 2.1 | 4.4 |
| F4 | 0.68 | 31% | 0.30 | 0.51 | 11.3 | 0.8 | 2.3 |
| F5 | 3.88 | 36% | 0.36 | 0.55 | 10.3 | 3.4 | 8.3 |
| F6 | 0.35 | 0% | 0.08 | 0.35 | 5.3 | 0.2 | 1.0 |
| F7 | 0.53 | 0% | 0.08 | 0.35 | 6.9 | 0.2 | 1.5 |
| OS1 | 17.73 | 80% | 0.59 | 0.70 | 15.1 | 36.7 | 73.1 |
| OS2 | 8.93 | 90% | 0.59 | 0.70 | 10.6 | 21.3 | 42.4 |

LEGEND:

- PROPOSED STORM SEWER
- PROPOSED ROOF DRAIN SEWER
- 6200— PROPOSED MAJOR CONTOUR
- 6200— PROPOSED MINOR CONTOUR
- EXISTING MAJOR CONTOUR
- EXISTING MINOR CONTOUR
- MAJOR DRAINAGE BASIN
- MINOR DRAINAGE BASIN
- 1 DESIGN POINT
- HP HIGH POINT
- LP LOW POINT
- DRAINAGE ARROW
- EXISTING DRAINAGE ARROW
- A
B
C A = BASIN DESIGNATION
B = AREA IN ACRES
C = PERCENT IMPERVIOUS




DRAINAGE MAP
 SOLACE AT CIMARRON HILLS
 JOB NO. 25174.00
 3/12/21
 SHEET 1 OF 3



Centennial 303-740-9393 • Colorado Springs 719-593-2593
 Fort Collins 970-491-9888 • www.jrengineering.com

SEE SHEET 2

SEE SHEET 3




SEE SHEET 1


LEGEND:

- PROPOSED STORM SEWER
 - PROPOSED ROOF DRAIN SEWER
 - 6200 PROPOSED MAJOR CONTOUR
 - PROPOSED MINOR CONTOUR
 - 6200 EXISTING MAJOR CONTOUR
 - EXISTING MINOR CONTOUR
 - MAJOR DRAINAGE BASIN
 - MINOR DRAINAGE BASIN
 - DESIGN POINT
 - HP** HIGH POINT
 - LP** LOW POINT
 - DRAINAGE ARROW
 - EXISTING DRAINAGE ARROW
- A** = BASIN DESIGNATION
B = AREA IN ACRES
C = PERCENT IMPERVIOUS

DRAINAGE MAP
 SOLACE AT CIMARRON HILLS
 JOB NO. 25174.00
 3/12/21
 SHEET 2 OF 3



J-R ENGINEERING
 A Westrian Company
 Centennial 303-740-9393 • Colorado Springs 719-593-2593
 Fort Collins 970-491-9888 • www.jrengineering.com




SEE SHEET 1

SEE SHEET 2

LEGEND:

- PROPOSED STORM SEWER
- PROPOSED ROOF DRAIN SEWER
- PROPOSED MAJOR CONTOUR
- PROPOSED MINOR CONTOUR
- EXISTING MAJOR CONTOUR
- EXISTING MINOR CONTOUR
- MAJOR DRAINAGE BASIN
- MINOR DRAINAGE BASIN
- DESIGN POINT
- HIGH POINT
- LOW POINT
- DRAINAGE ARROW
- EXISTING DRAINAGE ARROW


A = BASIN DESIGNATION
 B = AREA IN ACRES
 C = PERCENT IMPERVIOUS



DRAINAGE MAP
 SOLACE AT CIMARRON HILLS
 JOB NO. 25174.00
 3/12/21
 SHEET 3 OF 3


J-R ENGINEERING
 A Westrian Company

Centennial 303-740-9393 • Colorado Springs 719-593-2593
 Fort Collins 970-491-9888 • www.jrengineering.com



LEGEND:

- POND A CAPTURE AREA
- POND B CAPTURE AREA
- OFFSITE FLOW AREA
- SAND CREEK CAPTURE AREA



DRAINAGE EXCLUSION MAP
 SOLACE AT CIMARRON HILLS
 JOB NO. 25174.00
 03/10/21
 SHEET 1 OF 1



Centennial 303-740-9393 • Colorado Springs 719-593-2593
 Fort Collins 970-491-9888 • www.jrengineering.com