Kimley »Horn

Please proofread before next submittal.

Add section regarding the

Substitute Landscape Plan

UDON RV Storage

PCD File # PPR2422

Site Development Plan

Letter of Intent

June 2024

APPLICANT-OWNER/CONSULTANT INFORMATION:

OWNER/APPLICANT

UDON HOLDINGS, LLC 5755 Mark Dabling Boulevard, Suite 245 Colorado Springs, CO 80919 <u>rillax2@gmail.com</u> 719-321-7705

PLANNING SUPPORT

KIMLEY-HORN AND ASSOCIATES, INC. 2 NORTH NEVADA AVENUE, SUITE 900 COLORADO SPRINGS, CO 80903

ENGINEERING

KIMLEY-HORN AND ASSOCIATES, INC. 2 NORTH NEVADA AVENUE, SUITE 900 COLORADO SPRINGS, CO 80903 <u>Kevin.Kofford@kimley-horn.com</u> 719-352-9154


LOCATION, ACREAGE, PARCEL ID INFO, & ZONING

The application for a site development plan (SDP) and includes Parcel No. 4400000237. The proposed SDP is located on the south right of way line of State Highway 94, approximately 1,800 feet east from the Coral Valley Road intersection and 2,270 feet west from the N Franceville Coal Mine Road intersection (see vicinity map) The total acreage of the proposed Grading SDP is ±18.06. (Currently Zoned: Commercial Services [CS]).

719-453-0180

Kimley »Horn

Page 2



UTILITIES

Please

access

one has been obtained

permit and detail that

obtain a CDOT

The project connects to existing Cherokee Metro District and CSU public utilities in the area. See utility plan for future detail. Outside of the details provided with the utility plans, the project will also be coordinating final design with CSU for the required gas and electrical services.

DRAINAGE AND GRADING

The total area studied drainage area is 52.69 acres in size. The project involves the construction of vehicle/RV storage and parking areas with associated driveways, internal roads, landscaping, stormwater quality and detention pond, and associated drainage culverts. The total disturbed area of the site is approximately ±18.06 acres. Generally, stormwater runoff will follow the existing and natural pattern associated with the existing conditions. The flows generated from the improved and graded area are to be conveyed via overland sheet flow towards an existing naturally vegetated

these specific details so that the letter of intent does not have to be revised each Kimley »Horn time the drainage report is revised

recommend removing

Page 3

drainage swale. These flows will then continue to the proposed planned detention basin. Flows are released from this proposed detention basin feature via outlet pipe with prifice plate into the existing shallow natural drainage channel that runs generally southwest over natural vacant existing meadowlands that ultimately discharges into Jimmy Camp Creek. Flows generated from the proposed conditions will generally follow historic patterns. Under proposed conditions the studied drainage area associated with this project is ±52.69 acres with a 24.2% weighted imperviousness and 5 and 100-yr flows of 99.12 cfs and 178.64 cfs respectively. The proposed conditions drainage map can be found in the Appendix of the Final Drainage Report dated 06/26/24.

TRAFFIC

Per the current traffic study and the proposed use scenario, it is recommended that the access intersection along SH-94 be stop a controlled access with a R1-1 "STOP" sign installed on the northbound approach. Access will initially be a T-intersection with only the south area being developed. The recommended intersection lane configurations and control for the project development are illustrated in the attached submitted Traffic Study. Study dated April 18, 2024

PARKING

The project provides off-street parking as required by El Paso County, Section 6.2.5. The project requires three (3) parking spaces out side of the planned storage parking, which will include one (1) ADA parking space, which will be provided. The parking is associated with site office (an existing building).

ADA

The project provides and has been planned for the parking and access in compliance of the ADA and Federal and State accessibility laws. Walk and access has been provided in associated site office.

SITE LIGHTING

All site lighting will meet the EPC design standards and shall be submitted in accordance with submittal requirements for (photometrics) lighting plans. Light fixtures shall be arranged and positioned such that the light sources are concealed and fully shielded as to so minimized impacts to adjacent properties and rights-of-way. Light fixtures are required to be full cutoff.

LANDSCAPING

Is this word supposed to be trees or grass?

The project provides landscaped areas per El Paso County code. The plan provides the minimum required landscape setbacks along all front and side frontages. The planting design will provide a combination of berms, fencing, trass and shrubs. The project also reflects the 25' setback along Hwy 24. See landscape sheets for further details. The application also request an Alternative Compliance approval. The request is to locate the internal and parking lot tree requirements to the setback zones. See the alternative compliance request below. This is not illustrated

The standards:

- Expressway, principal Arterial 25' feet-Setback, Trees, 1 per 20' feet of Frontagin the landscape plan. •
- Non-Arterial 10'-Setback, Trees 1 per 10 'feet of Frontage •

Kimley »Horn

- Parking lot Trees, 1 tree per 15 parking spaces
- Internal Landscape, Trees, 1/500sf of internal landscape

LANDSCAPE ALTERNATIVE COMPLIANCE REQUEST

An alternative compliance request will be submitted in relationship to internal tree counts and parking lot counts due to the flexible use of exterior storage and the existing nature of the landscape.

SITE SIGNAGE

A separate signage program and application will be provided under separate application. No sign locations have been identified at this time.