

UDON SOUTH SITE DEVELOPMENT PLAN 12265 HIGHWAY 94

**THE NORTHEAST QUARTER OF THE NORTHWEST QUARTER OF SECTION 18,
TOWNSHIP 14 SOUTH, RANGE 64 WEST OF THE 6TH PRINCIPAL MERIDIAN, COUNTY OF
EL PASO, STATE OF COLORADO, EXCEPT ANY PORTION THEREOF WITHIN THE RIGHT
OF WAY FOR HIGHWAY 94**

GENERAL NOTES

1. THE PARTIES RESPONSIBLE FOR THIS PLAN HAVE FAMILIARIZED THEMSELVES WITH ALL CURRENT ACCESSIBILITY CRITERIA AND SPECIFICATIONS AND THE PROPOSED PLAN REFLECTS ALL SITE ELEMENTS REQUIRED BY THE APPLICABLE ADA DESIGN STANDARDS AND GUIDELINES AS PUBLISHED BY THE UNITED STATES DEPARTMENT OF JUSTICE. APPROVAL OF THIS PLAN BY EL PASO COUNTY DOES NOT ASSURE COMPLIANCE WITH THE ADA OR ANY REGULATIONS OR GUIDELINES ENACTED OR PROMULGATED UNDER OR WITH RESPECT TO SUCH LAWS.
2. THE OWNER AGREES ON BEHALF OF HIM/HERSELF AND ANY DEVELOPER OR BUILDER SUCCESSORS AND ASSIGNEES THAT SUBDIVIDER AND/OR SAID SUCCESSORS AND ASSIGNS SHALL BE REQUIRED TO PAY TRAFFIC IMPACT FEES IN ACCORDANCE WITH THE EL PASO COUNTY ROAD IMPACT FEE PROGRAM RESOLUTION (RESOLUTION NO. 19-471), OR ANY AMENDMENTS THERETO, AT OR PRIOR TO THE TIME OF BUILDING PERMIT SUBMITTALS. THE FEE OBLIGATION, IF NOT PAID AT FINAL PLAT RECORDING, SHALL BE DOCUMENTED ON ALL SALES DOCUMENTS AND ON PLAT NOTES TO ENSURE THAT A TITLE SEARCH WOULD FIND THE FEE OBLIGATION BEFORE SALE OF THE PROPERTY.
3. OWNER IS RESPONSIBLE FOR PAYING OR POSTING AN APPROVED BOND OR LETTER OF CREDIT IN THE AMOUNT REFLECTED ON THE EPC DPW APPROVED FINANCIAL ASSURANCE ESTIMATE (FAE) FORM PRIOR TO ISSUANCE OF A CONSTRUCTION NOTICE TO PROCEED

EASEMENT NOTES:

PER PLAT RECEPTION #220900117

EASEMENT GRANTED TO EL PASO MUTUAL TELEPHONE COMPANY, FOR UTILITY, AND INCIDENTAL PURPOSES, BY INSTRUMENT RECORDED APRIL 26, 1971, IN BOOK 2404 AT PAGE 587 AND 588 - IS LOCATED ON SUBJECT PARCEL, INSUFFICIENT MATHEMATICAL DATA TO PLOT

SITE DATA

ZONING CLASSIFICATION: COMMERCIAL SERVICE (CS)
 CURRENT LAND USE: RESIDENTIAL RURAL / COMMERCIAL
 JURISDICTION: EL PASO COUNTY
 SITE ADDRESS: 12265 & 12345 HIGHWAY 94
 TAX SCHEDULE NO.: 4400000237
 BUILDING SETBACKS: 25' FRONT SETBACK
 25' REAR SETBACK
 25' SIDE SETBACK
 MAXIMUM BUILDING HEIGHT: 45 FT
 MIN. AREA PER ZONING DISTRICT: 2 ACRES
 MIN. LOT SIZE: N/A
 MAX LOT COVERAGE: N/A
 EXISTING GROSS BUILDING AREA: ±9,002 SF
 OPEN SPACE: ±10.51 AC
 LANDSCAPING: ±12.03 AC
 IMPERMEABLE SURFACE: ±1.09 AC (EXISTING)
 ±11.08 AC (PROPOSED)

LAND AREA

TOTAL PROPERTY AREA: ± 34.71 ACRES

GEOLOGICAL HAZARDS NOTE:

A "SOIL, GEOLOGY, AND GEOLOGIC HAZARD EVALUATION 12265 HIGHWAY 94 EL PASO COUNTY, COLORADO" WAS PREPARED BY ENTECH, DATED MAY 19, 2022. MAPPING HAS BEEN PERFORMED ON THIS SITE TO IDENTIFY AREAS WHERE VARIOUS GEOLOGIC CONDITIONS EXIST OF WHICH DEVELOPERS SHOULD BE COGNIZANT DURING THE PLANNING, DESIGN, AND CONSTRUCTION STAGES SHOULD NEW CONSTRUCTION BE PROPOSED. THE ENGINEERING GEOLOGIC HAZARDS IDENTIFIED ON THE THIS SITE INCLUDE:

- ARTIFICIAL FILL
- EXPANSIVE SOILS
- POTENTIALLY UNSTABLE SLOPES
- DRAINAGE AREAS/FLOODPLAINS
- POTENTIALLY SEASONAL SHALLOW GROUNDWATER AREA

THE EXISTING GEOLOGIC AND ENGINEERING GEOLOGIC CONDITIONS WILL IMPOSE SOME MINOR CONSTRAINTS ON DEVELOPMENT AND CONSTRUCTION. THESE AREAS WHICH CAN BE SATISFACTORILY MITIGATED THROUGH PROPER ENGINEERING DESIGN AND CONSTRUCTION PRACTICES, OR AVOIDANCE.

LEGAL DESCRIPTION

THE NORTHEAST QUARTER OF THE NORTHWEST QUARTER OF SECTION 18, TOWNSHIP 14 SOUTH, RANGE 64 WEST, OF THE 6TH PRINCIPAL MERIDIAN, COUNTY OF EL PASO, STATE OF COLORADO, EXCEPT ANY PORTION THEREOF WITHIN THE RIGHT OF WAY FOR HIGHWAY 94, AS DESCRIBED IN THAT GENERAL WARRANTY DEED, RECORDED AS RECEPTION NO. 219151478, ON DECEMBER 3, 2019, IN THE OFFICIAL PUBLIC RECORDS, EL PASO COUNTY, COLORADO.

CONTAINING 34.71 +/- ACRES

BENCHMARK:

NO. 6 REBAR WITH 3-1/4" ALUMINUM CAP, STAMPED "PE-LS 9853", 0.72' ABOVE GRADE, AS SHOWN. ELEVATION: 6227.66' (NAVD 88)

BASIS OF BEARINGS:



BEARINGS ARE BASED ON THE SOUTH LINE OF THE NORTHEAST QUARTER OF THE NORTHWEST QUARTER OF SECTION 18, TOWNSHIP 14 SOUTH, RANGE 64 WEST, OF THE 6TH PRINCIPAL MERIDIAN, EL PASO COUNTY, COLORADO, MONUMENTED AT NORTH 1/16 CENTER CORNER OF SAID SECTION 18, BY A NO. 6 REBAR WITH A 2 INCH ALUMINUM CAP, STAMPED "PLS 18465", FLUSH WITH GRADE, AND AT THE NORTHWEST 1/16 CORNER OF SAID SECTION 18, BY A NO. 6 REBAR WITH A 3-1/4 INCH ALUMINUM CAP, STAMPED "PE-LS 9853", 0.72 FEET ABOVE GRADE, AS SHOWN HEREON, AND MEASURED TO BEAR S89°48'31"W A DISTANCE OF 1246.37 FEET.

SOIL TYPE:

±100% OF THE SOIL ON SITE IS CLASSIFIED WITH THE USCS AS HYDROLOGIC SOIL GROUP D.

FEMA CLASSIFICATION:

THE PROPOSED PROJECT SITE IS LOCATED IN ZONE X AN AREA OF MINIMAL FLOOD HAZARD. FEDERAL EMERGENCY MANAGEMENT AGENCY, FLOOD INSURANCE RATE MAP, MAP NUMBERS 08041C0780G EFFECTIVE DATE DECEMBER 7, 2018.



CONTACTS:

OWNER:
UDON HOLDINGS, LLC.
12265 HIGHWAY 94
COLORADO SPRINGS, CO 80929
TEL: (719) 321-7705
EMAIL: RILLAX2@GMAIL.COM
CONTACT: BEN WILBOR

ENGINEER:
KIMLEY-HORN AND ASSOCIATES, INC.
2 NEVADA NORTH AVE., SUITE 900
COLORADO SPRINGS, CO 80903
TEL: (719) 453-0180
CONTACT: KEVIN KOFFORD, P.E.

PLANNER:
KIMLEY-HORN AND ASSOCIATES, INC.
2 NEVADA NORTH AVE., SUITE 900
COLORADO SPRINGS, CO 80903
TEL: (719) 453-0180
CONTACT: JIM HOUK

SURVEYOR:
CLARK LAND SURVEYING, INC.
1777 S. TIFFANY DR. UNIT 1
PUEBLO WEST, CO 81007
TEL: (719) 582-1270
CONTACT: STUART MAPES, JR, P.L.S.

EL PASO COUNTY:
EL PASO COUNTY
DEVELOPMENT SERVICES DEPARTMENT
2880 INTERNATIONAL CIRCLE, SUITE 110
COLORADO SPRINGS, CO 80910
PHONE: (719) 520-3600

Sheet List Table	
Sheet Number	Sheet Title
1	COVER SHEET
2	SITE MAP
3	SITE PLAN

EL PASO COUNTY PCD APPROVAL:



MEGGAN HERINGTON, EXECUTIVE DIRECTOR
PLANNING AND COMMUNITY DEVELOPMENT

DATE



© 2024 KIMLEY-HORN AND ASSOCIATES, INC.
2 NORTH NEVADA AVENUE, SUITE 900
COLORADO SPRINGS, COLORADO 80903 (719) 453-0180

ISSUED: 10.31.2024
COVER SHEET
SHEET 1 OF 3



11980 HIGHWAY 94
OWNER: BUSCHMANN, JOHN
& STILSON, RUSSELL
PARCEL NO. 440000475
CURRENT ZONING: RR-5

12220 HIGHWAY 94
OWNER: WHITNEY, CASEY
PARCEL NO. 440000476
CURRENT ZONING: RR-5

12150 HIGHWAY 94
OWNER: THANI HOLDINGS LLC
PARCEL NO. 440000185
CURRENT ZONING: RR-5

HIGHWAY 94
OWNER: CITY OF COLORADO
SPRINGS
PARCEL NO. 440000506
CURRENT ZONING: RR-5

12135 HIGHWAY 94
OWNER: FAIR DINKUM TRUST
PARCEL NO. 440000239
CURRENT ZONING: RR-5

12265 HIGHWAY 94
OWNER: UDON HOLDINGS LLC
PARCEL NO. 440000237
CURRENT ZONING: CS



12455 HIGHWAY 94
OWNER: EMPIRE ACQUISITIONS LLC
PARCEL NO. 440000056
CURRENT ZONING: CS

HIGHWAY 94
OWNER: MILLER, GARY D &
VETTE, MARIE & VETTE, TAD
PARCEL NO. 440000061
CURRENT ZONING: RR-5

N FRANCEVILLE COAL MINE RD
OWNER: MILLER, GARY D & VETTE, TAD
PARCEL NO. 440000310
CURRENT ZONING: RR-5

K:\CCS_Civil\19822003_UDON South\CADD\PlanSheets\SDP_SDP_SMDwg_Cct 31_2024_1.rvt

CO STATE HIGHWAY 94
(100' PUBLIC RIGHT-OF-WAY)
(REC. NO. 219151478)






LEGEND

WL	EXISTING WATER LINE
G	EXISTING GAS LINE
OH	EXISTING OVERHEAD ELECTRIC
UT	EXISTING UNDERGROUND ELECTRIC UTILITY
SS	EXISTING SANITARY SEWER
X	EXISTING FENCE
X	PROPOSED FENCE
---	PROPOSED STORM PIPE
---	PROPOSED GRAVEL
---	PROPOSED RIPRAP
---	PROPOSED CONCRETE
---	PROPOSED POND MAINTENANCE ROAD
---	PROPOSED ASPHALT

NOTE:


1. ALL EXISTING INFRASTRUCTURE TO REMAIN UNLESS OTHERWISE SPECIFIED
2. ALL PROPOSED PARKING AREAS, DRIVE AISLES, AND INTERNAL ROADS TO BE GRAVEL UNLESS OTHERWISE NOTED
3. CSU FIELD ENGINEER TO DETERMINE FINAL GAS/ELECTRIC METER, TRANSFORMER, AND SERVICE LINE LOCATIONS. CONTACT FIELD ENGINEERING AT 719-668-4985 (GAS) OR 719-668-5564 (ELECTRIC) WITH ANY QUESTIONS.
4. NO COMMERCIAL SIGNS TO BE PROPOSED



TYPICAL PARKING STALL DIMENSIONS
1" = 20'

ESTIMATED PARKING DATA:

TOTAL PARKING COUNTS NOT TO EXCEED 860 PER TRAFFIC IMPACT ANALYSIS. PARKING COUNTS MAY VARY IN TERMS OF QUANTITY AND SIZE. POTENTIAL STORED EQUIPMENT TO INCLUDE BUT NOT LIMITED TO VEHICLES, RV'S, BOATS, AND TRAILERS



12135 HIGHWAY 94
OWNER: FAIR DINKUM TRUST
PARCEL NO. 4400000239

12455 HIGHWAY 94
OWNER: EMPIRE ACQUISITIONS LLC
PARCEL NO. 4400000056

HIGHWAY 94
OWNER: MILLER, GARY D & VETTE, MARIE & VETTE, TAD
PARCEL NO. 4400000061

N FRANCEVILLE COAL MINE RD
OWNER: MILLER, GARY D & VETTE, TAD
PARCEL NO. 4400000310



© 2024 KIMLEY-HORN AND ASSOCIATES, INC.
2 NORTH NEVADA AVENUE, SUITE 900
COLORADO SPRINGS, COLORADO 80903 (719) 453-0180

ISSUED: 10.31.2024
SITE PLAN
SHEET 3 OF 3