



FINAL DRAINAGE LETTER TANNER RANCH
FILING NO.1

Tanner Ranch Filing No. 1
El Paso County, Colorado
PCD File No. DA261

Prepared for:

Pusan Holdings, LLC
5801 N. Union Blvd, Suite 100
Colorado Springs, CO 80918
Contact: Ben Wilbor


Prepared by:

Kimley-Horn and Associates, Inc.
2 North Nevada Avenue, Suite 900
Colorado Springs, CO 80903
(719) 453-0181
Contact: Kevin Kofford, P.E.

Project #: 296172000

Prepared: July 8, 2026

Kimley»Horn



CERTIFICATION

ENGINEERS STATEMENT

This report and plan for the drainage design of the Pond A Tanner Ranch Filing No. 1 was prepared by me (or under my direct supervision) and is correct to the best of my knowledge and belief. Said report and plan has been prepared according to the criteria established by the County for drainage reports. I accept responsibility for any liability caused by any negligent acts, errors, or omissions on my part in preparing this report.

SIGNATURE (Affix Seal): _____
Kevin R. Kofford
Colorado P.E. No. 57234

_____ Date

DEVELOPER'S STATEMENT

I, the developer, have read and will comply with all of the requirements specified in this Drainage Report and Plan.

Name of Developer

Authorized Signature

_____ Date

Printed Name

Title

Address

EL PASO COUNTY

Filed in accordance with the requirements of the Drainage Criteria Manual, Volumes 1 and 2, El Paso County Engineering Criteria Manual and Land Development Code as amended.

Joshua J. Palmer, P.E.
County Engineer/ ECM Administrator

_____ Date

Conditions:

TABLE OF CONTENTS

Contents

CERTIFICATION	1
ENGINEERS STATEMENT	1
DEVELOPER'S STATEMENT	1
EL PASO COUNTY	1
TABLE OF CONTENTS	2
INTRODUCTION.....	3
PURPOSE AND SCOPE OF STUDY	3
LOCATION	3
DESCRIPTION OF PROPERTY	3
SOILS DATA.....	3
DRAINAGE DESIGN CRITERIA	4
PREVIOUS DRAINAGE STUDIES.....	4
DEVELOPMENT DESIGN CRITERIA REFERENCE	4
HYDROLOGIC CRITERIA	4
HYDRAULIC CRITERIA.....	4
VARIANCES FROM CRITERIA	4
EXISTING DRAINAGE CONDITIONS	4
Existing Sub-Basin Summary	5
Sub-Basin EX-A	5
PROPOSED DRAINAGE CONDITIONS.....	5
Proposed Sub-Basin Summary	5
Sub-Basin A-2.....	5
FOUR-STEP PROCCES	5
DRAINAGE FACILITY DESIGN	6
Pond A1	7
Pond A	7
Pond B	7
Pond C	7
Pond D	8
FLOODPLAIN STATEMENT.....	8
GRADING AND EROSION CONTROL.....	8
DRAINAGE FEES.....	8
REFERENCES.....	9
APPENDIX.....	10
APPENDIX A – VICINITY MAP	11
APPENDIX B – FEMA FIRM PANEL.....	12
APPENDIX C – NRCS SOIL SURVEY.....	13
APPENDIX D – HYDROLOGIC CALCULATIONS	14
APPENDIX E – HYDRAULIC CALCULATIONS.....	15
APPENDIX F – PREVIOUS DRAINAGE STUDIES.....	16

INTRODUCTION

PURPOSE AND SCOPE OF STUDY

The purpose of this Final Drainage Letter (“FDL”) is to outline the required drainage improvements and grading design necessary to support the Tanner Ranch Filing No. 1 maintenance and proposed upgrades to Pond A on the Tanner Ranch Project located at 350 N Dinner Bell Drive (the “Property” or “Site”), Town of Calhan, County of El Paso, State of Colorado. It is also to account for current water quality requirements in regard to the active disturbance associated with the Tanner Ranch Project with respect to the entirety of the site being analyzed.

The Final Drainage Report for Tanner Ranch Filing No. 1 was completed by WestWorks Engineering and approved by El Paso County dated July 18th, 2005. This Final Drainage Letter identifies needed maintenance to existing stormwater infrastructure and detention facilities along with the proposed improvements to the Pond A associated with the proposed repairs and improvements to existing infrastructure to bring into Preliminary Acceptance with the County.

LOCATION

The Property was previously platted and developed with an existing land use as single-family residential. The Project is located in Section 18, Township 14 south, Range 61 west of the 6th Principal Meridian, County of El Paso, State of Colorado. The Property is located within the Upper Pond Creek Basin, HOPO0600. The Site is bounded by Highway 94 to the north, S Calhan Highway to the east, Handle Road to the south, and vacant properties to the west (see Vicinity map in Appendix).

The overall project consists of repairing and maintaining the existing infrastructure consisting of paving the existing roadways, removing sediment from roadside ditches and pond bottoms, and other required improvements to bring the overall Project to Preliminary Acceptance with the County. As part of the overall Project, upgrading Pond A is required with these improvements.

DESCRIPTION OF PROPERTY

The overall Project is located on approximately 209 Acres (EPC Parcel No. 1418002020). In existing conditions, the Site has been partially developed with a gravel road and single family homes. Existing vegetation on the Site consists of natural vegetation with scattered patches of native shrubs and trees. Currently, the site provides stormwater quality in detention ponds scattered throughout the site. The existing Pond A was constructed per the approved Construction Documents completed by WestWorks Engineering and approved by El Paso County and dated July 18, 2005. Since the time of construction, drainage standards have been modified by El Paso County. Pond A will be upgraded to meet the current County Standards and follow the Mile High Flood District guidance on extended detention basins. The area currently draining to Pond A is ±15.40 acres in size and is in the northeast portion of the Site. This Final Drainage Letter describes the upgrades with associated calculations found in the **Appendix**. The overall project site generally drains from northwest to southeast with slopes ranging from 1% to 10%. Runoff from the site outfalls into local tributaries that eventually outfalls into Pond Creek.

SOILS DATA

NRCS soil data for the Site is provided in the Appendix and the onsite soils are almost entirely USCS Hydrologic Soil Group B. Group B soils have moderate infiltration rates.

DRAINAGE DESIGN CRITERIA

PREVIOUS DRAINAGE STUDIES

Previous drainage studies include Final Drainage Report for Tanner Ranch Filing No. 1 prepared by Westworks Engineering. This drainage study is used as the basis for the drainage delineation and design for the Pond A improvements.

DEVELOPMENT DESIGN CRITERIA REFERENCE

The proposed storm facilities follow the El Paso County Drainage Criteria Manual (the “CRITERIA”), El Paso Engineering Criteria Manual (the “ECM”), and the Mile High Flood District Urban Storm Drainage Criteria Manual (the “MANUAL”). Site drainage is not significantly impacted by such constraints as utilities or existing development. Further detail regarding onsite drainage patterns is provided in the Proposed Drainage Conditions Section.

HYDROLOGIC CRITERIA

The 5-year and 100-year design storm events were used in determining rainfall and runoff for the proposed drainage calculations per section 6 of the CRITERIA. Table 6-2 of the CRITERIA is the source for rainfall data for the 5-year and 100-year design storm events. Design runoff was calculated using the Rational Method for developed conditions as established in the CRITERIA and MANUAL. Runoff coefficients for the proposed development were determined using Table 6-6 of the CRITERIA by calculating weighted impervious values for each specific site basin. Based upon this approach, the drainage design provided for the Site is conservative and in keeping with the zoning and historic drainage concept for the area.

HYDRAULIC CRITERIA

The proposed site will be designed in accordance with the CRITERIA and MANUAL. Floodplain identification was determined using FIRM panels by FEMA and information provided in the CRITERIA.

The full project disturbance was evaluated based on the proposed site improvements. The following discussion outlines the anticipated disturbance associated with Pond A1, A, B, C, and D and their associated modifications and calculations. Refer to **Appendix E** for the detailed calculations.

VARIANCES FROM CRITERIA

There are no proposed variances from the El Paso County Drainage Criteria.

EXISTING DRAINAGE CONDITIONS

The Site was divided into 4 sub-basins in the approved overall Final Drainage Report. For the purposes of examining Pond A, Sub-basin A is the only basin that will be examined. The approved report was written in 2005 and runoff coefficient values have been updated since then. Because of this, updated runoff calculations have been provided in summary below and in the **Appendix**. Overall delineation of the basins did not change from the approved Drainage Report.

Existing Sub-Basin Summary

Sub-Basin EX-A

Sub-Basin EX-A is 43.50 acres and consists of the northeastern portion of the Site. This sub-basin is undeveloped and consists of native grasses and trees. The runoff developed within this basin sheet flows overland from the northwest to southeast at slopes that range approximately 2-5%. Flows are currently captured by an existing 18" culvert that outflows into the property to the east. The property to the east consists of native grasses and trees. The direct runoff from sub-basin EX-A is 7.11 CFS for the 5-year event and 52.20 cfs for the 100-year event. No offsite improvements will be required. Pond A1 is existing and improvements will be made by the fire department, reference **Appendix E** for the hydraulic calculations to support these changes.

PROPOSED DRAINAGE CONDITIONS

The proposed Site has been divided into one (1) on-site sub-basin: A-2. Calculations of the proposed sub-basin were previously completed in the previously approved drainage report. These calculations have been updated to meet current standards in the Criteria. The divided sub-basin includes everything flowing to Pond A. The proposed updated hydrologic calculations are provided in the **Appendix**. The proposed drainage map from the previous drainage report is also included in the **Appendix**. No new hydrology is being completed since the maintenance activities such as modifying the orifice plates and cleaning out ditches and rip rap are based on the previously approved hydrology and hydraulics. In the proposed conditions, stormwater generally travels from the proposed road to the northeast and travels in a natural swale to Pond A. The water is then collected into the existing Pond A and is released at less than existing conditions to the neighboring property. Runoff calculations for sub-basin A-2 have been summarized for the updated pond below.

Proposed Sub-Basin Summary

Sub-Basin A-2

Sub-Basin A-2 is 15.40 acres and consists of the areas tributary to Pond A. This sub-basin consists of a portion of a proposed upgraded road, residential lots that are greater than 2.5 acres, and undeveloped landscape area. The runoff developed from this basin sheets flows through the site into a natural swale at 2-5% slopes. Flows are captured in Pond A and then released at less than historic rates to the adjacent property. The weighed imperviousness for the sub-basin is 8.50%. The developed direct runoff from sub-basin A-2 is 7.08 cfs for the 5-year event and 29.71 cfs for the 100-year event. The decrease in tributary area between EX-A and A-2 is due to the division of EX-A into three proposed sub-basins, A-1, A-2, and A-3 because of proposed roadway development and roadside swales. A-1 is tributary to DP-A1 (Pond A1), flows from A-2 are tributary to Pond A, and flows tributary to A-3 flow offsite.

FOUR-STEP PROCESS

Step 1: Employ Runoff Reduction Practices

Within the basin draining to the pond, there are three (3) 2.5-acre single-family lots. Per Section I.7.1B of Appendix I of the ECM, the single-family residences fall under the large lot exemption as the total impervious area is less than 10% of the area. A BESQCP permit will be required by the County to prevent erosion and mitigate any runoff due to those activities.

Pond A water-quality detention basin is proposed to be upgraded as a part of this project and will have a water quality capture volume designed to accommodate the total imperviousness from the proposed upgraded paved road. The total disturbance onsite includes all of Filing No. 1 and the proposed emergency access. All the disturbed area is captured through existing channels or infrastructure to one of the 5 ponds. Ponds B,C, and D will have modifications to the orifice plates to show compliance with the MS4 drain times, Pond A1 is being upgraded by the Tri-County Fire Department, and Pond A is being fully upgraded as part of Filing 1.

Step 2: Stabilize Drainageways

Generally, stormwater runoff from the site ultimately drains through existing tributaries into Pond Creek. There are no proposed drainageway improvements anticipated as a part of this project. The Site maintains 2-5% imperviousness under existing and proposed conditions. The existing gravel road will be upgraded as a part of this project and a proposed paved road will be added to serve future development of the residential lots.

Step 3: Provide Water Quality Capture Volume (WQCV)

Pond A was designed with a water quality capture volume to include the proposed paved road and associated imperviousness. However, the updated orifice plate design of Pond A accounts for the final tributary areas adjacent to Pond A and updated associated overall imperviousness. Large lots are exempt from the Water Quality Capture Volume as indicated in I.7.1.B.5.

Ponds B, C, and D orifice plates will need to be adjusted. The orifice data was input into the MHFD Detention spreadsheet to better analyze WQCV drain times. Pond A1 improvements will be by the Fire Department in a separate application.

Large Lot - Single Family Sites

A single-family residential lot, or agricultural zoned lands, greater than or equal to 2.5 acres in size per dwelling and having a total lot impervious area of less than 10 percent. A total lot imperviousness greater than 10 percent is allowed when a study specific to the watershed and/or MS4 shows that expected soil and vegetation conditions are suitable for infiltration/filtration of the WQCV for a typical site, and the permittee accepts such study as applicable within its MS4 boundaries. The maximum total lot impervious covered under this exclusion shall be 20 percent.

Step 4: Consider need for Industrial and Commercial BMPs

The proposed Project consists of residential lots with a Final Plat. There are no industrial and commercial uses or developments proposed with the project.

DRAINAGE FACILITY DESIGN

Overall, there are 5 existing ponds located on-site. As part of the Trinity Ranch Filing No. 1 development, Ponds A and A1 require full upgrades. Pond A1 upgrades will be by the Tri-County Fire Department and Pond A upgrades will be by the Owner. Pond B, C, and D will need modifications as part of the Filing No. 1 to their orifice plates to show compliance with MS4 drain times. Pond improvement descriptions can be found below, along with associated calculations found in the **Appendix**.

Pond A1

Pond A1 is located along the northern edge of Dinner Bell Drive with access from the ROW on the northern edge of subdivision. The Tri-County Fire Department is planning to build a new fire station on Lots 1 & 2 and will be responsible for the updates to the existing pond to the proposed site plan and to reflect EPC and MHFD standards.

The accumulated sediment is to be removed along the bottom contours of the pond down to the original 6220 and 6221 contours. The Pond will be reseeded and mulched to provide permanent stabilization following the sediment removal.

Pond A

A private full spectrum extended detention basin ("Pond A") is proposed to provide water quality for the proposed paved road upgrades, and to provide adequate capture volume for all tributary flows entering from offsite or being generated onsite. The required capture volume for water quality is 0.017 ac-ft. There is approximately 15.40 acres of area tributary to Pond A. This tributary area is delineated in the previously approved final drainage report proposed drainage map in the **Appendix**. The required 100-year detention volume for tributary area to Pond A is 0.604 ac-ft. The total volume provided for Pond A is 2.613 ac-ft. The proposed detention facility includes a trickle channel, a concrete cast-in-place outlet structure, and a 6" type VL (12" depth) riprap emergency spillway. The detention facility is designed to adequately manage stormwater flows as required by the County and State. Flows leaving the Pond do so at ~50% of the pre-existing condition. It is to be noted that there will be no increase in flows of the channel downstream of Pond A from existing to the proposed conditions, thus no modifications nor upgrades will be required. Design documents for the proposed detention facility are included in the **Appendix**.

Pond B

The orifice plate on the outlet structure for Pond B will need to be adjusted. The orifice data was input into the MHFD Detention spreadsheet to better analyze WQCV drain times. Row 1 will have the same centroid elevation and will revise 2-inch to 2-3/4" diameter hole. Row 2 will have the same centroid elevation and will revise 2-inch to 3" diameter holes. The Plate Height to be installed at 1.5' above the invert. The accumulated sediment is to be removed along the bottom contours of the pond down to the original 6182 contours. Pond will need to be reseeded and mulched to provide permanent stabilization following the sediment removal.

It is to be noted that Pond B accepts runoff from future Filing No. 2. It is assumed that the pond will be updated to reflect the current EPC and MHFD standards when the Filing No. 2 Final Drainage Report is completed for the future phase.

Pond C

The orifice data was inputted into the MHFD Detention spreadsheet to better analyze the WQCV drain times. The analysis with the MHFD Detention spreadsheet shows that the original design with 2" diameter holes provide the adequate drain time. The accumulated sediment is to be removed along the bottom contours of the pond down to the original 6220 and 6221 contours. The Pond will be reseeded and mulched to provide permanent stabilization following the sediment removal.

It is to be noted that Pond C accepts runoff from future Filing No. 3. It is assumed that the pond will be updated to reflect the current EPC and MHFD standards when the Filing No. 3 Final Drainage Report is completed for the future phase.

Pond D

The orifice plate on the outlet structure for Pond D will need to be adjusted. The orifice data was input into the MHFD Detention spreadsheet to better analyze WQCV drain times. Row 1 will have the same centroid elevation and will be revised from a 2-inch to 1-1/4" diameter hole. Row 2 will have the same centroid elevation and will be revised from a 2-inch to 3" diameter holes. The accumulated sediment is to be removed along the bottom contours of the pond down to the original 6190 contour. Pond will need to be reseeded and mulched to provide permanent stabilization following the sediment removal.

It is to be noted that Pond D accepts runoff from future Filing No. 3. It is assumed that the pond will be updated to reflect the current EPC and MHFD standards when the Filing No. 3 Final Drainage Report is completed for the future phase.

FLOODPLAIN STATEMENT

According to the National Flood Insurance Program, Flood Insurance Rate Map Panel 08041C0850G with an effective date of December 7th, 2018, the subject property is entirely within Zone X and is located outside of the 100-year and 500-year flood plains. This panel is included in the **Appendix**.

GRADING AND EROSION CONTROL

Grading and erosion control plans have been submitted concurrently with this Final Drainage Letter.

DRAINAGE FEES


There are no drainage basin fees required due to the fact that the plat for the Site has been finalized.

REFERENCES

1. El Paso County Drainage Criteria Manual, Vol. 1 and 2, October 1994.
2. El Paso County Engineering Criteria Manual, December 2004, Revised 2016
3. Mile High Flood District Drainage Criteria Manual (MHFDCM), Vol. 1, prepared by Wright-McLaughlin Engineers, June 2001, with latest revisions.
4. Flood Insurance Rate Map, El Paso County, Colorado and Incorporated Areas, Map Number 08041C0850G Effective Date December 7, 2018, prepared by the Federal Emergency Management Agency (FEMA).
5. “Custom Soil Resource Report for El Paso County Area, Colorado” prepared by USGS National Cooperative Soil Survey, September 9th, 2025.
6. “Final Drainage Report for Tanner Ranch Filing No. 1” prepared by WestWorks Engineering, July 18th, 2005.

APPENDIX

APPENDIX A – VICINITY MAP



VICINITY MAP
N.T.S.

APPENDIX B – FEMA FIRM PANEL

NOTES TO USERS

This map is for use in administering the National Flood Insurance Program. It does not necessarily identify all areas subject to flooding, particularly from local drainage sources of small size. The community map repository should be consulted for possible updated or additional flood hazard information.

To obtain more detailed information in areas where **Base Flood Elevations (BFEs)** and/or **Floodway Data** have been determined, users are encouraged to consult the Flood Profiles and Floodway Data and/or Summary of Stillwater Elevations tables contained within the Flood Insurance Study (FIS) report that accompanies this FIRM. Users should be aware that BFEs shown on the FIRM represent rounded whole-foot elevations. These BFEs are intended for flood insurance rating purposes only and should not be used as the sole source of flood elevation information. Accordingly, flood elevation data presented in the FIS report should be utilized in conjunction with the FIRM for purposes of construction and/or floodplain management.

Coastal Base Flood Elevations shown on this map apply only to landward of 0' North American Vertical Datum of 1988 (NAVD83). Users of this FIRM should be aware that coastal flood elevations are also provided in the Summary of Stillwater Elevations table in the Flood Insurance Study report for this jurisdiction. Elevations shown in the Summary of Stillwater Elevations table should be used for construction and/or floodplain management purposes when they are higher than the elevations shown on this FIRM.

Boundaries of the **floodways** were computed at cross sections and interpolated between cross sections. The floodways were based on hydraulic considerations with regard to requirements of the National Flood Insurance Program. Floodway widths and other pertinent floodway data are provided in the Flood Insurance Study report for this jurisdiction.

Certain areas not in Special Flood Hazard Areas may be protected by **flood control structures**. Refer to section 2.4 "Flood Protection Measures" of the Flood Insurance Study report for information on flood control structures for this jurisdiction.

The projection used in the preparation of this map was Universal Transverse Mercator (UTM) zone 13. The horizontal datum was NAD83. GRS80 adjusted differences in datum, spheroid, projection or UTM zones used in the production of FIRMs for adjacent jurisdictions may result in slight positional differences in map features across jurisdiction boundaries. These differences do not affect the accuracy of this FIRM.

Flood elevations on this map are referenced to the **North American Vertical Datum of 1988 (NAVD83)**. These flood elevations must be compared to structure and ground elevations referenced to the same datum for flood insurance rating purposes. For information regarding conversion between the National Geodetic Vertical Datum of 1929 and the North American Vertical Datum of 1988, visit the National Geodetic Survey website at <http://www.ngs.noaa.gov/> or contact the National Geodetic Survey at the following address:

NGS Information Services
NOAA, NGS12
National Geodetic Survey
SSNIC-3, BR022
1315 East-West Highway
Silver Spring, MD 20910-3282

To obtain current elevation, description, and/or location information for **bench marks** shown on this map, please contact the Information Services Branch of the National Geodetic Survey at (801) 713-3242 or visit its website at <http://www.ngs.noaa.gov/>.

Base Map information shown on this FIRM was provided in digital format by El Paso County, Colorado Springs Utilities, and Anderson Consulting Engineers, Inc. These data are current as of 2008.

This map reflects more detailed and up-to-date stream channel configurations and floodplain delineations than those shown on the previous FIRM for this jurisdiction. The floodplains and floodways that were transferred from the previous FIRM may have been adjusted to conform to these new stream channel configurations. As a result, the Flood Profiles and Floodway Data tables in the Flood Insurance Study Report (which contains authoritative hydraulic data) may reflect stream channel distances that differ from what is shown on this map. The profile baselines depicted on this map represent the hydraulic modeling baselines that match the flood profiles and Floodway Data Tables (if applicable, in the FIS report). As a result, the profile baselines may deviate significantly from the new base map channel representation and may appear outside of the floodplain.

Corporate limits shown on this map are based on the best data available at the time of publication. Because changes due to annexations or de-annexations may have occurred after this map was published, map users should contact appropriate community officials to verify current corporate limit locations.

Please refer to the separately printed **Map Index** for an overview map of the county showing the layout of map panels, community map repository addresses, and a Listing of Communities table containing National Flood Insurance Program dates for each community as well as a listing of the panels on which each community is located.

Contact **FEMA Map Service Center (MSC)** via the FEMA Map Information eXchange (FMIX) 1-877-336-2627 for information on available products associated with the FIRM. Available products may include previously issued Letters of Map Change, a Flood Insurance Study Report, and/or digital versions of this map. The MSC may also be reached by Fax at 1-800-358-9620 and its website at <http://www.msc.fema.gov/>.

If you have questions about this map or questions concerning the National Flood Insurance Program in general, please call 1-877-FEMA-MAP (1-877-336-2627) or visit the FEMA website at <http://www.fema.gov/business/firm>.

El Paso County Vertical Datum Offset Table

Flooding Source Vertical Datum Offset (ft.)

REFER TO SECTION 3.3 OF THE EL PASO COUNTY FLOOD INSURANCE STUDY FOR STREAM BY STREAM VERTICAL DATUM CONVERSION INFORMATION

Panel Location Map

Panel 0802

Panel 0803

Panel 0804

Panel 0805

Panel 0806

Panel 0807

Panel 0808

Panel 0809

Panel 0810

Panel 0811

Panel 0812

Panel 0813

Panel 0814

Panel 0815

Panel 0816

Panel 0817

Panel 0818

Panel 0819

Panel 0820

Panel 0821

Panel 0822

Panel 0823

Panel 0824

Panel 0825

Panel 0826

Panel 0827

Panel 0828

Panel 0829

Panel 0830

Panel 0831

Panel 0832

Panel 0833

Panel 0834

Panel 0835

Panel 0836

Panel 0837

Panel 0838

Panel 0839

Panel 0840

Panel 0841

Panel 0842

Panel 0843

Panel 0844

Panel 0845

Panel 0846

Panel 0847

Panel 0848

Panel 0849

Panel 0850

Panel 0851

Panel 0852

Panel 0853

Panel 0854

Panel 0855

Panel 0856

Panel 0857

Panel 0858

Panel 0859

Panel 0860

Panel 0861

Panel 0862

Panel 0863

Panel 0864

Panel 0865

Panel 0866

Panel 0867

Panel 0868

Panel 0869

Panel 0870

Panel 0871

Panel 0872

Panel 0873

Panel 0874

Panel 0875

Panel 0876

Panel 0877

Panel 0878

Panel 0879

Panel 0880

Panel 0881

Panel 0882

Panel 0883

Panel 0884

Panel 0885

Panel 0886

Panel 0887

Panel 0888

Panel 0889

Panel 0890

Panel 0891

Panel 0892

Panel 0893

Panel 0894

Panel 0895

Panel 0896

Panel 0897

Panel 0898

Panel 0899

Panel 0900

Panel 0901

Panel 0902

Panel 0903

Panel 0904

Panel 0905

Panel 0906

Panel 0907

Panel 0908

Panel 0909

Panel 0910

Panel 0911

Panel 0912

Panel 0913

Panel 0914

Panel 0915

Panel 0916

Panel 0917

Panel 0918

Panel 0919

Panel 0920

Panel 0921

Panel 0922

Panel 0923

Panel 0924

Panel 0925

Panel 0926

Panel 0927

Panel 0928

Panel 0929

Panel 0930

Panel 0931

Panel 0932

Panel 0933

Panel 0934

Panel 0935

Panel 0936

Panel 0937

Panel 0938

Panel 0939

Panel 0940

Panel 0941

Panel 0942

Panel 0943

Panel 0944

Panel 0945

Panel 0946

Panel 0947

Panel 0948

Panel 0949

Panel 0950

Panel 0951

Panel 0952

Panel 0953

Panel 0954

Panel 0955

Panel 0956

Panel 0957

Panel 0958

Panel 0959

Panel 0960

Panel 0961

Panel 0962

Panel 0963

Panel 0964

Panel 0965

Panel 0966

Panel 0967

Panel 0968

Panel 0969

Panel 0970

Panel 0971

Panel 0972

Panel 0973

Panel 0974

Panel 0975

Panel 0976

Panel 0977

Panel 0978

Panel 0979

Panel 0980

Panel 0981

Panel 0982

Panel 0983

Panel 0984

Panel 0985

Panel 0986

Panel 0987

Panel 0988

Panel 0989

Panel 0990

Panel 0991

Panel 0992

Panel 0993

Panel 0994

Panel 0995

Panel 0996

Panel 0997

Panel 0998

Panel 0999

Panel 1000

Panel 1001

Panel 1002

Panel 1003

Panel 1004

Panel 1005

Panel 1006

Panel 1007

Panel 1008

Panel 1009

Panel 1010

Panel 1011

Panel 1012

Panel 1013

Panel 1014

Panel 1015

Panel 1016

Panel 1017

Panel 1018

Panel 1019

Panel 1020

Panel 1021

Panel 1022

Panel 1023

Panel 1024

Panel 1025

Panel 1026

Panel 1027

Panel 1028

Panel 1029

Panel 1030

Panel 1031

Panel 1032

Panel 1033

Panel 1034

Panel 1035

Panel 1036

Panel

APPENDIX C – NRCS SOIL SURVEY




United States
Department of
Agriculture

NRCS

Natural
Resources
Conservation
Service

A product of the National
Cooperative Soil Survey,
a joint effort of the United
States Department of
Agriculture and other
Federal agencies, State
agencies including the
Agricultural Experiment
Stations, and local
participants

Custom Soil Resource Report for **El Paso County Area, Colorado**



Preface

Soil surveys contain information that affects land use planning in survey areas. They highlight soil limitations that affect various land uses and provide information about the properties of the soils in the survey areas. Soil surveys are designed for many different users, including farmers, ranchers, foresters, agronomists, urban planners, community officials, engineers, developers, builders, and home buyers. Also, conservationists, teachers, students, and specialists in recreation, waste disposal, and pollution control can use the surveys to help them understand, protect, or enhance the environment.

Various land use regulations of Federal, State, and local governments may impose special restrictions on land use or land treatment. Soil surveys identify soil properties that are used in making various land use or land treatment decisions. The information is intended to help the land users identify and reduce the effects of soil limitations on various land uses. The landowner or user is responsible for identifying and complying with existing laws and regulations.

Although soil survey information can be used for general farm, local, and wider area planning, onsite investigation is needed to supplement this information in some cases. Examples include soil quality assessments (<http://www.nrcs.usda.gov/wps/portal/nrcs/main/soils/health/>) and certain conservation and engineering applications. For more detailed information, contact your local USDA Service Center (<https://offices.sc.egov.usda.gov/locator/app?agency=nrcs>) or your NRCS State Soil Scientist (http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/contactus/?cid=nrcs142p2_053951).

Great differences in soil properties can occur within short distances. Some soils are seasonally wet or subject to flooding. Some are too unstable to be used as a foundation for buildings or roads. Clayey or wet soils are poorly suited to use as septic tank absorption fields. A high water table makes a soil poorly suited to basements or underground installations.

The National Cooperative Soil Survey is a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local agencies. The Natural Resources Conservation Service (NRCS) has leadership for the Federal part of the National Cooperative Soil Survey.

Information about soils is updated periodically. Updated information is available through the NRCS Web Soil Survey, the site for official soil survey information.

The U.S. Department of Agriculture (USDA) prohibits discrimination in all its programs and activities on the basis of race, color, national origin, age, disability, and where applicable, sex, marital status, familial status, parental status, religion, sexual orientation, genetic information, political beliefs, reprisal, or because all or a part of an individual's income is derived from any public assistance program. (Not all prohibited bases apply to all programs.) Persons with disabilities who require

alternative means for communication of program information (Braille, large print, audiotape, etc.) should contact USDA's TARGET Center at (202) 720-2600 (voice and TDD). To file a complaint of discrimination, write to USDA, Director, Office of Civil Rights, 1400 Independence Avenue, S.W., Washington, D.C. 20250-9410 or call (800) 795-3272 (voice) or (202) 720-6382 (TDD). USDA is an equal opportunity provider and employer.

Contents

Preface	2
How Soil Surveys Are Made	5
Soil Map	8
Soil Map.....	9
Legend.....	10
Map Unit Legend.....	11
Map Unit Descriptions.....	11
El Paso County Area, Colorado.....	13
2—Ascalon sandy loam, 1 to 3 percent slopes.....	13
3—Ascalon sandy loam, 3 to 9 percent slopes.....	14
6—Bijou sandy loam, 0 to 3 percent slopes.....	15
11—Bresser sandy loam, cool, 0 to 3 percent slopes.....	17
Soil Information for All Uses	19
Soil Properties and Qualities.....	19
Soil Qualities and Features.....	19
Hydrologic Soil Group.....	19
References	24

How Soil Surveys Are Made

Soil surveys are made to provide information about the soils and miscellaneous areas in a specific area. They include a description of the soils and miscellaneous areas and their location on the landscape and tables that show soil properties and limitations affecting various uses. Soil scientists observed the steepness, length, and shape of the slopes; the general pattern of drainage; the kinds of crops and native plants; and the kinds of bedrock. They observed and described many soil profiles. A soil profile is the sequence of natural layers, or horizons, in a soil. The profile extends from the surface down into the unconsolidated material in which the soil formed or from the surface down to bedrock. The unconsolidated material is devoid of roots and other living organisms and has not been changed by other biological activity.

Currently, soils are mapped according to the boundaries of major land resource areas (MLRAs). MLRAs are geographically associated land resource units that share common characteristics related to physiography, geology, climate, water resources, soils, biological resources, and land uses (USDA, 2006). Soil survey areas typically consist of parts of one or more MLRA.

The soils and miscellaneous areas in a survey area occur in an orderly pattern that is related to the geology, landforms, relief, climate, and natural vegetation of the area. Each kind of soil and miscellaneous area is associated with a particular kind of landform or with a segment of the landform. By observing the soils and miscellaneous areas in the survey area and relating their position to specific segments of the landform, a soil scientist develops a concept, or model, of how they were formed. Thus, during mapping, this model enables the soil scientist to predict with a considerable degree of accuracy the kind of soil or miscellaneous area at a specific location on the landscape.

Commonly, individual soils on the landscape merge into one another as their characteristics gradually change. To construct an accurate soil map, however, soil scientists must determine the boundaries between the soils. They can observe only a limited number of soil profiles. Nevertheless, these observations, supplemented by an understanding of the soil-vegetation-landscape relationship, are sufficient to verify predictions of the kinds of soil in an area and to determine the boundaries.

Soil scientists recorded the characteristics of the soil profiles that they studied. They noted soil color, texture, size and shape of soil aggregates, kind and amount of rock fragments, distribution of plant roots, reaction, and other features that enable them to identify soils. After describing the soils in the survey area and determining their properties, the soil scientists assigned the soils to taxonomic classes (units). Taxonomic classes are concepts. Each taxonomic class has a set of soil characteristics with precisely defined limits. The classes are used as a basis for comparison to classify soils systematically. Soil taxonomy, the system of taxonomic classification used in the United States, is based mainly on the kind and character of soil properties and the arrangement of horizons within the profile. After the soil

scientists classified and named the soils in the survey area, they compared the individual soils with similar soils in the same taxonomic class in other areas so that they could confirm data and assemble additional data based on experience and research.

The objective of soil mapping is not to delineate pure map unit components; the objective is to separate the landscape into landforms or landform segments that have similar use and management requirements. Each map unit is defined by a unique combination of soil components and/or miscellaneous areas in predictable proportions. Some components may be highly contrasting to the other components of the map unit. The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The delineation of such landforms and landform segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, onsite investigation is needed to define and locate the soils and miscellaneous areas.

Soil scientists make many field observations in the process of producing a soil map. The frequency of observation is dependent upon several factors, including scale of mapping, intensity of mapping, design of map units, complexity of the landscape, and experience of the soil scientist. Observations are made to test and refine the soil-landscape model and predictions and to verify the classification of the soils at specific locations. Once the soil-landscape model is refined, a significantly smaller number of measurements of individual soil properties are made and recorded. These measurements may include field measurements, such as those for color, depth to bedrock, and texture, and laboratory measurements, such as those for content of sand, silt, clay, salt, and other components. Properties of each soil typically vary from one point to another across the landscape.

Observations for map unit components are aggregated to develop ranges of characteristics for the components. The aggregated values are presented. Direct measurements do not exist for every property presented for every map unit component. Values for some properties are estimated from combinations of other properties.

While a soil survey is in progress, samples of some of the soils in the area generally are collected for laboratory analyses and for engineering tests. Soil scientists interpret the data from these analyses and tests as well as the field-observed characteristics and the soil properties to determine the expected behavior of the soils under different uses. Interpretations for all of the soils are field tested through observation of the soils in different uses and under different levels of management. Some interpretations are modified to fit local conditions, and some new interpretations are developed to meet local needs. Data are assembled from other sources, such as research information, production records, and field experience of specialists. For example, data on crop yields under defined levels of management are assembled from farm records and from field or plot experiments on the same kinds of soil.

Predictions about soil behavior are based not only on soil properties but also on such variables as climate and biological activity. Soil conditions are predictable over long periods of time, but they are not predictable from year to year. For example, soil scientists can predict with a fairly high degree of accuracy that a given soil will have a high water table within certain depths in most years, but they cannot predict that a high water table will always be at a specific level in the soil on a specific date.

After soil scientists located and identified the significant natural bodies of soil in the survey area, they drew the boundaries of these bodies on aerial photographs and


Custom Soil Resource Report

identified each as a specific map unit. Aerial photographs show trees, buildings, fields, roads, and rivers, all of which help in locating boundaries accurately.

Soil Map

The soil map section includes the soil map for the defined area of interest, a list of soil map units on the map and extent of each map unit, and cartographic symbols displayed on the map. Also presented are various metadata about data used to produce the map, and a description of each soil map unit.

Custom Soil Resource Report Soil Map



Custom Soil Resource Report

MAP LEGEND

Area of Interest (AOI)

 Area of Interest (AOI)

Soils

 Soil Map Unit Polygons

 Soil Map Unit Lines

 Soil Map Unit Points

Special Point Features

 Blowout

 Borrow Pit

 Clay Spot

 Closed Depression

 Gravel Pit

 Gravelly Spot

 Landfill

 Lava Flow

 Marsh or swamp

 Mine or Quarry

 Miscellaneous Water

 Perennial Water

 Rock Outcrop

 Saline Spot

 Sandy Spot

 Severely Eroded Spot

 Sinkhole

 Slide or Slip

 Sodic Spot

 Spoil Area

 Stony Spot

 Very Stony Spot

 Wet Spot

 Other

 Special Line Features

Water Features

 Streams and Canals

Transportation

 Rails

 Interstate Highways

 US Routes

 Major Roads

 Local Roads

Background

 Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service

Web Soil Survey URL:

Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: El Paso County Area, Colorado

Survey Area Data: Version 22, Sep 3, 2024

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Sep 11, 2018—Oct 20, 2018

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
2	Ascalon sandy loam, 1 to 3 percent slopes	374.9	60.2%
3	Ascalon sandy loam, 3 to 9 percent slopes	223.6	35.9%
6	Bijou sandy loam, 0 to 3 percent slopes	4.9	0.8%
11	Bresser sandy loam, cool, 0 to 3 percent slopes	19.4	3.1%
Totals for Area of Interest		622.8	100.0%

Map Unit Descriptions

The map units delineated on the detailed soil maps in a soil survey represent the soils or miscellaneous areas in the survey area. The map unit descriptions, along with the maps, can be used to determine the composition and properties of a unit.

A map unit delineation on a soil map represents an area dominated by one or more major kinds of soil or miscellaneous areas. A map unit is identified and named according to the taxonomic classification of the dominant soils. Within a taxonomic class there are precisely defined limits for the properties of the soils. On the landscape, however, the soils are natural phenomena, and they have the characteristic variability of all natural phenomena. Thus, the range of some observed properties may extend beyond the limits defined for a taxonomic class. Areas of soils of a single taxonomic class rarely, if ever, can be mapped without including areas of other taxonomic classes. Consequently, every map unit is made up of the soils or miscellaneous areas for which it is named and some minor components that belong to taxonomic classes other than those of the major soils.

Most minor soils have properties similar to those of the dominant soil or soils in the map unit, and thus they do not affect use and management. These are called noncontrasting, or similar, components. They may or may not be mentioned in a particular map unit description. Other minor components, however, have properties and behavioral characteristics divergent enough to affect use or to require different management. These are called contrasting, or dissimilar, components. They generally are in small areas and could not be mapped separately because of the scale used. Some small areas of strongly contrasting soils or miscellaneous areas are identified by a special symbol on the maps. If included in the database for a given area, the contrasting minor components are identified in the map unit descriptions along with some characteristics of each. A few areas of minor components may not have been observed, and consequently they are not mentioned in the descriptions, especially where the pattern was so complex that it was impractical to make enough observations to identify all the soils and miscellaneous areas on the landscape.

Custom Soil Resource Report

The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The objective of mapping is not to delineate pure taxonomic classes but rather to separate the landscape into landforms or landform segments that have similar use and management requirements. The delineation of such segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, however, onsite investigation is needed to define and locate the soils and miscellaneous areas.

An identifying symbol precedes the map unit name in the map unit descriptions. Each description includes general facts about the unit and gives important soil properties and qualities.

Soils that have profiles that are almost alike make up a *soil series*. Except for differences in texture of the surface layer, all the soils of a series have major horizons that are similar in composition, thickness, and arrangement.

Soils of one series can differ in texture of the surface layer, slope, stoniness, salinity, degree of erosion, and other characteristics that affect their use. On the basis of such differences, a soil series is divided into *soil phases*. Most of the areas shown on the detailed soil maps are phases of soil series. The name of a soil phase commonly indicates a feature that affects use or management. For example, Alpha silt loam, 0 to 2 percent slopes, is a phase of the Alpha series.

Some map units are made up of two or more major soils or miscellaneous areas. These map units are complexes, associations, or undifferentiated groups.

A *complex* consists of two or more soils or miscellaneous areas in such an intricate pattern or in such small areas that they cannot be shown separately on the maps. The pattern and proportion of the soils or miscellaneous areas are somewhat similar in all areas. Alpha-Beta complex, 0 to 6 percent slopes, is an example.

An *association* is made up of two or more geographically associated soils or miscellaneous areas that are shown as one unit on the maps. Because of present or anticipated uses of the map units in the survey area, it was not considered practical or necessary to map the soils or miscellaneous areas separately. The pattern and relative proportion of the soils or miscellaneous areas are somewhat similar. Alpha-Beta association, 0 to 2 percent slopes, is an example.

An *undifferentiated group* is made up of two or more soils or miscellaneous areas that could be mapped individually but are mapped as one unit because similar interpretations can be made for use and management. The pattern and proportion of the soils or miscellaneous areas in a mapped area are not uniform. An area can be made up of only one of the major soils or miscellaneous areas, or it can be made up of all of them. Alpha and Beta soils, 0 to 2 percent slopes, is an example.

Some surveys include *miscellaneous areas*. Such areas have little or no soil material and support little or no vegetation. Rock outcrop is an example.

El Paso County Area, Colorado

2—Ascalon sandy loam, 1 to 3 percent slopes

Map Unit Setting

National map unit symbol: 367q
Elevation: 5,500 to 6,500 feet
Mean annual precipitation: 14 to 16 inches
Mean annual air temperature: 47 to 50 degrees F
Frost-free period: 130 to 150 days
Farmland classification: Prime farmland if irrigated

Map Unit Composition

Ascalon and similar soils: 98 percent
Minor components: 2 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Ascalon

Setting

Landform: Flats
Landform position (three-dimensional): Talf
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Mixed alluvium and/or eolian deposits

Typical profile

A - 0 to 8 inches: sandy loam
Bt - 8 to 21 inches: sandy clay loam
BC - 21 to 27 inches: sandy loam
Ck1 - 27 to 48 inches: sandy loam
Ck2 - 48 to 60 inches: loamy sand

Properties and qualities

Slope: 1 to 3 percent
Depth to restrictive feature: More than 80 inches
Drainage class: Well drained
Runoff class: Low
Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high
(0.60 to 2.00 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate, maximum content: 10 percent
Maximum salinity: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)
Available water supply, 0 to 60 inches: Moderate (about 7.1 inches)

Interpretive groups

Land capability classification (irrigated): 3e
Land capability classification (nonirrigated): 4e
Hydrologic Soil Group: B
Ecological site: R069XY026CO - Sandy Plains
Other vegetative classification: SANDY PLAINS (069BY026CO)
Hydric soil rating: No

Minor Components

Other soils

Percent of map unit: 1 percent

Hydric soil rating: No

Pleasant

Percent of map unit: 1 percent

Landform: Depressions

Hydric soil rating: Yes

3—Ascalon sandy loam, 3 to 9 percent slopes

Map Unit Setting

National map unit symbol: 2tlny

Elevation: 3,870 to 5,960 feet

Mean annual precipitation: 13 to 18 inches

Mean annual air temperature: 46 to 54 degrees F

Frost-free period: 95 to 155 days

Farmland classification: Not prime farmland

Map Unit Composition

Ascalon and similar soils: 85 percent

Minor components: 15 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Ascalon

Setting

Landform: Interfluves

Landform position (two-dimensional): Backslope

Landform position (three-dimensional): Side slope

Down-slope shape: Linear

Across-slope shape: Linear

Parent material: Wind-reworked alluvium and/or calcareous sandy eolian deposits

Typical profile

Ap - 0 to 6 inches: sandy loam

Bt1 - 6 to 12 inches: sandy clay loam

Bt2 - 12 to 19 inches: sandy clay loam

Bk1 - 19 to 35 inches: fine sandy loam

Bk2 - 35 to 80 inches: fine sandy loam

Properties and qualities

Slope: 3 to 9 percent

Depth to restrictive feature: More than 80 inches

Drainage class: Well drained

Runoff class: Medium

Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high
(0.60 to 5.98 in/hr)

Custom Soil Resource Report

Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate, maximum content: 10 percent
Maximum salinity: Nonsaline (0.1 to 1.9 mmhos/cm)
Sodium adsorption ratio, maximum: 1.0
Available water supply, 0 to 60 inches: Moderate (about 7.1 inches)

Interpretive groups

Land capability classification (irrigated): 6e
Land capability classification (nonirrigated): 6e
Hydrologic Soil Group: B
Ecological site: R067BY024CO - Sandy Plains
Hydric soil rating: No

Minor Components

Olnest

Percent of map unit: 10 percent
Landform: Interfluves
Landform position (two-dimensional): Backslope
Landform position (three-dimensional): Side slope
Down-slope shape: Linear
Across-slope shape: Linear
Ecological site: R067BY024CO - Sandy Plains
Hydric soil rating: No

Vona

Percent of map unit: 5 percent
Landform: Interfluves
Landform position (two-dimensional): Backslope
Landform position (three-dimensional): Side slope
Down-slope shape: Linear
Across-slope shape: Linear
Ecological site: R067BY024CO - Sandy Plains
Hydric soil rating: No

6—Bijou sandy loam, 0 to 3 percent slopes

Map Unit Setting

National map unit symbol: 2tqxr
Elevation: 5,700 to 6,200 feet
Mean annual precipitation: 14 to 16 inches
Mean annual air temperature: 50 to 54 degrees F
Frost-free period: 130 to 170 days
Farmland classification: Prime farmland if irrigated and the product of I (soil erodibility) x C (climate factor) does not exceed 60

Map Unit Composition

Bijou and similar soils: 85 percent

Custom Soil Resource Report

Minor components: 15 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Bijou

Setting

Landform: Sand sheets

Landform position (two-dimensional): Summit

Landform position (three-dimensional): Interfluve

Down-slope shape: Linear

Across-slope shape: Linear

Parent material: Eolian sands

Typical profile

A - 0 to 4 inches: sandy loam

Bt1 - 4 to 8 inches: sandy loam

Bt2 - 8 to 21 inches: sandy loam

Bw - 21 to 28 inches: sandy loam

C - 28 to 79 inches: loamy coarse sand

Properties and qualities

Slope: 0 to 3 percent

Depth to restrictive feature: More than 80 inches

Drainage class: Somewhat excessively drained

Capacity of the most limiting layer to transmit water (Ksat): High (2.00 to 6.00 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Maximum salinity: Nonsaline (0.1 to 0.2 mmhos/cm)

Available water supply, 0 to 60 inches: Low (about 5.0 inches)

Interpretive groups

Land capability classification (irrigated): 3e

Land capability classification (nonirrigated): 4c

Hydrologic Soil Group: A

Ecological site: R067BY024CO - Sandy Plains

Hydric soil rating: No

Minor Components

Valent

Percent of map unit: 10 percent

Landform: Sand sheets

Landform position (two-dimensional): Backslope

Landform position (three-dimensional): Side slope

Down-slope shape: Linear

Across-slope shape: Linear

Ecological site: R067BY015CO - Deep Sand

Hydric soil rating: No

Olnest

Percent of map unit: 5 percent

Landform: Swales

Down-slope shape: Linear

Across-slope shape: Concave

Ecological site: R067BY024CO - Sandy Plains

Hydric soil rating: No

11—Bresser sandy loam, cool, 0 to 3 percent slopes

Map Unit Setting

National map unit symbol: 2tlph

Elevation: 5,850 to 6,880 feet

Mean annual precipitation: 15 to 19 inches

Mean annual air temperature: 48 to 52 degrees F

Frost-free period: 100 to 130 days

Farmland classification: Prime farmland if irrigated and the product of I (soil erodibility) x C (climate factor) does not exceed 60

Map Unit Composition

Bresser, cool, and similar soils: 85 percent

Minor components: 15 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Bresser, Cool

Setting

Landform: Interfluves

Landform position (two-dimensional): Summit

Landform position (three-dimensional): Interfluve

Down-slope shape: Linear

Across-slope shape: Convex

Parent material: Tertiary aged alluvium derived from arkose

Typical profile

Ap - 0 to 5 inches: sandy loam

Bt1 - 5 to 8 inches: sandy loam

Bt2 - 8 to 27 inches: sandy clay loam

Bt3 - 27 to 36 inches: sandy loam

C - 36 to 80 inches: loamy coarse sand

Properties and qualities

Slope: 0 to 3 percent

Depth to restrictive feature: More than 80 inches

Drainage class: Well drained

Runoff class: Low

Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high
(0.60 to 6.00 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Calcium carbonate, maximum content: 5 percent

Maximum salinity: Nonsaline to very slightly saline (0.1 to 2.0 mmhos/cm)

Available water supply, 0 to 60 inches: Low (about 5.4 inches)

Interpretive groups

Land capability classification (irrigated): 3e

Custom Soil Resource Report

Land capability classification (nonirrigated): 4c
Hydrologic Soil Group: B
Ecological site: R049XB210CO - Sandy Foothill
Hydric soil rating: No

Minor Components

Truckton

Percent of map unit: 10 percent
Landform: Interfluves
Landform position (two-dimensional): Summit
Landform position (three-dimensional): Interfluve
Down-slope shape: Linear
Across-slope shape: Linear
Ecological site: R049XB210CO - Sandy Foothill
Hydric soil rating: No

Yoder

Percent of map unit: 5 percent
Landform: Alluvial fans
Down-slope shape: Linear
Across-slope shape: Linear
Ecological site: R049XY214CO - Gravelly Foothill
Hydric soil rating: No

Soil Information for All Uses

Soil Properties and Qualities

The Soil Properties and Qualities section includes various soil properties and qualities displayed as thematic maps with a summary table for the soil map units in the selected area of interest. A single value or rating for each map unit is generated by aggregating the interpretive ratings of individual map unit components. This aggregation process is defined for each property or quality.

Soil Qualities and Features

Soil qualities are behavior and performance attributes that are not directly measured, but are inferred from observations of dynamic conditions and from soil properties. Example soil qualities include natural drainage, and frost action. Soil features are attributes that are not directly part of the soil. Example soil features include slope and depth to restrictive layer. These features can greatly impact the use and management of the soil.

Hydrologic Soil Group

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.


Custom Soil Resource Report

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

Custom Soil Resource Report Map—Hydrologic Soil Group



Custom Soil Resource Report

MAP LEGEND

Area of Interest (AOI)

 Area of Interest (AOI)

Soils

Soil Rating Polygons

 A
 A/D
 B
 B/D
 C
 C/D
 D
 Not rated or not available

Soil Rating Lines

 A
 A/D
 B
 B/D
 C
 C/D
 D
 Not rated or not available

Soil Rating Points

 A
 A/D
 B
 B/D

 C
 C/D
 D
 Not rated or not available

Water Features

 Streams and Canals

Transportation

 Rails
 Interstate Highways
 US Routes
 Major Roads
 Local Roads

Background

 Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
Web Soil Survey URL:
Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: El Paso County Area, Colorado
Survey Area Data: Version 22, Sep 3, 2024

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Sep 11, 2018—Oct 20, 2018

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Table—Hydrologic Soil Group

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
2	Ascalon sandy loam, 1 to 3 percent slopes	B	374.9	60.2%
3	Ascalon sandy loam, 3 to 9 percent slopes	B	223.6	35.9%
6	Bijou sandy loam, 0 to 3 percent slopes	A	4.9	0.8%
11	Bresser sandy loam, cool, 0 to 3 percent slopes	B	19.4	3.1%
Totals for Area of Interest			622.8	100.0%

Rating Options—Hydrologic Soil Group

Aggregation Method: Dominant Condition

Component Percent Cutoff: None Specified

Tie-break Rule: Higher

References

- American Association of State Highway and Transportation Officials (AASHTO). 2004. Standard specifications for transportation materials and methods of sampling and testing. 24th edition.
- American Society for Testing and Materials (ASTM). 2005. Standard classification of soils for engineering purposes. ASTM Standard D2487-00.
- Cowardin, L.M., V. Carter, F.C. Golet, and E.T. LaRoe. 1979. Classification of wetlands and deep-water habitats of the United States. U.S. Fish and Wildlife Service FWS/OBS-79/31.
- Federal Register. July 13, 1994. Changes in hydric soils of the United States.
- Federal Register. September 18, 2002. Hydric soils of the United States.
- Hurt, G.W., and L.M. Vasilas, editors. Version 6.0, 2006. Field indicators of hydric soils in the United States.
- National Research Council. 1995. Wetlands: Characteristics and boundaries.
- Soil Survey Division Staff. 1993. Soil survey manual. Soil Conservation Service. U.S. Department of Agriculture Handbook 18. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_054262
- Soil Survey Staff. 1999. Soil taxonomy: A basic system of soil classification for making and interpreting soil surveys. 2nd edition. Natural Resources Conservation Service, U.S. Department of Agriculture Handbook 436. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053577
- Soil Survey Staff. 2010. Keys to soil taxonomy. 11th edition. U.S. Department of Agriculture, Natural Resources Conservation Service. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053580
- Tiner, R.W., Jr. 1985. Wetlands of Delaware. U.S. Fish and Wildlife Service and Delaware Department of Natural Resources and Environmental Control, Wetlands Section.
- United States Army Corps of Engineers, Environmental Laboratory. 1987. Corps of Engineers wetlands delineation manual. Waterways Experiment Station Technical Report Y-87-1.
- United States Department of Agriculture, Natural Resources Conservation Service. National forestry manual. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/home/?cid=nrcs142p2_053374
- United States Department of Agriculture, Natural Resources Conservation Service. National range and pasture handbook. <http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/landuse/rangepasture/?cid=stelpdb1043084>

Custom Soil Resource Report

United States Department of Agriculture, Natural Resources Conservation Service. National soil survey handbook, title 430-VI. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/scientists/?cid=nrcs142p2_054242

United States Department of Agriculture, Natural Resources Conservation Service. 2006. Land resource regions and major land resource areas of the United States, the Caribbean, and the Pacific Basin. U.S. Department of Agriculture Handbook 296. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053624

United States Department of Agriculture, Soil Conservation Service. 1961. Land capability classification. U.S. Department of Agriculture Handbook 210. http://www.nrcs.usda.gov/Internet/FSE_DOCUMENTS/nrcs142p2_052290.pdf

APPENDIX D – HYDROLOGIC CALCULATIONS



NOAA Atlas 14, Volume 8, Version 2
Location name: Yoder, Colorado, USA*
Latitude: 38.8322°, Longitude: -104.2663°
Elevation: m/ft**
 * source: ESRI Maps
 ** source: USGS



POINT PRECIPITATION FREQUENCY ESTIMATES

Sanja Perica, Deborah Martin, Sandra Pavlovic, Ishani Roy, Michael St. Laurent, Carl Trypaluk, Dale Unruh, Michael Yekta, Geoffrey Bonnin

NOAA, National Weather Service, Silver Spring, Maryland

[PF tabular](#) | [PF graphical](#) | [Maps & aerals](#)

PF tabular

PDS-based point precipitation frequency estimates with 90% confidence intervals (in inches) ¹										
Duration	Average recurrence interval (years)									
	1	2	5	10	25	50	100	200	500	1000
5-min	0.247 (0.196-0.315)	0.301 (0.239-0.385)	0.397 (0.313-0.508)	0.483 (0.379-0.620)	0.610 (0.468-0.817)	0.715 (0.535-0.967)	0.827 (0.598-1.14)	0.947 (0.658-1.34)	1.12 (0.747-1.62)	1.25 (0.814-1.82)
10-min	0.362 (0.287-0.461)	0.441 (0.350-0.563)	0.581 (0.459-0.744)	0.707 (0.555-0.907)	0.893 (0.685-1.20)	1.05 (0.783-1.42)	1.21 (0.876-1.67)	1.39 (0.964-1.96)	1.64 (1.09-2.36)	1.83 (1.19-2.67)
15-min	0.441 (0.350-0.563)	0.538 (0.426-0.687)	0.709 (0.560-0.907)	0.862 (0.677-1.11)	1.09 (0.835-1.46)	1.28 (0.955-1.73)	1.48 (1.07-2.04)	1.69 (1.18-2.39)	1.99 (1.33-2.88)	2.24 (1.45-3.26)
30-min	0.665 (0.527-0.848)	0.808 (0.640-1.03)	1.06 (0.837-1.36)	1.29 (1.01-1.65)	1.63 (1.25-2.18)	1.91 (1.42-2.58)	2.20 (1.59-3.04)	2.52 (1.76-3.57)	2.98 (1.99-4.30)	3.34 (2.17-4.86)
60-min	0.845 (0.670-1.08)	1.04 (0.825-1.33)	1.38 (1.09-1.77)	1.69 (1.32-2.17)	2.14 (1.64-2.86)	2.50 (1.87-3.38)	2.89 (2.09-3.99)	3.30 (2.30-4.66)	3.88 (2.60-5.61)	4.35 (2.83-6.33)
2-hr	1.03 (0.819-1.30)	1.28 (1.02-1.62)	1.71 (1.36-2.17)	2.09 (1.65-2.66)	2.64 (2.04-3.51)	3.10 (2.33-4.15)	3.58 (2.60-4.89)	4.08 (2.86-5.72)	4.79 (3.23-6.87)	5.36 (3.51-7.74)
3-hr	1.09 (0.876-1.38)	1.37 (1.10-1.73)	1.85 (1.48-2.34)	2.27 (1.80-2.88)	2.88 (2.22-3.79)	3.37 (2.54-4.48)	3.89 (2.84-5.28)	4.43 (3.11-6.17)	5.19 (3.51-7.40)	5.79 (3.81-8.33)
6-hr	1.26 (1.01-1.57)	1.51 (1.21-1.88)	1.95 (1.57-2.45)	2.36 (1.89-2.97)	2.98 (2.33-3.92)	3.50 (2.67-4.64)	4.05 (2.99-5.49)	4.66 (3.30-6.45)	5.51 (3.77-7.82)	6.20 (4.12-8.85)
12-hr	1.37 (1.11-1.70)	1.62 (1.31-2.00)	2.06 (1.66-2.56)	2.46 (1.98-3.08)	3.08 (2.44-4.03)	3.61 (2.78-4.76)	4.18 (3.11-5.62)	4.80 (3.43-6.60)	5.68 (3.91-7.99)	6.39 (4.28-9.05)
24-hr	1.48 (1.21-1.82)	1.73 (1.41-2.13)	2.19 (1.78-2.70)	2.61 (2.11-3.23)	3.26 (2.59-4.22)	3.80 (2.95-4.97)	4.40 (3.30-5.87)	5.05 (3.64-6.89)	5.98 (4.15-8.34)	6.73 (4.54-9.45)
2-day	1.66 (1.37-2.03)	1.91 (1.57-2.33)	2.36 (1.94-2.89)	2.79 (2.28-3.43)	3.46 (2.77-4.45)	4.02 (3.15-5.22)	4.65 (3.52-6.16)	5.33 (3.88-7.22)	6.31 (4.43-8.75)	7.12 (4.84-9.91)
3-day	1.80 (1.49-2.19)	2.09 (1.73-2.54)	2.62 (2.16-3.19)	3.10 (2.54-3.78)	3.82 (3.06-4.87)	4.42 (3.46-5.69)	5.08 (3.85-6.67)	5.78 (4.22-7.78)	6.78 (4.77-9.34)	7.60 (5.19-10.5)
4-day	1.93 (1.60-2.34)	2.26 (1.88-2.74)	2.84 (2.35-3.45)	3.36 (2.76-4.09)	4.13 (3.32-5.24)	4.77 (3.74-6.10)	5.45 (4.14-7.12)	6.17 (4.51-8.26)	7.20 (5.07-9.86)	8.02 (5.50-11.1)
7-day	2.31 (1.93-2.78)	2.68 (2.24-3.23)	3.34 (2.77-4.02)	3.91 (3.24-4.73)	4.76 (3.84-5.98)	5.46 (4.31-6.93)	6.20 (4.74-8.04)	6.99 (5.14-9.28)	8.09 (5.74-11.0)	8.98 (6.20-12.3)
10-day	2.63 (2.20-3.14)	3.04 (2.54-3.64)	3.75 (3.13-4.50)	4.38 (3.64-5.28)	5.30 (4.30-6.63)	6.06 (4.79-7.65)	6.85 (5.25-8.84)	7.69 (5.68-10.2)	8.87 (6.31-12.0)	9.80 (6.80-13.4)
20-day	3.42 (2.89-4.06)	4.00 (3.37-4.75)	4.97 (4.18-5.91)	5.79 (4.84-6.92)	6.94 (5.64-8.55)	7.86 (6.24-9.79)	8.79 (6.77-11.2)	9.75 (7.24-12.7)	11.1 (7.92-14.8)	12.1 (8.44-16.3)
30-day	4.11 (3.48-4.85)	4.81 (4.08-5.69)	5.96 (5.04-7.06)	6.92 (5.81-8.22)	8.23 (6.70-10.0)	9.24 (7.36-11.4)	10.2 (7.92-12.9)	11.3 (8.39-14.6)	12.6 (9.06-16.7)	13.6 (9.58-18.4)
45-day	5.04 (4.29-5.92)	5.87 (4.99-6.90)	7.20 (6.10-8.48)	8.27 (6.98-9.78)	9.71 (7.92-11.7)	10.8 (8.63-13.2)	11.9 (9.19-14.9)	12.9 (9.63-16.6)	14.2 (10.3-18.7)	15.2 (10.8-20.4)
60-day	5.90 (5.04-6.91)	6.80 (5.80-7.96)	8.22 (6.99-9.65)	9.36 (7.92-11.0)	10.9 (8.87-13.1)	12.0 (9.59-14.6)	13.0 (10.1-16.2)	14.1 (10.5-18.0)	15.4 (11.1-20.1)	16.3 (11.6-21.8)


¹ Precipitation frequency (PF) estimates in this table are based on frequency analysis of partial duration series (PDS). Numbers in parenthesis are PF estimates at lower and upper bounds of the 90% confidence interval. The probability that precipitation frequency estimates (for a given duration and average recurrence interval) will be greater than the upper bound (or less than the lower bound) is 5%. Estimates at upper bounds are not checked against probable maximum precipitation (PMP) estimates and may be higher than currently valid PMP values. Please refer to NOAA Atlas 14 document for more information.

[Back to Top](#)

PF graphical

PDS-based depth-duration-frequency (DDF) curves

Latitude: 38.8322°, Longitude: -104.2663°




NOAA Atlas 14, Volume 8, Version 2

Created (GMT): Wed Mar 4 22:13:01 2026


[Back to Top](#)

Maps & aerials


Small scale terrain




Large scale terrain



Large scale map



Large scale aerial



[Back to Top](#)

[US Department of Commerce](#)
[National Oceanic and Atmospheric Administration](#)
[National Weather Service](#)
[National Water Center](#)
1325 East West Highway
Silver Spring, MD 20910
Questions?: HDSC.Questions@noaa.gov

[Disclaimer](#)



STANDARD FORM SF-1 (EXISITNG CONDITIONS)
RUNOFF COEFFICIENTS - IMPERVIOUS CALCULATION

PROJECT NAME: **Tanner Ranch Pond A**
PROJECT NUMBER: 296172000
CALCULATED BY: MEO
CHECKED BY: KRK

HYDROLOGIC SOIL GROUP: A

Impervious values and runoff coefficients are taken from the El Paso County Drainage Criteria Manual (Vol. 1 Update)	<u>LAND USE (HSG A/B):</u>											
	2-YEAR COEFF.	0.89	0.57	0.02								
	5-YEAR COEFF.	0.90	0.59	0.08								
	10-YEAR COEFF.	0.92	0.63	0.15								
	100-YEAR COEFF.	0.96	0.70	0.35								
	IMPERVIOUS %	100%	80%	0%								
DESIGN BASIN	DESIGN POINT	PAVEMENT <u>AREA</u> (SF)	GRAVEL <u>AREA</u> (SF)	LANDSCAPE <u>AREA</u> (SF)	TOTAL AREA (SF)	TOTAL AREA (AC)	C(2)	C(5)	C(10)	C(100)	Imp %	HSG
Basins												
EX-A	DP-EXA			1,894,860	1,894,860	43.50	0.02	0.08	0.15	0.35	0%	A
BASIN SUBTOTAL		-	-	1,894,860	1,894,860	43.50	0.02	0.08	0.15	0.35	0.00%	A
		0%	0%	100%	100%	100%						

STANDARD FORM SF-2 (EXISTING CONDITIONS)
Time of Concentration

PROJECT NAME: Tanner Ranch Pond A
PROJECT NUMBER: 296008000
CALCULATED BY: MEO
CHECKED BY: KRK

SUB-BASIN DATA			INITIAL TIME (T _i)			TRAVEL TIME (T _t)					T _c CHECK (URBANIZED BASINS)					FINAL T _c
DESIGN BASIN (1)	AREA Ac (2)	C5 (3)	LENGTH Ft (4)	SLOPE % (5)	T _i Min. (6)	LENGTH Ft. (7)	SLOPE % (8)	C _v (9)	VEL fps (11)	T _t Min. (12)	COMP. t _c (13)	TOTAL LENGTH (14)	TOTAL SLOPE (15)	TOTAL IMP. (16)	T _c Min. (17)	Min.
All Basins																
EX-A	1,894,860	0.08	500	4.0%	26.3	1161	4.0%	7.0	1.4	13.8	40.2	1661	4.0%	0%	41.4	40.2

$$t_i = \frac{0.395(1.1 - C_s)\sqrt{L_i}}{S_o^{0.33}}$$

$$t_t = \frac{L_t}{60K\sqrt{S_o}} = \frac{L_t}{60V_t}$$

$$t_c = (26 - 17i) + \frac{L_t}{60(14i + 9)\sqrt{S_i}}$$


Kimley»Horn

STANDARD FORM SF-3 (EXISTING CONDITIONS)
STORM DRAINAGE DESIGN - RATIONAL METHOD 5 YEAR EVENT

PROJECT NAME: Tanner Ranch Pond A
PROJECT NUMBER: 296008000
CALCULATED BY: MEO
CHECKED BY: KRK

P₁ (1-Hour Rainfall) = 1.38

STORM LINE	DESIGN POINT	DIRECT RUNOFF								TOTAL RUNOFF				REMARKS
		DESIGN BASIN	AREA (AC)	RUNOFF COEFF	t _c (min)	C*A(ac)	I (in/hr)	Q (cfs)	t _c (max)	S(C*A) (ac)	I (in/hr)	Q (cfs)		
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)	(11)	(12)	(13)	(22)	
All Basins														
		DP-EXA	EX-A	43.50	0.08	40.2	3.48	2.04	7.11					






STANDARD FORM SF-3 (EXISTING CONDITIONS)
STORM DRAINAGE DESIGN - RATIONAL METHOD 100 YEAR EVENT

PROJECT NAME: Tanner Ranch Pond A
PROJECT NUMBER: 296008000
CALCULATED BY: MEO
CHECKED BY: KRK

P₁ (1-Hour Rainfall) = 2.89

STORM LINE	DESIGN POINT	DIRECT RUNOFF							TOTAL RUNOFF				REMARKS
		DESIGN BASIN	AREA (AC)	RUNOFF COEFF	t _c (min)	C*A(ac)	I (in/hr)	Q (cfs)	t _c (max)	S(C*A) (ac)	I (in/hr)	Q (cfs)	
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)	(11)	(12)	(13)	(22)
All Basins													
		DP-EXA	EX-A	43.50	0.35	40.2	15.23	3.43	52.20				

Figure 6-5. Colorado Springs Rainfall Intensity Duration Frequency



IDF Equations

$I_{100} = -2.52 \ln(D) + 12.735$

$I_{50} = -2.25 \ln(D) + 11.375$

$I_{25} = -2.00 \ln(D) + 10.111$

$I_{10} = -1.75 \ln(D) + 8.847$

$I_5 = -1.50 \ln(D) + 7.583$

$I_2 = -1.19 \ln(D) + 6.035$

Note: Values calculated by
equations may not precisely



EXISTING CONDITIONS

Tanner Ranch Pond A

DATE: 3/10/2026

PROJECT NUMBER: 296008000

CALCULATED BY: MEO

CHECKED BY: KRK

EXISTING RATIONAL CALCULATIONS SUMMARY

DESIGN POINT	TRIBUTARY BASINS	TRIBUTARY AREA (AC)	PEAK FLOWS (CFS)	
			Q5	Q100
On-site Basins				
DP-EXA	EX-A	43.50	7.11	52.20
Total		43.50	7.11	52.20



STANDARD FORM SF-1 (PROPOSED CONDITIONS)
RUNOFF COEFFICIENTS - IMPERVIOUS CALCULATION

PROJECT NAME: Tanner Ranch Pond A
PROJECT NUMBER: 296172000
CALCULATED BY: MEO
CHECKED BY: KRK

HYDROLOGIC SOIL GROUP: A

Impervious values and runoff coefficients are taken from the El Paso County Drainage Criteria Manual (Vol. 1 Update)	RESIDENTIAL												
	LAND USE (HSG A/B):	PAVEMENT	(>2.5AC)	GRAVEL	LANDSCAPE								
	2-YEAR COEFF.	0.89	0.12	0.57	0.02								
	5-YEAR COEFF.	0.90	0.20	0.59	0.08								
	10-YEAR COEFF.	0.92	0.27	0.63	0.15								
	100-YEAR COEFF.	0.96	0.44	0.70	0.35								
	IMPERVIOUS %	100%	11%	80%	0%								
DESIGN BASIN	DESIGN POINT	PAVEMENT AREA (SF)	RESIDENTIAL (>2.5AC) AREA (SF)	GRAVEL AREA (SF)	LANDSCAPE AREA (SF)	TOTAL AREA (SF)	TOTAL AREA (AC)	C(2)	C(5)	C(10)	C(100)	Imp %	HSG
Basins													
A-2	POND A	17,612	358,136		295,076	670,824	15.40	0.41	0.17	0.23	0.41	8%	A
BASIN SUBTOTAL		17,612	358,136	-	295,076	670,824	15.40	0.10	0.17	0.23	0.41	8.50%	A
		3%	53%	0%	44%	100%	100%						

STANDARD FORM SF-2 (PROPOSED CONDITIONS)
Time of Concentration

PROJECT NAME: Tanner Ranch Pond A
PROJECT NUMBER: 296008000
CALCULATED BY: MEO
CHECKED BY: KRK


SUB-BASIN DATA			INITIAL TIME (T _i)			TRAVEL TIME (T _t)					T _c CHECK (URBANIZED BASINS)					FINAL T _c
DESIGN BASIN (1)	AREA Ac (2)	C5 (3)	LENGTH Ft (4)	SLOPE % (5)	T _i Min. (6)	LENGTH Ft. (7)	SLOPE % (8)	C _v (9)	VEL fps (11)	T _t Min. (12)	COMP. t _c (13)	TOTAL LENGTH (14)	TOTAL SLOPE (15)	TOTAL IMP. (16)	T _c Min. (17)	Min.
All Basins																
A-2	670,824	0.17	300	4.0%	18.7	500	4.0%	7.0	1.4	6.0	24.6	800	4.0%	8%	31.1	24.6

$$t_i = \frac{0.395(1.1 - C_s)\sqrt{L_i}}{S_o^{0.33}}$$

$$t_t = \frac{L_t}{60K\sqrt{S_o}} = \frac{L_t}{60V_t}$$

$$t_c = (26 - 17i) + \frac{L_t}{60(14i + 9)\sqrt{S_i}}$$

Kimley»Horn STANDARD FORM SF-3 (PROPOSED CONDITIONS) STORM DRAINAGE DESIGN - RATIONAL METHOD 5 YEAR EVENT PROJECT NAME: Tanner Ranch Pond A PROJECT NUMBER: 296008000 CALCULATED BY: MEO CHECKED BY: KRK P₁ (1-Hour Rainfall) = 1.38													
STORM LINE	DESIGN POINT	DIRECT RUNOFF							TOTAL RUNOFF				REMARKS
		DESIGN BASIN	AREA (AC)	RUNOFF COEFF	t _c (min)	C*A(ac)	I (in/hr)	Q (cfs)	t _c (max)	S(C*A) (ac)	I (in/hr)	Q (cfs)	
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)	(11)	(12)	(13)	(22)
All Basins													
		POND A	A-2	15.40	0.17	24.6	2.55	2.78	7.08				






STANDARD FORM SF-3 (PROPOSED CONDITIONS)
STORM DRAINAGE DESIGN - RATIONAL METHOD 100 YEAR EVENT

PROJECT NAME: Tanner Ranch Pond A
PROJECT NUMBER: 296008000
CALCULATED BY: MEO
CHECKED BY: KRK

P₁ (1-Hour Rainfall) = 2.89

STORM LINE	DESIGN POINT	DIRECT RUNOFF							TOTAL RUNOFF				REMARKS
		DESIGN BASIN	AREA (AC)	RUNOFF COEFF	t _c (min)	C*A(ac)	I (in/hr)	Q (cfs)	t _c (max)	S(C*A) (ac)	I (in/hr)	Q (cfs)	
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)	(11)	(12)	(13)	(22)
All Basins													
	POND A	A-2	15.40	0.41	24.6	6.38	4.66	29.71					

Figure 6-5. Colorado Springs Rainfall Intensity Duration Frequency



IDF Equations

$I_{100} = -2.52 \ln(D) + 12.735$

$I_{50} = -2.25 \ln(D) + 11.375$

$I_{25} = -2.00 \ln(D) + 10.111$

$I_{10} = -1.75 \ln(D) + 8.847$

$I_5 = -1.50 \ln(D) + 7.583$

$I_2 = -1.19 \ln(D) + 6.035$

Note: Values calculated by equations may not precisely



PROPOSED CONDITIONS

Tanner Ranch Pond A

DATE: 3/10/2026

PROJECT NUMBER: 296008000

CALCULATED BY: MEO

CHECKED BY: KRK

EXISTING RATIONAL CALCULATIONS SUMMARY

DESIGN POINT	TRIBUTARY BASINS	TRIBUTARY AREA (AC)	PEAK FLOWS (CFS)	
			Q5	Q100

On-site Basins

POND A	A-2	15.40	7.08	29.71
<u>Total</u>		15.40	7.08	29.71


APPENDIX E – HYDRAULIC CALCULATIONS

DETENTION BASIN STAGE-STORAGE TABLE BUILDER

MHFD-Detention, Version 4.06 (July 2022)

Project: Tanner Ranch

Basin ID: Pond A



Example Zone Configuration (Retention Pond)

Watershed Information

Selected BMP Type =	EDB
Watershed Area =	0.40 acres
Watershed Length =	900 ft
Watershed Length to Centroid =	450 ft
Watershed Slope =	0.040 ft/ft
Watershed Imperviousness =	100.00% percent
Percentage Hydrologic Soil Group A =	0.0% percent
Percentage Hydrologic Soil Group B =	100.0% percent
Percentage Hydrologic Soil Groups C/D =	0.0% percent
Target WQCV Drain Time =	40.0 hours
Location for 1-hr Rainfall Depths =	User Input

After providing required inputs above including 1-hour rainfall depths, click "Run CUHP" to generate runoff hydrographs using the embedded Colorado Urban Hydrograph Procedure.

Water Quality Capture Volume (WQCV) =	0.017 acre-feet
Excess Urban Runoff Volume (EURV) =	0.046 acre-feet
2-yr Runoff Volume (P1 = 1.04 in.) =	0.035 acre-feet
5-yr Runoff Volume (P1 = 1.38 in.) =	0.047 acre-feet
10-yr Runoff Volume (P1 = 1.69 in.) =	0.058 acre-feet
25-yr Runoff Volume (P1 = 2.14 in.) =	0.075 acre-feet
50-yr Runoff Volume (P1 = 2.5 in.) =	0.088 acre-feet
100-yr Runoff Volume (P1 = 2.89 in.) =	0.102 acre-feet
500-yr Runoff Volume (P1 = 3.88 in.) =	0.138 acre-feet
Approximate 2-yr Detention Volume =	0.032 acre-feet
Approximate 5-yr Detention Volume =	0.044 acre-feet
Approximate 10-yr Detention Volume =	0.056 acre-feet
Approximate 25-yr Detention Volume =	0.067 acre-feet
Approximate 50-yr Detention Volume =	0.072 acre-feet
Approximate 100-yr Detention Volume =	0.076 acre-feet

Note: L / W Ratio > 8
L / W Ratio = 46.03

Optional User Overrides

	acre-feet
	acre-feet
1.04	inches
1.38	inches
1.69	inches
2.14	inches
2.50	inches
2.89	inches
3.88	inches


This sheet is provided to override the WCQV for Pond A calculations. This is the associated impervious area from the road as shown in blue on the proposed drainage map. Per code section, I.7.1.B.5 large lots are exempt from WQCV. Stage-storage is not applicable.

Define Zones and Basin Geometry

Select Zone 1 Storage Volume (Required) =	acre-feet
Select Zone 2 Storage Volume (Optional) =	acre-feet
Select Zone 3 Storage Volume (Optional) =	acre-feet
Total Detention Basin Volume =	acre-feet
Initial Surge Volume (ISV) =	ft ³
Initial Surge Depth (ISD) =	ft
Total Available Detention Depth (H _{total}) =	ft
Depth of Trickle Channel (H _{TC}) =	ft
Slope of Trickle Channel (S _{TC}) =	ft/ft
Slopes of Main Basin Sides (S _{main}) =	H:V
Basin Length-to-Width Ratio (R _{LW}) =	
Initial Surge Area (A _{ISV}) =	ft ²
Surge Volume Length (L _{ISV}) =	ft
Surge Volume Width (W _{ISV}) =	ft
Depth of Basin Floor (H _{FLOOR}) =	ft
Length of Basin Floor (L _{FLOOR}) =	ft
Width of Basin Floor (W _{FLOOR}) =	ft
Area of Basin Floor (A _{FLOOR}) =	ft ²
Volume of Basin Floor (V _{FLOOR}) =	ft ³
Depth of Main Basin (H _{MAIN}) =	ft
Length of Main Basin (L _{MAIN}) =	ft
Width of Main Basin (W _{MAIN}) =	ft
Area of Main Basin (A _{MAIN}) =	ft ²
Volume of Main Basin (V _{MAIN}) =	ft ³
Calculated Total Basin Volume (V _{total}) =	acre-feet

MHFD-Detention, Version 4.06 (July 2022)

Basin ID: Pond A




Initial Surcharge Area (A_{S1})	=	user	ft ²
Surcharge Volume Length (L_{S1})	=	user	ft
Surcharge Volume Width (W_{S1})	=	user	ft
Depth of Basin Floor (H_{FLOOR})	=	user	ft
Length of Basin Floor (L_{FLOOR})	=	user	ft
Width of Basin Floor (W_{FLOOR})	=	user	ft
Area of Basin Floor (A_{FLOOR})	=	user	ft ²
Volume of Basin Floor (V_{FLOOR})	=	user	ft ³
Depth of Main Basin (H_{MAIN})	=	user	ft
Length of Main Basin (L_{MAIN})	=	user	ft
Width of Main Basin (W_{MAIN})	=	user	ft
Area of Main Basin (A_{MAIN})	=	user	ft ²
Volume of Main Basin (V_{MAIN})	=	user	ft ³
Calculated Total Basin Volume (V_{TOTAL})	=	user	acre-feet

[illegible]

DETENTION BASIN STAGE-STORAGE TABLE BUILDER

MHFD-Detention, Version 4.06 (July 2022)




DETENTION BASIN OUTLET STRUCTURE DESIGN

MHFD-Detention, Version 4.06 (July 2022)

Project: **Tanner Ranch**

Basin ID: **Pond A**



Example Zone Configuration (Retention Pond)

	Estimated Stage (ft)	Estimated Volume (ac-ft)	Outlet Type
Zone 1 (WQCV)	0.85	0.017	Orifice Plate
Zone 2 (EURV)	1.33	0.104	Orifice Plate
Zone 3 (100-year)	2.05	0.483	Weir&Pipe (Restrict)
Total (all zones)		0.604	

User Input: Orifice at Underdrain Outlet (typically used to drain WQCV in a Filtration BMP)

Underdrain Orifice Invert Depth = ft (distance below the filtration media surface)
Underdrain Orifice Diameter = inches

Calculated Parameters for Underdrain
Underdrain Orifice Area = ft²
Underdrain Orifice Centroid = feet

User Input: Orifice Plate with one or more orifices or Elliptical Slot Weir (typically used to drain WQCV and/or EURV in a sedimentation BMP)

Centroid of Lowest Orifice = ft (relative to basin bottom at Stage = 0 ft)
Depth at top of Zone using Orifice Plate = ft (relative to basin bottom at Stage = 0 ft)
Orifice Plate: Orifice Vertical Spacing = inches
Orifice Plate: Orifice Area per Row = sq. inches

Calculated Parameters for Plate
WQ Orifice Area per Row = ft²
Elliptical Half-Width = feet
Elliptical Slot Centroid = feet
Elliptical Slot Area = ft²

User Input: Stage and Total Area of Each Orifice Row (numbered from lowest to highest)

	Row 1 (required)	Row 2 (optional)	Row 3 (optional)	Row 4 (optional)	Row 5 (optional)	Row 6 (optional)	Row 7 (optional)	Row 8 (optional)
Stage of Orifice Centroid (ft)	0.00	0.75	1.00					
Orifice Area (sq. inches)	0.15	0.79	1.77					

	Row 9 (optional)	Row 10 (optional)	Row 11 (optional)	Row 12 (optional)	Row 13 (optional)	Row 14 (optional)	Row 15 (optional)	Row 16 (optional)
Stage of Orifice Centroid (ft)								
Orifice Area (sq. inches)								

User Input: Vertical Orifice (Circular or Rectangular)

	Not Selected	Not Selected	
Invert of Vertical Orifice =	N/A	N/A	ft (relative to basin bottom at Stage = 0 ft)
Depth at top of Zone using Vertical Orifice =	N/A	N/A	ft (relative to basin bottom at Stage = 0 ft)
Vertical Orifice Diameter =	N/A	N/A	inches

Calculated Parameters for Vertical Orifice
Vertical Orifice Area = ft²
Vertical Orifice Centroid = feet

User Input: Overflow Weir (Dropbox with Flat or Sloped Grate and Outlet Pipe OR Rectangular/Trapezoidal Weir and No Outlet Pipe)

	Zone 3 Weir	Not Selected	
Overflow Weir Front Edge Height, Ho =	1.33	N/A	ft (relative to basin bottom at Stage = 0 ft)
Overflow Weir Front Edge Length =	3.92	N/A	feet
Overflow Weir Grate Slope =	4.00	N/A	H:V
Horiz. Length of Weir Sides =	2.92	N/A	feet
Overflow Grate Type =	Type C Grate	N/A	
Debris Clogging % =	50%	N/A	%

Calculated Parameters for Overflow Weir
Height of Grate Upper Edge, H_u = feet
Overflow Weir Slope Length = feet
Grate Open Area / 100-yr Orifice Area = ft²
Overflow Grate Open Area w/o Debris = ft²
Overflow Grate Open Area w/ Debris = ft²

User Input: Outlet Pipe w/ Flow Restriction Plate (Circular Orifice, Restrictor Plate, or Rectangular Orifice)

	Zone 3 Restrictor	Not Selected	
Depth to Invert of Outlet Pipe =	0.23	N/A	ft (distance below basin bottom at Stage = 0 ft)
Outlet Pipe Diameter =	18.00	N/A	inches
Restrictor Plate Height Above Pipe Invert =	3.00	N/A	inches

Calculated Parameters for Outlet Pipe w/ Flow Restriction Plate
Outlet Orifice Area = ft²
Outlet Orifice Centroid = feet
Half-Central Angle of Restrictor Plate on Pipe = radians

User Input: Emergency Spillway (Rectangular or Trapezoidal)

Spillway Invert Stage = ft (relative to basin bottom at Stage = 0 ft)
Spillway Crest Length = feet
Spillway End Slopes = H:V
Freeboard above Max Water Surface = feet

Calculated Parameters for Spillway
Spillway Design Flow Depth = feet
Stage at Top of Freeboard = feet
Basin Area at Top of Freeboard = acres
Basin Volume at Top of Freeboard = acre-ft




Routed Hydrograph Results

The user can override the default CUHP hydrographs and runoff volumes by entering new values in the Inflow Hydrographs table (Columns W through AF).

	WQCV	EURV	2 Year	5 Year	10 Year	25 Year	50 Year	100 Year	500 Year
Design Storm Return Period	N/A	N/A	1.04	1.38	1.69	2.14	2.50	2.89	3.88
One-Hour Rainfall Depth (in)	N/A	N/A	0.121	0.079	0.320	0.601	1.282	1.718	2.312
CUHP Runoff Volume (acre-ft)	0.017	0.104	0.079	0.320	0.601	1.282	1.718	2.312	3.597
Inflow Hydrograph Volume (acre-ft)	N/A	N/A	0.079	0.320	0.601	1.282	1.718	2.312	3.597
CUHP Predevelopment Peak Q (cfs)	N/A	N/A	0.3	3.8	7.1	16.1	21.1	27.2	41.6
OPTIONAL Override Predevelopment Peak Q (cfs)	N/A	N/A							
Predevelopment Unit Peak Flow, q (cfs/acre)	N/A	N/A	0.02	0.25	0.46	1.04	1.37	1.76	2.70
Peak Inflow Q (cfs)	N/A	N/A	1.1	4.7	8.1	17.1	22.1	28.2	42.7
Peak Outflow Q (cfs)	0.0	0.1	0.0	0.6	1.3	1.5	5.6	12.1	26.2
Ratio Peak Outflow to Predevelopment Q	N/A	N/A	N/A	0.2	0.2	0.1	0.3	0.4	0.6
Structure Controlling Flow	Plate	Overflow Weir 1	Plate	Overflow Weir 1	Outlet Plate 1	Outlet Plate 1	Spillway	Spillway	Spillway
Max Velocity through Grate 1 (fps)	N/A	N/A	N/A	0.1	0.1	0.2	0.2	0.2	0.2
Max Velocity through Grate 2 (fps)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Time to Drain 97% of Inflow Volume (hours)	40	64	60	58	48	40	36	32	23
Time to Drain 99% of Inflow Volume (hours)	41	72	66	77	71	59	55	51	42
Maximum Ponding Depth (ft)	0.85	1.33	1.19	1.59	1.86	2.49	2.66	2.80	3.02
Area at Maximum Ponding Depth (acres)	0.08	0.42	0.29	0.63	0.78	1.18	1.29	1.38	1.53
Maximum Volume Stored (acre-ft)	0.018	0.122	0.072	0.262	0.445	1.069	1.279	1.466	1.786

DETENTION BASIN OUTLET STRUCTURE DESIGN

MHFD-Detention, Version 4.06 (July 2022)



S-A-V-D Chart Axis Override

X-axis	Left Y-Axis	Right Y-Axis
minimum bound		
maximum bound		

DETENTION BASIN OUTLET STRUCTURE DESIGN

Outflow Hydrograph Workbook Filename: _____

Inflow Hydrographs

The user can override the calculated inflow hydrographs from this workbook with inflow hydrographs developed in a separate program.

	SOURCE	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP
Time Interval	TIME	WQCV [cfs]	EURV [cfs]	2 Year [cfs]	5 Year [cfs]	10 Year [cfs]	25 Year [cfs]	50 Year [cfs]	100 Year [cfs]	500 Year [cfs]
5.00 min	0:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	0:05:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	0:10:00	0.00	0.00	0.00	0.00	0.00	0.00	0.01	0.00	0.02
	0:15:00	0.00	0.00	0.02	0.03	0.04	0.03	0.05	0.05	0.07
	0:20:00	0.00	0.00	0.07	0.11	0.37	0.09	0.14	0.28	0.75
	0:25:00	0.00	0.00	0.61	1.71	4.57	0.99	2.21	3.64	9.61
	0:30:00	0.00	0.00	1.01	4.36	7.71	11.06	15.08	18.72	30.27
	0:35:00	0.00	0.00	1.08	4.74	8.13	15.45	20.31	26.17	40.24
	0:40:00	0.00	0.00	1.04	4.45	7.66	17.06	22.11	28.25	42.70
	0:45:00	0.00	0.00	0.93	3.93	7.02	16.35	21.19	27.88	42.04
	0:50:00	0.00	0.00	0.83	3.52	6.28	15.75	20.42	26.79	40.36
	0:55:00	0.00	0.00	0.74	3.11	5.61	14.28	18.64	25.06	37.86
	1:00:00	0.00	0.00	0.67	2.77	5.09	12.94	17.03	23.50	35.67
	1:05:00	0.00	0.00	0.62	2.51	4.66	11.87	15.74	22.31	33.95
	1:10:00	0.00	0.00	0.55	2.25	4.25	10.56	14.16	19.93	30.62
	1:15:00	0.00	0.00	0.47	1.97	3.84	9.29	12.62	17.56	27.28
	1:20:00	0.00	0.00	0.40	1.68	3.31	7.99	10.87	15.05	23.41
	1:25:00	0.00	0.00	0.35	1.43	2.85	6.76	9.24	12.76	19.94
	1:30:00	0.00	0.00	0.31	1.26	2.51	5.80	7.95	10.96	17.21
	1:35:00	0.00	0.00	0.28	1.14	2.24	5.07	6.97	9.59	15.09
	1:40:00	0.00	0.00	0.26	1.02	2.00	4.47	6.15	8.44	13.28
	1:45:00	0.00	0.00	0.23	0.90	1.78	3.94	5.42	7.41	11.67
	1:50:00	0.00	0.00	0.21	0.79	1.57	3.46	4.76	6.47	10.20
	1:55:00	0.00	0.00	0.18	0.68	1.35	3.00	4.14	5.59	8.82
	2:00:00	0.00	0.00	0.15	0.56	1.12	2.56	3.54	4.77	7.53
	2:05:00	0.00	0.00	0.12	0.45	0.90	2.12	2.93	3.96	6.24
	2:10:00	0.00	0.00	0.09	0.34	0.68	1.68	2.33	3.18	4.99
	2:15:00	0.00	0.00	0.07	0.23	0.48	1.25	1.75	2.40	3.78
	2:20:00	0.00	0.00	0.04	0.14	0.32	0.84	1.20	1.67	2.67
	2:25:00	0.00	0.00	0.03	0.09	0.22	0.52	0.78	1.11	1.85
	2:30:00	0.00	0.00	0.02	0.06	0.17	0.34	0.54	0.76	1.31
	2:35:00	0.00	0.00	0.02	0.05	0.13	0.22	0.37	0.53	0.93
	2:40:00	0.00	0.00	0.02	0.04	0.10	0.15	0.26	0.35	0.65
	2:45:00	0.00	0.00	0.01	0.03	0.08	0.10	0.18	0.23	0.44
	2:50:00	0.00	0.00	0.01	0.02	0.06	0.07	0.12	0.14	0.28
	2:55:00	0.00	0.00	0.01	0.02	0.04	0.04	0.08	0.08	0.17
	3:00:00	0.00	0.00	0.01	0.01	0.03	0.03	0.06	0.05	0.11
	3:05:00	0.00	0.00	0.00	0.01	0.02	0.02	0.04	0.04	0.08
	3:10:00	0.00	0.00	0.00	0.01	0.02	0.02	0.03	0.03	0.06
	3:15:00	0.00	0.00	0.00	0.00	0.01	0.01	0.02	0.02	0.05
	3:20:00	0.00	0.00	0.00	0.00	0.01	0.01	0.02	0.02	0.04
	3:25:00	0.00	0.00	0.00	0.00	0.01	0.01	0.01	0.01	0.03
	3:30:00	0.00	0.00	0.00	0.00	0.00	0.00	0.01	0.01	0.02
	3:35:00	0.00	0.00	0.00	0.00	0.00	0.00	0.01	0.01	0.01
	3:40:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.01
	3:45:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:50:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:55:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:05:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:10:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:15:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:20:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:25:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:30:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:35:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:40:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:45:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:50:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:55:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:05:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:10:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:15:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:20:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:25:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:30:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:35:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:40:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:45:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:50:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:55:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	6:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

DETENTION BASIN OUTLET STRUCTURE DESIGN

MHFD-Detention, Version 4.06 (July 2022)

The user can create a summary S-A-V-D by entering the desired stage increments and the remainder of the table will populate automatically.

The user should graphically compare the summary S-A-V-D table to the full S-A-V-D table in the chart to confirm it captures all key transition points.


	Stage	Area	Area	Volume	Volume	Total
--	-------	------	------	--------	--------	-------

[illegible]

DETERMINATION OF CULVERT HEADWATER AND OUTLET PROTECTION

MHFD-Culvert, Version 4.01 (April 2025)

Project: **Miller Downs**
ID: **FSD Pond Outfall**



Soil Type:

Choose One:

☐ Sandy

☒ Non-Sandy

Supercritical Flow! Using Adjusted Diameter to calculate protection type.

Design Information:

Design Discharge

Q = 1.1 cfs

Circular Culvert:

Barrel Diameter in Inches

D = 18 inches

Inlet Edge Type (Choose from pull-down list)

Grooved Edge Projecting

OR:

Box Culvert:

Barrel Height (Rise) in Feet

H (Rise) =

Barrel Width (Span) in Feet

W (Span) =

Inlet Edge Type (Choose from pull-down list)

Number of Barrels

Barrels = 1

Inlet Elevation

Elev IN = 6217.27 ft

Outlet Elevation OR Slope

Elev OUT = 6217.15 ft

Culvert Length

L = 19 ft

Manning's Roughness

n = 0.012

Bend Loss Coefficient

k_b = 0

Exit Loss Coefficient

k_x = 1

Tailwater Surface Elevation

Y_t Elevation =

Max Allowable Channel Velocity

V = 7 ft/s

Calculated Results:

Culvert Cross Sectional Area Available

A = 1.77 ft²

Culvert Normal Depth

Y_n = 0.35 ft

Culvert Critical Depth

Y_c = 0.39 ft

Froude Number

Fr = 1.23 **Supercritical!**

Entrance Loss Coefficient

k_e = 0.20

Friction Loss Coefficient

k_f = 0.29

Sum of All Loss Coefficients

k_s = 1.49 ft

Headwater:

Inlet Control Headwater

HW_I = 0.53 ft

Outlet Control Headwater

HW_O = N/A ft

Design Headwater Elevation

HW = N/A ft

Headwater/Diameter OR Headwater/Rise Ratio

HW/D = N/A

Outlet Control Headwater Approximation Method Inaccurate for Low Flow - Backwater Calculations Required

Outlet Protection:

Flow/(Diameter^{2.5})

Q/D^{2.5} = 0.40 ft^{0.5}/s

Tailwater Surface Height

Y_t = 0.60 ft

Tailwater/Diameter

Y_t/D = 0.40

Expansion Factor

1/(2*tan(θ)) = 6.70

Flow Area at Max Channel Velocity

A_t = 0.16 ft²

Width of Equivalent Conduit for Multiple Barrels

W_{eq} = - ft

Length of Riprap Protection

L_p = 5 ft

Width of Riprap Protection at Downstream End

T = 3 ft

Adjusted Diameter for Supercritical Flow

Da = 0.93 ft

Minimum Theoretical Riprap Size




d₅₀ min = 1 in

Nominal Riprap Size

d₅₀ nominal = 6 in

MHFD Riprap Type

Type = VL




Unit discharge = $Q_{out}(100 \text{ year}) / \text{Spillway Width}$
 Unit discharge = $14.5/20 = 0.725$

Figure 12-21. Embankment protection details and rock sizing chart (adapted from Arapahoe County)


MHFD-Detention, Version 4.07 (June 2025)

Basin ID: Pond A1- Post Construction



DETENTION BASIN STAGE-STORAGE TABLE BUILDER


MHFD-Detention, Version 4.07 (June 2025)



DETENTION BASIN OUTLET STRUCTURE DESIGN

MHFD-Detention, Version 4.07 (June 2025)

Project: Tanner Ranch Subdivision
Basin ID: Pond A1- Post Construction



Example Zone Configuration (Retention Pond)

	Estimated Stage (ft)	Estimated Volume (ac-ft)	Outlet Type
Zone 1 (WQCV)	1.11	0.078	Orifice Plate
Zone 2 (100-year)			Rectangular Orifice
Zone 3			Not Utilized
Total (all zones)		0.078	

User Input: Orifice at Underdrain Outlet (typically used to drain WQCV in a Filtration SCM)

Underdrain Orifice Invert Depth = ft (distance below the filtration media surface)
Underdrain Orifice Diameter = inches

Calculated Parameters for Underdrain

Underdrain Orifice Area = ft²
Underdrain Orifice Centroid = feet

User Input: Orifice Plate with one or more orifices or Elliptical Slot Weir (typically used to drain WQCV and/or EURV in a sedimentation SCM)

Calculated Parameters for Plate

Centroid of Lowest Orifice = 0.08 ft (relative to basin bottom at Stage = 0 ft)
Depth at top of Zone using Orifice Plate = 0.50 ft (relative to basin bottom at Stage = 0 ft)
Orifice Plate: Orifice Vertical Spacing = N/A inches
Orifice Plate: Orifice Area per Row = N/A sq. inches

WQ Orifice Area per Row = N/A ft²
Elliptical Half-Width = N/A feet
Elliptical Slot Centroid = N/A feet
Elliptical Slot Area = N/A ft²

User Input: Stage and Total Area of Each Orifice Row (numbered from lowest to highest)

	Row 1 (required)	Row 2 (optional)	Row 3 (optional)	Row 4 (optional)	Row 5 (optional)	Row 6 (optional)	Row 7 (optional)	Row 8 (optional)
Stage of Orifice Centroid (ft)	0.08	0.28	0.28					
Orifice Area (sq. inches)	0.31	0.20	0.20					

	Row 9 (optional)	Row 10 (optional)	Row 11 (optional)	Row 12 (optional)	Row 13 (optional)	Row 14 (optional)	Row 15 (optional)	Row 16 (optional)
Stage of Orifice Centroid (ft)								
Orifice Area (sq. inches)								

User Input: Vertical Orifice (Circular or Rectangular)

Calculated Parameters for Vertical Orifice

Invert of Vertical Orifice = 1.11 Not Selected ft (relative to basin bottom at Stage = 0 ft)
Depth at top of Zone using Vertical Orifice = 0.00 Not Selected ft (relative to basin bottom at Stage = 0 ft)
Vertical Orifice Height = 10.00 Not Selected inches
Vertical Orifice Width = 16.00 Not Selected inches

Vertical Orifice Area = 1.11 Not Selected ft²
Vertical Orifice Centroid = 0.42 Not Selected feet

User Input: Overflow Weir (Dropbox with Flat or Sloped Gate and Outlet Pipe OR Rectangular/Trapezoidal Weir and No Outlet Pipe)

Calculated Parameters for Overflow Weir

Overflow Weir Front Edge Height, Ho = Not Selected Not Selected ft (relative to basin bottom at Stage = 0 ft)
Overflow Weir Front Edge Length = Not Selected Not Selected feet
Overflow Weir Gate Slope = Not Selected Not Selected H:V
Horiz. Length of Weir Sides = Not Selected Not Selected feet
Overflow Gate Type = Not Selected Not Selected %
Debris Clogging % = Not Selected Not Selected %

Height of Gate Upper Edge, H₁ = Not Selected Not Selected feet
Overflow Weir Slope Length = Not Selected Not Selected feet
Gate Open Area / 100-yr Orifice Area = Not Selected Not Selected ft²
Overflow Gate Open Area w/o Debris = Not Selected Not Selected ft²
Overflow Gate Open Area w/ Debris = Not Selected Not Selected ft²

User Input: Outlet Pipe w/ Flow Restriction Plate (Circular Orifice, Restrictor Plate, or Rectangular Orifice)

Calculated Parameters for Outlet Pipe w/ Flow Restriction Plate

Depth to Invert of Outlet Pipe = Not Selected Not Selected ft (distance below basin bottom at Stage = 0 ft)
Circular Orifice Diameter = Not Selected Not Selected inches

Outlet Orifice Area = Not Selected Not Selected ft²
Outlet Orifice Centroid = Not Selected Not Selected feet
Half-Central Angle of Restrictor Plate on Pipe = Not Selected Not Selected radians

User Input: Emergency Spillway (Rectangular or Trapezoidal)

Calculated Parameters for Spillway

Spillway Invert Stage = 1.50 ft (relative to basin bottom at Stage = 0 ft)
Spillway Crest Length = 100.00 feet
Spillway End Slopes = 0.00 H:V
Freeboard above Max Water Surface = 0.00 feet

Spillway Design Flow Depth = 0.25 feet
Stage at Top of Freeboard = 1.75 feet
Basin Area at Top of Freeboard = 1.40 acres
Basin Volume at Top of Freeboard = 0.66 acre-ft


Routed Hydrograph Results

The user can override the default CUHP hydrographs and runoff volumes by entering new values in the Inflow Hydrographs table (Columns W through AF).

	WQCV	EURV	2 Year	5 Year	10 Year	25 Year	50 Year	100 Year	500 Year
Design Storm Return Period	N/A	N/A	1.19	1.50	1.75	2.00	2.25	2.52	3.14
One-Hour Rainfall Depth (in)	N/A	N/A	1.19	1.50	1.75	2.00	2.25	2.52	3.14
CUHP Runoff Volume (acre-ft)	0.078	0.116	0.251	0.641	1.043	1.804	2.302	3.040	4.358
Inflow Hydrograph Volume (acre-ft)	N/A	N/A	0.251	0.641	1.043	1.804	2.302	3.040	4.358
CUHP Predevelopment Peak Q (cfs)	N/A	N/A	4.0	10.0	14.7	25.3	31.6	39.3	54.5
OPTIONAL Override Predevelopment Peak Q (cfs)	N/A	N/A							
Predevelopment Unit Peak Flow, q (cfs/acre)	N/A	N/A	0.15	0.39	0.57	0.97	1.21	1.51	2.10
Peak Inflow Q (cfs)	N/A	N/A	4.0	10.0	14.7	25.3	31.6	39.3	54.5
Peak Outflow Q (cfs)	0.0	0.1	0.4	4.0	9.3	21.3	27.5	36.1	51.8
Ratio Peak Outflow to Predevelopment Q	N/A	N/A	N/A	0.4	0.6	0.8	0.9	0.9	1.0
Structure Controlling Flow	Vertical Orifice 1	Vertical Orifice 1	Vertical Orifice 1	Spillway	Spillway	Spillway	Spillway	Spillway	Spillway
Max Velocity through Gate 1 (fps)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Max Velocity through Gate 2 (fps)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Time to Drain 97% of Inflow Volume (hours)	47	59	65	59	52	39	31	20	11
Time to Drain 99% of Inflow Volume (hours)	52	64	70	69	66	61	57	53	45
Maximum Ponding Depth (ft)	1.11	1.19	1.34	1.55	1.59	1.66	1.69	1.73	1.80
Area at Maximum Ponding Depth (acres)	0.41	0.53	0.77	1.07	1.14	1.26	1.31	1.37	1.47
Maximum Volume Stored (acre-ft)	0.080	0.118	0.215	0.399	0.444	0.539	0.578	0.631	0.731

DETENTION BASIN OUTLET STRUCTURE DESIGN

MHFD-Detention, Version 4.07 (June 2025)



S-A-V-D Chart Axis Override	X-axis	Left Y-Axis	Right Y-Axis
minimum bound			
maximum bound			

DETENTION BASIN OUTLET STRUCTURE DESIGN

Outflow Hydrograph Workbook Filename:

Inflow Hydrographs

The user can override the calculated inflow hydrographs from this workbook with inflow hydrographs developed in a separate program.

	SOURCE	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP
Time Interval	TIME	WQCV [cfs]	EURV [cfs]	2 Year [cfs]	5 Year [cfs]	10 Year [cfs]	25 Year [cfs]	50 Year [cfs]	100 Year [cfs]	500 Year [cfs]
5.00_min	0:00:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	0:05:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	0:10:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	0:15:00	0	0.00	0.01	0.02	0.03	0.02	0.02	0.02	0.03
	0:20:00	0	0.00	0.05	0.21	0.40	0.05	0.05	0.08	0.37
	0:25:00	0	0.00	0.85	3.90	7.77	0.80	1.06	2.01	7.49
	0:30:00	0	0.00	3.28	9.00	13.64	14.75	19.32	23.30	34.90
	0:35:00	0	0.00	4.01	10.04	14.73	22.37	28.30	35.47	50.10
	0:40:00	0	0.00	3.92	9.48	13.86	25.30	31.58	39.30	54.52
	0:45:00	0	0.00	3.42	8.31	12.65	24.34	30.28	38.79	53.74
	0:50:00	0	0.00	3.00	7.36	11.26	23.32	29.04	37.17	51.49
	0:55:00	0	0.00	2.61	6.42	10.02	20.99	26.29	34.54	48.05
	1:00:00	0	0.00	2.30	5.66	9.05	18.83	23.77	32.14	44.97
	1:05:00	0	0.00	2.06	5.02	8.24	17.06	21.73	30.31	42.57
	1:10:00	0	0.00	1.80	4.42	7.46	15.03	19.29	26.82	38.06
	1:15:00	0	0.00	1.53	3.80	6.68	13.03	16.87	23.21	33.39
	1:20:00	0	0.00	1.27	3.17	5.67	11.06	14.35	19.66	28.36
	1:25:00	0	0.00	1.05	2.68	4.88	9.22	11.98	16.42	23.87
	1:30:00	0	0.00	0.93	2.39	4.30	7.91	10.31	14.09	20.53
	1:35:00	0	0.00	0.82	2.15	3.80	6.89	9.00	12.28	17.91
	1:40:00	0	0.00	0.73	1.90	3.35	6.04	7.89	10.73	15.65
	1:45:00	0	0.00	0.64	1.65	2.94	5.27	6.89	9.34	13.61
	1:50:00	0	0.00	0.56	1.41	2.53	4.57	5.98	8.05	11.75
	1:55:00	0	0.00	0.47	1.17	2.13	3.90	5.11	6.85	10.00
	2:00:00	0	0.00	0.38	0.94	1.72	3.25	4.27	5.73	8.36
	2:05:00	0	0.00	0.29	0.71	1.32	2.61	3.44	4.65	6.78
	2:10:00	0	0.00	0.20	0.48	0.93	1.97	2.61	3.59	5.22
	2:15:00	0	0.00	0.11	0.27	0.59	1.34	1.80	2.53	3.72
	2:20:00	0	0.00	0.05	0.14	0.40	0.78	1.09	1.59	2.45
	2:25:00	0	0.00	0.03	0.09	0.30	0.47	0.70	1.04	1.67
	2:30:00	0	0.00	0.02	0.07	0.23	0.29	0.46	0.69	1.15
	2:35:00	0	0.00	0.02	0.05	0.17	0.18	0.30	0.44	0.77
	2:40:00	0	0.00	0.01	0.04	0.13	0.11	0.19	0.27	0.50
	2:45:00	0	0.00	0.01	0.03	0.10	0.07	0.12	0.15	0.30
	2:50:00	0	0.00	0.01	0.02	0.07	0.04	0.07	0.07	0.16
	2:55:00	0	0.00	0.00	0.02	0.05	0.02	0.04	0.03	0.08
	3:00:00	0	0.00	0.00	0.01	0.03	0.02	0.03	0.02	0.06
	3:05:00	0	0.00	0.00	0.01	0.02	0.01	0.02	0.02	0.04
	3:10:00	0	0.00	0.00	0.01	0.01	0.01	0.02	0.01	0.03
	3:15:00	0	0.00	0.00	0.00	0.01	0.01	0.01	0.01	0.02
	3:20:00	0	0.00	0.00	0.00	0.01	0.00	0.01	0.01	0.02
	3:25:00	0	0.00	0.00	0.00	0.00	0.00	0.01	0.01	0.01
	3:30:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.01
	3:35:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:40:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:45:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:50:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:55:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:00:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:05:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:10:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:15:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:20:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:25:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:30:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:35:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:40:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:45:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:50:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:55:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:00:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:05:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:10:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:15:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:20:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:25:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:30:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:35:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:40:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:45:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:50:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:55:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	6:00:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

DETENTION BASIN OUTLET STRUCTURE DESIGN

MHFD-Detention, Version 4.07 (June 2025)

Summary Stage-Area-Volume-Discharge Relationships

The user can create a summary S-A-V-D by entering the desired stage increments and the remainder of the table will populate automatically.

The user should graphically compare the summary S-A-V-D table to the full S-A-V-D table in the chart to confirm it captures all key transition points.

[illegible]

SDI-Design Data v2.00, Released January 2020

Facility Location & Jurisdiction: El Paso County

Extended Detention Basin (EDB)	EDB	
Watershed Area =	26.00	acres
Watershed Length =	1,370	ft
Watershed Length to Centroid =	685	ft
Watershed Slope =	0.030	ft/ft
Watershed Imperviousness =	5.0%	percent
Percentage Hydrologic Soil Group A =	0.0%	percent
Percentage Hydrologic Soil Group B =	100.0%	percent
Percentage Hydrologic Soil Groups C/D =	0.0%	percent
Target WQCV Drain Time =	40.0	hours
Location for 1-hr Rainfall Depths (use dropdown):		
User Input		


Once CUHP has been run and the Stage-Area-Discharge information has been provided, click 'Process Data' to interpolate the Stage-Area-Volume-Discharge data and generate summary results in the table below. Once this is complete, click 'Print to PDF'.

[illegible]

Create a new stormwater facility, and attach the PDF of this worksheet to that record.


Design Storm Return Period =		WQCV	2 Year	5 Year	10 Year	50 Year	100 Year	
One-Hour Rainfall Depth =	N/A	1.19	1.50	1.75	2.25	2.52		in
CUHP Runoff Volume =	0.078	0.251	0.641	1.043	2.302	3.040		acre-ft
Inflow Hydrograph Volume =	N/A	0.251	0.641	1.043	2.302	3.040		acre-ft
Time to Drain 97% of Inflow Volume =	26.1	27.1	20.2	12.9	9.0	7.9		hours
Time to Drain 99% of Inflow Volume =	29.5	32.1	30.0	26.8	18.0	13.5		hours
Maximum Ponding Depth =	1.11	1.32	1.44	1.48	1.58	1.63		ft
Maximum Poned Area =	0.40	0.73	0.93	0.98	1.14	1.22		acres
Maximum Volume Stored =	0.079	0.197	0.302	0.335	0.445	0.505		acre-ft

Stormwater Detention and Infiltration Design Data Sheet




MHFD-Detention, Version 4.07 (June 2025)

Basin ID: Pond B-Post Construction



DETENTION BASIN STAGE-STORAGE TABLE BUILDER


MHFD-Detention, Version 4.07 (June 2025)



DETENTION BASIN OUTLET STRUCTURE DESIGN

MHFD-Detention, Version 4.07 (June 2025)

Project: Tanner Ranch Subdivision
Basin ID: Pond B-Post Construction



Example Zone Configuration (Retention Pond)

	Estimated Stage (ft)	Estimated Volume (ac-ft)	Outlet Type
Zone 1 (WQCV)	0.77	0.750	Orifice Plate
Zone 2 (100-year)			Rectangular Orifice
Zone 3			Not Utilized
Total (all zones)		0.750	

User Input: Orifice at Underdrain Outlet (typically used to drain WQCV in a Filtration SCM)

Underdrain Orifice Invert Depth = N/A ft (distance below the filtration media surface)
Underdrain Orifice Diameter = N/A inches

Calculated Parameters for Underdrain

Underdrain Orifice Area = N/A ft²
Underdrain Orifice Centroid = N/A feet

User Input: Orifice Plate with one or more orifices or Elliptical Slot Weir (typically used to drain WQCV and/or EURV in a sedimentation SCM)

Calculated Parameters for Plate

Centroid of Lowest Orifice = 0.08 ft (relative to basin bottom at Stage = 0 ft)
Depth at top of Zone using Orifice Plate = 1.50 ft (relative to basin bottom at Stage = 0 ft)
Orifice Plate: Orifice Vertical Spacing = N/A inches
Orifice Plate: Orifice Area per Row = N/A sq. inches

WQ Orifice Area per Row = N/A ft²
Elliptical Half-Width = N/A feet
Elliptical Slot Centroid = N/A feet
Elliptical Slot Area = N/A ft²

User Input: Stage and Total Area of Each Orifice Row (numbered from lowest to highest)

	Row 1 (required)	Row 2 (optional)	Row 3 (optional)	Row 4 (optional)	Row 5 (optional)	Row 6 (optional)	Row 7 (optional)	Row 8 (optional)
Stage of Orifice Centroid (ft)	0.00	0.33	0.33					
Orifice Area (sq. inches)	5.94	7.07	7.07					

	Row 9 (optional)	Row 10 (optional)	Row 11 (optional)	Row 12 (optional)	Row 13 (optional)	Row 14 (optional)	Row 15 (optional)	Row 16 (optional)
Stage of Orifice Centroid (ft)								
Orifice Area (sq. inches)								

User Input: Vertical Orifice (Circular or Rectangular)

Calculated Parameters for Vertical Orifice

	Zone 2 Rectangular	Not Selected	
Invert of Vertical Orifice =	0.77	N/A	ft (relative to basin bottom at Stage = 0 ft)
Depth at top of Zone using Vertical Orifice =	0.00	N/A	ft (relative to basin bottom at Stage = 0 ft)
Vertical Orifice Height =	12.00	N/A	inches
Vertical Orifice Width =	22.00		inches

	Zone 2 Rectangular	Not Selected	
Vertical Orifice Area =	1.83	N/A	ft ²
Vertical Orifice Centroid =	0.50	N/A	feet

User Input: Overflow Weir (Dropbox with Flat or Sloped Gate and Outlet Pipe OR Rectangular/Trapezoidal Weir and No Outlet Pipe)

Calculated Parameters for Overflow Weir

	Not Selected	Not Selected	
Overflow Weir Front Edge Height, Ho =	N/A	N/A	ft (relative to basin bottom at Stage = 0 ft)
Overflow Weir Front Edge Length =	N/A	N/A	feet
Overflow Weir Gate Slope =	N/A	N/A	H:V
Horiz. Length of Weir Sides =	N/A	N/A	feet
Overflow Gate Type =	N/A	N/A	
Debris Clogging % =	N/A	N/A	%

	Not Selected	Not Selected	
Height of Gate Upper Edge, H ₁ =	N/A	N/A	feet
Overflow Weir Slope Length =	N/A	N/A	feet
Grate Open Area / 100-yr Orifice Area =	N/A	N/A	
Overflow Grate Open Area w/o Debris =	N/A	N/A	ft ²
Overflow Grate Open Area w/ Debris =	N/A	N/A	ft ²

User Input: Outlet Pipe w/ Flow Restriction Plate (Circular Orifice, Restrictor Plate, or Rectangular Orifice)

Calculated Parameters for Outlet Pipe w/ Flow Restriction Plate

	Not Selected	Not Selected	
Depth to Invert of Outlet Pipe =	N/A	N/A	ft (distance below basin bottom at Stage = 0 ft)
Circular Orifice Diameter =	N/A	N/A	inches

	Not Selected	Not Selected	
Outlet Orifice Area =	N/A	N/A	ft ²
Outlet Orifice Centroid =	N/A	N/A	feet
Half-Central Angle of Restrictor Plate on Pipe =	N/A	N/A	radians

User Input: Emergency Spillway (Rectangular or Trapezoidal)

Calculated Parameters for Spillway

Spillway Invert Stage =	2.50	ft (relative to basin bottom at Stage = 0 ft)
Spillway Crest Length =	300.00	feet
Spillway End Slopes =	0.00	H:V
Freeboard above Max Water Surface =	0.00	feet

Spillway Design Flow Depth =	0.41	feet
Stage at Top of Freeboard =	2.91	feet
Basin Area at Top of Freeboard =	5.28	acres
Basin Volume at Top of Freeboard =	8.74	acre-ft


Routed Hydrograph Results

The user can override the default CUHP hydrographs and runoff volumes by entering new values in the Inflow Hydrographs table (Columns W through AF).

	WQCV	EURV	2 Year	5 Year	10 Year	25 Year	50 Year	100 Year	500 Year
Design Storm Return Period =	N/A	N/A	1.19	1.50	1.75	2.00	2.25	2.52	3.14
One-Hour Rainfall Depth (in) =	N/A	N/A	1.19	1.50	1.75	2.00	2.25	2.52	3.14
CUHP Runoff Volume (acre-ft) =	0.750	1.107	2.415	6.163	10.034	17.347	22.143	29.237	41.906
Inflow Hydrograph Volume (acre-ft) =	N/A	N/A	2.415	6.163	10.034	17.347	22.143	29.237	41.906
CUHP Predevelopment Peak Q (cfs) =	N/A	N/A	22.1	55.5	84.0	150.3	188.1	242.3	338.2
OPTIONAL Override Predevelopment Peak Q (cfs) =	N/A	N/A							
Predevelopment Unit Peak Flow, q (cfs/acre) =	N/A	N/A	0.09	0.22	0.34	0.60	0.76	0.97	1.36
Peak Inflow Q (cfs) =	N/A	N/A	22.1	55.5	84.0	150.3	188.1	242.3	338.2
Peak Outflow Q (cfs) =	0.5	0.8	2.5	8.5	25.2	100.8	148.3	216.9	323.1
Ratio Peak Outflow to Predevelopment Q =	N/A	N/A	N/A	0.2	0.3	0.7	0.8	0.9	1.0
Structure Controlling Flow =	Vertical Orifice 1	Vertical Orifice 1	Vertical Orifice 1	Vertical Orifice 1	Spillway	Spillway	Spillway	Spillway	Spillway
Max Velocity through Gate 1 (fps) =	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Max Velocity through Gate 2 (fps) =	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Time to Drain 97% of Inflow Volume (hours) =	39	44	49	43	40	33	30	25	18
Time to Drain 99% of Inflow Volume (hours) =	42	49	57	57	54	47	44	41	37
Maximum Ponding Depth (ft) =	0.77	0.94	1.27	2.02	2.56	2.71	2.78	2.87	2.99
Area at Maximum Ponding Depth (acres) =	1.88	2.29	2.89	4.05	4.82	5.02	5.11	5.23	5.39
Maximum Volume Stored (acre-ft) =	0.755	1.109	1.970	4.579	6.974	7.711	8.066	8.531	9.168

DETENTION BASIN OUTLET STRUCTURE DESIGN

MHFD-Detention, Version 4.07 (June 2025)



S-A-V-D Chart Axis Override	X-axis	Left Y-Axis	Right Y-Axis
minimum bound			
maximum bound			

DETENTION BASIN OUTLET STRUCTURE DESIGN

Outflow Hydrograph Workbook Filename:

Inflow Hydrographs

The user can override the calculated inflow hydrographs from this workbook with inflow hydrographs developed in a separate program.

	SOURCE	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP
Time Interval	TIME	WQCV [cfs]	EURV [cfs]	2 Year [cfs]	5 Year [cfs]	10 Year [cfs]	25 Year [cfs]	50 Year [cfs]	100 Year [cfs]	500 Year [cfs]
5.00_min	0:00:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	0:05:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	0:10:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.01
	0:15:00	0	0.00	0.02	0.03	0.03	0.02	0.03	0.03	0.05
	0:20:00	0	0.00	0.08	0.30	0.54	0.09	0.11	0.15	0.53
	0:25:00	0	0.00	1.15	5.24	10.41	1.10	1.45	2.69	10.10
	0:30:00	0	0.00	5.78	19.19	32.97	19.90	26.13	33.08	59.07
	0:35:00	0	0.00	12.71	36.21	57.14	58.44	75.44	93.87	143.89
	0:40:00	0	0.00	18.38	48.61	73.95	98.32	124.98	155.79	226.58
	0:45:00	0	0.00	21.43	54.45	81.92	127.64	160.73	201.54	286.05
	0:50:00	0	0.00	22.14	55.49	83.97	143.57	179.83	227.50	319.80
	0:55:00	0	0.00	21.70	54.05	82.32	150.31	188.08	239.99	335.83
	1:00:00	0	0.00	20.51	50.69	77.83	149.43	187.25	242.32	338.24
	1:05:00	0	0.00	18.85	46.51	72.61	142.77	179.44	236.75	331.00
	1:10:00	0	0.00	17.31	42.92	68.47	133.91	169.20	227.11	319.20
	1:15:00	0	0.00	16.05	39.95	65.00	125.25	159.24	215.41	304.67
	1:20:00	0	0.00	14.84	37.06	61.35	116.38	148.71	201.44	286.65
	1:25:00	0	0.00	13.63	34.14	57.24	107.31	137.57	186.09	265.97
	1:30:00	0	0.00	12.50	31.56	53.41	98.35	126.32	170.66	244.96
	1:35:00	0	0.00	11.61	29.54	50.00	90.87	116.88	157.36	226.40
	1:40:00	0	0.00	10.85	27.70	46.75	84.35	108.57	145.73	209.86
	1:45:00	0	0.00	10.14	25.87	43.57	78.46	101.00	135.30	194.82
	1:50:00	0	0.00	9.44	24.03	40.47	72.91	93.85	125.65	180.83
	1:55:00	0	0.00	8.74	22.19	37.45	67.60	87.03	116.38	167.47
	2:00:00	0	0.00	8.04	20.36	34.44	62.39	80.36	107.38	154.54
	2:05:00	0	0.00	7.34	18.52	31.42	57.24	73.78	98.59	141.89
	2:10:00	0	0.00	6.63	16.69	28.40	52.14	67.25	90.00	129.51
	2:15:00	0	0.00	5.93	14.88	25.42	47.05	60.73	81.44	117.18
	2:20:00	0	0.00	5.29	13.39	23.08	42.03	54.31	73.03	105.50
	2:25:00	0	0.00	4.86	12.39	21.39	38.17	49.42	66.44	96.25
	2:30:00	0	0.00	4.55	11.61	19.98	35.23	45.65	61.29	88.86
	2:35:00	0	0.00	4.28	10.91	18.68	32.80	42.48	56.87	82.43
	2:40:00	0	0.00	4.02	10.24	17.46	30.63	39.63	52.93	76.64
	2:45:00	0	0.00	3.77	9.58	16.28	28.66	37.03	49.32	71.34
	2:50:00	0	0.00	3.52	8.93	15.13	26.79	34.57	45.95	66.38
	2:55:00	0	0.00	3.27	8.30	14.01	24.98	32.21	42.80	61.73
	3:00:00	0	0.00	3.03	7.67	12.93	23.24	29.94	39.86	57.40
	3:05:00	0	0.00	2.79	7.05	11.89	21.52	27.72	36.97	53.20
	3:10:00	0	0.00	2.55	6.43	10.87	19.81	25.53	34.10	49.05
	3:15:00	0	0.00	2.31	5.82	9.87	18.11	23.35	31.24	44.92
	3:20:00	0	0.00	2.08	5.21	8.87	16.41	21.17	28.37	40.80
	3:25:00	0	0.00	1.84	4.60	7.88	14.71	18.99	25.51	36.68
	3:30:00	0	0.00	1.60	4.00	6.89	13.02	16.82	22.65	32.57
	3:35:00	0	0.00	1.37	3.40	5.90	11.32	14.65	19.79	28.46
	3:40:00	0	0.00	1.13	2.80	4.92	9.63	12.49	16.93	24.36
	3:45:00	0	0.00	0.89	2.19	3.94	7.93	10.32	14.07	20.26
	3:50:00	0	0.00	0.66	1.59	2.96	6.24	8.16	11.22	16.17
	3:55:00	0	0.00	0.43	1.00	2.00	4.55	6.01	8.37	12.09
	4:00:00	0	0.00	0.22	0.53	1.28	2.89	3.88	5.59	8.27
	4:05:00	0	0.00	0.10	0.30	0.90	1.70	2.39	3.57	5.52
	4:10:00	0	0.00	0.06	0.21	0.69	1.03	1.54	2.34	3.78
	4:15:00	0	0.00	0.05	0.16	0.53	0.64	1.01	1.53	2.58
	4:20:00	0	0.00	0.04	0.12	0.41	0.38	0.65	0.96	1.71
	4:25:00	0	0.00	0.03	0.09	0.31	0.23	0.42	0.56	1.08
	4:30:00	0	0.00	0.02	0.07	0.23	0.14	0.27	0.29	0.63
	4:35:00	0	0.00	0.01	0.05	0.16	0.08	0.16	0.13	0.33
	4:40:00	0	0.00	0.01	0.04	0.11	0.05	0.10	0.07	0.19
	4:45:00	0	0.00	0.01	0.03	0.07	0.04	0.07	0.05	0.13
	4:50:00	0	0.00	0.01	0.02	0.05	0.03	0.05	0.04	0.10
	4:55:00	0	0.00	0.01	0.01	0.03	0.02	0.04	0.03	0.08
	5:00:00	0	0.00	0.00	0.01	0.03	0.01	0.03	0.02	0.06
	5:05:00	0	0.00	0.00	0.00	0.02	0.01	0.02	0.02	0.04
	5:10:00	0	0.00	0.00	0.00	0.01	0.01	0.01	0.01	0.03
	5:15:00	0	0.00	0.00	0.00	0.01	0.00	0.01	0.01	0.02
	5:20:00	0	0.00	0.00	0.00	0.00	0.00	0.01	0.00	0.01
	5:25:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:30:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:35:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:40:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:45:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:50:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:55:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	6:00:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

DETENTION BASIN OUTLET STRUCTURE DESIGN

MHFD-Detention, Version 4.07 (June 2025)

Summary Stage-Area-Volume-Discharge Relationships

The user can create a summary S-A-V-D by entering the desired stage increments and the remainder of the table will populate automatically.

The user should graphically compare the summary S-A-V-D table to the full S-A-V-D table in the chart to confirm it captures all key transition points.

[illegible]

SDI-Design Data v2.00, Released January 2020

Facility Location & Jurisdiction: El Paso County

Extended Detention Basin (EDB)	EDB	
Watershed Area =	249.00	acres
Watershed Length =	5,185	ft
Watershed Length to Centroid =	2,592	ft
Watershed Slope =	0.010	ft/ft
Watershed Imperviousness =	5.0%	percent
Percentage Hydrologic Soil Group A =	0.0%	percent
Percentage Hydrologic Soil Group B =	100.0%	percent
Percentage Hydrologic Soil Groups C/D =	0.0%	percent
Target WQCV Drain Time =	40.0	hours
Location for 1-hr Rainfall Depths (use dropdown):		
User Input		



Once CUHP has been run and the Stage-Area-Discharge information has been provided, click 'Process Data' to interpolate the Stage-Area-Volume-Discharge data and generate summary results in the table below. Once this is complete, click 'Print to PDF'.

[illegible]


Create a new stormwater facility, and attach the PDF of this worksheet to that record.

Design Storm Return Period =		WQCV	2 Year	5 Year	10 Year	50 Year	100 Year	
One-Hour Rainfall Depth =	N/A	1.19	1.50	1.75	2.25	2.52		in
CUHP Runoff Volume =	0.750	2.415	6.163	10.034	22.143	29.237		acre-ft
Inflow Hydrograph Volume =	N/A	2.415	6.163	10.034	22.143	29.237		acre-ft
Time to Drain 97% of Inflow Volume =	29.3	38.6	37.6	35.4	26.2	22.7		hours
Time to Drain 99% of Inflow Volume =	33.3	44.3	45.8	45.4	39.0	36.2		hours
Maximum Ponding Depth =	0.77	1.26	2.02	2.53	2.72	2.82		ft
Maximum Poned Area =	1.88	2.86	4.05	4.77	5.03	5.16		acres
Maximum Volume Stored =	0.754	1.931	4.594	6.822	7.758	8.260		acre-ft

Stormwater Detention and Infiltration Design Data Sheet




MHFD-Detention, Version 4.07 (June 2025)

Basin ID: Pond C-Post Construction[illegible]

DETENTION BASIN STAGE-STORAGE TABLE BUILDER


MHFD-Detention, Version 4.07 (June 2025)



DETENTION BASIN OUTLET STRUCTURE DESIGN

MHFD-Detention, Version 4.07 (June 2025)

Project: Tanner Ranch Subdivision
Basin ID: Pond C-Post Construction



Example Zone Configuration (Retention Pond)

	Estimated Stage (ft)	Estimated Volume (ac-ft)	Outlet Type
Zone 1 (WQCV)	0.90	0.525	Orifice Plate
Zone 2 (100-year)	2.08	3.223	Rectangular Orifice
Zone 3			Not Utilized
Total (all zones)		3.748	

User Input: Orifice at Underdrain Outlet (typically used to drain WOCV in a Filtration SCM)

Underdrain Orifice Invert Depth = N/A ft (distance below the filtration media surface)
Underdrain Orifice Diameter = N/A inches

Calculated Parameters for Underdrain

Underdrain Orifice Area = N/A ft²
Underdrain Orifice Centroid = N/A feet

User Input: Orifice Plate with one or more orifices or Elliptical Slot Weir (typically used to drain WOCV and/or EURV in a sedimentation SCM)

Calculated Parameters for Plate

Centroid of Lowest Orifice = 0.08 ft (relative to basin bottom at Stage = 0 ft)
Depth at top of Zone using Orifice Plate = 0.50 ft (relative to basin bottom at Stage = 0 ft)
Orifice Plate: Orifice Vertical Spacing = N/A inches
Orifice Plate: Orifice Area per Row = N/A sq. inches

WQ Orifice Area per Row = N/A ft²
Elliptical Half-Width = N/A feet
Elliptical Slot Centroid = N/A feet
Elliptical Slot Area = N/A ft²

User Input: Stage and Total Area of Each Orifice Row (numbered from lowest to highest)

	Row 1 (required)	Row 2 (optional)	Row 3 (optional)	Row 4 (optional)	Row 5 (optional)	Row 6 (optional)	Row 7 (optional)	Row 8 (optional)
Stage of Orifice Centroid (ft)	0.08	0.28	0.28					
Orifice Area (sq. inches)	3.14	3.14	3.14					

	Row 9 (optional)	Row 10 (optional)	Row 11 (optional)	Row 12 (optional)	Row 13 (optional)	Row 14 (optional)	Row 15 (optional)	Row 16 (optional)
Stage of Orifice Centroid (ft)								
Orifice Area (sq. inches)								

User Input: Vertical Orifice (Circular or Rectangular)

Calculated Parameters for Vertical Orifice

Invert of Vertical Orifice = 0.90 ft (relative to basin bottom at Stage = 0 ft)
Depth at top of Zone using Vertical Orifice = 2.08 ft (relative to basin bottom at Stage = 0 ft)
Vertical Orifice Height = 24.00 inches
Vertical Orifice Width = 25.00 inches

Zone 2 Rectangular Not Selected
Vertical Orifice Area = 4.17 ft²
Vertical Orifice Centroid = 1.00 ft

User Input: Overflow Weir (Dropbox with Flat or Sloped Gate and Outlet Pipe OR Rectangular/Trapezoidal Weir and No Outlet Pipe)

Calculated Parameters for Overflow Weir

Overflow Weir Front Edge Height, Ho = N/A ft (relative to basin bottom at Stage = 0 ft)
Overflow Weir Front Edge Length = N/A feet
Overflow Weir Grate Slope = N/A H:V
Horiz. Length of Weir Sides = N/A feet
Overflow Grate Type = N/A
Debris Clogging % = N/A %

Not Selected Not Selected
Height of Grate Upper Edge, H₁ = N/A feet
Overflow Weir Slope Length = N/A feet
Grate Open Area / 100-yr Orifice Area = N/A
Overflow Grate Open Area w/o Debris = N/A ft²
Overflow Grate Open Area w/ Debris = N/A ft²

User Input: Outlet Pipe w/ Flow Restriction Plate (Circular Orifice, Restrictor Plate, or Rectangular Orifice)

Calculated Parameters for Outlet Pipe w/ Flow Restriction Plate

Depth to Invert of Outlet Pipe = N/A ft (distance below basin bottom at Stage = 0 ft)
Circular Orifice Diameter = N/A inches

Not Selected Not Selected
Outlet Orifice Area = N/A ft²
Outlet Orifice Centroid = N/A feet
Half-Central Angle of Restrictor Plate on Pipe = N/A radians

User Input: Emergency Spillway (Rectangular or Trapezoidal)

Calculated Parameters for Spillway

Spillway Invert Stage = 2.50 ft (relative to basin bottom at Stage = 0 ft)
Spillway Crest Length = 200.00 feet
Spillway End Slopes = 0.00 H:V
Freeboard above Max Water Surface = 0.00 feet

Spillway Design Flow Depth = 0.34 feet
Stage at Top of Freeboard = 2.84 feet
Basin Area at Top of Freeboard = 5.75 acres
Basin Volume at Top of Freeboard = 7.44 acre-ft


Routed Hydrograph Results

The user can override the default CUHP hydrographs and runoff volumes by entering new values in the Inflow Hydrographs table (Columns W through AF).

	WQCV	EURV	2 Year	5 Year	10 Year	25 Year	50 Year	100 Year	500 Year
Design Storm Return Period	N/A	N/A	1.19	1.50	1.75	2.00	2.25	2.52	3.14
One-Hour Rainfall Depth (in)	N/A	N/A	1.19	1.50	1.75	2.00	2.25	2.52	3.14
CUHP Runoff Volume (acre-ft)	0.525	0.652	0.483	1.542	3.347	7.827	10.770	15.842	24.236
Inflow Hydrograph Volume (acre-ft)	N/A	N/A	0.483	1.542	3.347	7.827	10.770	15.842	24.236
CUHP Predevelopment Peak Q (cfs)	N/A	N/A	4.0	12.7	27.4	65.3	89.3	124.1	186.8
OPTIONAL Override Predevelopment Peak Q (cfs)	N/A	N/A							
Predevelopment Unit Peak Flow, q (cfs/acre)	N/A	N/A	0.02	0.07	0.16	0.37	0.51	0.71	1.07
Peak Inflow Q (cfs)	N/A	N/A	4.0	12.7	27.4	65.3	89.3	124.1	186.8
Peak Outflow Q (cfs)	0.3	0.3	0.2	1.4	4.4	13.1	38.4	82.3	153.2
Ratio Peak Outflow to Predevelopment Q	N/A	N/A	N/A	0.1	0.2	0.2	0.4	0.7	0.8
Structure Controlling Flow	Vertical Orifice 1	Vertical Orifice 1	Plate	Vertical Orifice 1	Vertical Orifice 1	Vertical Orifice 1	Spillway	Spillway	Spillway
Max Velocity through Grate 1 (fps)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Max Velocity through Grate 2 (fps)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Time to Drain 97% of Inflow Volume (hours)	38	42	38	51	50	46	41	34	24
Time to Drain 99% of Inflow Volume (hours)	44	48	43	59	59	57	55	51	46
Maximum Ponding Depth (ft)	0.90	0.98	0.82	1.29	1.73	2.45	2.61	2.73	2.87
Area at Maximum Ponding Depth (acres)	1.48	1.68	1.27	2.33	3.23	4.76	5.17	5.45	5.81
Maximum Volume Stored (acre-ft)	0.533	0.659	0.409	1.261	2.489	5.343	6.186	6.771	7.559

DETENTION BASIN OUTLET STRUCTURE DESIGN

MHFD-Detention, Version 4.07 (June 2025)



S-A-V-D Chart Axis Override	X-axis	Left Y-Axis	Right Y-Axis
minimum bound			
maximum bound			

DETENTION BASIN OUTLET STRUCTURE DESIGN

Outflow Hydrograph Workbook Filename:

Inflow Hydrographs

The user can override the calculated inflow hydrographs from this workbook with inflow hydrographs developed in a separate program.

	SOURCE	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP
Time Interval	TIME	WQCV [cfs]	EURV [cfs]	2 Year [cfs]	5 Year [cfs]	10 Year [cfs]	25 Year [cfs]	50 Year [cfs]	100 Year [cfs]	500 Year [cfs]
5.00_min	0:00:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	0:05:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	0:10:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	0:15:00	0	0.00	0.01	0.02	0.02	0.01	0.02	0.02	0.03
	0:20:00	0	0.00	0.05	0.08	0.18	0.06	0.07	0.07	0.17
	0:25:00	0	0.00	0.55	0.97	3.20	0.49	0.70	0.82	2.94
	0:30:00	0	0.00	1.65	4.25	11.17	8.18	12.13	15.48	27.79
	0:35:00	0	0.00	2.80	8.47	19.96	24.90	35.73	46.80	75.54
	0:40:00	0	0.00	3.58	11.32	25.44	43.00	59.98	79.40	122.80
	0:45:00	0	0.00	3.91	12.53	27.44	56.19	77.24	103.33	156.55
	0:50:00	0	0.00	3.95	12.66	27.42	62.92	86.00	116.56	175.17
	0:55:00	0	0.00	3.85	12.41	26.66	65.32	89.29	122.72	184.30
	1:00:00	0	0.00	3.64	11.86	25.26	64.60	88.33	124.08	186.77
	1:05:00	0	0.00	3.35	11.01	23.29	61.68	84.35	121.92	184.16
	1:10:00	0	0.00	3.10	10.13	21.56	57.04	78.04	116.12	176.42
	1:15:00	0	0.00	2.90	9.59	20.44	52.97	72.72	110.00	167.91
	1:20:00	0	0.00	2.71	9.02	19.30	49.34	67.83	103.46	158.24
	1:25:00	0	0.00	2.53	8.42	18.08	45.94	63.16	96.52	147.71
	1:30:00	0	0.00	2.35	7.80	16.78	42.54	58.51	89.56	137.07
	1:35:00	0	0.00	2.20	7.23	15.60	39.28	54.05	82.66	126.58
	1:40:00	0	0.00	2.08	6.79	14.66	36.47	50.23	76.62	117.44
	1:45:00	0	0.00	1.97	6.41	13.81	34.11	46.99	71.50	109.62
	1:50:00	0	0.00	1.86	6.02	12.97	32.01	44.08	66.99	102.71
	1:55:00	0	0.00	1.76	5.65	12.14	30.02	41.32	62.73	96.14
	2:00:00	0	0.00	1.65	5.28	11.32	28.10	38.67	58.63	89.83
	2:05:00	0	0.00	1.54	4.91	10.50	26.21	36.05	54.62	83.67
	2:10:00	0	0.00	1.42	4.53	9.68	24.31	33.43	50.69	77.64
	2:15:00	0	0.00	1.30	4.16	8.86	22.42	30.82	46.84	71.75
	2:20:00	0	0.00	1.18	3.78	8.04	20.53	28.22	43.02	65.89
	2:25:00	0	0.00	1.07	3.41	7.23	18.64	25.62	39.20	60.05
	2:30:00	0	0.00	0.97	3.08	6.56	16.78	23.05	35.42	54.33
	2:35:00	0	0.00	0.90	2.85	6.12	15.24	20.97	32.27	49.63
	2:40:00	0	0.00	0.85	2.70	5.79	14.13	19.48	29.92	46.06
	2:45:00	0	0.00	0.80	2.55	5.48	13.28	18.30	27.98	43.06
	2:50:00	0	0.00	0.76	2.41	5.18	12.53	17.26	26.27	40.37
	2:55:00	0	0.00	0.72	2.27	4.88	11.85	16.31	24.70	37.92
	3:00:00	0	0.00	0.67	2.14	4.58	11.19	15.40	23.24	35.63
	3:05:00	0	0.00	0.63	2.00	4.29	10.55	14.51	21.84	33.47
	3:10:00	0	0.00	0.59	1.87	4.01	9.91	13.62	20.53	31.44
	3:15:00	0	0.00	0.55	1.75	3.73	9.27	12.75	19.25	29.48
	3:20:00	0	0.00	0.51	1.62	3.45	8.64	11.88	17.97	27.53
	3:25:00	0	0.00	0.47	1.49	3.18	8.01	11.01	16.70	25.57
	3:30:00	0	0.00	0.43	1.37	2.91	7.38	10.14	15.42	23.62
	3:35:00	0	0.00	0.39	1.24	2.64	6.75	9.28	14.15	21.67
	3:40:00	0	0.00	0.35	1.12	2.37	6.12	8.41	12.88	19.72
	3:45:00	0	0.00	0.31	0.99	2.10	5.49	7.55	11.61	17.77
	3:50:00	0	0.00	0.27	0.87	1.83	4.86	6.68	10.33	15.82
	3:55:00	0	0.00	0.23	0.74	1.56	4.24	5.82	9.06	13.87
	4:00:00	0	0.00	0.19	0.62	1.29	3.61	4.95	7.79	11.93
	4:05:00	0	0.00	0.15	0.50	1.02	2.98	4.09	6.52	9.98
	4:10:00	0	0.00	0.11	0.37	0.75	2.35	3.22	5.25	8.04
	4:15:00	0	0.00	0.08	0.25	0.49	1.73	2.36	3.98	6.09
	4:20:00	0	0.00	0.04	0.14	0.26	1.10	1.50	2.72	4.18
	4:25:00	0	0.00	0.03	0.07	0.14	0.57	0.78	1.63	2.59
	4:30:00	0	0.00	0.02	0.05	0.11	0.28	0.41	1.01	1.67
	4:35:00	0	0.00	0.02	0.04	0.09	0.15	0.22	0.64	1.09
	4:40:00	0	0.00	0.01	0.03	0.07	0.08	0.12	0.39	0.69
	4:45:00	0	0.00	0.01	0.02	0.05	0.04	0.07	0.23	0.41
	4:50:00	0	0.00	0.01	0.02	0.04	0.03	0.05	0.12	0.22
	4:55:00	0	0.00	0.01	0.01	0.03	0.02	0.03	0.05	0.09
	5:00:00	0	0.00	0.01	0.01	0.02	0.01	0.02	0.01	0.04
	5:05:00	0	0.00	0.01	0.01	0.01	0.01	0.01	0.01	0.03
	5:10:00	0	0.00	0.00	0.01	0.01	0.01	0.01	0.01	0.02
	5:15:00	0	0.00	0.00	0.00	0.01	0.01	0.01	0.01	0.02
	5:20:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.01
	5:25:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.01
	5:30:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.01
	5:35:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:40:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:45:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:50:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:55:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	6:00:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

DETENTION BASIN OUTLET STRUCTURE DESIGN

MHFD-Detention, Version 4.07 (June 2025)

Summary Stage-Area-Volume-Discharge Relationships

The user can create a summary S-A-V-D by entering the desired stage increments and the remainder of the table will populate automatically.

The user should graphically compare the summary S-A-V-D table to the full S-A-V-D table in the chart to confirm it captures all key transition points.

[illegible]

SDI-Design Data v2.00, Released January 2020

Facility Location & Jurisdiction: El Paso County

Extended Detention Basin (EDB)	▼	EDB	
Watershed Area =	174.40	acres	
Watershed Length =	5,662	ft	
Watershed Length to Centroid =	2,831	ft	
Watershed Slope =	0.015	ft/ft	
Watershed Imperviousness =	5.0%	percent	
Percentage Hydrologic Soil Group A =	50.0%	percent	
Percentage Hydrologic Soil Group B =	50.0%	percent	
Percentage Hydrologic Soil Groups C/D =	0.0%	percent	
Target WQCV Drain Time =	40.0	hours	

User Input



Once CUHP has been run and the Stage-Area-Discharge information has been provided, click 'Process Data' to interpolate the Stage-Area-Volume-Discharge data and generate summary results in the table below. Once this is complete, click 'Print to PDF'.

[illegible]

Create a new stormwater facility, and attach the PDF of this worksheet to that record.


	WQCV	2 Year	5 Year	10 Year	50 Year	100 Year	
Design Storm Return Period =							
One-Hour Rainfall Depth =	N/A	1.19	1.50	1.75	2.25	2.52	in
CUHP Runoff Volume =	0.525	0.483	1.542	3.347	10.770	15.842	acre-ft
Inflow Hydrograph Volume =	N/A	0.483	1.542	3.347	10.770	15.842	acre-ft
Time to Drain 97% of Inflow Volume =	31.0	30.8	43.7	43.8	35.7	29.6	hours
Time to Drain 99% of Inflow Volume =	33.8	33.4	48.3	50.8	48.0	44.7	hours
Maximum Ponding Depth =	0.90	0.81	1.27	1.72	2.57	2.66	ft
Maximum Poned Area =	1.48	1.26	2.30	3.22	5.06	5.31	acres
Maximum Volume Stored =	0.529	0.406	1.229	2.470	5.950	6.468	acre-ft

Stormwater Detention and Infiltration Design Data Sheet



MHFD-Detention, Version 4.07 (June 2025)

Basin ID: Pond D-Post Construction



Example Zone Configuration (Retention Pond)

Selected SCM Type =	EDB	
Watershed Area =	20.20	acres
Watershed Length =	1.066	ft
Watershed Length to Centroid =	533	ft
Watershed Slope =	0.020	ft/ft
Watershed Imperviousness =	5.00%	percent
Percentage Hydrologic Soil Group A =	50.0%	percent
Percentage Hydrologic Soil Group B =	0.0%	percent
Percentage Hydrologic Soil Group C/D =	50.0%	percent
Target WQCV Drain Time =	40.0	hours
Location for 1-hr Rainfall Depths = User Input		

Optional User Overrides

Water Quality Capture Volume (WQCV) =	0.061	acre-feet
Excess Urban Runoff Volume (EURV) =	0.070	acre-feet
2-yr Runoff Volume ($P1 = 1.19$ in.) =	0.061	acre-feet
5-yr Runoff Volume ($P1 = 1.5$ in.) =	0.260	acre-feet
10-yr Runoff Volume ($P1 = 1.75$ in.) =	0.482	acre-feet
25-yr Runoff Volume ($P1 = 2.1$) =	1.029	acre-feet
50-yr Runoff Volume ($P1 = 2.25$ in.) =	1.390	acre-feet
100-yr Runoff Volume ($P1 = 2.52$ in.) =	1.976	acre-feet
500-yr Runoff Volume ($P1 = 3.14$ in.) =	2.948	acre-feet
Approximate 2-yr Detention Volume =	0.049	acre-feet
Approximate 5-yr Detention Volume =	0.128	acre-feet
Approximate 10-yr Detention Volume =	0.189	acre-feet
Approximate 25-yr Detention Volume =	0.230	acre-feet
Approximate 50-yr Detention Volume =	0.262	acre-feet
Approximate 100-yr Detention Volume =	0.433	acre-feet


Zone 1 Volume (WQCV) =	0.061	acre-feet
Zone 2 Volume (100-year - Zone 1) =	0.372	acre-feet
Select Zone 3 Storage Volume (Optional) =		acre-feet
Total Detention Basin Volume =	0.433	acre-feet
Initial Surcharge Volume (ISV) =	user	ft ³
Initial Surcharge Depth (ISD) =	user	ft
Total Available Detention Depth (H_{total}) =	user	ft
Depth of Trickle Channel (H_{TC}) =	user	ft
Slope of Trickle Channel (ST_C) =	user	ft/ft
Slopes of Main Basin Sides (S_{main}) =	user	H:V
Basin Length-to-Width Ratio (R_{LW}) =	user	

Initial Surcharge Area (A_{ISV}) =	<u>user</u>	ft ²
Surcharge Volume Length (L_{SV}) =	<u>user</u>	ft
Surcharge Volume Width (W_{SV}) =	<u>user</u>	ft
Depth of Basin Floor (H_{FLOOR}) =	<u>user</u>	ft
Length of Basin Floor (L_{FLOOR}) =	<u>user</u>	ft
Width of Basin Floor (W_{FLOOR}) =	<u>user</u>	ft
Area of Basin Floor (A_{FLOOR}) =	<u>user</u>	ft ²
Volume of Basin Floor (V_{FLOOR}) =	<u>user</u>	ft ³
Depth of Main Basin (H_{MAIN}) =	<u>user</u>	ft
Length of Main Basin (L_{MAIN}) =	<u>user</u>	ft
Width of Main Basin (W_{MAIN}) =	<u>user</u>	ft
Area of Main Basin (A_{MAIN}) =	<u>user</u>	ft ²
Volume of Main Basin (V_{MAIN}) =	<u>user</u>	ft ³
Calculated Total Basin Volume (V_{TOTAL}) =	<u>user</u>	acre-feet

[illegible]

DETENTION BASIN STAGE-STORAGE TABLE BUILDER


MHFD-Detention, Version 4.07 (June 2025)



DETENTION BASIN OUTLET STRUCTURE DESIGN

MHFD-Detention, Version 4.07 (June 2025)

Project: Tanner Ranch Subdivision
Basin ID: Pond D-Post Construction



	Estimated Stage (ft)	Estimated Volume (ac-ft)	Outlet Type
Zone 1 (WQCV)	0.27	0.061	Orifice Plate
Zone 2 (100-year)	1.19	0.372	Rectangular Orifice
Zone 3			Not Utilized
Total (all zones)		0.433	

User Input: Orifice at Underdrain Outlet (typically used to drain WQCV in a Filtration SCM)

Underdrain Orifice Invert Depth = ft (distance below the filtration media surface)
Underdrain Orifice Diameter = inches

Calculated Parameters for Underdrain

Underdrain Orifice Area = ft²
Underdrain Orifice Centroid = feet

User Input: Orifice Plate with one or more orifices or Elliptical Slot Weir (typically used to drain WQCV and/or EURV in a sedimentation SCM)

Calculated Parameters for Plate

Centroid of Lowest Orifice = ft (relative to basin bottom at Stage = 0 ft)
Depth at top of Zone using Orifice Plate = ft (relative to basin bottom at Stage = 0 ft)
Orifice Plate: Orifice Vertical Spacing = inches
Orifice Plate: Orifice Area per Row = sq. inches

WQ Orifice Area per Row = ft²
Elliptical Half-Width = feet
Elliptical Slot Centroid = feet
Elliptical Slot Area = ft²

User Input: Stage and Total Area of Each Orifice Row (numbered from lowest to highest)

	Row 1 (required)	Row 2 (optional)	Row 3 (optional)	Row 4 (optional)	Row 5 (optional)	Row 6 (optional)	Row 7 (optional)	Row 8 (optional)
Stage of Orifice Centroid (ft)	0.00	0.28	0.28					
Orifice Area (sq. inches)	1.23	1.23	1.23					

	Row 9 (optional)	Row 10 (optional)	Row 11 (optional)	Row 12 (optional)	Row 13 (optional)	Row 14 (optional)	Row 15 (optional)	Row 16 (optional)
Stage of Orifice Centroid (ft)								
Orifice Area (sq. inches)								

User Input: Vertical Orifice (Circular or Rectangular)

Calculated Parameters for Vertical Orifice

	Zone 2 Rectangular	Not Selected	
Invert of Vertical Orifice =	0.27	N/A	ft (relative to basin bottom at Stage = 0 ft)
Depth at top of Zone using Vertical Orifice =	1.19	N/A	ft (relative to basin bottom at Stage = 0 ft)
Vertical Orifice Height =	12.00	N/A	inches
Vertical Orifice Width =	15.00		inches

	Zone 2 Rectangular	Not Selected	
Vertical Orifice Area =	1.25	N/A	ft ²
Vertical Orifice Centroid =	0.50	N/A	feet

User Input: Overflow Weir (Dropbox with Flat or Sloped Gate and Outlet Pipe OR Rectangular/Trapezoidal Weir and No Outlet Pipe)

Calculated Parameters for Overflow Weir

	Not Selected	Not Selected	
Overflow Weir Front Edge Height, Ho =	N/A	N/A	ft (relative to basin bottom at Stage = 0 ft)
Overflow Weir Front Edge Length =	N/A	N/A	feet
Overflow Weir Gate Slope =	N/A	N/A	H:V
Horiz. Length of Weir Sides =	N/A	N/A	feet
Overflow Gate Type =	N/A	N/A	
Debris Clogging % =	N/A	N/A	%

	Not Selected	Not Selected	
Height of Gate Upper Edge, H ₁ =	N/A	N/A	feet
Overflow Weir Slope Length =	N/A	N/A	feet
Grate Open Area / 100-yr Orifice Area =	N/A	N/A	
Overflow Grate Open Area w/o Debris =	N/A	N/A	ft ²
Overflow Grate Open Area w/ Debris =	N/A	N/A	ft ²

User Input: Outlet Pipe w/ Flow Restriction Plate (Circular Orifice, Restrictor Plate, or Rectangular Orifice)

Calculated Parameters for Outlet Pipe w/ Flow Restriction Plate

	Not Selected	Not Selected	
Depth to Invert of Outlet Pipe =	N/A	N/A	ft (distance below basin bottom at Stage = 0 ft)
Circular Orifice Diameter =	N/A	N/A	inches

	Not Selected	Not Selected	
Outlet Orifice Area =	N/A	N/A	ft ²
Outlet Orifice Centroid =	N/A	N/A	feet
Half-Central Angle of Restrictor Plate on Pipe =	N/A	N/A	radians

User Input: Emergency Spillway (Rectangular or Trapezoidal)

Calculated Parameters for Spillway

Spillway Invert Stage =	1.50	ft (relative to basin bottom at Stage = 0 ft)
Spillway Crest Length =	200.00	feet
Spillway End Slopes =	0.00	H:V
Freeboard above Max Water Surface =	0.00	feet

Spillway Design Flow Depth =	0.12	feet
Stage at Top of Freeboard =	1.62	feet
Basin Area at Top of Freeboard =	0.61	acres
Basin Volume at Top of Freeboard =	0.67	acre-ft


Routed Hydrograph Results

The user can override the default CUHP hydrographs and runoff volumes by entering new values in the Inflow Hydrographs table (Columns W through AF).

	WQCV	EURV	2 Year	5 Year	10 Year	25 Year	50 Year	100 Year	500 Year
Design Storm Return Period =	N/A	N/A	1.19	1.50	1.75	2.00	2.25	2.52	3.14
One-Hour Rainfall Depth (in) =	N/A	N/A	1.19	1.50	1.75	2.00	2.25	2.52	3.14
CUHP Runoff Volume (acre-ft) =	0.061	0.070	0.061	0.260	0.482	1.029	1.390	1.976	2.948
Inflow Hydrograph Volume (acre-ft) =	N/A	N/A	0.061	0.260	0.482	1.029	1.390	1.976	2.948
CUHP Predevelopment Peak Q (cfs) =	N/A	N/A	1.0	4.4	7.9	15.9	20.9	27.1	39.2
OPTIONAL Override Predevelopment Peak Q (cfs) =	N/A	N/A							
Predevelopment Unit Peak Flow, q (cfs/acre) =	N/A	N/A	0.05	0.22	0.39	0.79	1.03	1.34	1.94
Peak Inflow Q (cfs) =	N/A	N/A	1.0	4.4	7.9	15.9	20.9	27.1	39.2
Peak Outflow Q (cfs) =	0.0	0.0	0.0	0.8	2.1	5.2	14.2	25.8	37.7
Ratio Peak Outflow to Predevelopment Q =	N/A	N/A	N/A	0.2	0.3	0.3	0.7	1.0	1.0
Structure Controlling Flow =	Vertical Orifice 1	Vertical Orifice 1	Plate	Vertical Orifice 1	Vertical Orifice 1	Vertical Orifice 1	Spillway	Spillway	Spillway
Max Velocity through Gate 1 (fps) =	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Max Velocity through Gate 2 (fps) =	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Time to Drain 97% of Inflow Volume (hours) =	45	49	45	53	48	36	29	18	9
Time to Drain 99% of Inflow Volume (hours) =	47	51	47	59	57	52	49	45	37
Maximum Ponding Depth (ft) =	0.27	0.30	0.26	0.64	0.93	1.49	1.56	1.60	1.64
Area at Maximum Ponding Depth (acres) =	0.33	0.33	0.33	0.38	0.44	0.58	0.59	0.61	0.62
Maximum Volume Stored (acre-ft) =	0.062	0.072	0.056	0.190	0.308	0.590	0.631	0.661	0.685

DETENTION BASIN OUTLET STRUCTURE DESIGN

MHFD-Detention, Version 4.07 (June 2025)



S-A-V-D Chart Axis Override	X-axis	Left Y-Axis	Right Y-Axis
minimum bound			
maximum bound			

DETENTION BASIN OUTLET STRUCTURE DESIGN

Outflow Hydrograph Workbook Filename:

Inflow Hydrographs

The user can override the calculated inflow hydrographs from this workbook with inflow hydrographs developed in a separate program.

	SOURCE	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP
Time Interval	TIME	WQCV [cfs]	EURV [cfs]	2 Year [cfs]	5 Year [cfs]	10 Year [cfs]	25 Year [cfs]	50 Year [cfs]	100 Year [cfs]	500 Year [cfs]
5.00_min	0:00:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	0:05:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	0:10:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	0:15:00	0	0.00	0.01	0.02	0.02	0.01	0.02	0.02	0.03
	0:20:00	0	0.00	0.04	0.07	0.23	0.04	0.04	0.05	0.20
	0:25:00	0	0.00	0.56	1.13	4.17	0.51	0.73	0.84	3.90
	0:30:00	0	0.00	0.92	4.31	7.84	9.24	13.03	16.30	25.51
	0:35:00	0	0.00	0.96	4.38	7.93	14.21	18.96	24.83	36.50
	0:40:00	0	0.00	0.89	3.96	7.02	15.91	20.88	27.11	39.23
	0:45:00	0	0.00	0.78	3.38	6.07	14.94	19.64	26.46	38.25
	0:50:00	0	0.00	0.67	2.98	5.27	14.02	18.51	24.98	36.25
	0:55:00	0	0.00	0.58	2.58	4.60	12.21	16.24	22.78	33.36
	1:00:00	0	0.00	0.52	2.28	4.08	10.63	14.33	20.95	30.98
	1:05:00	0	0.00	0.46	2.03	3.62	9.30	12.75	19.54	29.11
	1:10:00	0	0.00	0.39	1.78	3.16	8.10	11.13	17.11	25.49
	1:15:00	0	0.00	0.33	1.51	2.70	6.96	9.55	14.68	21.84
	1:20:00	0	0.00	0.28	1.24	2.27	5.82	8.00	12.29	18.30
	1:25:00	0	0.00	0.24	1.05	1.96	4.85	6.69	10.28	15.39
	1:30:00	0	0.00	0.22	0.94	1.73	4.15	5.75	8.82	13.24
	1:35:00	0	0.00	0.19	0.83	1.53	3.62	5.01	7.66	11.51
	1:40:00	0	0.00	0.17	0.73	1.33	3.17	4.37	6.66	10.00
	1:45:00	0	0.00	0.15	0.63	1.14	2.75	3.79	5.75	8.63
	1:50:00	0	0.00	0.13	0.53	0.96	2.36	3.24	4.90	7.35
	1:55:00	0	0.00	0.11	0.43	0.77	1.98	2.71	4.10	6.15
	2:00:00	0	0.00	0.08	0.33	0.58	1.59	2.19	3.35	5.03
	2:05:00	0	0.00	0.06	0.24	0.40	1.21	1.67	2.62	3.93
	2:10:00	0	0.00	0.04	0.14	0.22	0.83	1.15	1.89	2.84
	2:15:00	0	0.00	0.02	0.06	0.11	0.46	0.65	1.17	1.81
	2:20:00	0	0.00	0.02	0.04	0.08	0.24	0.36	0.73	1.17
	2:25:00	0	0.00	0.01	0.03	0.06	0.12	0.20	0.46	0.77
	2:30:00	0	0.00	0.01	0.02	0.05	0.07	0.12	0.29	0.50
	2:35:00	0	0.00	0.01	0.02	0.04	0.03	0.07	0.17	0.31
	2:40:00	0	0.00	0.01	0.01	0.03	0.02	0.04	0.10	0.18
	2:45:00	0	0.00	0.01	0.01	0.02	0.02	0.03	0.04	0.09
	2:50:00	0	0.00	0.00	0.01	0.01	0.01	0.01	0.01	0.04
	2:55:00	0	0.00	0.00	0.00	0.01	0.01	0.01	0.01	0.02
	3:00:00	0	0.00	0.00	0.00	0.01	0.00	0.01	0.00	0.02
	3:05:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.01
	3:10:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.01
	3:15:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.01
	3:20:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.01
	3:25:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:30:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:35:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:40:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:45:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:50:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:55:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:00:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:05:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:10:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:15:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:20:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:25:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:30:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:35:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:40:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:45:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:50:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:55:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:00:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:05:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:10:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:15:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:20:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:25:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:30:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:35:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:40:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:45:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:50:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:55:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	6:00:00	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

DETENTION BASIN OUTLET STRUCTURE DESIGN

MHFD-Detention, Version 4.07 (June 2025)

Summary Stage-Area-Volume-Discharge Relationships

The user can create a summary S-A-V-D by entering the desired stage increments and the remainder of the table will populate automatically.

The user should graphically compare the summary S-A-V-D table to the full S-A-V-D table in the chart to confirm it captures all key transition points.

[illegible]

SDI-Design Data v2.00, Released January 2020

Facility Location & Jurisdiction: El Paso County

Extended Detention Basin (EDB)	▼	EDB	
Watershed Area =	20.20	acres	
Watershed Length =	1,066	ft	
Watershed Length to Centroid =	533	ft	
Watershed Slope =	0.020	ft/ft	
Watershed Imperviousness =	5.0%	percent	
Percentage Hydrologic Soil Group A =	50.0%	percent	
Percentage Hydrologic Soil Group B =	0.0%	percent	
Percentage Hydrologic Soil Groups C/D =	50.0%	percent	
Target WQCV Drain Time =	40.0	hours	
Location for 1-hr Rainfall Depths (use dropdown):			
User Input	▼		


Once CUHP has been run and the Stage-Area-Discharge information has been provided, click 'Process Data' to interpolate the Stage-Area-Volume-Discharge data and generate summary results in the table below. Once this is complete, click 'Print to PDF'.

[illegible]

Create a new stormwater facility, and attach the PDF of this worksheet to that record.

	WQCV	2 Year	5 Year	10 Year	50 Year	100 Year	
Design Storm Return Period =							
One-Hour Rainfall Depth =	N/A	1.19	1.50	1.75	2.25	2.52	in
CUHP Runoff Volume =	0.061	0.061	0.260	0.482	1.390	1.976	acre-ft
Inflow Hydrograph Volume =	N/A	0.061	0.260	0.482	1.390	1.976	acre-ft
Time to Drain 97% of Inflow Volume =	26.4	27.4	23.3	18.3	8.7	7.3	hours
Time to Drain 99% of Inflow Volume =	29.8	30.8	30.3	27.8	19.4	15.3	hours
Maximum Ponding Depth =	0.27	0.23	0.62	0.91	1.32	1.41	ft
Maximum Poned Area =	0.33	0.32	0.38	0.44	0.53	0.56	acres
Maximum Volume Stored =	0.061	0.048	0.185	0.302	0.499	0.551	acre-ft

Stormwater Detention and Infiltration Design Data Sheet



APPENDIX F – PREVIOUS DRAINAGE STUDIES



FINAL DRAINAGE REPORT FOR TANNER RANCH FILING NO. 1

January 17, 2005
Revised June 16, 2005
Revised July 18, 2005

Prepared for:


High Plains Land & Cattle, LLC
9 Ridge Road
Colorado Springs, CO 80904
(719) 475-0517

WestWorks Job #90330

FINAL DRAINAGE REPORT for TANNER RANCH FILING NO. 1

Engineer's Statement:

The attached drainage plan and report were prepared under my direction and supervision and are correct to the best of my knowledge and belief. Said drainage report has been prepared according the criteria established by the City/County for drainage reports and said report is in conformity with the master plan of the drainage basin. I accept responsibility for any liability caused by any negligent acts, errors, or omissions on my part in preparing this report.


Chad D. Kuzbek, Colorado PE #35751
For and on behalf of West Works Engineering


7/18/05
Date

Developer's Statement:

I, the developer have read and will comply with all of the requirements specified in this drainage report and plan.

Tanner Ranch, LLC

Business Name

By: 


Title: member / owner

Address: 9 Ridge Road

Colorado Springs, CO 80904

El Paso County, Colorado:

Filed in accordance with Section 51.1 of the El Paso County Land Development Code, as amended.


For the County Engineer

7-20-05
Date

Conditions:

FINAL DRAINAGE REPORT for TANNER RANCH FILING NO. 1

TABLE OF CONTENTS

Description	Page
Table of Contents	1
Engineer's Statement	2
Developer's Statement	2
El Paso County Approval	2
Purpose	3
General Location & Description	3
Drainage Basins & Sub-basins	4
Existing Drainage Conditions	4
Developed Drainage Conditions	4
Drainage Design Criteria	6
Drainage Facility Design	7
Floodplain Statement	7
Erosion Control Plan Statement	8
Drainage Fees	8
Opinion of Probable Cost	8
APPENDIX:	
Vicinity Map	
F.E.M.A. Floodplain Map	
S.C.S. Soils Map	
Time of Concentration Calculations	
Riprap Sizing Calculations	
WQCV Sizing Calculations	
Pond Outfall Structure Details	
Typical Road Section	
Typical Swale Sections	
Hydraulic Calculations	
Existing Conditions Hydrologic Analysis, Minor Storm	
Existing Conditions Hydrologic Analysis, Major Storm	
Developed Conditions Hydrologic Analysis, Minor Storm	
Developed Conditions Hydrologic Analysis, Major Storm	
Drainage Maps (Existing & Proposed Conditions)	

FINAL DRAINAGE REPORT for TANNER RANCH FILING NO. 1

Engineer's Statement:

The attached drainage plan and report were prepared under my direction and supervision and are correct to the best of my knowledge and belief. Said drainage report has been prepared according the criteria established by the City/County for drainage reports and said report is in conformity with the master plan of the drainage basin. I accept responsibility for any liability caused by any negligent acts, errors, or omissions on my part in preparing this report.

Chad D. Kuzbek, Colorado PE #35751
For and on behalf of WestWorks Engineering

Date

Developer's Statement:

I, the developer have read and will comply with all of the requirements specified in this drainage report and plan.

High Plains Land & Cattle, LLC

Business Name

By: _____

Title: _____

Address: 9 Ridge Road

Colorado Springs, CO 80904

El Paso County, Colorado:

Filed in accordance with Section 51.1 of the El Paso County Land Development Code, as amended.

For the County Engineer

Date

Conditions:

FINAL DRAINAGE REPORT for TANNER RANCH FILING NO. 1

PURPOSE

The purpose of this drainage report is to identify specific solutions to problems on site and off-site resulting from the development of this subdivision to be platted.

GENERAL LOCATION AND DESCRIPTION

Tanner Ranch Filing No. 1 is a 209-acre subdivision within a portion of Section 18, Township 14 south, Range 62 west of the 6th P.M. in El Paso County, Colorado. Filing No. 1 represents the first phase of the overall 480-acre subdivision approved for development. More specifically, the site is located on the south side State Hwy 94 between Ellicott to the east and Yoder to the west (see Vicinity Map in Appendix). The study area is in the Upper Pond Creek Drainage Basin. There are no Drainage or Bridge Fees currently in the Upper Pond Creek Drainage Basin.

The site is currently undeveloped and covered mostly with native grasses. The site is generally flat, sloping generally from northwest to southeast over grades of 1% to 3%. Proposed development of Filing No. 1 includes 46 low density single-family residential lots with public asphalt streets.

According to the Soil Survey of El Paso County, prepared by the Soil Conservation Service, existing soils consist of the following soil types (see map in Appendix):

- Map Symbol 96 – “Truckton sandy loam”: slow surface runoff, moderate erosion hazard (Hydrologic Soil Group ‘B’)
- Map Symbol 95 – “Truckton loamy sand”: slow surface runoff, moderate to high erosion hazard (Hydrologic Soil Group ‘B’)
- Map Symbol 101 – “Ustic Torrifluvents, loamy”: slow surface runoff, moderate to high erosion hazard (Hydrologic Soil Group ‘B’)
- Map Symbol 11 – “Bresser sandy loam”: slow surface runoff, slight to moderate erosion hazard (Hydrologic Soil Group ‘B’)
- Map Symbol 19 – “Columbine gravelly sandy loam”: slow surface runoff, slight to moderate erosion hazard (Hydrologic Soil Group ‘A’)
- Map Symbol 4 – “Badland series”: rapid runoff, high erosion hazard (Hydrologic Soil Group ‘D’)

The majority of the site consists of the Truckton series; therefore Hydrologic Soil Group ‘B’ is used for calculation purposes.

DRAINAGE BASINS AND SUB-BASINS

The overall 480-acre site is divided into 4 Major Basins – A, B, C, & D. Existing condition analysis adds the prefix “EX” to each of the Major Basins (e.g. EX-A). Developed condition analysis further divides the Major Basins into Sub-Basins, such as, A1, A2, B1, B2, etc. Each major basin will have a proposed on-site detention pond to detain developed flows and release them at or below historic peak flow levels. All on-site detention ponds shall be privately owned and maintained by the HOA. Developed flows are calculated for the entire 480-acre site for pond sizing. Future filings within this subdivision will need to design any proposed culvert crossings and swales and confirm the each detention pond will function as designed.

Existing Drainage Conditions:

The site is currently undeveloped and covered with mostly native grasses. Runoff travels overland over gentle slopes, sometimes forming general drainageways, to adjacent properties. The site is divided into the following Major Basins for analysis (See Existing Conditions Drainage Map in Appendix):

Basin EX-A consists of 43.5 acres and generates runoff of $Q_5 = 25$ cfs and $Q_{100} = 63$ cfs at Design Point exA (DP-exA). DP-exA represents overland flow travel onto the adjacent property to the east.

Basin EX-B consists of 224.3 acres and generates runoff of $Q_{10} = 26$ cfs and $Q_{100} = 96$ cfs at DP-exB. Also draining to DP-exB is off-site Basin OS1. Basin OS1 consists of 22.3 acres and generates runoff of $Q_5 = 15$ cfs and $Q_{100} = 38$ cfs. The total combined flow at DP-exB is $Q_{10} = 28$ cfs and $Q_{100} = 106$ cfs. DP-exB is an existing 18” CMP culvert under Handle Road.

Basin EX-C consists of 177.1 acres and generates runoff of $Q_{10} = 18$ cfs and $Q_{100} = 66$ cfs at DP-exC. DP-exC is an existing 24” CMP culvert under Handle Road.

Basin EX-D consists of 26.0 acres and generates runoff of $Q_5 = 15$ cfs and $Q_{100} = 36$ cfs at DP-exD. DP-exD is the existing roadside ditch along the west side of South Calhan Hwy.

Developed Drainage Conditions:

Proposed development of Filing No. 1 includes 46 low density single-family residential lots on 209 acres. The overall development of the entire 480-acre site will include 93 low density single-family residential lots. Analysis of the Major Basins is as follows (See Developed Conditions Drainage Map in Appendix):

MAJOR BASIN A:

Basin A1 includes 26.0 acres and generates runoff of $Q_5 = 22$ cfs and $Q_{100} = 51$ cfs at DP-A1. DP-A1 is a proposed 18” CMP culvert running under Dinner Bell Drive. The culvert at DP-A1 will drain directly onto the adjacent property. Therefore, this culvert includes Water Quality Capture Volume (WQCV) and the special outfall structure (see pond outfall details in Appendix). The outflow from the Pond created at DP-A1 is $Q_5 = 1$ cfs and $Q_{100} =$

4 cfs. The outfall from DP-A1 shall be protected by a 4' wide x 6' long $D_{50} = 6''$ diameter riprap (1' thick). Basin A2 includes 15.4 acres and generates runoff of $Q_5 = 13$ cfs and $Q_{100} = 31$ cfs to Pond A. Outflow from Pond A is $Q_5 = 1$ cfs and $Q_{100} = 2$ cfs. The outfall structure is a proposed 18" CMP culvert with a WCQV orifice plate (see pond outfall details in Appendix). The outfall from Pond A shall be protected by a 4' wide x 6' long $D_{50} = 6''$ diameter riprap (1' thick). Basin A3 includes 2.1 acres and generates runoff of $Q_5 = 2$ cfs and $Q_{100} = 4$ cfs. Basins A1 and A3 do not drain into Pond A. The total combined peak flow from Basins A1, A2, and A3 is $Q_5 = 2$ cfs and $Q_{100} = 7$ cfs (DP A). This is less than the existing peak flows from Basin EX-A of $Q_5 = 25$ cfs and $Q_{100} = 63$ cfs; therefore development of this basin will not adversely impact downstream properties.

MAJOR BASIN B:

Basin B1 includes 24.0 acres and generates runoff of $Q_5 = 16$ cfs and $Q_{100} = 39$ cfs at DP-B1. DP-B1 is a proposed 24" CMP culvert with riprap outfall protection running under Dinner Bell Drive. Basin B2 includes 6.4 acres and generates runoff of $Q_5 = 5$ cfs and $Q_{100} = 12$ cfs at DP-B2. DP-B2 is a proposed 18" CMP culvert running under Dinner Bell Drive. Basin B3 includes 44.0 acres and generates runoff of $Q_5 = 34$ cfs and $Q_{100} = 81$ cfs. The combined flows of Basins B1, B2, and B3 will be routed south via proposed Swale #1. Swale #1 is intended to prevent developed flows from traveling onto the adjacent property prior to heading south. Swale #1 is a proposed grass-lined trapezoidal swale with a 10' bottom width and 3:1 side slopes to a minimum depth of 2'. The slope of Swale #1 is 0.5% and the 100-year velocity is approximately 3.6 fps. This is within El Paso County permissible channel velocities. Swale #1 ends at the Filing No. 1 boundary. The swale flow will continue southeast over the existing ground into Basin B4. Future development of Basin B4 may require the continuation of Swale #1 to accommodate future lot layouts, road crossings, etc. Basin B4 includes 66.3 acres of future development that will generate runoff of $Q_5 = 49$ cfs and $Q_{100} = 115$ cfs at DP-B4. The total combined flow at DP-B4 is $Q_{10} = 24$ cfs and $Q_{100} = 153$ cfs. DP-B4 is a pair of proposed 24" CMP culverts with riprap outfall protection running under Dinner Bell Drive. Runoff at DP-B4 will overtop the roadway, however it is within El Paso County allowable roadway overtopping criteria. Basin B5 includes 86.0 acres of future development that will generate runoff of $Q_5 = 62$ cfs and $Q_{100} = 148$ cfs to Pond B. The total combined developed flow to Pond B from Basins B1, B2, B3, B4, B5, and OS1 is $Q_5 = 59$ cfs and $Q_{100} = 247$ cfs. Outflow from Pond B is $Q_{10} = 6$ cfs and $Q_{100} = 20$ cfs at DP-B. The outfall structure is a proposed 30" CMP culvert with a WCQV orifice plate (see pond outfall details in Appendix). The outfall from Pond B shall be protected by a 10' wide x 20' long $D_{50} = 12''$ diameter riprap (2' thick). The outflow from Pond B is less than the existing peak flows from Basin EX-B of $Q_{10} = 26$ cfs and $Q_{100} = 96$ cfs; therefore development of this basin will not adversely impact downstream properties. DP-B is an existing 18" CMP culvert running under Handle Road. Runoff at DP-B will overtop the roadway; however it is within El Paso County allowable roadway overtopping criteria.

MAJOR BASIN C:

Basin C1 includes 43.1 acres and generates runoff of $Q_5 = 24$ cfs and $Q_{100} = 57$ cfs at DP-C1. DP-C1 is a pair of proposed 30" CMP culverts with riprap outfall protection running under Blue Duck Way. The total combined flow at DP-C1 ($Q_5 = 32$ cfs and $Q_{100} = 57$ cfs) includes runoff from Basins C2 and C3. Basin C2 includes 13.7 acres and generates runoff

of $Q_5 = 10$ cfs and $Q_{100} = 24$ cfs at DP-C2. DP-C2 is a proposed 24" CMP culvert with riprap outfall protection running under Dinner Bell Drive. Basin C3 includes 8.9 acres and generates runoff of $Q_5 = 8$ cfs and $Q_{100} = 9$ cfs. DP-C3 is a proposed 18" CMP culvert running under Dinner Bell Drive. Basin C4 includes 7.1 acres and generates runoff of $Q_5 = 6$ cfs and $Q_{100} = 14$ cfs. The combined flows of Basins C1, C2, and C4 will be routed south via proposed Swale #2. Swale #2 is intended to route developed flows through an existing buffalo wallow (or low area) and into Pond C. Swale #2 is a proposed grass-lined trapezoidal swale with a 10' bottom width and 4:1 side slopes to a minimum depth of 2'. The slope of Swale #2 is 0.5% and 1.1% resulting in 100-year velocities of approximately 3.8 fps and 5.0 fps respectively. These are within El Paso County permissible channel velocities. Swale #2 ends by tapering out into Pond C. Future development of Cross Bow Court will require the design of a culvert crossing with Swale #2. Basin C5 includes 21.1 acres and generates runoff of $Q_5 = 16$ cfs and $Q_{100} = 37$ cfs. Basin C6 includes 80.5 acres of future development that will generate runoff of $Q_5 = 56$ cfs and $Q_{100} = 134$ cfs to Pond C. The total combined developed flow to Pond C from Basins C1, C2, C3, C4, C5, and C6 is $Q_{10} = 52$ cfs and $Q_{100} = 155$ cfs. Outflow from Pond C is $Q_{10} = 3$ cfs and $Q_{100} = 13$ cfs at DP-C. The outfall structure is a proposed 30" CMP culvert with a WCQV orifice plate (see pond outfall details in Appendix). The outfall from Pond D shall be protected by a 10' wide x 20' long $D_{50} = 12$ " diameter riprap (2' thick). The outflow from Pond C is less than the existing peak flows from Basin EX-C of $Q_{10} = 18$ cfs and $Q_{100} = 66$ cfs; therefore development of this basin will not adversely impact downstream properties. DP-C is an existing 24" CMP culvert running under Handle Road. Runoff at DP-C will overtop the roadway; however it is within El Paso County allowable roadway overtopping criteria.

MAJOR BASIN D:

Basin D1 includes 5.8 acres of future development that will generate runoff of $Q_5 = 5$ cfs and $Q_{100} = 12$ cfs at DP-D. Basin D2 includes 20.2 acres of future development that will generate runoff of $Q_5 = 18$ cfs and $Q_{100} = 43$ cfs to Pond D. Outflow from Pond D is $Q_5 = 1$ cfs and $Q_{100} = 3$ cfs. The outfall structure is a proposed 18" CMP culvert with a WCQV orifice plate (see pond outfall details in Appendix). The outfall from Pond D shall be protected by a 4' wide x 6' long $D_{50} = 6$ " diameter riprap (1' thick). Basin D1 does not drain into Pond D. The total combined peak flow from Basins D1 and D2 is $Q_5 = 5$ cfs and $Q_{100} = 13$ cfs (DP-D). This is less than the existing peak flows from Basin EX-D of $Q_5 = 15$ cfs and $Q_{100} = 36$ cfs; therefore development of this basin will not adversely impact downstream properties.

DRAINAGE DESIGN CRITERIA

This drainage report was prepared in accordance to the criteria established in the City of Colorado Springs and El Paso County Drainage Criteria Manual, updated in October 1994. This report has taken into the account the results and recommendations of the following previous drainage studies:

"Master Development Drainage Plan and Preliminary Drainage Report for Tanner Ranch," prepared by JPS Engineering, dated October 29, 2001

Per the City/County Drainage Criteria Manual and the request of El Paso County, WestWorks Engineering used the Rational Method for analysis of any individual basins or total tributary area less than 100 acres. The SCS Unit Hydrograph Procedure (TR-20) for individual drainage basins or total tributary areas greater than 100 acres. This methodology is implemented in accordance with the City/County Drainage Criteria Manual Guidelines.

For the Rational Method, flows are calculated for the 5-year and 100-year recurrence intervals. The average runoff coefficients, 'C' values, are taken from Table 5-1 and the Intensity-Duration-Frequency curves are taken from Figure 5-1 of the City/County Drainage Criteria Manual. Time of concentration for overland flow and channel are calculated per Section 5.2.3 of the City/County Drainage Criteria Manual. Calculations for the Rational Method, if used, are shown in the Appendix of this report. Any detention volume, in drainage total tributary basin areas less than 100 acres is calculated using the Modified Rational Method. The Modified Rational Method calculations are performed with the aid of HydroCAD version 7.00. Per the City/County Drainage Criteria Manual, the Modified Rational Method is only recommended for detention pond analysis on total tributary areas up to 20 acres. Per the specific request of El Paso County Development Services Engineering, this methodology was used on pond analyses with tributary areas up to 100 acres.

For the SCS Unit Hydrograph Procedure (TR-20), WestWorks Engineering uses the aid of HydroCAD version 7.00 for runoff calculations, routing quantities, and detention. Runoff quantities are analyzed for storms with recurrence intervals of 10 years and 100 years. The 24-hour storm distributions are based on a Type IIA distribution as shown in Figure 5-5b of the City/County Drainage Criteria Manual. Rainfall depths are based on the Isopluvial maps in City/County Drainage Criteria Manual Figures 5-4d and 5-4e. The 10-year 24-hour rainfall depth for this site is 3.0 inches. The 100-year 24-hour rainfall depth for this site is 4.4 inches. Runoff Curve Numbers are taken from Tables 5-6 and 5-7 (using AMC II) of the City/County Drainage Criteria Manual. Calculations for the SCS Unit Hydrograph Procedure (TR-20) are shown in the Appendix of this report.

DRAINAGE FACILITY DESIGN

All culverts and open channels are sized using the procedures outlined in the City/County Drainage Criteria Manual Chapters 7, 8, 9, and 10 respectively. All of the drainage systems, including the streets, are designed to safely route the 5-year and 100-year storm flows.

FLOODPLAIN STATEMENT

To the best of my knowledge and belief, no portion of Tanner Ranch Filing No. 1 is within a F.E.M.A. designated floodplain per Flood Insurance Rate Map Community Panel No. 08041C0850 F, effective March 17th, 1997.

EROSION CONTROL PLAN

The City of Colorado Springs/El Paso County Drainage Criteria Manual specifies that an Erosion Control Plan and associated cost estimate be submitted in conjunction with the Final Drainage Report. We respectfully request the Erosion Control Plan be submitted in conjunction with the site construction drawings and construction assurances posted prior to obtaining a grading permit.

DRAINAGE FEES

The study area is in the Upper Pond Creek Drainage Basin. There are no Drainage or Bridge Fees currently in the Upper Pond Creek Drainage Basin.


OPINION OF PROBABLE COST

(Non-Reimbursable Private Facilities)

Description	Quantity		Unit Cost	Total Cost
1. 18" CMP	190	LF	\$ 20/LF	\$ 3,800
2. 24" CMP	200	LF	\$ 25/LF	\$ 5,000
3. 30" CMP	150	LF	\$ 30/LF	\$ 4,500
3. Riprap	125	CY	\$ 35/CY	\$ 4,375
Subtotal				\$17,675
10% Contingency				\$ 1,768
TOTAL				<u>\$19,443</u>

This opinion of probable cost is made on the basis of experience and qualifications and represents WestWorks Engineering's best judgment as an experienced and qualified professional firm, familiar with the construction industry. WestWorks Engineering cannot and will not guarantee that actual construction costs will not vary from this opinion of probable cost.


APPENDIX





APPROXIMATE SCALE IN FEET

2000
0
2000



NATIONAL FLOOD INSURANCE PROGRAM

FIRM
FLOOD INSURANCE RATE MAP
EL PASO COUNTY,
COLORADO AND
INCORPORATED AREAS

PANEL 850 OF 1300
(SEE MAP INDEX FOR PANELS NOT PRINTED)


CONTAINS:
COMMUNITY
EL PASO COUNTY
UNINCORPORATED AREAS
060068 0860 F

MAP NUMBER
08041C0850 F
EFFECTIVE DATE:
MARCH 17, 1997



Federal Emergency Management Agency

This is an official copy of a portion of the above referenced flood map. It was extracted using F-MIT On-Line. This map does not reflect changes or amendments which may have been made subsequent to the date on the title block. For the latest product information about National Flood Insurance Program flood maps check the FEMA Flood Map Store at www.msc.fema.gov



S.C.S. SOILS
MAP

Time of Concentration Calculations

Sub-Basin Area [ac]	Time of Concentration, Tc [min.]					Sub-Basin Area [ac]	Time of Concentration, Tc [min.]					Sub-Basin Area [ac]	Time of Concentration, Tc [min.]				
	Flowline	L [ft.]	S [%]	v [ft/s]	Tc [min.]		Flowline	L [ft.]	S [%]	v [ft/s]	Tc [min.]		Flowline	L [ft.]	S [%]	v [ft/s]	Tc [min.]
<u>EX1</u> 43.5	overland	850	3.5		30.5	<u>OS1</u> 22.3	overland	300	2.0		21.9						
	channel	520	1.5	4.29	2.0		channel	680	1.5	4.29	2.6						
	Total Tc =				32.5		Total Tc =				24.5						
<u>EX2</u> 224.3	overland	800	1.3		41.2												
	channel	6250	1.1	3.67	28.4												
	Total Tc =				69.6												
<u>EX3</u> 177.1	overland	1000	0.8		54.1												
	channel	6252	1.0	3.50	29.8												
	Total Tc =				83.9												
<u>EX4</u> 26	overland	830	2.4		34.2												
	channel	0	0.0	0.35	0.0												
	Total Tc =				34.2												



Project: Tanner Ranch Filing No. 1

Job No.: 90330

Engineer: Chad Kuzbek, PE

Date: December 17, 2004

Time of Concentration Calculations

Sub-Basin Area [ac]	Time of Concentration, Tc [min.]					Sub-Basin Area [ac]	Time of Concentration, Tc [min.]					Sub-Basin Area [ac]	Time of Concentration, Tc [min.]				
	Flowline	L [ft.]	S [%]	v [ft/s]	Tc [min.]		Flowline	L [ft.]	S [%]	v [ft/s]	Tc [min.]		Flowline	L [ft.]	S [%]	v [ft/s]	Tc [min.]
<u>A-1</u> 26	overland	300	2.3		20.9	<u>B-4</u> 66.3	overland	300	3.0		19.1	<u>C-4</u> 7.1	overland	300	2.7		19.8
	channel	1050	2.9	5.96	<u>2.9</u>		channel	2240	1.0	3.50	<u>10.7</u>		channel	560	0.7	2.93	<u>3.2</u>
	Total Tc =				23.8		Total Tc =				29.8		Total Tc =				23.0
<u>A-2</u> 17.5	overland	300	3.0		19.1	<u>B-5</u> 86	overland	300	2.7		19.8	<u>C-5</u> 21.1	overland	300	2.0		21.9
	channel	1070	1.8	4.70	<u>3.8</u>		channel	2530	1.3	3.99	<u>10.6</u>		channel	1760	1.3	3.99	<u>7.4</u>
	Total Tc =				22.9		Total Tc =				30.3		Total Tc =				29.2
<u>B-1</u> 24	overland	300	1.0		27.5	<u>C-1</u> 43.1	overland	300	0.7		31.0	<u>C-6</u> 80.5	overland	300	2.7		19.8
	channel	1330	1.0	3.50	<u>6.3</u>		channel	3590	1.2	3.83	<u>15.6</u>		channel	2290	0.8	3.13	<u>12.2</u>
	Total Tc =				33.9		Total Tc =				46.6		Total Tc =				32.0
<u>B-2</u> 6.4	overland	300	1.3		25.2	<u>C-2</u> 13.7	overland	300	1.3		25.2	<u>D-1</u> 5.8	overland	300	3.3		18.5
	channel	490	1.4	4.14	<u>2.0</u>		channel	1050	1.7	4.56	<u>3.8</u>		channel	950	2.1	5.07	<u>3.1</u>
	Total Tc =				27.2		Total Tc =				29.1		Total Tc =				21.6
<u>B-3</u> 44	overland	300	2.7		19.8	<u>C-3</u> 8.9	overland	300	3.0		19.1	<u>D-2</u> 20.2	overland	300	3.3		18.5
	channel	1780	1.5	4.29	<u>6.9</u>		channel	540	1.9	4.82	<u>1.9</u>		channel	510	2.0	4.95	<u>1.7</u>
	Total Tc =				26.7		Total Tc =				21.0		Total Tc =				20.2
												<u>A-3</u> 2.1	overland	300	1.7		23.1
													channel	50	2.0	4.95	<u>0.2</u>
													Total Tc =				23.2



Project: Tanner Ranch Filing No. 1

Job No.: 90330

Engineer: Chad Kuzbek, PE

Date: December 17, 2004

RIPRAP SIZING

Channel Section Description	Velocity V [ft/s]	Slope, S [ft/ft]	Specific Gravity	*Channel/Riprap Relationship	Rock Type	Mean Particle Size [in]
Design Point A1	3.3	1.00%	2.5	1.15	N/A	<i>none req'd</i>
Pond A Discharge	2.1	1.00%	2.5	0.73	N/A	<i>none req'd</i>
Design Point B1	4.7	1.00%	2.5	1.64	VL	6
Design Point B2	3.8	1.00%	2.5	1.33	N/A	<i>none req'd</i>
Design Point B4	5.8	1.00%	2.5	2.03	VL	6
Pond B Discharge	4.6	1.00%	2.5	1.61	VL	6
Design Point C1	5.5	1.00%	2.5	1.92	VL	6
Design Point C2	5	1.00%	2.5	1.75	VL	6
Design Point C3	3.6	1.00%	2.5	1.26	N/A	<i>none req'd</i>
Pond C Discharge	4.3	1.00%	2.5	1.50	VL	6

*Channel/Riprap Relationship = $\frac{V \cdot S^{0.17}}{(S_s - 1)^{0.66}}$

*taken from El Paso County Drainage Criteria
Manual Section 10.10

where: V = mean channel flow velocity [ft/sec]
S = longitudinal channel slope [ft/ft]
S_s = specific gravity of stone (min = 2.5)

Design Procedure Form: Extended Detention Basin (EDB) - Sedimentation Facility

Designer: Chad Kuzbek, PE
Company: WestWorks Engineering
Date: June 14, 2005
Project: Tanner Ranch Filing No. 1

Pond A1

1. Basin Storage Volume	
A) Tributary Area's Imperviousness Ratio ($i = I_a / 100$)	$I_a = \underline{4.00} \%$ $i = \underline{0.04}$
B) Contributing Watershed Area (Area)	Area = <u>26.0</u> acres
C) Water Quality Capture Volume (WQCV) ($WQCV = 1.0 * (0.91 * I^3 - 1.19 * I^2 + 0.78 * I)$)	WQCV = <u>0.03</u> watershed inches
D) Design Volume: Vol = (WQCV / 12) * Area * 1.2	Vol = <u>0.076</u> acre-feet (0.10 ac-ft provided)

Pond A

1. Basin Storage Volume	
A) Tributary Area's Imperviousness Ratio ($i = I_a / 100$)	$I_a = \underline{4.00} \%$ $i = \underline{0.04}$
B) Contributing Watershed Area (Area)	Area = <u>15.4</u> acres
C) Water Quality Capture Volume (WQCV) ($WQCV = 1.0 * (0.91 * I^3 - 1.19 * I^2 + 0.78 * I)$)	WQCV = <u>0.03</u> watershed inches
D) Design Volume: Vol = (WQCV / 12) * Area * 1.2	Vol = <u>0.045</u> acre-feet (0.42 ac-ft provided)

Pond B

1. Basin Storage Volume	
A) Tributary Area's Imperviousness Ratio ($i = I_a / 100$)	$I_a = \underline{4.00} \%$ $i = \underline{0.04}$
B) Contributing Watershed Area (Area)	Area = <u>249.0</u> acres
C) Water Quality Capture Volume (WQCV) ($WQCV = 1.0 * (0.91 * I^3 - 1.19 * I^2 + 0.78 * I)$)	WQCV = <u>0.03</u> watershed inches
D) Design Volume: Vol = (WQCV / 12) * Area * 1.2	Vol = <u>0.731</u> acre-feet (1.52 ac-ft provided)

Design Procedure Form: Extended Detention Basin (EDB) - Sedimentation Facility

Designer: Chad Kuzbek, PE
Company: WestWorks Engineering
Date: June 14, 2005
Project: Tanner Ranch Filing No. 1

Pond C

1. Basin Storage Volume	
A) Tributary Area's Imperviousness Ratio ($i = I_a / 100$)	$I_a = \underline{4.00} \%$ $i = \underline{0.04}$
B) Contributing Watershed Area (Area)	Area = <u>174.4</u> acres
C) Water Quality Capture Volume (WQCV) ($WQCV = 1.0 * (0.91 * I^3 - 1.19 * I^2 + 0.78 * I)$)	WQCV = <u>0.03</u> watershed inches
D) Design Volume: Vol = (WQCV / 12) * Area * 1.2	Vol = <u>0.512</u> acre-feet (1.52 ac-ft provided)

Pond D

1. Basin Storage Volume	
A) Tributary Area's Imperviousness Ratio ($i = I_a / 100$)	$I_a = \underline{4.00} \%$ $i = \underline{0.04}$
B) Contributing Watershed Area (Area)	Area = <u>20.2</u> acres
C) Water Quality Capture Volume (WQCV) ($WQCV = 1.0 * (0.91 * I^3 - 1.19 * I^2 + 0.78 * I)$)	WQCV = <u>0.03</u> watershed inches
D) Design Volume: Vol = (WQCV / 12) * Area * 1.2	Vol = <u>0.059</u> acre-feet (0.24 ac-ft provided)



WATER QUALITY POND



Maintenance Recommendations


Extended detention basins have low to moderate maintenance requirements. Routine and nonroutine maintenance is necessary to assure performance, enhance aesthetics, and protect structural integrity. The dry basins can result in nuisance complaints if not properly designed or maintained. Bio-degradable pesticides may be required to limit insect problems. Frequent debris removal and grass-mowing can reduce aesthetic complaints. If a shallow wetland or marshy area is included, mosquito breeding and nuisance odors could occur if the water becomes stagnant. Access to critical elements of the pond (inlet, outlet, spillway, and sediment collection areas) must be provided. The basic elements of the maintenance requirements are presented in Table EDB-1.

TABLE EDB-1
Extended Detention Basin Maintenance Considerations

Required Action	Maintenance Objective	Frequency of Action
Lawn mowing and lawn care	Occasional mowing to limit unwanted vegetation. Maintain irrigated turf grass as 2 to 4 inches tall and nonirrigated native turf grasses at 4 to 6 inches.	Routine – Depending on aesthetic requirements.
Debris and litter removal	Remove debris and litter from the entire pond to minimize outlet clogging and improve aesthetics.	Routine – Including just before annual storm seasons (that is, April and May) and following significant rainfall events.
Erosion and sediment control	Repair and revegetate eroded areas in the basin and channels.	Nonroutine – Periodic and repair as necessary based on inspection.
Structural	Repair pond inlets, outlets, forebays, low flow channel liners, and energy dissipators whenever damage is discovered.	Nonroutine – Repair as needed based on regular inspections.
Inspections	Inspect basins to insure that the basin continues to function as initially intended. Examine the outlet for clogging, erosion, slumping, excessive sedimentation levels, overgrowth, embankment and spillway integrity, and damage to any structural element.	Routine – Annual inspection of hydraulic and structural facilities. Also check for obvious problems during routine maintenance visits, especially for plugging of outlets.
Nuisance control	Address odor, insects, and overgrowth issues associated with stagnant or standing water in the bottom zone.	Nonroutine – Handle as necessary per inspection or local complaints.
Sediment removal	Remove accumulated sediment from the forebay, micro-pool, and the bottom of the basin.	Nonroutine – Performed when sediment accumulation occupies 20 percent of the WQCV. This may vary considerably, but expect to do this every 10 to 20 years, as necessary per inspection if no construction activities take place in the tributary watershed. More often if they do. The forebay and the micro-pool will require more frequent cleanout than other areas of the basin, say every 1 or 2 years.










POND OUTFALL NOTES:

1. EMBANKMENT SLOPES AROUND HEADWALL TO BE GRADED FLUSH WITH TOP AND SIDE EDGES OF THE HEADWALL. SEE GRADING PLAN FOR SOIL COMPACTION REQUIREMENTS.
2. THE POND OUTFALL STRUCTURE SHALL BE LOCATED SUCH THAT THE INVERT OF THE OUTFALL IS AT THE LOWEST POINT OF THE POND. OR THE BOTTOM OF THE POND SHALL BE GRADED SO THAT THE INVERT OF THE OUTFALL IS AT THE LOWEST POINT OF THE POND.





SWALE #1

TRAPEZOIDAL CHANNEL ANALYSIS
NORMAL DEPTH COMPUTATION

June 16, 2005

PROGRAM INPUT DATA

DESCRIPTION	VALUE
Flow Rate (cfs).....	87.0 ← Q_{100}
Channel Bottom Slope (ft/ft).....	0.005 ← $S = 0.5\%$
Manning's Roughness Coefficient (n-value).....	0.033
Channel Left Side Slope (horizontal/vertical).....	3.0
Channel Right Side Slope (horizontal/vertical).....	3.0
Channel Bottom Width (ft).....	10.0

COMPUTATION RESULTS

DESCRIPTION	VALUE
Normal Depth (ft).....	1.63 ← D_{100}
Flow Velocity (fps).....	3.58
Froude Number.....	0.57 ← V_{100}
Velocity Head (ft).....	0.2
Energy Head (ft).....	1.83
Cross-Sectional Area of Flow (sq ft).....	24.27
Top Width of Flow (ft).....	19.78

HYDROCALC Hydraulics for Windows, Version 1.2a Copyright (c) 1996
Dodson & Associates, Inc., 5629 FM 1960 West, Suite 314, Houston, TX 77069
Phone: (281) 440-3787, Fax: (281) 440-4742, Email: software@dodson-hydro.com
All Rights Reserved.

SWALE #2

TRAPEZOIDAL CHANNEL ANALYSIS
NORMAL DEPTH COMPUTATION

December 23, 2004

PROGRAM INPUT DATA	
DESCRIPTION	VALUE
Flow Rate (cfs).....	123.0 ← Q_{100}
Channel Bottom Slope (ft/ft).....	0.005 ← $S = 0.5\%$
Manning's Roughness Coefficient (n-value).....	0.033
Channel Left Side Slope (horizontal/vertical).....	4.0
Channel Right Side Slope (horizontal/vertical).....	4.0
Channel Bottom Width (ft).....	10.0

COMPUTATION RESULTS	
DESCRIPTION	VALUE
Normal Depth (ft).....	1.87 ← D_{100}
Flow Velocity (fps).....	3.76 ← V_{100}
Froude Number.....	0.58
Velocity Head (ft).....	0.22
Energy Head (ft).....	2.09
Cross-Sectional Area of Flow (sq ft).....	32.69
Top Width of Flow (ft).....	24.96

HYDROCALC Hydraulics for Windows, Version 1.2a Copyright (c) 1996
Dodson & Associates, Inc., 5629 FM 1960 West, Suite 314, Houston, TX 77069
Phone: (281) 440-3787, Fax: (281) 440-4742, Email: software@dodson-hydro.com
All Rights Reserved.

SWALE #2

TRAPEZOIDAL CHANNEL ANALYSIS
NORMAL DEPTH COMPUTATION

December 23, 2004

PROGRAM INPUT DATA

DESCRIPTION	VALUE
Flow Rate (cfs).....	123.0 ← $Q_{1.00}$
Channel Bottom Slope (ft/ft).....	0.011 ← $S = 1.1\%$
Manning's Roughness Coefficient (n-value).....	0.033
Channel Left Side Slope (horizontal/vertical).....	4.0
Channel Right Side Slope (horizontal/vertical).....	4.0
Channel Bottom Width (ft).....	10.0

COMPUTATION RESULTS

DESCRIPTION	VALUE
Normal Depth (ft).....	1.53 ← $D_{1.00}$
Flow Velocity (fps).....	5.0 ← $V_{1.00}$
Froude Number.....	0.837
Velocity Head (ft).....	0.39
Energy Head (ft).....	1.92
Cross-Sectional Area of Flow (sq ft).....	24.61
Top Width of Flow (ft).....	22.22

HYDROCALC Hydraulics for Windows, Version 1.2a Copyright (c) 1996
Dodson & Associates, Inc., 5629 FM 1960 West, Suite 314, Houston, TX 77069
Phone: (281) 440-3787, Fax: (281) 440-4742, Email: software@dodson-hydro.com
All Rights Reserved.

PIPE CULVERT ANALYSIS
COMPUTATION OF CULVERT PERFORMANCE CURVE

December 27, 2004

DP EX-B
-EX 18" CMA CAPACITY

PROGRAM INPUT DATA

DESCRIPTION	VALUE
Culvert Diameter (ft).....	1.5 ← 18"
FHWA Chart Number.....	2
FHWA Scale Number (Type of Culvert Entrance).....	3
Manning's Roughness Coefficient (n-value).....	0.024 ← CMA
Entrance Loss Coefficient of Culvert Opening.....	0.8
Culvert Length (ft).....	40.0
Invert Elevation at Downstream end of Culvert (ft).....	100.0
Invert Elevation at Upstream end of Culvert (ft).....	100.4
Culvert Slope (ft/ft).....	0.01
Starting Flow Rate (cfs).....	1.0
Incremental Flow Rate (cfs).....	1.0
Ending Flow Rate (cfs).....	16.0
Starting Tailwater Depth (ft).....	0.1
Incremental Tailwater Depth (ft).....	0.1
Ending Tailwater Depth (ft).....	1.6

COMPUTATION RESULTS


Flow Rate (cfs)	Tailwater Depth (ft)	Headwater Inlet Control (ft)	Headwater Outlet Control (ft)	Normal Depth (ft)	Critical Depth (ft)	Depth at Outlet (ft)	Outlet Velocity (fps)
1.0	0.1	0.51	0.59	0.43	0.37	0.37	2.92
2.0	0.2	0.77	0.86	0.61	0.53	0.53	3.55
3.0	0.3	0.99	1.07	0.77	0.66	0.66	4.02
4.0	0.4	1.19	1.27	0.93	0.77	0.77	4.41
5.0	0.5	1.39	1.45	1.09	0.86	0.86	4.77
6.0	0.6	1.58	1.65	1.32	0.95	0.95	5.11
7.0	0.7	1.77	1.87	1.5	1.02	1.02	5.44
8.0	0.8	2.02	1.9	1.5	1.1	1.5	4.53
9.0	0.9	2.24	2.24	1.5	1.16	1.16	6.13
10.0	1.0	2.57	2.59	1.5	1.22	1.22	6.5
11.0	1.1	2.95	2.98	1.5	1.27	1.27	6.89
12.0	1.2	3.35	3.37	1.5	1.31	1.31	7.31
13.0	1.3	3.8	3.81	1.5	1.35	1.35	7.76
14.0	1.4	4.27	4.26	1.5	1.38	1.5	7.92
15.0	1.5	4.79	5.9	1.5	1.41	1.5	8.49
16.0	1.6	5.34	6.66	1.5	1.42	1.5	9.05

Q CAPACITY

HYDROCALC Hydraulics for Windows, Version 1.2a Copyright (c) 1996
 Dodson & Associates, Inc., 5629 FM 1960 West, Suite 314, Houston, TX 77069
 Phone: (281) 440-3787, Fax: (281) 440-4742, Email: software@dodson-hydro.com
 All Rights Reserved.

- DESIGN POINT B AND EX-B

- EX 18" CMA ON HANDLE ROAD
- Q_{100} (HISTORIC) = 101 CFS
- Q_{100} (DEVELOPED) = 50 CFS
- MAXIMUM OVERTOPPING DEPTH = 6 INCHES



USE MANNING'S EQUATION TO FIND $Q_{(MAX)}$:

$$Q_{(MAX)} = \underbrace{\frac{1.49}{n} A R^{2/3} \sqrt{S}}_{\text{OVERTOPPING FLOW}} + \text{CULVERT CAPACITY}$$

$$= \frac{1.49}{0.023} (62 \text{ FT}^2) \left(\frac{62 \text{ FT}^2}{248 \text{ FT}} \right)^{2/3} \sqrt{0.01} + 6 \text{ CFS}$$

$$= 159 \text{ CFS} + 6 \text{ CFS}$$

$$Q_{(MAX)} = 165 \text{ CFS} > 50 \text{ CFS } (Q_{100}) \therefore \text{EX CULVERT ADEQUATE}$$

PIPE CULVERT ANALYSIS
COMPUTATION OF CULVERT PERFORMANCE CURVE

December 27, 2004

DP EX-C
-EX 24" CMA CAPACITY

PROGRAM INPUT DATA

DESCRIPTION	VALUE
Culvert Diameter (ft).....	2.0 ← 24"
FHWA Chart Number.....	2
FHWA Scale Number (Type of Culvert Entrance).....	3
Manning's Roughness Coefficient (n-value).....	0.024 ← CMA
Entrance Loss Coefficient of Culvert Opening.....	0.8
Culvert Length (ft).....	40.0
Invert Elevation at Downstream end of Culvert (ft).....	100.0
Invert Elevation at Upstream end of Culvert (ft).....	100.4
Culvert Slope (ft/ft).....	0.01
Starting Flow Rate (cfs).....	1.0
Incremental Flow Rate (cfs).....	1.0
Ending Flow Rate (cfs).....	16.0
Starting Tailwater Depth (ft).....	0.1
Incremental Tailwater Depth (ft).....	0.1
Ending Tailwater Depth (ft).....	1.6

COMPUTATION RESULTS


Flow Rate (cfs)	Tailwater Depth (ft)	Headwater Inlet Control (ft)	Headwater Outlet Control (ft)	Normal Depth (ft)	Critical Depth (ft)	Depth at Outlet (ft)	Outlet Velocity (fps)
1.0	0.1	0.46	0.54	0.39	0.34	0.34	2.77
2.0	0.2	0.67	0.78	0.55	0.49	0.49	3.34
3.0	0.3	0.85	0.96	0.67	0.6	0.6	3.75
4.0	0.4	1.01	1.13	0.79	0.7	0.7	4.07
5.0	0.5	1.15	1.27	0.89	0.79	0.79	4.35
6.0	0.6	1.29	1.41	0.99	0.87	0.87	4.6
7.0	0.7	1.43	1.54	1.08	0.94	0.94	4.83
8.0	0.8	1.56	1.66	1.18	1.01	1.01	5.05
9.0	0.9	1.69	1.78	1.27	1.07	1.07	5.26
10.0	1.0	1.81	1.9	1.37	1.13	1.13	5.45
11.0	1.1	1.94	2.02	1.48	1.19	1.19	5.65
12.0	1.2	2.07	2.14	1.6	1.24	1.24	5.84
13.0	1.3	2.19	2.26	1.78	1.3	1.3	6.01
14.0	1.4	2.32	2.39	2.0	1.35	1.4	5.96
15.0	1.5	2.45	2.52	2.0	1.4	1.5	5.93
16.0	1.6	2.61	2.69	2.0	1.44	1.6	5.94

Q CAPACITY

HYDROCALC Hydraulics for Windows, Version 1.2a Copyright (c) 1996
Dodson & Associates, Inc., 5629 FM 1960 West, Suite 314, Houston, TX 77069
Phone: (281) 440-3787, Fax: (281) 440-4742, Email: software@dodson-hydro.com
All Rights Reserved.

- DESIGN POINT C AND EX-C

- EX 24" CMP ON HANDLE ROAD
- Q_{100} (HISTORIC) = 66 CFS
- Q_{100} (DEVELOPED) = 40 CFS
- MAXIMUM OVERTOPPING DEPTH = 6 INCHES



USE MANNING'S EQN TO FIND $Q_{(max)}$:

$$Q_{(max)} = \underbrace{\frac{1.49}{n} A R^{2/3} \sqrt{S}}_{\text{OVERTOPPING FLOW}} + \text{CULVERT CAPACITY}$$

$$= \frac{1.49}{0.023} (120 \text{ FT}^2) \left(\frac{120 \text{ FT}^2}{480 \text{ FT}} \right)^{2/3} \sqrt{0.01} + 15 \text{ CFS}$$

$$= 308 \text{ CFS} + 15 \text{ CFS}$$

$$= 323 \text{ CFS} > 40 \text{ CFS } (Q_{100}) \therefore \text{EX CULVERT IS ADEQUATE}$$

TABLE 10-4

**MAXIMUM PERMISSIBLE VELOCITIES FOR EARTH CHANNELS WITH
VARIED GRASS LININGS AND SLOPES**

<u>Channel Slope</u>	<u>Lining</u>	<u>Permissible Mean Channel Velocity *</u> (ft/sec)
0 - 5%	Sodded grass	7
	Bermudagrass	6
	Reed canarygrass	5
	Tall fescue	5
	Kentucky bluegrass	5
	Grass-legume mixture	4
	Red fescue	2.5
	Redtop	2.5
	Sericea lespedeza	2.5
	Annual lespedeza	2.5
	Small grains (temporary)	2.5
5 - 10%	Sodded grass	6
	Bermudagrass	5
	Reed canarygrass	4
	Tall fescue	4
	Kentucky bluegrass	4
	Grass-legume mixture	3
Greater than 10%	Sodded grass	5
	Bermudagrass	4
	Reed canarygrass	3
	Tall fescue	3
	Kentucky bluegrass	3

* For highly erodible soils, decrease permissible velocities by 25%.

* Grass lined channels are dependent upon assurances of continuous growth and maintenance of grass.

TABLE 10-2 (Continued)

TYPICAL ROUGHNESS COEFFICIENTS FOR OPEN CHANNELS

Type of Channel and Description	Minimum	Normal	Maximum
c. Concrete bottom float finished with sides of			
1. Dressed stone in mortar	0.015	0.017	0.020
2. Random stone in mortar	0.017	0.020	0.024
3. Cement rubble masonry, plastered	0.016	0.020	0.024
4. Cement rubble masonry	0.020	0.025	0.030
5. Dry rubble or riprap	0.020	0.030	0.035
d. Gravel bottom with sides of			
1. Formed concrete	0.017	0.020	0.025
2. Random stone in mortar	0.020	0.023	0.026
3. Dry rubble or riprap	0.023	0.033	0.036
e. Asphalt			
1. Smooth		0.013	
2. Rough		0.016	
f. Grassed	0.030	0.040	0.050

TABLE 10-3

MAXIMUM PERMISSIBLE DESIGN
OPEN CHANNEL FLOW VELOCITIES IN EARTH*

Soil Types	Permissible Mean Channel Velocity (ft/sec)
Fine Sand (noncolloidal)	2.0
Coarse Sand (noncolloidal)	4.0
Sandy Loam (noncolloidal)	2.5
Silt Loam (noncolloidal)	3.0
Ordinary Firm Loam	3.5
Silty Clay	3.5
Fine Gravel	5.0
Stiff Clay (very colloidal)	5.0
Graded, Loam to Cobbles (noncolloidal)	5.0
Graded, Silt to Cobbles (colloidal)	5.5
Alluvial Silts (noncolloidal)	3.5
Alluvial Silts (colloidal)	5.0
Coarse Gravel (noncolloidal)	6.0
Cobbles and Shingles	5.5
Hard Shales and Hard Pans	6.0
Soft Shales	3.5
Soft Sandstone	8.0
Sound rock (usu. igneous or hard metamorphic)	20.0

* These velocities shall be used in conjunction with scour calculations and as approved by City/County.

TABLE 6-4

ALLOWABLE CULVERT OVERTOPPINGS*

<u>Drainage Classification</u>	<u>Initial Drainage System Maximum Depth</u>	<u>Major Drainage System Maximum Depth</u>
Types A & B (Local/Residential and Collector)	Headwater Depth Ratio is Less Than Pipe Height	12 inches of depth at the gutter flow line
Types A & B (Local/Residential and collector without C/G)	Headwater Depth Ratio is Less Than Pipe Height	6 inches of depth at the street
Types C & D (Arterial, Highway or Freeway with or without Roadside Ditch)**	Headwater Depth Ratio is Less Than Pipe Height	No shoulder encroachment

* A culvert is defined as any buried structure with both a clear opening less than 200 square feet, and span less than 20 feet and capacity less than 1500 cfs.

**On state highways, CDOH criteria shall be utilized.

TABLE 6-5

ALLOWABLE CULVERT HEADWATER DEPTHS FOR DESIGN FLOWS

<u>Clear Opening (Ft²)</u>	<u>Hw/D</u>
200 or Greater	See allowable bridge clearance
200 to 50	<u>500 - Area</u>
	300
50 or Less	Greater than 1.5 If approved by City/County.

The Engineer shall consider various factors in determining permissible headwater depths such as backwater effects, possible flooding, embankment erosion, overtopping and public safety.

6.4.2 Allowable Clearance for Bridges and Other Major Drainageway Crossings

All structures classified as bridge shall not be overtopped. For clear span bridges, the minimum clearance between the bridge low chord and the water surface profile shall be a minimum of 2 feet for the 100-year design flow. For box culverts classified as bridges or culverts at major drainageways (100-year flows greater than 1500 cfs) adequate freeboard shall be provided for the passage of debris and should be no less than 2 feet.

**EXISTING CONDITIONS
HYDROLOGIC CALCULATIONS
INITIAL STORM
(RATIONAL METHOD – 5 YEAR)
(TR-20 – 10 YEAR)**



Basin EX-A





Design Point EX-A



Basin EX-D



Design Point EX-D



Drainage Diagram for Rational-5YR Existing

Prepared by WestWorks Engineering 6/16/2005

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

Rational-5YR Existing

El Paso County 5-Year Duration=33 min, Inten=2.29 in/hr

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment EX-A: Basin EX-A

Runoff = 25.15 cfs @ 0.55 hrs, Volume= 1.141 af, Depth= 0.31"


Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
El Paso County 5-Year Duration=33 min, Inten=2.29 in/hr

Area (ac)	C	Description
43.500	0.25	Pasture/grassland/range, Good, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
32.5					Direct Entry, Basin EX-A

Subcatchment EX-A: Basin EX-A

Hydrograph




Runoff

Link DPexA: Design Point EX-A

Inflow Area = 43.500 ac, Inflow Depth = 0.31" for 5-Year event
 Inflow = 25.15 cfs @ 0.55 hrs, Volume= 1.141 af
 Primary = 25.15 cfs @ 0.55 hrs, Volume= 1.141 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs

Link DPexA: Design Point EX-A



Rational-5YR Existing

El Paso County 5-Year Duration=34 min, Inten=2.25 in/hr

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment EX-D: Basin EX-D

Runoff = 14.59 cfs @ 0.57 hrs, Volume= 0.687 af, Depth= 0.32"


Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
El Paso County 5-Year Duration=34 min, Inten=2.25 in/hr

Area (ac)	C	Description
26.000	0.25	Pasture/grassland/range, Good, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
34.2					Direct Entry, Basin EX-D

Subcatchment EX-D: Basin EX-D

Hydrograph




Runoff


Link DPexD: Design Point EX-D

Inflow Area = 26.000 ac, Inflow Depth = 0.32" for 5-Year event
 Inflow = 14.59 cfs @ 0.57 hrs, Volume= 0.687 af
 Primary = 14.59 cfs @ 0.57 hrs, Volume= 0.687 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs

Link DPexD: Design Point EX-D






Basin EX-B & OS1





Design Point EX-B



Basin EX-C



Design Point EX-C



TR20-10YR-24HR Existing

Type IIA 24-hr Rainfall=3.00"

Prepared by WestWorks Engineering

Page 2

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Time span=0.00-20.00 hrs, dt=0.05 hrs, 401 points

Runoff by SCS TR-20 method, UH=SCS

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment EX-B: Basin EX-B & OS1

Runoff Area=246.600 ac Runoff Depth=0.33"

Tc=69.6 min CN=61 Runoff=28.26 cfs 6.809 af

Subcatchment EX-C: Basin EX-C

Runoff Area=177.100 ac Runoff Depth=0.33"

Tc=83.9 min CN=61 Runoff=17.61 cfs 4.855 af

Link DPexB: Design Point EX-B

Inflow=28.26 cfs 6.809 af

Primary=28.26 cfs 6.809 af

Link DPexC: Design Point EX-C

Inflow=17.61 cfs 4.855 af

Primary=17.61 cfs 4.855 af

Total Runoff Area = 423.700 ac Runoff Volume = 11.664 af Average Runoff Depth = 0.33"

TR20-10YR-24HR Existing

Type IIA 24-hr Rainfall=3.00"

Prepared by WestWorks Engineering

Page 3

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment EX-B: Basin EX-B & OS1

Runoff = 28.26 cfs @ 6.90 hrs, Volume= 6.809 af, Depth= 0.33"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.05 hrs
Type IIA 24-hr Rainfall=3.00"

Area (ac)	CN	Description
224.300	61	Pasture/grassland/range, Good, HSG B
22.300	61	Basin OS1
246.600	61	Weighted Average

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
69.6					Direct Entry, Basin EX-B

Subcatchment EX-C: Basin EX-C

Runoff = 17.61 cfs @ 7.13 hrs, Volume= 4.855 af, Depth= 0.33"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.05 hrs
Type IIA 24-hr Rainfall=3.00"

Area (ac)	CN	Description
177.100	61	Pasture/grassland/range, Good, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
83.9					Direct Entry, Basin EX-C

Link DPexB: Design Point EX-B

Inflow Area = 246.600 ac, Inflow Depth = 0.33"

Inflow = 28.26 cfs @ 6.90 hrs, Volume= 6.809 af

Primary = 28.26 cfs @ 6.90 hrs, Volume= 6.809 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-20.00 hrs, dt= 0.05 hrs

Link DPexC: Design Point EX-C

Inflow Area = 177.100 ac, Inflow Depth = 0.33"

Inflow = 17.61 cfs @ 7.13 hrs, Volume= 4.855 af

Primary = 17.61 cfs @ 7.13 hrs, Volume= 4.855 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-20.00 hrs, dt= 0.05 hrs

**EXISTING CONDITIONS
HYDROLOGIC CALCULATIONS
MAJOR STORM
(RATIONAL METHOD – 100 YEAR)
(TR-20 – 100 YEAR)**



Basin EX-A





Design Point EX-A



Basin EX-D



Design Point EX-D



Drainage Diagram for Rational-100YR Existing

Prepared by WestWorks Engineering 6/16/2005

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

Rational-100YR Existing

El Paso County 100-Year Duration=33 min, Inten=4.08 in/hr

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment EX-A: Basin EX-A

Runoff = 62.72 cfs @ 0.55 hrs, Volume= 2.847 af, Depth= 0.79"

Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs


El Paso County 100-Year Duration=33 min, Inten=4.08 in/hr

Area (ac)	C	Description
43.500	0.35	Pasture/grassland/range, Good, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
32.5					Direct Entry, Basin EX-A

Subcatchment EX-A: Basin EX-A


Hydrograph



Link DPexA: Design Point EX-A

Inflow Area = 43.500 ac, Inflow Depth = 0.79" for 100-Year event
Inflow = 62.72 cfs @ 0.55 hrs, Volume= 2.847 af
Primary = 62.72 cfs @ 0.55 hrs, Volume= 2.847 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs

Link DPexA: Design Point EX-A

Rational-100YR Existing

El Paso County 100-Year Duration=34 min, Inten=4.01 in/hr

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment EX-D: Basin EX-D

Runoff = 36.39 cfs @ 0.57 hrs, Volume= 1.713 af, Depth= 0.79"

Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs


El Paso County 100-Year Duration=34 min, Inten=4.01 in/hr

Area (ac)	C	Description
26.000	0.35	Pasture/grassland/range, Good, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
34.2					Direct Entry, Basin EX-D

Subcatchment EX-D: Basin EX-D

Hydrograph




Runoff


Link DPexD: Design Point EX-D

Inflow Area = 26.000 ac, Inflow Depth = 0.79" for 100-Year event
 Inflow = 36.39 cfs @ 0.57 hrs, Volume= 1.713 af
 Primary = 36.39 cfs @ 0.57 hrs, Volume= 1.713 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs

Link DPexD: Design Point EX-D






Basin EX-B & OS1





Design Point EX-B



Basin EX-C



Design Point EX-C



TR20-100YR-24HR Existing

Type IIA 24-hr Rainfall=4.40"

Prepared by WestWorks Engineering

Page 2

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Time span=0.00-20.00 hrs, dt=0.05 hrs, 401 points

Runoff by SCS TR-20 method, UH=SCS

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment EX-B: Basin EX-B & OS1

Runoff Area=246.600 ac Runoff Depth=0.95"
Tc=69.6 min CN=61 Runoff=106.04 cfs 19.559 af

Subcatchment EX-C: Basin EX-C

Runoff Area=177.100 ac Runoff Depth=0.95"
Tc=83.9 min CN=61 Runoff=65.58 cfs 13.970 af

Link DPexB: Design Point EX-B

Inflow=106.04 cfs 19.559 af
Primary=106.04 cfs 19.559 af

Link DPexC: Design Point EX-C

Inflow=65.58 cfs 13.970 af
Primary=65.58 cfs 13.970 af

Total Runoff Area = 423.700 ac Runoff Volume = 33.530 af Average Runoff Depth = 0.95"

TR20-100YR-24HR Existing

Type IIA 24-hr Rainfall=4.40"

Prepared by WestWorks Engineering

Page 3

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment EX-B: Basin EX-B & OS1

Runoff = 106.04 cfs @ 6.81 hrs, Volume= 19.559 af, Depth= 0.95"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.05 hrs
Type IIA 24-hr Rainfall=4.40"

Area (ac)	CN	Description
224.300	61	Pasture/grassland/range, Good, HSG B
22.300	61	Basin OS1
246.600	61	Weighted Average

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
69.6					Direct Entry, Basin EX-B

Subcatchment EX-C: Basin EX-C

Runoff = 65.58 cfs @ 7.01 hrs, Volume= 13.970 af, Depth= 0.95"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.05 hrs
Type IIA 24-hr Rainfall=4.40"

Area (ac)	CN	Description
177.100	61	Pasture/grassland/range, Good, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
83.9					Direct Entry, Basin EX-C

Link DPexB: Design Point EX-B

Inflow Area = 246.600 ac, Inflow Depth = 0.95"
 Inflow = 106.04 cfs @ 6.81 hrs, Volume= 19.559 af
 Primary = 106.04 cfs @ 6.81 hrs, Volume= 19.559 af, Atten= 0%, Lag= 0.0 min




Primary outflow = Inflow, Time Span= 0.00-20.00 hrs, dt= 0.05 hrs

Link DPexC: Design Point EX-C

Inflow Area = 177.100 ac, Inflow Depth = 0.95"
 Inflow = 65.58 cfs @ 7.01 hrs, Volume= 13.970 af
 Primary = 65.58 cfs @ 7.01 hrs, Volume= 13.970 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-20.00 hrs, dt= 0.05 hrs

**DEVELOPED CONDITIONS
HYDROLOGIC CALCULATIONS
MINOR STORM
(RATIONAL METHOD – 5 YEAR)
(TR-20 – 10 YEAR)**



Drainage Diagram for Rational-5YR Developed
 Prepared by WestWorks Engineering 6/16/2005
 HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

Rational-5YR Developed

El Paso County 5-Year Duration=24 min, Inten=2.74 in/hr

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment A-1: Basin A-1

Runoff = 21.55 cfs @ 0.40 hrs, Volume= 0.712 af, Depth= 0.33"


Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
El Paso County 5-Year Duration=24 min, Inten=2.74 in/hr

Area (ac)	C	Description
26.000	0.30	5 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
23.8					Direct Entry, Basin A-1

Subcatchment A-1: Basin A-1

Hydrograph



Rational-5YR Developed

El Paso County 5-Year Duration=24 min, Inten=2.74 in/hr

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Pond DP-A1: Design Point A1

Inflow Area = 26.000 ac, Inflow Depth = 0.33" for 5-Year event
 Inflow = 21.55 cfs @ 0.40 hrs, Volume= 0.712 af
 Outflow = 1.25 cfs @ 0.77 hrs, Volume= 0.209 af, Atten= 94%, Lag= 22.5 min
 Primary = 1.25 cfs @ 0.77 hrs, Volume= 0.209 af

Routing by Stor-Ind method, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
 Peak Elev= 6,220.67' @ 0.77 hrs Surf.Area= 0.700 ac Storage= 0.678 af
 Plug-Flow detention time= 83.4 min calculated for 0.209 af (29% of inflow)
 Center-of-Mass det. time= 71.7 min (95.6 - 23.9)

#	Invert	Avail.Storage	Storage Description
1	6,220.00'	2.033 af	Custom Stage Data (Prismatic) Listed below

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
6,220.00	0.067	0.000	0.000
6,222.00	1.966	2.033	2.033


#	Routing	Invert	Outlet Devices
1	Primary	6,219.70'	2.0" Vert. Orifice/Grate X 2.00 C= 0.600
2	Primary	6,220.10'	14.2" x 50.0' long Culvert CMP, projecting, no headwall, Ke= 0.900 Outlet Invert= 6,219.00' S= 0.0220 ' n= 0.024 Cc= 0.900

Primary OutFlow Max=1.25 cfs @ 0.77 hrs HW=6,220.67' (Free Discharge)

1=Orifice/Grate (Orifice Controls 0.20 cfs @ 4.5 fps)
 2=Culvert (Inlet Controls 1.05 cfs @ 2.0 fps)

Pond DP-A1: Design Point A1

Hydrograph



Rational-5YR Developed

El Paso County 5-Year Duration=23 min, Inten=2.80 in/hr

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment A-2: Basin A-2

Runoff = 12.99 cfs @ 0.38 hrs, Volume= 0.413 af, Depth= 0.32"

Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs


El Paso County 5-Year Duration=23 min, Inten=2.80 in/hr

Area (ac)	C	Description
15.400	0.30	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
22.9					Direct Entry, Basin A-2

Subcatchment A-2: Basin A-2

Hydrograph



Rational-5YR Developed*El Paso County 5-Year Duration=23 min, Inten=2.80 in/hr*

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Pond Pond A: Pond A

Inflow Area = 15.400 ac, Inflow Depth = 0.32" for 5-Year event
 Inflow = 12.99 cfs @ 0.38 hrs, Volume= 0.413 af
 Outflow = 0.10 cfs @ 0.76 hrs, Volume= 0.019 af, Atten= 99%, Lag= 23.0 min
 Primary = 0.10 cfs @ 0.76 hrs, Volume= 0.019 af

Routing by Stor-Ind method, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
 Peak Elev= 6,218.49' @ 0.76 hrs Surf.Area= 0.444 ac Storage= 0.411 af
 Plug-Flow detention time= 99.0 min calculated for 0.019 af (5% of inflow)
 Center-of-Mass det. time= 80.8 min (103.8 - 23.0)

#	Invert	Avail.Storage	Storage Description
1	6,218.00'	1.678 af	Custom Stage Data (Prismatic) Listed below

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
6,218.00	0.064	0.000	0.000
6,220.00	1.614	1.678	1.678

#	Routing	Invert	Outlet Devices
1	Primary	6,218.20'	2.0" Vert. Orifice/Grate X 2.00 C= 0.600
2	Primary	6,218.50'	15.1" x 20.0' long Culvert CMP, projecting, no headwall, Ke= 0.900 Outlet Invert= 6,217.80' S= 0.0350 '/' n= 0.022 Cc= 0.900


Primary OutFlow Max=0.10 cfs @ 0.76 hrs HW=6,218.49' (Free Discharge)

1=Orifice/Grate (Orifice Controls 0.10 cfs @ 2.2 fps)

2=Culvert (Controls 0.00 cfs)

Pond Pond A: Pond A

Hydrograph



Rational-5YR Developed*El Paso County 5-Year Duration=23 min, Inten=2.80 in/hr*

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment A-3: Basin A-3

Runoff = 1.75 cfs @ 0.38 hrs, Volume= 0.056 af, Depth= 0.32"

Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs


El Paso County 5-Year Duration=23 min, Inten=2.80 in/hr

Area (ac)	C	Description
2.100	0.30	5 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
23.2					Direct Entry, Basin A-3

Subcatchment A-3: Basin A-3


Hydrograph



Link DP-A: Design Point A

Inflow Area = 43.500 ac, Inflow Depth = 0.08" for 5-Year event
Inflow = 2.14 cfs @ 0.40 hrs, Volume= 0.286 af
Primary = 2.14 cfs @ 0.40 hrs, Volume= 0.286 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs

Link DP-A: Design Point A

Rational-5YR Developed*El Paso County 5-Year Duration=34 min, Inten=2.25 in/hr*

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment B-1: Basin B-1

Runoff = 16.26 cfs @ 0.57 hrs, Volume= 0.765 af, Depth= 0.38"


Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
El Paso County 5-Year Duration=34 min, Inten=2.25 in/hr

Area (ac)	C	Description
24.000	0.30	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
33.9					Direct Entry, Basin B-1

Subcatchment B-1: Basin B-1

Hydrograph



Rational-5YR Developed

El Paso County 5-Year Duration=34 min, Inten=2.25 in/hr

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Pond DP-B1: Design Point B-1

Inflow Area = 24.000 ac, Inflow Depth = 0.38" for 5-Year event
 Inflow = 16.26 cfs @ 0.57 hrs, Volume= 0.765 af
 Outflow = 7.42 cfs @ 0.87 hrs, Volume= 0.734 af, Atten= 54%, Lag= 18.5 min
 Primary = 7.42 cfs @ 0.87 hrs, Volume= 0.734 af

Routing by Stor-Ind method, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
 Peak Elev= 6,245.01' @ 0.87 hrs Surf.Area= 0.401 ac Storage= 0.442 af
 Plug-Flow detention time= 40.2 min calculated for 0.731 af (96% of inflow)
 Center-of-Mass det. time= 39.3 min (73.3 - 34.0)

#	Invert	Avail.Storage	Storage Description
1	6,243.00'	2.049 af	Custom Stage Data (Prismatic) Listed below


Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
6,243.00	0.005	0.000	0.000
6,244.00	0.077	0.041	0.041
6,246.00	0.721	0.798	0.839
6,247.00	1.700	1.210	2.049

#	Routing	Invert	Outlet Devices
1	Primary	6,243.50'	24.0" x 50.0' long Culvert CMP, end-section conforming to fill, Ke= 0.500 Outlet Invert= 6,243.00' S= 0.0100 '/ n= 0.024 Cc= 0.900

Primary OutFlow Max=7.42 cfs @ 0.87 hrs HW=6,245.01' (Free Discharge)
 ↑1=Culvert (Barrel Controls 7.42 cfs @ 4.1 fps)

Pond DP-B1: Design Point B-1

Hydrograph



Rational-5YR Developed

El Paso County 5-Year Duration=27 min, Inten=2.57 in/hr

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment B-2: Basin B-2

Runoff = 4.94 cfs @ 0.45 hrs, Volume= 0.184 af, Depth= 0.34"


Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
El Paso County 5-Year Duration=27 min, Inten=2.57 in/hr

Area (ac)	C	Description
6.400	0.30	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
27.2					Direct Entry, Basin B-2

Subcatchment B-2: Basin B-2

Hydrograph



Runoff

Rational-5YR Developed

El Paso County 5-Year Duration=27 min, Inten=2.57 in/hr

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Pond DP-B2: Design Point B2

Inflow Area = 6.400 ac, Inflow Depth = 0.34" for 5-Year event
 Inflow = 4.94 cfs @ 0.45 hrs, Volume= 0.184 af
 Outflow = 1.37 cfs @ 0.78 hrs, Volume= 0.131 af, Atten= 72%, Lag= 19.5 min
 Primary = 1.37 cfs @ 0.78 hrs, Volume= 0.131 af

Routing by Stor-Ind method, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
 Peak Elev= 6,244.64' @ 0.78 hrs Surf.Area= 0.151 ac Storage= 0.144 af
 Plug-Flow detention time= 55.3 min calculated for 0.131 af (71% of inflow)
 Center-of-Mass det. time= 50.2 min (77.2 - 27.0)

#	Invert	Avail.Storage	Storage Description
1	6,244.00'	0.446 af	Custom Stage Data (Prismatic) Listed below


Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
6,244.00	0.019	0.000	0.000
6,246.00	0.427	0.446	0.446

#	Routing	Invert	Outlet Devices
1	Primary	6,244.00'	18.0" x 50.0' long Culvert CMP, end-section conforming to fill, Ke= 0.500 Outlet Invert= 6,243.50' S= 0.0100 ' /' n= 0.022 Cc= 0.900

Primary OutFlow Max=1.37 cfs @ 0.78 hrs HW=6,244.64' (Free Discharge)
 1=Culvert (Barrel Controls 1.37 cfs @ 2.8 fps)

Pond DP-B2: Design Point B2

Hydrograph



Rational-5YR Developed

El Paso County 5-Year Duration=27 min, Inten=2.57 in/hr

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment B-3: Basin B-3

Runoff = 34.22 cfs @ 0.45 hrs, Volume= 1.272 af, Depth= 0.35"

Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs


El Paso County 5-Year Duration=27 min, Inten=2.57 in/hr

Area (ac)	C	Description
44.000	0.30	5 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
26.7					Direct Entry, Basin B-3

Subcatchment B-3: Basin B-3

Hydrograph



Rational-5YR Developed

El Paso County 5-Year Duration=30 min, Inten=2.42 in/hr

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment B-4: Basin B-4

Runoff = 48.54 cfs @ 0.50 hrs, Volume= 2.006 af, Depth= 0.36"


Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
El Paso County 5-Year Duration=30 min, Inten=2.42 in/hr

Area (ac)	C	Description
66.300	0.30	5 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
29.8					Direct Entry, Basin B-4

Subcatchment B-4: Basin B-4

Hydrograph



Runoff

Rational-5YR Developed

El Paso County 5-Year Duration=30 min, Inten=2.42 in/hr

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment B-5: Basin B-5

Runoff = 62.33 cfs @ 0.50 hrs, Volume= 2.576 af, Depth= 0.36"


Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
El Paso County 5-Year Duration=30 min, Inten=2.42 in/hr

Area (ac)	C	Description
86.000	0.30	5 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
30.3					Direct Entry, Basin B-5

Subcatchment B-5: Basin B-5

Hydrograph



Rational-5YR Developed*El Paso County 5-Year Duration=25 min, Inten=2.68 in/hr*

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment OS1: Off-Site Basin OS1

Runoff = 15.08 cfs @ 0.41 hrs, Volume= 0.519 af, Depth= 0.28"


Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
El Paso County 5-Year Duration=25 min, Inten=2.68 in/hr

Area (ac)	C	Description
22.300	0.25	Pasture/grassland/range, Good, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
24.5					Direct Entry, Basin OS1

Subcatchment OS1: Off-Site Basin OS1

Hydrograph



Rational-5YR Developed

Prepared by WestWorks Engineering

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

El Paso County 5-Year Duration=47 min, Inten=1.85 in/hr

Page 1

6/16/2005

Subcatchment C-1: Basin C-1

Runoff = 24.12 cfs @ 0.78 hrs, Volume= 1.561 af, Depth= 0.43"

Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs


El Paso County 5-Year Duration=47 min, Inten=1.85 in/hr

Area (ac)	C	Description
43.100	0.30	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
46.6					Direct Entry, Basin C-1

Subcatchment C-1: Basin C-1

Hydrograph



Runoff

Rational-5YR Developed

El Paso County 5-Year Duration=47 min, Inten=1.85 in/hr

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Pond DP-C1: Design Point C1

Inflow Area = 56.800 ac, Inflow Depth = 0.43" for 5-Year event
Inflow = 31.79 cfs @ 0.78 hrs, Volume= 2.058 af
Outflow = 31.71 cfs @ 0.79 hrs, Volume= 2.058 af, Atten= 0%, Lag= 0.3 min
Primary = 31.71 cfs @ 0.79 hrs, Volume= 2.058 af

Routing by Stor-Ind method, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
Peak Elev= 6,213.81' @ 0.79 hrs Surf.Area= 0.015 ac Storage= 0.019 af
Plug-Flow detention time= 0.5 min calculated for 2.051 af (100% of inflow)
Center-of-Mass det. time= 0.5 min (45.9 - 45.4)

#	Invert	Avail.Storage	Storage Description
1	6,212.00'	0.894 af	Custom Stage Data (Prismatic) Listed below

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
6,212.00	0.005	0.000	0.000
6,214.00	0.016	0.021	0.021
6,215.50	1.148	0.873	0.894


#	Routing	Invert	Outlet Devices
1	Primary	6,211.70'	30.0" x 50.0' long Culvert X 2.00 CMP, end-section conforming to fill, Ke= 0.500 Outlet Invert= 6,211.20' S= 0.0100 '/' n= 0.024 Cc= 0.900

Primary OutFlow Max=31.67 cfs @ 0.79 hrs HW=6,213.81' (Free Discharge)

↑1=Culvert (Barrel Controls 31.67 cfs @ 4.8 fps)

Pond DP-C1: Design Point C1

Hydrograph



Rational-5YR Developed*El Paso County 5-Year Duration=29 min, Inten=2.47 in/hr*

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment C-2: Basin C-2

Runoff = 10.14 cfs @ 0.48 hrs, Volume= 0.407 af, Depth= 0.36"


Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
El Paso County 5-Year Duration=29 min, Inten=2.47 in/hr

Area (ac)	C	Description
13.700	0.30	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
29.1					Direct Entry, Basin C-2

Subcatchment C-2: Basin C-2

Hydrograph



Runoff

Rational-5YR Developed

El Paso County 5-Year Duration=29 min, Inten=2.47 in/hr

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Pond DP-C2: Design Point C2

Inflow Area = 13.700 ac, Inflow Depth = 0.36" for 5-Year event
 Inflow = 10.14 cfs @ 0.48 hrs, Volume= 0.407 af
 Outflow = 9.52 cfs @ 0.52 hrs, Volume= 0.407 af, Atten= 6%, Lag= 2.0 min
 Primary = 9.52 cfs @ 0.52 hrs, Volume= 0.407 af

Routing by Stor-Ind method, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
 Peak Elev= 6,221.76' @ 0.52 hrs Surf.Area= 0.052 ac Storage= 0.039 af
 Plug-Flow detention time= 3.0 min calculated for 0.406 af (100% of inflow)
 Center-of-Mass det. time= 3.0 min (32.0 - 29.0)

#	Invert	Avail.Storage	Storage Description	
1	6,220.50'	0.301 af	Custom Stage Data (Prismatic) Listed below	
Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)	
6,220.50	0.000	0.000	0.000	
6,222.00	0.062	0.046	0.046	
6,223.33	0.321	0.255	0.301	


#	Routing	Invert	Outlet Devices	
1	Primary	6,220.00'	24.0" x 50.0' long Culvert CMP, end-section conforming to fill, Ke= 0.500 Outlet Invert= 6,219.50' S= 0.0100 '/ n= 0.024 Cc= 0.900	

Primary OutFlow Max=9.52 cfs @ 0.52 hrs HW=6,221.76' (Free Discharge)

↑1=Culvert (Barrel Controls 9.52 cfs @ 4.3 fps)

Pond DP-C2: Design Point C2

Hydrograph



Rational-5YR Developed

El Paso County 5-Year Duration=21 min, Inten=2.94 in/hr

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment C-3: Basin C-3

Runoff = 7.92 cfs @ 0.35 hrs, Volume= 0.229 af, Depth= 0.31"


Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
El Paso County 5-Year Duration=21 min, Inten=2.94 in/hr

Area (ac)	C	Description
8.900	0.30	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
21.0					Direct Entry, Basin C-3

Subcatchment C-3: Basin C-3

Hydrograph



Rational-5YR Developed

El Paso County 5-Year Duration=21 min, Inten=2.94 in/hr

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Pond DP-C3: Design Point C3

Inflow Area = 8.900 ac, Inflow Depth = 0.31" for 5-Year event
Inflow = 7.92 cfs @ 0.35 hrs, Volume= 0.229 af
Outflow = 1.91 cfs @ 0.62 hrs, Volume= 0.229 af, Atten= 76%, Lag= 15.9 min
Primary = 1.91 cfs @ 0.62 hrs, Volume= 0.229 af

Routing by Stor-Ind method, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs

Peak Elev= 6,220.30' @ 0.62 hrs Surf.Area= 0.239 ac Storage= 0.161 af

Plug-Flow detention time= 43.0 min calculated for 0.229 af (100% of inflow)

Center-of-Mass det. time= 42.9 min (63.9 - 21.0)

#	Invert	Avail.Storage	Storage Description
1	6,220.00'	1.083 af	Custom Stage Data (Prismatic) Listed below

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
6,220.00	0.110	0.000	0.000
6,222.00	0.973	1.083	1.083


#	Routing	Invert	Outlet Devices
1	Primary	6,219.50'	18.0" x 50.0' long Culvert CMP, end-section conforming to fill, Ke= 0.500 Outlet Invert= 6,219.00' S= 0.0100 ' /' n= 0.024 Cc= 0.900

Primary OutFlow Max=1.91 cfs @ 0.62 hrs HW=6,220.30' (Free Discharge)

↑1=Culvert (Barrel Controls 1.91 cfs @ 2.9 fps)

Pond DP-C3: Design Point C3

Hydrograph



Rational-5YR Developed*El Paso County 5-Year Duration=23 min, Inten=2.80 in/hr*

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment C-4: Basin C-4

Runoff = 5.97 cfs @ 0.38 hrs, Volume= 0.191 af, Depth= 0.32"


Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
El Paso County 5-Year Duration=23 min, Inten=2.80 in/hr

Area (ac)	C	Description
7.100	0.30	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
23.0					Direct Entry, Basin C-4

Subcatchment C-4: Basin C-4

Hydrograph



Rational-5YR Developed

El Paso County 5-Year Duration=29 min, Inten=2.47 in/hr

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment C-5: Basin C-5

Runoff = 15.56 cfs @ 0.48 hrs, Volume= 0.625 af, Depth= 0.36"


Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
El Paso County 5-Year Duration=29 min, Inten=2.47 in/hr

Area (ac)	C	Description
21.100	0.30	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
29.2					Direct Entry, Basin C-5

Subcatchment C-5: Basin C-5

Hydrograph



Runoff

Rational-5YR Developed

El Paso County 5-Year Duration=32 min, Inten=2.33 in/hr

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment C-6: Basin C-6

Runoff = 56.43 cfs @ 0.53 hrs, Volume= 2.501 af, Depth= 0.37"


Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
El Paso County 5-Year Duration=32 min, Inten=2.33 in/hr

Area (ac)	C	Description
80.500	0.30	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
32.0					Direct Entry, Basin C-6

Subcatchment C-6: Basin C-6

Hydrograph



Rational-5YR Developed*El Paso County 5-Year Duration=22 min, Inten=2.87 in/hr*

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment D-1: Basin D-1

Runoff = 5.04 cfs @ 0.36 hrs, Volume= 0.153 af, Depth= 0.32"


Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
El Paso County 5-Year Duration=22 min, Inten=2.87 in/hr

Area (ac)	C	Description
5.800	0.30	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
21.6					Direct Entry, Basin D-1

Subcatchment D-1: Basin D-1

Hydrograph



Rational-5YR Developed*El Paso County 5-Year Duration=20 min, Inten=3.01 in/hr*

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment D-2: Basin D-2

Runoff = 18.05 cfs @ 0.33 hrs, Volume= 0.502 af, Depth= 0.30"

Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs


El Paso County 5-Year Duration=20 min, Inten=3.01 in/hr

Area (ac)	C	Description
20.200	0.30	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
20.2					Direct Entry, Basin D-2

Subcatchment D-2: Basin D-2

Hydrograph



Runoff

Rational-5YR Developed*El Paso County 5-Year Duration=20 min, Inten=3.01 in/hr*

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Pond Pond D: Pond D

Inflow Area = 20.200 ac, Inflow Depth = 0.30" for 5-Year event
 Inflow = 18.05 cfs @ 0.33 hrs, Volume= 0.502 af
 Outflow = 0.32 cfs @ 0.66 hrs, Volume= 0.056 af, Atten= 98%, Lag= 19.8 min
 Primary = 0.32 cfs @ 0.66 hrs, Volume= 0.056 af

Routing by Stor-Ind method, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
 Peak Elev= 6,190.52' @ 0.66 hrs Surf.Area= 0.659 ac Storage= 0.496 af
 Plug-Flow detention time= 92.4 min calculated for 0.056 af (11% of inflow)
 Center-of-Mass det. time= 78.7 min (98.7 - 20.0)

#	Invert	Avail.Storage	Storage Description
1	6,190.00'	1.921 af	Custom Stage Data (Prismatic) Listed below

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
6,190.00	0.337	0.000	0.000
6,192.00	1.584	1.921	1.921

#	Routing	Invert	Outlet Devices
1	Primary	6,190.08'	1.0" Vert. Orifice/Grate X 2.00 C= 0.600
2	Primary	6,190.25'	17.0" x 15.0' long Culvert CMP, projecting, no headwall, Ke= 0.900 Outlet Invert= 6,189.80' S= 0.0300 '/' n= 0.022 Cc= 0.900


Primary OutFlow Max=0.32 cfs @ 0.66 hrs HW=6,190.52' (Free Discharge)

1=Orifice/Grate (Orifice Controls 0.03 cfs @ 3.0 fps)

2=Culvert (Inlet Controls 0.29 cfs @ 1.4 fps)

Pond Pond D: Pond D

Hydrograph



Rational-5YR Developed*El Paso County 5-Year Duration=22 min, Inten=2.87 in/hr*

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005


Link DP-D: Design Point D




Inflow Area = 26.000 ac, Inflow Depth = 0.10" for 5-Year event
Inflow = 5.07 cfs @ 0.36 hrs, Volume= 0.219 af
Primary = 5.07 cfs @ 0.36 hrs, Volume= 0.219 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs

Link DP-D: Design Point D

Hydrograph





Drainage Diagram for TR20-10YR-24HR Developed
 Prepared by WestWorks Engineering 6/16/2005
 HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

TR20-10YR-24HR Developed

Type IIA 24-hr Rainfall=3.00"

Prepared by WestWorks Engineering

Page 2

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Time span=0.00-20.00 hrs, dt=0.01 hrs, 2001 points

Runoff by SCS TR-20 method, UH=SCS

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment B-1: Basin B-1	Runoff Area=24.000 ac Runoff Depth=0.47" Tc=33.9 min CN=65 Runoff=7.89 cfs 0.945 af
Subcatchment B-2: Basin B-2	Runoff Area=6.400 ac Runoff Depth=0.47" Tc=27.2 min CN=65 Runoff=2.49 cfs 0.253 af
Subcatchment B-3: Basin B-3	Runoff Area=44.000 ac Runoff Depth=0.47" Tc=26.7 min CN=65 Runoff=17.46 cfs 1.737 af
Subcatchment B-4: Basin B-4	Runoff Area=66.300 ac Runoff Depth=0.47" Tc=29.8 min CN=65 Runoff=24.04 cfs 2.614 af
Subcatchment B-5: Basin B-5	Runoff Area=86.000 ac Runoff Depth=0.47" Tc=30.3 min CN=65 Runoff=30.98 cfs 3.390 af
Subcatchment C-1: Basin C-1	Runoff Area=43.100 ac Runoff Depth=0.47" Tc=46.6 min CN=65 Runoff=11.01 cfs 1.687 af
Subcatchment C-2: Basin C-2	Runoff Area=13.700 ac Runoff Depth=0.47" Tc=29.1 min CN=65 Runoff=5.07 cfs 0.540 af
Subcatchment C-3: Basin C-3	Runoff Area=8.900 ac Runoff Depth=0.48" Tc=21.0 min CN=65 Runoff=4.18 cfs 0.352 af
Subcatchment C-4: Basin C-4	Runoff Area=7.100 ac Runoff Depth=0.47" Tc=23.0 min CN=65 Runoff=3.13 cfs 0.281 af
Subcatchment C-5: Basin C-5	Runoff Area=21.100 ac Runoff Depth=0.47" Tc=29.2 min CN=65 Runoff=7.76 cfs 0.832 af
Subcatchment C-6: Basin C-6	Runoff Area=80.500 ac Runoff Depth=0.47" Tc=32.0 min CN=65 Runoff=27.57 cfs 3.171 af
Subcatchment OS1: Off-Site Basin OS1	Runoff Area=22.300 ac Runoff Depth=0.34" Tc=24.5 min CN=61 Runoff=5.68 cfs 0.630 af
Pond DP-B1: Design Point B-1	Peak Elev=6,244.45' Storage=0.219 af Inflow=7.89 cfs 0.945 af 24.0" x 50.0' Culvert Outflow=3.44 cfs 0.912 af
Pond DP-B2: Design Point B2	Peak Elev=6,244.39' Storage=0.088 af Inflow=2.49 cfs 0.253 af 18.0" x 50.0' Culvert Outflow=0.52 cfs 0.215 af
Pond DP-B4: Design Point B4	Peak Elev=6,194.50' Storage=0.652 af Inflow=48.32 cfs 6.109 af Outflow=30.25 cfs 6.041 af

TR20-10YR-24HR Developed*Type IIA 24-hr Rainfall=3.00"*

Prepared by WestWorks Engineering

Page 3

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Pond DP-C1: Design Point C1Peak Elev=6,213.06' Storage=0.011 af Inflow=15.04 cfs 2.220 af
30.0" x 50.0' Culvert Outflow=15.04 cfs 2.220 af**Pond DP-C2: Design Point C2**Peak Elev=6,221.68' Storage=0.036 af Inflow=5.07 cfs 0.540 af
24.0" x 50.0' Culvert Outflow=4.85 cfs 0.533 af**Pond DP-C3: Design Point C3**Peak Elev=6,220.15' Storage=0.080 af Inflow=4.18 cfs 0.352 af
18.0" x 50.0' Culvert Outflow=1.29 cfs 0.351 af**Pond Pond B: Pond B**Peak Elev=6,183.60' Storage=4.918 af Inflow=58.99 cfs 9.431 af
Outflow=5.82 cfs 5.243 af**Pond Pond C: Pond C**Peak Elev=6,201.36' Storage=4.119 af Inflow=52.19 cfs 6.855 af
Outflow=3.01 cfs 2.934 af**Total Runoff Area = 423.400 ac Runoff Volume = 16.432 af Average Runoff Depth = 0.47"**

TR20-10YR-24HR Developed

Prepared by WestWorks Engineering
HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

Type IIA 24-hr Rainfall=3.00"

Page 4
6/16/2005

Subcatchment B-1: Basin B-1

Runoff = 7.89 cfs @ 6.36 hrs, Volume= 0.945 af, Depth= 0.47"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs
Type IIA 24-hr Rainfall=3.00"

Area (ac)	CN	Description
24.000	65	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
33.9					Direct Entry, Basin B-1

Subcatchment B-2: Basin B-2

Runoff = 2.49 cfs @ 6.26 hrs, Volume= 0.253 af, Depth= 0.47"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs
Type IIA 24-hr Rainfall=3.00"

Area (ac)	CN	Description
6.400	65	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
27.2					Direct Entry, Basin B-2

Subcatchment B-3: Basin B-3

Runoff = 17.46 cfs @ 6.26 hrs, Volume= 1.737 af, Depth= 0.47"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs
Type IIA 24-hr Rainfall=3.00"

Area (ac)	CN	Description
44.000	65	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
26.7					Direct Entry, Basin B-3

Subcatchment B-4: Basin B-4

Runoff = 24.04 cfs @ 6.29 hrs, Volume= 2.614 af, Depth= 0.47"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs
Type IIA 24-hr Rainfall=3.00"

TR20-10YR-24HR Developed

Type IIA 24-hr Rainfall=3.00"

Prepared by WestWorks Engineering

Page 5

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Area (ac)	CN	Description
66.300	65	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
29.8					Direct Entry, Basin B-4

Subcatchment B-5: Basin B-5

Runoff = 30.98 cfs @ 6.30 hrs, Volume= 3.390 af, Depth= 0.47"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs
Type IIA 24-hr Rainfall=3.00"

Area (ac)	CN	Description
86.000	65	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
30.3					Direct Entry, Basin B-5

Subcatchment C-1: Basin C-1

Runoff = 11.01 cfs @ 6.52 hrs, Volume= 1.687 af, Depth= 0.47"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs
Type IIA 24-hr Rainfall=3.00"

Area (ac)	CN	Description
43.100	65	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
46.6					Direct Entry, Basin C-1

Subcatchment C-2: Basin C-2

Runoff = 5.07 cfs @ 6.30 hrs, Volume= 0.540 af, Depth= 0.47"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs
Type IIA 24-hr Rainfall=3.00"

Area (ac)	CN	Description
13.700	65	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
29.1					Direct Entry, Basin C-2

TR20-10YR-24HR Developed

Type IIA 24-hr Rainfall=3.00"

Prepared by WestWorks Engineering

Page 6

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment C-3: Basin C-3

Runoff = 4.18 cfs @ 6.18 hrs, Volume= 0.352 af, Depth= 0.48"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs
Type IIA 24-hr Rainfall=3.00"

Area (ac)	CN	Description
8.900	65	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
21.0					Direct Entry, Basin C-3

Subcatchment C-4: Basin C-4

Runoff = 3.13 cfs @ 6.21 hrs, Volume= 0.281 af, Depth= 0.47"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs
Type IIA 24-hr Rainfall=3.00"

Area (ac)	CN	Description
7.100	65	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
23.0					Direct Entry, Basin C-4

Subcatchment C-5: Basin C-5

Runoff = 7.76 cfs @ 6.29 hrs, Volume= 0.832 af, Depth= 0.47"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs
Type IIA 24-hr Rainfall=3.00"

Area (ac)	CN	Description
21.100	65	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
29.2					Direct Entry, Basin C-5

Subcatchment C-6: Basin C-6

Runoff = 27.57 cfs @ 6.33 hrs, Volume= 3.171 af, Depth= 0.47"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs
Type IIA 24-hr Rainfall=3.00"

TR20-10YR-24HR Developed

Type IIA 24-hr Rainfall=3.00"

Prepared by WestWorks Engineering

Page 7

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Area (ac)	CN	Description
80.500	65	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
32.0					Direct Entry, Basin C-6

Subcatchment OS1: Off-Site Basin OS1

Runoff = 5.68 cfs @ 6.24 hrs, Volume= 0.630 af, Depth= 0.34"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs

Type IIA 24-hr Rainfall=3.00"

Area (ac)	CN	Description
22.300	61	Pasture/grassland/range, Good, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
24.5					Direct Entry, Basin OS1

Pond DP-B1: Design Point B-1

Inflow Area = 24.000 ac, Inflow Depth = 0.47"

Inflow = 7.89 cfs @ 6.36 hrs, Volume= 0.945 af

Outflow = 3.44 cfs @ 6.78 hrs, Volume= 0.912 af, Atten= 56%, Lag= 25.3 min

Primary = 3.44 cfs @ 6.78 hrs, Volume= 0.912 af

Routing by Stor-Ind method, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs

Peak Elev= 6,244.45' @ 6.78 hrs Surf.Area= 0.220 ac Storage= 0.219 af

Plug-Flow detention time= 49.3 min calculated for 0.912 af (97% of inflow)

Center-of-Mass det. time= 28.4 min (601.4 - 572.9)

#	Invert	Avail.Storage	Storage Description
1	6,243.00'	2.049 af	Custom Stage Data (Prismatic) Listed below

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
6,243.00	0.005	0.000	0.000
6,244.00	0.077	0.041	0.041
6,246.00	0.721	0.798	0.839
6,247.00	1.700	1.210	2.049

#	Routing	Invert	Outlet Devices
1	Primary	6,243.50'	24.0" x 50.0' long Culvert CMP, end-section conforming to fill, Ke= 0.500 Outlet Invert= 6,243.00' S=0.0100 '/ n= 0.022 Cc= 0.900

Primary OutFlow Max=3.44 cfs @ 6.78 hrs HW=6,244.45' (Free Discharge)

1=Culvert (Barrel Controls 3.44 cfs @ 3.5 fps)

TR20-10YR-24HR Developed

Type IIA 24-hr Rainfall=3.00"

Prepared by WestWorks Engineering

Page 8

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Pond DP-B2: Design Point B2

Inflow Area = 6.400 ac, Inflow Depth = 0.47"
 Inflow = 2.49 cfs @ 6.26 hrs, Volume= 0.253 af
 Outflow = 0.52 cfs @ 6.97 hrs, Volume= 0.215 af, Atten= 79%, Lag= 42.7 min
 Primary = 0.52 cfs @ 6.97 hrs, Volume= 0.215 af

Routing by Stor-Ind method, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs
 Peak Elev= 6,244.39' @ 6.97 hrs Surf.Area= 0.099 ac Storage= 0.088 af
 Plug-Flow detention time= 170.0 min calculated for 0.215 af (85% of inflow)
 Center-of-Mass det. time= 88.3 min (656.9 - 568.6)

#	Invert	Avail.Storage	Storage Description
1	6,244.00'	0.446 af	Custom Stage Data (Prismatic) Listed below
Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
6,244.00	0.019	0.000	0.000
6,246.00	0.427	0.446	0.446

#	Routing	Invert	Outlet Devices
1	Primary	6,244.00'	18.0" x 50.0' long Culvert CMP, end-section conforming to fill, Ke= 0.500 Outlet Invert= 6,243.50' S= 0.0100 ' n= 0.022 Cc= 0.900

Primary OutFlow Max=0.52 cfs @ 6.97 hrs HW=6,244.39' (Free Discharge)
 ↑1=Culvert (Barrel Controls 0.52 cfs @ 2.1 fps)

Pond DP-B4: Design Point B4

Inflow Area = 163.000 ac, Inflow Depth = 0.45"
 Inflow = 48.32 cfs @ 6.27 hrs, Volume= 6.109 af
 Outflow = 30.25 cfs @ 6.52 hrs, Volume= 6.041 af, Atten= 37%, Lag= 14.7 min
 Primary = 30.25 cfs @ 6.52 hrs, Volume= 6.041 af

Routing by Stor-Ind method, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs
 Peak Elev= 6,194.50' @ 6.52 hrs Surf.Area= 0.516 ac Storage= 0.652 af
 Plug-Flow detention time= 15.4 min calculated for 6.038 af (99% of inflow)
 Center-of-Mass det. time= 8.6 min (588.3 - 579.7)

#	Invert	Avail.Storage	Storage Description
1	6,192.00'	1.821 af	Custom Stage Data (Prismatic) Listed below
Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
6,192.00	0.009	0.000	0.000
6,194.00	0.253	0.262	0.262
6,196.00	1.306	1.559	1.821

#	Routing	Invert	Outlet Devices
1	Primary	6,192.00'	24.0" x 50.0' long Culvert X 2.00 CMP, end-section conforming to fill, Ke= 0.500

2 Primary 6,195.00' Outlet Invert= 6,191.50' S= 0.0100 '/ n= 0.022 Cc= 0.900
Roadway Overtop
 Head (feet) 0.00 0.50
 Disch. (cfs) 0.00 280.00

Primary OutFlow Max=30.26 cfs @ 6.52 hrs HW=6,194.50' (Free Discharge)

1=Culvert (Barrel Controls 30.26 cfs @ 4.9 fps)

2=Roadway Overtop (Controls 0.00 cfs)

Pond DP-C1: Design Point C1

[88] Warning: Qout>Qin may require Finer Routing>1

Inflow Area = 56.800 ac, Inflow Depth = 0.47"
 Inflow = 15.04 cfs @ 6.46 hrs, Volume= 2.220 af
 Outflow = 15.04 cfs @ 6.47 hrs, Volume= 2.220 af, Atten= 0%, Lag= 0.3 min
 Primary = 15.04 cfs @ 6.47 hrs, Volume= 2.220 af

Routing by Stor-Ind method, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs
 Peak Elev= 6,213.06' @ 6.47 hrs Surf.Area= 0.011 ac Storage= 0.011 af
 Plug-Flow detention time= 0.6 min calculated for 2.219 af (100% of inflow)
 Center-of-Mass det. time= 0.4 min (580.5 - 580.1)

#	Invert	Avail.Storage	Storage Description
1	6,212.00'	5.735 af	Custom Stage Data (Prismatic) Listed below

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
6,212.00	0.005	0.000	0.000
6,214.00	0.016	0.021	0.021
6,216.00	1.295	1.311	1.332
6,218.00	3.108	4.403	5.735

#	Routing	Invert	Outlet Devices
1	Primary	6,211.70'	30.0" x 50.0' long Culvert X 2.00 CMP, end-section conforming to fill, Ke= 0.500 Outlet Invert= 6,211.20' S= 0.0100 '/ n= 0.024 Cc= 0.900

Primary OutFlow Max=15.04 cfs @ 6.47 hrs HW=6,213.06' (Free Discharge)

1=Culvert (Barrel Controls 15.04 cfs @ 4.0 fps)

Pond DP-C2: Design Point C2

Inflow Area = 13.700 ac, Inflow Depth = 0.47"
 Inflow = 5.07 cfs @ 6.30 hrs, Volume= 0.540 af
 Outflow = 4.85 cfs @ 6.34 hrs, Volume= 0.533 af, Atten= 4%, Lag= 2.7 min
 Primary = 4.85 cfs @ 6.34 hrs, Volume= 0.533 af

Routing by Stor-Ind method, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs

TR20-10YR-24HR Developed

Type IIA 24-hr Rainfall=3.00"

Prepared by WestWorks Engineering
HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer SystemsPage 10
6/16/2005

Peak Elev= 6,221.68' @ 6.34 hrs Surf.Area= 0.049 ac Storage= 0.036 af
 Plug-Flow detention time= 15.1 min calculated for 0.533 af (99% of inflow)
 Center-of-Mass det. time= 6.9 min (576.8 - 569.8)

#	Invert	Avail.Storage	Storage Description
1	6,220.50'	0.301 af	Custom Stage Data (Prismatic) Listed below

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
6,220.50	0.000	0.000	0.000
6,222.00	0.062	0.046	0.046
6,223.33	0.321	0.255	0.301

#	Routing	Invert	Outlet Devices
1	Primary	6,220.50'	24.0" x 50.0' long Culvert CMP, end-section conforming to fill, Ke= 0.500 Outlet Invert= 6,220.00' S= 0.0100 ' n= 0.024 Cc= 0.900

Primary OutFlow Max=4.85 cfs @ 6.34 hrs HW=6,221.68' (Free Discharge)
 1=Culvert (Barrel Controls 4.85 cfs @ 3.6 fps)

Pond DP-C3: Design Point C3

Inflow Area = 8.900 ac, Inflow Depth = 0.48"
 Inflow = 4.18 cfs @ 6.18 hrs, Volume= 0.352 af
 Outflow = 1.29 cfs @ 6.54 hrs, Volume= 0.351 af, Atten= 69%, Lag= 21.3 min
 Primary = 1.29 cfs @ 6.54 hrs, Volume= 0.351 af

Routing by Stor-Ind method, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs
 Peak Elev= 6,220.15' @ 6.54 hrs Surf.Area= 0.174 ac Storage= 0.080 af
 Plug-Flow detention time= 22.0 min calculated for 0.351 af (100% of inflow)
 Center-of-Mass det. time= 19.1 min (583.8 - 564.7)

#	Invert	Avail.Storage	Storage Description
1	6,220.00'	1.083 af	Custom Stage Data (Prismatic) Listed below

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
6,220.00	0.110	0.000	0.000
6,222.00	0.973	1.083	1.083

#	Routing	Invert	Outlet Devices
1	Primary	6,219.50'	18.0" x 50.0' long Culvert CMP, end-section conforming to fill, Ke= 0.500 Outlet Invert= 6,219.00' S= 0.0100 ' n= 0.024 Cc= 0.900

Primary OutFlow Max=1.29 cfs @ 6.54 hrs HW=6,220.15' (Free Discharge)
 1=Culvert (Barrel Controls 1.29 cfs @ 2.6 fps)

TR20-10YR-24HR Developed

Type IIA 24-hr Rainfall=3.00"

Prepared by WestWorks Engineering

Page 11

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Pond Pond B: Pond B

Inflow Area = 249.000 ac, Inflow Depth = 0.45"
 Inflow = 58.99 cfs @ 6.33 hrs, Volume= 9.431 af
 Outflow = 5.82 cfs @ 9.81 hrs, Volume= 5.243 af, Atten= 90%, Lag= 208.5 min
 Primary = 5.82 cfs @ 9.81 hrs, Volume= 5.243 af

Routing by Stor-Ind method, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs
 Peak Elev= 6,183.60' @ 9.81 hrs Surf.Area= 3.964 ac Storage= 4.918 af
 Plug-Flow detention time= 377.7 min calculated for 5.243 af (56% of inflow)
 Center-of-Mass det. time= 206.1 min (788.1 - 581.9)

#	Invert	Avail.Storage	Storage Description
1	6,182.00'	18.024 af	Custom Stage Data (Prismatic) Listed below

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
6,182.00	1.586	0.000	0.000
6,184.00	4.555	6.141	6.141
6,186.00	7.328	11.883	18.024

#	Routing	Invert	Outlet Devices
1	Primary	6,182.20'	2.0" Vert. Orifice/Grate X 2.00 C= 0.600
2	Primary	6,182.50'	27.8" x 25.0' long Culvert CMP, projecting, no headwall, Ke= 0.900 Outlet Invert= 6,181.75' S= 0.0300 '/ n= 0.024 Cc= 0.900

Primary OutFlow Max=5.82 cfs @ 9.81 hrs HW=6,183.60' (Free Discharge)

1=Orifice/Grate (Orifice Controls 0.24 cfs @ 5.5 fps)

2=Culvert (Inlet Controls 5.58 cfs @ 2.8 fps)

Pond Pond C: Pond C

Inflow Area = 174.400 ac, Inflow Depth = 0.47"
 Inflow = 52.19 cfs @ 6.34 hrs, Volume= 6.855 af
 Outflow = 3.01 cfs @ 13.92 hrs, Volume= 2.934 af, Atten= 94%, Lag= 454.8 min
 Primary = 3.01 cfs @ 13.92 hrs, Volume= 2.934 af

Routing by Stor-Ind method, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs
 Peak Elev= 6,201.36' @ 13.92 hrs Surf.Area= 3.692 ac Storage= 4.119 af
 Plug-Flow detention time= 432.6 min calculated for 2.934 af (43% of inflow)
 Center-of-Mass det. time= 247.7 min (822.4 - 574.7)

#	Invert	Avail.Storage	Storage Description
1	6,200.00'	20.381 af	Custom Stage Data (Prismatic) Listed below

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
6,200.00	1.196	0.000	0.000
6,202.00	4.876	6.072	6.072
6,204.00	9.433	14.309	20.381

TR20-10YR-24HR Developed*Type IIA 24-hr Rainfall=3.00"*

Prepared by WestWorks Engineering

Page 12

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005



#	Routing	Invert	Outlet Devices
1	Primary	6,200.20'	2.0" Vert. Orifice/Grate X 2.00 C= 0.600
2	Primary	6,200.50'	27.8" x 25.0' long Culvert CMP, projecting, no headwall, Ke= 0.900 Outlet Invert= 6,200.25' S= 0.0100 '/ n= 0.024 Cc= 0.900

Primary OutFlow Max=3.01 cfs @ 13.92 hrs HW=6,201.36' (Free Discharge)

1=Orifice/Grate (Orifice Controls 0.22 cfs @ 5.0 fps)

2=Culvert (Barrel Controls 2.79 cfs @ 2.9 fps)

**DEVELOPED CONDITIONS
HYDROLOGIC CALCULATIONS
MAJOR STORM
(RATIONAL METHOD – 100 YEAR)
(TR-20 – 100 YEAR)**



Rational-100YR Developed

El Paso County 100-Year Duration=24 min, Inten=4.88 in/hr

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment A-1: Basin A-1

Runoff = 51.19 cfs @ 0.40 hrs, Volume= 1.692 af, Depth= 0.78"


Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
El Paso County 100-Year Duration=24 min, Inten=4.88 in/hr

Area (ac)	C	Description
26.000	0.40	5 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
23.8					Direct Entry, Basin A-1

Subcatchment A-1: Basin A-1

Hydrograph



Pond DP-A1: Design Point A1

Inflow Area = 26.000 ac, Inflow Depth = 0.78" for 100-Year event
 Inflow = 51.19 cfs @ 0.40 hrs, Volume= 1.692 af
 Outflow = 4.13 cfs @ 0.76 hrs, Volume= 0.722 af, Atten= 92%, Lag= 21.9 min
 Primary = 4.13 cfs @ 0.76 hrs, Volume= 0.722 af

Routing by Stor-Ind method, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
 Peak Elev= 6,221.54' @ 0.76 hrs Surf.Area= 1.531 ac Storage= 1.567 af
 Plug-Flow detention time= 80.1 min calculated for 0.722 af (43% of inflow)
 Center-of-Mass det. time= 70.9 min (94.8 - 23.9)

#	Invert	Avail.Storage	Storage Description
1	6,220.00'	2.033 af	Custom Stage Data (Prismatic) Listed below

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
6,220.00	0.067	0.000	0.000
6,222.00	1.966	2.033	2.033

#	Routing	Invert	Outlet Devices
1	Primary	6,219.70'	2.0" Vert. Orifice/Grate X 2.00 C= 0.600
2	Primary	6,220.10'	14.2" x 50.0' long Culvert CMP, projecting, no headwall, Ke= 0.900 Outlet Invert= 6,219.00' S= 0.0220 '/ n= 0.024 Cc= 0.900


Primary OutFlow Max=4.13 cfs @ 0.76 hrs HW=6,221.54' (Free Discharge)

1=Orifice/Grate (Orifice Controls 0.28 cfs @ 6.4 fps)

2=Culvert (Inlet Controls 3.85 cfs @ 3.5 fps)

Pond DP-A1: Design Point A1

Hydrograph



Rational-100YR Developed*El Paso County 100-Year Duration=23 min, Inten=4.99 in/hr*

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment A-2: Basin A-2

Runoff = 30.88 cfs @ 0.38 hrs, Volume= 0.982 af, Depth= 0.77"


Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
El Paso County 100-Year Duration=23 min, Inten=4.99 in/hr

Area (ac)	C	Description
15.400	0.40	5 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
22.9					Direct Entry, Basin A-2

Subcatchment A-2: Basin A-2

Hydrograph



Rational-100YR Developed

El Paso County 100-Year Duration=23 min, Inten=4.99 in/hr

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment A-3: Basin A-3

Runoff = 4.16 cfs @ 0.38 hrs, Volume= 0.133 af, Depth= 0.76"


Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
El Paso County 100-Year Duration=23 min, Inten=4.99 in/hr

Area (ac)	C	Description
2.100	0.40	5 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
23.2					Direct Entry, Basin A-3

Subcatchment A-3: Basin A-3

Hydrograph



Rational-100YR Developed*El Paso County 100-Year Duration=23 min, Inten=4.99 in/hr*

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Pond Pond A: Pond A

Inflow Area = 15.400 ac, Inflow Depth = 0.77" for 100-Year event
 Inflow = 30.88 cfs @ 0.38 hrs, Volume= 0.982 af
 Outflow = 1.53 cfs @ 0.75 hrs, Volume= 0.229 af, Atten= 95%, Lag= 21.9 min
 Primary = 1.53 cfs @ 0.75 hrs, Volume= 0.229 af

Routing by Stor-Ind method, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
 Peak Elev= 6,219.13' @ 0.75 hrs Surf.Area= 0.942 ac Storage= 0.951 af
 Plug-Flow detention time= 84.6 min calculated for 0.228 af (23% of inflow)
 Center-of-Mass det. time= 72.4 min (95.4 - 23.0)

#	Invert	Avail.Storage	Storage Description
1	6,218.00'	1.678 af	Custom Stage Data (Prismatic) Listed below

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
6,218.00	0.064	0.000	0.000
6,220.00	1.614	1.678	1.678

#	Routing	Invert	Outlet Devices
1	Primary	6,218.20'	2.0" Vert. Orifice/Grate X 2.00 C= 0.600
2	Primary	6,218.50'	15.1" x 20.0' long Culvert CMP, projecting, no headwall, Ke= 0.900 Outlet Invert= 6,217.80' S= 0.0350 '/' n= 0.022 Cc= 0.900


Primary OutFlow Max=1.53 cfs @ 0.75 hrs HW=6,219.13' (Free Discharge)

1=Orifice/Grate (Orifice Controls 0.19 cfs @ 4.4 fps)

2=Culvert (Inlet Controls 1.34 cfs @ 2.1 fps)

Pond Pond A: Pond A

Hydrograph



Link DP-A: Design Point A

Inflow Area = 43.500 ac, Inflow Depth = 0.30" for 100-Year event


Inflow = 7.03 cfs @ 0.57 hrs, Volume= 1.098 af

Primary = 7.03 cfs @ 0.57 hrs, Volume= 1.098 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs

Link DP-A: Design Point A

Hydrograph



Rational-100YR Developed*El Paso County 100-Year Duration=34 min, Inten=4.01 in/hr*

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment B-1: Basin B-1

Runoff = 38.64 cfs @ 0.57 hrs, Volume= 1.818 af, Depth= 0.91"


Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
El Paso County 100-Year Duration=34 min, Inten=4.01 in/hr

Area (ac)	C	Description
24.000	0.40	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
33.9					Direct Entry, Basin B-1

Subcatchment B-1: Basin B-1

Hydrograph



Rational-100YR Developed*El Paso County 100-Year Duration=34 min, Inten=4.01 in/hr*

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Pond DP-B1: Design Point B-1

Inflow Area = 24.000 ac, Inflow Depth = 0.91" for 100-Year event
 Inflow = 38.64 cfs @ 0.57 hrs, Volume= 1.818 af
 Outflow = 14.64 cfs @ 0.71 hrs, Volume= 1.738 af, Atten= 62%, Lag= 8.8 min
 Primary = 14.64 cfs @ 0.71 hrs, Volume= 1.738 af

Routing by Stor-Ind method, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
 Peak Elev= 6,246.19' @ 0.92 hrs Surf.Area= 0.909 ac Storage= 1.072 af
 Plug-Flow detention time= 40.3 min calculated for 1.732 af (95% of inflow)
 Center-of-Mass det. time= 39.3 min (73.3 - 34.0)

#	Invert	Avail.Storage	Storage Description
1	6,243.00'	2.049 af	Custom Stage Data (Prismatic) Listed below


Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
6,243.00	0.005	0.000	0.000
6,244.00	0.077	0.041	0.041
6,246.00	0.721	0.798	0.839
6,247.00	1.700	1.210	2.049

#	Routing	Invert	Outlet Devices
1	Primary	6,243.50'	24.0" x 50.0' long Culvert CMP, end-section conforming to fill, Ke= 0.500 Outlet Invert= 6,243.00' S= 0.0100 '/ n= 0.024 Cc= 0.900

Primary OutFlow Max=14.65 cfs @ 0.71 hrs HW=6,246.09' (Free Discharge)↑ **1=Culvert** (Barrel Controls 14.65 cfs @ 4.7 fps)

Pond DP-B1: Design Point B-1

Hydrograph



Rational-100YR Developed*El Paso County 100-Year Duration=27 min, Inten=4.57 in/hr*

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment B-2: Basin B-2

Runoff = 11.71 cfs @ 0.45 hrs, Volume= 0.435 af, Depth= 0.82"


Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
El Paso County 100-Year Duration=27 min, Inten=4.57 in/hr

Area (ac)	C	Description
6.400	0.40	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
27.2					Direct Entry, Basin B-2

Subcatchment B-2: Basin B-2

Hydrograph



Rational-100YR Developed

El Paso County 100-Year Duration=27 min, Inten=4.57 in/hr

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Pond DP-B2: Design Point B2

Inflow Area = 6.400 ac, Inflow Depth = 0.82" for 100-Year event
Inflow = 11.71 cfs @ 0.45 hrs, Volume= 0.435 af
Outflow = 4.68 cfs @ 0.72 hrs, Volume= 0.370 af, Atten= 60%, Lag= 16.2 min
Primary = 4.68 cfs @ 0.72 hrs, Volume= 0.370 af

Routing by Stor-Ind method, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
Peak Elev= 6,245.31' @ 0.72 hrs Surf.Area= 0.286 ac Storage= 0.292 af
Plug-Flow detention time= 42.1 min calculated for 0.369 af (85% of inflow)
Center-of-Mass det. time= 39.4 min (66.4 - 27.0)

#	Invert	Avail.Storage	Storage Description
1	6,244.00'	0.446 af	Custom Stage Data (Prismatic) Listed below

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
6,244.00	0.019	0.000	0.000
6,246.00	0.427	0.446	0.446


#	Routing	Invert	Outlet Devices
1	Primary	6,244.00'	18.0" x 50.0' long Culvert CMP, end-section conforming to fill, Ke= 0.500 Outlet Invert= 6,243.50' S= 0.0100 1' n= 0.022 Cc= 0.900

Primary OutFlow Max=4.68 cfs @ 0.72 hrs HW=6,245.31' (Free Discharge)

1=Culvert (Barrel Controls 4.68 cfs @ 3.8 fps)

Pond DP-B2: Design Point B2

Hydrograph



Rational-100YR Developed*El Paso County 100-Year Duration=27 min, Inten=4.57 in/hr*

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment B-3: Basin B-3

Runoff = 81.14 cfs @ 0.45 hrs, Volume= 3.016 af, Depth= 0.82"


Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
El Paso County 100-Year Duration=27 min, Inten=4.57 in/hr

Area (ac)	C	Description
44.000	0.40	5 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
26.7					Direct Entry, Basin B-3

Subcatchment B-3: Basin B-3

Hydrograph



Runoff

Rational-100YR Developed

El Paso County 100-Year Duration=30 min, Inten=4.31 in/hr

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment B-4: Basin B-4

Runoff = 115.27 cfs @ 0.50 hrs, Volume= 4.763 af, Depth= 0.86"


Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
El Paso County 100-Year Duration=30 min, Inten=4.31 in/hr

Area (ac)	C	Description
66.300	0.40	5 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
29.8					Direct Entry, Basin B-4

Subcatchment B-4: Basin B-4

Hydrograph



Rational-100YR Developed

El Paso County 100-Year Duration=30 min, Inten=4.31 in/hr

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment B-5: Basin B-5

Runoff = 148.02 cfs @ 0.50 hrs, Volume= 6.117 af, Depth= 0.85"


Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
El Paso County 100-Year Duration=30 min, Inten=4.31 in/hr

Area (ac)	C	Description
86.000	0.40	5 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
30.3					Direct Entry, Basin B-5

Subcatchment B-5: Basin B-5

Hydrograph



Rational-100YR Developed

El Paso County 100-Year Duration=25 min, Inten=4.77 in/hr

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment OS1: Off-Site Basin OS1

Runoff = 37.56 cfs @ 0.41 hrs, Volume= 1.293 af, Depth= 0.70"


Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
El Paso County 100-Year Duration=25 min, Inten=4.77 in/hr

Area (ac)	C	Description
22.300	0.35	Pasture/grassland/range, Good, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
24.5					Direct Entry, Basin OS1

Subcatchment OS1: Off-Site Basin OS1

Hydrograph



Rational-100YR Developed

El Paso County 100-Year Duration=47 min, Inten=3.29 in/hr

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment C-1: Basin C-1

Runoff = 57.19 cfs @ 0.78 hrs, Volume= 3.702 af, Depth= 1.03"


Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
El Paso County 100-Year Duration=47 min, Inten=3.29 in/hr

Area (ac)	C	Description
43.100	0.40	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
46.6					Direct Entry, Basin C-1

Subcatchment C-1: Basin C-1

Hydrograph



Rational-100YR Developed*El Paso County 100-Year Duration=47 min, Inten=3.29 in/hr*

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Pond DP-C1: Design Point C1

Inflow Area = 56.800 ac, Inflow Depth = 1.03" for 100-Year event
 Inflow = 71.81 cfs @ 0.78 hrs, Volume= 4.879 af
 Outflow = 53.81 cfs @ 1.03 hrs, Volume= 4.879 af, Atten= 25%, Lag= 14.8 min
 Primary = 53.81 cfs @ 1.03 hrs, Volume= 4.879 af

Routing by Stor-Ind method, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
 Peak Elev= 6,215.14' @ 1.03 hrs Surf.Area= 0.873 ac Storage= 0.682 af
 Plug-Flow detention time= 5.3 min calculated for 4.863 af (100% of inflow)
 Center-of-Mass det. time= 5.3 min (51.5 - 46.2)

#	Invert	Avail.Storage	Storage Description
1	6,212.00'	0.894 af	Custom Stage Data (Prismatic) Listed below


Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
6,212.00	0.005	0.000	0.000
6,214.00	0.016	0.021	0.021
6,215.50	1.148	0.873	0.894

#	Routing	Invert	Outlet Devices
1	Primary	6,211.70'	30.0" x 50.0' long Culvert X 2.00 CMP, end-section conforming to fill, Ke= 0.500 Outlet Invert= 6,211.20' S= 0.0100 '/ n= 0.024 Cc= 0.900

Primary OutFlow Max=53.81 cfs @ 1.03 hrs HW=6,215.14' (Free Discharge)↑ **1=Culvert** (Barrel Controls 53.81 cfs @ 5.5 fps)

Pond DP-C1: Design Point C1

Hydrograph



Rational-100YR Developed

El Paso County 100-Year Duration=29 min, Inten=4.40 in/hr

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment C-2: Basin C-2

Runoff = 24.08 cfs @ 0.48 hrs, Volume= 0.968 af, Depth= 0.85"


Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
El Paso County 100-Year Duration=29 min, Inten=4.40 in/hr

Area (ac)	C	Description
13.700	0.40	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
29.1					Direct Entry, Basin C-2

Subcatchment C-2: Basin C-2

Hydrograph



Rational-100YR Developed*El Paso County 100-Year Duration=29 min, Inten=4.40 in/hr*

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Pond DP-C2: Design Point C2

Inflow Area = 13.700 ac, Inflow Depth = 0.85" for 100-Year event
 Inflow = 24.08 cfs @ 0.48 hrs, Volume= 0.968 af
 Outflow = 15.68 cfs @ 0.65 hrs, Volume= 0.968 af, Atten= 35%, Lag= 10.3 min
 Primary = 15.68 cfs @ 0.65 hrs, Volume= 0.968 af

Routing by Stor-Ind method, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
 Peak Elev= 6,222.90' @ 0.65 hrs Surf.Area= 0.238 ac Storage= 0.219 af
 Plug-Flow detention time= 6.8 min calculated for 0.965 af (100% of inflow)
 Center-of-Mass det. time= 6.8 min (35.8 - 29.0)

#	Invert	Avail.Storage	Storage Description
1	6,220.50'	0.301 af	Custom Stage Data (Prismatic) Listed below

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
6,220.50	0.000	0.000	0.000
6,222.00	0.062	0.046	0.046
6,223.33	0.321	0.255	0.301


#	Routing	Invert	Outlet Devices
1	Primary	6,220.00'	24.0" x 50.0' long Culvert CMP, end-section conforming to fill, Ke= 0.500 Outlet Invert= 6,219.50' S= 0.0100 '/' n= 0.024 Cc= 0.900

Primary OutFlow Max=15.68 cfs @ 0.65 hrs HW=6,222.90' (Free Discharge)

1=Culvert (Barrel Controls 15.68 cfs @ 5.0 fps)

Pond DP-C2: Design Point C2

Hydrograph



Rational-100YR Developed

El Paso County 100-Year Duration=21 min, Inten=5.23 in/hr

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment C-3: Basin C-3

Runoff = 18.77 cfs @ 0.35 hrs, Volume= 0.543 af, Depth= 0.73"


Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
El Paso County 100-Year Duration=21 min, Inten=5.23 in/hr

Area (ac)	C	Description
8.900	0.40	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
21.0					Direct Entry, Basin C-3

Subcatchment C-3: Basin C-3

Hydrograph



Rational-100YR Developed

El Paso County 100-Year Duration=21 min, Inten=5.23 in/hr

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Pond DP-C3: Design Point C3

Inflow Area = 8.900 ac, Inflow Depth = 0.73" for 100-Year event
 Inflow = 18.77 cfs @ 0.35 hrs, Volume= 0.543 af
 Outflow = 4.19 cfs @ 0.62 hrs, Volume= 0.522 af, Atten= 78%, Lag= 16.3 min
 Primary = 4.19 cfs @ 0.62 hrs, Volume= 0.522 af

Routing by Stor-Ind method, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
 Peak Elev= 6,220.76' @ 0.62 hrs Surf.Area= 0.439 ac Storage= 0.413 af
 Plug-Flow detention time= 55.2 min calculated for 0.520 af (96% of inflow)
 Center-of-Mass det. time= 54.8 min (75.8 - 21.0)

#	Invert	Avail.Storage	Storage Description
1	6,220.00'	1.083 af	Custom Stage Data (Prismatic) Listed below

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
6,220.00	0.110	0.000	0.000
6,222.00	0.973	1.083	1.083


#	Routing	Invert	Outlet Devices
1	Primary	6,219.50'	18.0" x 50.0' long Culvert CMP, end-section conforming to fill, Ke= 0.500 Outlet Invert= 6,219.00' S= 0.0100 /' n= 0.024 Cc= 0.900

Primary OutFlow Max=4.19 cfs @ 0.62 hrs HW=6,220.76' (Free Discharge)

←1=Culvert (Barrel Controls 4.19 cfs @ 3.6 fps)

Pond DP-C3: Design Point C3

Hydrograph



Rational-100YR Developed

El Paso County 100-Year Duration=23 min, Inten=4.99 in/hr

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment C-4: Basin C-4

Runoff = 14.18 cfs @ 0.38 hrs, Volume= 0.453 af, Depth= 0.77"


Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
El Paso County 100-Year Duration=23 min, Inten=4.99 in/hr

Area (ac)	C	Description
7.100	0.40	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
23.0					Direct Entry, Basin C-4

Subcatchment C-4: Basin C-4

Hydrograph



Rational-100YR Developed*El Paso County 100-Year Duration=29 min, Inten=4.40 in/hr*

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment C-5: Basin C-5

Runoff = 36.96 cfs @ 0.48 hrs, Volume= 1.485 af, Depth= 0.84"


Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
El Paso County 100-Year Duration=29 min, Inten=4.40 in/hr

Area (ac)	C	Description
21.100	0.40	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
29.2					Direct Entry, Basin C-5

Subcatchment C-5: Basin C-5

Hydrograph



Rational-100YR Developed*El Paso County 100-Year Duration=32 min, Inten=4.15 in/hr*

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment C-6: Basin C-6

Runoff = 134.01 cfs @ 0.53 hrs, Volume= 5.939 af, Depth= 0.89"


Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
El Paso County 100-Year Duration=32 min, Inten=4.15 in/hr

Area (ac)	C	Description
80.500	0.40	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
32.0					Direct Entry, Basin C-6

Subcatchment C-6: Basin C-6

Hydrograph



Rational-100YR Developed*El Paso County 100-Year Duration=22 min, Inten=5.11 in/hr*

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment D-1: Basin D-1

Runoff = 11.97 cfs @ 0.36 hrs, Volume= 0.362 af, Depth= 0.75"


Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
El Paso County 100-Year Duration=22 min, Inten=5.11 in/hr

Area (ac)	C	Description
5.800	0.40	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
21.6					Direct Entry, Basin D-1

Subcatchment D-1: Basin D-1

Hydrograph



Rational-100YR Developed

El Paso County 100-Year Duration=20 min, Inten=5.37 in/hr

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment D-2: Basin D-2

Runoff = 42.94 cfs @ 0.33 hrs, Volume= 1.193 af, Depth= 0.71"


Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
El Paso County 100-Year Duration=20 min, Inten=5.37 in/hr

Area (ac)	C	Description
20.200	0.40	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
20.2					Direct Entry, Basin D-2

Subcatchment D-2: Basin D-2

Hydrograph



Rational-100YR Developed

El Paso County 100-Year Duration=20 min, Inten=5.37 in/hr

Prepared by WestWorks Engineering

Page 1

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Pond Pond D: Pond D

Inflow Area = 20.200 ac, Inflow Depth = 0.71" for 100-Year event
 Inflow = 42.94 cfs @ 0.33 hrs, Volume= 1.193 af
 Outflow = 2.91 cfs @ 0.64 hrs, Volume= 0.422 af, Atten= 93%, Lag= 18.7 min
 Primary = 2.91 cfs @ 0.64 hrs, Volume= 0.422 af

Routing by Stor-Ind method, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
 Peak Elev= 6,191.18' @ 0.64 hrs Surf.Area= 1.074 ac Storage= 1.136 af
 Plug-Flow detention time= 78.8 min calculated for 0.422 af (35% of inflow)
 Center-of-Mass det. time= 70.0 min (90.0 - 20.0)

#	Invert	Avail.Storage	Storage Description
1	6,190.00'	1.921 af	Custom Stage Data (Prismatic) Listed below

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
6,190.00	0.337	0.000	0.000
6,192.00	1.584	1.921	1.921

#	Routing	Invert	Outlet Devices
1	Primary	6,190.08'	1.0" Vert. Orifice/Grate X 2.00 C= 0.600
2	Primary	6,190.25'	17.0" x 15.0' long Culvert CMP, projecting, no headwall, Ke= 0.900 Outlet Invert= 6,189.80' S= 0.0300 '/' n= 0.022 Cc= 0.900


Primary OutFlow Max=2.91 cfs @ 0.64 hrs HW=6,191.18' (Free Discharge)

1=Orifice/Grate (Orifice Controls 0.05 cfs @ 5.0 fps)

2=Culvert (Inlet Controls 2.85 cfs @ 2.6 fps)

Pond Pond D: Pond D

Hydrograph



Link DP-D: Design Point D

Inflow Area = 26.000 ac, Inflow Depth = 0.38" for 100-Year event


Inflow = 12.74 cfs @ 0.37 hrs, Volume= 0.826 af





Primary = 12.74 cfs @ 0.37 hrs, Volume= 0.826 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs

Link DP-D: Design Point D

Hydrograph





Drainage Diagram for TR20-100YR-24HR Developed
 Prepared by WestWorks Engineering 6/16/2005
 HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

TR20-100YR-24HR Developed

Prepared by WestWorks Engineering

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

Type IIA 24-hr Rainfall=4.40"

Page 2

6/16/2005

Time span=0.00-20.00 hrs, dt=0.01 hrs, 2001 points

Runoff by SCS TR-20 method, UH=SCS

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment B-1: Basin B-1Runoff Area=24.000 ac Runoff Depth=1.20"
Tc=33.9 min CN=65 Runoff=24.29 cfs 2.402 af**Subcatchment B-2: Basin B-2**Runoff Area=6.400 ac Runoff Depth=1.20"
Tc=27.2 min CN=65 Runoff=7.58 cfs 0.642 af**Subcatchment B-3: Basin B-3**Runoff Area=44.000 ac Runoff Depth=1.20"
Tc=26.7 min CN=65 Runoff=52.98 cfs 4.415 af**Subcatchment B-4: Basin B-4**Runoff Area=66.300 ac Runoff Depth=1.20"
Tc=29.8 min CN=65 Runoff=73.91 cfs 6.645 af**Subcatchment B-5: Basin B-5**Runoff Area=86.000 ac Runoff Depth=1.20"
Tc=30.3 min CN=65 Runoff=94.91 cfs 8.618 af**Subcatchment C-1: Basin C-1**Runoff Area=43.100 ac Runoff Depth=1.20"
Tc=46.6 min CN=65 Runoff=34.46 cfs 4.295 af**Subcatchment C-2: Basin C-2**Runoff Area=13.700 ac Runoff Depth=1.20"
Tc=29.1 min CN=65 Runoff=15.56 cfs 1.373 af**Subcatchment C-3: Basin C-3**Runoff Area=8.900 ac Runoff Depth=1.21"
Tc=21.0 min CN=65 Runoff=12.40 cfs 0.895 af**Subcatchment C-4: Basin C-4**Runoff Area=7.100 ac Runoff Depth=1.21"
Tc=23.0 min CN=65 Runoff=9.36 cfs 0.713 af**Subcatchment C-5: Basin C-5**Runoff Area=21.100 ac Runoff Depth=1.20"
Tc=29.2 min CN=65 Runoff=23.83 cfs 2.115 af**Subcatchment C-6: Basin C-6**Runoff Area=80.500 ac Runoff Depth=1.20"
Tc=32.0 min CN=65 Runoff=85.19 cfs 8.062 af**Subcatchment OS1: Off-Site Basin OS1**Runoff Area=22.300 ac Runoff Depth=0.97"
Tc=24.5 min CN=61 Runoff=21.50 cfs 1.799 af**Pond DP-B1: Design Point B-1**Peak Elev=6,245.50' Storage=0.638 af Inflow=24.29 cfs 2.402 af
24.0' x 50.0' Culvert Outflow=11.91 cfs 2.365 af**Pond DP-B2: Design Point B2**Peak Elev=6,244.96' Storage=0.213 af Inflow=7.58 cfs 0.642 af
18.0' x 50.0' Culvert Outflow=2.81 cfs 0.591 af**Pond DP-B4: Design Point B4**Peak Elev=6,195.21' Storage=1.203 af Inflow=153.20 cfs 15.814 af
Outflow=152.47 cfs 15.716 af

TR20-100YR-24HR Developed*Type IIA 24-hr Rainfall=4.40"*

Prepared by WestWorks Engineering

Page 3

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Pond DP-C1: Design Point C1Peak Elev=6,214.21' Storage=0.157 af Inflow=46.07 cfs 5.658 af
30.0" x 50.0' Culvert Outflow=40.87 cfs 5.657 af**Pond DP-C2: Design Point C2**Peak Elev=6,222.55' Storage=0.151 af Inflow=15.56 cfs 1.373 af
24.0" x 50.0' Culvert Outflow=11.77 cfs 1.363 af**Pond DP-C3: Design Point C3**Peak Elev=6,220.56' Storage=0.304 af Inflow=12.40 cfs 0.895 af
18.0" x 50.0' Culvert Outflow=3.16 cfs 0.892 af**Pond Pond B: Pond B**Peak Elev=6,185.13' Storage=12.828 af Inflow=247.33 cfs 24.334 af
Outflow=19.76 cfs 17.732 af**Pond Pond C: Pond C**Peak Elev=6,202.49' Storage=9.596 af Inflow=155.26 cfs 17.438 af
Outflow=12.63 cfs 11.577 af**Total Runoff Area = 423.400 ac Runoff Volume = 41.972 af Average Runoff Depth = 1.19"**

TR20-100YR-24HR Developed

Type IIA 24-hr Rainfall=4.40"

Prepared by WestWorks Engineering

Page 4

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment B-1: Basin B-1

Runoff = 24.29 cfs @ 6.30 hrs, Volume= 2.402 af, Depth= 1.20"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs
Type IIA 24-hr Rainfall=4.40"

Area (ac)	CN	Description
24.000	65	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
33.9					Direct Entry, Basin B-1

Subcatchment B-2: Basin B-2

Runoff = 7.58 cfs @ 6.23 hrs, Volume= 0.642 af, Depth= 1.20"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs
Type IIA 24-hr Rainfall=4.40"

Area (ac)	CN	Description
6.400	65	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
27.2					Direct Entry, Basin B-2

Subcatchment B-3: Basin B-3

Runoff = 52.98 cfs @ 6.23 hrs, Volume= 4.415 af, Depth= 1.20"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs
Type IIA 24-hr Rainfall=4.40"

Area (ac)	CN	Description
44.000	65	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
26.7					Direct Entry, Basin B-3

Subcatchment B-4: Basin B-4

Runoff = 73.91 cfs @ 6.26 hrs, Volume= 6.645 af, Depth= 1.20"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs
Type IIA 24-hr Rainfall=4.40"

TR20-100YR-24HR Developed

Type IIA 24-hr Rainfall=4.40"

Prepared by WestWorks Engineering

Page 5

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Area (ac)	CN	Description
66.300	65	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
29.8					Direct Entry, Basin B-4

Subcatchment B-5: Basin B-5

Runoff = 94.91 cfs @ 6.26 hrs, Volume= 8.618 af, Depth= 1.20"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs
Type IIA 24-hr Rainfall=4.40"

Area (ac)	CN	Description
86.000	65	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
30.3					Direct Entry, Basin B-5

Subcatchment C-1: Basin C-1

Runoff = 34.46 cfs @ 6.47 hrs, Volume= 4.295 af, Depth= 1.20"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs
Type IIA 24-hr Rainfall=4.40"

Area (ac)	CN	Description
43.100	65	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
46.6					Direct Entry, Basin C-1

Subcatchment C-2: Basin C-2

Runoff = 15.56 cfs @ 6.24 hrs, Volume= 1.373 af, Depth= 1.20"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs
Type IIA 24-hr Rainfall=4.40"

Area (ac)	CN	Description
13.700	65	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
29.1					Direct Entry, Basin C-2

TR20-100YR-24HR Developed

Type IIA 24-hr Rainfall=4.40"

Prepared by WestWorks Engineering

Page 6

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Subcatchment C-3: Basin C-3

Runoff = 12.40 cfs @ 6.16 hrs, Volume= 0.895 af, Depth= 1.21"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs
Type IIA 24-hr Rainfall=4.40"

Area (ac)	CN	Description
8.900	65	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
21.0					Direct Entry, Basin C-3

Subcatchment C-4: Basin C-4

Runoff = 9.36 cfs @ 6.18 hrs, Volume= 0.713 af, Depth= 1.21"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs
Type IIA 24-hr Rainfall=4.40"

Area (ac)	CN	Description
7.100	65	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
23.0					Direct Entry, Basin C-4

Subcatchment C-5: Basin C-5

Runoff = 23.83 cfs @ 6.26 hrs, Volume= 2.115 af, Depth= 1.20"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs
Type IIA 24-hr Rainfall=4.40"

Area (ac)	CN	Description
21.100	65	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
29.2					Direct Entry, Basin C-5

Subcatchment C-6: Basin C-6

Runoff = 85.19 cfs @ 6.29 hrs, Volume= 8.062 af, Depth= 1.20"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs
Type IIA 24-hr Rainfall=4.40"

TR20-100YR-24HR Developed

Type IIA 24-hr Rainfall=4.40"

Prepared by WestWorks Engineering

Page 7

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Area (ac)	CN	Description
80.500	65	2 acre lots, 12% imp, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
32.0					Direct Entry, Basin C-6

Subcatchment OS1: Off-Site Basin OS1

Runoff = 21.50 cfs @ 6.21 hrs, Volume= 1.799 af, Depth= 0.97"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs

Type IIA 24-hr Rainfall=4.40"

Area (ac)	CN	Description
22.300	61	Pasture/grassland/range, Good, HSG B

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
24.5					Direct Entry, Basin OS1

Pond DP-B1: Design Point B-1

Inflow Area = 24.000 ac, Inflow Depth = 1.20"
 Inflow = 24.29 cfs @ 6.30 hrs, Volume= 2.402 af
 Outflow = 11.91 cfs @ 6.66 hrs, Volume= 2.365 af, Atten= 51%, Lag= 21.4 min
 Primary = 11.91 cfs @ 6.66 hrs, Volume= 2.365 af

Routing by Stor-Ind method, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs
 Peak Elev= 6,245.50' @ 6.66 hrs Surf.Area= 0.559 ac Storage= 0.638 af
 Plug-Flow detention time= 40.3 min calculated for 2.365 af (98% of inflow)
 Center-of-Mass det. time= 30.3 min (566.4 - 536.1)

#	Invert	Avail.Storage	Storage Description
1	6,243.00'	2.049 af	Custom Stage Data (Prismatic) Listed below

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
6,243.00	0.005	0.000	0.000
6,244.00	0.077	0.041	0.041
6,246.00	0.721	0.798	0.839
6,247.00	1.700	1.210	2.049

#	Routing	Invert	Outlet Devices
1	Primary	6,243.50'	24.0" x 50.0' long Culvert CMP, end-section conforming to fill, Ke= 0.500 Outlet Invert= 6,243.00' S= 0.0100 ' n= 0.022 Cc= 0.900

Primary OutFlow Max=11.91 cfs @ 6.66 hrs HW=6,245.50' (Free Discharge)

↑1=Culvert (Barrel Controls 11.91 cfs @ 4.7 fps)

TR20-100YR-24HR Developed

Type IIA 24-hr Rainfall=4.40"

Prepared by WestWorks Engineering

Page 8

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Pond DP-B2: Design Point B2

Inflow Area = 6.400 ac, Inflow Depth = 1.20"
 Inflow = 7.58 cfs @ 6.23 hrs, Volume= 0.642 af
 Outflow = 2.81 cfs @ 6.59 hrs, Volume= 0.591 af, Atten= 63%, Lag= 21.8 min
 Primary = 2.81 cfs @ 6.59 hrs, Volume= 0.591 af

Routing by Stor-Ind method, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs
 Peak Elev= 6,244.96' @ 6.59 hrs Surf.Area= 0.214 ac Storage= 0.213 af
 Plug-Flow detention time= 102.8 min calculated for 0.591 af (92% of inflow)
 Center-of-Mass det. time= 54.1 min (585.6 - 531.5)

#	Invert	Avail.Storage	Storage Description
1	6,244.00'	0.446 af	Custom Stage Data (Prismatic) Listed below

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
6,244.00	0.019	0.000	0.000
6,246.00	0.427	0.446	0.446

#	Routing	Invert	Outlet Devices
1	Primary	6,244.00'	18.0" x 50.0' long Culvert CMP, end-section conforming to fill, Ke= 0.500 Outlet Invert= 6,243.50' S= 0.0100 ' n= 0.022 Cc= 0.900

Primary OutFlow Max=2.80 cfs @ 6.59 hrs HW=6,244.96' (Free Discharge)
 ↑1=Culvert (Barrel Controls 2.80 cfs @ 3.4 fps)

Pond DP-B4: Design Point B4

Inflow Area = 163.000 ac, Inflow Depth = 1.16"
 Inflow = 153.20 cfs @ 6.26 hrs, Volume= 15.814 af
 Outflow = 152.47 cfs @ 6.27 hrs, Volume= 15.716 af, Atten= 0%, Lag= 0.7 min
 Primary = 152.47 cfs @ 6.27 hrs, Volume= 15.716 af

Routing by Stor-Ind method, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs
 Peak Elev= 6,195.21' @ 6.27 hrs Surf.Area= 0.889 ac Storage= 1.203 af
 Plug-Flow detention time= 12.5 min calculated for 15.708 af (99% of inflow)
 Center-of-Mass det. time= 8.5 min (549.3 - 540.8)

#	Invert	Avail.Storage	Storage Description
1	6,192.00'	1.821 af	Custom Stage Data (Prismatic) Listed below

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
6,192.00	0.009	0.000	0.000
6,194.00	0.253	0.262	0.262
6,196.00	1.306	1.559	1.821

#	Routing	Invert	Outlet Devices
1	Primary	6,192.00'	24.0" x 50.0' long Culvert X 2.00 CMP, end-section conforming to fill, Ke= 0.500

TR20-100YR-24HR Developed

Type IIA 24-hr Rainfall=4.40"

Prepared by WestWorks Engineering

Page 9

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

2 Primary 6,195.00' Outlet Invert= 6,191.50' S= 0.0100 ' /' n= 0.022 Cc= 0.900
Roadway Overtop
 Head (feet) 0.00 0.50
 Disch. (cfs) 0.00 280.00

Primary OutFlow Max=152.42 cfs @ 6.27 hrs HW=6,195.21' (Free Discharge)

1=Culvert (Barrel Controls 36.35 cfs @ 5.8 fps)

2=Roadway Overtop (Custom Controls 116.06 cfs)

Pond DP-C1: Design Point C1

Inflow Area = 56.800 ac, Inflow Depth = 1.20"
 Inflow = 46.07 cfs @ 6.47 hrs, Volume= 5.658 af
 Outflow = 40.87 cfs @ 6.62 hrs, Volume= 5.657 af, Atten= 11%, Lag= 9.2 min
 Primary = 40.87 cfs @ 6.62 hrs, Volume= 5.657 af

Routing by Stor-Ind method, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs
 Peak Elev= 6,214.21' @ 6.62 hrs Surf.Area= 0.149 ac Storage= 0.157 af
 Plug-Flow detention time= 1.1 min calculated for 5.657 af (100% of inflow)
 Center-of-Mass det. time= 0.9 min (544.3 - 543.4)

#	Invert	Avail.Storage	Storage Description
1	6,212.00'	5.735 af	Custom Stage Data (Prismatic) Listed below

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
6,212.00	0.005	0.000	0.000
6,214.00	0.016	0.021	0.021
6,216.00	1.295	1.311	1.332
6,218.00	3.108	4.403	5.735

#	Routing	Invert	Outlet Devices
1	Primary	6,211.70'	30.0" x 50.0' long Culvert X 2.00 CMP, end-section conforming to fill, Ke= 0.500 Outlet Invert= 6,211.20' S= 0.0100 ' /' n= 0.024 Cc= 0.900

Primary OutFlow Max=40.87 cfs @ 6.62 hrs HW=6,214.21' (Free Discharge)

1=Culvert (Barrel Controls 40.87 cfs @ 5.2 fps)

Pond DP-C2: Design Point C2

Inflow Area = 13.700 ac, Inflow Depth = 1.20"
 Inflow = 15.56 cfs @ 6.24 hrs, Volume= 1.373 af
 Outflow = 11.77 cfs @ 6.41 hrs, Volume= 1.363 af, Atten= 24%, Lag= 10.2 min
 Primary = 11.77 cfs @ 6.41 hrs, Volume= 1.363 af

Routing by Stor-Ind method, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs
 Peak Elev= 6,222.55' @ 6.41 hrs Surf.Area= 0.168 ac Storage= 0.151 af
 Plug-Flow detention time= 10.8 min calculated for 1.363 af (99% of inflow)
 Center-of-Mass det. time= 6.0 min (538.8 - 532.8)

TR20-100YR-24HR Developed

Type IIA 24-hr Rainfall=4.40"

Prepared by WestWorks Engineering

Page 10

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

#	Invert	Avail.Storage	Storage Description
1	6,220.50'	0.301 af	Custom Stage Data (Prismatic) Listed below

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
6,220.50	0.000	0.000	0.000
6,222.00	0.062	0.046	0.046
6,223.33	0.321	0.255	0.301

#	Routing	Invert	Outlet Devices
1	Primary	6,220.50'	24.0" x 50.0' long Culvert CMP, end-section conforming to fill, Ke= 0.500 Outlet Invert= 6,220.00' S= 0.0100 '/ n= 0.024 Cc= 0.900

Primary OutFlow Max=11.77 cfs @ 6.41 hrs HW=6,222.55' (Free Discharge)

↑1=Culvert (Barrel Controls 11.77 cfs @ 4.6 fps)

Pond DP-C3: Design Point C3

Inflow Area = 8.900 ac, Inflow Depth = 1.21"
 Inflow = 12.40 cfs @ 6.16 hrs, Volume= 0.895 af
 Outflow = 3.16 cfs @ 6.55 hrs, Volume= 0.892 af, Atten= 74%, Lag= 23.0 min
 Primary = 3.16 cfs @ 6.55 hrs, Volume= 0.892 af

Routing by Stor-Ind method, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs
 Peak Elev= 6,220.56' @ 6.55 hrs Surf.Area= 0.352 ac Storage= 0.304 af
 Plug-Flow detention time= 44.3 min calculated for 0.891 af (100% of inflow)
 Center-of-Mass det. time= 41.9 min (569.2 - 527.2)

#	Invert	Avail.Storage	Storage Description
1	6,220.00'	1.083 af	Custom Stage Data (Prismatic) Listed below

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
6,220.00	0.110	0.000	0.000
6,222.00	0.973	1.083	1.083

#	Routing	Invert	Outlet Devices
1	Primary	6,219.50'	18.0" x 50.0' long Culvert CMP, end-section conforming to fill, Ke= 0.500 Outlet Invert= 6,219.00' S= 0.0100 '/ n= 0.024 Cc= 0.900

Primary OutFlow Max=3.16 cfs @ 6.55 hrs HW=6,220.56' (Free Discharge)

↑1=Culvert (Barrel Controls 3.16 cfs @ 3.3 fps)

Pond Pond B: Pond B

Inflow Area = 249.000 ac, Inflow Depth = 1.17"
 Inflow = 247.33 cfs @ 6.27 hrs, Volume= 24.334 af
 Outflow = 19.76 cfs @ 8.48 hrs, Volume= 17.732 af, Atten= 92%, Lag= 132.8 min
 Primary = 19.76 cfs @ 8.48 hrs, Volume= 17.732 af

Routing by Stor-Ind method, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs

TR20-100YR-24HR Developed

Type IIA 24-hr Rainfall=4.40"

Prepared by WestWorks Engineering

Page 11

HydroCAD® 7.00 s/n 002053 © 1986-2003 Applied Microcomputer Systems

6/16/2005

Peak Elev= 6,185.13' @ 8.48 hrs Surf.Area= 6.115 ac Storage= 12.828 af
 Plug-Flow detention time= 331.7 min calculated for 17.723 af (73% of inflow)
 Center-of-Mass det. time= 209.9 min (753.7 - 543.7)

#	Invert	Avail.Storage	Storage Description
1	6,182.00'	18.024 af	Custom Stage Data (Prismatic) Listed below

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
6,182.00	1.586	0.000	0.000
6,184.00	4.555	6.141	6.141
6,186.00	7.328	11.883	18.024

#	Routing	Invert	Outlet Devices
1	Primary	6,182.20'	2.0" Vert. Orifice/Grate X 2.00 C= 0.600
2	Primary	6,182.50'	27.8" x 25.0' long Culvert CMP, projecting, no headwall, Ke= 0.900 Outlet Invert= 6,181.75' S= 0.0300 '/ n= 0.024 Cc= 0.900

Primary OutFlow Max=19.76 cfs @ 8.48 hrs HW=6,185.13' (Free Discharge)

1=Orifice/Grate (Orifice Controls 0.35 cfs @ 8.1 fps)

2=Culvert (Inlet Controls 19.41 cfs @ 4.6 fps)

Pond Pond C: Pond C

Inflow Area = 174.400 ac, Inflow Depth = 1.20"
 Inflow = 155.26 cfs @ 6.29 hrs, Volume= 17.438 af
 Outflow = 12.63 cfs @ 8.55 hrs, Volume= 11.577 af, Atten= 92%, Lag= 136.0 min
 Primary = 12.63 cfs @ 8.55 hrs, Volume= 11.577 af

Routing by Stor-Ind method, Time Span= 0.00-20.00 hrs, dt= 0.01 hrs
 Peak Elev= 6,202.49' @ 8.55 hrs Surf.Area= 5.998 ac Storage= 9.596 af
 Plug-Flow detention time= 358.3 min calculated for 11.571 af (66% of inflow)
 Center-of-Mass det. time= 223.3 min (762.4 - 539.2)

#	Invert	Avail.Storage	Storage Description
1	6,200.00'	20.381 af	Custom Stage Data (Prismatic) Listed below

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
6,200.00	1.196	0.000	0.000
6,202.00	4.876	6.072	6.072
6,204.00	9.433	14.309	20.381


#	Routing	Invert	Outlet Devices
1	Primary	6,200.20'	2.0" Vert. Orifice/Grate X 2.00 C= 0.600
2	Primary	6,200.50'	27.8" x 25.0' long Culvert CMP, projecting, no headwall, Ke= 0.900 Outlet Invert= 6,200.25' S= 0.0100 '/ n= 0.024 Cc= 0.900

Primary OutFlow Max=12.63 cfs @ 8.55 hrs HW=6,202.49' (Free Discharge)

1=Orifice/Grate (Orifice Controls 0.31 cfs @ 7.2 fps)

2=Culvert (Barrel Controls 12.32 cfs @ 4.3 fps)

**DRAINAGE MAPS
(EXISTING & DEVELOPED CONDITIONS)**



RATIONAL METHOD ANALYSIS:

BASIN	Q5 [CFS]	Q100 [CFS]
EX-A	25	63
EX-D	15	36
OS1	15	38


DESIGN POINT	Q5 [CFS]	Q100 [CFS]	STRUCTURE
exA	25	63	OVERLAND TO ADJACENT PROPERTY
exD	15	36	EX ROADSIDE DITCH


TR-20 ANALYSIS:

BASIN	Q10 [CFS]	Q100 [CFS]
EX-B	26	96
EX-C	18	66

DESIGN POINT	Q10 [CFS]	Q100 [CFS]	STRUCTURE
exB	28	106	EX 18" CMP CULVERT
exC	18	66	EX 24" CMP CULVERT

LEGEND





DETENTION POND SUMMARY (RATIONAL METHOD):

POND A: Q5(N)=13 CFS Q5(OUT)=1 CFS Q100(N)=31 CFS Q100(OUT)=2 CFS WQCV REQ'D=0.045 AC-FT WQCV PROVIDED=0.42 AC-FT 100YR VOLUME=1.0 AC-FT	POND D: Q5(N)=18 CFS Q5(OUT)=1 CFS Q100(N)=43 CFS Q100(OUT)=3 CFS WQCV REQ'D=0.059 AC-FT WQCV PROVIDED=0.24 AC-FT 100YR VOLUME=1.1 AC-FT
--	--

DETENTION POND SUMMARY (TR-20):

POND B: Q10(N)=59 CFS Q10(OUT)=6 CFS Q100(N)=247 CFS Q100(OUT)=20 CFS WQCV REQ'D=0.731 AC-FT WQCV PROVIDED=1.52 AC-FT 100YR VOLUME=12.8 AC-FT	POND C: Q10(N)=52 CFS Q10(OUT)=3 CFS Q100(N)=155 CFS Q100(OUT)=13 CFS WQCV REQ'D=0.512 AC-FT WQCV PROVIDED=1.52 AC-FT 100YR VOLUME=9.3 AC-FT
---	--

RATIONAL METHOD ANALYSIS:

BASIN	Q5 [CFS]	Q100 [CFS]
A-1	22	51
A-2	13	31
A-3	2	4
B-1	16	39
B-2	5	12
B-3	34	81
B-4	49	115
B-5	62	148
C-1	24	57
C-2	10	24
C-3	8	19
C-4	6	14
C-5	16	37
C-6	56	134
D-1	5	12
D-2	18	43
OS1	15	38

RATIONAL METHOD ANALYSIS:

DESIGN POINT	Q5 [CFS]	Q100 [CFS]	STRUCTURE
A1	22	51	18" CMP CULVERT
A	2	7	OVERLAND TO ADJACENT PROPERTY
B1	16	39	24" CMP CULVERT
B2	5	12	18" CMP CULVERT
C1	32	57	DUAL 30" CMP CULVERTS
C2	10	24	24" CMP CULVERT
C3	8	19	18" CMP CULVERT
D	5	13	EX ROADSIDE DITCH

TR-20 ANALYSIS:

DESIGN POINT	Q10 [CFS]	Q100 [CFS]	STRUCTURE
B4	24	153	DUAL 24" CMP CULVERTS
B	6	20	EX 18" CMP CULVERT
C	3	13	EX 24" CMP CULVERT

LEGEND

- BASIN IDENTIFIER: A 1.0
- BASIN AREA [AC]: A 1.0
- DESIGN POINT IDENTIFIER: DP-0
- DRAINAGE BASIN BOUNDARY: - - - - -
- SURFACE FLOW DIRECTION: →
- EXISTING MAJOR CONTOUR (10'): ---
- EXISTING MINOR CONTOUR (2'): ---
- PROPOSED MAJOR CONTOUR (10'): ---
- PROPOSED MINOR CONTOUR (2'): ---
- TIME OF CONCENTRATION PATH: - - - - -

