

ANNEXATION PETITION

The undersigned landowner, in accordance with the provisions of Section 31-12- 101 et. seq. C.R.S., and known as the Municipal Annexation Act of 1965, as amended, hereby petitions the Board of Trustees of the Town of Palmer Lake for annexation to the Town of Palmer Lake of the within described unincorporated area situated and being in the County of El Paso, State of Colorado. In support of this Petition, the petitioners allege and submit the following and make the within requests:

- 1) That it is desirable and necessary to annex the property shown on Exhibit A, attached hereto, comprising a total of 5.6233 acres more or less.
- 2) That the area sought to be annexed to the Town of Palmer Lake meets the requirements of section 31-12-104 and 105 C.R.S. of the Municipal Annexation Act of 1965, as amended, in that:
 - a. Not less than one-sixth of the perimeter of the described property is contiguous to the Town of Palmer Lake. The property for which annexation is sought has a total of 17,261.41 feet contiguous to the Town of Palmer Lake.
 - b. The area for which annexation is sought shares a community of interest with the Town of Palmer Lake.
 - c. The area for which annexation is sought will be urban in character in the near future.
 - d. The area for which annexation is sought is integrated with or is capable of being integrated with the Town of Palmer Lake.
 - e. Within the area for which annexation is sought, no lands held in identical ownership shall be divided into separate lots or parcels without the written consent of the landowners thereof.
 - f. No land held in identical ownership comprising twenty (20) acres or more shall be included within the annexation without the written consent of the landowners thereof.
 - g. The annexation which is sought will not result in a detachment of area from any school district and will not result in the attachment of the annexed area to another school district other than that in which it already is.
 - h. The annexation of the area proposed to be annexed will not have the effect of extending the boundary of the Town of Palmer Lake more than three miles in any direction from any point of the Town's boundary in any one year.

3) That the signers of this Petition comprise the landowners of one hundred percent (100%) of the territory included in the area for which annexation is sought.

4) That the petitioners request that the Town of Palmer Lake approve this annexation.

5) That the legal description of the territory proposed to be annexed is attached hereto as Exhibit B.

6) The names and addresses of adjacent property owners to the property for which annexation is sought and within 300 feet of the boundary of the property for which annexation is sought are attached as Exhibit C; the applicant must inform each property owner within 300 feet of the boundary of the property of the annexation petition by way of certified mail; the return receipts will be required to complete the applicants file.

7) No annexation proceedings have been commenced for the annexation to another municipality of part or all of the territory proposed to be annexed.

8) If a portion of a platted street or alley is to be annexed, the entire width of said street or alley is included within the area to be annexed.

9) The Town of Palmer Lake will distribute a copy of the annexation plat to the affected agencies for comment, including public entities of school district and various utilities (i.e., gas, cable, sewer).

10) That upon the Annexation Ordinance becoming effective, all lands within the area sought to be annexed shall become subject to the Colorado Revised Statutes and all ordinances, resolutions, and regulations of the Town of Palmer Lake.

WHEREFORE, the undersigned petitioners request that the Town of Palmer Lake approve the annexation of the Property.

Maria Larsen
Petitioner Name

Petitioner Name

Maria Larsen 10/18/2024
Signature Date

Signature Date

STATE OF COLORADO)

) ss.

COUNTY OF El Paso)

Subscribed and sworn to before me this 18th day of October,
2024,

by Maria Lausew

Donna Zamora
Notary Public

My commission expires:

5/30/2027



BUC'EES PALMER LAKE NO. 5 ANNEXATION MAP

LOCATED IN THE NORTHEAST QUARTER OF SECTION 4,
THE NORTH HALF OF SECTION 3, AND THE NORTHWEST QUARTER OF SECTION 2
TOWNSHIP 11 SOUTH, RANGE 67 WEST OF THE 6TH P.M..
COUNTY OF EL PASO, STATE OF COLORADO

ANNEXATION DESCRIPTION

A PARCEL OF LAND BEING A PORTION OF THE SOUTH HALF OF THAT DECLARED PUBLIC HIGHWAY KNOWN AS, COUNTY LINE ROAD (A.K.A. WEST PALMER DIVIDE ROAD), DESCRIBED IN BOOK 571 AT PAGE 55; ALL OF THOSE SPECIAL WARRANTY DEEDS RECORDED AT RECEPTION NUMBERS 222083003, 222112629, 222082812, AND 222120338; ALL OF TRACT A, AS DEDICATED TO THE COUNTY OF EL PASO, BY EHRRICH SUBDIVISION, RECEPTION NO. 204031593; AND A PORTION OF THAT DECLARED PUBLIC HIGHWAY KNOWN AS BEACON LITE ROAD, DESCRIBED IN BOOK 571 AT PAGE 55, ALL DOCUMENTS FOUND IN THE EL PASO COUNTY OFFICE OF THE CLERK AND RECORDER; SITUATED IN THE NORTHEAST QUARTER OF SECTION 4, THE NORTH HALF OF SECTION 3, AND THE NORTHWEST QUARTER OF SECTION 2, TOWNSHIP 11 SOUTH, RANGE 67 WEST OF THE SIX PRINCIPAL MERIDIAN, BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

COMMENCING AT THE NORTHWEST CORNER OF SAID SECTION 4, AS MONUMENTED BY A NO. 6 REBAR WITH 3.25" ALUMINUM CAP STAMPED, "PE-LS 9853, 2001", 0.3' BELOW GRADE;
THENCE COINCIDENT WITH THE NORTH LINE OF SECTION 4, NORTH 89°42'31" EAST, A DISTANCE OF 2666.90 FEET TO THE CALCULATED POSITION OF THE NORTH QUARTER CORNER OF SAID SECTION 4 AND THE **POINT OF BEGINNING**;

THENCE CONTINUING COINCIDENT WITH LAST SAID LINE, NORTH 89°42'31" EAST, A DISTANCE OF 2667.55 FEET TO THE NORTHEAST CORNER OF SAID SECTION 4, AS MONUMENTED BY A NO. 6 REBAR WITH 3.25" ALUMINUM CAP STAMPED, "EL PASO, 2001, LS 17496" 0.4' BELOW GRADE, IN MONUMENT BOX;
THENCE COINCIDENT WITH THE NORTH LINE OF SAID SECTION 3, AND CONTINUING ON LAST SAID BEARING, NORTH 89°42'31" EAST, A DISTANCE OF 73.46 FEET TO THE SOUTHEAST CORNER OF SECTION 33, TOWNSHIP 10 SOUTH, RANGE 67 WEST, AS MONUMENTED BY A NO. 6 REBAR WITH 3.5" ALUMINUM CAP STAMPED, "EL PASO, 2001, LS 17496" 0.4' BELOW GRADE, IN MONUMENT BOX;
THENCE CONTINUING COINCIDENT WITH SAID NORTH LINE, NORTH 89°42'55" EAST, A DISTANCE OF 5285.47 FEET TO THE NORTHWEST CORNER OF SECTION 2, AS MONUMENTED BY A NO. 6 REBAR WITH 3.25" ALUMINUM CAP STAMPED, "LS 17496" IN MONUMENT BOX;
THENCE COINCIDENT WITH THE NORTH LINE OF THE NORTHWEST QUARTER OF SAID SECTION 2, NORTH 89°22'36" EAST, A DISTANCE OF 615.77 FEET;

THENCE SOUTH 00°37'24" EAST, A DISTANCE OF 30.00 FEET TO THE SOUTHERLY LINE OF SAID COUNTY LINE ROAD, AS DESCRIBED IN BOOK 571, PAGE 55, IN SAID RECORDS;
THENCE SOUTH 89°22'36" WEST, A DISTANCE OF 220.93 FEET TO THE NORTHEASTERLY CORNER OF THAT SPECIAL WARRANTY DEED RECORDED AT RECEPTION NO. 222083003, IN SAID RECORDS;
THENCE COINCIDENT WITH THE SOUTHERLY AND EASTERLY LINES OF LAST SAID WARRANTY DEED THE FOLLOWING SEVEN (7) COURSES:
1) SOUTH 00°10'14" WEST, A DISTANCE OF 18.15 FEET;
2) NORTH 88°38'48" WEST, A DISTANCE OF 307.11 FEET;
3) SOUTH 44°02'37" WEST, A DISTANCE OF 49.33 FEET;
4) SOUTH 00°08'41" EAST, A DISTANCE OF 203.28 FEET;
5) SOUTH 04°08'13" WEST, A DISTANCE OF 160.73 FEET;
6) SOUTH 00°08'41" EAST, A DISTANCE OF 188.22 FEET;
7) SOUTH 89°51'19" WEST, A DISTANCE OF 7.75 FEET TO THE EAST LINE OF BEACON LITE ROAD, AS DESCRIBED IN SAID BOOK 571, PAGE 55;

THENCE COINCIDENT WITH LAST SAID EAST LINE, SOUTH 00°29'49" EAST, A DISTANCE OF 835.22 FEET;
THENCE SOUTH 89°30'11" WEST, A DISTANCE OF 60.00 FEET TO THE WEST LINE OF SAID BEACON LITE ROAD;
THENCE COINCIDENT WITH LAST SAID WEST LINE, NORTH 00°29'49" WEST, A DISTANCE OF 1063.52 FEET TO THE SOUTHEAST CORNER OF THAT SPECIAL WARRANTY DEED RECORDED AT RECEPTION NO. 222112629, IN SAID RECORDS;
THENCE COINCIDENT WITH THE SOUTHERLY AND WESTERLY LINES OF LAST SAID SPECIAL WARRANTY DEED, THE FOLLOWING SIX (6) COURSES:
1) SOUTH 89°42'55" WEST, A DISTANCE OF 6.85 FEET;
2) NORTH 00°08'43" WEST, A DISTANCE OF 342.58 FEET;
3) NORTH 53°19'35" WEST, A DISTANCE OF 23.64 FEET;
4) SOUTH 89°00'38" WEST, A DISTANCE OF 352.21 FEET;
5) NORTH 77°43'28" WEST, A DISTANCE OF 16.95 FEET;
6) SOUTH 89°00'38" WEST, A DISTANCE OF 201.06 FEET TO THE WESTERLY MOST SOUTHWEST CORNER OF LAST SAID SPECIAL WARRANTY DEED, SAID CORNER ALSO CONTIGUOUS WITH TRACT A, EHRRICH SUBDIVISION, RECORDED AT RECEPTION NO. 204031593, IN SAID RECORDS;
THENCE COINCIDENT WITH THE EASTERLY, SOUTHERLY, AND WESTERLY LINES OF SAID TRACT A THE FOLLOWING THREE (3) COURSES:
1) SOUTH 00°00'50" EAST, A DISTANCE OF 17.69 FEET;
2) SOUTH 89°42'55" WEST, A DISTANCE OF 30.00 FEET;
3) NORTH 00°00'50" WEST, A DISTANCE OF 23.32 FEET TO THE SOUTHEAST CORNER OF THAT SPECIAL WARRANTY DEED RECORDED AT RECEPTION NO. 222082812, IN SAID RECORDS;

THENCE COINCIDENT WITH THE SOUTH LINE OF LAST SAID SPECIAL WARRANTY DEED, SOUTH 89°00'40" WEST, A DISTANCE OF 457.79 FEET TO THE SOUTHWEST CORNER OF LAST SAID SPECIAL WARRANTY DEED, SAID CORNER BEING COTERMINOUS WITH THE SOUTHEAST CORNER OF THAT SPECIAL WARRANTY DEED RECORDED AT RECEPTION NO. 222120338, IN SAID RECORDS;
THENCE COINCIDENT WITH THE SOUTH LINE OF LAST SAID SPECIAL WARRANTY DEED, NORTH 85°25'38" WEST, A DISTANCE OF 145.38 FEET TO THE WESTERLY CORNER OF LAST SAID SPECIAL WARRANTY DEED AND THE SOUTH LINE OF SAID COUNTY LINE ROAD;
THENCE COINCIDENT WITH SAID SOUTH LINE THE FOLLOWING TWO (2) COURSES:
1) SOUTH 89°42'55" WEST, A DISTANCE OF 4029.68 FEET;
2) SOUTH 89°42'31" WEST, A DISTANCE OF 2740.67 FEET;
THENCE NORTH 89°35'21" EAST, A DISTANCE OF 8630.54 FEET;
THENCE SOUTH 89°47'18" WEST, A DISTANCE OF 8630.88 FEET TO THE **POINT OF BEGINNING**.

CONTAINING 244,951 SQUARE FEET OR 5.6233 ACRES.

SIGNED THIS _____ DAY OF _____, 20____.

BY: _____ AS: _____ OF: _____

NOTARY:

I HEREBY CERTIFY THAT ON THE _____ DAY OF _____, 20____, APPEARED BEFORE

ME, _____ AS _____ OF _____,

A COLORADO _____, WHO FIRST BEING SWORN, DULY EXECUTED THE ABOVE DOCUMENT.

NOTARY PUBLIC MY COMMISSION EXPIRES: _____

CONTIGUITY STATEMENT:

TOTAL PERIMETER OF AREA CONSIDERED FOR ANNEXATION = 37,435.73 FEET.
• ONE-SIXTH (1/6) OF TOTAL PERIMETER AREA = 6,239.33 FEET (16.67%).
• PERIMETER OF AREA CONTIGUOUS WITH EXISTING CITY LIMITS = 17,261.41 FEET (46.11%).

PLANNING DEPARTMENT:

THIS ANNEXATION PLAT WAS REVIEWED BY THE TOWN OF PALMER LAKE PLANNING DEPARTMENT THIS _____ DAY OF _____, 20____.

PLANNING DIRECTOR _____

TOWN APPROVAL:

PURSUANT TO AN ORDINANCE MADE AND ADOPTED BY THE TOWN OF PALMER LAKE, COUNTY OF EL PASO, COLORADO, THIS _____ DAY OF _____, OF 20____.


MAJOR _____ DATE _____

ATTEST:

TOWN CLERK _____ DATE _____

NOTES:

1. ACCORDING TO COLORADO LAW YOU MUST COMMENCE ANY LEGAL ACTION BASED UPON ANY DEFECT IN THIS SURVEY WITHIN THREE YEARS AFTER YOU FIRST DISCOVER SUCH DEFECT. IN NO EVENT MAY ANY ACTION BASED UPON ANY DEFECT IN THIS SURVEY BE COMMENCED MORE THAN TEN YEARS FROM THE DATE OF THE CERTIFICATION SHOWN HEREON.
2. ANY PERSON WHO KNOWINGLY REMOVES, ALTERS OR DEFACES ANY PUBLIC LAND SURVEY MONUMENT OR LAND BOUNDARY MONUMENT OR ACCESSORY COMMITS A CLASS TWO (2) MISDEMEANOR PURSUANT TO STATE STATUTE 18-4-508, C.R.S.
3. **BASIS OF BEARINGS:** BEARINGS ARE BASED ON THE NORTH LINE OF SECTION 4, TOWNSHIP 11 SOUTH, RANGE 67 WEST OF THE 6TH PRINCIPAL MERIDIAN, ASSUMED TO BEAR NORTH 89°42'31" EAST, A DISTANCE OF 5334.45 FEET, AS MONUMENTED AT THE NORTHWEST CORNER BY A NO. 6 REBAR WITH 3.25" ALUMINUM CAP STAMPED, "PE-LS 9853, 2001" 0.3' BELOW GRADE AND AT THE NORTHEAST CORNER BY A NO. 6 REBAR WITH 3.5" ALUMINUM CAP STAMPED, "EL PASO, 2001, LS17496" 0.4' BELOW GRADE IN MONUMENT BOX
4. ALL DISTANCES SHOWN HEREON ARE GROUND DISTANCES IN U.S. SURVEY FEET.
5. EXCEPT AS SPECIFICALLY STATED OR SHOWN ON THIS MAP, THIS SURVEY DOES NOT PURPORT TO REFLECT ANY OF THE FOLLOWING WHICH MAY BE APPLICABLE TO THE SUBJECT TRACT: EASEMENTS, BUILDING SETBACK LINES, RESTRICTIVE COVENANTS, SUBDIVISION RESTRICTIONS, ZONING OR OTHER LAND-USE REGULATIONS, AGREEMENTS, LEASE AGREEMENTS AND OWNERSHIP TITLE EVIDENCE.
6. THE WORD "CERTIFY" OR "CERTIFICATE" AS SHOWN AND USED HEREON MEANS AN EXPRESSION OF PROFESSIONAL OPINION REGARDING THE FACTS OF THE SURVEY AND DOES NOT CONSTITUTE A WARRANTY OR GUARANTEE, EXPRESSED OR IMPLIED.
7. FIELD WORK WAS COMPLETED SEPTEMBER 27, 2024.



CLERK AND RECORDER:

STATE OF COLORADO)
COUNTY OF EL PASO)SS

I HEREBY CERTIFY THAT THIS INSTRUMENT WAS FILED FOR RECORD IN MY OFFICE AT _____ O'CLOCK ____.

THIS _____ DAY OF _____, 20____ A.D.,

AND IS DULY RECORDED AT RECEPTION NO. _____ OF THE RECORDS COUNTY OF EL PASO, COLORADO

_____, RECORDER

BY: _____
DEPUTY

FEE: _____

SURCHARGE: _____

SURVEYOR'S CERTIFICATION

I, DARREN R. WOLTERSTORFF, A DULY LICENSED PROFESSIONAL LAND SURVEYOR IN THE STATE OF COLORADO, DO HEREBY CERTIFY THAT THE ANNEXATION SHOWN HEREON TRULY AND CORRECTLY REPRESENTS THE ABOVE DESCRIBED PARCEL OF LAND.



PURSUANT TO COLORADO STATE BOARD OF LICENSURE FOR PROFESSIONAL LAND SURVEYORS RULE 6.2.2 THE UNDERSIGNED FURTHER CERTIFIES THAT THIS MAP OR PLAT WAS PREPARED BY ME OR UNDER MY RESPONSIBLE CHARGE, IS ACCURATE TO THE BEST OF MY INFORMATION, KNOWLEDGE AND BELIEF, IS IN ACCORDANCE WITH APPLICABLE STANDARDS OF PRACTICE AND IS NOT A GUARANTY OR WARRANTY, EITHER EXPRESSED OR IMPLIED.

I ATTEST THE ABOVE ON THIS _____ DAY OF _____, 20____.

PRELIMINARY
THIS DOCUMENT SHALL NOT BE RECORDED FOR ANY PURPOSE AND SHALL NOT BE USED OR VIEWED OR RELIED UPON AS A FINAL SURVEY DOCUMENT



DARREN R. WOLTERSTORFF, PLS 38281
FOR AND ON BEHALF OF KIMLEY-HORN AND ASSOCIATES, INC.
DARREN.WOLTERSTORFF@KIMLEY-HORN.COM

| | | | | | |
|---|-------------|-----------------------------|----------|-------------|-----------|
| Kimley»Horn | | | | | |
| 6200 S. SYRACUSE WAY, # 300 GREENWOOD VILLAGE, CO 80111 Tel. No. (303) 228-2300 www.kimley-horn.com | | | | | |
| Scale | Drawn by | Checked by | Date | Project No. | Sheet No. |
| N/A | JAF | DRW | 10/17/24 | 196094002 | 1 OF 3 |
| No. | DATE | REVISION DESCRIPTION | | | |



BUC'EES PALMER LAKE NO. 5 ANNEXATION MAP

LOCATED IN THE NORTHEAST QUARTER OF SECTION 4,
THE NORTH HALF OF SECTION 3, AND THE NORTHWEST QUARTER OF SECTION 2
TOWNSHIP 11 SOUTH, RANGE 67 WEST OF THE 6TH P.M..
COUNTY OF EL PASO, STATE OF COLORADO



**ANNEXATION AREA
244,951 S.F.
5.6233 AC.**

LEGEND

- ◆ RECOVERED SECTION CORNER AS NOTED
- RECOVERED PROPERTY MONUMENT AS NOTED
- BOUNDARY TO BE ANNEXED
- - - - EXISTING CITY LIMITS
- - - - SECTION LINE
- RIGHT-OF-WAY LINE



| No. | DATE | REVISION DESCRIPTION |
|-----|------|----------------------|
| | | |
| | | |

Kimley»Horn



6200 S. SYRACUSE WAY, # 300
GREENWOOD VILLAGE, CO 80111
Tel. No. (303) 228-2300
www.kimley-horn.com

| Scale | Drawn by | Checked by | Date | Project No. | Sheet No. |
|----------|----------|------------|----------|-------------|-----------|
| 1" = 50' | JAF | DRW | 10/17/24 | 196094002 | 2 OF 3 |

D:\WORK\2024\10\17\24\ANNEXATION\196094002 - BUC'EES PALMER LAKE CAD\DWG\ANNEXATION.DWG PLOTTED BY FELDER, JEREMY 10/16/2024 2:28 PM LAST SAVED 10/16/2024 2:40 PM



BUC'EES PALMER LAKE NO. 5 ANNEXATION MAP
LOCATED IN THE NORTHEAST QUARTER OF SECTION 4,
THE NORTH HALF OF SECTION 3, AND THE NORTHWEST QUARTER OF SECTION 2
TOWNSHIP 11 SOUTH, RANGE 67 WEST OF THE 6TH P.M..
COUNTY OF EL PASO, STATE OF COLORADO



| No. | DATE | REVISION DESCRIPTION |
|-----|------|----------------------|
| | | |
| | | |
| | | |

Kimley»Horn

6200 S. SYRACUSE WAY, # 300
GREENWOOD VILLAGE, CO 80111

Tel. No. (303) 228-2300
www.kimley-horn.com

| Scale | Drawn by | Checked by | Date | Project No. | Sheet No. |
|----------|----------|------------|----------|-------------|-----------|
| 1" = 50' | JAF | DRW | 10/17/24 | 196094002 | 3 OF 3 |

DWG NAME: JORDEN_CADULLI196094002 - BUC'EES PALMER LAKE CADASTRIAL/PROXY/ANNEXATIONS/196094002 - BUC'EES PALMER LAKE CADASTRIAL/PROXY/ANNEXATIONS/196094002 - PLOTTED BY: FELDER, JEREMY - 10/16/2024 2:28 PM LAST SAVED: 10/16/2024 2:49 PM



A PARCEL OF LAND BEING A PORTION OF THE SOUTH HALF OF THAT DECLARED PUBLIC HIGHWAY KNOWN AS, COUNTY LINE ROAD (A.K.A. WEST PALMER DIVIDE ROAD), DESCRIBED IN BOOK 571 AT PAGE 55; ALL OF THOSE SPECIAL WARRANTY DEEDS RECORDED AT RECEPTION NUMBERS 222083003, 222112629, 222082812, AND 222120338; ALL OF TRACT A, AS DEDICATED TO THE COUNTY OF EL PASO, BY EHRICH SUBDIVISION, RECEPTION NO. 204031593; AND A PORTION OF THAT DECLARED PUBLIC HIGHWAY KNOWN AS BEACON LITE ROAD, DESCRIBED IN BOOK 571 AT PAGE 55, ALL DOCUMENTS FOUND IN THE EL PASO COUNTY OFFICE OF THE CLERK AND RECORDER; SITUATED IN THE NORTHEAST QUARTER OF SECTION 4, THE NORTH HALF OF SECTION 3, AND THE NORTHWEST QUARTER OF SECTION 2, TOWNSHIP 11 SOUTH, RANGE 67 WEST OF THE SIX PRINCIPAL MERIDIAN, BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

COMMENCING AT THE NORTHWEST CORNER OF SAID SECTION 4, AS MONUMENTED BY A NO. 6 REBAR WITH

3.25" ALUMINUM CAP STAMPED, "PE-LS 9853, 2001", 0.3' BELOW GRADE;

THENCE COINCIDENT WITH THE NORTH LINE OF SECTION 4, NORTH 89°42'31" EAST, A DISTANCE OF 2666.90 FEET TO THE CALCULATED POSITION OF THE NORTH QUARTER CORNER OF SAID SECTION 4 AND THE **POINT OF BEGINNING**;

THENCE CONTINUING COINCIDENT WITH LAST SAID LINE, NORTH 89°42'31" EAST, A DISTANCE OF 2667.55 FEET TO THE NORTHEAST CORNER OF SAID SECTION 4, AS MONUMENTED BY A NO. 6 REBAR WITH 3.25" ALUMINUM CAP STAMPED, "EL PASO, 2001, LS 17496" 0.4' BELOW GRADE, IN MONUMENT BOX;

THENCE COINCIDENT WITH THE NORTH LINE OF SAID SECTION 3, AND CONTINUING ON LAST SAID BEARING,

NORTH 89°42'31" EAST, A DISTANCE OF 73.46 FEET TO THE SOUTHEAST CORNER OF SECTION 33, TOWNSHIP 10 SOUTH, RANGE 67 WEST, AS MONUMENTED BY A NO. 6 REBAR WITH 3.5" ALUMINUM CAP STAMPED, "EL PASO, 2001, LS 17496" 0.4' BELOW GRADE, IN MONUMENT BOX;

THENCE CONTINUING COINCIDENT WITH SAID NORTH LINE, NORTH 89°42'55" EAST, A DISTANCE OF 5285.47 FEET TO THE NORTHWEST CORNER OF SECTION 2, AS MONUMENTED BY A NO. 6 REBAR WITH 3.25" ALUMINUM CAP STAMPED, "LS 17496" IN MONUMENT BOX;

THENCE COINCIDENT WITH THE NORTH LINE OF THE NORTHWEST QUARTER OF SAID SECTION 2, NORTH 89°22'36" EAST, A DISTANCE OF 615.77 FEET;

THENCE SOUTH 00°37'24" EAST, A DISTANCE OF 30.00 FEET TO THE SOUTHERLY LINE OF SAID COUNTY LINE ROAD, AS DESCRIBED IN BOOK 571, PAGE 55, IN SAID RECORDS;

THENCE SOUTH 89°22'36" WEST, A DISTANCE OF 220.93 FEET TO THE NORTHEASTERLY CORNER OF THAT SPECIAL WARRANTY DEED RECORDED AT RECEPTION NO. 222083003, IN SAID RECORDS;

THENCE COINCIDENT WITH THE SOUTHERLY AND EASTERLY LINES OF LAST SAID WARRANTY DEED THE FOLLOWING SEVEN (7) COURSES:

- 1) SOUTH 00°10'14" WEST, A DISTANCE OF 18.15 FEET;
- 2) NORTH 88°38'48" WEST, A DISTANCE OF 307.11 FEET;
- 3) SOUTH 44°02'37" WEST, A DISTANCE OF 49.33 FEET;
- 4) SOUTH 00°08'41" EAST, A DISTANCE OF 203.28 FEET;
- 5) SOUTH 04°08'13" WEST, A DISTANCE OF 160.73 FEET;
- 6) SOUTH 00°08'41" EAST, A DISTANCE OF 188.22 FEET;
- 7) SOUTH 89°51'19" WEST, A DISTANCE OF 7.75 FEET TO THE EAST LINE OF BEACON LITE ROAD, AS DESCRIBED IN SAID BOOK 571, PAGE 55;

THENCE COINCIDENT WITH LAST SAID EAST LINE, SOUTH 00°29'49" EAST, A DISTANCE OF 835.22 FEET;

THENCE SOUTH 89°30'11" WEST, A DISTANCE OF 60.00 FEET TO THE WEST LINE OF SAID BEACON LITE ROAD;

THENCE COINCIDENT WITH LAST SAID WEST LINE, NORTH 00°29'49" WEST, A DISTANCE OF 1063.52 FEET TO THE SOUTHEAST CORNER OF THAT SPECIAL WARRANTY DEED RECORDED AT RECEPTION NO. 222112629, IN SAID RECORDS;

THENCE COINCIDENT WITH THE SOUTHERLY AND WESTERLY LINES OF LAST SAID SPECIAL WARRANTY DEED, THE FOLLOWING SIX (6) COURSES:

- 1) SOUTH 89°42'55" WEST, A DISTANCE OF 6.85 FEET;
- 2) NORTH 00°08'43" WEST, A DISTANCE OF 342.58 FEET;
- 3) NORTH 53°19'35" WEST, A DISTANCE OF 23.64 FEET;
- 4) SOUTH 89°00'36" WEST, A DISTANCE OF 352.21 FEET;
- 5) NORTH 77°43'28" WEST, A DISTANCE OF 16.95 FEET;
- 6) SOUTH 89°00'38" WEST, A DISTANCE OF 201.06 FEET TO THE WESTERLY MOST SOUTHWEST CORNER OF LAST SAID SPECIAL WARRANTY DEED, SAID CORNER ALSO

CONTIGUOUS WITH TRACT A, EHRICH SUBDIVISION, RECORDED AT RECEPTION NO. 204031593, IN SAID RECORDS;

THENCE COINCIDENT WITH THE EASTERLY, SOUTHERLY, AND WESTERLY LINES OF SAID TRACT A THE FOLLOWING THREE (3) COURSES:

- 1) SOUTH 00°00'50" EAST, A DISTANCE OF 17.69 FEET;
- 2) SOUTH 89°42'55" WEST, A DISTANCE OF 30.00 FEET;
- 3) NORTH 00°00'50" WEST, A DISTANCE OF 23.32 FEET TO THE SOUTHEAST CORNER OF THAT SPECIAL WARRANTY DEED RECORDED AT RECEPTION NO. 222082812, IN SAID RECORDS;

THENCE COINCIDENT WITH THE SOUTH LINE OF LAST SAID SPECIAL WARRANTY DEED, SOUTH 89°00'40" WEST, A DISTANCE OF 457.79 FEET TO THE SOUTHWEST CORNER OF LAST SAID SPECIAL WARRANTY DEED, SAID CORNER BEING COTERMINOUS WITH THE SOUTHEAST CORNER OF THAT SPECIAL WARRANTY DEED RECORDED AT RECEPTION NO. 222120338, IN SAID RECORDS;

THENCE COINCIDENT WITH THE SOUTH LINE OF LAST SAID SPECIAL WARRANTY DEED, NORTH 85°25'38" WEST, A DISTANCE OF 145.38 FEET TO THE WESTERLY CORNER OF LAST SAID SPECIAL WARRANTY DEED AND THE SOUTH LINE OF SAID COUNTY LINE ROAD;

THENCE COINCIDENT WITH SAID SOUTH LINE THE FOLLOWING TWO (2) COURSES:

- 1) SOUTH 89°42'55" WEST, A DISTANCE OF 4029.68 FEET;
- 2) SOUTH 89°42'31" WEST, A DISTANCE OF 2740.67 FEET;

THENCE NORTH 89°35'21" EAST, A DISTANCE OF 8630.54 FEET;

THENCE SOUTH 89°47'18" WEST, A DISTANCE OF 8630.88 FEET TO THE **POINT OF BEGINNING**.

CONTAINING 244,951 SQUARE FEET OR 5.6233 ACRES.