

TRI-STATE GENERATION & TRANSMISSION, INC.

FOX RUN SUBSTATION FINAL DRAINAGE REPORT

PCD FILE # PPR-22-044

October 11, 2022

Prepared by:



DEL-MONT CONSULTANTS, INC.
ENGINEERING ▼ SURVEYING

125 Colorado Ave. ▼ Montrose, CO 81401 ▼ (970) 249-2251 ▼ (970) 249-2342 FAX
www.del-mont.com ▼ service@del-mont.com



TRI-STATE GENERATION & TRANSMISSION, INC.

FOX RUN SUBSTATION FINAL DRAINAGE REPORT

Design Engineer's Statement:

The attached drainage plan and report were prepared under my direction and supervision and are correct to the best of my knowledge and belief. Said drainage report has been prepared according to the criteria established by the County for drainage reports and said report is in conformity with the applicable master plan of the drainage basin. I accept responsibility for any liability caused by any negligent acts, errors or omissions on my part in preparing this report.

David Schieldt
Registered Professional Engineer
State of Colorado No. 47195

Date

Owner/Developer's Statement:

I, the owner/developer have read and will comply with all of the requirements specified in this drainage report and plan.

Karl Myers
Tri-State Generation and Transmission Association, Inc.
1100 W. 116th Ave
Westminster, CO 80234

Date

El Paso County:

Filed in accordance with the requirements of the Drainage Criteria Manual, Volumes 1 and 2, El Paso County Engineering Criteria Manual and Land Development Code as amended.

County Engineer / ECM Administrator

Date



TABLE OF CONTENTS

1.0	General Location and Description	1-1
1.1	Site Location	1-1
1.2	Site Description	1-1
2.0	Drainage Basins and Sub-Basins	2-1
2.1	Existing Drainage Sub-Basins	2-1
2.2	Proposed Drainage Sub-Basins	2-1
3.0	Drainage Design Criteria	3-1
3.1	Methodology	3-1
3.2	Land Cover Hydrologic Properties	3-1
3.3	Weighted Design Values	3-1
4.0	Drainage Facility Design	4-1
4.1	Historical Drainage	4-1
4.2	Proposed Drainage	4-1
5.0	Conclusions	5-1
5.1	Drainage Concept	5-1
5.2	Compliance with Common Practices	5-1
6.0	References	6-1

Appendix A – Site Maps & Design Drawings
Appendix B – Yeh and Associates Geotechnical Engineering Study
Appendix C – Site Specific Physical Design Properties
Appendix D – SWMM Modeling Results

See unresolved
comments from V1
and in GEOTECH
report.

Unresolved - dsdschoenheit
12/08/2022 7:03:28 AM

1.0 General Location and Description

Tri-State Generation and Transmission (TSGT) in coordination with Del-Mont Consultants, Inc. (DMC) is in the process of designing a new substation yard. The scope of work includes the construction of the substation yard & retaining walls, driveway, detention pond and swales, installation of new perimeter fence, and the addition of high voltage electrical equipment and facilities. The purpose of this report is to present the findings from the hydrologic and hydraulic analyses that were performed on the existing property as well as present the results from a detailed analysis performed on the proposed improvements to the property.

1.1 Site Location

The proposed substation yard is located on a 14.92-acre parcel owned by TSGT, situated in the NW $\frac{1}{4}$ of Section 21, Township 11 South, Range 66 West, 6th Principal Meridian in El Paso County, Colorado. The substation site is accessed from Shahara Road.

1.2 Site Description

The site naturally drains to the northeast and is currently covered in various grasses. There are currently no features on the site to provide water quality or quantity treatment for discharge from the site. Site layout details will be discussed in more detail in **Section 2**.

There are developments on the properties to the south and the west of the site. MVEA Substation located on the neighboring property to the south, and Jackson Ranch Subdivision to the west. No wetlands are present on the site and the site is not located within a floodplain. ✓

Reference should be made to any applicable major drainageway planning studies; Such as Drainage Basin Planning Studies; Flood Hazard delineation reports, and flood insurance studies or maps if available.

Unresolved - dsdschoenheit
12/08/2022 7:04:12 AM

2.0 Drainage Basins and Sub-Basins

The property functions overall as one large basin, flowing to the northeast into a drainage on the east edge of the property, ultimately flowing into West Cherry Creek. Proposed conditions produce several smaller sub-basins and will be discussed in detail in the following sections.

2.1 Existing Drainage Sub-Basins

The existing site was analyzed as one basin. A small portion of the existing site was unanalyzed as it did not affect the majority of the site. A map illustrating the delineation of the existing property can be found in **Appendix A**. There are developments on the properties to the south and the west of the site. MVEA Substation located on the neighboring property to the south, and Jackson Ranch Subdivision to the west. **Table 2-1** presents the existing basin and its corresponding acreage. The existing member substation was not analyzed as a part of this project.

Table 2-1: Existing Basin Acreages

Sub-Basin	Total Area (Acres)
Existing	14.38
Unanalyzed	0.54

2.2 Proposed Drainage Sub-Basins

The proposed conditions will produce several different sub-basins. The proposed site is divided into three different sub-basins; Yard Area, Proposed North, and Proposed South. A map illustrating the delineation of the sub-basins can be found in **Appendix A**. The Yard Area contains the entirety of the yard and the detention pond. The Proposed North and Proposed South areas contain swales that will route any run-on around the substation site, returning to historical discharge patterns. The run-on flows are minimal and will have negligible effects on the site. An offsite basin has been analyzed to verify culvert sizing for the diversion swale. **Table 2-2** presents the proposed sub-basins and their corresponding acreages.

Table 2-2: Proposed Sub-Basin Acreages

Sub-Basin	Total Area (Acres)
Yard Area	5.23
Proposed North	6.70
Proposed South	2.44
Offsite	4.5

3.0 Drainage Design Criteria

3.1 Methodology

The hydrologic/hydraulic analysis of the site was performed using the Autodesk Storm and Sanitary analysis utilizing the Rational Method model for a 5-year and a 100-year rainfall event. Runoff Coefficients were obtained from El Paso County Drainage Criteria Manual Volume 1 Update, Chapter 6, Section 3.1, Table 6-6. Rainfall Intensity was obtained from EPC DCM Volume 1 Update, Figure 6-5. Modeling results are presented in **Appendix D**.

The Mile High Flood District *Detention Basin Design Workbook* was utilized to determine the required water quality capture volume (WQCV) and to aid in the design the outlet structure. The spreadsheets/worksheets can be found in **Appendix C** and are discussed in more detail in **Section 4.0**.

add and detention

Soil data was obtained from a USDA Soils Report and gives a hydrologic soil group B for the site. The soils report is included in **Appendix B**.

The described methods/tools used in the analysis, are in accordance with common engineering practices and guidelines.

3.2 Land Cover Hydrologic Properties

Runoff Coefficients and Percent Impervious numbers, for hydrologic soil group B, were assigned to the various land cover types found on the project, both existing and proposed, and are presented in **Table 3-1**.

Table 3-1: Land Cover Hydrologic Properties

Land Cover Type	Percent Impervious	Runoff Coefficient 5 Year	Runoff Coefficient 100 Year
Gravel	80	0.59	0.70
Historical Flow Analysis	2	0.09	0.36
Pond	100	0.85	0.89

3.3 Weighted Design Values

Utilizing the land cover hydrologic properties presented above, a weighted Runoff Coefficient and Percent Impervious value was calculated for each of the sub-basins, presented in **Section 2.0** to be used for analysis. **Table 3-2** presents the weighted design values for existing conditions and **Table 3-3** presents the weighted design values for proposed conditions. Detailed calculations can be found in **Appendix C**.

Table 3-2: Existing Sub-Basin Weighted Design Values

Sub-Basin	Total Area (Acres)	Weighted Percent Impervious	Weighted Runoff Coefficient 5 year	Weighted Runoff Coefficient 100 year
Existing	14.38	2%	0.09	0.36
Offsite	4.5	2%	0.09	0.36

Table 3-3: Proposed Sub-Basin Weighted Design Values

Sub-Basin	Total Area (Acres)	Weighted Percent Impervious	Weighted Runoff Coefficient 5 year	Weighted Runoff Coefficient 100 year
Yard Area	5.23	71%	0.55	0.68
Proposed North	6.70	5%	0.12	0.38
Proposed South	2.44	9%	0.14	0.40

4.0 Drainage Facility Design

4.1 Historical Drainage

Per common practice, the 100-year historical discharge value for the site shall be used to determine the allowable discharge from the site for the proposed conditions. Values presented in **Table 3-2** were used in the model to calculate a historical discharge rate for the existing property. **Table 4-1** presents the discharge rate for the existing property for both the 5-year and 100-year 1-hour storm events although the design is based on the 100-year discharge values.

Table 4-1: Existing Property Discharge Values

Sub-Basin	5-Year Discharge (CFS)	100-Year Discharge (CFS)
Existing	7.20	48.26
Offsite	2.36	15.81

4.2 Proposed Drainage

Values presented in **Table 3-3** were utilized in the model to calculate the runoff for the proposed conditions. The Mile High Flood District *Detention Basin Design Workbook* was utilized to determine the WQCV in conjunction with the model to size the detention pond. Once the pond was sized, the Mile High Flood District *Detention Basin Design Workbook* was utilized to estimate required orifice sizes in the outlet structure to provide water quality treatment. The model was then used to verify all design elements of the pond and the outlet structure to ensure the pond not only retained the correct WQCV but to also discharge at or less than the required 100-year historic discharge rate presented in **Table 4-1** as well as drain the pond in less than the allowable time per State Requirements. The spreadsheet showing the detailed calculations can be found in **Appendix C**. The design of the outlet structure is detailed in the grading drawings.

The proposed detention pond was designed to provide water quality treatment as well as detain the 100-year storm event while maintaining the required 1-foot of freeboard. The proposed detention pond stage-storage curve is presented in **Table 4-2**.

Table 4-2: Detention Pond Stage-Storage Table

Elevation	Surface Area (Sq. Ft.)
7444	0
7445	20,284
7446	23,645
7447	26,149
7448	28,766

The model of the proposed site conditions was utilized to calculate discharge flow rates from the outlet structure in order to size the pond discharge culvert. **Table 4-3** presents the

hydraulic capacity of the culvert and the required capacity to discharge flow from the outlet structure for the 100-year event. Detailed design of the pipe is provided in **Appendix A**.

Table 4-3: Outlet Pipe Hydraulic Capacity (100-year event)

Drainage Feature	Pipe Diameter (in)	Total Capacity (cfs)	Required Flow Capacity (cfs)	Remaining Capacity (cfs)
Pond Outlet	18	8.05	0.17	7.88

Table 4-4 presents the discharge rates for the proposed sub-basins for both the 5-year and 100-year 1-hour storm events prior to detention. This discharge value represents the flow rate that the pond is receiving. The discharge from the pond and other basins (total discharge from site) is summarized in **Table 5-1**.

Table 4-4: Proposed Sub-Basin Discharge Values (Pre-Detention)

Sub-Basin	5-Year Discharge (CFS)	100-Year Discharge (CFS)
Yard Area	12.13	25.16
Proposed North	4.15	22.03
Proposed South	2.03	9.73

Utilizing the flow rates presented above, the model was utilized to analyze the flow path of water through the piping and pond system. With the installation of the outlet structure, the pond was designed to pass both the 5-year and 100-year events, treat the required WQCV, and slowly release the water in the required length of time after the end of an event set forth by the State. The entire substation drains to the pond and the discharge rate leaving the pond is presented in **Table 5-1**.

Provide and explain Four Step Process

1. Runoff reduction proposed
2. Stabilization of drainage ways proposed/discussed
3. Proposed Stormwater Quality Capture Volume (WQCV) proposed
4. Identify Best Management Practices (BMP's) to be used to control industrial and commercial pollutants

Unresolved - dsdschoenheit
12/08/2022 7:13:46 AM

5.0 Conclusions

5.1 Drainage Concept

The drainage design has been prepared using sound engineering judgement and practices and will provide an effective means of controlling runoff on the project site as well as protect the site from damage. The design has been completed according to common engineering practices and will result in no downstream impacts to any people or structures. Historic flow paths, discharge rates, and water quality have been maintained or improved.

5.2 Compliance with Common Practices

Per common practices, the historical discharge rate from the 100-year storm shall be utilized to determine the allowable discharge rate for the proposed improvements. To demonstrate compliance with this requirement, both the existing and proposed conditions were combined into one overall sub-basin. **Table 5-1** presents the overall discharge rates for the overall basin as well as the individual basins.

Table 5-1: Overall Sub-Basin Discharge Values (Post Detention)

Basin	5-Year Discharge (CFS)		100-Year Discharge (CFS)	
	Existing	Proposed	Existing	Proposed
Yard Area (Pond Outlet)	7.2	0.14	48.26	0.17
North		4.15		22.03
South		2.03		9.73
Total	7.2	6.32	48.26	31.93

The pond outlet structure was sized according to common practices so that the proposed condition 100-year discharge rate is less than the required discharge rate from the 100-year storm event, resulting in compliance with common practices.

The detention pond was also sized according to UDFCD requirements to treat the WQCV, detain the 100-year event, maintain 1 foot of freeboard, and maintain historical discharge patterns resulting in no downstream impacts.

Inspections of the pond and outlet structure will be conducted by the owner on an annual basis as well as after large storm events. If deficiencies are identified or if maintenance is required, maintenance of the outlet structure will be performed by the owner of the property in an effort to return the structure to its original level of functionality. Maintenance may involve cleaning of sediment and debris from the facility, maintaining vegetation growth around the structure, and performing any additional maintenance required.

6.0 References

United States Department of Agriculture Natural Resources Conservation Service. Web Soil Survey

Mile High Flood District and Flood Control District. *Detention Basin Design Workbook*, Version 4.04, February 2021.

Urban Drainage and Flood Control District. *Urban Storm Drainage Criteria Manual*, Volume 1-3, June 2001.

El Paso County, Colorado, *Drainage Criteria Manual*, Volume 1-2, October 31, 2018

El Paso County, Colorado, *Engineering Criteria Manual*, December 13, 2016

Yeh and Associates, Inc. *Geotechnical Engineering Study, Fox Run Substation. Yeh Project Number 221-290*. November 11, 2021

Provide sw pipe calculations, drainage ditch calculations, culvert calculations, spillway riprap calculations, and riprap outlet protection calculations

Appendix A

Site Maps & Design Drawings

move to end of report

show existing flow arrows unresolved.


There are basins that are not being captured by the proposed ponds. Explain in the narrative how WQ is being addressed for these basins. Possible exclusions include I.7.1.B.7 (land disturbance to undeveloped land that will remain undeveloped) and/or I.7.1.C.1 (which allows for 20% not to exceed 1 acre of the applicable development site area to not be captured).

design point

include basin for this disturbance and WQ

CEL NO. 0060357

CEL NO. 0060357 PLOTTED BY TCLEMENT, FILE PATH & NAME = \\DMS1\PROJECTS\ACTIVE PROJECTS\2021\12\1036-TSGT MONUMENT SUB SURVEY & CIVIL\FACILITY\CIVIL\MODEL\1036C_BASE.DWG, PLOT DATE = 10/11/2022 7:37 AM



Provide existing conditions map with offsite basin flows
Unresolved - ddschoenheit
12/08/2022 7:28:55 AM

Existing conditions and basin map should show parcel without new structures and development. Show flow arrows pre-development

Please move drainage maps to end of report
Unresolved - ddschoenheit
12/08/2022 10:53:09 AM

NO	DATE	REVISIONS	BY

DMC DEL-MONT CONSULTANTS, INC.
ENGINEERING & SURVEYING
122 Colorado Ave., Monument, CO 80132
(719) 249-2562 FAX (719) 249-2562

DESIGNED BY: TMC DATE ISSUED: 12/16/21
CHECKED BY: DWS
SCALE: AS NOTED
FILE NAME: 21036_BASE.DWG
DRAWN BY: TMC

TRI-STATE GENERATION & TRANSMISSION
FOX RUN SUBSTATION
MONUMENT, CO

DRAINAGE BASIN DELINEATION

DMC JOB NO. 21036

SHEET NO. A-1




PLOTTED BY TCLEMENT, FILE PATH & NAME = I:\DMAS\PROJECTS\ACTIVE PROJECTS\2021\12\1036-TSGT MONUMENT SUB SURVEY & CIVIL FACILITY\MODEL\1036C_BASE.DWG, PLOT DATE = 10/11/2022 7:37 AM

The manner of flow can be changed from sheet flow to concentrated flow. Analyze the conveyance path up to the suitable outfall as defined in ECM 3.2.4. The conveyance path must be hydraulically adequate/stable.

Unresolved. Add a paragraph or section in the Drainage Facility design summarizing the results.
 - Identify the velocity along the highlighted section and state whether it's within the permissible non-erosive velocity for the given soil, ground cover, and slope. Mitigation will be required if the concentrated pond discharge is likely to erode the existing ground downstream of the proposed swale. Contact the review engineer to discuss if additional clarification is required.

Determine if this a suitable outfall. Where will the overflow be directed?

provide riprap sizing calculation in the appendix.



LEGEND

- 5800 PROPOSED INDEX CONTOUR
- 5796 PROPOSED INTERMEDIATE CONTOUR
- PROPOSED DRAINAGE FLOWLINE
- STM PROPOSED STORM PIPE
- DRAINAGE LINK
- DIRECT LINK
- DRAINAGE BASIN
- Pond DRAINAGE NODE
- Yard SUB-BASIN

NO	DATE	REVISIONS	BY

DMC DEL-MONT CONSULTANTS, INC.
 ENGINEERING & SURVEYING
 122 Colorado Ave., Monument, CO 80132
 (719) 486-2562 FAX
 (719) 486-2562

DESIGNED BY: TMC
 CHECKED BY: TMC
 SCALE: AS NOTED
 DATE ISSUED: 12/16/21

TRI-STATE GENERATION & TRANSMISSION
 FOX RUN SUBSTATION
 MONUMENT, CO

DRAINAGE MODEL SCHEMATIC

Appendix B

Geotechnical Engineering Study

Appendix C

Site Specific Physical Design Properties

Fox Run Drainage Design
Existing Conditions-5 Year

Area Name	Total Area		Flow Length	Slope (%)	TOC (min)
	(sf)	(acres)			
Existing	626336.766	14.38	1000	6%	4.70
Offsite	196020	4.50	700	4%	4.18

Land Cover Type	Percent Impervious	Runoff Coefficient
Historical Flow Analysis	2%	0.09
Gravel	80%	0.59
Pond	100%	0.85

Roughness Coefficient and Curve Number Analysis

Existing						
	<u>Description</u>	<u>Total Area (ac)</u>	<u>Runoff Coefficient</u>	<u>A*C</u>	<u>Percent Impervious</u>	<u>A*%</u>
Existing Site		14.38	0.09	1.29	2%	29%
			sum	1.29		29%
Total Area (ac)		14.379	Weighted	0.09		2%
Weighted Runoff Coefficient		0.09				
Weighted Percent Impervious		2%				

Offsite						
	<u>Description</u>	<u>Total Area (ac)</u>	<u>Runoff Coefficient</u>	<u>A*C</u>	<u>Percent Impervious</u>	<u>A*%</u>
Existing Site		4.50	0.09	0.41	2%	9%
			sum	0.41		9%
Total Area (ac)		4.500	Weighted	0.09		2%
Weighted Runoff Coefficient		0.09				
Weighted Percent Impervious		2%				

Fox Run Drainage Design

Proposed Conditions-5 Year

Area Name	Total Area		Flow Length	Slope (%)	TOC (min)
	(sf)	(acres)			
Yard	228010.3171	5.23	1000	1.00%	9.38
North Proposed	292051.9481	6.70	1000	5.00%	5.05
South Proposed	106271.1511	2.44	800	6.00%	3.96

Land Cover Type	Percent Impervious	Runoff Coefficient
Historical Flow Analysis	2%	0.09
Gravel	80%	0.59
Pond	100%	0.85

Roughness Coefficient and Curve Number Analysis

Yard					
Description	Total Area (ac)	Runoff Coefficient	A*C	Percent Impervious	A*%
Substation Yard	3.83	0.59	2.26	80%	306.2%
Native	0.75	0.09	0.07	2%	1.5%
Pond	0.66	0.85	0.56	100%	65.6%
		sum	2.88		373.4%
Total Area (ac)	5.23	Weighted	0.55		71%
Weighted Runoff Coefficient	0.55				
Weighted Percent Impervious	71%				

North Proposed					
Description	Total Area (ac)	Runoff Coefficient	A*C	Percent Impervious	A*%
Native	6.47	0.09	0.58	2%	12.9%
Swale	0.23	0.85	0.20	100%	23.2%
		sum	0.78		36.1%
Total Area (ac)	6.70	Weighted	0.12		5%
Weighted Runoff Coefficient	0.12				
Weighted Percent Impervious	5%				

South Proposed					
Description	Total Area (ac)	Runoff Coefficient	A*C	Percent Impervious	A*%
Native	2.24	0.09	0.20	2%	4.5%
Gravel	0.08	0.59	0.05	80%	6.2%
Swale	0.12	0.85	0.10	100%	12.0%
		sum	0.35		22.7%
Total Area (ac)	2.44	Weighted	0.14		9%
Weighted Runoff Coefficient	0.14				
Weighted Percent Impervious	9%				

Fox Run Drainage Design
Existing Conditions-100 Year

Area Name	Total Area		Flow Length	Slope (%)	TOC (min)
	(sf)	(acres)			
Existing	626336.766	14.38	1000	6%	4.70
Offsite	196020	4.50	700	4%	4.18

Land Cover Type	Percent Impervious	Runoff Coefficient
Historical Flow Analysis	2%	0.36
Gravel	80%	0.7
Pond	100%	0.89

Roughness Coefficient and Curve Number Analysis

Existing						
	<u>Description</u>	<u>Total Area (ac)</u>	<u>Runoff Coefficient</u>	<u>A*C</u>	<u>Percent Impervious</u>	<u>A*%</u>
Existing Site		14.38	0.36	5.18	2%	29%
			sum	5.18		29%
Total Area (ac)		14.379	Weighted	0.36		2%
Weighted Runoff Coefficient		0.36				
Weighted Percent Impervious		2%				

Offsite						
	<u>Description</u>	<u>Total Area (ac)</u>	<u>Runoff Coefficient</u>	<u>A*C</u>	<u>Percent Impervious</u>	<u>A*%</u>
Existing Site		4.50	0.36	1.62	2%	9%
			sum	1.62		9%
Total Area (ac)		4.500	Weighted	0.36		2%
Weighted Runoff Coefficient		0.36				
Weighted Percent Impervious		2%				

Fox Run Drainage Design
Proposed Conditions-100 Year

Area Name	Total Area		Flow Length	Slope (%)	TOC (min)
	(sf)	(acres)			
Yard	228010.3171	5.23	1000	1.00%	9.38
North Proposed	292051.9481	6.70	1000	5.00%	5.05
South Proposed	106271.1511	2.44	800	6.00%	3.96

Land Cover Type	Percent Impervious	Runoff Coefficient
Historical Flow Analysis	2%	0.36
Gravel	80%	0.7
Pond	100%	0.89

Roughness Coefficient and Curve Number Analysis


Yard					
Description	Total Area (ac)	Runoff Coefficient	A*C	Percent Impervious	A*%
Substation Yard	3.83	0.7	2.68	80%	306.2%
Native	0.75	0.36	0.27	2%	1.5%
Pond	0.66	0.89	0.58	100%	65.6%
		sum	3.53		373.4%
Total Area (ac)	5.23	Weighted	0.68		71%
Weighted Runoff Coefficient	0.68				
Weighted Percent Impervious	71%				

North Proposed					
Description	Total Area (ac)	Runoff Coefficient	A*C	Percent Impervious	A*%
Native	6.47	0.36	2.33	2%	12.9%
Swale	0.23	0.89	0.21	100%	23.2%
		sum	2.54		36.1%
Total Area (ac)	6.70	Weighted	0.38		5%
Weighted Runoff Coefficient	0.38				
Weighted Percent Impervious	5%				

South Proposed					
Description	Total Area (ac)	Runoff Coefficient	A*C	Percent Impervious	A*%
Native	2.24	0.36	0.81	2%	4.5%
Gravel	0.08	0.7	0.05	80%	6.2%
Swale	0.12	0.89	0.11	100%	12.0%
		sum	0.97		22.7%
Total Area (ac)	2.44	Weighted	0.40		9%
Weighted Runoff Coefficient	0.40				
Weighted Percent Impervious	9%				

DETENTION BASIN STAGE-STORAGE TABLE BUILDER


MHFD-Detention, Version 4.04 (February 2021)



DETENTION BASIN OUTLET STRUCTURE DESIGN

MHFD-Detention, Version 4.04 (February 2021)

Project: Fox Run Substation
Basin ID: Detention Pond



	Estimated Stage (ft)	Estimated Volume (ac-ft)	Outlet Type
Zone 1 (WQCV)	0.82	0.115	Orifice Plate
Zone 2 (EURV)	1.55	0.271	Weir&Pipe (Circular)
Zone 3 (100-year)	2.09	0.219	
Total (all zones)		0.606	

Change Zone 2 to Orifice Plate

Update Zone 3 to Weir & pipe (w/ Restrictor Plate)

User Input: Orifice at Underdrain Outlet (typically used to drain WQCV in a Filtration BMP)

Underdrain Orifice Invert Depth =	N/A	ft (distance below the filtration media surface)
Underdrain Orifice Diameter =	N/A	inches

Underdrain Orifice Area =	N/A	ft ²
Underdrain Orifice Centroid =	N/A	ft

User Input: Orifice Plate with one or more orifices or Elliptical Slot Weir (typically used to drain WQCV and/or EURV in a sedimentation BMP)

Invert of Lowest Orifice =	0.00	ft (relative to basin bottom at Stage = 0 ft)
Depth at top of Zone using Orifice Plate =	2.00	ft (relative to basin bottom at Stage = 0 ft)
Orifice Plate: Orifice Vertical Spacing =	6.00	inches
Orifice Plate: Orifice Area per Row =	1.22	sq. inches (diameter = 1-1/4 inches)

WQ Orifice Area per Row =	8.472E-03	ft ²
Elliptical Half-Width =	N/A	feet
Elliptical Slot Centroid =	N/A	feet
Elliptical Slot Area =	N/A	ft ²

User Input: Stage and Total Area of Each Orifice Row (numbered from lowest to highest)

	Row 1 (required)	Row 2 (optional)	Row 3 (optional)	Row 4 (optional)	Row 5 (optional)	Row 6 (optional)	Row 7 (optional)	Row 8 (optional)
Stage of Orifice Centroid (ft)	0.00	0.50	1.00	1.50				
Orifice Area (sq. inches)	1.22	1.22	1.22	1.22				

Height needs to match the outlet height from the micropool to the top of grate.

Provide input to model the top of the outlet structure.


Orifice Shape =	Not Selected	Not Selected	ft (relative to basin bottom at Stage = 0 ft)
Depth at top of Zone using Vertical Orifice =			ft (relative to basin bottom at Stage = 0 ft)
Vertical Orifice Diameter =			inches

Vertical Orifice Area =	Not Selected	Not Selected	ft ²
Vertical Orifice Centroid =			ft

User Input: Overflow Weir (Dropbox with Flat or Sloped Grate and Outlet Pipe OR Rectangular/Trapezoidal Weir (and No Outlet Pipe))

Overflow Weir Front Edge Height, H _o =	0.53	ft (relative to basin bottom at Stage = 0 ft)
Overflow Weir Front Edge Length =		feet
Overflow Weir Grate Slope =		H:V
Horiz. Length of Weir Sides =		feet
Overflow Grate Type =		
Debris Clogging % =		%

Height of Grate Upper Edge, H _g =		ft
Overflow Weir Slope Length =		feet
Grate Open Area / 100-yr Orifice Area =		
Overflow Grate Open Area w/o Debris =		ft ²
Overflow Grate Open Area w/ Debris =		ft ²



User Input: Outlet Pipe w/ Flow Restriction Plate (Circular Orifice, Restrictor Plate, or Rectangular Orifice)

Depth to Invert of Outlet Pipe =		ft (distance below basin bottom at Stage = 0 ft)
Circular Orifice Diameter =		inches

Outlet Orifice Area =		ft ²
Outlet Orifice Centroid =		ft
Restrictor Plate on Pipe =		

provide input to model the outlet pipe

User Input: Emergency Spillway (Rectangular or Trapezoidal)

Spillway Invert Stage =	3.00	ft (relative to basin bottom at Stage = 0 ft)
Spillway Crest Length =	10.00	feet
Spillway End Slopes =	0.17	H:V
Freeboard above Max Water Surface =	1.00	feet

Spillway Design Flow Depth =	0.78	feet
Stage at Top of Freeboard =	4.78	feet
Basin Area at Top of Freeboard =	0.53	acres
Basin Volume at Top of Freeboard =	1.52	acre-ft

change side slopes to "4" per plans




Routed Hydrograph Results

The user can override the default CUHP hydrographs and runoff volumes by entering new values in the Inflow Hydrographs table (Columns W through AF).

	WQCV	EURV	2 Year	5 Year	10 Year	25 Year	50 Year	100 Year	500 Year
Design Storm Return Period =	N/A	N/A	1.19	1.50	1.75	2.00	2.25	2.52	3.14
One-Hour Rainfall Depth (in) =	N/A	N/A	1.19	1.50	1.75	2.00	2.25	2.52	3.14
CUHP Runoff Volume (acre-ft) =	0.115	0.386	0.287	0.385	0.468	0.566	0.652	0.755	0.975
Inflow Hydrograph Volume (acre-ft) =	N/A	N/A	0.287	0.385	0.468	0.566	0.652	0.755	0.975
CUHP Predevelopment Peak Q (cfs) =	N/A	N/A	1.0	3.0	4.4	7.2	9.1	11.5	15.9
OPTIONAL Override Predevelopment Peak Q (cfs) =	N/A	N/A							
Predevelopment Unit Peak Flow, q (cfs/acre) =	N/A	N/A	0.21	0.61	0.90	1.45	1.83	2.32	3.21
Peak Inflow Q (cfs) =	N/A	N/A	7.8	10.7	13.2	16.3	18.9	21.2	27.1
Peak Outflow Q (cfs) =	0.1	0.1	0.1	0.1	0.2	0.2	0.2	0.2	0.2
Ratio Peak Outflow to Predevelopment Q =	N/A	N/A	N/A	0.0	0.0	0.0	0.0	0.0	0.0
Structure Controlling Flow =	Plate	Plate	Plate	Plate	Plate	Plate	Plate	Plate	Plate
Max Velocity through Grate 1 (fps) =	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Max Velocity through Grate 2 (fps) =	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Time to Drain 97% of Inflow Volume (hours) =	38	69	61	70	76	81	85	90	99
Time to Drain 99% of Inflow Volume (hours) =	40	74	65	75	81	88	93	98	109
Maximum Ponding Depth (ft) =	0.82	1.55	1.26	1.51	1.70	1.93	2.13	2.36	2.84
Area at Maximum Ponding Depth (acres) =	0.30	0.40	0.38	0.40	0.41	0.42	0.43	0.44	0.47
Maximum Volume Stored (acre-ft) =	0.116	0.387	0.269	0.367	0.447	0.542	0.627	0.727	0.940

DETENTION BASIN OUTLET STRUCTURE DESIGN

MHFD-Detention, Version 4.04 (February 2021)



S-A-V-D Chart Axis Override	X-axis	Left Y-Axis	Right Y-Axis
minimum bound			
maximum bound			

DETENTION BASIN OUTLET STRUCTURE DESIGN

Outflow Hydrograph Workbook Filename: _____

Inflow Hydrographs

The user can override the calculated inflow hydrographs from this workbook with inflow hydrographs developed in a separate program.

Time Interval	SOURCE	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	
	TIME	WQCV [cfs]	EURV [cfs]	2 Year [cfs]	5 Year [cfs]	10 Year [cfs]	25 Year [cfs]	50 Year [cfs]	100 Year [cfs]	500 Year [cfs]	
5.00 min	0:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	0:05:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	0:10:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.15	0.01	0.47
	0:15:00	0.00	0.00	1.30	2.11	2.61	1.75	2.11	2.12	2.83	2.83
	0:20:00	0.00	0.00	4.02	5.08	6.05	3.66	4.18	4.58	5.90	5.90
	0:25:00	0.00	0.00	7.79	10.72	13.18	7.61	8.80	9.56	13.11	13.11
	0:30:00	0.00	0.00	7.17	9.44	10.89	16.31	18.91	21.22	27.09	27.09
	0:35:00	0.00	0.00	4.53	5.79	6.69	13.09	15.02	18.32	23.21	23.21
	0:40:00	0.00	0.00	2.86	3.47	4.01	9.36	10.70	12.69	16.03	16.03
	0:45:00	0.00	0.00	1.63	2.22	2.75	5.74	6.56	8.55	10.83	10.83
	0:50:00	0.00	0.00	1.23	1.87	2.14	4.37	5.01	6.11	7.79	7.79
	0:55:00	0.00	0.00	1.12	1.59	1.96	2.98	3.44	4.66	5.98	5.98
	1:00:00	0.00	0.00	1.10	1.49	1.90	2.49	2.89	4.16	5.36	5.36
	1:05:00	0.00	0.00	1.10	1.45	1.90	2.31	2.68	4.01	5.16	5.16
	1:10:00	0.00	0.00	0.87	1.44	1.90	1.84	2.14	2.56	3.36	3.36
	1:15:00	0.00	0.00	0.77	1.28	1.90	1.65	1.92	1.96	2.61	2.61
	1:20:00	0.00	0.00	0.73	1.11	1.60	1.30	1.51	1.25	1.65	1.65
	1:25:00	0.00	0.00	0.72	1.03	1.23	1.17	1.35	1.01	1.31	1.31
	1:30:00	0.00	0.00	0.72	1.01	1.08	0.96	1.09	0.92	1.20	1.20
	1:35:00	0.00	0.00	0.72	1.00	1.02	0.88	0.99	0.91	1.17	1.17
	1:40:00	0.00	0.00	0.72	0.81	1.01	0.85	0.95	0.91	1.17	1.17
	1:45:00	0.00	0.00	0.72	0.72	1.01	0.84	0.95	0.91	1.17	1.17
	1:50:00	0.00	0.00	0.72	0.68	1.01	0.84	0.95	0.91	1.17	1.17
	1:55:00	0.00	0.00	0.50	0.68	0.94	0.84	0.95	0.91	1.17	1.17
	2:00:00	0.00	0.00	0.41	0.62	0.78	0.84	0.95	0.91	1.17	1.17
	2:05:00	0.00	0.00	0.15	0.24	0.30	0.33	0.37	0.36	0.46	0.46
	2:10:00	0.00	0.00	0.05	0.08	0.10	0.11	0.13	0.12	0.16	0.16
	2:15:00	0.00	0.00	0.01	0.01	0.02	0.02	0.02	0.02	0.03	0.03
	2:20:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	2:25:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	2:30:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	2:35:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	2:40:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	2:45:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	2:50:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	2:55:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:05:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:10:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:15:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:20:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:25:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:30:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:35:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:40:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:45:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:50:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:55:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:05:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:10:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:15:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:20:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:25:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:30:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:35:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:40:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:45:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:50:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:55:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
5:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
5:05:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
5:10:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
5:15:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
5:20:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
5:25:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
5:30:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
5:35:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
5:40:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
5:45:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
5:50:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
5:55:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
6:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	

Design Procedure Form: Extended Detention Basin (EDB)

UD-BMP (Version 3.07, March 2018)

Sheet 1 of 3

Designer: Thayne Clement
Company: Del-Mont Consultants
Date: October 11, 2022
Project: Fox Run Substation
Location: Monument, CO

<p>1. Basin Storage Volume</p> <p>A) Effective Imperviousness of Tributary Area, I_a</p> <p>B) Tributary Area's Imperviousness Ratio ($i = I_a / 100$)</p> <p>C) Contributing Watershed Area</p> <p>D) For Watersheds Outside of the Denver Region, Depth of Average Runoff Producing Storm</p> <p>E) Design Concept (Select EURV when also designing for flood control)</p> <p>F) Design Volume (WQCV) Based on 40-hour Drain Time ($V_{DESIGN} = (1.0 * (0.91 * i^3 - 1.19 * i^2 + 0.78 * i) / 12 * Area)$)</p> <p>G) For Watersheds Outside of the Denver Region, Water Quality Capture Volume (WQCV) Design Volume ($V_{WQCV\ OTHER} = (d_c * V_{DESIGN} / 0.43)$)</p> <p>H) User Input of Water Quality Capture Volume (WQCV) Design Volume (Only if a different WQCV Design Volume is desired)</p> <p>I) NRCS Hydrologic Soil Groups of Tributary Watershed i) Percentage of Watershed consisting of Type A Soils ii) Percentage of Watershed consisting of Type B Soils iii) Percentage of Watershed consisting of Type C/D Soils</p> <p>J) Excess Urban Runoff Volume (EURV) Design Volume For HSG A: $EURV_A = 1.68 * i^{1.28}$ For HSG B: $EURV_B = 1.36 * i^{1.08}$ For HSG C/D: $EURV_{C/D} = 1.20 * i^{1.08}$</p> <p>K) User Input of Excess Urban Runoff Volume (EURV) Design Volume (Only if a different EURV Design Volume is desired)</p>	<p align="center">doesn't match MHFD Spreadsheet above</p> <p>$I_a =$ <input type="text" value="71.0"/> %</p> <p>$i =$ <input type="text" value="0.710"/></p> <p>Area = <input type="text" value="5.230"/> ac</p> <p>$d_c =$ <input type="text" value="0.41"/> in</p> <div style="border: 1px solid black; padding: 5px; margin: 5px 0;"> Choose One <input checked="" type="radio"/> Water Quality Capture Volume (WQCV) <input type="radio"/> Excess Urban Runoff Volume (EURV) </div> <p>$V_{DESIGN} =$ <input type="text"/> ac-ft</p> <p>$V_{DESIGN\ OTHER} =$ <input type="text"/> ac-ft</p> <p>$V_{DESIGN\ USER} =$ <input type="text" value="0.074"/> ac-ft</p> <p>HSG A = <input type="text" value="0.116"/> %</p> <p>HSG B = <input type="text"/> %</p> <p>HSG C/D = <input type="text"/> %</p> <p>EURV_{DESIGN} = <input type="text"/> ac-ft</p> <p>EURV_{DESIGN\ USER} = <input type="text"/> ac-ft</p> <p align="center">doesn't match design</p>
<p>2. Basin Shape: Length to Width Ratio (A basin length to width ratio of at least 2:1 will improve TSS reduction.)</p>	<p>L : W = <input type="text" value="2.0"/> : 1</p>
<p>3. Basin Side Slopes</p> <p>A) Basin Maximum Side Slopes (Horizontal distance per unit vertical, 4:1 or flatter preferred)</p>	<p>Z = <input type="text" value="4.00"/> ft / ft</p>
<p>4. Inlet</p> <p>A) Describe means of providing energy dissipation at concentrated inflow locations:</p>	<p>_____</p> <p>_____</p> <p>_____</p>
<p>5. Forebay</p> <p>A) Minimum Forebay Volume ($V_{MIN} =$ <input type="text" value="2%"/> of the WQCV)</p> <p>B) Actual Forebay Volume</p> <p>C) Forebay Depth ($D_F =$ <input type="text" value="18"/> inch maximum)</p> <p>D) Forebay Discharge</p> <p>i) Undetained 100-year Peak Discharge</p> <p>ii) Forebay Discharge Design Flow ($Q_F = 0.02 * Q_{100}$)</p> <p>E) Forebay Discharge Design</p> <p>F) Discharge Pipe Size (minimum 8-inches)</p> <p>G) Rectangular Notch Width</p>	<p>$V_{MIN} =$ <input type="text" value="0.001"/> ac-ft</p> <p>$V_F =$ <input type="text" value="0.001"/> ac-ft</p> <p>$D_F =$ <input type="text" value="18.0"/> in</p> <p>$Q_{100} =$ <input type="text" value="25.16"/> cfs</p> <p>$Q_F =$ <input type="text" value="0.50"/> cfs</p> <div style="border: 1px solid black; padding: 5px; margin: 5px 0;"> Choose One <input type="radio"/> Berm With Pipe <input checked="" type="radio"/> Wall with Rect. Notch <input type="radio"/> Wall with V-Notch Weir </div> <p align="right">Flow too small for berm w/ pipe</p> <p>Calculated $D_P =$ <input type="text"/> in</p> <p>Calculated $W_N =$ <input type="text" value="4.6"/> in</p>

Design Procedure Form: Extended Detention Basin (EDB)

Designer: Thayne Clement
Company: Del-Mont Consultants
Date: October 11, 2022
Project: Fox Run Substation
Location: Monument, CO

<p>6. Trickle Channel</p> <p>A) Type of Trickle Channel</p> <p>F) Slope of Trickle Channel</p>	<div style="border: 1px solid black; padding: 5px; margin-bottom: 10px;"> Choose One <input checked="" type="radio"/> Concrete <input type="radio"/> Soft Bottom </div> <p>S = <input type="text" value="0.0050"/> ft / ft</p>
<p>7. Micropool and Outlet Structure</p> <p>A) Depth of Micropool (2.5-foot minimum)</p> <p>B) Surface Area of Micropool (10 ft² minimum)</p> <p>C) Outlet Type</p> <p>D) Smallest Dimension of Orifice Opening Based on Hydrograph Routing (Use UD-Detention)</p> <p>E) Total Outlet Area</p>	<div style="margin-bottom: 10px;"> 11? → $D_M =$<input type="text" value="2.5"/> ft $A_M =$<input type="text" value="10"/> sq ft </div> <div style="border: 1px solid black; padding: 5px; margin-bottom: 10px;"> Choose One <input checked="" type="radio"/> Orifice Plate <input type="radio"/> Other (Describe): </div> <hr/> <hr/> <hr/> <div style="margin-bottom: 10px;"> 4.68? → $D_{orifice} =$<input type="text" value="1.22"/> inches $A_{ot} =$<input type="text" value="5.10"/> square inches </div>
<p>8. Initial Surcharge Volume</p> <p>A) Depth of Initial Surcharge Volume (Minimum recommended depth is 4 inches)</p> <p>B) Minimum Initial Surcharge Volume (Minimum volume of 0.3% of the WQCV)</p> <p>C) Initial Surcharge Provided Above Micropool</p>	<p>$D_{is} =$<input type="text" value="4"/> in</p> <p>$V_{is} =$<input type="text"/> cu ft</p> <p>$V_s =$<input type="text" value="3.3"/> cu ft</p>
<p>9. Trash Rack</p> <p>A) Water Quality Screen Open Area: $A_t = A_{ot} * 38.5 * (e^{-0.095D})$</p> <p>B) Type of Screen (If specifying an alternative to the materials recommended in the USDCM, indicate "other" and enter the ratio of the total open area to the total screen area for the material specified.)</p> <p style="margin-left: 100px;">Other (Y/N): <input type="text" value="Y"/> ← N</p> <p>C) Ratio of Total Open Area to Total Area (only for type 'Other')</p> <p>D) Total Water Quality Screen Area (based on screen type)</p> <p>E) Depth of Design Volume (EURV or WQCV) (Based on design concept chosen under 1E)</p> <p>F) Height of Water Quality Screen (H_{TR})</p> <p>G) Width of Water Quality Screen Opening ($W_{opening}$) (Minimum of 12 inches is recommended)</p>	<p>$A_t =$<input type="text" value="209"/> square inches</p> <div style="border: 1px solid black; padding: 2px; margin-bottom: 5px;"> Other (Please describe below) </div> <hr/> <hr/> <hr/> <p>User Ratio = <input type="text" value="0.6"/></p> <p>$A_{total} =$<input type="text" value="349"/> sq. in. Based on type 'Other' screen ratio</p> <p>H = <input type="text" value="0.82"/> feet</p> <p>$H_{TR} =$<input type="text" value="37.84"/> inches</p> <p>$W_{opening} =$<input type="text" value="12.0"/> inches VALUE LESS THAN RECOMMENDED MIN. WIDTH. WIDTH HAS BEEN SET TO 12 INCHES.</p>

Design Procedure Form: Extended Detention Basin (EDB)

Sheet 3 of 3

Designer: Thayne Clement
Company: Del-Mont Consultants
Date: October 11, 2022
Project: Fox Run Substation
Location: Monument, CO

10. Overflow Embankment A) Describe embankment protection for 100-year and greater overtopping: B) Slope of Overflow Embankment (Horizontal distance per unit vertical, 4:1 or flatter preferred)	<hr/> <hr/> <hr/> Ze = <input type="text" value="4.00"/> ft / ft
--	---

11. Vegetation	Choose One <input type="radio"/> Irrigated <input checked="" type="radio"/> Not Irrigated
----------------	---

12. Access A) Describe Sediment Removal Procedures	<hr/> <hr/> <hr/> <hr/> <hr/> <hr/>
---	-------------------------------------

Notes: _____

Appendix D

Rational Method Modeling Results



Project Description

File Name 21036-Fox Run Drainage - RM5.SPF

Project Options

Flow Units CFS
 Elevation Type Elevation
 Hydrology Method Rational
 Time of Concentration (TOC) Method Kirpich
 Link Routing Method Kinematic Wave
 Enable Overflow Ponding at Nodes YES
 Skip Steady State Analysis Time Periods NO

Analysis Options

Start Analysis On 00:00:00 0:00:00
 End Analysis On 00:00:00 0:00:00
 Start Reporting On 00:00:00 0:00:00
 Antecedent Dry Days 0 days
 Runoff (Dry Weather) Time Step 0 01:00:00 days hh:mm:ss
 Runoff (Wet Weather) Time Step 0 00:05:00 days hh:mm:ss
 Reporting Time Step 0 00:05:00 days hh:mm:ss
 Routing Time Step 30 seconds

Number of Elements

	Qty
Rain Gages	0
Subbasins	5
Nodes.....	8
<i>Junctions</i>	4
<i>Outfalls</i>	3
<i>Flow Diversions</i>	0
<i>Inlets</i>	0
<i>Storage Nodes</i>	1
Links.....	11
<i>Channels</i>	1
<i>Pipes</i>	3
<i>Pumps</i>	0
<i>Orifices</i>	5
<i>Weirs</i>	2
<i>Outlets</i>	0
Pollutants	0
Land Uses	0

Rainfall Details

Return Period..... 5 year(s)

Subbasin Summary

SN Subbasin ID	Area (ac)	Weighted Runoff Coefficient	Average Slope (%)	Flow Length (ft)	Total Rainfall (in)	Total Runoff (in)	Total Runoff Volume (ac-in)	Peak Runoff (cfs)	Time of Concentration (days hh:mm:ss)
1 Existing	14.38	0.0900	6.0000	1000.00	0.43	0.04	0.56	7.20	0 00:04:42
2 Offsite	4.50	0.0900	4.0000	700.00	0.40	0.04	0.16	2.36	0 00:04:10
3 Proposed-North	6.70	0.1200	5.0000	1000.00	0.43	0.05	0.35	4.14	0 00:05:03
4 Proposed-South	2.44	0.1400	6.0000	800.00	0.40	0.06	0.14	2.03	0 00:03:57
5 Yard	5.23	0.5500	1.0000	1000.00	0.66	0.36	1.89	12.13	0 00:09:22

Node Summary

SN	Element ID	Element Type	Invert Elevation (ft)	Ground/Rim (Max) Elevation (ft)	Initial Water Elevation (ft)	Surcharge Elevation (ft)	Ponded Area (ft ²)	Peak Inflow (cfs)	Max HGL Elevation (ft)	Max Surcharge Depth (ft)	Min Freeboard (ft)	Time of Peak Flooding Occurrence (days hh:mm)	Total Flooded Volume (ac-in)	Total Time Flooded (min)
1	Culvert-In	Junction	7461.56	7464.00	0.00	0.00	0.00	2.36	7461.89	0.00	2.67	0 00:00	0.00	0.00
2	Culvert-Out	Junction	7460.44	7462.00	0.00	0.00	0.00	2.34	7460.75	0.00	2.69	0 00:00	0.00	0.00
3	Pipe-Out	Junction	7443.22	7445.19	0.00	7446.00	0.00	0.08	7443.33	0.00	1.86	0 00:00	0.00	0.00
4	Pond-Out	Junction	7443.42	7447.00	0.00	7447.00	0.00	0.08	7443.53	0.00	3.89	0 00:00	0.00	0.00
5	Existing-Out	Outfall	7435.00					7.20	7435.00					
6	Out-North	Outfall	7435.00					4.15	7435.03					
7	Out-South	Outfall	7435.00					4.25	7435.00					
8	Pond	Storage Node	7444.00	7448.00	0.00		0.00	12.13	7444.86				0.00	0.00

Link Summary

SN	Element ID	Element Type	From (Inlet) Node	To (Outlet) Node	Length (ft)	Inlet Invert Elevation (ft)	Outlet Invert Elevation (ft)	Average Slope (%)	Diameter or Height (in)	Manning's Roughness	Peak Flow (cfs)	Design Flow Capacity (cfs)	Peak Flow/Design Flow Ratio	Peak Flow Velocity (ft/sec)	Peak Flow Depth (ft)	Peak Flow Depth/Total Depth Ratio	Total Time Surcharged (min)	Reported Condition
1	Access-Culvert	Pipe	Culvert-In	Culvert-Out	56.00	7461.56	7460.44	2.0000	36.000	0.0120	2.34	102.19	0.02	7.39	0.32	0.11	0.00	Calculated
2	Link-04	Pipe	Culvert-Out	Out-South	414.64	0.00	7435.00	-1793.1200	0.000	0.0150	2.34	0.00	0.02	0.00	0.32	0.11	0.00	Calculated
3	Out-Pipe	Pipe	Pond-Out	Pipe-Out	40.00	7443.42	7443.22	0.5000	18.000	0.0120	0.08	8.05	0.01	1.47	0.11	0.07	0.00	Calculated
4	Out-Swale	Channel	Pipe-Out	Out-North	150.00	7443.22	7435.00	5.4800	12.000	0.0270	0.08	54.11	0.00	1.24	0.03	0.03	0.00	
5	Orifice-01	Orifice	Pond	Pond-Out		7444.00	7443.42		1.220		0.04							
6	Orifice-02	Orifice	Pond	Pond-Out		7444.00	7443.42		1.220		0.03							
7	Orifice-03	Orifice	Pond	Pond-Out		7444.00	7443.42		1.220		0.02							
8	Orifice-04	Orifice	Pond	Pond-Out		7444.00	7443.42		1.220		0.00							
9	Orifice-05	Orifice	Pond	Pond-Out		7444.00	7443.42		1.220		0.00							
10	Spillway	Weir	Pond	Pond-Out		7444.00	7443.42				0.00							
11	Weir	Weir	Pond	Pond-Out		7444.00	7443.42				0.00							

Subbasin Hydrology

Subbasin : Existing

Input Data

Area (ac) 14.38
 Weighted Runoff Coefficient 0.09
 Average Slope (%) 6
 Flow Length (ft) 1000

Runoff Coefficient

Soil/Surface Description	Area (acres)	Soil Group	Runoff Coeff.
-	14.38	-	0.09
Composite Area & Weighted Runoff Coeff.	14.38		0.09

Time of Concentration

TOC Method : Kirpich

Sheet Flow Equation :

$$T_c = (0.0078 * ((L_f^{0.77}) * (S_f^{-0.385})))$$

Where :

Tc = Time of Concentration (min)

Lf = Flow Length (ft)

Sf = Slope (ft/ft)


Flow Length (ft) 1000
 Slope (%) 6
 Computed TOC (min) 4.7

Subbasin Runoff Results

Total Rainfall (in) 0.43
 Total Runoff (in) 0.04
 Peak Runoff (cfs) 7.2
 Rainfall Intensity 5.562
 Weighted Runoff Coefficient 0.09
 Time of Concentration (days hh:mm:ss) 0 00:04:42

Subbasin : Existing

Runoff Hydrograph



Subbasin : Offsite

Input Data

Area (ac) 4.5
Weighted Runoff Coefficient 0.09
Average Slope (%) 4
Flow Length (ft) 700

Runoff Coefficient

Soil/Surface Description	Area (acres)	Soil Group	Runoff Coeff.
-	4.5	-	0.09
Composite Area & Weighted Runoff Coeff.	4.5		0.09

Time of Concentration


Flow Length (ft) 700
Slope (%) 4
Computed TOC (min) 4.18

Subbasin Runoff Results

Total Rainfall (in) 0.4
Total Runoff (in) 0.04
Peak Runoff (cfs) 2.36
Rainfall Intensity 5.825
Weighted Runoff Coefficient 0.09
Time of Concentration (days hh:mm:ss) 0 00:04:11

Subbasin : Offsite

Runoff Hydrograph



Subbasin : Proposed-North

Input Data

Area (ac) 6.7
 Weighted Runoff Coefficient 0.12
 Average Slope (%) 5
 Flow Length (ft) 1000

Runoff Coefficient

Soil/Surface Description	Area (acres)	Soil Group	Runoff Coeff.
-	6.7	-	0.12
Composite Area & Weighted Runoff Coeff.	6.7		0.12

Time of Concentration


Flow Length (ft) 1000
 Slope (%) 5
 Computed TOC (min) 5.05

Subbasin Runoff Results

Total Rainfall (in) 0.43
 Total Runoff (in) 0.05
 Peak Runoff (cfs) 4.14
 Rainfall Intensity 5.153
 Weighted Runoff Coefficient 0.12
 Time of Concentration (days hh:mm:ss) 0 00:05:03

Subbasin : Proposed-North

Runoff Hydrograph



Subbasin : Proposed-South

Input Data

Area (ac) 2.44
Weighted Runoff Coefficient 0.14
Average Slope (%) 6
Flow Length (ft) 800

Runoff Coefficient

Soil/Surface Description	Area (acres)	Soil Group	Runoff Coeff.
-	2.44	-	0.14
Composite Area & Weighted Runoff Coeff.	2.44		0.14

Time of Concentration


Flow Length (ft) 800
Slope (%) 6
Computed TOC (min) 3.96

Subbasin Runoff Results

Total Rainfall (in) 0.4
Total Runoff (in) 0.06
Peak Runoff (cfs) 2.03
Rainfall Intensity 5.95
Weighted Runoff Coefficient 0.14
Time of Concentration (days hh:mm:ss) 0 00:03:58

Subbasin : Proposed-South

Runoff Hydrograph



Subbasin : Yard

Input Data

Area (ac) 5.23
Weighted Runoff Coefficient 0.55
Average Slope (%) 1
Flow Length (ft) 1000

Runoff Coefficient

Soil/Surface Description	Area (acres)	Soil Group	Runoff Coeff.
-	5.23	-	0.55
Composite Area & Weighted Runoff Coeff.	5.23		0.55

Time of Concentration


Flow Length (ft) 1000
Slope (%) 1
Computed TOC (min) 9.38

Subbasin Runoff Results

Total Rainfall (in) 0.66
Total Runoff (in) 0.36
Peak Runoff (cfs) 12.13
Rainfall Intensity 4.217
Weighted Runoff Coefficient 0.55
Time of Concentration (days hh:mm:ss) 0 00:09:23

Subbasin : Yard

Runoff Hydrograph



Junction Input

SN Element ID	Invert Elevation (ft)	Ground/Rim (Max) Elevation (ft)	Ground/Rim (Max) Offset (ft)	Initial Water Elevation (ft)	Initial Water Depth (ft)	Surcharge Elevation (ft)	Surcharge Depth (ft)	Ponded Area (ft ²)	Minimum Pipe Cover (in)
1 Culvert-In	7461.56	7464.00	2.44	0.00	-7461.56	0.00	-7464.00	0.00	0.00
2 Culvert-Out	7460.44	7462.00	1.56	0.00	-7460.44	0.00	-7462.00	0.00	0.00
3 Pipe-Out	7443.22	7445.19	1.97	0.00	-7443.22	7446.00	0.81	0.00	0.00
4 Pond-Out	7443.42	7447.00	3.58	0.00	-7443.42	7447.00	0.00	0.00	0.00

Junction Results

SN Element ID	Peak Inflow (cfs)	Peak Lateral Inflow (cfs)	Max HGL Elevation Attained (ft)	Max HGL Depth Attained (ft)	Max Surcharge Depth Attained (ft)	Min Freeboard Attained (ft)	Average HGL Elevation Attained (ft)	Average HGL Depth Attained (ft)	Time of Max HGL Occurrence (days hh:mm)	Time of Peak Flooding Occurrence (days hh:mm)	Total Flooded Volume (ac-in)	Total Time Flooded (min)
1 Culvert-In	2.36	2.36	7461.89	0.33	0.00	2.67	7461.56	0.00	0 00:04	0 00:00	0.00	0.00
2 Culvert-Out	2.34	0.00	7460.75	0.31	0.00	2.69	7460.44	0.00	0 00:04	0 00:00	0.00	0.00
3 Pipe-Out	0.08	0.00	7443.33	0.11	0.00	1.86	7443.25	0.03	0 00:19	0 00:00	0.00	0.00
4 Pond-Out	0.08	0.00	7443.53	0.11	0.00	3.89	7443.45	0.03	0 00:18	0 00:00	0.00	0.00

Channel Input

SN Element ID	Length (ft)	Inlet Invert Elevation (ft)	Inlet Invert Offset (ft)	Outlet Invert Elevation (ft)	Outlet Invert Offset (ft)	Total Drop (ft)	Average Slope (%)	Shape	Height (ft)	Width (ft)	Manning's Roughness	Entrance Losses	Exit/Bend Losses	Additional Losses	Initial Flow (cfs)	Flap Gate
1 Out-Swale	150.00	7443.22	0.00	7435.00	0.00	8.22	5.4800	Trapezoidal	1.000	10.000	0.0270	0.5000	0.5000	0.0000	0.00	No

Channel Results

SN Element ID	Peak Flow (cfs)	Time of Peak Flow Occurrence (days hh:mm)	Design Flow Capacity (cfs)	Peak Flow/Design Flow Ratio	Peak Flow Velocity (ft/sec)	Travel Time (min)	Peak Flow Depth (ft)	Peak Flow Depth/Total Depth Ratio	Total Time Surcharged (min)	Froude Number	Reported Condition
1 Out-Swale	0.08	0 00:21	54.11	0.00	1.24	2.02	0.03	0.03	0.00		

Pipe Input

SN Element ID	Length (ft)	Inlet Invert Elevation (ft)	Inlet Invert Offset (ft)	Outlet Invert Elevation (ft)	Outlet Invert Offset (ft)	Total Drop (ft)	Average Pipe Slope (%)	Pipe Shape	Pipe Diameter or Height (in)	Pipe Width (in)	Manning's Roughness	Entrance Losses	Exit/Bend Losses	Additional Losses	Initial Flow (cfs)	Flap Gate
1 Access-Culvert	56.00	7461.56	0.00	7460.44	0.00	1.12	2.0000	CIRCULAR	36.000	36.000	0.0120	0.5000	0.5000	0.0000	0.00	No
2 Link-04	414.64	0.00	-7460.44	7435.00	0.00	-7435.00	-1793.1200	Dummy	0.000	0.000	0.0150	0.5000	0.5000	0.0000	0.00	No
3 Out-Pipe	40.00	7443.42	0.00	7443.22	0.00	0.20	0.5000	CIRCULAR	18.000	18.000	0.0120	0.5000	0.5000	0.0000	0.00	No

21036 Fox Run Substation
5 Year Storm Event

No. of
Barrels

1
1
1

Pipe Results

SN Element ID	Peak Flow (cfs)	Time of Peak Flow Occurrence (days hh:mm)	Design Flow Capacity (cfs)	Peak Flow/Design Flow Ratio	Peak Flow Velocity (ft/sec)	Travel Time (min)	Peak Flow Depth (ft)	Peak Flow Depth/Total Depth Ratio	Total Time Surcharged (min)	Froude Number	Reported Condition
1 Access-Culvert	2.34	0 00:04	102.19	0.02	7.39	0.13	0.32	0.11	0.00		Calculated
2 Link-04	2.34	0 00:04	0.00	0.02	0.00		0.32	0.11	0.00		Calculated
3 Out-Pipe	0.08	0 00:19	8.05	0.01	1.47	0.45	0.11	0.07	0.00		Calculated

Storage Nodes

Storage Node : Pond

Input Data


Invert Elevation (ft) 7444
Max (Rim) Elevation (ft) 7448
Max (Rim) Offset (ft) 4
Initial Water Elevation (ft) 0
Initial Water Depth (ft) -7444
Ponded Area (ft²) 0
Evaporation Loss 0

Storage Area Volume Curves

Storage Curve : Detention-Pond

Stage (ft)	Storage Area (ft ²)	Storage Volume (ft ³)
0	0	0
0.5	8482	2120.5
1	20284	9312
1.5	22437	19992.25
2	23645	31512.75
2.5	24883	43644.75
3	26149	56402.75
3.5	27443	69800.75
4	28766	83853

Storage Area Volume Curves



— Storage Area — Storage Volume

Storage Node : Pond (continued)

Outflow Weirs

SN Element ID	Weir Type	Flap Gate	Crest Elevation (ft)	Crest Offset (ft)	Length (ft)	Weir Total Height (ft)	Discharge Coefficient
1 Spillway	Trapezoidal	No	7447.00	3.00	10.00	1.00	3.37
2 Weir	Rectangular	No	7446.50	2.50	4.00	1.00	3.33

Outflow Orifices

SN Element ID	Orifice Type	Orifice Shape	Flap Gate	Circular Orifice Diameter (in)	Rectangular Orifice Height (in)	Rectangular Orifice Width (in)	Orifice Invert Elevation (ft)	Orifice Coefficient
1 Orifice-01	Side	CIRCULAR	No	1.22			7443.67	0.61
2 Orifice-02	Side	CIRCULAR	No	1.22			7444.17	0.61
3 Orifice-03	Side	CIRCULAR	No	1.22			7444.67	0.61
4 Orifice-04	Side	CIRCULAR	No	1.22			7445.17	0.61
5 Orifice-05	Side	CIRCULAR	No	1.22			7445.67	0.61

Output Summary Results

Peak Inflow (cfs)	12.13
Peak Lateral Inflow (cfs)	12.13
Peak Outflow (cfs)	0.08
Peak Exfiltration Flow Rate (cfm)	0
Max HGL Elevation Attained (ft)	7444.86
Max HGL Depth Attained (ft)	0.86
Average HGL Elevation Attained (ft)	7444.17
Average HGL Depth Attained (ft)	0.17
Time of Max HGL Occurrence (days hh:mm)	0 00:18
Total Exfiltration Volume (1000-ft³)	0
Total Flooded Volume (ac-in)	0
Total Time Flooded (min)	0
Total Retention Time (sec)	0

Project Description

File Name 21036-Fox Run Drainage - RM100.SPF

Project Options

Flow Units CFS
Elevation Type Elevation
Hydrology Method Rational
Time of Concentration (TOC) Method Kirpich
Link Routing Method Kinematic Wave
Enable Overflow Ponding at Nodes YES
Skip Steady State Analysis Time Periods NO

Analysis Options

Start Analysis On 00:00:00 0:00:00
End Analysis On 00:00:00 0:00:00
Start Reporting On 00:00:00 0:00:00
Antecedent Dry Days 0 days
Runoff (Dry Weather) Time Step 0 01:00:00 days hh:mm:ss
Runoff (Wet Weather) Time Step 0 00:05:00 days hh:mm:ss
Reporting Time Step 0 00:05:00 days hh:mm:ss
Routing Time Step 30 seconds

Number of Elements

	Qty
Rain Gages	0
Subbasins	5
Nodes.....	8
<i>Junctions</i>	4
<i>Outfalls</i>	3
<i>Flow Diversions</i>	0
<i>Inlets</i>	0
<i>Storage Nodes</i>	1
Links.....	11
<i>Channels</i>	1
<i>Pipes</i>	3
<i>Pumps</i>	0
<i>Orifices</i>	5
<i>Weirs</i>	2
<i>Outlets</i>	0
Pollutants	0
Land Uses	0

Rainfall Details

Return Period..... 100 year(s)

Subbasin Summary

SN Subbasin ID	Area (ac)	Weighted Runoff Coefficient	Average Slope (%)	Flow Length (ft)	Total Rainfall (in)	Total Runoff (in)	Total Runoff Volume (ac-in)	Peak Runoff (cfs)	Time of Concentration (days hh:mm:ss)
1 Existing	14.38	0.3600	6.0000	1000.00	0.73	0.26	3.75	48.26	0 00:04:42
2 Offsite	4.50	0.3600	4.0000	700.00	0.68	0.24	1.10	15.81	0 00:04:10
3 Proposed-North	6.70	0.3800	5.0000	1000.00	0.72	0.27	1.84	22.03	0 00:05:03
4 Proposed-South	2.44	0.4000	6.0000	800.00	0.67	0.27	0.65	9.73	0 00:03:57
5 Yard	5.23	0.6800	1.0000	1000.00	1.10	0.75	3.91	25.16	0 00:09:22

Node Summary

SN	Element ID	Element Type	Invert Elevation (ft)	Ground/Rim (Max) Elevation (ft)	Initial Water Elevation (ft)	Surcharge Elevation (ft)	Ponded Area (ft ²)	Peak Inflow (cfs)	Max HGL Elevation (ft)	Max Surcharge Depth (ft)	Min Freeboard (ft)	Time of Peak Flooding Occurrence (days hh:mm)	Total Flooded Volume (ac-in)	Total Time Flooded (min)
1	Culvert-In	Junction	7461.56	7464.00	0.00	0.00	0.00	15.81	7462.36	0.00	2.20	0 00:00	0.00	0.00
2	Culvert-Out	Junction	7460.44	7462.00	0.00	0.00	0.00	15.73	7461.24	0.00	2.20	0 00:00	0.00	0.00
3	Pipe-Out	Junction	7443.22	7445.19	0.00	7446.00	0.00	0.12	7443.35	0.00	1.84	0 00:00	0.00	0.00
4	Pond-Out	Junction	7443.42	7447.00	0.00	7447.00	0.00	0.12	7443.55	0.00	3.87	0 00:00	0.00	0.00
5	Existing-Out	Outfall	7435.00					48.26	7435.00					
6	Out-North	Outfall	7435.00					22.05	7435.04					
7	Out-South	Outfall	7435.00					24.96	7435.00					
8	Pond	Storage Node	7444.00	7448.00	0.00		0.00	25.16	7445.23				0.00	0.00

Link Summary

SN	Element ID	Element Type	From (Inlet) Node	To (Outlet) Node	Length (ft)	Inlet Invert Elevation (ft)	Outlet Invert Elevation (ft)	Average Slope (%)	Diameter or Height (in)	Manning's Roughness	Peak Flow (cfs)	Design Flow Capacity (cfs)	Peak Flow/Design Flow Ratio	Peak Flow Velocity (ft/sec)	Peak Flow Depth (ft)	Peak Flow Depth/Total Depth Ratio	Total Time Reported (min)	Surcharged Condition
1	Access-Culvert	Pipe	Culvert-In	Culvert-Out	56.00	7461.56	7460.44	2.0000	36.000	0.0120	15.73	102.19	0.15	11.63	0.79	0.26	0.00	Calculated
2	Link-04	Pipe	Culvert-Out	Out-South	414.64	0.00	7435.00	-1793.1200	0.000	0.0150	15.73	0.00	0.15	0.00	0.79	0.26	0.00	Calculated
3	Out-Pipe	Pipe	Pond-Out	Pipe-Out	40.00	7443.42	7443.22	0.5000	18.000	0.0120	0.12	8.05	0.01	1.63	0.13	0.08	0.00	Calculated
4	Out-Swale	Channel	Pipe-Out	Out-North	150.00	7443.22	7435.00	5.4800	12.000	0.0270	0.12	54.11	0.00	1.40	0.04	0.04	0.00	
5	Orifice-01	Orifice	Pond	Pond-Out		7444.00	7443.42		1.220		0.04							
6	Orifice-02	Orifice	Pond	Pond-Out		7444.00	7443.42		1.220		0.04							
7	Orifice-03	Orifice	Pond	Pond-Out		7444.00	7443.42		1.220		0.03							
8	Orifice-04	Orifice	Pond	Pond-Out		7444.00	7443.42		1.220		0.00							
9	Orifice-05	Orifice	Pond	Pond-Out		7444.00	7443.42		1.220		0.00							
10	Spillway	Weir	Pond	Pond-Out		7444.00	7443.42				0.00							
11	Weir	Weir	Pond	Pond-Out		7444.00	7443.42				0.00							

Subbasin Hydrology

Subbasin : Existing

Input Data

Area (ac)	14.38
Weighted Runoff Coefficient	0.36
Average Slope (%)	6
Flow Length (ft)	1000

Runoff Coefficient

Soil/Surface Description	Area (acres)	Soil Group	Runoff Coeff.
-	14.38	-	0.36
Composite Area & Weighted Runoff Coeff.	14.38		0.36

Time of Concentration

TOC Method : Kirpich

Sheet Flow Equation :

$$T_c = (0.0078 * ((L_f^{0.77}) * (S_f^{-0.385})))$$

Where :

Tc = Time of Concentration (min)
 Lf = Flow Length (ft)
 Sf = Slope (ft/ft)


Flow Length (ft)	1000
Slope (%)	6
Computed TOC (min)	4.7

Subbasin Runoff Results

Total Rainfall (in)	0.73
Total Runoff (in)	0.26
Peak Runoff (cfs)	48.26
Rainfall Intensity	9.322
Weighted Runoff Coefficient	0.36
Time of Concentration (days hh:mm:ss)	0 00:04:42

Subbasin : Existing

Runoff Hydrograph



Subbasin : Offsite

Input Data

Area (ac) 4.5
 Weighted Runoff Coefficient 0.36
 Average Slope (%) 4
 Flow Length (ft) 700

Runoff Coefficient

Soil/Surface Description	Area (acres)	Soil Group	Runoff Coeff.
-	4.5	-	0.36
Composite Area & Weighted Runoff Coeff.	4.5		0.36

Time of Concentration


Flow Length (ft) 700
 Slope (%) 4
 Computed TOC (min) 4.18

Subbasin Runoff Results

Total Rainfall (in) 0.68
 Total Runoff (in) 0.24
 Peak Runoff (cfs) 15.81
 Rainfall Intensity 9.761
 Weighted Runoff Coefficient 0.36
 Time of Concentration (days hh:mm:ss) 0 00:04:11

Subbasin : Offsite

Runoff Hydrograph



Subbasin : Proposed-North

Input Data

Area (ac) 6.7
 Weighted Runoff Coefficient 0.38
 Average Slope (%) 5
 Flow Length (ft) 1000

Runoff Coefficient

Soil/Surface Description	Area (acres)	Soil Group	Runoff Coeff.
-	6.7	-	0.38
Composite Area & Weighted Runoff Coeff.	6.7		0.38

Time of Concentration


Flow Length (ft) 1000
 Slope (%) 5
 Computed TOC (min) 5.05

Subbasin Runoff Results

Total Rainfall (in) 0.72
 Total Runoff (in) 0.27
 Peak Runoff (cfs) 22.03
 Rainfall Intensity 8.652
 Weighted Runoff Coefficient 0.38
 Time of Concentration (days hh:mm:ss) 0 00:05:03

Subbasin : Proposed-North

Runoff Hydrograph



Subbasin : Proposed-South

Input Data

Area (ac) 2.44
Weighted Runoff Coefficient 0.4
Average Slope (%) 6
Flow Length (ft) 800

Runoff Coefficient

Soil/Surface Description	Area (acres)	Soil Group	Runoff Coeff.
-	2.44	-	0.4
Composite Area & Weighted Runoff Coeff.	2.44		0.4

Time of Concentration


Flow Length (ft) 800
Slope (%) 6
Computed TOC (min) 3.96

Subbasin Runoff Results

Total Rainfall (in) 0.67
Total Runoff (in) 0.27
Peak Runoff (cfs) 9.73
Rainfall Intensity 9.97
Weighted Runoff Coefficient 0.4
Time of Concentration (days hh:mm:ss) 0 00:03:58

Subbasin : Proposed-South

Runoff Hydrograph



Subbasin : Yard

Input Data

Area (ac) 5.23
Weighted Runoff Coefficient 0.68
Average Slope (%) 1
Flow Length (ft) 1000

Runoff Coefficient

Soil/Surface Description	Area (acres)	Soil Group	Runoff Coeff.
-	5.23	-	0.68
Composite Area & Weighted Runoff Coeff.	5.23		0.68

Time of Concentration


Flow Length (ft) 1000
Slope (%) 1
Computed TOC (min) 9.38

Subbasin Runoff Results

Total Rainfall (in) 1.1
Total Runoff (in) 0.75
Peak Runoff (cfs) 25.16
Rainfall Intensity 7.076
Weighted Runoff Coefficient 0.68
Time of Concentration (days hh:mm:ss) 0 00:09:23

Subbasin : Yard

Runoff Hydrograph



Junction Input

SN Element ID	Invert Elevation (ft)	Ground/Rim (Max) Elevation (ft)	Ground/Rim (Max) Offset (ft)	Initial Water Elevation (ft)	Initial Water Depth (ft)	Surcharge Elevation (ft)	Surcharge Depth (ft)	Ponded Area (ft²)	Minimum Pipe Cover (in)
1 Culvert-In	7461.56	7464.00	2.44	0.00	-7461.56	0.00	-7464.00	0.00	0.00
2 Culvert-Out	7460.44	7462.00	1.56	0.00	-7460.44	0.00	-7462.00	0.00	0.00
3 Pipe-Out	7443.22	7445.19	1.97	0.00	-7443.22	7446.00	0.81	0.00	0.00
4 Pond-Out	7443.42	7447.00	3.58	0.00	-7443.42	7447.00	0.00	0.00	0.00

Junction Results

SN	Element ID	Peak Inflow	Peak Lateral Inflow	Max HGL Elevation Attained	Max HGL Depth Attained	Max Surcharge Depth Attained	Min Freeboard Attained	Average HGL Elevation Attained	Average HGL Depth Attained	Time of Max HGL Occurrence	Time of Peak Flooding Occurrence	Total Flooded Volume	Total Time Flooded
		(cfs)	(cfs)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(days hh:mm)	(days hh:mm)	(ac-in)	(min)
1	Culvert-In	15.81	15.81	7462.36	0.80	0.00	2.20	7461.56	0.00	0 00:04	0 00:00	0.00	0.00
2	Culvert-Out	15.73	0.00	7461.24	0.80	0.00	2.20	7460.44	0.00	0 00:04	0 00:00	0.00	0.00
3	Pipe-Out	0.12	0.00	7443.35	0.13	0.00	1.84	7443.27	0.05	0 00:19	0 00:00	0.00	0.00
4	Pond-Out	0.12	0.00	7443.55	0.13	0.00	3.87	7443.47	0.05	0 00:18	0 00:00	0.00	0.00

Channel Input

SN Element ID	Length (ft)	Inlet Invert Elevation (ft)	Inlet Invert Offset (ft)	Outlet Invert Elevation (ft)	Outlet Invert Offset (ft)	Total Drop (ft)	Average Slope (%)	Shape	Height (ft)	Width (ft)	Manning's Roughness	Entrance Losses	Exit/Bend Losses	Additional Losses	Initial Flow (cfs)	Flap Gate
1 Out-Swale	150.00	7443.22	0.00	7435.00	0.00	8.22	5.4800	Trapezoidal	1.000	10.000	0.0270	0.5000	0.5000	0.0000	0.00	No

Channel Results

SN Element ID	Peak Flow (cfs)	Time of Peak Flow Occurrence (days hh:mm)	Design Flow Capacity (cfs)	Peak Flow/Design Flow Ratio	Peak Flow Velocity (ft/sec)	Travel Time (min)	Peak Flow Depth (ft)	Peak Flow Depth/Total Depth Ratio	Total Time Surcharged (min)	Froude Number	Reported Condition
1 Out-Swale	0.12	0 00:21	54.11	0.00	1.40	1.79	0.04	0.04	0.00		

Pipe Input

SN Element ID	Length (ft)	Inlet Invert Elevation (ft)	Inlet Invert Offset (ft)	Outlet Invert Elevation (ft)	Outlet Invert Offset (ft)	Total Drop (ft)	Average Pipe Slope (%)	Pipe Shape	Pipe Diameter or Height (in)	Pipe Width (in)	Manning's Roughness	Entrance Losses	Exit/Bend Losses	Additional Losses	Initial Flow (cfs)	Flap Gate
1 Access-Culvert	56.00	7461.56	0.00	7460.44	0.00	1.12	2.0000	CIRCULAR	36.000	36.000	0.0120	0.5000	0.5000	0.0000	0.00	No
2 Link-04	414.64	0.00	-7460.44	7435.00	0.00	-7435.00	-1793.1200	Dummy	0.000	0.000	0.0150	0.5000	0.5000	0.0000	0.00	No
3 Out-Pipe	40.00	7443.42	0.00	7443.22	0.00	0.20	0.5000	CIRCULAR	18.000	18.000	0.0120	0.5000	0.5000	0.0000	0.00	No

21036 Fox Run Substation
100 Year Storm Event

No. of
Barrels

1
1
1

Pipe Results

SN Element ID	Peak Flow	Time of Peak Flow Occurrence	Design Flow Capacity	Peak Flow/Design Flow Ratio	Peak Flow Velocity	Travel Time	Peak Flow Depth	Peak Flow Depth/Total Depth Ratio	Total Time Surcharged	Froude Number	Reported Condition
	(cfs)	(days hh:mm)	(cfs)		(ft/sec)	(min)	(ft)		(min)		
1 Access-Culvert	15.73	0 00:04	102.19	0.15	11.63	0.08	0.79	0.26	0.00		Calculated
2 Link-04	15.73	0 00:04	0.00	0.15	0.00		0.79	0.26	0.00		Calculated
3 Out-Pipe	0.12	0 00:19	8.05	0.01	1.63	0.41	0.13	0.08	0.00		Calculated

Storage Nodes

Storage Node : Pond

Input Data


Invert Elevation (ft) 7444
Max (Rim) Elevation (ft) 7448
Max (Rim) Offset (ft) 4
Initial Water Elevation (ft) 0
Initial Water Depth (ft) -7444
Ponded Area (ft²) 0
Evaporation Loss 0

Storage Area Volume Curves

Storage Curve : Detention-Pond

Stage (ft)	Storage Area (ft ²)	Storage Volume (ft ³)
0	0	0
0.5	8482	2120.5
1	20284	9312
1.5	22437	19992.25
2	23645	31512.75
2.5	24883	43644.75
3	26149	56402.75
3.5	27443	69800.75
4	28766	83853

Storage Area Volume Curves



Storage Node : Pond (continued)

Outflow Weirs

SN Element ID	Weir Type	Flap Gate	Crest Elevation (ft)	Crest Offset (ft)	Length (ft)	Weir Total Height (ft)	Discharge Coefficient
1 Spillway	Trapezoidal	No	7447.00	3.00	10.00	1.00	3.37
2 Weir	Rectangular	No	7446.50	2.50	4.00	1.00	3.33

Outflow Orifices


SN Element ID	Orifice Type	Orifice Shape	Flap Gate	Circular Orifice Diameter (in)	Rectangular Orifice Height (in)	Rectangular Orifice Width (in)	Orifice Invert Elevation (ft)	Orifice Coefficient
1 Orifice-01	Side	CIRCULAR	No	1.22			7443.67	0.61
2 Orifice-02	Side	CIRCULAR	No	1.22			7444.17	0.61
3 Orifice-03	Side	CIRCULAR	No	1.22			7444.67	0.61
4 Orifice-04	Side	CIRCULAR	No	1.22			7445.17	0.61
5 Orifice-05	Side	CIRCULAR	No	1.22			7445.67	0.61

Output Summary Results

Peak Inflow (cfs)	25.16
Peak Lateral Inflow (cfs)	25.16
Peak Outflow (cfs)	0.12
Peak Exfiltration Flow Rate (cfm)	0
Max HGL Elevation Attained (ft)	7445.23
Max HGL Depth Attained (ft)	1.23
Average HGL Elevation Attained (ft)	7444.35
Average HGL Depth Attained (ft)	0.35
Time of Max HGL Occurrence (days hh:mm)	0 00:18
Total Exfiltration Volume (1000-ft³)	0
Total Flooded Volume (ac-in)	0
Total Time Flooded (min)	0
Total Retention Time (sec)	0

Drainage Report Final_V2.pdf Markup Summary

12/11/2022 3:48:54 PM (1)



Subject: Engineer
Page Label: 13
Author: dotprete
Date: 12/11/2022 3:48:54 PM
Status:
Color: ■
Layer:
Space:

show existing flow arrows
unresolved.


12/11/2022 3:53:52 PM (1)

2.32	3.21
21.2	27.1
0.2	0.2
0.0	0.0
Plate	Plate
N/A	N/A
90	95
98	109

Subject: Engineer
Page Label: 23
Author: dotprete
Date: 12/11/2022 3:53:52 PM
Status:
Color: ■
Layer:
Space:

Plate Plate


12/11/2022 3:54:11 PM (1)



Subject: Engineer
Page Label: 23
Author: dotprete
Date: 12/11/2022 3:54:11 PM
Status:
Color: ■
Layer:
Space:

update


12/11/2022 4:02:40 PM (1)



Subject: Engineer
Page Label: 27
Author: dotprete
Date: 12/11/2022 4:02:40 PM
Status:
Color: ■
Layer:
Space:

doesnt match MHFD Spreadsheet above


12/11/2022 4:06:16 PM (1)



Subject: Engineer
Page Label: 27
Author: dotprete
Date: 12/11/2022 4:06:16 PM
Status:
Color: ■
Layer:
Space:

0.116


12/11/2022 4:06:37 PM (1)



Subject: Engineer
Page Label: 27
Author: dotprete
Date: 12/11/2022 4:06:37 PM
Status:
Color: ■
Layer:
Space:

doesnt match design


12/11/2022 4:14:18 PM (1)



Subject: Engineer
Page Label: 28
Author: dotprete
Date: 12/11/2022 4:14:18 PM
Status:
Color: ■
Layer:
Space:

11?

12/11/2022 4:20:18 PM (1)



Subject: Engineer
Page Label: 28
Author: dotprete
Date: 12/11/2022 4:20:18 PM
Status:
Color: ■
Layer:
Space:

4.68?


12/11/2022 4:30:21 PM (1)



Subject: Engineer
Page Label: 13
Author: dotprete
Date: 12/11/2022 4:30:21 PM
Status:
Color: ■
Layer:
Space:

move to end of report


12/11/2022 4:33:46 PM (1)



Subject: Engineer
Page Label: 28
Author: dotprete
Date: 12/11/2022 4:33:46 PM
Status:
Color: ■
Layer:
Space:


N

12/11/2022 4:34:04 PM (1)



Subject: Engineer
Page Label: 27
Author: dotprete
Date: 12/11/2022 4:34:04 PM
Status:
Color: ■
Layer:
Space:

12/11/2022 4:53:16 PM (1)



Subject: Engineer
Page Label: 14
Author: dotprete
Date: 12/11/2022 4:53:16 PM
Status:
Color: ■
Layer:
Space:

Determine if this a suitable outfall. Where will the overflow be directed?


12/11/2022 4:56:37 PM (1)



Subject: Engineer
Page Label: 11
Author: dotprete
Date: 12/11/2022 4:56:37 PM
Status:
Color: ■
Layer:
Space:

Provide sw pipe calculations, drainage ditch calculations, culvert calculations, spillway riprap calculations, and riprap outlet protection calculations


12/11/2022 5:01:11 PM (1)



Subject: Engineer
Page Label: 13
Author: dotprete
Date: 12/11/2022 5:01:11 PM
Status:
Color: ■
Layer:
Space:

include basin for this disturbance and WQ


12/11/2022 5:03:58 PM (1)



Subject: Engineer
Page Label: 13
Author: dotprete
Date: 12/11/2022 5:03:58 PM
Status:
Color: ■
Layer:
Space:

There are basins that are not being captured by the proposed ponds. Explain in the narrative how WQ is being addressed for these basins. Possible exclusions include I.7.1.B.7 (land disturbance to undeveloped land that will remain undeveloped) and/or I.7.1.C.1 (which allows for 20% not to exceed 1 acre of the applicable development site area to not be captured).

12/11/2022 5:07:17 PM (1)



Subject: Engineer
Page Label: 13
Author: dotprete
Date: 12/11/2022 5:07:17 PM
Status:
Color: ■
Layer:
Space:


design point

12/7/2022 3:26:43 PM (1)




Subject: Text Box
Page Label: 4
Author: eschoenheit
Date: 12/7/2022 3:26:43 PM
Status:
Color: ■
Layer:
Space:

12/7/2022 4:27:10 PM (1)



Subject: Cloud
Page Label: 23
Author: dsdlaforce
Date: 12/7/2022 4:27:10 PM
Status:
Color: ■
Layer:
Space:

12/7/2022 4:29:37 PM (1)



Subject: Image
Page Label: 23
Author: dsdlaforce
Date: 12/7/2022 4:29:37 PM
Status:
Color: ■
Layer:
Space:


12/7/2022 4:29:50 PM (1)



Subject: Callout
Page Label: 23
Author: dsdlaforce
Date: 12/7/2022 4:29:50 PM
Status:
Color: ■
Layer:
Space:


Provide input to model the top of the outlet structure.

12/7/2022 4:30:35 PM (1)




Subject: Highlight
Page Label: 23
Author: dsdlaforce
Date: 12/7/2022 4:30:35 PM
Status:
Color: ■
Layer:
Space:

12/7/2022 4:31:03 PM (1)



Subject: Cloud
Page Label: 23
Author: dsdlaforce
Date: 12/7/2022 4:31:03 PM
Status:
Color: ■
Layer:
Space:


12/7/2022 4:31:20 PM (1)



Subject: Callout
Page Label: 23
Author: dsdlaforce
Date: 12/7/2022 4:31:20 PM
Status:
Color: ■
Layer:
Space:


provide input to model the outlet pipe

12/8/2022 10:42:21 AM (1)



Subject: Highlight
Page Label: 14
Author: dsdlaforce
Date: 12/8/2022 10:42:21 AM
Status:
Color:
Layer:
Space:

12/8/2022 10:43:34 AM (1)




Subject: Callout
Page Label: 14
Author: dsdlaforce
Date: 12/8/2022 10:43:34 AM
Status:
Color:
Layer:
Space:

The manner of flow has changed from sheet flow to concentrated flow. Analyze the conveyance path up to the suitable outfall as defined in ECM 3.2.4. The conveyance path must be hydraulically adequate/stable.

Unresolved. Add a paragraph or section in the Drainage Facility design summarizing the results.
- Identify the velocity along the highlighted section and state whether it's within the permissible non-erosive velocity for the given soil, ground cover, and slope. Mitigation will be required if the concentrated pond discharge is likely to erode the existing ground downstream of the proposed swale. Contact the review engineer to discuss if additional clarification is required.


12/8/2022 12:13:48 PM (1)



Subject: Callout
Page Label: 23
Author: dsdlaforce
Date: 12/8/2022 12:13:48 PM
Status:
Color:
Layer:
Space:

Change Zone 2 to Orifice Plate

12/8/2022 12:14:15 PM (1)



Subject: Callout
Page Label: 23
Author: dsdlaforce
Date: 12/8/2022 12:14:15 PM
Status:
Color:
Layer:
Space:


Update Zone 3 to Weir & pipe (w/ Restrictor Plate)

12/8/2022 12:20:19 PM (1)

e=	3.00	ft
l=	10.00	ft
s=	0.17	H:
z=	1.00	ft

Subject: Highlight
Page Label: 23
Author: dsdlaforce
Date: 12/8/2022 12:20:19 PM
Status:
Color:
Layer:
Space:


12/8/2022 12:20:43 PM (1)



Subject: Callout
Page Label: 23
Author: dsdlaforce
Date: 12/8/2022 12:20:43 PM
Status:
Color: ■
Layer:
Space:

change side slopes to "4" per plans

12/8/2022 12:24:01 PM (1)



Subject: Callout
Page Label: 23
Author: dsdlaforce
Date: 12/8/2022 12:24:01 PM
Status:
Color: ■
Layer:
Space:

Height needs to match the outlet height from the micropool to the top of grate.


12/8/2022 6:03:27 AM (1)



Subject: Cloud+
Page Label: 3
Author: eschoenheit
Date: 12/8/2022 6:03:27 AM
Status:
Color: ■
Layer:
Space:


See unresolved comments from V1 and in GEOTECH report.

12/8/2022 6:03:30 AM (1)



Subject: Unresolved
Page Label: 3
Author: eschoenheit
Date: 12/8/2022 6:03:30 AM
Status:
Color: ■
Layer:
Space:


12/8/2022 6:04:12 AM (1)



heast into a drainage on
eek, Proposed
l in detail in the followinn

Subject: Unresolved
Page Label: 5
Author: eschoenheit
Date: 12/8/2022 6:04:12 AM
Status:
Color: ■
Layer:
Space:

12/8/2022 6:04:26 AM (1)



Subject: Text Box
Page Label: 5
Author: eschoenheit
Date: 12/8/2022 6:04:26 AM
Status:
Color: ■
Layer:
Space:

Reference should be made to any applicable major drainageway planning studies; Such as Drainage Basin Planning Studies; Flood Hazard delineation reports, and flood insurance studies or maps if available.

12/8/2022 6:13:42 AM (1)



Subject: Text Box
Page Label: 9
Author: eschoenheit
Date: 12/8/2022 6:13:42 AM
Status:
Color: ■
Layer:
Space:

Provide and explain Four Step Process
1. Runoff reduction proposed
2. Stabilization of drainage ways proposed/discussed
3. Proposed Stormwater Quality Capture Volume (WQCV) proposed
4. Identify Best Management Practices (BMP's) to be used to control industrial and commercial pollutants

12/8/2022 6:13:46 AM (1)



Subject: Unresolved
Page Label: 9
Author: eschoenheit
Date: 12/8/2022 6:13:46 AM
Status:
Color: ■
Layer:
Space:


12/8/2022 7:52:43 AM (1)



Subject: Text Box
Page Label: 13
Author: eschoenheit
Date: 12/8/2022 7:52:43 AM
Status:
Color: ■
Layer:
Space:

Please move drainage maps to end of report

12/8/2022 8:25:47 AM (1)



Subject: Cloud+
Page Label: 14
Author: eschoenheit
Date: 12/8/2022 8:25:47 AM
Status:
Color: ■
Layer:
Space:

Please call out pipe, riprap size and FES.


12/8/2022 8:26:16 AM (1)



Subject: Text Box
Page Label: 13
Author: eschoenheit
Date: 12/8/2022 8:26:16 AM
Status:
Color: ■
Layer:
Space:

Existing conditions and basin map should show parcel without new structures and development. Show flow arrows pre-development


12/8/2022 8:27:02 AM (1)



Subject: Callout
Page Label: 6
Author: eschoenheit
Date: 12/8/2022 8:27:02 AM
Status:
Color: ■
Layer:
Space:

add and detention

12/8/2022 9:52:03 AM (1)




Subject: Image
Page Label: 13
Author: eschoenheit
Date: 12/8/2022 9:52:03 AM
Status:
Color: ■
Layer:
Space:

12/8/2022 9:53:15 AM (1)



Subject: Unresolved
Page Label: 13
Author: eschoenheit
Date: 12/8/2022 9:53:15 AM
Status:
Color: ■
Layer:
Space:


12/8/2022 9:54:16 AM (1)



Subject: Callout
Page Label: 14
Author: dsdlaforce
Date: 12/8/2022 9:54:16 AM
Status:
Color: ■
Layer:
Space:

provide riprap sizing calculation in the appendix.

12/8/2022 9:54:39 AM (1)



Subject: Image
Page Label: 14
Author: dsdlaforce
Date: 12/8/2022 9:54:39 AM
Status:
Color: ■
Layer:
Space: