

Owl Ridge Subdivision Final Drainage Report

Colorado Springs, El Paso County, Colorado

March 2022

Revised: September 2022

Completed By:

Brett Louk, P.E.

Jody Thayer, I.E.

PCD No. MS-22-005



411 South Tejon, Suite i
Colorado Springs, Colorado 80903
719-465-2145
blouk@smhconsultants.com

TABLE OF CONTENTS

TABLE OF CONTENTS	1
STATEMENT SHEET	2
1. INTRODUCTION	3
2. DRAINAGE BASINS AND SUB-BASINS	3
3. DRAINAGE DESIGN CRITERIA	4
4. DRAINAGE FACILITY DESIGN	5
5. FOUR STEP PROCESS	6
6. FLOODPLAIN STATEMENT	7
7. DRAINAGE BASIN FEES	7
8. SUMMARY	7

APPENDIX

Figure 1 - Vicinity Map

Exhibit 1 – Custom Soil Resource Report

Figure 2 - FEMA Flood Plain Map

Table 1 – Existing Weighted C Values

Table 2 – Proposed Weighted C Values

Table 3 – Calculation of Time of Concentration – Pre-Development

Table 4 – Calculation of Time of Concentration – Post Development

Exhibit 2 – Hydraflow Output for 5-Year and 100-Year Events

Figure 3 – Pre-Development Drainage Map


Figure 4 – Post-Development Drainage Map

STATEMENT SHEET

Engineer's Statement:

The attached drainage plan and report were prepared under my direction and supervision and are correct to the best of my knowledge and belief. Said drainage report has been prepared according to the criteria established by the City/County for drainage reports and said report is in conformity with the master plan of the drainage basin. I accept responsibility for any liability caused by any negligent ~~and~~ errors or omissions on my part in preparing this report.

Brett Louk, P.E. # _____



Date

Developer's Statement:

I, the developer have read and will comply with all of the requirements specified in this drainage report and plan.

Owner: _____

A handwritten signature in black ink, appearing to be "C. H. H.", written over a horizontal line.

9-6-22

Date

Address: 18885 Brown Road

Colorado Springs, CO 80908

El Paso County:

Filed in accordance with the requirements of the Drainage Criteria Manual, Volumes 1 and 2, El Paso County Engineering Criteria Manual and Land Development Code as amended

Joshua Palmer
Interim County Engineer

Date

Conditions:

1. INTRODUCTION

The owner of the property located at 18885 Brown Road has asked SMH Consultants, P.A. (SMH) to conduct a stormwater drainage analysis for the proposed Owl Ridge Subdivision to satisfy the El Paso County drainage criteria manual requirements. This analysis will determine potential impacts resulting from subdividing a 61.95-acre residential lot into two single-family residential lots, and a 35 acre lot that will not be modified.

a. Development Location

The property is located in the SW $\frac{1}{4}$ of NW $\frac{1}{4}$ of Section 7, Township 11 South, Range 65 West in El Paso County, Colorado. The site consists of 61.95-acres with a single residential house, free-standing garage, and a barn. The lot is bordered by Agricultural land on all sides of the property. The site is accessed via private drive off of Brown Road. The general location of the site can be found in Figure 1 in the appendix.

b. Description of Property

The 61.95-acre site is to be divided into two residential lots, as well as a 35 acre lot that will remain unchanged. The site is located within the East Cherry Creek Drainage Basin.

Based on a Custom Soil Resource Report, obtained from the USDA NRCS Web Soil Survey (accessed August 2, 2021) for the site, the majority of the site consists of *Peyton – Pring Complex* with slopes ranging from 8-15 percent. This is a well-drained soil, with a medium runoff class. This soil typically does not flood or pond. The rest of the site is made up of Peyton Sandy Loam and Brussett Loam with slopes ranging from 3-9 percent. All of these soils are classified in Hydrologic Soil Group B. The Custom Soil Report is included as Exhibit 1 of the appendix.

2. DRAINAGE BASINS AND SUB-BASINS

a. Major Basin Descriptions

The subject site is located entirely in the East Cherry Creek Drainage Basin. The site can be split into 4 smaller sub-basin drainage areas based on where flows leave the site. The Drainage Areas can be seen in Figures 3 & 4 in the appendix. The entirety of the site will either sheet flow north or southeast at varying slopes from 1-5 percent and eventually meet in the East Cherry Creek.

b. Sub-Basin Descriptions

Offsite Drainage Area OS1 is approximately 23.42 acres located to northwest of the site. Stormwater runoff will flow northeast at slopes ranging from 1-6 percent and flow along existing terrain patterns to Design Point 1 through Drainage Area 1 to Design Point 4 then eventually to point of concentration 1 north of the site. Offsite Drainage Area OS1 is a pastured area and will have no improvements with this development.

Offsite Drainage Area OS2 is approximately 114.68 acres located west of the site. Stormwater runoff will flow east along at slopes ranging from 1-6 percent and flow along existing terrain patterns to Design Point 3 through Drainage Area 3 to Design Point 7 then eventually to point of concentration 3 east of the site. Offsite Drainage Area OS2 is pastured area and will have no improvements with this development.

Drainage Area 1 is approximately 10.72 acres located on the north side of the site. Stormwater runoff will flow north at slopes ranging from 1-4 percent and flow along existing terrain patterns to Design Point 4 then eventually to point of concentration 1 north of the site. Drainage Area 1 is a pastured area. As part of the planned improvements, Drainage Area 1 will have one single-family residential home constructed on it. The home is anticipated to be approximately 7,000 square feet. A new gravel drive is proposed to serve the residence. The proposed layout of the gravel drive can be seen on Exhibit 4. The overall flow pattern for Drainage Area 1 will remain unchanged from existing conditions.

Drainage Area 2 is approximately 1.39 acres located on the east side of the site. Stormwater will flow southeast at slopes ranging from 1-5 percent and flow along existing terrain patterns to Design Point 5 then eventually to point of concentration 2 east of the site. Drainage Area 2 is primarily pasture, with a small gravel drive along the east lot line. As part of the planned improvements, Drainage Area 2 will have a portion of the new gravel drive to serve the proposed single-family residence. The proposed layout of the gravel drive can be seen on Exhibit 4. The overall flow pattern for Drainage Area 2 will remain unchanged from existing conditions.

Drainage Area 3 is approximately 9.45 acres located on the west side of the site. Stormwater will flow southeast at slopes ranging from 1-4 percent and flow along existing terrain patterns to either Drainage Point 6 or Drainage Point 7 then eventually to point of concentration 3 east of the site. Drainage Area 3 is mostly pasture area with a portion of an existing gravel drive. As part of the planned improvements Drainage Area 3 will have a new gravel drive to serve the new single family residence on the north side of the site. The proposed layout of the gravel drive can be seen on Exhibit 4. The overall flow pattern for Drainage Area 3 will remain unchanged from existing conditions.

Drainage Area 4 is approximately 5.37 acres located on the south side of the site. Stormwater will sheet flow northeast at slopes ranging from 1-4 percent and flow along existing terrain patterns to Design Point 8 eventually to point of concentration 3 east of the site. Drainage Area 4 is mostly pasture area with an existing house, a free-standing garage, barn, paved parking and gravel drives. Drainage Area 4 is to remain unchanged. The overall flow pattern for Drainage Area 4 will remain unchanged from existing conditions.

3. DRAINAGE DESIGN CRITERIA

a. Development Criteria Reference

Pre- and post-development drainage characteristics were reviewed, studied, and analyzed using the *El Paso County Drainage Criteria Manual*, Federal Emergency Management

Agency's Flood Insurance Rate Map and USDA NRCS Web Soil Survey. Hydraflow Hydrographs Extension and AutoCAD Civil3D modeling software were utilized to develop a model to determine peak flow hydrographs for the site.

b. Hydrologic Criteria

Hydrology calculations in this report were performed following the methodologies outlined in the El Paso County Engineering Criteria Manual and the El Paso County Drainage Criteria Manual (DCM) Volumes 1 and 2. Drainage characteristics were delineated based on existing topographic information from Lidar and USGS topographical maps. In the appendix, Figures 3 & 4 show the site drainage information.

Since the watershed area encompassing the development site is less than 100 acres, the Rational Method was used to determine peak flows for the 5-year and 100-year storm events. Weighted C values were determined for each drainage area within the proposed site based on the amount of impervious and pervious areas. A runoff coefficient (C) was chosen from Table 6-6 of the *El Paso County Drainage Criteria Manual, Volume 1 Update*. As mentioned earlier, the site consists of Hydrological Soil Group B. The Weighted C values are shown in the Appendix in Tables 1 and 2.

The time of concentration was calculated for each drainage area based off methods found in Chapter 6, Section 3.2 of the *El Paso County Drainage Criteria Manual, Volume 1 update*. The first 300 feet of unconcentrated overland flow time was calculated and added to the subsequent channelized flow times. Channelized flow times were calculated using channel flow time equation. Tables 3 & 4, in the appendix, depict the assumptions and variables used to determine the time of concentrations.

4. DRAINAGE FACILITY DESIGN

a. General Concept

The site will be subdivided into two single-family residential lots. This development does not include any site grading, roadway construction or drainage structure installation. Due to this, the developed drainage basins and design points are the same as pre-developed. The C values for the site will change minimally due to the addition of the single-family residences. The 5- and 100-year hydrographs for existing and proposed conditions are shown in Exhibit 2 in the appendix.

Offsite Drainage Area OS1 is approximately 23.42 acres located to northwest of the site. This area will be undisturbed throughout the proposed development. The overall flow pattern for Offsite Drainage Area OS1 will remain unchanged from existing conditions. The runoff values will remain the same. The drainage area has existing and proposed 5-year and 100-year flows of 3.36 cfs and 28.26 cfs, respectively.

Offsite Drainage Area OS2 is approximately 114.68 acres located to west of the site. This area will be undisturbed throughout the proposed development. The overall flow pattern for

Offsite Drainage Area OS2 will remain unchanged from existing conditions. The runoff values will remain the same. The drainage area has existing and proposed 5-year and 100-year flows of 18.94 cfs and 158.20 cfs, respectively.

Drainage Area 1 is approximately 10.72 acres located on the north side of the site. This area will have one new single-family residence built, which is assumed to be approximately 7,000 square feet. A new gravel drive will serve the proposed single-family residence. The overall flow pattern for Drainage Area 1 will remain unchanged from existing conditions. The drainage area has existing 5-year and 100-year flows of 1.77 cfs and 14.79 cfs, respectively. The drainage area has proposed 5-year and 100-year flows of 1.99 cfs and 15.21 cfs, respectively.

Drainage Area 2 is approximately 1.39 acres located on the east side of the site. This area will have a portion of the new gravel drive that will serve the proposed single-family residence. The overall flow pattern for Drainage Area 2 will remain unchanged from existing conditions. The drainage area has existing 5-year and 100-year flows of 0.24 cfs and 1.99 cfs, respectively. The drainage area has proposed 5-year and 100-year flows of 0.24 cfs and 1.97 cfs, respectively.

Drainage Area 3 is approximately 9.45 acres located on the west side of the site. A new gravel drive will serve the two proposed single-family residences. The overall flow pattern for Drainage Area 3 will remain unchanged from existing conditions. The drainage area has existing 5-year and 100-year flows of 1.83 cfs and 11.83 cfs, respectively. The drainage area has proposed 5-year and 100-year flows of 2.18 cfs and 12.27 cfs, respectively.

Drainage Area 4 is approximately 5.38 acres located on the south side of the site. Drainage Area 4 is to remain unchanged. The overall flow pattern for Drainage Area 4 will remain unchanged from existing conditions. The drainage area has existing and proposed 5-year and 100-year flows of 1.39 cfs and 8.00 cfs respectively.

5. FOUR STEP PROCESS

El Paso County requires a four step process for stormwater quality management: reducing runoff volumes, treating the water quality capture volume, stabilizing streams, and implementing long-term source controls. These steps are further outlined in Volumes 1 and 2 of the County's Drainage Criteria Manual.

Step 1: Employ Runoff Reduction Practices. The site has been designed so that all runoff runs through native pasture before leaving the site and entering downstream receiving waters. The new driveway will be constructed of gravel, which has a greater infiltration rate than that of typical pavement. These factors will contribute to less runoff leaving the site.

Step 2: Implement BMPs that Provide Water Quality Capture Volume (WQCV) with Slow Release. Per the Phase II Stormwater Regulations in Volume II of the Drainage Criteria Manual, this site is not required to provide permanent stormwater quality facilities. The total area to be disturbed will be less than 1 acre. Per the County's Post Construction Stormwater

Management Applicability (PBMP) Evaluation Form, permanent BMPs are not required as the project is considered a Large Lot Single-Family site with greater than 2.5 acres per dwelling and less than 10% impervious area for each lot. Per clarification from Colorado Department of Health and Environment, this exclusion only pertains to the lots and does not include roadways. The proposed driveway serving the proposed single family residence will be 15 feet wide by 1,005 feet long, which results in a disturbance of 15,075 ft². The proposed single family residence will be approximately 7,000 ft² in size. The total area of disturbance will be approximately 22,075 ft². Therefore, no permanent BMPs will be required for the site.

Step 3: Stabilize Drainageways. The existing natural channels will remain in place and undisturbed. Leaving the existing native vegetation will provide established vegetation to help prevent erosion. Once runoff leaves the site, it will travel approximately 12,000 feet, through natural channels, before it enters East Cherry Creek. Because of the path of the runoff from the subject site takes, before it enters the first receiving waters, no downstream improvements are needed.

Step 4: Implement Site Specific and Other Source Control BMPs. Soil erosion control measures will be implemented during construction of the single family residence and the gravel driveway. Some of the measures to be implemented during construction include: silt fence, temporary construction entrance, permanent/temporary seeding, etc. The full soil erosion control measures to be utilized during construction on the single family residence will be further outlined at the time of building permit application.

6. FLOODPLAIN STATEMENT

No portion of the site is located within a 100-year floodplain as determined by the Flood Insurance Rate Map (FIRM) number 08041C0305G effective date December 7, 2018 (see Figure 2 in the appendix).

7. DRAINAGE BASIN FEES

The site is located entirely within the East Cherry Creek Drainage Basin. The East Cherry Creek Drainage Basin is not studied within El Paso County, therefore no fees are due.

8. SUMMARY

A drainage analysis was conducted for a 61.95-acre residential site to be subdivided into two single-family residential lots and will be known as Owl Ridge Subdivision. The site is located in the East Cherry Creek drainage basin. Based on the analysis, the 5-year & 100-year post-development stormwater peak flow rates will be slightly higher than the pre-developed stormwater peak flow rates. Subdividing the site and developing an additional residential lot should not adversely impact surrounding or downstream properties.

References

El Paso County Assessor (2020). *El Paso County Assessor's Real Property Search*. Retrieved from <https://www.elpasoco.com/search-el-paso-county/>

El Paso County Clerk and Recorder (2001-2020). *El Paso County Clerk and Recorder Web Access*. Retrieved from publicrecordsearch.elpasoco.com/

United States Department of Agriculture Natural Resources Conservation Service (2091, July 31). *Web Soil Survey*. Retrieved from <https://websoilsurvey.sc.egov.usda.gov/App/WebSoilSurvey.aspx>

Federal Emergency Management Agency (2020). *FEMA Flood Map Service Center*. Retrieved from <https://msc.fema.gov/portal/home>

El Paso County, Colorado (2018). *Drainage Criteria Manual Volume 1*. Retrieved from: https://library.municode.com/co/el_paso_county/codes/drainage_criteria_manual?nodeId=DRCRMAVO1ELPACO

El Paso County, Colorado (2018). *Drainage Criteria Manual Volume 2*. Retrieved from: https://library.municode.com/co/el_paso_county/codes/drainage_criteria_manual?nodeId=DRCRMAVO2STQUPOPRBEMAPRBM

APPENDIX

VICINITY MAP

FIGURE 1



OWL RIDGE SUBDIVISION

DRAINAGE STUDY

EL PASO COUNTY, COLORADO


REVISION DATE	REVISION DESCRIPTION (DESCRIPTION)	VICINITY MAP
00/00/00	.	 NORTH
.	.	
SCALE: 1" = 500'		PROJECT #: 2010CS4031 CHECKED BY: BML DRAWN BY: JMT
DATE: 03/11/2022		

FIG. 1

SOILS REPORT

EXHIBIT 1



United States
Department of
Agriculture

NRCS

Natural
Resources
Conservation
Service

A product of the National
Cooperative Soil Survey,
a joint effort of the United
States Department of
Agriculture and other
Federal agencies, State
agencies including the
Agricultural Experiment
Stations, and local
participants

Custom Soil Resource Report for **El Paso County Area, Colorado**



August 2, 2021

Preface

Soil surveys contain information that affects land use planning in survey areas. They highlight soil limitations that affect various land uses and provide information about the properties of the soils in the survey areas. Soil surveys are designed for many different users, including farmers, ranchers, foresters, agronomists, urban planners, community officials, engineers, developers, builders, and home buyers. Also, conservationists, teachers, students, and specialists in recreation, waste disposal, and pollution control can use the surveys to help them understand, protect, or enhance the environment.

Various land use regulations of Federal, State, and local governments may impose special restrictions on land use or land treatment. Soil surveys identify soil properties that are used in making various land use or land treatment decisions. The information is intended to help the land users identify and reduce the effects of soil limitations on various land uses. The landowner or user is responsible for identifying and complying with existing laws and regulations.

Although soil survey information can be used for general farm, local, and wider area planning, onsite investigation is needed to supplement this information in some cases. Examples include soil quality assessments (<http://www.nrcs.usda.gov/wps/portal/nrcs/main/soils/health/>) and certain conservation and engineering applications. For more detailed information, contact your local USDA Service Center (<https://offices.sc.egov.usda.gov/locator/app?agency=nrcs>) or your NRCS State Soil Scientist (http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/contactus/?cid=nrcs142p2_053951).

Great differences in soil properties can occur within short distances. Some soils are seasonally wet or subject to flooding. Some are too unstable to be used as a foundation for buildings or roads. Clayey or wet soils are poorly suited to use as septic tank absorption fields. A high water table makes a soil poorly suited to basements or underground installations.

The National Cooperative Soil Survey is a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local agencies. The Natural Resources Conservation Service (NRCS) has leadership for the Federal part of the National Cooperative Soil Survey.

Information about soils is updated periodically. Updated information is available through the NRCS Web Soil Survey, the site for official soil survey information.

The U.S. Department of Agriculture (USDA) prohibits discrimination in all its programs and activities on the basis of race, color, national origin, age, disability, and where applicable, sex, marital status, familial status, parental status, religion, sexual orientation, genetic information, political beliefs, reprisal, or because all or a part of an individual's income is derived from any public assistance program. (Not all prohibited bases apply to all programs.) Persons with disabilities who require

alternative means for communication of program information (Braille, large print, audiotape, etc.) should contact USDA's TARGET Center at (202) 720-2600 (voice and TDD). To file a complaint of discrimination, write to USDA, Director, Office of Civil Rights, 1400 Independence Avenue, S.W., Washington, D.C. 20250-9410 or call (800) 795-3272 (voice) or (202) 720-6382 (TDD). USDA is an equal opportunity provider and employer.

Contents

Preface	2
How Soil Surveys Are Made	5
Soil Map	8
Soil Map.....	9
Legend.....	10
Map Unit Legend.....	11
Map Unit Descriptions.....	11
El Paso County Area, Colorado.....	13
15—Brussett loam, 3 to 5 percent slopes.....	13
67—Peyton sandy loam, 5 to 9 percent slopes.....	14
69—Peyton-Pring complex, 8 to 15 percent slopes.....	15
References	17

How Soil Surveys Are Made

Soil surveys are made to provide information about the soils and miscellaneous areas in a specific area. They include a description of the soils and miscellaneous areas and their location on the landscape and tables that show soil properties and limitations affecting various uses. Soil scientists observed the steepness, length, and shape of the slopes; the general pattern of drainage; the kinds of crops and native plants; and the kinds of bedrock. They observed and described many soil profiles. A soil profile is the sequence of natural layers, or horizons, in a soil. The profile extends from the surface down into the unconsolidated material in which the soil formed or from the surface down to bedrock. The unconsolidated material is devoid of roots and other living organisms and has not been changed by other biological activity.

Currently, soils are mapped according to the boundaries of major land resource areas (MLRAs). MLRAs are geographically associated land resource units that share common characteristics related to physiography, geology, climate, water resources, soils, biological resources, and land uses (USDA, 2006). Soil survey areas typically consist of parts of one or more MLRA.

The soils and miscellaneous areas in a survey area occur in an orderly pattern that is related to the geology, landforms, relief, climate, and natural vegetation of the area. Each kind of soil and miscellaneous area is associated with a particular kind of landform or with a segment of the landform. By observing the soils and miscellaneous areas in the survey area and relating their position to specific segments of the landform, a soil scientist develops a concept, or model, of how they were formed. Thus, during mapping, this model enables the soil scientist to predict with a considerable degree of accuracy the kind of soil or miscellaneous area at a specific location on the landscape.

Commonly, individual soils on the landscape merge into one another as their characteristics gradually change. To construct an accurate soil map, however, soil scientists must determine the boundaries between the soils. They can observe only a limited number of soil profiles. Nevertheless, these observations, supplemented by an understanding of the soil-vegetation-landscape relationship, are sufficient to verify predictions of the kinds of soil in an area and to determine the boundaries.

Soil scientists recorded the characteristics of the soil profiles that they studied. They noted soil color, texture, size and shape of soil aggregates, kind and amount of rock fragments, distribution of plant roots, reaction, and other features that enable them to identify soils. After describing the soils in the survey area and determining their properties, the soil scientists assigned the soils to taxonomic classes (units). Taxonomic classes are concepts. Each taxonomic class has a set of soil characteristics with precisely defined limits. The classes are used as a basis for comparison to classify soils systematically. Soil taxonomy, the system of taxonomic classification used in the United States, is based mainly on the kind and character of soil properties and the arrangement of horizons within the profile. After the soil

scientists classified and named the soils in the survey area, they compared the individual soils with similar soils in the same taxonomic class in other areas so that they could confirm data and assemble additional data based on experience and research.

The objective of soil mapping is not to delineate pure map unit components; the objective is to separate the landscape into landforms or landform segments that have similar use and management requirements. Each map unit is defined by a unique combination of soil components and/or miscellaneous areas in predictable proportions. Some components may be highly contrasting to the other components of the map unit. The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The delineation of such landforms and landform segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, onsite investigation is needed to define and locate the soils and miscellaneous areas.

Soil scientists make many field observations in the process of producing a soil map. The frequency of observation is dependent upon several factors, including scale of mapping, intensity of mapping, design of map units, complexity of the landscape, and experience of the soil scientist. Observations are made to test and refine the soil-landscape model and predictions and to verify the classification of the soils at specific locations. Once the soil-landscape model is refined, a significantly smaller number of measurements of individual soil properties are made and recorded. These measurements may include field measurements, such as those for color, depth to bedrock, and texture, and laboratory measurements, such as those for content of sand, silt, clay, salt, and other components. Properties of each soil typically vary from one point to another across the landscape.

Observations for map unit components are aggregated to develop ranges of characteristics for the components. The aggregated values are presented. Direct measurements do not exist for every property presented for every map unit component. Values for some properties are estimated from combinations of other properties.

While a soil survey is in progress, samples of some of the soils in the area generally are collected for laboratory analyses and for engineering tests. Soil scientists interpret the data from these analyses and tests as well as the field-observed characteristics and the soil properties to determine the expected behavior of the soils under different uses. Interpretations for all of the soils are field tested through observation of the soils in different uses and under different levels of management. Some interpretations are modified to fit local conditions, and some new interpretations are developed to meet local needs. Data are assembled from other sources, such as research information, production records, and field experience of specialists. For example, data on crop yields under defined levels of management are assembled from farm records and from field or plot experiments on the same kinds of soil.

Predictions about soil behavior are based not only on soil properties but also on such variables as climate and biological activity. Soil conditions are predictable over long periods of time, but they are not predictable from year to year. For example, soil scientists can predict with a fairly high degree of accuracy that a given soil will have a high water table within certain depths in most years, but they cannot predict that a high water table will always be at a specific level in the soil on a specific date.

After soil scientists located and identified the significant natural bodies of soil in the survey area, they drew the boundaries of these bodies on aerial photographs and


Custom Soil Resource Report

identified each as a specific map unit. Aerial photographs show trees, buildings, fields, roads, and rivers, all of which help in locating boundaries accurately.

Soil Map

The soil map section includes the soil map for the defined area of interest, a list of soil map units on the map and extent of each map unit, and cartographic symbols displayed on the map. Also presented are various metadata about data used to produce the map, and a description of each soil map unit.

Custom Soil Resource Report Soil Map



Custom Soil Resource Report

MAP LEGEND

Area of Interest (AOI)

 Area of Interest (AOI)

Soils


 Soil Map Unit Polygons


 Soil Map Unit Lines


 Soil Map Unit Points

Special Point Features

 Blowout

 Borrow Pit


 Clay Spot

 Closed Depression

 Gravel Pit

 Gravelly Spot

 Landfill

 Lava Flow

 Marsh or swamp

 Mine or Quarry

 Miscellaneous Water


 Perennial Water

 Rock Outcrop

 Saline Spot

 Sandy Spot

 Severely Eroded Spot


 Sinkhole

 Slide or Slip


 Sodic Spot


 Spoil Area

 Stony Spot


 Very Stony Spot

 Wet Spot

 Other

 Special Line Features

Water Features

 Streams and Canals


Transportation

 Rails


 Interstate Highways

 US Routes

 Major Roads

 Local Roads

Background

 Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
Web Soil Survey URL:
Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: El Paso County Area, Colorado
Survey Area Data: Version 18, Jun 5, 2020

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Sep 8, 2018—May 26, 2019

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
15	Brussett loam, 3 to 5 percent slopes	22.0	18.7%
67	Peyton sandy loam, 5 to 9 percent slopes	32.1	27.4%
69	Peyton-Pring complex, 8 to 15 percent slopes	63.2	53.9%
Totals for Area of Interest		117.2	100.0%

Map Unit Descriptions

The map units delineated on the detailed soil maps in a soil survey represent the soils or miscellaneous areas in the survey area. The map unit descriptions, along with the maps, can be used to determine the composition and properties of a unit.

A map unit delineation on a soil map represents an area dominated by one or more major kinds of soil or miscellaneous areas. A map unit is identified and named according to the taxonomic classification of the dominant soils. Within a taxonomic class there are precisely defined limits for the properties of the soils. On the landscape, however, the soils are natural phenomena, and they have the characteristic variability of all natural phenomena. Thus, the range of some observed properties may extend beyond the limits defined for a taxonomic class. Areas of soils of a single taxonomic class rarely, if ever, can be mapped without including areas of other taxonomic classes. Consequently, every map unit is made up of the soils or miscellaneous areas for which it is named and some minor components that belong to taxonomic classes other than those of the major soils.

Most minor soils have properties similar to those of the dominant soil or soils in the map unit, and thus they do not affect use and management. These are called noncontrasting, or similar, components. They may or may not be mentioned in a particular map unit description. Other minor components, however, have properties and behavioral characteristics divergent enough to affect use or to require different management. These are called contrasting, or dissimilar, components. They generally are in small areas and could not be mapped separately because of the scale used. Some small areas of strongly contrasting soils or miscellaneous areas are identified by a special symbol on the maps. If included in the database for a given area, the contrasting minor components are identified in the map unit descriptions along with some characteristics of each. A few areas of minor components may not have been observed, and consequently they are not mentioned in the descriptions, especially where the pattern was so complex that it was impractical to make enough observations to identify all the soils and miscellaneous areas on the landscape.

The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The objective of mapping is not to delineate pure taxonomic classes but rather to separate the landscape into landforms or

landform segments that have similar use and management requirements. The delineation of such segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, however, onsite investigation is needed to define and locate the soils and miscellaneous areas.

An identifying symbol precedes the map unit name in the map unit descriptions. Each description includes general facts about the unit and gives important soil properties and qualities.

Soils that have profiles that are almost alike make up a *soil series*. Except for differences in texture of the surface layer, all the soils of a series have major horizons that are similar in composition, thickness, and arrangement.

Soils of one series can differ in texture of the surface layer, slope, stoniness, salinity, degree of erosion, and other characteristics that affect their use. On the basis of such differences, a soil series is divided into *soil phases*. Most of the areas shown on the detailed soil maps are phases of soil series. The name of a soil phase commonly indicates a feature that affects use or management. For example, Alpha silt loam, 0 to 2 percent slopes, is a phase of the Alpha series.

Some map units are made up of two or more major soils or miscellaneous areas. These map units are complexes, associations, or undifferentiated groups.

A *complex* consists of two or more soils or miscellaneous areas in such an intricate pattern or in such small areas that they cannot be shown separately on the maps. The pattern and proportion of the soils or miscellaneous areas are somewhat similar in all areas. Alpha-Beta complex, 0 to 6 percent slopes, is an example.

An *association* is made up of two or more geographically associated soils or miscellaneous areas that are shown as one unit on the maps. Because of present or anticipated uses of the map units in the survey area, it was not considered practical or necessary to map the soils or miscellaneous areas separately. The pattern and relative proportion of the soils or miscellaneous areas are somewhat similar. Alpha-Beta association, 0 to 2 percent slopes, is an example.

An *undifferentiated group* is made up of two or more soils or miscellaneous areas that could be mapped individually but are mapped as one unit because similar interpretations can be made for use and management. The pattern and proportion of the soils or miscellaneous areas in a mapped area are not uniform. An area can be made up of only one of the major soils or miscellaneous areas, or it can be made up of all of them. Alpha and Beta soils, 0 to 2 percent slopes, is an example.

Some surveys include *miscellaneous areas*. Such areas have little or no soil material and support little or no vegetation. Rock outcrop is an example.

El Paso County Area, Colorado

15—Brussett loam, 3 to 5 percent slopes

Map Unit Setting

National map unit symbol: 367k

Elevation: 7,200 to 7,500 feet

Frost-free period: 115 to 125 days

Farmland classification: Prime farmland if irrigated

Map Unit Composition

Brussett and similar soils: 85 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Brussett

Setting

Landform: Hills

Landform position (three-dimensional): Side slope

Down-slope shape: Linear

Across-slope shape: Linear

Parent material: Eolian deposits

Typical profile

A - 0 to 8 inches: loam

BA - 8 to 12 inches: loam

Bt - 12 to 26 inches: clay loam

Bk - 26 to 60 inches: silt loam

Properties and qualities

Slope: 3 to 5 percent

Depth to restrictive feature: More than 80 inches

Drainage class: Well drained

Runoff class: Low

Capacity of the most limiting layer to transmit water (Ksat): Moderately high (0.20 to 0.60 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Calcium carbonate, maximum content: 5 percent

Maximum salinity: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)

Available water capacity: High (about 9.1 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 4e

Hydrologic Soil Group: B

Ecological site: R048AY222CO

Hydric soil rating: No

Minor Components

Other soils

Percent of map unit:

Hydric soil rating: No

67—Peyton sandy loam, 5 to 9 percent slopes

Map Unit Setting

National map unit symbol: 369d
Elevation: 6,800 to 7,600 feet
Mean annual air temperature: 43 to 45 degrees F
Frost-free period: 115 to 125 days
Farmland classification: Not prime farmland

Map Unit Composition

Peyton and similar soils: 85 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Peyton

Setting

Landform: Hills
Landform position (three-dimensional): Side slope
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Arkosic alluvium derived from sedimentary rock and/or arkosic residuum weathered from sedimentary rock

Typical profile

A - 0 to 12 inches: sandy loam
Bt - 12 to 25 inches: sandy clay loam
BC - 25 to 35 inches: sandy loam
C - 35 to 60 inches: sandy loam

Properties and qualities

Slope: 5 to 9 percent
Depth to restrictive feature: More than 80 inches
Drainage class: Well drained
Runoff class: Medium
Capacity of the most limiting layer to transmit water (Ksat): Moderately high (0.20 to 0.60 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water capacity: Moderate (about 7.3 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 4e
Hydrologic Soil Group: B
Ecological site: R049XB216CO - Sandy Divide
Hydric soil rating: No

Minor Components

Pleasant

Percent of map unit:
Landform: Depressions
Hydric soil rating: Yes

Other soils

Percent of map unit:
Hydric soil rating: No

69—Peyton-Pring complex, 8 to 15 percent slopes

Map Unit Setting

National map unit symbol: 369g
Elevation: 6,800 to 7,600 feet
Farmland classification: Not prime farmland

Map Unit Composition

Peyton and similar soils: 40 percent
Pring and similar soils: 30 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Peyton

Setting

Landform: Hills
Landform position (three-dimensional): Side slope
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Arkosic alluvium derived from sedimentary rock and/or arkosic residuum weathered from sedimentary rock

Typical profile

A - 0 to 12 inches: sandy loam
Bt - 12 to 25 inches: sandy clay loam
BC - 25 to 35 inches: sandy clay loam
C - 35 to 60 inches: sandy loam

Properties and qualities

Slope: 8 to 9 percent
Depth to restrictive feature: More than 80 inches
Drainage class: Well drained
Runoff class: Medium
Capacity of the most limiting layer to transmit water (Ksat): Moderately high (0.20 to 0.60 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water capacity: Moderate (about 7.3 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 4e

Hydrologic Soil Group: B

Ecological site: R049XB216CO - Sandy Divide

Hydric soil rating: No

Description of Pring

Setting

Landform: Hills

Landform position (three-dimensional): Side slope

Down-slope shape: Linear

Across-slope shape: Linear

Parent material: Arkosic alluvium derived from sedimentary rock

Typical profile

A - 0 to 14 inches: coarse sandy loam

C - 14 to 60 inches: gravelly sandy loam

Properties and qualities

Slope: 8 to 15 percent

Depth to restrictive feature: More than 80 inches

Drainage class: Well drained

Runoff class: Low

Capacity of the most limiting layer to transmit water (Ksat): High (2.00 to 6.00 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Available water capacity: Low (about 6.0 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 6e

Hydrologic Soil Group: B

Ecological site: R049XB222CO - Loamy Park

Hydric soil rating: No

Minor Components

Pleasant

Percent of map unit:

Landform: Depressions

Hydric soil rating: Yes

Other soils

Percent of map unit:

Hydric soil rating: No

References

- American Association of State Highway and Transportation Officials (AASHTO). 2004. Standard specifications for transportation materials and methods of sampling and testing. 24th edition.
- American Society for Testing and Materials (ASTM). 2005. Standard classification of soils for engineering purposes. ASTM Standard D2487-00.
- Cowardin, L.M., V. Carter, F.C. Golet, and E.T. LaRoe. 1979. Classification of wetlands and deep-water habitats of the United States. U.S. Fish and Wildlife Service FWS/OBS-79/31.
- Federal Register. July 13, 1994. Changes in hydric soils of the United States.
- Federal Register. September 18, 2002. Hydric soils of the United States.
- Hurt, G.W., and L.M. Vasilas, editors. Version 6.0, 2006. Field indicators of hydric soils in the United States.
- National Research Council. 1995. Wetlands: Characteristics and boundaries.
- Soil Survey Division Staff. 1993. Soil survey manual. Soil Conservation Service. U.S. Department of Agriculture Handbook 18. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_054262
- Soil Survey Staff. 1999. Soil taxonomy: A basic system of soil classification for making and interpreting soil surveys. 2nd edition. Natural Resources Conservation Service, U.S. Department of Agriculture Handbook 436. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053577
- Soil Survey Staff. 2010. Keys to soil taxonomy. 11th edition. U.S. Department of Agriculture, Natural Resources Conservation Service. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053580
- Tiner, R.W., Jr. 1985. Wetlands of Delaware. U.S. Fish and Wildlife Service and Delaware Department of Natural Resources and Environmental Control, Wetlands Section.
- United States Army Corps of Engineers, Environmental Laboratory. 1987. Corps of Engineers wetlands delineation manual. Waterways Experiment Station Technical Report Y-87-1.
- United States Department of Agriculture, Natural Resources Conservation Service. National forestry manual. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/home/?cid=nrcs142p2_053374
- United States Department of Agriculture, Natural Resources Conservation Service. National range and pasture handbook. <http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/landuse/rangepasture/?cid=stelprdb1043084>

Custom Soil Resource Report

United States Department of Agriculture, Natural Resources Conservation Service. National soil survey handbook, title 430-VI. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/scientists/?cid=nrcs142p2_054242

United States Department of Agriculture, Natural Resources Conservation Service. 2006. Land resource regions and major land resource areas of the United States, the Caribbean, and the Pacific Basin. U.S. Department of Agriculture Handbook 296. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053624

United States Department of Agriculture, Soil Conservation Service. 1961. Land capability classification. U.S. Department of Agriculture Handbook 210. http://www.nrcs.usda.gov/Internet/FSE_DOCUMENTS/nrcs142p2_052290.pdf

FEMA FLOOD PLAIN MAP

FIGURE 2

HYDROLOGIC CALCULATIONS

TABLES 1-4, EXHIBIT 2

Table 1 - Existing Weighted C Calculations				
Drainage Area	Cover Type	C _s Value	Area (AC)	CxA
EX-1	Pasture/Meadow	0.08	10.72	0.86
Weighted C: $(CxA)_{tot}/A_{tot}$				0.08
Drainage Area	Cover Type	C _s Value	Area (AC)	CxA
EX-2	Pasture/Meadow	0.08	1.39	0.11
Weighted C: $(CxA)_{tot}/A_{tot}$				0.08
Drainage Area	Cover Type	C _s Value	Area (AC)	CxA
EX-3	Pasture/Meadow	0.08	8.88	0.71
	Gravel	0.59	0.56	0.33
Weighted C: $(CxA)_{tot}/A_{tot}$				0.11
Drainage Area	Cover Type	C _s Value	Area (AC)	CxA
EX-4	Pasture/Meadow	0.08	4.93	0.39
	Gravel	0.59	0.22	0.13
	Paved	0.90	0.07	0.06
	Building	0.73	0.16	0.12
Weighted C: $(CxA)_{tot}/A_{tot}$				0.13
Drainage Area	Cover Type	C _s Value	Area (AC)	CxA
OS1	Pasture/Meadow	0.08	23.42	1.87
Weighted C: $(CxA)_{tot}/A_{tot}$				0.08
Drainage Area	Cover Type	C _s Value	Area (AC)	CxA
OS2	Pasture/Meadow	0.08	114.68	9.17
Weighted C: $(CxA)_{tot}/A_{tot}$				0.08
Drainage Area	Cover Type	C ₁₀₀ Value	Area (AC)	CxA
EX-1	Pasture/Meadow	0.35	10.72	3.75
Weighted C: $(CxA)_{tot}/A_{tot}$				0.35
Drainage Area	Cover Type	C ₁₀₀ Value	Area (AC)	CxA
EX-2	Pasture/Meadow	0.35	1.39	0.49
Weighted C: $(CxA)_{tot}/A_{tot}$				0.35
Drainage Area	Cover Type	C ₁₀₀ Value	Area (AC)	CxA
EX-3	Pasture/Meadow	0.35	8.88	3.11
	Gravel	0.70	0.56	0.39
Weighted C: $(CxA)_{tot}/A_{tot}$				0.37
Drainage Area	Cover Type	C ₁₀₀ Value	Area (AC)	CxA
EX-4	Pasture/Meadow	0.35	4.93	1.73
	Gravel	0.70	0.22	0.15
	Paved	0.96	0.07	0.07
	Building	0.81	0.16	0.13
Weighted C: $(CxA)_{tot}/A_{tot}$				0.39
Drainage Area	Cover Type	C ₁₀₀ Value	Area (AC)	CxA
OS1	Pasture/Meadow	0.35	23.42	8.20
Weighted C: $(CxA)_{tot}/A_{tot}$				0.35
Drainage Area	Cover Type	C ₁₀₀ Value	Area (AC)	CxA
OS2	Pasture/Meadow	0.35	114.68	40.14
Weighted C: $(CxA)_{tot}/A_{tot}$				0.35

Table 2 - Proposed Weighted C Calculations				
Drainage Area	Cover Type	C ₅ Value	Area (AC)	CxA
P-1	Pasture/Meadow	0.08	10.54	0.84
	Building	0.73	0.16	0.12
	Gravel	0.59	0.02	0.01
Weighted C: (CxA) _{tot} /A _{tot}				0.09
Drainage Area	Cover Type	C ₅ Value	Area (AC)	CxA
P-2	Pasture/Meadow	0.08	1.37	0.11
	Gravel	0.59	0.01	0.01
Weighted C: (CxA) _{tot} /A _{tot}				0.08
Drainage Area	Cover Type	C ₅ Value	Area (AC)	CxA
P-3	Pasture/Meadow	0.08	8.57	0.69
	Gravel	0.59	0.88	0.52
Weighted C: (CxA) _{tot} /A _{tot}				0.13
Drainage Area	Cover Type	C ₅ Value	Area (AC)	CxA
P-4	Pasture/Meadow	0.08	4.93	0.39
	Gravel	0.59	0.22	0.13
	Paved	0.90	0.07	0.06
	Building	0.73	0.16	0.12
Weighted C: (CxA) _{tot} /A _{tot}				0.13
Drainage Area	Cover Type	C ₅ Value	Area (AC)	CxA
OS1	Pasture/Meadow	0.08	23.42	1.87
Weighted C: (CxA) _{tot} /A _{tot}				0.08
Drainage Area	Cover Type	C ₅ Value	Area (AC)	CxA
OS2	Pasture/Meadow	0.08	114.68	9.17
Weighted C: (CxA) _{tot} /A _{tot}				0.08
Drainage Area	Cover Type	C ₁₀₀ Value	Area (AC)	CxA
P-1	Pasture/Meadow	0.35	10.54	3.69
	Building	0.81	0.16	0.13
	Gravel	0.70	0.02	0.01
Weighted C: (CxA) _{tot} /A _{tot}				0.36
Drainage Area	Cover Type	C ₁₀₀ Value	Area (AC)	CxA
P-2	Pasture/Meadow	0.35	1.37	0.48
	Gravel	0.70	0.01	0.01
Weighted C: (CxA) _{tot} /A _{tot}				0.35
Drainage Area	Cover Type	C ₁₀₀ Value	Area (AC)	CxA
P-3	Pasture/Meadow	0.35	8.57	3.00
	Gravel	0.70	0.88	0.62
Weighted C: (CxA) _{tot} /A _{tot}				0.38
Drainage Area	Cover Type	C ₅ Value	Area (AC)	CxA
P-4	Pasture/Meadow	0.35	4.93	1.73
	Gravel	0.70	0.22	0.15
	Paved	0.96	0.07	0.07
	Building	0.81	0.16	0.13
Weighted C: (CxA) _{tot} /A _{tot}				0.39
Drainage Area	Cover Type	C ₁₀₀ Value	Area (AC)	CxA
OS1	Pasture/Meadow	0.35	23.42	8.20
Weighted C: (CxA) _{tot} /A _{tot}				0.35
Drainage Area	Cover Type	C ₁₀₀ Value	Area (AC)	CxA
OS2	Pasture/Meadow	0.35	114.68	40.14
Weighted C: (CxA) _{tot} /A _{tot}				0.35

Table 3 - Calculation of Time of Concentration - Pre-Development

Drainage Area	SF	Acreage	C5	C100	Longest Flow Path (ft)	High Elev.	Low Elev.	Average Slope	Unconcentrated Flow Time	Channel Travel Time From Equation 6-9	Time of Concentration (Minutes)
EX-1	467130.16	10.72	0.08	0.35	2100	7489.40	7406.66	3.94%	27.86	20.58	48
EX-2	60446.35	1.39	0.08	0.35	2481	7494.47	7366.14	5.17%	23.11	22.13	45
EX-3	411548.97	9.45	0.11	0.37	3289	7489.40	7359.38	3.95%	27.91	34.70	63
EX-4	234134.60	5.37	0.13	0.39	2944	7482.81	7359.38	4.19%	20.81	30.35	51
OS1	1020065.96	23.42	0.08	0.35	3079	7514.85	7406.66	3.51%	28.76	32.30	61
OS2	4995571.60	114.68	0.08	0.35	5617	7545.00	7359.38	3.30%	19.24	28.92	48

Table 4 - Calculation of Time of Concentration - Post-Development

Drainage Area	SF	Acreage	C5	C100	Longest Flow Path (ft)	High Elev.	Low Elev.	Average Slope	Unconcentrated Flow Time	Channel Travel Time From Equation 6-9	Time of Concentration (Minutes)
P-1	467130.16	10.72	0.09	0.36	2100	7489.40	7406.66	3.94%	27.57	20.58	48
P-2	60446.35	1.39	0.08	0.35	2481	7494.47	7366.14	5.17%	23.03	22.13	45
P-3	411548.97	9.45	0.13	0.38	3289	7489.40	7359.38	3.95%	27.43	34.70	62
P-4	234134.60	5.37	0.13	0.39	2944	7482.81	7359.38	4.19%	20.81	30.35	51
OS1	1020065.96	23.42	0.08	0.35	3079	7514.85	7406.66	3.51%	28.76	32.30	61
OS2	4995571.60	114.68	0.08	0.35	5617	7545.00	7359.38	3.30%	19.24	28.92	48

Hydrograph Summary Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2022

Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description
1	Rational	1.770	1	48	5,098	-----	-----	-----	EX-1 (5-Year)
2	Rational	0.238	1	45	643	-----	-----	-----	EX-2 (5-Year)
3	Rational	1.828	1	63	6,909	-----	-----	-----	EX-3 (5-Year)
4	Rational	1.391	1	51	4,256	-----	-----	-----	EX-4 (5-Year)
5	Rational	3.358	1	61	12,291	-----	-----	-----	OS1 (5-Year)
6	Rational	18.94	1	48	54,540	-----	-----	-----	OS2 (5-Year)
7	Rational	1.992	1	48	5,736	-----	-----	-----	P-1 (5-Year)
8	Rational	0.238	1	45	643	-----	-----	-----	P-2 (5-Year)
9	Rational	2.181	1	62	8,112	-----	-----	-----	P-3 (5-Year)
10	Rational	1.391	1	51	4,256	-----	-----	-----	P-4 (5-Year)
18885 Brown Road - 5-Year.gpw					Return Period: 5 Year			Friday, 08 / 19 / 2022	

Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2022

Friday, 08 / 19 / 2022

Hyd. No. 1

EX-1 (5-Year)

Hydrograph type	= Rational	Peak discharge	= 1.770 cfs
Storm frequency	= 5 yrs	Time to peak	= 0.80 hrs
Time interval	= 1 min	Hyd. volume	= 5,098 cuft
Drainage area	= 10.720 ac	Runoff coeff.	= 0.08
Intensity	= 2.064 in/hr	Tc by User	= 48.00 min
IDF Curve	= Colorado Springs.IDF	Asc/Rec limb fact	= 1/1



Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2022

Friday, 08 / 19 / 2022

Hyd. No. 2

EX-2 (5-Year)

Hydrograph type	= Rational	Peak discharge	= 0.238 cfs
Storm frequency	= 5 yrs	Time to peak	= 0.75 hrs
Time interval	= 1 min	Hyd. volume	= 643 cuft
Drainage area	= 1.390 ac	Runoff coeff.	= 0.08
Intensity	= 2.143 in/hr	Tc by User	= 45.00 min
IDF Curve	= Colorado Springs.IDF	Asc/Rec limb fact	= 1/1




Hydrograph Report

Hyd. No. 3

EX-3 (5-Year)

Hydrograph type	= Rational	Peak discharge	= 1.828 cfs
Storm frequency	= 5 yrs	Time to peak	= 1.05 hrs
Time interval	= 1 min	Hyd. volume	= 6,909 cuft
Drainage area	= 9.450 ac	Runoff coeff.	= 0.11
Intensity	= 1.758 in/hr	Tc by User	= 63.00 min
IDF Curve	= Colorado Springs.IDF	Asc/Rec limb fact	= 1/1



Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2022

Friday, 08 / 19 / 2022

Hyd. No. 4

EX-4 (5-Year)

Hydrograph type	= Rational	Peak discharge	= 1.391 cfs
Storm frequency	= 5 yrs	Time to peak	= 0.85 hrs
Time interval	= 1 min	Hyd. volume	= 4,256 cuft
Drainage area	= 5.370 ac	Runoff coeff.	= 0.13
Intensity	= 1.992 in/hr	Tc by User	= 51.00 min
IDF Curve	= Colorado Springs.IDF	Asc/Rec limb fact	= 1/1



Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2022

Friday, 08 / 19 / 2022

Hyd. No. 5

OS1 (5-Year)

Hydrograph type	= Rational	Peak discharge	= 3.358 cfs
Storm frequency	= 5 yrs	Time to peak	= 1.02 hrs
Time interval	= 1 min	Hyd. volume	= 12,291 cuft
Drainage area	= 23.420 ac	Runoff coeff.	= 0.08
Intensity	= 1.792 in/hr	Tc by User	= 61.00 min
IDF Curve	= Colorado Springs.IDF	Asc/Rec limb fact	= 1/1



Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2022

Friday, 08 / 19 / 2022

Hyd. No. 6

OS2 (5-Year)

Hydrograph type	= Rational	Peak discharge	= 18.94 cfs
Storm frequency	= 5 yrs	Time to peak	= 0.80 hrs
Time interval	= 1 min	Hyd. volume	= 54,540 cuft
Drainage area	= 114.680 ac	Runoff coeff.	= 0.08
Intensity	= 2.064 in/hr	Tc by User	= 48.00 min
IDF Curve	= Colorado Springs.IDF	Asc/Rec limb fact	= 1/1




Hydrograph Report

Hyd. No. 7

P-1 (5-Year)

Hydrograph type	= Rational	Peak discharge	= 1.992 cfs
Storm frequency	= 5 yrs	Time to peak	= 0.80 hrs
Time interval	= 1 min	Hyd. volume	= 5,736 cuft
Drainage area	= 10.720 ac	Runoff coeff.	= 0.09
Intensity	= 2.064 in/hr	Tc by User	= 48.00 min
IDF Curve	= Colorado Springs.IDF	Asc/Rec limb fact	= 1/1



Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2022

Friday, 08 / 19 / 2022

Hyd. No. 8

P-2 (5-Year)

Hydrograph type	= Rational	Peak discharge	= 0.238 cfs
Storm frequency	= 5 yrs	Time to peak	= 0.75 hrs
Time interval	= 1 min	Hyd. volume	= 643 cuft
Drainage area	= 1.390 ac	Runoff coeff.	= 0.08
Intensity	= 2.143 in/hr	Tc by User	= 45.00 min
IDF Curve	= Colorado Springs.IDF	Asc/Rec limb fact	= 1/1




Hydrograph Report

Hyd. No. 9

P-3 (5-Year)

Hydrograph type	= Rational	Peak discharge	= 2.181 cfs
Storm frequency	= 5 yrs	Time to peak	= 1.03 hrs
Time interval	= 1 min	Hyd. volume	= 8,112 cuft
Drainage area	= 9.450 ac	Runoff coeff.	= 0.13
Intensity	= 1.775 in/hr	Tc by User	= 62.00 min
IDF Curve	= Colorado Springs.IDF	Asc/Rec limb fact	= 1/1



Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2022

Friday, 08 / 19 / 2022

Hyd. No. 10

P-4 (5-Year)

Hydrograph type	= Rational	Peak discharge	= 1.391 cfs
Storm frequency	= 5 yrs	Time to peak	= 0.85 hrs
Time interval	= 1 min	Hyd. volume	= 4,256 cuft
Drainage area	= 5.370 ac	Runoff coeff.	= 0.13
Intensity	= 1.992 in/hr	Tc by User	= 51.00 min
IDF Curve	= Colorado Springs.IDF	Asc/Rec limb fact	= 1/1



Hydrograph Summary Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2022

Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description
1	Rational	14.79	1	48	42,589	-----	-----	-----	EX-1 (100-Year)
2	Rational	1.987	1	45	5,365	-----	-----	-----	EX-2 (100-Year)
3	Rational	11.83	1	63	44,703	-----	-----	-----	EX-3 (100-Year)
4	Rational	7.996	1	51	24,468	-----	-----	-----	EX-4 (100-Year)
5	Rational	28.26	1	61	103,439	-----	-----	-----	OS1
6	Rational	158.20	1	48	455,609	-----	-----	-----	OS2
7	Rational	15.21	1	48	43,806	-----	-----	-----	P-1 (100-Year)
8	Rational	1.973	1	45	5,327	-----	-----	-----	P-2 (100-Year)
9	Rational	12.27	1	62	45,639	-----	-----	-----	P-3 (100-Year)
10	Rational	7.996	1	51	24,468	-----	-----	-----	P-4 (100-Year)
18885 Brown Road - 100-Year.gpw					Return Period: 100 Year			Friday, 08 / 19 / 2022	

Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2022

Friday, 08 / 19 / 2022

Hyd. No. 1

EX-1 (100-Year)

Hydrograph type	= Rational	Peak discharge	= 14.79 cfs
Storm frequency	= 100 yrs	Time to peak	= 0.80 hrs
Time interval	= 1 min	Hyd. volume	= 42,589 cuft
Drainage area	= 10.720 ac	Runoff coeff.	= 0.35
Intensity	= 3.941 in/hr	Tc by User	= 48.00 min
IDF Curve	= Colorado Springs.IDF	Asc/Rec limb fact	= 1/1



Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2022

Friday, 08 / 19 / 2022

Hyd. No. 2

EX-2 (100-Year)

Hydrograph type	= Rational	Peak discharge	= 1.987 cfs
Storm frequency	= 100 yrs	Time to peak	= 0.75 hrs
Time interval	= 1 min	Hyd. volume	= 5,365 cuft
Drainage area	= 1.390 ac	Runoff coeff.	= 0.35
Intensity	= 4.085 in/hr	Tc by User	= 45.00 min
IDF Curve	= Colorado Springs.IDF	Asc/Rec limb fact	= 1/1




Hydrograph Report

Hyd. No. 3

EX-3 (100-Year)

Hydrograph type	= Rational	Peak discharge	= 11.83 cfs
Storm frequency	= 100 yrs	Time to peak	= 1.05 hrs
Time interval	= 1 min	Hyd. volume	= 44,703 cuft
Drainage area	= 9.440 ac	Runoff coeff.	= 0.37
Intensity	= 3.386 in/hr	Tc by User	= 63.00 min
IDF Curve	= Colorado Springs.IDF	Asc/Rec limb fact	= 1/1



Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2022

Friday, 08 / 19 / 2022

Hyd. No. 4

EX-4 (100-Year)

Hydrograph type	= Rational	Peak discharge	= 7.996 cfs
Storm frequency	= 100 yrs	Time to peak	= 0.85 hrs
Time interval	= 1 min	Hyd. volume	= 24,468 cuft
Drainage area	= 5.380 ac	Runoff coeff.	= 0.39
Intensity	= 3.811 in/hr	Tc by User	= 51.00 min
IDF Curve	= Colorado Springs.IDF	Asc/Rec limb fact	= 1/1




Hydrograph Report

Hyd. No. 5

OS1

Hydrograph type	= Rational	Peak discharge	= 28.26 cfs
Storm frequency	= 100 yrs	Time to peak	= 1.02 hrs
Time interval	= 1 min	Hyd. volume	= 103,439 cuft
Drainage area	= 23.420 ac	Runoff coeff.	= 0.35
Intensity	= 3.448 in/hr	Tc by User	= 61.00 min
IDF Curve	= Colorado Springs.IDF	Asc/Rec limb fact	= 1/1



Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2022

Friday, 08 / 19 / 2022

Hyd. No. 6

OS2

Hydrograph type	= Rational	Peak discharge	= 158.20 cfs
Storm frequency	= 100 yrs	Time to peak	= 0.80 hrs
Time interval	= 1 min	Hyd. volume	= 455,609 cuft
Drainage area	= 114.680 ac	Runoff coeff.	= 0.35
Intensity	= 3.941 in/hr	Tc by User	= 48.00 min
IDF Curve	= Colorado Springs.IDF	Asc/Rec limb fact	= 1/1



Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2022

Friday, 08 / 19 / 2022

Hyd. No. 7

P-1 (100-Year)

Hydrograph type	= Rational	Peak discharge	= 15.21 cfs
Storm frequency	= 100 yrs	Time to peak	= 0.80 hrs
Time interval	= 1 min	Hyd. volume	= 43,806 cuft
Drainage area	= 10.720 ac	Runoff coeff.	= 0.36
Intensity	= 3.941 in/hr	Tc by User	= 48.00 min
IDF Curve	= Colorado Springs.IDF	Asc/Rec limb fact	= 1/1




Hydrograph Report

Hyd. No. 8

P-2 (100-Year)

Hydrograph type	= Rational	Peak discharge	= 1.973 cfs
Storm frequency	= 100 yrs	Time to peak	= 0.75 hrs
Time interval	= 1 min	Hyd. volume	= 5,327 cuft
Drainage area	= 1.380 ac	Runoff coeff.	= 0.35
Intensity	= 4.085 in/hr	Tc by User	= 45.00 min
IDF Curve	= Colorado Springs.IDF	Asc/Rec limb fact	= 1/1




Hydrograph Report

Hyd. No. 9

P-3 (100-Year)

Hydrograph type	= Rational	Peak discharge	= 12.27 cfs
Storm frequency	= 100 yrs	Time to peak	= 1.03 hrs
Time interval	= 1 min	Hyd. volume	= 45,639 cuft
Drainage area	= 9.450 ac	Runoff coeff.	= 0.38
Intensity	= 3.416 in/hr	Tc by User	= 62.00 min
IDF Curve	= Colorado Springs.IDF	Asc/Rec limb fact	= 1/1




Hydrograph Report

Hyd. No. 10

P-4 (100-Year)


Hydrograph type	= Rational	Peak discharge	= 7.996 cfs
Storm frequency	= 100 yrs	Time to peak	= 0.85 hrs
Time interval	= 1 min	Hyd. volume	= 24,468 cuft
Drainage area	= 5.380 ac	Runoff coeff.	= 0.39
Intensity	= 3.811 in/hr	Tc by User	= 51.00 min
IDF Curve	= Colorado Springs.IDF	Asc/Rec limb fact	= 1/1




DRAINAGE MAPS

FIGURES 3 & 4

LEGEND



PRE-DEVELOPMENT DRAINAGE MAP TABLE						
DRAINAGE AREA ID	AREA (ACRE)	C5	C100	TIME OF CONCENTRATION (TC)	Q5 (CFS)	Q100 (CFS)
EX-1	10.72	0.08	0.35	48	1.77	14.79
EX-2	1.39	0.08	0.35	45	0.24	1.99
EX-3	9.45	0.11	0.37	63	1.83	11.83
EX-4	5.38	0.13	0.39	51	1.39	8.00
OS1	23.42	0.08	0.35	61	3.36	28.26
OS2	114.68	0.08	0.35	48	18.94	158.20



OWL RIDGE SUBDIVISION


DRAINAGE STUDY

EL PASO COUNTY, COLORADO

REVISION DESCRIPTION
(DESCRIPTION)

REVISION DATE
0000000

NORTH



PROJECT #: 2010CS4031
CHECKED BY: BML
DRAWN BY: JMT

DATE: 08/19/2022


SHEET #

FIG. 3


TOTAL SHEETS

PRE-DEVELOPMENT DRAINAGE MAP

LEGEND



POST-DEVELOPMENT DRAINAGE MAP TABLE						
DRAINAGE AREA ID	AREA (ACRE)	C5	C100	TIME OF CONCENTRATION (TC)	Q5 (CFS)	Q100 (CFS)
P-1	10.72	0.09	0.36	48	1.99	15.21
P-2	1.39	0.08	0.35	45	0.24	1.97
P-3	9.45	0.13	0.38	62	2.18	12.27
P-4	5.38	0.13	0.39	51	1.39	8.00
OS1	23.42	0.08	0.35	61	3.36	28.26
OS2	114.68	0.08	0.35	48	18.94	158.20



OWL RIDGE SUBDIVISION

DRAINAGE STUDY


EL PASO COUNTY, COLORADO

REVISION DESCRIPTION
(DESCRIPTION)

REVISION DATE

0000000

NORTH



250' 125' 0' 250'
SCALE: 1" = 250'

PROJECT #: 2010CS4031
CHECKED BY: BML
DRAWN BY: JMT

DATE: 08/19/2022

SHEET #

FIG. 4

TOTAL SHEETS

POST DEVELOPMENT DRAINAGE MAP