

LEGAL DESCRIPTION

BEING A PART OF THE SOUTH ONE HALF OF THE NORTHEAST ONE-QUARTER (S 1/2 NE 1/4) OF SECTION 1, TOWNSHIP 13 SOUTH, RANGE 65 WEST OF THE 6TH PRINCIPAL MERIDIAN, COUNTY OF EL PASO, STATE OF COLORADO, MORE FULLY DESCRIBED AS FOLLOWS:

BASIS OF BEARINGS: BEARINGS ARE BASED ON THE WESTERLY BOUNDARY LINE OF SUBJECT PARCEL, COINCIDENT WITH THE EASTERLY LINE OF THE BENT GRASS RESIDENTIAL FILING NO.2 BY RECEPTION NO. 220714559, MONUMENTED ON THE NORTH END WITH A FOUND NO.5 REBAR WITH 1-3/8" RED PLASTIC CAP, "ALC PLS 38087", FLUSH WITH GRADE, AND ON THE SOUTH END WITH A NO.4 REBAR WITH 1" ORANGE PLASTIC CAP MARKED "PLS 38141", RECOVERED 0.6' BELOW GRADE, SAID LINE TO BEAR NORTH 00°08'14" EAST, A MEASURED DISTANCE OF 619.52 FEET.

COMMENCING AT THE CENTER NORTH 1/16 CORNER, SEC. 1 T.1S. R.65W. BEING A FOUND NUMBER 6 REBAR WITH 3-1/4" ALUMINUM CAP MARKED "N 1/16 S1 2019, PLS 38069", 1.4' ABOVE GRADE; THENCE SOUTH 89°41'32" EAST ALONG THE NORTHERLY BOUNDARY OF THE BENT GRASS RESIDENTIAL FILING NO.2 BY RECEPTION NO. 220714559, COINCIDENT WITH THE SOUTHERLY BOUNDARY OF A PORTION OF WOODMEN HILLS FILING NO. 3 BY RECEPTION NO. 97059838, A DISTANCE OF 28.26 FEET TO A NO.5 REBAR WITH 1-3/8" RED PLASTIC CAP, "ALC PLS 38087", FLUSH WITH GRADE, BEING THE **POINT OF BEGINNING:** OF THE HEREINAFTER DESCRIBED LANDS;

THENCE NORTH 89°54'26" WEST ALONG THE NORTHERLY BOUNDARY OF SUBJECT PARCEL COINCIDENT OF SOUTHERLY BOUNDARY OF A PORTION OF WOODMEN HILLS FILING NO. 3 BY RECEPTION NO. 97059838, A DISTANCE OF 631.24 FEET TO A NO. 5 REBAR WITH A 1-1/4' PURPLE PLASTIC CAP, PLS 38759, FLUSH WITH GRADE;

THENCE SOUTH 00°09'43" WEST, ALONG THE EASTERLY LINE OF SUBJECT PARCEL, COINCIDENT WITH THE WESTERLY BOUNDARY LINE OF UNPLATTED LANDS PER QUIT CLAIM DEED BY RECEPTION NO. 208133006, A DISTANCE OF 619.92 FEET TO A NO. 5 REBAR WITH A 1-1/4' PURPLE PLASTIC CAP, PLS 38759, FLUSH WITH GRADE;

THENCE NORTH 89°52'36" WEST ALONG THE SOUTHERLY LINE OF SUBJECT PARCEL, COINCIDENT WITH A PORTION OF THE NORTHERLY RIGHT OF WAY LINE OF GRASS MEADOWS DRIVE, A DISTANCE OF 630.97 FEET TO A NO.4 REBAR WITH 1" ORANGE PLASTIC CAP MARKED "PLS 38141", RECOVERED 0.6' BELOW GRADE;

THENCE NORTH 00°08'14" EAST, ALONG THE WESTERLY LINE OF SUBJECT PARCEL, COINCIDENT WITH THE EASTERLY LINE OF THE BENT GRASS RESIDENTIAL FILING NO.2 BY RECEPTION NO. 220714559, A MEASURED DISTANCE OF 619.52 FEET TO THE **POINT OF BEGINNING.**

SAID LANDS CONTAINING 391,129 SQUARE FEET (8.98 ACRES) OF LAND, MORE OR LESS.