

2026 Financial Assurance Estimate Form (with pre-plat construction)

Updated: 2/2026

PROJECT INFORMATION			
Project Name: Trails at Aspen Ridge Filing 5	Date: 8/17/2026	PCD File No.	SF2618

Description	Quantity	Units	Unit Cost		Total	(with Pre-Plat Construction) % Complete	Remaining
SECTION 1 - GRADING AND EROSION CONTROL (Construction and Permanent BMPs)							
Earthwork							
less than 5,000; \$8,000 min		CY	\$ 7.50	=	\$ -		\$ -
5,001-20,000; \$30,000 min		CY	\$ 6.50	=	\$ -		\$ -
20,001-50,000; \$100,000 min		CY	\$ 4.50	=	\$ -		\$ -
50,001-200,000; \$175,000 min	93783.	CY	\$ 3.00	=	\$ 281,349.00		\$ 281,349.00
greater than 200,000; \$500,000 min		CY	\$ 2.50	=	\$ -		\$ -
Erosion Control Blanket	5572.	SY	\$ 6.00	=	\$ 33,432.00		\$ 33,432.00
Seeding (inc. noxious weed mgmnt.) & Mulching	10.	AC	\$ 2,037.00	=	\$ 20,370.00		\$ 20,370.00
Permanent Pond/PCM (provide engineer's estimate)		EA		=	\$ -		\$ -
				=	\$ -		\$ -
				=	\$ -		\$ -
[insert items not listed but part of construction plans]				=	\$ -		\$ -
Safety Fence		LF	\$ 5.00	=	\$ -		\$ -
Inlet Protection	2.	EA	\$ 322.00	=	\$ 644.00		\$ 644.00
Rock Check Dam		EA	\$ 908.00	=	\$ -		\$ -
Concrete Washout Basin	1.	EA	\$ 1,790.00	=	\$ 1,790.00		\$ 1,790.00
Sediment Basin		EA	\$ 3,483.00	=	\$ -		\$ -
Sediment Trap		EA	\$ 877.00	=	\$ -		\$ -
Silt Fence	1758.	LF	\$ 3.00	=	\$ 5,274.00		\$ 5,274.00
Slope Drain		LF	\$ 30.00	=	\$ -		\$ -
Straw Bale		EA	\$ 56.00	=	\$ -		\$ -
Straw Wattle/Rock Sock	2896.	LF	\$ 11.00	=	\$ 31,856.00		\$ 31,856.00
Surface Roughening		AC	\$ 507.00	=	\$ -		\$ -
Vehicle Tracking Control	2.	EA	\$ 3,840.00	=	\$ 7,680.00		\$ 7,680.00
				=	\$ -		\$ -
				=	\$ -		\$ -
				=	\$ -		\$ -
[insert items not listed but part of construction plans]				=	\$ -		\$ -
MAINTENANCE (35% of Construction BMPs)					=	\$ 16,535.40	\$ 16,535.40
Section 1 Subtotal					=	\$ 398,930.40	\$ 398,930.40
SECTION 2 - PUBLIC IMPROVEMENTS *							
ROADWAY IMPROVEMENTS							
Construction Traffic Control		LS		=	\$ -		\$ -
Aggregate Base Course (135 lbs/cf)		Tons	\$ 42.00	=	\$ -		\$ -
Aggregate Base Course (135 lbs/cf)	3294.	CY	\$ 81.00	=	\$ 266,814.00		\$ 266,814.00
Asphalt Pavement (3" thick)		SY	\$ 22.00	=	\$ -		\$ -
Asphalt Pavement (4" thick)	4942.	SY	\$ 31.00	=	\$ 153,202.00		\$ 153,202.00
Asphalt Pavement (6" thick)		SY	\$ 47.00	=	\$ -		\$ -
Asphalt Pavement (147 lbs/cf) ___" thick		Tons	\$ 140.00	=	\$ -		\$ -
Raised Median, Paved		SF	\$ 15.00	=	\$ -		\$ -
Signs (regulatory/advisory/guide/street)	4.	EA	\$ 293.00	=	\$ 1,172.00		\$ 1,172.00
Epoxy Pavement Marking		SF	\$ 19.00	=	\$ -		\$ -
Thermoplastic Pavement Marking		SF	\$ 29.00	=	\$ -		\$ -
Barricade - Type 3	1.	EA	\$ 380.00	=	\$ 380.00		\$ 380.00
Delineator - Type I		EA	\$ 38.00	=	\$ -		\$ -
Curb and Gutter, Type A (6" Vertical)	455.	LF	\$ 49.00	=	\$ 22,295.00		\$ 22,295.00
Curb and Gutter, Type B (Median)		LF	\$ 50.00	=	\$ -		\$ -
Curb and Gutter, Type C (Ramp)	1935.	LF	\$ 51.00	=	\$ 98,685.00		\$ 98,685.00
4" Sidewalk (common areas)		SY	\$ 69.00	=	\$ -		\$ -
5" Sidewalk		SY	\$ 85.00	=	\$ -		\$ -
6" Sidewalk		SY	\$ 113.00	=	\$ -		\$ -
8" Sidewalk		SY	\$ 141.00	=	\$ -		\$ -
Pedestrian Ramp		EA	\$ 1,961.00	=	\$ -		\$ -
Cross Pan, local (8" thick, 6'	35.	LF	\$ 87.00	=	\$ 3,045.00		\$ 3,045.00
Cross Pan, collector (9" thick)		LF	\$ 131.00	=	\$ -		\$ -
Curb Opening with Drainage		EA	\$ 2,341.00	=	\$ -		\$ -
Guardrail Type 3 (W-Beam)		LF	\$ 87.00	=	\$ -		\$ -
Guardrail Type 7 (Concrete)		LF	\$ 104.00	=	\$ -		\$ -
Guardrail End Anchorage		EA	\$ 2,485.00	=	\$ -		\$ -
Guardrail Impact Attenuator		EA	\$ 22,568.00	=	\$ -		\$ -
Sound Barrier Fence (CMU block, 6' high)		LF	\$ 113.00	=	\$ -		\$ -
Sound Barrier Fence (panels, 6' high)		LF	\$ 115.00	=	\$ -		\$ -
Electrical Conduit, Size =		LF	\$ 33.00	=	\$ -		\$ -
Traffic Signal, (provide engineer's estimate)		EA		=	\$ -		\$ -
Survey Monumentation		EA	\$ 638.00	=	\$ -		\$ -
				=	\$ -		\$ -

Please include exhibit showing what sidewalk is being built as common area vs. privately. Include a copy of that sheet in CDs so contractor will know what sidewalk they will need to build

PROJECT INFORMATION							
Project Name: Trails at Aspen Ridge Filing 5			Date: 8/17/2026			PCD File No.	
Description	Quantity	Units	Unit Cost		Total	(with Pre-Plat Construction)	
						% Complete	Remaining
				=	\$ -		\$ - *
				=	\$ -		\$ - *
<i>[insert items not listed but part of construction plans]</i>				=	\$ -		\$ - *
STORM DRAIN IMPROVEMENTS							
Concrete Box Culvert (M Standard), Size (W x H)		LF		=	\$ -		\$ - *
18" Reinforced Concrete Pipe		LF	\$ 111.00	=	\$ -		\$ - *
24" Reinforced Concrete Pipe		LF	\$ 161.00	=	\$ -		\$ - *
30" Reinforced Concrete Pipe		LF	\$ 167.00	=	\$ -		\$ - *
36" Reinforced Concrete Pipe		LF	\$ 191.00	=	\$ -		\$ - *
42" Reinforced Concrete Pipe		LF	\$ 275.00	=	\$ -		\$ - *
48" Reinforced Concrete Pipe		LF	\$ 349.00	=	\$ -		\$ - *
54" Reinforced Concrete Pipe		LF	\$ 465.00	=	\$ -		\$ - *
60" Reinforced Concrete Pipe		LF	\$ 476.00	=	\$ -		\$ - *
66" Reinforced Concrete Pipe		LF	\$ 550.00	=	\$ -		\$ - *
72" Reinforced Concrete Pipe		LF	\$ 616.00	=	\$ -		\$ - *
18" Corrugated Steel Pipe		LF	\$ 136.00	=	\$ -		\$ - *
24" Corrugated Steel Pipe		LF	\$ 229.00	=	\$ -		\$ - *
30" Corrugated Steel Pipe		LF	\$ 244.00	=	\$ -		\$ - *
36" Corrugated Steel Pipe		LF	\$ 244.00	=	\$ -		\$ - *
42" Corrugated Steel Pipe		LF	\$ 226.00	=	\$ -		\$ - *
48" Corrugated Steel Pipe		LF	\$ 465.00	=	\$ -		\$ - *
54" Corrugated Steel Pipe		LF	\$ 459.00	=	\$ -		\$ - *
60" Corrugated Steel Pipe		LF	\$ 501.00	=	\$ -		\$ - *
66" Corrugated Steel Pipe		LF	\$ 580.00	=	\$ -		\$ - *
72" Corrugated Steel Pipe		LF	\$ 654.00	=	\$ -		\$ - *
78" Corrugated Steel Pipe		LF	\$ 728.00	=	\$ -		\$ - *
84" Corrugated Steel Pipe		LF	\$ 901.00	=	\$ -		\$ - *
Flared End Section (FES) RCP Size = (unit cost = 6x pipe unit cost)		EA		=	\$ -		\$ - *
Flared End Section (FES) CSP Size = (unit cost = 6x pipe unit cost)		EA		=	\$ -		\$ - *
				=	\$ -		\$ - *
<i>[insert items not listed but part of construction plans]</i>				=	\$ -		\$ - *
End Treatment- Headwall		EA		=	\$ -		\$ - *
End Treatment- Wingwall		EA		=	\$ -		\$ - *
End Treatment - Cutoff Wall		EA		=	\$ -		\$ - *
Curb Inlet (Type R) L=5', Depth < 5'		EA	\$ 8,814.00	=	\$ -		\$ - *
Curb Inlet (Type R) L=5', 5' ≤ Depth < 10'		EA	\$ 10,835.00	=	\$ -		\$ - *
Curb Inlet (Type R) L=5', 10' ≤ Depth < 15'		EA	\$ 12,206.00	=	\$ -		\$ - *
Curb Inlet (Type R) L=10', Depth < 5'		EA	\$ 11,438.00	=	\$ -		\$ - *
Curb Inlet (Type R) L=10', 5' ≤ Depth < 10'		EA	\$ 12,689.00	=	\$ -		\$ - *
Curb Inlet (Type R) L=10', 10' ≤ Depth < 15'		EA	\$ 16,174.00	=	\$ -		\$ - *
Curb Inlet (Type R) L=15', Depth < 5'		EA	\$ 14,452.00	=	\$ -		\$ - *
Curb Inlet (Type R) L=15', 5' ≤ Depth < 10'		EA	\$ 17,237.00	=	\$ -		\$ - *
Curb Inlet (Type R) L=15', 10' ≤ Depth < 15'		EA	\$ 21,610.00	=	\$ -		\$ - *
Curb Inlet (Type R) L=20', Depth < 5'		EA	\$ 16,499.00	=	\$ -		\$ - *
Curb Inlet (Type R) L=20', 5' ≤ Depth < 10'		EA	\$ 20,012.00	=	\$ -		\$ - *
Grated Inlet (Type C), Depth < 5'		EA	\$ 8,156.00	=	\$ -		\$ - *
Grated Inlet (Type D), Depth < 5'		EA	\$ 11,435.00	=	\$ -		\$ - *
Storm Sewer Manhole, Box Base		EA	\$ 18,950.00	=	\$ -		\$ - *
Storm Sewer Manhole, Slab Base		EA	\$ 9,314.00	=	\$ -		\$ - *
Geotextile (Erosion Control)		SY	\$ 6.00	=	\$ -		\$ - *
Rip Rap, d50 size from 6" to 24"		Tons	\$ 102.00	=	\$ -		\$ - *
Rip Rap, Grouted		Tons	\$ 136.00	=	\$ -		\$ - *
Drainage Channel Construction, Size (W x H)		LF		=	\$ -		\$ - *
Drainage Channel Lining, Concrete		CY	\$ 815.00	=	\$ -		\$ - *
Drainage Channel Lining, Rip Rap		CY	\$ 234.00	=	\$ -		\$ - *
Drainage Channel Lining, Grass		AC	\$ 2,100.00	=	\$ -		\$ - *
Permanent Drainage Channel Lining or Roadside Ditch TRM		SY	\$ 13.00	=	\$ -		\$ - *
				=	\$ -		\$ - *
				=	\$ -		\$ - *
<i>[insert items not listed but part of construction plans]</i>				=	\$ -		\$ - *
Section 2 Subtotal				=	\$ 545,593.00		\$ 545,593.00 *

* - Subject to defect warranty financial assurance. A minimum of 20% shall be retained until final acceptance (MAXIMUM OF 80% COMPLETE ALLOWED)

PROJECT INFORMATION							
Project Name: Trails at Aspen Ridge Filing 5				Date: 8/17/2026		PCD File No.	
Description	Quantity	Units	Unit Cost		Total	(with Pre-Plat Construction)	
						% Complete	Remaining
SECTION 3 - COMMON DEVELOPMENT IMPROVEMENTS (Private or District and NOT Maintained by EPC)**							
ROADWAY IMPROVEMENTS							
				=	\$ -		\$ -
				=	\$ -		\$ -
				=	\$ -		\$ -
				=	\$ -		\$ -
				=	\$ -		\$ -
				=	\$ -		\$ -
STORM DRAIN IMPROVEMENTS (Exception: Permanent Pond/BMP shall be itemized under Section 1)							
				=	\$ -		\$ -
				=	\$ -		\$ -
				=	\$ -		\$ -
				=	\$ -		\$ -
				=	\$ -		\$ -
				=	\$ -		\$ -
WATER SYSTEM IMPROVEMENTS							
Water Main Pipe (PVC), Size 8"	1113.	LF	\$ 90.00	=	\$ 100,170.00		\$ 100,170.00
Water Main Pipe (Ductile Iron), Size 8"		LF	\$ 105.00	=	\$ -		\$ -
Gate Valves, 8"	6.	EA	\$ 2,599.00	=	\$ 15,594.00		\$ 15,594.00
Fire Hydrant Assembly, w/ all valves	2.	EA	\$ 9,228.00	=	\$ 18,456.00		\$ 18,456.00
Water Service Line Installation, inc. tap and valves	53.	EA	\$ 1,852.00	=	\$ 98,156.00		\$ 98,156.00
Fire Cistern Installation, complete		EA		=	\$ -		\$ -
Water Main Pipe (PVC), Size 12"	1087.	LF	\$ 110.00	=	\$ 119,570.00		\$ 119,570.00
[insert items not listed but part of construction plans]				=	\$ -		\$ -
SANITARY SEWER IMPROVEMENTS							
Sewer Main Pipe (PVC), Size 8"	1313.	LF	\$ 90.00	=	\$ 118,170.00		\$ 118,170.00
Sanitary Sewer Manhole, Depth < 15 feet	4.	EA	\$ 6,136.00	=	\$ 24,544.00		\$ 24,544.00
Sanitary Service Line Installation, complete	53.	EA	\$ 1,962.00	=	\$ 103,986.00		\$ 103,986.00
Sanitary Sewer Lift Station, complete		EA		=	\$ -		\$ -
				=	\$ -		\$ -
[insert items not listed but part of construction plans]				=	\$ -		\$ -
LANDSCAPING IMPROVEMENTS (For subdivision specific condition of approval, or PUD)							
		EA		=	\$ -		\$ -
		EA		=	\$ -		\$ -
		EA		=	\$ -		\$ -
		EA		=	\$ -		\$ -
		EA		=	\$ -		\$ -
** - Section 3 is not subject to defect warranty requirements				Section 3 Subtotal	= \$ 598,646.00		\$ 598,646.00
AS-BUILT PLANS (Public Improvements inc. Permanent WQCV BMPs)		LS		=	\$ -		\$ -
POND/BMP CERTIFICATION (inc. elevations and volume calculations)		LS		=	\$ -		\$ -
Total Construction Financial Assurance						\$ 1,543,169.40	
(Sum of all section subtotals plus as-builts and pond/BMP certification)							
Total Remaining Construction Financial Assurance (with Pre-Plat Construction)						\$ 1,543,169.40	
(Sum of all section totals less credit for items complete plus as-builts and pond/BMP certification)							
Total Defect Warranty Financial Assurance						\$ 176,148.80	
(20% of all items identified as (*). To be collateralized at time of preliminary acceptance)							

add costs for these two items.
Even though a Pond Cert Letter isn't needed, we still need a Public Improvements Cert Letter

Approvals	
I hereby certify that this is an accurate and complete estimate of costs for the work as shown on the Grading and Erosion Control Plan and Construction Drawings associated with the Project.	
_____ Engineer (P.E. Seal Required) _____ Approved by Owner / Applicant _____ Approved by El Paso County Engineer / ECM Administrator _____ Date _____ Date	