

Radiant Floor Zone Plan

Shaun Nelms
7196416595
snelms956@gmail.com

4371 Prairie Ranch View
Peyton CO 80831
Parcel # 3329001002
Legal Description
LOT 2 Prairie View
Estates
FIL NO 1

Notes:

All Equipment will be mounted a minimum of 36" AFF

- ① Well Water Pressure Tank/Electrical Connection/ entrance to building
- ② Radiant Floor Electric Tankless Water Heater
- ③ Potable Water Electric Tankless Water Heater
- ④ Pressure tank, radiant manifold, Air Eliminator, zone pump, temp gauge, pressure gauge, zone controller

Installing 1/2" Oxygen barrier pex piping beneath the concrete slab for 300 ft per run. Total of 6 runs

Installing a plastic drop cloth barrier and 2" foamboard under the slab

