


Remote Mount Detail



ILLUMINATED CHANNEL LETTERS-LOGO

FABRICATED ALUMINUM CHANNEL LETTERS
 RETURNS BRONZE
 FACES ARE 3/16" WHITE ACRYLIC
 WITH TRANSLUCENT VINYL OVERLAY
 1" BRONZE TRIMCAP
 ILLUMINATED WITH WHITE LED
 REMOTE MOUNTED DIRECT TO BUILDING
 U.L. APPROVED

NON-ILLUMINATED PIN MOUNT LETTERS

"ISSUES OF LIFE
 CHURCH MINISTRIES"
 2" THICK ROUTED HDU POLYURETANE SIGN FOAM
 LETTERS PAINTED YELLOW & ORANGE
 STUD MOUNTED DIRECT TO BUILDING

SPECTRUM
 LIGHTING, SIGN & ELECTRICAL
 COMPANY
 (719) 520-5167 FAX (719) 520-5902

Copyright © 2009

This drawing is provided for the purpose of illustrating the proposed project. Unauthorized use, copying, scanning or sharing is strictly prohibited and protected by law.

Electrical hookup by others.
 Electrical requirements: 120V (or as indicated)
 All landscaping by others

This conceptual illustration is designed to provide a view of how the sign might look in its chosen location. Due to variables in digital photography, architectural renderings and unforeseen structural obstacles, the ratio of the finished sign to the area it is installed in may appear slightly different from the illustration. Colors shown are representative of the actual color code chosen. Variables in monitors, printers, inks and paper will alter how these colors appear on the drawing. Please refer to the actual color codes prior to approval.

Customer Information

Business Name: Issues of Life Church Ministry
 Project Name: New sign
 Location Address: 320 Main Street

Customer Approval

Name and Title _____
 Authorization _____ Date _____

