

**MVE, INC.**  
ENGINEERS SURVEYORS

1903 kelaray street, suite 200  
colorado springs, co 80909  
719.635.5736

# Final Drainage Report

**Jackson Ranch  
Filing No. 4**

**April 18, 2017**

Project No. 61073

Add: "PCD Project No. SF-17-016"

# Final Drainage Report

for

**Jackson Ranch Filing No. 4**

**Project No. 61073**

**April 18, 2017**

prepared for

**Four Gates Land Development LLC**

17435 Roller Coaster Road

Monument, CO 80132

719.488.9329

prepared by

**MVE, Inc.**

1903 Lelaray Street, Suite 200

Colorado Springs, CO 80909

719.635.5736

Copyright © MVE, Inc., 2017


*61073 Filing - Final Drainage Report.dwg*

# Statements and Acknowledgments

"master"

## Engineer's Statement

The attached drainage plan and report were prepared under my direction and supervision and are correct to the best of my knowledge and belief. Said drainage report has been prepared according to the criteria established by El Paso County for drainage reports and said report is in conformity with the applicable master plan of the drainage basin. I accept responsibility for any liability caused by any negligent acts, errors or omissions on my part in preparing this report.

  
Charles C. Crum, P.E.  
For and on Behalf of MVE, Inc.


Colorado No. 13348

4-27-17  
Date

## Developer's Statement


I, the developer have read and will comply with all of the requirements specified in this drainage report and plan.

Add title

  
\_\_\_\_\_  
Marlene J. Brown  
Four Gates Land Development, LLC

\_\_\_\_\_  
Date

Address



## El Paso County

Filed in accordance with the requirements of the Drainage Criteria Manual 1 & 2, El Paso County Engineering Manual, and the Land Development Code as amended.

Revise to "Jennifer Irvine, P.E."

  
\_\_\_\_\_  
Jennifer Irvine, County Engineer / ECM Administrator Date  
El Paso County

# Contents

Statements and Acknowledgments.....	iii
Contents.....	v
Final Drainage Report.....	1
<b>1 General Location and Description.....</b>	<b>1</b>
1.1 Location.....	1
1.2 Description of Property.....	1
<b>2 Drainage Basins and Sub-Basins.....</b>	<b>2</b>
2.1 Major Basin Descriptions.....	2
2.2 Sub-Basin Description.....	2
<b>3 Drainage Design Criteria.....</b>	<b>3</b>
3.1 Development Criteria Reference.....	3
3.2 Previous Drainage Studies.....	3
3.3 Hydrologic Criteria.....	3
3.4 Hydraulic Criteria.....	3
<b>4 Drainage Facility Design.....</b>	<b>3</b>
4.1 General Concept.....	3
4.2 Specific Details.....	4
<b>5 Opinion of Probable Cost for Drainage Facilities.....</b>	<b>5</b>
<b>6 Drainage and Bridge Fees.....</b>	<b>5</b>
<b>7 Conclusion.....</b>	<b>5</b>
References.....	7

Appendices.....	8
<b>General Maps and Supporting Data.....</b>	<b>8</b>
<b>Hydrologic Calculations.....</b>	<b>22</b>
<b>Report Maps.....</b>	<b>30</b>

# Final Drainage Report

The purpose of this Final Drainage Report is to identify drainage patterns and quantities within and affecting the proposed Jackson Ranch Filing No. 4 subdivision. The development project is a residential subdivision with 2.5 +/- and 5.0 +/- acre lots. The report will identify specific solutions to problems on-site and off-site resulting from the proposed project.<sup>1</sup> The report and included maps present results of hydrologic and drainage facilities analyses. The report will discuss the recommend drainage improvements to the site and identify drainage requirements relative to the proposed project. This report has been prepared and submitted in accordance with the requirements of the El Paso County Final Plat approval process. An Appendix is included with this report with pertinent calculations and graphs used in the facility design and drainage analyses.

## 1 General Location and Description

### 1.1 Location

The proposed Jackson Ranch Filing No. 4 site is located to the north and adjacent to Jackson Ranch Filing No. 3 and is in the Northwest One-Quarter of Section 21, Township 11 South, Range 66 West of the 6th principal meridian in unincorporated El Paso County, Colorado. The site is situated to the north of Higby Road, and to the east of Roller Coaster Road. The property is currently unplatted. A **Vicinity Map** is included in the **Appendix**.

### 1.2 Description of Property

Jackson Ranch Filing No. 4 site contains ~~31.165~~<sup>2</sup> ± acres of undeveloped property. The acreage will remain zoned RR-2.5 (Residential Rural District). The proposed Jackson Ranch Filing No. 4 includes 8 rural residential lots, Tract B open space and drainage area, and about 680 feet of paved roads. The road system to be constructed at this time include the remaining southern 680+/- linear feet of Jackson Ranch Court up to the end of said court.

The ground cover, which is in fair to good condition, consists of native grasses, sparse brush and areas of mature coniferous trees. The trees are concentrated on the site along a line from the center of the southern boundary of the site and along the ridge line traversing the site towards the northeast.

The existing topography on the eastern portion of the Jackson Ranch Filing No. 4 site slopes to the northeast with grades that range from 5% to 6%. The existing topography on the western portion of Jackson Ranch Filing No. 4 slopes from the east to the west at slopes of 5% to 7% into the existing channel which slopes to the northeast at a slope of about 2%. Off-site flows enter the property via ditch flow from Basin C2.2 combining with overland flow from Basin C2.3.

Soils on the site are generally conducive for land development. According to the National Resources Conservation Service, there are three (3) soil types in the immediate area of the Jackson Ranch Filing No. 4 site. Kettle Complex (map unit 40), makes up a portion of the soils in the center of the sites watershed. The Kettle Complex is deep and well drained. Permeability is rapid, surface runoff is slow, and the hazard of erosion is slight to moderate. Kettle Complex is classified as being part of Hydrologic Soil Group B.

The second type is Tomah-Crowfoot Complex (map unit 93) which makes up a the portion of the soils in the east and west portion of the site watershed with slopes of 8% to 15%. The Tomah-

<sup>1</sup> DCM, 4-6.

Revise to map unit 92 as shown  
on the NRCS soils map.

Crowfoot Complex is typically deep and well drained. Permeability is moderately rapid, surface runoff is medium, and the hazard of erosion is moderate. Tomah-Crowfoot Complex is classified as being part of Hydrologic Soil Group B.

The last soil type is Ustic Torrfluvents Complex (map unit 101), makes up a very minor portion (0.1+/- acres) of the soils at the northwestern corner of the sites watershed. The Ustic Torrfluvents Complex is deep and well drained. Permeability is moderate, surface runoff is slow, and the hazard of erosion is moderate to high. Ustic Torrfluvents Complex is classified as being part of Hydrologic Soil Group B.

The soil has good potential for urban development, but is prone to water and wind erosion if protective vegetation is removed and not mitigated by proper erosion control practices.<sup>2 3</sup> A portion of the **Soil Map** and data tables from the National Cooperative Soil Survey are included in the **Appendix**.

No significant utilities occupy the site. There are no irrigation facilities on the site.

## 2 Drainage Basins and Sub-Basins

### 2.1 Major Basin Descriptions

Jackson Ranch Filing No. 4 site is located in the West Cherry Creek Basin of the Cherry Creek Major Drainage Basin. The basin is an unstudied drainage basin with no Drainage or Bridge fees required.

The current Flood Insurance Study of the region includes Flood Insurance Rate Maps (FIRM), effective March 17, 1997.<sup>4 5</sup> The project site is included in Community Panel Number 08041C0285 F of the FIRM for El Paso County, Colorado. No part of the site is shown to be included in a 100-year flood hazard area as determined by FEMA. The project site and surrounding property is Zone X, being "Areas determined to be outside 500-year floodplain". A portion of the current **FEMA Flood Insurance Rate Maps** is included in the **Appendix**.

Jackson Ranch Filing No. 4 development includes storm water detention as identified in the Jackson Ranch Filing No. 1 Preliminary and Final Drainage Report and in the Jackson Ranch Preliminary Drainage Report which mitigate increased storm flows that would otherwise be directed downstream through the existing drainage way.<sup>6 7</sup> No new storm detention facilities are proposed.

### 2.2 Sub-Basin Description

#### 2.2.1 Existing Drainage Patterns (On-Site)

The majority of the western portion western portion of the existing site drains to the existing natural channel in Tract A which traverses the total Jackson Ranch site from the southwest corner to the northern boundary of said site. An existing dam interrupts the natural channel flow about 100' northerly of the southwest corner of the proposed Jackson Ranch Filing No. 3. The dam incorporates a 12" CSP standpipe and flows are released to downstream once the water surface level reaches the stand pipe end elevation. The eastern edge of of the property drains overland and exits the eastern boundary. An **Existing Drainage Map** is included and shows existing basin delineations.

#### 2.2.2 Off-Site Drainage Flow Patterns

There is no off-site inflow to the site except for some minor ditch flow from Basin C2.2 that flows into into the site. These overland flows combine with Basin C2.3 at the eastern portion of the site adjacent to Jackson Court..

---

2 WSS El Paso County Area, Colorado.  
3 OSD  
4 FIS  
5 FIRM, Map No. 08041C0285 F  
6 JRF1  
7 JR Prelim

### 3 Drainage Design Criteria

#### 3.1 Development Criteria Reference

This *Final Drainage Report for Jackson Ranch Filing No. 4* has been prepared according to the report guidelines presented in the latest edition of *City of Colorado Springs/El Paso County Drainage Criteria Manual* (DCM)<sup>8</sup>. This *Final Drainage Report* is consistent with the Preliminary Drainage Report for Jackson Ranch. The on-site (local) hydrologic analysis is based on a collection of data from the DCM, the NRCS Web Soil Survey<sup>9</sup>, a topographic survey of the site prepared by LWA Land Surveying, Inc., proposed residential site layout by Land Resource Associates (LRA), future land use according to RR-2.5 zoning and property boundary information provided by LWA Land Surveying, Inc.

#### 3.2 Previous Drainage Studies

The West Cherry Creek Basin of the Cherry Creek Major Drainage Basin has not been studied.

Drainage reports for Jackson Ranch Filing No. 1<sup>10</sup>, Oldborough Subdivision<sup>11</sup>, the Preliminary Drainage Report for Jackson Ranch<sup>12</sup>, Jackson Ranch Filing No. 2<sup>13</sup>, and Jackson Ranch Filing No. 3<sup>14</sup> were reviewed for the preparation of this Final Drainage Report.

#### 3.3 Hydrologic Criteria

Flow rates at all design points in the subdivision with contributing areas greater than 100 acres are calculated using SCS hydrologic flow computation method in accordance with El Paso County criteria. Flow rates at all design points having contributing areas less than 100 acres are calculated using the Rational Method as described in the DCM. Flow rates were calculated for 5-year and 100-year rainfall recurrence intervals.

The Rational Method utilized 'Intensity Duration Frequency Curves' Figure 6-5 in the DCM to obtain the design rainfall values. The 'Overland Flow Equation' Page 6-18, and Manning's equation with estimated depths were used in time of concentration calculation. Table 6-6 'Runoff Coefficients for Rational Method' was utilized as a guide in estimating runoff coefficient values.

#### 3.4 Hydraulic Criteria

The hydraulic design and analysis for the facilities in this *Final Drainage Report* have been prepared according to the provisions of the *City of Colorado Springs/El Paso County Drainage Criteria Manual* (DCM)<sup>15</sup>.

### 4 Drainage Facility Design

#### 4.1 General Concept

The proposed *Jackson Ranch Filing No. 4* project will consist of 8 rural residential lots, Tract A and Tract B open space and drainage areas, and about 680 feet of paved roads. Runoff from the western portion of this Phase will drain into Tract A. Tracts A and B are owned and maintained by the Jackson Ranch Homeowners Association for open space/drainage.

The intent of the drainage concept presented in this report is to maintain existing drainage directions and patterns as much as practically allowable, while safely routing developed on-site storm flows through the property to the designated discharge points in accordance with El Paso County drainage criteria.

8 DCM Section 4.3 and Section 4.4  
 9 WSS  
 10 JRF1  
 11 Old  
 12 JR Prelim  
 13 JRF2  
 14 JRF3  
 15 DCM Section 4.3 and Section 4.4

Add a section addressing water quality.  
 Describe why water quality is not required.  
 See ECM I.7.1.B for the specific criteria.

Revise. Construction plans show 836 ft (sta 16+75 to 25+11) from fil 3 to cul-de-sac bulb center



No drainage way encumbrances due to existing or proposed utilities are anticipated.

The existing drainage conditions and the proposed drainage concept are described in more detail below. Input data and results for all calculations are included in the **Appendix**. Drainage maps for the site hydrology are also included in the **Appendix**.

## 4.2 Specific Details

### 4.2.1 Existing Hydrologic Conditions

The Jackson Ranch Filing No. 4 site includes all or part of 6 sub-basins delineated in the Jackson Ranch Preliminary Drainage Report. Portions of Sub-basins B3, C3, and C4 lie within the Jackson Ranch Filing No. 4 developed area, as indicated on the attached **Existing Drainage Map**.

The **Existing Drainage Map** depicts the existing topographic mapping, drainage basin delineations, drainage patterns, adjacent roads with storm drain facilities/piping, the existing dam, and runoff quantities with a data table including drainage areas and storm water runoff flows along with storm water runoff flows.

### 4.2.2 Proposed Hydrologic Conditions

The Proposed Drainage basins within the Site basically mirror the Existing Basins as the proposed Roads were laid out along or near the common Drainage Basin lines. Five (5) sub-basins have been delineated in *Jackson Ranch Filing No. 4* project site for analysis and design of the developed drainage system composed of overland, road & ditch flows as indicated on the attached **Developed Drainage Map**.

Point of Interest No. 1 reflects developed off site flows from Basin B3.2b discharging from the existing swale and along a small portion of the northerly Lot 2 lot line. These storm water runoff flows combine with Basin B3.2c collect and flow in the existing swale through Lot 2, *Jackson Ranch Filing No. 4* which ultimately drains into said existing natural channel. These flows at Point of Interest No. 1 exit the western boundary and have a developed storm water flow of  $Q_5 = 4.6$  cfs and  $Q_{100} = 20.8$  cfs. A rock ditch check is proposed at the end of said swale within the proposed drainage easement.

Point of Interest No. 2 reflects developed storm water runoff flow rates from Basin B3.2.d and are  $Q_5 = 4.0$  cfs and  $Q_{100} = 20.5$  cfs. A small portion of this flow is contributed by the ditch along the western side of the Jackson Ranch Court and the ditch has been designed to accommodate the ditch flow. In general, the ditch will be a 2.5-foot deep V-channel, seeded and mulched to protect against erosion. In sections where the slope exceeds 6%, erosion control blankets will be used in conjunction with the seeding and mulching to provide further protection against erosion. A rock ditch check is proposed at the end of the road way ditch at the connection to the Tract A access leg. The combined storm water runoff flows from Basin B3.2d flow westerly and exit the subdivision along the westerly boundaries of Lots 2, 4, & 5 into the existing natural channel located within Tract A.

Provide calculation for the ditches. See Table 10-4 of the DCM for permissible velocity. If the seed is similar to grass-legume mixture then permissible velocity is 4 fps for channel slope between 0-5% and 3fps for 5-10% slope.

Point of Interest No. 4 reflects developed storm water runoff flow rates from Basins C2.1, C2.2, and C.3 with combined storm water runoff of  $Q_5 = 6.0$  cfs and  $Q_{100} = 26.4$  cfs. A small portion of this flow is contributed by the ditch along the eastern side of the Jackson Ranch Court with in Jackson Ranch Filing No.4. The ditch has been designed to accommodate the ditch flow. In general, the ditch will be a 2.5-foot deep V-channel, seeded and mulched to protect against erosion. In sections where the slope exceeds 6%, erosion control blankets will be used in conjunction with the seeding and mulching to provide further protection against erosion. A rock ditch check is proposed at the end of the road way ditch at the connection to the Tract B access leg. The combined storm water runoff

flows northeasterly via ditch and overland flow and exits the subdivision along the easterly boundaries of Lots 5, & 6 into the existing natural channel located within Tract B and drain northerly. The ultimate flow exiting the northern boundary of the subdivision is Point of Interest No. 4 and offsite flows combined for a value of  $Q_5 = 60$  cfs and  $Q_{100} = 299$  cfs as described in the approved Preliminary Drainage Report for Jackson Ranch at that reports Point of Interest No.7.

Point of Interest 5 is located along the eastern boundary of said subdivision No. 4. This point represents the overland storm water from Basin C3. This flow drains into said existing natural channel located within Tract B and drains northerly. The runoff at this point is  $Q_5 = 2.8$  cfs and  $Q_{100} = 13.8$  cfs.

For all lots within this Jackson Ranch Filing No. 4 that require the driveway to cross a roadside drainage ditch, the minimum size for the culvert is 18" RCP. Other approved products with equivalent or greater capacity may be used in lieu of the 18" RCP.

#### 4.2.3 Proposed Drainage Facilities

No new flows are being added to to the adjacent Higby Road and Roller Coaster Road. The proposed new subdivision Roads will have ditches.

### 5 Opinion of Probable Cost for Drainage Facilities

There are no costs of new drainage facilities anticipated for the Jackson Ranch Filing No. 4 development.

### 6 Drainage and Bridge Fees

Jackson Ranch Filing No. 4 is located within the Cherry Creek Major Drainage Basin which is unstudied. There are no Drainage Fees or Bridge Fees adopted for this Basin. The property is being subdivided into a lots, tracts and road right-of-way.

#### Drainage Fee

(None Required)

**Drainage Fees Due = \$0.00**

#### Bridge Fee

(None Required)

**Bridge Fee Due = \$0.00**

### 7 Conclusion

This Final Drainage Report for the Jackson Ranch Filing No. 4 presents a drainage concept for this proposed subdivision. The subdivision development will function to route and convey storm runoff with the site grading and drainage facilities to be provided as part of the development. The proposed project with associated improvements will not, with respect to stormwater runoff, negatively impact the adjacent properties and downstream drainage facilities.

Review of the June 2016 Preliminary Drainage Report shows an increase in flows at the ultimate release point. Also, based on rough estimate Fil 3 & 4 creates around 6 acres of impervious land (17 lots @ 11% imp = 4.7 ac and 2300 lf @ 28' wide asphalt road = 1.5 ac) which could result in approximately 2 ac-ft of detention. Therefore, detention seems to be required for the overall development so the ultimate release is at or below historic rate.

## References

*City of Colorado Springs/El Paso County Drainage Criteria Manual.* City of Colorado Springs, Department of Public Works, Engineering Division; HDR Infrastructure, Inc.; El Paso County, Department of Public Works, Engineering Division (Colorado Springs: City of Colorado Springs, Revised November 1991).

*Official Soil Series Descriptions.* Soil Survey Staff, Natural Resources Conservation Service, United States Department of Agriculture ("Available online at <http://soils.usda.gov/technical/classification/osd/index.html>", accessed December 12, 2013).

*Web Soil Survey.* Soil Survey Staff, Natural Resources Conservation Service, United States Department of Agriculture ("Available online at <http://websoilsurvey.nrcs.usda.gov/>", accessed December 12, 2013).

*Flood Insurance Rate Map.* Federal Emergency Management Agency, National Flood Insurance Program (Washington D.C.: FEMA, March 17, 1997).

*Flood Insurance Study for El Paso County, Colorado and incorporated Areas.* Federal Emergency Management Agency (Washington D.C.: FEMA, March 17, 1997).

*Preliminary Drainage Report, Jackson Ranch.* M.V.E., Inc. (Colorado Springs, CO: , February 29, 2016).

*Preliminary and Final Drainage Report, Jackson Ranch Filing No. 1.* MVE, Inc. (Colorado Springs, CO: , Rev. September 23, 2014).

*Final Drainage Report for Jackson Ranch Filing No. 3.* M.V.E., Inc. (Colorado Springs, CO: , April 18, 2017).

*Final Drainage Report for Jackson Ranch Filing No. 2.* M.V.E., Inc. (Colorado Springs, CO: , May 9, 2016).

*Final Drainage Report and Plan for Oldborough Subdivision.* Leigh, Whitehead & Assoc (Colorado Springs, CO: , September, 2003).


# Appendices

## **General Maps and Supporting Data**

Vicinity Map

Portions of Flood Insurance Rate Map and LOMR Maps

NRCS Soil Map and Data



# VICINITY MAP

NOT TO SCALE



**NATIONAL FLOOD INSURANCE PROGRAM**

**FIRM**  
**FLOOD INSURANCE RATE MAP**  
 EL PASO COUNTY,  
 COLORADO AND  
 INCORPORATED AREAS

**PANEL 285 OF 1300**  
 (SEE MAP INDEX FOR PANELS NOT PRINTED)

CONTAINS:  
 COMMUNITY

EL PASO COUNTY,  
 UNINCORPORATED AREAS


NUMBER PANEL SUFFIX  
 080059 0285 F

MAP NUMBER  
 08041C0285 F

EFFECTIVE DATE:  
 MARCH 17, 1997




Federal Emergency Management Agency



**NOTE: MAP AREA SHOWN ON THIS PANEL IS LOCATED WITHIN TOWNSHIP 11 SOUTH, RANGE 66 WEST.**

This is an official copy of a portion of the above referenced flood map. It was extracted using F-MIT On-Line. This map does not reflect changes or amendments which may have been made subsequent to the date on the title block. For the latest product information about National Flood Insurance Program flood maps check the FEMA Flood Map Store at [www.msc.fema.gov](http://www.msc.fema.gov)

Soil Map—El Paso County Area, Colorado  
(Jackson Ranch)



Map Scale: 1:6,230 if printed on A portrait (8.5" x 11") sheet.

Meters












































Feet

0 300 600 1200 1800

Map projection: Web Mercator Corner coordinates: WGS84 Edge tics: UTM Zone 13N WGS84



## MAP LEGEND

 Area of Interest (AOI)	 Spoil Area
 Soils	 Stony Spot
 Soil Map Unit Polygons	 Very Stony Spot
 Soil Map Unit Lines	 Wet Spot
 Soil Map Unit Points	 Other
 Special Point Features	 Special Line Features
 Blowout	 Water Features
 Borrow Pit	 Streams and Canals
 Clay Spot	 Transportation
 Closed Depression	 Rails
 Gravel Pit	 Interstate Highways
 Gravelly Spot	 US Routes
 Landfill	 Major Roads
 Lava Flow	 Local Roads
 Marsh or swamp	 Background
 Mine or Quarry	 Aerial Photography
 Miscellaneous Water	
 Perennial Water	
 Rock Outcrop	
 Saline Spot	
 Sandy Spot	
 Severely Eroded Spot	
 Sinkhole	
 Slide or Slip	
 Sodic Spot	

## MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service  
Web Soil Survey URL:

Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: El Paso County Area, Colorado  
Survey Area Data: Version 14, Sep 23, 2016

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Apr 15, 2011—Sep 22, 2011



The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.




## Map Unit Legend

El Paso County Area, Colorado (CO625)			
Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
40	Kettle gravelly loamy sand, 3 to 8 percent slopes	40.5	25.2%
68	Peyton-Pring complex, 3 to 8 percent slopes	22.9	14.2%
92	Tomah-Crowfoot loamy sands, 3 to 8 percent slopes	69.0	42.9%
93	Tomah-Crowfoot complex, 8 to 15 percent slopes	28.4	17.6%
101	Ustic Torrifluvents, loamy	0.2	0.1%
<b>Totals for Area of Interest</b>		<b>161.0</b>	<b>100.0%</b>

Hydrologic Soil Group—El Paso County Area, Colorado  
(Jackson Ranch)



## MAP LEGEND



## MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service  
 Web Soil Survey URL:  
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: El Paso County Area, Colorado  
 Survey Area Data: Version 14, Sep 23, 2016

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Apr 15, 2011—Sep 22, 2011

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

## Hydrologic Soil Group

Hydrologic Soil Group— Summary by Map Unit — El Paso County Area, Colorado (CO625)				
Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
40	Kettle gravelly loamy sand, 3 to 8 percent slopes	B	40.5	25.2%
68	Peyton-Pring complex, 3 to 8 percent slopes	B	22.9	14.2%
92	Tomah-Crowfoot loamy sands, 3 to 8 percent slopes	B	69.0	42.9%
93	Tomah-Crowfoot complex, 8 to 15 percent slopes	B	28.4	17.6%
101	Ustic Torrifuvents, loamy	B	0.2	0.1%
<b>Totals for Area of Interest</b>			<b>161.0</b>	<b>100.0%</b>

## Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

**Group A.** Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

**Group B.** Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

**Group C.** Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

**Group D.** Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

## Rating Options

*Aggregation Method:* Dominant Condition

*Component Percent Cutoff:* None Specified

*Tie-break Rule:* Higher

pricklypear occur. Ample amounts of litter and forage should be left on the soil because of the high hazard of soil blowing.

Windbreaks and environmental plantings are generally well suited to this soil. Summer fallow a year prior to planting and continued cultivation for weed control are needed to insure establishment and survival of plantings. Trees that are best suited and have good survival are Rocky Mountain juniper, eastern redcedar, ponderosa pine, Siberian elm, Russian-olive, and hackberry. Shrubs that are best suited are skunkbush sumac, lilac, Siberian peashrub, and American plum.

Depending on land use, this soil can produce habitat that is suitable for either rangeland wildlife, such as antelope, or for openland wildlife, such as pheasant, cottontail, and mourning dove. Availability of irrigation water largely determines the land use. Where no irrigation water is available, this soil is mainly used as rangeland, a use that favors rangeland wildlife. If this soil is used as rangeland, fences, livestock water developments, and proper livestock grazing use are practices that enhance habitat for rangeland wildlife. Production of crops such as wheat, corn, and alfalfa provides suitable habitat for openland wildlife, especially pheasant. Among the practices that increase openland wildlife populations are planting trees and shrubs and providing undisturbed nesting cover.

The main limitation of this soil for urban use is shrink-swell potential. Buildings and roads need to be designed to overcome this limitation. Roads need to be designed to minimize frost-heave damage. Capability subclasses IVe, nonirrigated, and IIe, irrigated.

**40—Kettle gravelly loamy sand, 3 to 8 percent slopes.** This deep, well drained soil formed in sandy arkosic deposits on uplands. Elevation ranges from 7,000 to 7,700 feet. The average annual precipitation is about 18 inches, the average annual air temperature is about 43 degrees F, and the average frost-free period is about 120 days.

Typically, the surface layer is gray gravelly loamy sand about 3 inches thick. The subsurface layer is light gray gravelly loamy sand about 13 inches thick. The subsoil is very pale brown gravelly sandy loam about 24 inches thick. It consists of a matrix of loamy coarse sand that has thin bands of coarse sandy loam or sandy clay loam. The substratum to a depth of 60 inches or more is light yellowish brown extremely gravelly loamy sand.

Included with this soil in mapping are small areas of Alamosa loam, 1 to 3 percent slopes; Elbeth sandy loam, 3 to 8 percent slopes; Pring coarse sandy loam, 3 to 8 percent slopes; Tomah-Crowfoot loamy sands, 3 to 8 percent slopes; and a few rock outcrops.

Permeability of this Kettle soil is rapid. Effective rooting depth is 60 inches or more. Available water capacity is low to moderate. Surface runoff is slow, and the hazard of erosion is slight to moderate. A few gullies have formed in drainageways.

This soil is used for woodland, livestock grazing, wildlife habitat, recreation, and homesites.

This soil is suited to the production of ponderosa pine. It is capable of producing about 2,240 cubic feet or 4,900 board feet (International rule), of merchantable timber per acre from a fully stocked, even-aged stand of 80-year-old trees. The main limitation for the production or harvesting of timber is the low available water capacity. The low available water capacity also influences seedling survival, especially in areas where understory plants are plentiful. Erosion must be kept to a minimum when harvesting timber.

This soil has good potential for mule deer, tree squirrels, cottontail rabbit, and wild turkey. These animals obtain their food and shelter from pine trees, shrubs, and ground cover, which provide browse, forbs, fruit, and seeds. The presence of ponderosa pine and Gambel oak should encourage wild turkey populations; however, where water is not naturally present, wildlife watering facilities must be provided to attract and maintain wild turkey and other wildlife species. Livestock grazing management is vital on this soil if wildlife populations are to be maintained.

This soil has good potential for use as homesites. Plans for homesite development on this soil should provide for the preservation of as many trees as possible in order to maintain the esthetic value of the sites. During seasons of low precipitation, fire may become a hazard to homesites. This hazard can be minimized by installing firebreaks and reducing the amount of litter on the forest floor. Capability subclass VIe.

**41—Kettle gravelly loamy sand, 8 to 40 percent slopes.** This deep, well drained soil formed in sandy arkosic deposits on uplands. Elevation ranges from 7,000 to 7,700 feet. The average annual precipitation is about 18 inches, the average annual air temperature is about 43 degrees F, and the average frost-free period is about 120 days.

Typically, the surface layer is gray gravelly loamy sand about 3 inches thick. The subsurface layer is light gray gravelly loamy sand about 13 inches thick. The subsoil is very pale brown gravelly sandy loam about 24 inches thick. It consists of a matrix of loamy coarse sand that has thin bands of coarse sandy loam or sandy clay loam. The substratum to a depth of 60 inches or more is light yellowish brown extremely gravelly loamy sand.

Included with this soil in mapping are small areas of Elbeth sandy loam, 8 to 15 percent slopes; Pring coarse sandy loam, 8 to 15 percent slopes; Tomah-Crowfoot loamy sands, 8 to 15 percent slopes; and a few rock outcrops.

Permeability of this Kettle soil is rapid. Effective rooting depth is 60 inches or more. Available water capacity is low to moderate. Surface runoff is medium, and the hazard of erosion is moderate. Some gullies have formed in drainageways.

The soil is used for woodland, livestock grazing, wildlife habitat, recreation, and homesites.

This soil is suited to the production of ponderosa pine. It is capable of producing 2,240 cubic feet, or 4,900 board

strength. Special designs for buildings and roads are required to offset these limitations. Methods of sewage disposal other than septic tank absorption fields are needed because of the limited depth to bedrock. Capability subclass VIe.

**92—Tomah-Crowfoot loamy sands, 3 to 8 percent slopes.** These gently sloping to moderately sloping soils are on alluvial fans, hills, and ridges in the uplands. Elevation ranges from about 7,300 to 7,600 feet. The average annual precipitation is about 17 inches, the average annual air temperature is about 42 degrees F, and the average frost-free period is about 120 days.

The Tomah soil makes up about 50 percent of the complex, the Crowfoot soil about 30 percent, and other soils about 20 percent.

Included with these soils in mapping are areas of Elbeth sandy loam, 3 to 8 percent slopes; Kettle gravelly loamy sand, 3 to 8 percent slopes; and Pring coarse sandy loam, 3 to 8 percent slopes.

The Tomah soil is deep and well drained. It formed in alluvium or residuum derived from arkose beds. Typically, the surface layer is dark grayish brown loamy sand about 10 inches thick. The subsurface layer is very pale brown coarse sand about 12 inches thick. The subsoil, about 26 inches thick, is a matrix of very pale brown coarse sand in which are embedded many thin bands and lamellae of pale brown coarse sandy clay loam. The substratum is very pale brown coarse sand to a depth of 60 inches or more.

Permeability of the Tomah soil is moderately rapid. Effective rooting depth is 60 inches or more. Available water capacity is moderate. Surface runoff is slow, and the hazard of erosion is slight to moderate.

The Crowfoot soil is deep and well drained. It formed in sediment weathered from arkosic sandstone. Typically, the surface layer is grayish brown loamy sand about 12 inches thick. The subsurface layer is very pale brown sand about 11 inches thick. The subsoil is light yellowish brown sandy clay loam about 13 inches thick. The substratum is very pale brown coarse sand to a depth of about 68 inches.

Permeability of the Crowfoot soil is moderate. Effective rooting depth is 60 inches or more. Available water capacity is moderate. Surface runoff is slow, and the hazard of erosion is slight to moderate.

This complex is used as rangeland, for wildlife habitat, and as homesites.

Native vegetation is mainly mountain muhly, bluestem, mountain brome, needleandthread, and blue grama. These soils are subject to invasion by Kentucky bluegrass and Gambel oak. Noticeable forbs are hairy goldenrod, geranium, milkvetch, low larkspur, fringed sage, and buckwheat.

Properly locating livestock watering facilities helps to control grazing. Timely deferment of grazing is needed to protect the plant cover.

Windbreaks and environmental plantings are fairly well suited to these soils. Blowing sand and moderate available water capacity are the principal limitations for the

establishment of trees and shrubs. The soils are so loose that trees need to be planted in shallow furrows and plant cover needs to be maintained between the rows. Supplemental irrigation may be needed to insure survival. Trees that are best suited and have good survival are Rocky Mountain juniper, eastern redcedar, ponderosa pine, and Siberian elm. Shrubs that are best suited are skunkbush sumac, lilac, and Siberian peashrub.

These soils are best suited to habitat for openland wildlife such as pronghorn antelope and sharp-tailed grouse. Although sharp-tailed grouse are not plentiful, they could be encouraged on these soils, especially where brush species are interspersed with grasses and forbs. If these soils are used as rangeland, wildlife production can be increased by managing livestock grazing to preclude overuse of the more desirable grass species and depletion of the various brush species.

These soils have good potential for use as homesites. The main limitation of the Crowfoot soil is frost-action potential. Roads and streets need to be designed to minimize frost-heave damage. Maintaining the existing vegetation on building sites during construction helps to control erosion. Capability subclass IVe.

**93—Tomah-Crowfoot loamy sands, 8 to 15 percent slopes.** These moderately sloping to strongly sloping soils are on alluvial fans, hills, and ridges in the uplands. Elevation ranges from about 7,300 to 7,600 feet. The average annual precipitation is about 17 inches, the average annual air temperature is about 42 degrees F, and the average frost-free period is about 120 days.

The Tomah soil makes up about 50 percent of the complex, the Crowfoot soil about 30 percent, and other soils about 20 percent.

Included with these soils in mapping are areas of Elbeth sandy loam, 8 to 15 percent slopes; Peyton-Pring complex, 8 to 15 percent slopes; and Kettle gravelly loamy sand, 8 to 40 percent slopes.

The Tomah soil is deep and well drained. It formed in alluvium or residuum derived from arkose beds. Typically, the surface layer is dark grayish brown loamy sand about 10 inches thick. The subsurface layer is very pale brown coarse sand about 12 inches thick. The subsoil, about 26 inches thick, consists of a matrix of very pale brown coarse sandy clay loam. The substratum is very pale brown coarse sand to a depth of 60 inches or more.

Permeability of the Tomah soil is moderately rapid. Effective rooting depth is 60 inches or more. Available water capacity is moderate. Surface runoff is medium, and the hazard of erosion is moderate. Some gullies are present in some drainageways and along stock trails.

The Crowfoot soil is deep and well drained. It formed in sediment weathered from arkosic sandstone. Typically, the surface layer is grayish brown loamy sand about 12 inches thick. The subsurface layer is very pale brown sand about 11 inches thick. The subsoil is light yellowish brown sandy clay loam about 13 inches thick. The substratum is very pale brown coarse sand to a depth of about 68 inches.

rapid, and the hazard of erosion is high. Gullies 1 foot to 3 feet deep are common.

The Bresser soil is deep and well drained. It formed in alluvium and residuum derived from arkosic sedimentary rock. Typically, the grayish brown sandy loam surface layer is very thin or has been entirely removed by erosion. The subsoil is brown sandy clay loam about 31 inches thick. The substratum is light yellowish brown loamy coarse sand to a depth of 60 inches or more.

Permeability of the Bresser soil is moderate. Effective rooting depth is 60 inches or more. Available water capacity is moderate. Surface runoff is medium to rapid, and the hazard of erosion is high. Gullies 1 foot to 3 feet deep are common.

These soils are commonly used for grazing livestock and for wildlife habitat. Most areas of these soils are fields that were previously cropped but have either been abandoned or reseeded to grass.

These soils are suited to deep-rooted grasses. Native vegetation is dominantly western wheatgrass, side-oats grama, and needleandthread.

Proper range management is needed to prevent excessive removal of the plant cover from these soils. Interseeding improves the existing vegetation. Deferment of grazing in spring increases plant vigor and soil stability. Properly locating livestock watering facilities helps to control grazing.

Windbreaks and environmental plantings generally are suited to these soils. Soil blowing is the main limitation for establishing trees and shrubs. This limitation can be overcome by cultivating only in the tree rows and leaving a strip of vegetation between the rows. Supplemental irrigation may be needed when planting and during dry periods. Trees that are best suited and have good survival are Rocky Mountain juniper, eastern redcedar, ponderosa pine, Siberian elm, Russian-olive, and hackberry. Shrubs that are best suited are skunkbush sumac, lilac, and Siberian peashrub.

These soils are suited to wildlife habitat. They are best suited to habitat for openland and rangeland wildlife. Rangeland wildlife, such as pronghorn antelope, can be encouraged by developing livestock watering facilities, properly managing livestock grazing, and reseeding range where needed.

The main limitation of these soils for homesites is frost-action potential, especially in areas of the Truckton soil. Special practices are needed to reduce the hazard of erosion in areas of construction where vegetation has been removed from the soils. Access roads must be designed to minimize frost-heave damage in areas of the Truckton soil. Capability subclass VIe.

101—Ustic Torrifluvents, loamy. These deep, well drained soils are on terraces and flood plains along the major drainageways. Some of the larger areas of these soils are in the Jimmy Creek Camp and Black Squirrel Creek drainageways and in the Ellicott area. Slope is 0 to 3 percent. The average annual precipitation is about 15 inches, the average annual air temperature is about 48

degrees F, and the average frost-free period is about 135 days.

Typically, the surface layer is grayish brown to very dark grayish brown gravelly sandy loam to clay loam 6 to 18 inches thick. The stratified underlying material, to a depth of 60 inches, ranges from heavy clay loam to sand.

Included with these soils in mapping are small areas of Blendon sandy loam, 0 to 3 percent slopes; Bresser sandy loam, 0 to 3 percent slopes; Nunn clay loam, 0 to 3 percent slopes; and Sampson loam, 0 to 3 percent slopes.

Permeability of Ustic Torrifluvents, loamy, is moderate. Effective rooting depth is 60 inches or more. Available water capacity is moderate to high. Surface runoff is slow, and the hazard of erosion is moderate to high. These soils are occasionally flooded. The hazard of soil blowing is moderate to high.

About half of the acreage of these soils is used for irrigated corn, bluegrass sod, and alfalfa and for dryfarmed wheat. The slow surface runoff reduces the need for intensive conservation measures. Most irrigated areas are in the Ellicott area and the Jimmy Camp Creek area. The rest of the acreage is used as rangeland.

These soils are suited to the production of native vegetation suitable for grazing. The soils favor tall grasses. The native vegetation is mainly big bluestem, switchgrass, junegrass, western wheatgrass, and blue grama.

To achieve needed grazing management, including periodic deferment, fences are generally arranged in such a way that access to these soils can be controlled. Reseeding on these soils is needed if the vegetation is depleted or destroyed by plowing. Water spreading is highly beneficial in suitable areas of these soils.

Windbreaks and environmental plantings generally are suited to these soils. Soil blowing is the main limitation for the establishment of trees and shrubs. This limitation can be overcome by cultivating only in the tree rows and leaving a strip of vegetation between the rows. Supplemental irrigation may be needed when planting and during dry periods. Trees that are best suited and have good survival are Rocky Mountain juniper, eastern redcedar, ponderosa pine, Siberian elm, Russian-olive, and hackberry. Shrubs that are best suited are skunkbush sumac, lilac, and Siberian peashrub.

These soils are suited to wildlife habitat. They are best suited to habitat for openland and rangeland wildlife. In cropland areas, habitat favorable for ring-necked pheasant, mourning dove, and many nongame species can be developed by establishing areas for nesting and escape cover. For pheasant, undisturbed nesting cover is vital and should be provided for in plans for habitat development. This is especially true in areas of intensive farming. Rangeland wildlife, such as pronghorn antelope, can be encouraged by developing livestock watering facilities, properly managing livestock grazing, and reseeding range where needed.

The main limitation of these soils for urban use is the hazard of flooding. Buildings and roads should not be



built along drainageways and on flood plains. Access roads must be designed to minimize frost-heave damage. Capability subclasses IIIe, nonirrigated, and IIe, irrigated.

**102—Valent sand, 1 to 9 percent slopes.** This deep, nearly level to gently rolling, excessively drained soil formed in sandy eolian material on uplands. Elevation ranges from 5,100 to 5,600 feet. The average annual precipitation is about 13 inches, the average annual air temperature is about 49 degrees F, and the average frost-free period is about 145 days.

Typically, the surface layer is light brownish gray sand about 6 inches thick. The next layer is brown sand about 6 inches thick. The substratum is pale brown sand to a depth of 60 inches or more.

Included with this soil in mapping are small areas of Bijou loamy sand, 1 to 8 percent slopes, and Wigton loamy sand, 1 to 8 percent slopes.

Permeability of this Valent soil is rapid. Effective rooting depth is 60 inches or more. Available water capacity is low to moderate. Surface runoff is slow, and the hazards of erosion and soil blowing are high.

This soil is used as rangeland and for wildlife habitat.

The native vegetation is mainly sand reedgrass, sand bluestem, blue grama, little bluestem, and needle-andthread. Sand sagebrush is in the stand, but it makes up only a small part of the total ground cover. Large amounts of yucca are present in some places.

Mechanical and chemical control of sagebrush may be needed in overgrazed areas of this soil. The soil is highly susceptible to soil blowing, and water erosion occurs when the plant cover is inadequate. Interseeding is a good practice in overgrazed areas. Properly locating livestock watering facilities helps to control grazing.

Windbreaks and environmental plantings are fairly well suited to this soil. Blowing sand and low available water capacity are the main limitations for the establishment of trees and shrubs. The soil is so loose that trees need to be planted in shallow furrows and plant cover needs to be maintained between the rows. Supplemental irrigation may be needed to insure survival. Trees that are best suited and have good survival are Rocky Mountain juniper, eastern redcedar, ponderosa pine, and Siberian elm. Shrubs that are best suited are skunkbush sumac, lilac, and Siberian peashrub.

This soil is suited to wildlife habitat. It is best suited to habitat for openland and rangeland wildlife. Rangeland wildlife, such as pronghorn antelope, can be encouraged by developing livestock watering facilities, properly managing livestock grazing, and reseeding range where needed.

The main limitation of this soil for homesites is the sandy nature of the soil, which makes excavation difficult. Special erosion control practices are needed during construction. Because of the rapid permeability of this soil, there is a hazard of pollution if it is used for septic tank absorption fields. Capability subclass VIe.

**103—Valent sand, 9 to 20 percent slopes.** This deep, excessively drained, rolling to hilly soil formed in sandy eolian material on uplands. Elevation ranges from 5,100 to 5,600 feet. The average annual precipitation is about 13 inches, the average annual air temperature is about 49 degrees F, and the average frost-free period is about 145 days.

Typically, the surface layer is light brownish gray sand about 6 inches thick. The next layer is brown sand about 6 inches thick. The underlying material is pale brown sand to a depth of 60 inches or more.

Included with this soil in mapping are small areas of Bijou loamy sand, 1 to 8 percent slopes; Wigton loamy sand, 1 to 8 percent slopes; and Valent sand, 1 to 9 percent slopes.

Permeability of this Valent soil is rapid. Effective rooting depth is 60 inches or more. Available water capacity is low to moderate. Surface runoff is slow, and the hazard of erosion is high. Blowouts are common in all areas of this soil.

This soil is used as rangeland and for wildlife habitat.

The native vegetation is mainly prairie sandreed, sand bluestem, needleandthread, and sand dropseed.

Careful grazing management is essential on this soil to prevent overgrazing, because the hazard of soil blowing is high when the protective plant cover is destroyed. Livestock watering facilities should not be located on this soil, because they cause concentrations of animals that deplete the rangeland cover. No mechanical type of conservation treatment is practical on this soil.

Windbreaks and environmental plantings are fairly well suited to this soil. Blowing sand and low available water capacity are the main limitations for the establishment of trees and shrubs. The soil is so loose that trees need to be planted in shallow furrows and the plant cover should be maintained between the rows. Supplemental irrigation may be needed to insure survival. Trees that are best suited and have good survival are Rocky Mountain juniper, eastern redcedar, ponderosa pine, and Siberian elm. Shrubs that are best suited are skunkbush sumac, lilac, and Siberian peashrub.


This soil is suited to wildlife habitat. It is best suited to habitat for openland and rangeland wildlife. Rangeland wildlife, such as pronghorn antelope, can be encouraged by developing livestock watering facilities, properly managing livestock grazing, and reseeding range where needed.

The main limitations of this soil for urban use are slope and the sandy texture of the soil. Special designs are needed for buildings and roads to overcome these limitations. The sandy texture of the soil causes excavation problems, mostly the caving in of cut banks. Practices are needed to control soil blowing. Because of the rapid permeability of this soil, there is a hazard of pollution if it is used for septic tank absorption fields. Capability subclass VIe.

**104—Vona sandy loam, 1 to 3 percent slopes.** This deep, well drained soil formed in sandy, calcareous eolian

# Hydrologic Calculations

Figure 6-5. Colorado Springs Rainfall Intensity Duration Frequency



**IDF Equations**

$$I_{100} = -2.52 \ln(D) + 12.735$$

$$I_{50} = -2.25 \ln(D) + 11.375$$

$$I_{25} = -2.00 \ln(D) + 10.111$$

$$I_{10} = -1.75 \ln(D) + 8.847$$

$$I_5 = -1.50 \ln(D) + 7.583$$

$$I_2 = -1.19 \ln(D) + 6.035$$

Note: Values calculated by equations may not precisely duplicate values read from figure.

**Table 6-6. Runoff Coefficients for Rational Method**  
(Source: UDFCD 2001)

Land Use or Surface Characteristics	Percent Impervious	Runoff Coefficients															
		2-year		5-year		10-year		25-year		50-year		100-year					
		HSG A&B	HSG C&D	HSG A&B	HSG C&D	HSG A&B	HSG C&D	HSG A&B	HSG C&D	HSG A&B	HSG C&D	HSG A&B	HSG C&D				
Business																	
Commercial Areas	95	0.79	0.80	0.81	0.82	0.83	0.84	0.85	0.87	0.87	0.88	0.88	0.88	0.88	0.88	0.89	0.89
Neighborhood Areas	70	0.45	0.49	0.49	0.53	0.53	0.57	0.58	0.62	0.60	0.65	0.65	0.65	0.62	0.62	0.68	0.68
Residential																	
1/8 Acre or less	65	0.41	0.45	0.45	0.49	0.49	0.54	0.54	0.59	0.57	0.62	0.62	0.59	0.57	0.59	0.65	0.65
1/4 Acre	40	0.23	0.28	0.30	0.35	0.36	0.42	0.42	0.50	0.46	0.54	0.54	0.50	0.46	0.50	0.58	0.58
1/3 Acre	30	0.18	0.22	0.25	0.30	0.32	0.38	0.39	0.47	0.43	0.52	0.52	0.47	0.43	0.47	0.57	0.57
1/2 Acre	25	0.15	0.20	0.22	0.28	0.30	0.36	0.37	0.46	0.41	0.51	0.51	0.46	0.41	0.46	0.56	0.56
1 Acre	20	0.12	0.17	0.20	0.26	0.27	0.34	0.35	0.44	0.40	0.50	0.50	0.44	0.40	0.44	0.55	0.55
Industrial																	
Light Areas	80	0.57	0.60	0.59	0.63	0.63	0.66	0.66	0.70	0.68	0.72	0.72	0.70	0.68	0.70	0.74	0.74
Heavy Areas	90	0.71	0.73	0.73	0.75	0.75	0.77	0.78	0.80	0.80	0.82	0.82	0.80	0.80	0.81	0.83	0.83
Parks and Cemeteries	7	0.05	0.09	0.12	0.19	0.20	0.29	0.30	0.40	0.34	0.46	0.46	0.40	0.34	0.39	0.52	0.52
Playgrounds	13	0.07	0.13	0.16	0.23	0.24	0.31	0.32	0.42	0.37	0.48	0.48	0.42	0.37	0.41	0.54	0.54
Railroad Yard Areas	40	0.23	0.28	0.30	0.35	0.36	0.42	0.42	0.50	0.46	0.54	0.54	0.50	0.46	0.50	0.58	0.58
Undeveloped Areas																	
Historic Flow Analysis--																	
Greenbelts, Agriculture	2	0.03	0.05	0.09	0.16	0.17	0.26	0.26	0.38	0.31	0.45	0.45	0.38	0.31	0.36	0.51	0.51
Pasture/Meadow	0	0.02	0.04	0.08	0.15	0.15	0.25	0.25	0.37	0.30	0.44	0.44	0.37	0.30	0.35	0.50	0.50
Forest	0	0.02	0.04	0.08	0.15	0.15	0.25	0.25	0.37	0.30	0.44	0.44	0.37	0.30	0.35	0.50	0.50
Exposed Rock	100	0.89	0.89	0.90	0.90	0.92	0.92	0.94	0.94	0.95	0.95	0.95	0.94	0.95	0.96	0.96	0.96
Offsite Flow Analysis (when landuse is undefined)	45	0.26	0.31	0.32	0.37	0.38	0.44	0.44	0.51	0.48	0.55	0.55	0.51	0.48	0.51	0.59	0.59
Streets																	
Paved	100	0.89	0.89	0.90	0.90	0.92	0.92	0.94	0.94	0.95	0.95	0.95	0.94	0.95	0.96	0.96	0.96
Gravel	80	0.57	0.60	0.59	0.63	0.63	0.66	0.66	0.70	0.68	0.72	0.72	0.70	0.68	0.70	0.74	0.74
Drive and Walks	100	0.89	0.89	0.90	0.90	0.92	0.92	0.94	0.94	0.95	0.95	0.95	0.94	0.95	0.96	0.96	0.96
Roofs	90	0.71	0.73	0.73	0.75	0.75	0.77	0.78	0.80	0.80	0.82	0.82	0.80	0.80	0.81	0.83	0.83
Lawns	0	0.02	0.04	0.08	0.15	0.15	0.25	0.25	0.37	0.30	0.44	0.44	0.37	0.30	0.35	0.50	0.50

**Time of Concentration (Modified from Standard Form SF-1)**

Sub-Basin	Sub-Basin Data			Overland			Shallow Channel			Channelized			t <sub>c</sub> Check					
	Area (Acres)	C <sub>5</sub>	C <sub>100</sub> /CN	% Imp.	L <sub>0</sub> (ft)	S <sub>0</sub> (%)	t <sub>f</sub> (min)	L <sub>0t</sub> (ft)	S <sub>0t</sub> (ft/ft)	V <sub>osc</sub> (ft/s)	t <sub>t</sub> (min)	L <sub>0c</sub> (ft)	S <sub>0c</sub> (ft/ft)	V <sub>oc</sub> (ft/s)	t <sub>c</sub> (min)	L (min)	t <sub>c,alt</sub> (min)	t <sub>c</sub> (min)
EX B3.1	2.75	0.20	0.44	15.4%	300	6%	15.8	340	0.068	1.8	3.1	175	0.011	3.1	0.9	815	N/A	19.9
EX B3.2a	6.54	0.12	0.38	5.0%	190	10%	11.5	700	0.070	1.9	6.3	0	0.000	0.0	0.0	890	N/A	17.8
EX B3.2b	9.99	0.14	0.40	8.1%	300	7%	15.5	640	0.047	1.5	7.0	0	0.000	0.0	0.0	940	N/A	22.6
EX B3.2c	1.40	0.09	0.36	2.0%	238	9%	13.5	288	0.042	1.4	3.4	0	0.000	0.0	0.0	526	N/A	16.9
EX B3.2d	11.63	0.09	0.36	2.0%	200	6%	14.3	780	0.064	1.8	7.3	400	0.020	2.2	3.0	1380	N/A	24.6
EX C2.1	1.21	0.20	0.44	15.9%	205	3%	15.4	0	0.000	0.0	0.0	0	0.000	0.0	0.0	205	N/A	15.4
EX C2.2	6.03	0.17	0.42	12.5%	300	5%	17.1	225	0.053	1.6	2.3	540	0.017	4.3	2.1	1065	N/A	21.5
EX C2.3	8.83	0.09	0.36	2.0%	260	4%	18.9	410	0.063	1.8	3.9	0	0.000	0.0	0.0	670	N/A	22.7
EX C3	7.95	0.09	0.36	2.0%	300	3%	21.2	605	0.063	1.8	5.7	265	0.026	2.4	1.9	1170	N/A	28.8
EX C4	1.73	0.09	0.36	2.0%	300	5%	18.2	65	0.062	1.7	0.6	0	0.000	0.0	0.0	365	N/A	18.8

Job No. 61073  
 Project: Jackson Ranch Filing No. 4  
 Design Storm: 5-Year Storm (20% Probability)  
 Jurisdiction: UDFCD

Date: 4/21/17 12:17  
 Calcs By: D. Gorman  
 Checked By:

Sub-Basin and Combined Flows (Modified from Standard Form SF-2)

DP	Sub-Basin	Area (Acres)	C5	Direct Runoff			Combined Runoff			Streetflow			Pipe Flow			Travel Time	
				t <sub>c</sub> (min)	CA (Acres)	I5 (in/hr)	Q5 (cfs)	t <sub>c</sub> (min)	CA (Acres)	I5 (in/hr)	Q5 (cfs)	Slope (%)	Length (ft)	Q (cfs)	Mnngs n	Length (ft)	D <sub>pipe</sub> (in)
	EX B3.1	2.75	0.20	19.9	0.55	2.96	1.6										
	EX B3.2a	6.54	0.12	17.8	0.76	3.14	2.4										
	EX B3.2b	9.99	0.14	22.6	1.42	2.77	3.9										
	EX B3.2c	1.40	0.09	16.9	0.13	3.22	0.4										
	EX B3.2d	11.63	0.09	24.6	1.05	2.64	2.8										
	EX C2.1	1.21	0.20	15.4	0.25	3.36	0.8										
	EX C2.2	6.03	0.17	21.5	1.04	2.84	2.9										
	EX C2.3	8.83	0.09	22.7	0.79	2.76	2.2										
	EX C3	7.95	0.09	28.8	0.72	2.41	1.7										
	EX C4	1.73	0.09	18.8	0.16	3.05	0.5										
POI 1	B3.2b, B3.2c	11.39	0.14					23.5	1.54	2.71	4.2						
POI 2	B3.2d	11.63	0.09					24.6	1.05	2.64	2.8						
POI 3	C2.1, C2.2	7.24	0.18					21.0	1.28	2.88	3.7						
POI 4	C2.1, C2.2, C2.3	16.07	0.13					24.6	2.08	2.64	5.5						

Combined flow must be for the total flows (including offsite flows) draining to the design point. similar comment for developed calculations.

Rainfall Intensity:  $I = (28.5 * P1) / (10 + t_c)^{0.785}$   
 P1: 1.5

Job No. **61073** Date: **4/21/17 12:17**  
 Project: **Jackson Ranch Filing No. 4** Calcs By: **D. Gorman**  
 Design Storm: **100-Year Storm (1% Probability)** Checked By:  
 Jurisdiction: **UDFCD**

**Sub-Basin and Combined Flows (Modified from Standard Form SF-2)**

DP	Sub-Basin	Area (Acres)	C-100	Direct Runoff			Combined Runoff			Streetflow			Pipe Flow			Travel Time		
				t <sub>c</sub> (min)	CA (Acres)	I100 (in/hr)	Q100 (cfs)	t <sub>c</sub> (min)	CA (Acres)	I100 (in/hr)	Q100 (cfs)	Slope (%)	Length (ft)	Q (cfs)	n	Slope (%)	Length (ft)	D <sub>Pipe</sub> (in)
	EX B3.1	2.75	0.44	19.9	1.21	4.97	6.0											
	EX B3.2a	6.54	0.38	17.8	2.46	5.27	13.0											
	EX B3.2b	9.99	0.40	22.6	3.95	4.65	18.4											
	EX B3.2c	1.40	0.36	16.9	0.51	5.41	2.7											
	EX B3.2d	11.63	0.36	24.6	4.19	4.43	18.5											
	EX C2.1	1.21	0.44	15.4	0.53	5.64	3.0											
	EX C2.2	6.03	0.42	21.5	2.51	4.77	12.0											
	EX C2.3	8.83	0.36	22.7	3.18	4.63	14.7											
	EX C3	7.95	0.36	28.8	2.86	4.05	11.6											
	EX C4	1.73	0.36	18.8	0.62	5.12	3.2											
POI 1	B3.2b, B3.2c	11.39	0.39					23.5	4.46	4.55	20.3							
POI 2	B3.2d	11.63	0.36					24.6	4.19	4.43	18.5							
POI 3	C2.1, C2.2	7.24	0.42					21.0	3.04	4.84	14.7							
POI 4	C2.1, C2.2, C2.3	16.07	0.39					24.6	6.22	4.43	27.6							

Rainfall Intensity:  $I = (28.5 * P1) / (10 + tc)^{0.786}$   
 P1: 2.52

**Time of Concentration** (Modified from Standard Form SF-1)

Sub-Basin	Sub-Basin Data			Overland			Shallow Channel			Channelized			t <sub>c</sub> Check					
	Area (Acres)	C <sub>5</sub>	C <sub>100</sub> /CN	% Imp.	L <sub>o</sub> (ft)	S <sub>o</sub> (%)	t <sub>i</sub> (min)	L <sub>ot</sub> (ft)	S <sub>ot</sub> (ft/ft)	V <sub>osc</sub> (ft/s)	t <sub>t</sub> (min)	L <sub>oc</sub> (ft)	S <sub>oc</sub> (ft/ft)	V <sub>oc</sub> (ft/s)	t <sub>c</sub> (min)	L (min)	t <sub>c,alt</sub> (min)	t <sub>c</sub> (min)
DV B3.1	2.75	0.20	0.44	15.4%	300	6%	15.8	340	0.068	1.8	3.1	175	0.011	3.1	0.9	815	N/A	19.9
DV B3.2a	6.54	0.12	0.38	5.0%	190	10%	11.5	700	0.070	1.9	6.3	0	0.000	0.0	0.0	890	N/A	17.8
DV B3.2b	9.99	0.16	0.40	9.7%	300	7%	15.3	640	0.047	1.5	7.0	0	0.000	0.0	0.0	940	N/A	22.3
DV B3.2c	1.40	0.11	0.37	3.6%	238	9%	13.3	288	0.042	1.4	3.4	0	0.000	0.0	0.0	526	N/A	16.6
DV B3.2d	11.07	0.13	0.38	6.1%	200	8%	12.5	640	0.072	1.9	5.7	400	0.020	2.3	2.9	1240	N/A	21.1
DV C2.1	1.21	0.20	0.44	15.9%	205	3%	15.4	0	0.000	0.0	0.0	0	0.000	0.0	0.0	205	N/A	15.4
DV C2.2	6.03	0.17	0.42	12.5%	300	5%	17.1	225	0.053	1.6	2.3	540	0.017	4.3	2.1	1065	N/A	21.5
DV C2.3	8.66	0.09	0.36	2.0%	260	4%	18.8	410	0.063	1.8	3.9	0	0.000	0.0	0.0	670	N/A	22.7
DV C3	8.68	0.13	0.39	6.7%	300	3%	20.4	605	0.063	1.8	5.7	265	0.026	2.3	1.9	1170	N/A	28.0
DV C4	1.73	0.11	0.37	4.2%	300	5%	17.8	65	0.062	1.7	0.6	0	0.000	0.0	0.0	365	N/A	18.4



Job No. **61073**  
 Project: **Jackson Ranch Filling No. 4**  
 Design Storm: **5-Year Storm**  
 Jurisdiction: **UDFCD**

Date: **4/30/17 16:52**  
 Calcs By: **D. Gorman**  
 Checked By:

UDFCD  
 (20% Probability)

**Sub-Basin and Combined Flows** (Modified from Standard Form SF-2)

DP	Sub-Basin	Area (Acres)	C5	Direct Runoff			Combined Runoff			Streetflow			Pipe Flow			Travel Time		
				t <sub>c</sub> (min)	CA (Acres)	I5 (in/hr)	Q5 (cfs)	t <sub>c</sub> (min)	CA (Acres)	I5 (in/hr)	Q5 (cfs)	Slope (%)	Length (ft)	Q (cfs)	n	Slope (%)	Length (ft)	D <sub>Pipe</sub> (in)
	DV B3.1	2.75	0.20	19.9	0.55	2.96	1.6											
	DV B3.2a	6.54	0.12	17.8	0.76	3.14	2.4											
	DV B3.2b	9.99	0.16	22.3	1.55	2.78	4.3											
	DV B3.2c	1.40	0.11	16.6	0.15	3.24	0.5											
	DV B3.2d	11.07	0.13	21.1	1.41	2.87	4.0											
	DV C2.1	1.21	0.20	15.4	0.25	3.36	0.8											
	DV C2.2	6.03	0.17	21.5	1.04	2.84	2.9											
	DV C2.3	8.66	0.09	22.7	0.81	2.76	2.2											
	DV C3	8.68	0.13	28.0	1.14	2.45	2.8											
	DV C4	1.73	0.11	18.4	0.19	3.08	0.6											
POI 1	B3.2b, B3.2c	11.39	0.15					23.3	1.70	2.72	4.6							
POI 2	B3.2d	11.07	0.13					21.1	1.41	2.87	4.0							
POI 3	C4	1.73	0.11					18.4	0.19	3.08	0.6							
POI 4	C2.1, C2.2, C3	15.92	0.15					27.9	2.43	2.45	6.0							
POI 5	C3	8.68	0.13					28.0	1.14	2.45	2.8							

Revise Jurisdiction to EPC (typ)

Rainfall Intensity:  $I = (28.5 * P1) / (10 + tc) * 0.786$   
 P1: 1.5

Job No. **61073** Date: **4/30/17 16:52**  
 Project: **Jackson Ranch Filing No. 4** Calcs By: **D. Gorman**  
 Design Storm: **100-Year Storm (1% Probability)** Checked By:  
 Jurisdiction: **UDFCD**

**Sub-Basin and Combined Flows (Modified from Standard Form SF-2)**

DP	Sub-Basin	Area (Acres)	C-100	Direct Runoff			Combined Runoff			Sireeflow			Pipe Flow			Travel Time	
				t <sub>c</sub> (min)	CA (Acres)	I100 (in/hr)	Q100 (cfs)	t <sub>c</sub> (min)	CA (Acres)	I100 (in/hr)	Q (cfs)	Slope (%)	Length (ft)	n	Length (ft)	D <sub>pipe</sub> (in)	Length (ft)
	DV B3.1	2.75	0.44	19.9	1.21	4.97	6.0										
	DV B3.2a	6.54	0.38	17.8	2.46	5.27	13.0										
	DV B3.2b	9.99	0.40	22.3	4.04	4.67	18.9										
	DV B3.2c	1.40	0.37	16.6	0.52	5.44	2.8										
	DV B3.2d	11.07	0.38	21.1	4.26	4.82	20.5										
	DV C2.1	1.21	0.44	15.4	0.53	5.64	3.0										
	DV C2.2	6.03	0.42	21.5	2.51	4.77	12.0										
	DV C2.3	8.66	0.36	22.7	3.12	4.64	14.5										
	DV C3	8.68	0.39	28.0	3.36	4.12	13.8										
	DV C4	1.73	0.37	18.4	0.64	5.17	3.3										
POI 1	B3.2b, B3.2c	11.39	0.40					23.3	4.56	4.57	20.8						
POI 2	B3.2d	11.07	0.38					21.1	4.26	4.82	20.5						
POI 3	C4	1.73	0.37					18.4	0.64	5.17	3.3						
POI 4	C2.1, C2.2, C3	15.92	0.40					27.9	6.41	4.12	26.4						
POI 5	C3	8.68	0.39					28.0	3.36	4.12	13.8						

Rainfall Intensity:  $I = (28.5 * P1) / (10 + tc)^{0.786}$   
 P1: 2.52

## **Report Maps**

Existing Drainage Map  
Developed Drainage Map



**LEGEND**


- PROPERTY LINE
- EASEMENT LINE
- LOT LINE
- BUILDING SETBACK LINE

**EXISTING**



- INDEX CONTOUR
- INTERMEDIATE CONTOUR
- BARBED WIRE FENCE
- TREE (EVERGREEN/DECID.)

**PROPOSED**

- INDEX CONTOUR
- INTERMEDIATE CONTOUR
- BASIN BOUNDARY
- GENERAL FLOW/DIRECTION
- SLOPE DIRECTION AND GRADE
- BASIN LABEL  
AREA IN ACRES  
PERCENT IMPERVIOUS
- POINT OF INTEREST



BENCHMARK



**MVE, INC.**  
ENGINEERS / SURVEYORS

1903 Library Street, Suite 200 Colorado Springs, CO 80909 719.635.5736

REVISIONS

DESIGNED BY \_\_\_\_\_  
DRAWN BY \_\_\_\_\_  
CHECKED BY \_\_\_\_\_  
AS-BUILTS BY \_\_\_\_\_  
CHECKED BY \_\_\_\_\_

**JACKSON RANCH  
FILING NO. 4**

**EXISTING  
DRAINAGE MAP**



POINT OF INTEREST / BASIN(S)	AREA (ACRES)	T <sub>c</sub> (MIN.)	RUNOFF (CFS)	
			Q <sub>5</sub>	Q <sub>100</sub>
B3.1	2.7	19.9	1.6	6.0
B3.2a	6.5	17.8	2.4	13.0
B3.1, B3.2a	9.3	22.9	3.6	16.9
POI 1 B3.2b	11.4	24.6	3.9	19.6
POI 2 B3.2c	11.6	24.6	2.8	18.5
C2.1	1.2	15.4	0.8	3.0
C2.2	6.0	21.5	2.9	12.0
POI 3 C2.1, C2.2	7.2	21.0	3.7	14.7
C2.3	8.8	22.7	2.2	14.7
POI 4 C2.1, C2.2, C2.3	16.1	24.6	5.5	27.6
C3	8.0	28.8	1.7	11.6
C4	1.7	18.8	0.5	3.2

MVE PROJECT 61073  
MVE DRAWING EX-DR-MapF4

April 18, 2017  
SHEET 1 OF 2

Z:\1073\_Sheet\Drawings\1073-EX-DR-MapF4.dwg 4/17/17 3:58:33 AM ERG

The combined flow runoff calculation worksheet needs to show how this value was calculated. With no proposed detention and an increase in imperviousness this should be greater than the existing condition. Comment also applies to the existing condition.






**FLOODPLAIN STATEMENT:**  
 A PORTION OF THE SUBJECT PROPERTY IS LOCATED WITHIN FEMA DESIGNATED SPECIAL FLOOD HAZARD AREA (SFHA) ZONE X (AREAS OF 500-YEAR FLOOD; AREAS OF 100-YEAR FLOOD WITH AVERAGE DEPTHS OF LESS THAN 1 FOOT OR WITH DRAINAGE AREAS LESS THAN 1 SQUARE MILE; AND AREAS PROTECTED BY LEVEES FROM 100-YEAR FLOOD) AS INDICATED ON THE FLOOD INSURANCE RATE MAP (FIRM) FOR EL PASO COUNTY, COLORADO AND INCORPORATED AREAS - MAP NUMBER 08041C0741 F, EFFECTIVE MARCH 17, 1997. THE STRUCTURES WILL BE CONSTRUCTED MORE THAN 1.0 FEET ABOVE THE ADJACENT FEMA BASE FLOOD ELEVATION.

**MAP NOTES:**  
 1. ALL BEARINGS USED HEREIN ARE BASED ON AN ASSUMED BEARING BETWEEN A NO. 4 REBAR WITH NO CAP AT THE NORTHEAST CORNER AND A NO. 5 REBAR WITH NO CAP AT THE SOUTHEAST CORNER OF THE SUBJECT PROPERTY. THE ASSUMED BEARING BETWEEN THOSE MONUMENTS IS S 17° 11' 24" E, PER THE RECORDED PLAT OF AIR PRODUCTS SUBDIVISION.  
 2. ELEVATIONS SHOWN ON THIS MAP ARE RELATIVE TO THE NORTHEAST CORNER OF THE SUBJECT PROPERTY, MONUMENTED WITH AN ALUMINUM CAP HAVING ILLEGIBLE MARKINGS. ELEVATION = 5816.25 (ASSUMED DATUM).  
 3. THE EXISTING TOPOGRAPHY SHOWN ON THIS PLAN WAS PREPARED BY ROCKY MOUNTAIN LAND SERVICES, INC. AND DATED AUGUST 14, 2014.  
 4. ALL EXISTING UNDERGROUND UTILITIES SHOWN ON THIS MAP ARE FROM UTILITY MAIN RECORD MAPS. UTILITY SERVICE LOCATION MAPS OBTAINED FROM COLORADO SPRINGS UTILITIES AND SURFACE EVIDENCE AS SURVEYED IN THE FIELD. THE LOCATION OF UTILITIES AS SHOWN ARE APPROXIMATE. ALL UTILITIES MAY NOT BE SHOWN OR MAY NOT HAVE BEEN LOCATED. BELOW GROUND UTILITY LOCATIONS WERE NOT PERFORMED.

**EASEMENTS FOR DRAINAGE:**  
 UNLESS SHOWN GREATER IN WIDTH, SIDE AND REAR LOT LINES ARE HEREBY PLATTED WITH A TEN (10) FOOT EASEMENT FOR DRAINAGE AND PUBLIC UTILITIES ONLY. FRONT LOT LINES ARE HEREBY PLATTED WITH A FIFTEEN (15) FEET EASEMENT FOR DRAINAGE AND PUBLIC UTILITIES ONLY. TRACTS A AND B ARE DRAINAGE AND PUBLIC UTILITY EASEMENT IN ITS ENTIRETY AND THE NORTH, EAST AND SOUTHEAST SUBDIVISION BOUNDARY IS HEREBY PLATTED WITH A THIRTY FOOT EASEMENT FOR DRAINAGE AND PUBLIC UTILITIES ONLY, WITH THE SOLE RESPONSIBILITY FOR MAINTENANCE BEING VESTED WITH THE PROPERTY OWNERS.

LOTS 1 AND 2 CONTAIN PLATTED DRAINAGE AND NO BUILD AREAS TO ACCOMMODATE OFFSITE AS WELL AS ONSITE DRAINAGE.

BENCHMARK



RURAL LOCAL ROAD SECTION  
 SCALE: 1" = 10'

DEVELOPED DRAINAGE SUMMARY TABLE					
POINT OF INTEREST/ BASIN(S)	AREA (AC)	Tc (MIN.)	RUNOFF		
			Q5 (CFS)	Q100 (CFS)	
B3.1	2.7	19.9	1.6	6.0	
B3.2a	6.5	17.8	2.4	13.0	
B3.1, B3.2a	9.3	22.9	3.6	16.9	
B3.2b	10.0	22.3	4.3	18.9	
B3.2c	1.4	16.6	0.5	2.8	
POI 1	B3.2b, B3.2c	11.4	23.3	4.6	20.8
POI 2	B3.2d	11.1	21.1	4.0	20.5
	C2.1	1.2	15.4	0.8	3.0
	C2.2	6.0	21.5	2.9	12.0
POI 3	C4	1.7	18.4	0.6	3.3
	C2.3	8.7	22.7	2.2	14.5
POI 4	C2.1, C2.2, C3	15.9	27.9	6.0	26.4
POI 5	C3	8.7	28	2.8	13.8

REVISIONS

DESIGNED BY \_\_\_\_\_  
 DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_  
 AS-BUILT BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_

**JACKSON RANCH  
 FILING NO. 4**

**DEVELOPED  
 DRAINAGE MAP**

MVE PROJECT 61073  
 MVE DRAWING PP-DR-MapF4

April 18, 2017  
 SHEET 2 OF 2



# Markup Summary

dsdlaforce (13)

Add: "PCD Project No. SF-17-016"

**Subject:** Text Box  
**Page Label:** 1  
**Lock:** Unlocked  
**Status:**  
**Checkmark:** Unchecked  
**Author:** dsdlaforce  
**Date:** 6/19/2017 4:25:29 PM  
**Color:** ■

Add: "PCD Project No. SF-17-016"

El Paso County  
Add to accordance with the requirements of the Drainage Criteria Manual 1.1.2.1.1.1  
Revised by Jennifer Irvine, P.E.  
El Paso County  
El Paso County  
El Paso County

**Subject:** Cloud+  
**Page Label:** 3  
**Lock:** Unlocked  
**Status:**  
**Checkmark:** Unchecked  
**Author:** dsdlaforce  
**Date:** 6/26/2017 9:10:35 AM  
**Color:** ■

Revise to "Jennifer Irvine, P.E."

Acknowledged  
"master"  
Engineer's Statement  
The attached drainage plan is correct to the best of my knowledge and belief and I am not aware of any negligent act or omission on the part of the engineer or contractor.

**Subject:** Cloud+  
**Page Label:** 3  
**Lock:** Unlocked  
**Status:**  
**Checkmark:** Unchecked  
**Author:** dsdlaforce  
**Date:** 6/26/2017 9:10:21 AM  
**Color:** ■

"master"

Developer's Statement  
I, the developer, have read and will comply with the requirements of the Drainage Criteria Manual 1.1.2.1.1.1.1.  
Address  
El Paso County  
El Paso County  
El Paso County

**Subject:** Cloud+  
**Page Label:** 3  
**Lock:** Unlocked  
**Status:**  
**Checkmark:** Unchecked  
**Author:** dsdlaforce  
**Date:** 6/20/2017 1:40:29 PM  
**Color:** ■

Address

Developer's Statement  
I, the developer, have read and will comply with the requirements of the Drainage Criteria Manual 1.1.2.1.1.1.1.  
Add title  
El Paso County  
El Paso County  
El Paso County


**Subject:** Cloud+  
**Page Label:** 3  
**Lock:** Unlocked  
**Status:**  
**Checkmark:** Unchecked  
**Author:** dsdlaforce  
**Date:** 6/20/2017 1:40:29 PM  
**Color:** ■

Add title

El Paso County  
Add to accordance with the requirements of the Drainage Criteria Manual 1.1.2.1.1.1.1.  
Revised by Jennifer Irvine, P.E.  
El Paso County  
El Paso County  
El Paso County


**Subject:** Cloud+  
**Page Label:** 6  
**Lock:** Unlocked  
**Status:**  
**Checkmark:** Unchecked  
**Author:** dsdlaforce  
**Date:** 6/20/2017 1:45:18 PM  
**Color:** ■

Revise to map unit 92 as shown on the NRCS soils map.




**Subject:** Cloud+  
**Page Label:** 8  
**Lock:** Unlocked  
**Status:**  
**Checkmark:** Unchecked  
**Author:** dsdlaforce  
**Date:** 6/26/2017 9:10:48 AM  
**Color:** ■

Revise. Construction plans show 836 ft (sta 16+75 to 25+11) from fil 3 to cul-de-sac bulb center



**Subject:** Callout  
**Page Label:** 8  
**Lock:** Unlocked  
**Status:**  
**Checkmark:** Unchecked  
**Author:** dsdlaforce  
**Date:** 6/26/2017 9:10:50 AM  
**Color:** ■

Add a section addressing water quality. Describe why water quality is not required. See ECM I.7.1.B for the specific criteria.




**Subject:** Callout  
**Page Label:** 9  
**Lock:** Unlocked  
**Status:**  
**Checkmark:** Unchecked  
**Author:** dsdlaforce  
**Date:** 6/26/2017 9:11:12 AM  
**Color:** ■

Provide calculation for the ditches. See Table 10-4 of the DCM for permissible velocity. If the seed is similar to grass-legume mixture then permissible velocity is 4 fps for channel slope between 0-5% and 3fps for 5-10% slope.




**Subject:** Callout  
**Page Label:** 10  
**Lock:** Unlocked  
**Status:**  
**Checkmark:** Unchecked  
**Author:** dsdlaforce  
**Date:** 6/26/2017 9:11:24 AM  
**Color:** ■

Review of the June 2016 Preliminary Drainage Report shows an increase in flows at the ultimate release point. Also, based on rough estimate Fil 3 & 4 creates around 6 acres of impervious land (17 lots @ 11% imp = 4.7 ac and 2300 lf @ 28' wide asphalt road = 1.5 ac) which could result in approximately 2 ac-ft of detention. Therefore, detention seems to be required for the overall development so the ultimate release is at or below historic rate.



**Subject:** Cloud+  
**Page Label:** 30  
**Lock:** Unlocked  
**Status:**  
**Checkmark:** Unchecked  
**Author:** dsdlaforce  
**Date:** 6/20/2017 2:51:07 PM  
**Color:** ■

Combined flow must be for the total flows (including offsite flows) draining to the design point. similar comment for developed calculations.



**Subject:** Cloud+  
**Page Label:** 33  
**Lock:** Unlocked  
**Status:**  
**Checkmark:** Unchecked  
**Author:** dsdlaforce  
**Date:** 6/21/2017 1:45:43 PM  
**Color:** ■

Revise Jurisdiction to EPC (typ)



---

**Subject:** Callout  
**Page Label:** 37  
**Lock:** Unlocked  
**Status:**  
**Checkmark:** Unchecked  
**Author:** dsdlaforce  
**Date:** 6/26/2017 9:11:38 AM  
**Color:** ■

The combined flow runoff calculation worksheet needs to show how this value was calculated. With no proposed detention and an increase in imperviousness this should be greater than the existing condition. Comment also applies to the existing condition.