

PROJECT INFORMATION							
Homestead North Filing No. 3		8/1/2022		SFXXX			
Project Name		Date		PCD File No.			
Description	Quantity	Units	Unit Cost		Total	(with Pre-Plat Construction) % Complete	Remaining
<b>SECTION 1 - GRADING AND EROSION CONTROL (Construction and Permanent BMPs)</b>							
* Earthwork							
less than 1,000; \$5,300 min		CY	\$ 8.00	=	\$ -		\$ -
1,000-5,000; \$8,000 min		CY	\$ 6.00	=	\$ -		\$ -
5,001-20,000; \$30,000 min		CY	\$ 5.00	=	\$ -		\$ -
20,001-50,000; \$100,000 min		CY	\$ 3.50	=	\$ -		\$ -
50,001-200,000; \$175,000 min (Fill)	117,573	CY	\$ 2.50	=	\$ 293,932.50		\$ 293,932.50
greater than 200,000; \$500,000 min		CY	\$ 2.00	=	\$ -		\$ -
* Permanent Seeding (inc. noxious weed mgmnt.)	31	AC	\$ 886.00	=	\$ 27,200.20		\$ 27,200.20
* Mulching	31	AC	\$ 831.00	=	\$ 25,761.00		\$ 25,761.00
* Permanent Erosion Control Blanket	78	SY	\$ 7.00	=	\$ 546.00		\$ 546.00
* Permanent Pond/BMP Construction		CY	\$ 22.00	=	\$ -		\$ -
* Permanent Pond/BMP (provide engineer's estimate)	1	EA	\$ 40,000.00	=	\$ 40,000.00		\$ 40,000.00
		EA		=	\$ -		\$ -
Safety Fence		LF	\$ 3.00	=	\$ -		\$ -
Temporary Erosion Control Blanket		SY	\$ 3.00	=	\$ -		\$ -
Vehicle Tracking Control	3	EA	\$ 2,625.00	=	\$ 7,875.00		\$ 7,875.00
Construction Fence	1,647	LF	\$ 3.00	=	\$ 4,941.00		\$ 4,941.00
Silt Fence	4,138	LF	\$ 3.00	=	\$ 12,414.00		\$ 12,414.00
Temporary Seeding	0	AC	\$ 695.00	=	\$ -		\$ -
Temporary Mulch	0	AC	\$ 831.00	=	\$ -		\$ -
Erosion Bales		EA	\$ 28.00	=	\$ -		\$ -
Erosion Logs/Straw Waddle	9,486	LF	\$ 6.00	=	\$ 56,916.00		\$ 56,916.00
Rock Check Dams	3	EA	\$ 554.00	=	\$ 1,662.00		\$ 1,662.00
Temporary Slope Drain	0	LF	\$ 30.00	=	\$ -		\$ -
Inlet Protection	7	EA	\$ 185.00	=	\$ 1,295.00		\$ 1,295.00
Sediment Basin	3	EA	\$ 1,952.00	=	\$ 5,856.00		\$ 5,856.00
Diversion Ditch	6,842	LF	\$ 2.00	=	\$ 13,684.00		\$ 13,684.00
Stabalized Staging Area	3,068	SY	\$ 3.00	=	\$ 9,204.00		\$ 9,204.00
Concrete Washout Basin	1	EA	\$ 997.00	=	\$ 997.00		\$ 997.00
				=	\$ -		\$ -
[insert items not listed but part of construction plans]				=	\$ -		\$ -
<b>MAINTENANCE (35% of Construction BMPs)</b>				=	\$ 40,195.40		\$ 40,195.40
* - Subject to defect warranty financial assurance. A minimum of 20% shall be retained until final acceptance (MAXIMUM OF 80% COMPLETE ALLOWED)							
<b>Section 1 Subtotal</b>				=	<b>\$ 542,479.10</b>		<b>\$ 542,479.10</b>
<b>SECTION 2 - PUBLIC IMPROVEMENTS *</b>							
<b>ROADWAY IMPROVEMENTS</b>							
Construction Traffic Control	1	LS	\$ 5,000.00	=	\$ 5,000.00		\$ 5,000.00
Aggregate Base Course (135 lbs/cf)		Tons	\$ 31.00	=	\$ -		\$ -
Aggregate Base Course (135 lbs/cf) (8" thick)	3,919	CY	\$ 56.00	=	\$ 219,464.00		\$ 219,464.00
Asphalt Pavement (3" thick)		SY	\$ 16.00	=	\$ -		\$ -
Asphalt Pavement (4" thick)	17,814	SY	\$ 21.00	=	\$ 374,094.00		\$ 374,094.00
Asphalt Pavement (6" thick)		SY	\$ 32.00	=	\$ -		\$ -
Asphalt Pavement (147 lbs/cf) _" thick		Tons	\$ 97.00	=	\$ -		\$ -
Raised Median, Paved		SF	\$ 9.00	=	\$ -		\$ -
Regulatory Sign/Advisory Sign	9	EA	\$ 333.00	=	\$ 2,997.00		\$ 2,997.00
Guide/Street Name Sign	7	EA	\$ 200.00	=	\$ 1,400.00		\$ 1,400.00
Epoxy Pavement Marking		SF	\$ 15.00	=	\$ -		\$ -
Thermoplastic Pavement Marking		SF	\$ 26.00	=	\$ -		\$ -
Barricade - Type 3		EA	\$ 221.00	=	\$ -		\$ -
Delineator - Type I		EA	\$ 27.00	=	\$ -		\$ -
Curb and Gutter, Type A (6" Vertical)	3,094	LF	\$ 32.00	=	\$ 99,008.00		\$ 99,008.00
Curb and Gutter, Type B (Median)		LF	\$ 32.00	=	\$ -		\$ -
Curb and Gutter, Type C (Ramp)	6,415	LF	\$ 32.00	=	\$ 205,280.00		\$ 205,280.00
4" Sidewalk (common areas only)		SY	\$ 53.00	=	\$ -		\$ -
5" Sidewalk	5,851	SY	\$ 66.00	=	\$ 386,152.80		\$ 386,152.80
6" Sidewalk		SY	\$ 80.00	=	\$ -		\$ -
8" Sidewalk		SY	\$ 106.00	=	\$ -		\$ -
Pedestrian Ramp	27	EA	\$ 1,273.00	=	\$ 34,371.00		\$ 34,371.00
Cross Pan, local (8" thick, 6' wide to include return)	238	LF	\$ 67.00	=	\$ 15,946.00		\$ 15,946.00
Cross Pan, collector (9" thick, 8' wide to include return)		LF	\$ 102.00	=	\$ -		\$ -
Curb Chase		EA	\$ 1,639.00	=	\$ -		\$ -
Guardrail Type 3 (W-Beam)		LF	\$ 55.00	=	\$ -		\$ -
Guardrail Type 7 (Concrete)		LF	\$ 80.00	=	\$ -		\$ -
Guardrail End Anchorage		EA	\$ 2,324.00	=	\$ -		\$ -
Guardrail Impact Attenuator		EA	\$ 4,172.00	=	\$ -		\$ -
Sound Barrier Fence (CMU block, 6' high)		LF	\$ 87.00	=	\$ -		\$ -
Sound Barrier Fence (panels)	1,200	LF	\$ 65.00	=	\$ 78,000.00		\$ 78,000.00
Electrical Conduit, Size =		LF	\$ 18.00	=	\$ -		\$ -
Traffic Signal, complete intersection		EA	\$ 470,666	=	\$ -		\$ -

**PROJECT INFORMATION**

**Homestead North Filing No. 3**

**8/1/2022**

**SFXXX**

**Project Name**

**Date**

**PCD File No.**

Description	Quantity	Units	Unit Cost		Total	(with Pre-Plat Construction)	
						% Complete	Remaining
[insert items not listed but part of construction plans]				=	\$ -		\$ -
[insert items not listed but part of construction plans]				=	\$ -		\$ -
<b>STORM DRAIN IMPROVEMENTS</b>							
Concrete Box Culvert (M Standard), Size ( W x H )		LF		=	\$ -		\$ -
18" Reinforced Concrete Pipe		LF	\$ 70.00	=	\$ -		\$ -
24" Reinforced Concrete Pipe	402	LF	\$ 83.00	=	\$ 33,366.00		\$ 33,366.00
30" Reinforced Concrete Pipe	8	LF	\$ 104.00	=	\$ 832.00		\$ 832.00
36" Reinforced Concrete Pipe	350	LF	\$ 128.00	=	\$ 44,800.00		\$ 44,800.00
42" Reinforced Concrete Pipe	28	LF	\$ 171.00	=	\$ 4,788.00		\$ 4,788.00
48" Reinforced Concrete Pipe		LF	\$ 209.00	=	\$ -		\$ -
54" Reinforced Concrete Pipe		LF	\$ 272.00	=	\$ -		\$ -
60" Reinforced Concrete Pipe		LF	\$ 319.00	=	\$ -		\$ -
66" Reinforced Concrete Pipe		LF	\$ 368.00	=	\$ -		\$ -
72" Reinforced Concrete Pipe		LF	\$ 421.00	=	\$ -		\$ -
18" Corrugated Steel Pipe		LF	\$ 90.00	=	\$ -		\$ -
24" Corrugated Steel Pipe		LF	\$ 103.00	=	\$ -		\$ -
30" Corrugated Steel Pipe		LF	\$ 131.00	=	\$ -		\$ -
36" Corrugated Steel Pipe		LF	\$ 157.00	=	\$ -		\$ -
42" Corrugated Steel Pipe		LF	\$ 180.00	=	\$ -		\$ -
48" Corrugated Steel Pipe		LF	\$ 190.00	=	\$ -		\$ -
54" Corrugated Steel Pipe		LF	\$ 278.00	=	\$ -		\$ -
60" Corrugated Steel Pipe		LF	\$ 300.00	=	\$ -		\$ -
66" Corrugated Steel Pipe		LF	\$ 364.00	=	\$ -		\$ -
72" Corrugated Steel Pipe		LF	\$ 428.00	=	\$ -		\$ -
78" Corrugated Steel Pipe		LF	\$ 492.00	=	\$ -		\$ -
84" Corrugated Steel Pipe		LF	\$ 492.01	=	\$ -		\$ -
Flared End Section (FES) RCP Size = (unit cost = 6x pipe unit cost)		EA		=	\$ -		\$ -
Flared End Section (FES) CSP Size = (unit cost = 6x pipe unit cost)		EA		=	\$ -		\$ -
End Treatment- Headwall		EA		=	\$ -		\$ -
End Treatment- Wingwall		EA		=	\$ -		\$ -
End Treatment - Cutoff Wall		EA		=	\$ -		\$ -
Curb Inlet (Type R) L=5', Depth < 5'		EA	\$ 6,138.00	=	\$ -		\$ -
Curb Inlet (Type R) L=5', 5' ≤ Depth < 10'		EA	\$ 7,981.00	=	\$ -		\$ -
Curb Inlet (Type R) L=5', 10' ≤ Depth < 15'		EA	\$ 9,242.00	=	\$ -		\$ -
Curb Inlet (Type R) L=10', Depth < 5'		EA	\$ 8,447.00	=	\$ -		\$ -
Curb Inlet (Type R) L=10', 5' ≤ Depth < 10'		EA	\$ 8,706.00	=	\$ -		\$ -
Curb Inlet (Type R) L=10', 10' ≤ Depth < 15'		EA	\$ 10,898.00	=	\$ -		\$ -
Curb Inlet (Type R) L=15', Depth < 5'	5	EA	\$ 10,984.00	=	\$ 54,920.00		\$ 54,920.00
Curb Inlet (Type R) L=15', 5' ≤ Depth < 10'		EA	\$ 11,775.00	=	\$ -		\$ -
Curb Inlet (Type R) L=15', 10' ≤ Depth < 15'		EA	\$ 12,876.00	=	\$ -		\$ -
Curb Inlet (Type R) L=20', Depth < 5'	1	EA	\$ 11,706.00	=	\$ 11,706.00		\$ 11,706.00
Curb Inlet (Type R) L=20', 5' ≤ Depth < 10'		EA	\$ 12,920.00	=	\$ -		\$ -
Grated Inlet (Type C), Depth < 5'		EA	\$ 5,138.00	=	\$ -		\$ -
Grated Inlet (Type D), Depth < 5'		EA	\$ 6,347.00	=	\$ -		\$ -
Storm Sewer Manhole, Box Base	2	EA	\$ 12,876.00	=	\$ 25,752.00		\$ 25,752.00
Storm Sewer Manhole, Slab Base	1	EA	\$ 7,082.00	=	\$ 7,082.00		\$ 7,082.00
Geotextile (Erosion Control)		SY	\$ 7.00	=	\$ -		\$ -
Rip Rap, d50 size from 6" to 24"		Tons	\$ 89.00	=	\$ -		\$ -
Rip Rap, Grouted		Tons	\$ 105.00	=	\$ -		\$ -
Drainage Channel Construction, Size ( W x H )		LF		=	\$ -		\$ -
Drainage Channel Lining, Concrete		CY	\$ 631.00	=	\$ -		\$ -
Drainage Channel Lining, Rip Rap		CY	\$ 124.00	=	\$ -		\$ -
Drainage Channel Lining, Grass		AC	\$ 1,626.00	=	\$ -		\$ -
Drainage Channel Lining, Other Stabilization				=	\$ -		\$ -
[insert items not listed but part of construction plans]				=	\$ -		\$ -
Section 2 Subtotal				=	\$ 1,604,958.80		\$ 1,604,958.80

\* - Subject to defect warranty financial assurance. A minimum of 20% shall be retained until final acceptance (MAXIMUM OF 80% COMPLETE ALLOWED)

**PROJECT INFORMATION**

<b>Homestead North Filing No. 3</b>	<b>8/1/2022</b>	<b>SFXXX</b>
<b>Project Name</b>	<b>Date</b>	<b>PCD File No.</b>

Description	Quantity	Units	Unit Cost		Total	(with Pre-Plat Construction) % Complete	Remaining
<b>SECTION 3 - COMMON DEVELOPMENT IMPROVEMENTS (Private or District and NOT Maintained by EPC)**</b>							
<b>ROADWAY IMPROVEMENTS</b>							
				=	\$ -		\$ -
				=	\$ -		\$ -
				=	\$ -		\$ -
				=	\$ -		\$ -
				=	\$ -		\$ -
				=	\$ -		\$ -
<b>STORM DRAIN IMPROVEMENTS</b> (Exception: Permanent Pond/BMP shall be itemized under Section 1)							
18" Reinforced Concrete Pipe	230	LF	\$ 70.00	=	\$ 16,100.00		\$ 16,100.00
42" Reinforced Concrete Pipe	156	LF	\$ 171.00	=	\$ 26,676.00		\$ 26,676.00
Flared End Section (FES) RCP Size = 18" (unit cost = 6x pipe unit cost)	1	EA	\$ 420.00	=	\$ 420.00		\$ 420.00
Drainage Channel Lining, Rip Rap 12" depth	111	CY	\$ 124.00	=	\$ 13,764.00		\$ 13,764.00
Rip Rap, d50 size from 6" to 24"	7	CY	\$ 124.00	=	\$ 868.00		\$ 868.00
Grated Inlet (Type C), Depth < 5'		EA	\$ 5,138.00	=	\$ -		\$ -
<b>WATER SYSTEM IMPROVEMENTS</b>							
				=	\$ -		\$ -
[insert items not listed but part of construction plans]				=	\$ -		\$ -
<b>SANITARY SEWER IMPROVEMENTS</b>							
				=	\$ -		\$ -
[insert items not listed but part of construction plans]				=	\$ -		\$ -
<b>LANDSCAPING IMPROVEMENTS</b> (For subdivision specific condition of approval, or PUD)							
Landscaping Improvments	1	EA	\$ 150,000.00	=	\$ 150,000.00		\$ 150,000.00
		EA		=	\$ -		\$ -
		EA		=	\$ -		\$ -
		EA		=	\$ -		\$ -
		EA		=	\$ -		\$ -
<b>Section 3 Subtotal</b>				=	<b>\$ 207,828.00</b>		<b>\$ 207,828.00</b>

\*\* - Section 3 is not subject to defect warranty requirements

**PROJECT INFORMATION**

<b>Homestead North Filing No. 3</b>	<b>8/1/2022</b>	<b>SFXXX</b>
<b>Project Name</b>	<b>Date</b>	<b>PCD File No.</b>

Description	Quantity	Units	Unit Cost		Total	(with Pre-Plat Construction) % Complete	Remaining
AS-BUILT PLANS (Public Improvements inc. Permanent WQCV BMPs)		LS	\$ 10,000.00	=	\$ 10,000.00		\$ 10,000.00
POND/BMP CERTIFICATION (inc. elevations and volume calculations)		LS	\$ 10,000.00	=	\$ 10,000.00		\$ 10,000.00
<b>Total Construction Financial Assurance</b>						<b>\$</b>	<b>2,375,265.90</b>
(Sum of all section subtotals plus as-builts and pond/BMP certification)							
<b>Total Remaining Construction Financial Assurance (with Pre-Plat Construction)</b>						<b>\$</b>	<b>2,375,265.90</b>
(Sum of all section totals less credit for items complete plus as-builts and pond/BMP certification)							
<b>Total Defect Warranty Financial Assurance</b>						<b>\$</b>	<b>398,479.70</b>
(20% of all items identified as (*). To be collateralized at time of preliminary acceptance)							

**Approvals**

I hereby certify that this is an accurate and complete estimate of costs for the work as shown on the Grading and Erosion Control Plan and Construction Drawings associated with the Project.

\_\_\_\_\_  
Engineer (P.E. Seal Required)

\_\_\_\_\_  
Approved by Owner / Applicant

\_\_\_\_\_  
Date

\_\_\_\_\_  
Approved by El Paso County Engineer / ECM Administrator

\_\_\_\_\_  
Date