
GRADING AND EROSION CONTROL NOTES:

- 1. STORMWATER DISCHARGES FROM CONSTRUCTION SITES SHALL NOT CAUSE OR THREATEN TO CAUSE POLLUTION, CONTAMINATION, OR DEGRADATION OF STATE WATERS. ALL WORK AND EARTH DISTURBANCE SHALL BE DONE IN A MANNER THAT MINIMIZES POLLUTION OF ANY **ON-SITE OR OFF-SITE WATERS, INCLUDING WETLANDS.**
- 2. NOTWITHSTANDING ANYTHING DEPICTED IN THESE PLANS IN WORDS OR GRAPHIC REPRESENTATION, ALL DESIGN AND CONSTRUCTION RELATED TO ROADS, STORM DRAINAGE AND EROSION CONTROL SHALL CONFORM TO THE STANDARDS AND REQUIREMENTS
- 3. A SEPARATE STORMWATER MANAGEMENT PLAN (SMWP) FOR THIS PROJECT SHALL BE COMPLETED AND AN EROSION AND STORMWATER QUALITY CONTROL PERMIT (ESQCP) ISSUED PRIOR TO COMMENCING CONSTRUCTION. MANAGEMENT OF THE SWMP DURING CONSTRUCTION IS THE RESPONSIBILITY OF THE DESIGNATED QUALIFIED STORMWATER MANAGER OR CERTIFIED EROSION CONTROL INSPECTOR. THE SWMP SHALL BE LOCATED ON-SITE AT ALL TIMES DURING CONSTRUCTION AND SHALL BE KEPT UP TO DATE WITH WORK PROGRESS AND CHANGES IN THE FIELD.
- ONCE THE ESQCP IS APPROVED AND A "NOTICE TO PROCEED" HAS BEEN ISSUED, THE CONTRACTOR MAY INSTALL THE INITIAL STAGE EROSION AND SEDIMENT CONTROL MEASURES AS INDICATED ON THE APPROVED GEC. A PRECONSTRUCTION MEETING BETWEEN THE CONTRACTOR, ENGINEER, AND EL PASO COUNTY WILL BE HELD PRIOR TO ANY CONSTRUCTION. IT IS THE RESPONSIBILITY OF THE APPLICANT TO COORDINATE THE MEETING TIME AND PLACE WITH COUNTY STAFF.
- CONTROL MEASURES MUST BE INSTALLED PRIOR TO COMMENCEMENT OF ACTIVITIES THAT COULD CONTRIBUTE POLLUTANTS TO STORMWATER. CONTROL MEASURES FOR ALL SLOPES, CHANNELS, DITCHES, AND DISTURBED LAND AREAS SHALL BE INSTALLED IMMEDIATELY UPON COMPLETION OF THE DISTURBANCE.
- 6. ALL TEMPORARY SEDIMENT AND EROSION CONTROL MEASURES SHALL BE MAINTAINED AND REMAIN IN EFFECTIVE OPERATING CONDITION UNTIL PERMANENT SOIL EROSION CONTROL MEASURES ARE IMPLEMENTED AND FINAL STABILIZATION IS ESTABLISHED. ALL PERSONS ENGAGED IN LAND DISTURBANCE ACTIVITIES SHALL ASSESS THE ADEQUACY OF CONTROL MEASURES AT THE SITE AND IDENTIFY IF CHANGES TO THOSE CONTROL MEASURES ARE NEEDED TO ENSURE THE CONTINUED EFFECTIVE PERFORMANCE OF THE CONTROL MEASURES. ALL CHANGES TO TEMPORARY SEDIMENT AND EROSION CONTROL MEASURES MUST BE INCORPORATED INTO THE STORMWATER MANAGEMENT PLAN.
- TEMPORARY STABILIZATION SHALL BE IMPLEMENTED ON DISTURBED AREAS AND STOCKPILES WHERE GROUND DISTURBING CONSTRUCTION ACTIVITY HAS PERMANENTLY CEASED OR TEMPORARILY CEASED FOR LONGER THAN 14 DAYS.
- 8. FINAL STABILIZATION MUST BE IMPLEMENTED AT ALL APPLICABLE CONSTRUCTION SITES. FINAL STABILIZATION IS ACHIEVED WHEN ALL GROUND DISTURBING ACTIVITIES ARE COMPLETE AND ALL DISTURBED AREAS EITHER HAVE A UNIFORM VEGETATIVE COVER WITH INDIVIDUAL PLANT DENSITY OF 70 PERCENT OF PRE-DISTURBANCE LEVELS ESTABLISHED OR EQUIVALENT PERMANENT ALTERNATIVE STABILIZATION METHOD IS IMPLEMENTED. ALL TEMPORARY SEDIMENT AND EROSION CONTROL MEASURES SHALL BE REMOVED UPON FINAL STABILIZATION AND BEFORE PERMIT CLOSURE.
- 9. ALL PERMANENT STORMWATER MANAGEMENT FACILITIES SHALL BE INSTALLED AS DESIGNED IN THE APPROVED PLANS. ANY PROPOSED CHANGES THAT EFFECT THE DESIGN OR FUNCTION OF PERMANENT STORMWATER MANAGEMENT STRUCTURES MUST BE APPROVED BY THE ECM ADMINISTRATOR PRIOR TO IMPLEMENTATION
- 10. EARTH DISTURBANCES SHALL BE CONDUCTED IN SUCH A MANNER SO AS TO EFFECTIVELY MINIMIZE ACCELERATED SOIL EROSION AND RESULTING SEDIMENTATION. ALL DISTURBANCES SHALL BE DESIGNED, CONSTRUCTED, AND COMPLETED SO THAT THE EXPOSED AREA OF ANY DISTURBED LAND SHALL BE LIMITED TO THE SHORTEST PRACTICAL PERIOD OF TIME. PRE-EXISTING VEGETATION SHALL BE PROTECTED AND MAINTAINED WITHIN 50 HORIZONTAL FEET OF A WATERS OF THE STATE UNLESS SHOWN TO BE INFEASIBLE AND SPECIFICALLY REQUESTED AND APPROVED.
- 11. COMPACTION OF SOIL MUST BE PREVENTED IN AREAS DESIGNATED FOR INFILTRATION CONTROL MEASURES OR WHERE FINAL STABILIZATION WILL BE ACHIEVED BY VEGETATIVE COVER. AREAS DESIGNATED FOR INFILTRATION CONTROL MEASURES SHALL ALSO BE PROTECTED FROM SEDIMENTATION DURING CONSTRUCTION UNTIL FINAL STABILIZATION IS ACHIEVED. IF COMPACTION PREVENTION IS NOT FEASIBLE DUE TO SITE CONSTRAINTS, ALL AREAS DESIGNATED FOR INFILTRATION AND VEGETATION CONTROL MEASURES MUST BE LOOSENED PRIOR TO INSTALLATION OF THE CONTROL MEASURE(S).
- 12. ANY TEMPORARY OR PERMANENT FACILITY DESIGNED AND CONSTRUCTED FOR THE CONVEYANCE OF STORMWATER AROUND. THROUGH. OR FROM THE EARTH DISTURBANCE AREA SHALL BE A STABILIZED CONVEYANCE DESIGNED TO MINIMIZE EROSION AND THE DISCHARGE OF SEDIMENT OFF-SITE.
- 13. CONCRETE WASH WATER SHALL BE CONTAINED AND DISPOSED OF IN ACCORDANCE WITH THE SWMP. NO WASH WATER SHALL BE DISCHARGED TO OR ALLOWED TO ENTER STATE WATERS, INCLUDING ANY SURFACE OR SUBSURFACE STORM DRAINAGE SYSTEM OR FACILITIES. CONCRETE WASHOUTS SHALL NOT BE LOCATED IN AN AREA WHERE SHALLOW GROUNDWATER MAY BE PRESENT, OR WITHIN 50 FEET OF A SURFACE WATER BODY, CREEK OR STREAM.
- 14. DURING DEWATERING OPERATIONS, UNCONTAMINATED GROUNDWATER MAY BE DISCHARGED ON-SITE, BUT SHALL NOT LEAVE THE SITE IN THE FORM OF SURFACE RUNOFF UNLESS AN APPROVED STATE DEWATERING PERMIT IS IN PLACE.
- 15. EROSION CONTROL BLANKETING OR OTHER PROTECTIVE COVERING SHALL BE USED ON SLOPES STEEPER THAN 3:1.
- 16. CONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL OF ALL WASTES FROM THE CONSTRUCTION SITE FOR DISPOSAL IN ACCORDANCE WITH LOCAL AND STATE REGULATORY REQUIREMENTS. NO CONSTRUCTION DEBRIS, TREE SLASH, BUILDING MATERIAL WASTES OR UNUSED BUILDING MATERIALS SHALL BE BURIED. DUMPED. OR DISCHARGED AT THE SITE.
- 17. WASTE MATERIALS SHALL NOT BE TEMPORARILY PLACED OR STORED IN THE STREET, ALLEY, OR OTHER PUBLIC WAY, UNLESS IN ACCORDANCE WITH AN APPROVED TRAFFIC CONTROL PLAN. CONTROL MEASURES MAY BE REQUIRED BY EL PASO COUNTY ENGINEERING IF DEEMED NECESSARY, BASED ON SPECIFIC CONDITIONS AND CIRCUMSTANCES.
- 18. TRACKING OF SOILS AND CONSTRUCTION DEBRIS OFF-SITE SHALL BE MINIMIZED. MATERIALS TRACKED OFF-SITE SHALL BE CLEANED UP AND PROPERLY DISPOSED OF IMMEDIATELY.
- 19. THE OWNER/DEVELOPER SHALL BE RESPONSIBLE FOR THE REMOVAL OF ALL CONSTRUCTION DEBRIS, DIRT, TRASH, ROCK, SEDIMENT, SOIL, AND SAND THAT MAY ACCUMULATE IN ROADS, STORM DRAINS AND OTHER DRAINAGE CONVEYANCE SYSTEMS AND STORMWATER APPURTENANCES AS A RESULT OF SITE DEVELOPMENT.
- 20. THE QUANTITY OF MATERIALS STORED ON THE PROJECT SITE SHALL BE LIMITED, AS MUCH AS PRACTICAL, TO THAT QUANTITY REQUIRED TO PERFORM THE WORK IN AN ORDERLY SEQUENCE. ALL MATERIALS STORED ON-SITE SHALL BE STORED IN A NEAT, ORDERLY MANNER, IN THEIR ORIGINAL CONTAINERS, WITH ORIGINAL MANUFACTURER'S LABELS.
- 21. NO CHEMICAL(S) HAVING THE POTENTIAL TO BE RELEASED IN STORMWATER ARE TO BE STORED OR USED ON-SITE UNLESS PERMISSION FOR THE USE OF SUCH CHEMICAL(S) IS GRANTED IN WRITING BY THE ECM ADMINISTRATOR. IN GRANTING APPROVAL FOR THE USE OF SUCH CHEMICAL(S), SPECIAL CONDITIONS AND MONITORING MAY BE REQUIRED.
- 22. BULK STORAGE OF ALLOWED PETROLEUM PRODUCTS OR OTHER ALLOWED LIQUID CHEMICALS IN EXCESS OF 55 GALLONS SHALL REQUIRE ADEQUATE SECONDARY CONTAINMENT PROTECTION TO CONTAIN ALL SPILLS ON-SITE AND TO PREVENT ANY SPILLED MATERIALS FROM ENTERING STATE WATERS. ANY SURFACE OR SUBSURFACE STORM DRAINAGE SYSTEM OR OTHER FACILITIES.
- 23. NO PERSON SHALL CAUSE THE IMPEDIMENT OF STORMWATER FLOW IN THE CURB AND GUTTER OR DITCH EXCEPT WITH APPROVED SEDIMENT CONTROL MEASURES.
- 24. OWNER/DEVELOPER AND THEIR AGENTS SHALL COMPLY WITH THE "COLORADO WATER QUALITY CONTROL ACT" (TITLE 25, ARTICLE 8, CRS), AND THE "CLEAN WATER ACT" (33 USC 1344), IN ADDITION TO THE REQUIREMENTS OF THE LAND DEVELOPMENT CODE, DCM VOLUME II AND THE ECM APPENDIX I. ALL APPROPRIATE PERMITS MUST BE OBTAINED BY THE CONTRACTOR PRIOR TO CONSTRUCTION (1041, NPDES, FLOODPLAIN, 404, FUGITIVE DUST, ETC.). IN THE EVENT OF CONFLICTS BETWEEN THESE REQUIREMENTS AND OTHER LAWS, RULES, OR REGULATIONS OF OTHER FEDERAL, STATE, LOCAL, OR COUNTY AGENCIES, THE MOST RESTRICTIVE LAWS, RULES, OR REGULATIONS SHALL APPLY.
- 25. ALL CONSTRUCTION TRAFFIC MUST ENTER/EXIT THE SITE ONLY AT APPROVED CONSTRUCTION ACCESS POINTS.
- 26. PRIOR TO CONSTRUCTION THE PERMITTEE SHALL VERIFY THE LOCATION OF EXISTING UTILITIES.
- 27. A WATER SOURCE SHALL BE AVAILABLE ON-SITE DURING EARTHWORK OPERATIONS AND SHALL BE UTILIZED AS REQUIRED TO MINIMIZE DUST FROM EARTHWORK EQUIPMENT AND WIND.
- 28. THE SOILS REPORT FOR THIS SITE HAS BEEN PREPARED BY ENTECH ENGINEERING, INC., DATED 3/25/2024 AND SHALL BE CONSIDERED A PART OF THESE PLANS.

29. AT LEAST TEN (10) DAYS PRIOR TO THE ANTICIPATED START OF CONSTRUCTION, FOR PROJECTS THAT WILL DISTURB ONE (1) ACRE OR MORE, THE OWNER OR OPERATOR OF CONSTRUCTION ACTIVITY SHALL SUBMIT A PERMIT APPLICATION FOR STORMWATER DISCHARGE TO THE COLORADO DEPARTMENT OF PUBLIC HEALTH AND ENVIRONMENT, WATER QUALITY DIVISION. THE APPLICATION CONTAINS CERTIFICATION OF COMPLETION OF A STORMWATER MANAGEMENT PLAN (SWMP), OF WHICH THIS GRADING AND EROSION CONTROL PLAN MAY BE A PART. FOR INFORMATION OR APPLICATION MATERIALS CONTACT: COLORADO DEPARTMENT OF PUBLIC HEALTH AND ENVIRONMENT WATER QUALITY CONTROL DIVISION WQCD – PERMITS 4300 CHERRY CREEK DRIVE SOUTH DENVER, CO 80246-1530 ATTN: PERMITS UNIT

ROLLING THUNDER BUSINESS PARK, LOT 12 10707 MALTESE POINT EL PASO COUNTY, PEYTON, CO



LEGAL DESCRIPTION:

LOT 12, ROLLING THUNDER BUSINESS PARK, COUNTY OF EL PASO, STATE OF COLORADO.

BENCHMARK:


FIMS MONUMENT BL74 BEING A 3.25" FIMS CAP IN A RANGE BOX LOCATED AT THE NORTHWEST CORNER OF E. WOODMEN FRONTAGE ROAD AND FALCON MEADOWS BLVD. ELEVATION 6908.88 NAVD88

48 HOURS BEFORE YOU DIG, CALL UTILITY LOCATORS


811 UTILITY NOTIFICATION CENTER OF COLORADO IT'S THE LAW


THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK, THE CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE CAUSED BY HIS FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES.

	CONTACTS OWNER WT HOLDINGS, LLC 30 E. UINTAH ST. COLORADO SPRINGS, CO 809 BILL TIBBITT (719) 465-2519 BTIBBITT@WDCONSTRUCT.CO CIVIL ENGINEER SK DESIGN GROUP, INC. 333 PERRY ST. SUITE 209		
	 333 PERRY ST. SUITE 209 CASTLE ROCK, CO 80104 AUROM MAHOBIAN, P.E. (913) 451-1818 AMAHOBIAN@SKDG.COM ENGINEERING DIVISIO EL PASO COUNTY PLANNING 2880 INTERNATIONAL CIRCLE COLORADO SPRINGS, CO 809 JOSHUA PALMER, P.E. (719) 520-6300 WATER FALCON HIGHLANDS METRO I 121 SOUTH TEJON STREET, SI COLORADO SPRINGS, CO 809 (719) 635-0330 WASTEWATER WOODMAN HILLS METRO DIST 8046 EASTONVILLE RD. PEYTON, CO 80831 (719) 495-2500 FIRE DEPARTMENT 	AND COMMUNITY DEVELOPMENT , SUITE 110, 10 DISTRICT UITE 1100 03 TRICT	DER BUSINESS LOT 12 PT. PEYTON, CO
DIRECTION AND SUPERVIS AND BELIEF. SAID PLAN HA ESTABLISHED BY THE COU ACCEPT RESPONSIBILITY F	FALCON FIRE PROTECTION D 7080 OLD MERIDIAN RD. FALCON, CO 80831 (719) 495-4050 TELEPHONE COMPAN U.S. WEST COMMUNICATIONS (800) 922-1987 AT&T (LOCATORS) (719) 635-3674 IENT ON CONTROL PLAN WAS PREPARE ION AND IS CORRECT TO THE BEST IS BEEN PREPARED ACCORDING T NTY FOR GRADING AND EROSION FOR ANY LIABILITY CAUSED BY ANY N MY PART IN PREPARING THIS PLA	Y S (LOCATORS) D UNDER MY T OF MY KNOWLEDGE O THE CRITERIA CONTROL PLANS. I Y NEGLIGENT ACTS,	NULTING HULL NULTING HULL NULTI
OWNER'S STATEMEN i, THE OWNER/DEVELOPER REQUIREMENTS OF THE GR OWNER SIGNATURE EL PASO COUNTY:	HAVE READ AND WILL COMPLY WI RADING AND EROSION CONTROL P	TH THE LAN. 07-23-24 DATE	Castle Rock, Colorado 8010- Phone: 913-451-1818 Fax: 913-451-7599 BATE: 07-17-2024 DATE: 07-17-2024 DESIGNED: AM CHECKED: SM DESIGNED: AU DESIGNED: AM CHECKED: SM
COUNTY DESIGN CRITERIA ACCURACY AND ADEQUAC WHICH SHALL BE CONFIRM APPROVAL OF THIS DOCUM COMPLETENESS AND/OR A FILED IN ACCORDANCE WIT DEVELOPMENT CODE, DRA ENGINEERING CRITERIA MA IN ACCORDANCE WITH ECH WILL BE VALID FOR CONST SIGNED BY THE EL PASO C STARTED WITHIN THOSE 2 FOR APPROVAL, INCLUDING	PROVIDED ONLY FOR GENERAL CO THE COUNTY IS NOT RESPONSIBILY OF THE DESIGN, DIMENSIONS, A MED AT THE JOB SITE. THE COUNTY MENT ASSUMES NO RESPONSIBILIT CCURACY OF THIS DOCUMENT. TH THE REQUIREMENTS OF THE EL INAGE CRITERIA MANUAL VOLUME ANUAL, AS AMENDED. M SECTION 1.12, THESE CONSTRUCT RUCTION FOR A PERIOD OF 2 YEA OUNTY ENGINEER. IF CONSTRUCT YEARS, THE PLANS WILL NEED TO G PAYMENT OF REVIEW FEES AT TH T DIRECTOR'S DISCRETION.	LE FOR THE ND/OR ELEVATIONS Y THROUGH THE TY FOR PASO COUNTY LAND ES 1 AND 2, AND CTION DOCUMENTS RS FROM THE DATE ION HAS NOT BE RESUBMITTED	47162 47162 7/19/24 GESC COVER SHEET
JOSHUA PALMER, P COUNTY ENGINEER/		DATE	SHEET









Silt Fence (SF)	
NOTES PLACED AWAY FROM THE TOE OF THE SLOPE TO ALLOW FOR WATER THE TOE OF A SLOPE SHOULD BE INSTALLED IN A FLAT LOCATION (2-5 FT) FROM THE TOE OF THE SLOPE TO ALLOW ROOM FOR	
NCHOR TRENCH SHALL BE EXCAVATED USING TRENCHER OR SILT CE. NO ROAD GRADERS, BACKHOES, OR SIMILAR EQUIPMENT SHALL	
NCH BY HAND WITH A "JUMPING JACK" OR BY WHEEL ROLLING. JCH THAT SILT FENCE RESISTS BEING PULLED OUT OF ANCHOR PULLED TIGHT AS IT IS ANCHORED TO THE STAKES. THERE SHOULD	
SETWEEN STAKES AFTER IT HAS BEEN ANCHORED TO THE STAKES. ALL BE ANCHORED TO THE STAKES USING 1" HEAVY DUTY STAPLES . STAPLES AND NAILS SHOULD BE PLACED 3" ALONG THE FABRIC	
N OF SILT FENCE ALONG A CONTOUR, THE SILT FENCE SHOULD BE TO THE CONTOUR TO CREATE A "J-HOOK." THE "J-HOOK" R TO THE CONTOUR SHOULD BE OF SUFFICIENT LENGTH TO KEEP ROUND THE END OF THE SILT FENCE (TYPICALLY 10' – 20'). INSTALLED PRIOR TO ANY LAND DISTURBING ACTIVITIES.	DATE
NOTES VORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION. HOULD BE PROACTIVE, NOT REACTIVE. INSPECT BMP's AS SOON AS ITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE NECESSARY MAINTENANCE. NS AND MAINTENANCE ARE NECESSARY TO MAINTAIN BMP's IN NOTION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE	
Y. LED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON XE.	
D UPSTREAM OF THE SILT FENCE SHALL BE REMOVED AS NEEDED NAUTY OF THE BMP, TYPICALLY WHEN DEPTH OF ACCUMULATED ELY 6". ILT FENCE WHEN THERE ARE SIGNS OF WEAR, SUCH AS SAGGING,	REVISIONS
AIN IN PLACE UNTIL THE UPSTREAM DISTURBED AREA IS STABILIZED DCAL JURISDICTION, OR IS REPLACED BY AN EQUIVALENT PERIMETER	
YEMOVED, ALL DISTURBED AREAS SHALL BE COVERED WITH TOPSOIL, © OTHERWISE STABILIZED AS APPROVED BY LOCAL JURISDICTION. PARKER, COLORADO AND CITY OF AURORA, NOT AVAILABLE IN AUTOCAD)	
S HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. ISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN	S
rainage and Flood Control District November 2010 rm Drainage Criteria Manual Volume 3	С S Ш S S O
	N S N
ontrol Products (RECP) EC-6	BU 12 BU
IKET MAINTENANCE NOTES	
WORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION. SHOULD BE PROACTIVE, NOT REACTIVE. INSPECT BMPs AS SOON AS WITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE NECESSARY MAINTENNANCE.	
ONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN BMPs IN DIDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE LY.	
AILED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON JRE. IN PLACE TO EVENTUALLY BIODEGRADE, UNLESS REQUESTED TO BE JURISDICTION.	
T, TORN, OR OTHERWISE DAMAGED SHALL BE REPAIRED OR RADE AREAS BELOW THE GEOTEXTILE THAT HAVE ERODED TO CREATED VKET, OR THAT REMAIN DEVOID OF GRASS SHALL BE REPAIRED,) AND THE CEB REINSTALLED.	
NS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. INFISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN).	U U Z Z
IS COUNTY, COLORADO AND TOWN OF PARKER COLORADO, NOT AVAILABLE IN AUTOCAD)	
	107 JLL
	Ř
Drainage and Flood Control District RECP-9 rm Drainage Criteria Manual Volume 3	SK Design Group, Inc.
	333 Perry St, Suite 209 Castle Rock, Colorado 80104
<u> </u> 1−1/2"	Phone: 913-451-1818 Fax: 913-451-7599
	S S
18"	
FOR SPILL CURB)	24-105 CHECKED: APPROVED:
	NUMBER: 7-17-20. 1. AM
	D: FP
OR SPILL CURB) D - GUTTER CROSS SLOPES SHALL BE 1/2 IN./FT. WHEN	SK JC DATE: DESIG
C = GUTTER CROSS SLOPES SHALL BE 1/2 IN./FT. WHEN DRAINING AWAY FROM CURB AND 1 IN./FT. WHEN DRAINING TOWARD CURB (WTH EXCEPTION TO IMMEDIATELY ADJACENT TO CURB RAMPS - SEE CURB RAMP STANDARDS FOR SLOPE PEFCIUEFLEMTS	RADO LICENOD
et the terminal store store to the terminal store store to the terminal store ter	COL ON MAHOR E
	47162
	7/19/24
(6" RAMP CURB)	SSIONAL ENGLAS
SCALE: NOT TO SCALE Typical Curb and Gutter	
Details Standard Drawing	GESC
6/23/20 SD_2-20	DETAILS
	SHEET

3 OF 3