

2021 Financial Assurance Estimate Form (with pre-plat construction)

Updated: 12/22/2020

PROJECT INFORMATION			
Trails at Aspen Ridge Filing No. 5	10/21/2021		SF2138
Project Name	Date	PCD File No.	

Description	Quantity	Units	Unit Cost	Total	(with Pre-Plat Construction) % Complete	Remaining
SECTION 1 - GRADING AND EROSION CONTROL (Construction and Permanent BMPs)						
* Earthwork						
less than 1,000; \$5,300 min		CY	\$ 8.00	= \$ -		\$ -
1,000-5,000; \$8,000 min		CY	\$ 6.00	= \$ -		\$ -
5,001-20,000; \$30,000 min		CY	\$ 5.00	= \$ -		\$ -
20,001-50,000; \$100,000 min		CY	\$ 3.50	= \$ -		\$ -
50,001-200,000; \$175,000 min	93,783	CY	\$ 2.50	= \$ 234,457.50		\$ 234,457.50
greater than 200,000; \$500,000 min		CY	\$ 2.00	= \$ -		\$ -
* Permanent Seeding (inc. noxious weed mgmnt.)		AC	\$ 828.00	= \$ -		\$ -
* Mulching		AC	\$ 777.00	= \$ -		\$ -
* Permanent Erosion Control Blanket		SY	\$ 6.00	= \$ -		\$ -
* Permanent Pond/BMP Construction		CY	\$ 21.00	= \$ -		\$ -
* Permanent Pond/BMP (provide engineer's estimate)		EA	\$ 25,000.00	= \$ -		\$ -
* Permanent Pond/BMP (Outlet Structure - Micropool)		EA	\$ 15,000.00	= \$ -		\$ -
* Permanent Pond/BMP (Forebay)		EA	\$ 25,000.00	= \$ -		\$ -
* Permanent Pond/BMP (Concrete Low Flow Channel)		CY	\$ 570.00	= \$ -		\$ -
* Permanent Pond/BMP Rip Rap (d50 size from 6" to 24")		Tons	\$ 83.00	= \$ -		\$ -
Safety Fence		LF	\$ 3.00	= \$ -		\$ -
Temporary Erosion Control Blanket	5,572	SY	\$ 3.00	= \$ 16,716.00		\$ 16,716.00
Vehicle Tracking Control	2	EA	\$ 4,906.00	= \$ 9,812.00		\$ 9,812.00
Silt Fence	1,758	LF	\$ 2,711.40	= \$ 4,757.80		\$ 4,757.80
Temporary Seeding	10	AC	\$ 626.00	= \$ 6,266.00		\$ 6,266.00
Temporary Mulch		AC	\$ -	= \$ -		\$ -
Erosion Bales		EA	\$ -	= \$ -		\$ -
Erosion Logs/Straw Wattle	2,606	LF	\$ 5,041.00	= \$ 13,028.98		\$ 13,028.98
Rock Check Dams	58	EA	\$ 517.24	= \$ 30,044.00		\$ 30,044.00
Inlet Protection	2?	EA	\$ 173.00	= \$ -		\$ -
Sediment Basin		EA	\$ 1,824.00	= \$ -		\$ -
Concrete Washout Basin	1	EA	\$ 932.00	= \$ -		\$ -
Outlet Protection		EA	\$ 200.00	= \$ -		\$ -
<i>[insert items not listed but part of construction plans]</i>						
MAINTENANCE (35% of Construction BMPs)				= \$ 26,436.12		\$ 26,436.12
Section 1 Subtotal				= \$ 336,425.40		\$ 336,425.40

These are meant to be riprap check dams in swales. For gravel bags, use the row above this one.

provide mulching quantity equal to seeding. Move quantities to the permanent section.

SECTION 2 - PUBLIC IMPROVEMENTS *						
ROADWAY IMPROVEMENTS						
Construction Traffic Control		LS		= \$ -		\$ -
Aggregate Base Course (135 lbs/cf)		Tons	\$ 29.00	= \$ -		\$ -
Aggregate Base Course (135 lbs/cf)	3,294	CY	\$ 52.00	= \$ 171,288.00		\$ 171,288.00
Asphalt Pavement (3" thick)		SY	\$ 14.50	= \$ -		\$ -
Asphalt Pavement (4" thick)	4,942	SY	\$ 20.00	= \$ 98,840.00		\$ 98,840.00
Asphalt Pavement (6" thick)		SY	\$ 30.00	= \$ -		\$ -
Asphalt Pavement (147 lbs/cf) ___" thick		Tons	\$ 91.00	= \$ -		\$ -
Raised Median, Paved		SF	\$ 8.30	= \$ -		\$ -
Regulatory Sign/Advisory Sign	1	EA	\$ 311.00	= \$ 311.00		\$ 311.00
Guide/Street Name Sign	2	EA	\$ 250.00	= \$ 500.00		\$ 500.00
Epoxy Pavement Marking		SF	\$ 14.00	= \$ -		\$ -
Thermoplastic Pavement Marking		SF	\$ 24.00	= \$ -		\$ -
Barricade - Type 3	2	EA	\$ 207.00	= \$ 414.00		\$ 414.00
Delineator - Type I		EA	\$ 25.00	= \$ -		\$ -
Curb and Gutter, Type A (6" Vertical)	455	LF	\$ 31.00	= \$ 14,105.00		\$ 14,105.00
Curb and Gutter, Type B (Median)		LF	\$ 31.00	= \$ -		\$ -
Curb and Gutter, Type C (Ramp)	1,935	LF	\$ 31.00	= \$ 59,985.00		\$ 59,985.00
4" Sidewalk (common areas only)		SY	\$ 50.00	= \$ -		\$ -
5" Sidewalk	6,761	SY	\$ 62.00	= \$ 419,168.22		\$ 419,168.22
6" Sidewalk		SY	\$ 75.00	= \$ -		\$ -
8" Sidewalk		SY	\$ 99.00	= \$ -		\$ -
Pedestrian Ramp	4	EA	\$ 1,190.00	= \$ 4,760.00		\$ 4,760.00
Cross Pan, local (8" thick, 6' wide to include return)	35	LF	\$ 63.00	= \$ 2,205.00		\$ 2,205.00
Cross Pan, collector (9" thick, 8' wide to include return)		LF	\$ 95.00	= \$ -		\$ -
Curb Chase		EA	\$ 1,532.00	= \$ -		\$ -
Guardrail Type 3 (W-Beam)		LF	\$ 51.00	= \$ -		\$ -
Guardrail Type 7 (Concrete)		LF	\$ 75.00	= \$ -		\$ -
Guardrail End Anchorage		EA	\$ 2,172.00	= \$ -		\$ -
Guardrail Impact Attenuator		EA	\$ 3,899.00	= \$ -		\$ -
Sound Barrier Fence (CMU block, 6' high)		LF	\$ 81.00	= \$ -		\$ -
Sound Barrier Fence (panels, 6' high)		LF	\$ 83.00	= \$ -		\$ -

PROJECT INFORMATION

Trails at Aspen Ridge Filing No. 5			10/21/2021	
Project Name	Date	PCD File No.		

Description	Quantity	Units	Unit Cost		Total	(with Pre-Plat Construction)		
						% Complete	Remaining	
Electrical Conduit, Size =		LF	\$ 17.00	=	\$ -		\$ -	*
Traffic Signal, complete intersection		EA	\$ 439,875	=	\$ -		\$ -	*

PROJECT INFORMATION

Trails at Aspen Ridge Filing No. 5

10/21/2021

Project Name

Date

PCD File No.

Description	Quantity	Units	Unit Cost	=	\$	Total	(with Pre-Plat Construction)	
							% Complete	Remaining
<i>[insert items not listed but part of construction plans]</i>				=	\$	-		\$ -
STORM DRAIN IMPROVEMENTS				=	\$	-		\$ -
Concrete Box Culvert (M Standard), Size (30W x 19H)		LF	\$ 150.00	=	\$	-		\$ -
18" Reinforced Concrete Pipe		LF	\$ 67.00	=	\$	-		\$ -
24" Reinforced Concrete Pipe		LF	\$ 81.00	=	\$	-		\$ -
30" Reinforced Concrete Pipe		LF	\$ 100.00	=	\$	-		\$ -
36" Reinforced Concrete Pipe		LF	\$ 124.00	=	\$	-		\$ -
42" Reinforced Concrete Pipe		LF	\$ 166.00	=	\$	-		\$ -
48" Reinforced Concrete Pipe		LF	\$ 202.00	=	\$	-		\$ -
54" Reinforced Concrete Pipe		LF	\$ 254.00	=	\$	-		\$ -
60" Reinforced Concrete Pipe		LF	\$ 298.00	=	\$	-		\$ -
66" Reinforced Concrete Pipe		LF	\$ 344.00	=	\$	-		\$ -
72" Reinforced Concrete Pipe		LF	\$ 393.00	=	\$	-		\$ -
18" Corrugated Steel Pipe		LF	\$ 87.00	=	\$	-		\$ -
24" Corrugated Steel Pipe		LF	\$ 99.00	=	\$	-		\$ -
30" Corrugated Steel Pipe		LF	\$ 126.00	=	\$	-		\$ -
36" Corrugated Steel Pipe		LF	\$ 152.00	=	\$	-		\$ -
42" Corrugated Steel Pipe		LF	\$ 174.00	=	\$	-		\$ -
48" Corrugated Steel Pipe		LF	\$ 184.00	=	\$	-		\$ -
54" Corrugated Steel Pipe		LF	\$ 269.00	=	\$	-		\$ -
60" Corrugated Steel Pipe		LF	\$ 290.00	=	\$	-		\$ -
66" Corrugated Steel Pipe		LF	\$ 352.00	=	\$	-		\$ -
72" Corrugated Steel Pipe		LF	\$ 414.00	=	\$	-		\$ -
78" Corrugated Steel Pipe		LF	\$ 476.00	=	\$	-		\$ -
84" Corrugated Steel Pipe		LF	\$ 569.00	=	\$	-		\$ -
Flared End Section (FES) RCP Size = <i>(unit cost = 6x pipe unit cost)</i>		EA		=	\$	-		\$ -
Flared End Section (FES) CSP Size = <i>(unit cost = 6x pipe unit cost)</i>		EA		=	\$	-		\$ -
End Treatment- Headwall		EA		=	\$	-		\$ -
End Treatment- Wingwall		EA		=	\$	-		\$ -
End Treatment - Cutoff Wall		EA		=	\$	-		\$ -
Curb Inlet (Type R) L=5', Depth < 5'		EA	\$ 5,736.00	=	\$	-		\$ -
Curb Inlet (Type R) L=5', 5' ≤ Depth < 10'		EA	\$ 7,440.00	=	\$	-		\$ -
Curb Inlet (Type R) L =5', 10' ≤ Depth < 15'		EA	\$ 8,637.00	=	\$	-		\$ -
Curb Inlet (Type R) L =10', Depth < 5'		EA	\$ 7,894.00	=	\$	-		\$ -
Curb Inlet (Type R) L =10', 5' ≤ Depth < 10'		EA	\$ 8,136.00	=	\$	-		\$ -
Curb Inlet (Type R) L =10', 10' ≤ Depth < 15'		EA	\$ 10,185.00	=	\$	-		\$ -
Curb Inlet (Type R) L =15', Depth < 5'		EA	\$ 10,265.00	=	\$	-		\$ -
Curb Inlet (Type R) L =15', 5' ≤ Depth < 10'		EA	\$ 11,005.00	=	\$	-		\$ -
Curb Inlet (Type R) L =15', 10' ≤ Depth < 15'		EA	\$ 12,034.00	=	\$	-		\$ -
Curb Inlet (Type R) L =20', Depth < 5'		EA	\$ 10,940.00	=	\$	-		\$ -
Curb Inlet (Type R) L =20', 5' ≤ Depth < 10'		EA	\$ 12,075.00	=	\$	-		\$ -
Grated Inlet (Type C), Depth < 5'		EA	\$ 4,802.00	=	\$	-		\$ -
Grated Inlet (Type D), Depth < 5'		EA	\$ 5,932.00	=	\$	-		\$ -
Storm Sewer Manhole, Box Base		EA	\$ 12,034.00	=	\$	-		\$ -
Storm Sewer Manhole, Slab Base		EA	\$ 6,619.00	=	\$	-		\$ -
Geotextile (Erosion Control)		SY	\$ 6.20	=	\$	-		\$ -
Rip Rap, d50 size from 6" to 24"		Tons	\$ 83.00	=	\$	-		\$ -
Rip Rap, Grouted		Tons	\$ 98.00	=	\$	-		\$ -
Drainage Channel Construction, Size (W x H)		LF		=	\$	-		\$ -
Drainage Channel Lining, Concrete		CY	\$ 590.00	=	\$	-		\$ -
Drainage Channel Lining, Rip Rap		CY	\$ 116.00	=	\$	-		\$ -
Drainage Channel Lining, Grass		AC	\$ 1,520.00	=	\$	-		\$ -
Drainage Channel Lining, Other Stabilization				=	\$	-		\$ -
<i>[insert items not listed but part of construction plans]</i>				=	\$	-		\$ -
<i>* - Subject to defect warranty financial assurance. A minimum of 20% shall be retained until final acceptance (MAXIMUM OF 80% COMPLETE ALLOWED)</i>				=	\$	-		\$ -
Section 2 Subtotal				=	\$	771,576.22		\$ 771,576.22

PROJECT INFORMATION

Trails at Aspen Ridge Filing No. 5 10/21/2021
 Project Name Date PCD File No.

Description	Quantity	Units	Unit Cost	Total	(with Pre-Plat Construction)	
					% Complete	Remaining
AS-BUILT PLANS (Public Improvements inc. Permanent WQCV BMPs)		LS		= \$ -		\$ -
POND/BMP CERTIFICATION (inc. elevations and volume calculations)		LS		= \$ -		\$ -
Total Construction Financial Assurance						\$ 1,537,109.62
(Sum of all section subtotals plus as-builts and pond/BMP certification)						
Remaining Construction Financial Assurance (with Pre-Plat Construction)						\$ 1,537,109.62
(Sum of all section totals less credit for items complete plus as-builts and pond/BMP certification)						
Total Defect Warranty Financial Assurance						\$ 201,206.74
(20% of all items identified as (*). To be collateralized at time of preliminary acceptance)						

provide quantity for as-built plans



Approvals

I hereby certify that this is an accurate and complete estimate of costs for the work as shown on the Grading and Erosion Control Plan and Construction Drawings associated with the Project.

 Engineer (P.E. Seal Required)

 Approved by Owner / Applicant

 Date

 Approved by El Paso County Engineer / ECM Administrator

 Date