

**Engineering Review**

07/12/2021 2:25:20 PM

*dsdrice*

JeffRice@elpasoco.com

(719) 520-7877

EPC Planning & Community  
Development Department

See comment letter also

**PRELIMINARY DRAINAGE REPORT  
FOR  
STERLING RANCH PHASE 2 PRELIMINARY PLAN**

**Prepared For:**

**SR Land, LLC  
20 Boulder Crescent, Suite 200  
Colorado Springs, CO 80903  
(719) 491-3024**

**May, 2021  
Project No. 25188.02  
SP-20-003**


**Prepared By:  
JR Engineering, LLC  
5475 Tech Center Drive, Suite 235  
Colorado Springs, CO 80919  
719-593-2593**

**ENGINEER'S STATEMENT:**

The attached drainage plan and report were prepared under my direction and supervision and are correct to the best of my knowledge and belief. Said drainage report has been prepared according to the criteria established by El Paso County for drainage reports and said report is in conformity with the master plan of the drainage basin. I accept responsibility for any liability caused by any negligent acts, errors, or omissions on my part in preparing this report.

*Mike Bramlett*

Mike Bramlett, Colorado P.E. 38861  
For and On Behalf of JR Engineering, LLC



**DEVELOPER'S STATEMENT:**

I, the developer, have read and will comply with all of the requirements specified in this drainage report and plan.

Business Name: SR Land, LLC

By:

*Janet Morley*

Title:

MANAGER

Address:

20 Boulder Crescent, Suite 200  
Colorado Springs, CO 80903

**El Paso County:**

Filed in accordance with the requirements of the El Paso County Land Development Code, Drainage Criteria Manual, Volumes 1 and 2 and Engineering Criteria Manual, as amended.

\_\_\_\_\_  
Jennifer Irvine, P.E.  
County Engineer/ ECM Administrator

\_\_\_\_\_  
Date

Conditions:



## Table of Contents

Purpose .....	1
General Site Description .....	1
General Location.....	1
Description of Property .....	1
Floodplain Statement .....	1
Existing Drainage Conditions .....	2
Major Basin Descriptions .....	2
Existing Sub-basin Drainage .....	2
Proposed Drainage Conditions.....	4
Proposed Sub-basin Drainage.....	4
Interim Condition Proposed Sub-basin Drainage.....	7
Drainage Design Criteria .....	7
Development Criteria Reference .....	7
Hydrologic Criteria.....	7
Hydraulic Criteria.....	8
Drainage Facility Design .....	8
General Concept.....	8
Four Step Process to Minimize Adverse Impacts of Urbanization .....	8
Water Quality.....	9
Erosion Control Plan .....	9
Operation & Maintenance.....	10
Drainage and Bridge Fees.....	10
Summary .....	10
References.....	11

### APPENDIX

- Appendix A – Vicinity Map, Soil Descriptions, FEMA Floodplain Map
- Appendix B – Hydrologic and Hydraulic Calculations
- Appendix C – Reference Material
- Appendix D – Drainage Maps

## **PURPOSE**

---

This document is the Preliminary Drainage Report for Sterling Ranch Phase 2. The purpose of this report is to identify on-site and off-site drainage patterns, storm sewer, culvert and inlet locations, areas tributary to the site, and to safely route developed storm water to adequate outfall facilities.

## **GENERAL SITE DESCRIPTION**

---

### **GENERAL LOCATION**

Sterling Ranch Phase 2 (hereby referred to as the “site”) is a proposed development within the Sterling Ranch master planned community with a total area of approximately 75 acres that are presently undeveloped.

The site is located in portions of Section 4, 5 & 33, Township 12 & 13 South, Range 65 West of the Sixth Principal Meridian in El Paso County, State of Colorado. The site is bounded by Un-platted land to the southwest, the Barbarick Subdivision to the north, Sterling Ranch Road cuts through the site, and Sand Creek borders the site to east. The parcels are planned to be platted after approval of the Preliminary Plan. Refer to the vicinity map in Appendix A for additional information.

### **DESCRIPTION OF PROPERTY**

The property will be primarily be single-family residential development (approximately 42 acres), Open space and drainage tracts (approximately 28 acres, and an approximate 5 acre tract in the southwest corner where the Sterling Ranch Lift Station is located. The site is comprised of variable sloping grasslands that generally slope(s) downward to the southeast at 3 to 8% towards the Sand Creek tributary basin.

Soil characteristics are comprised of Type A and B hydrologic Soil groups. Refer to the soil survey map in Appendix A for additional information.

There are no major drainage ways running through the site, although a tributary to the Sand Creek basin is immediately to the east of the site. Currently, Kiowa Engineering Corp. is performing studies and plans to address Sand Creek stabilization.

There are no known irrigation facilities located on the project site.

### **FLOODPLAIN STATEMENT**

Based on the FEMA FIRM Maps number 08041C0533G, dated December 7, 2018, the far eastern portion of the project site that is adjacent to the existing drainage way lies within Zone AE. Zone AE is defined as area subject to inundation by the 1-percent-annual-chance flood event. The majority of



the proposed development lies within Zone X. Zone X is defined as area outside the Special Flood Hazard Area (SFHA) and higher than the elevation of the 0.2-percent-annual-chance (or 500-year) flood. No grading operations are proposed within the Zone AE at this time. FIRM Maps have been presented in Appendix A.

## EXISTING DRAINAGE CONDITIONS

---

### MAJOR BASIN DESCRIPTIONS

The site lies within the Sand Creek Drainage Basin based on the "Sand Creek Drainage Basin Planning Study" (DBPS) completed by Kiowa Engineering Corporation in January 1993, revised March 1996. The Sand Creek Drainage Basin covers approximately 54 square miles and is divided into major sub-basins. The site is within the respective sub-basin is shown in Appendix E.

The Sand Creek DBPS assumed the Sterling Ranch Phase 2 property to have a "large lot residential" use for the majority of the site. The Sterling Ranch MDDP assumed a mix of commercial and single family residential lots ranging in size from 0.2 to 0.3 acres for the Sterling Ranch Phase 2 site. The proposed Sterling Ranch master plan is a mix of; school, multi-family, single-family, and commercial land uses, resulting in higher runoff. Any additional runoff will be provided for with the extended detention basin located at the southern edge of the site. The site generally drains from north to south consisting of rolling hills. Currently, the site is used as pasture land for cattle. Sand Creek is located east of the site running north to south. This reach of drainage conveyance is not currently improved. There are a few stock ponds within the creek channel used for cattle watering. Currently, Kiowa is performing studies and plans to address Sand Creek stabilization adjacent to the site.

The proposed drainage on the site closely follows the approved "Master Development Drainage Plan for Sterling Ranch", (MDDP) prepared by M&S Civil Consultants, Inc., dated October 24, 2018. The site is tributary to Pond W5 and full-spectrum detention for the site was previously analyzed and can be found in the Final Drainage Report for Sterling Ranch Filing 2.

### EXISTING SUB-BASIN DRAINAGE

The existing / predeveloped condition of the site was broken into two major basins: Basin A (western portion) and Basin B (Eastern Portion), as well as several offsite basins. The basin and sub-basin delineation is shown in the existing drainage map in Appendix E and is described as follows:

Sub-basin A1( $Q_5= 1.1\text{cfs}$ ,  $Q_{100}=8.0\text{cfs}$ ) is 5.17 acres and 0 percent impervious consists of the eastern portion of Sterling Ranch phase 2. Runoff from this basin drains to the south west into the assumed existing storm sewer built with Filing 2 just east of Marksheffel Road located at design point 1.



Collected runoff is piped south to the existing detention pond built with Filing 2 and outfalls to Sand Creek.

Sub-basin A2 ( $Q_5= 4.6\text{cfs}$ ,  $Q_{100}=33.6\text{cfs}$ ) is 27.48 acres and 0 percent impervious and consists the central portion of Sterling Ranch Phase 2. Runoff from this basin drains south onsite into the assumed existing storm sewer built with Filing 2 located at design point 2. Collected runoff is piped south to the existing detention pond built with Filing 2 and outfalls to Sand Creek.

Sub-basin A3 ( $Q_5= 2.9\text{cfs}$ ,  $Q_{100}=21.5\text{cfs}$ ) is 11.68 acres and 0 percent impervious and is located onsite in the northern part of Sterling Ranch Phase 2. Runoff from this basin drains to the assumed existing storm sewer built with Filing 2 just north of Sterling Ranch Road located at design point 5. Design Point 5.1 is a confluence of flows from basins A3, OS6 and OS7. Collected runoff is piped south to the existing detention pond built with Filing 2 and outfalls to Sand Creek.

Sub-basin B1 ( $Q_5= 2.6\text{cfs}$ ,  $Q_{100}=19.0\text{cfs}$ ) is 11.78 and is 0 percent impervious and is located on the eastern portion of the site portion of the site. Runoff from this basin drains to the southeast into Sand Creek at design point 6.

Sub-basin OS1( $Q_5= 13.4\text{cfs}$ ,  $Q_{100}=29.8\text{cfs}$ ) is 9.27 acres is 30.7 percent impervious and is located to the east of the site. Runoff from this basin drains into the Sterling Ranch Filing 2 detention Pond in confluence with upstream flows from the eastern portion of Sub-basin A2. Collected runoff is piped south to the existing detention pond built with Filing 2 and outfalls to Sand Creek.

Sub-basin OS2 ( $Q_5= 6.3\text{cfs}$ ,  $Q_{100}=11.2\text{cfs}$ ) is 5.00 acres and 100 percent impervious and is comprised of the southern half street of Sterling Ranch Road. Runoff from this basin drains into the assumed existing storm sewer built with Filing 2 located at design point 7. Collected runoff is piped south to the existing detention pond built with Filing 2 and outfalls to Sand Creek.

Sub-basin OS3 ( $Q_5= 8.1\text{cfs}$ ,  $Q_{100}=14.6\text{cfs}$ ) is 2.36 acres and 100 percent impervious and is comprised of the northern half street of Sterling Ranch Road. Runoff from this basin drains into the assumed existing storm sewer built with Filing 2 located at design point 8. Collected runoff is piped south to the existing detention pond built with Filing 2 and outfalls to Sand Creek.

Sub-basin OS4 ( $Q_5= 2.8\text{cfs}$ ,  $Q_{100}=16.9\text{cfs}$ ) is 11.71 acres and 3.6 percent impervious and is located immediately north of Sterling Ranch Road and the eastern portion of the site. Runoff from this basin drains south into assumed existing storm sewer built with Filing 2 located at design point 9. Collected runoff is piped south to the existing detention pond built with Filing 2 and outfalls to Sand Creek.

Sub-basin OS5 ( $Q_5= 0.7\text{cfs}$ ,  $Q_{100}=5.0\text{cfs}$ ) is 3.46 acres and 0 percent impervious and is located to the east of the northern portion of the site. Runoff from this basin drains to a low point just north of

Sterling Ranch Road located at Design Point 4 and will be collected in the assumed existing storm sewer built with Filing 2 and piped to the Filing 2 detention pond located south of the site and outfalls to Sand Creek.

Sub-basin OS6 ( $Q_5= 35.4\text{cfs}$ ,  $Q_{100}=72.2\text{cfs}$ ) is 18.38 acres and 11.3 percent impervious as is located northwest of the site in the Barbarick subdivision. Historic runoff from this basins drains south onto the site at design point 10. Detained flow from this basin will be piped through the site to the detention pond and will outfall to Sand Creek.

Sub-basin OS7( $Q_5= 20.6\text{cfs}$ ,  $Q_{100}=60.4\text{cfs}$ ) is 33.07 Acres and 19.1 percent impervious and is located directly north of the site in the Barbarick subdivision. Historic runoff from this site drains south onto the site at design point 11. Detained flow from this basin will be piped through the site to the detention pond and will outfall to Sand Creek.

## PROPOSED DRAINAGE CONDITIONS

---

### PROPOSED SUB-BASIN DRAINAGE

The proposed site was broken into three major basins: Basin A (lower-portion), Basin B (mid and eastern -portion) and Basin C (upper-portion) of the site. The proposed basin (and sub-basin) delineation is shown on the drainage basin map within Appendix E and is described as follows.

**Basin A1** ( $Q_5= 8.1\text{cfs}$ ,  $Q_{100}=17.4\text{cfs}$ ) is 4.31 acres and 63 percent impervious and is comprised of single-family residential lots, and a local road. Runoff from this basin drains to design point 15, a type R on grade inlet at the southwest corner of the basin.

**Basin A2** ( $Q_5= 1.4\text{cfs}$ ,  $Q_{100}=4.0\text{cfs}$ ) is 1.41 acres and 31 percent impervious is comprised of single-family residential lots, open space, several trails, and a local road. Runoff from this basin drains to design point 17, a type R on grade inlet on the southwest corner of the basin, in confluence with upstream by-pass flows from basin A1.

**Basin A3** ( $Q_5= 6.8\text{cfs}$ ,  $Q_{100}=14.6\text{cfs}$ ) is 3.68 acres and 65 percent impervious is comprised of single-family residential lots and a local road. Runoff from this basin drains to an on grade inlet located at design point 20.

**Basin A4** ( $Q_5= 5.7\text{cfs}$ ,  $Q_{100}=13.4\text{cfs}$ ) is 3.94 acres and 52 percent impervious is comprised of single-family residential lots, open space a local road and two urban knuckles. Runoff from this basin drains to a sump type R inlet located at design point 22 in confluence with upstream bypass flows from basins A1, A2, and A3.



**Basin A5** ( $Q_5= 1.4\text{cfs}$ ,  $Q_{100}=2.9\text{cfs}$ ) is 0.45 acres and 78 percent impervious is comprised of single-family residential lots and a local road. Runoff from this basin drains to an on grade inlet at design point 16.

**Basin A6** ( $Q_5= 15.3\text{cfs}$ ,  $Q_{100}=31.4\text{cfs}$ ) is 7.60 acres and 73 percent impervious is comprised of single-family residential lots, local roads. Runoff from this basin drains to an on grade type inlet at design point 19.

**Basin A7** ( $Q_5= 3.0\text{cfs}$ ,  $Q_{100}=6.1\text{cfs}$ ) is 1.43 acres and 75 percent impervious is comprised of single family residential lots and local roads. The Runoff from this basin drains to a sump type R inlet located at design point 21.

**Basin A8** ( $Q_5= 2.2\text{cfs}$ ,  $Q_{100}=9.1\text{cfs}$ ) 4.22 acres and 13 percent impervious is comprised of a single family residential lots and open space. The runoff from this basin drains to a swale on western side of the site and into an area inlet located at design point 24.

**Basin A9** ( $Q_5= 0.7\text{cfs}$ ,  $Q_{100}=3.5\text{cfs}$ ) 2.02 acres and 8 percent impervious is comprised of a single family residential lots and open space. The runoff from this basin drains to a swale on western side of the site and into a flared end section and pipe located at design point 25.

**Basin A10** ( $Q_5= 2.4\text{cfs}$ ,  $Q_{100}=8.0\text{cfs}$ ) 3.23 acres and 24 percent impervious is comprised of a single family residential lots and open space. The runoff from this basin sheet flows to the south and into existing pond W5 at design point 27.

**Basin B1** ( $Q_5= 6.2\text{cfs}$ ,  $Q_{100}=12.0\text{cfs}$ ) is 2.44 acres and 80 percent impervious is comprised of single-family residential lots, local roads, two urban knuckles, and a cul-de sac. The runoff from basin B1 drains to a type R sump inlet located at design point 13.

**Basin B2** ( $Q_5= 9.1\text{cfs}$ ,  $Q_{100}=18.7\text{cfs}$ ) is 4.33 acres and 73 percent impervious is comprised of single family residential lots. Runoff from basin B2 drains to a type R sump inlet located at design point 12.

### Sterling Ranch Road?

**Basin B3** ( $Q_5= 3.5\text{cfs}$ ,  $Q_{100}=7.3\text{cfs}$ ) is 2.34 acres and 61 percent impervious is comprised of open space and sidewalk. Runoff from basin B3 drains to a 15' type R on grade inlet located at design point 9 in existing Sterling Ranch Road. All of the runoff is captured in the 100 year event. Runoff from this sump inlet is piped and outfalls into pond W-5.

**Basin B4** ( $Q_5= 2.3\text{cfs}$ ,  $Q_{100}=5.6\text{cfs}$ ) is 1.80 acres and 51.3 percent impervious is comprised of single family residential lots and open space. Runoff from basin B4 drains to a rear lot area inlet at DP 10.

**Basin B5** ( $Q_5=0.7\text{cfs}$ ,  $Q_{100}=1.7\text{cfs}$ ) is 0.45 acres and 51 percent impervious is comprised of single family residential lots and open space. Runoff from basin B4 drains to a rear lot area inlet at DP 11.





**Basin B6** ( $Q_5=0.8\text{cfs}$ ,  $Q_{100}=2.2\text{cfs}$ ) is 0.78 acres and 44 percent impervious is comprised of single family residential lots and open space. Runoff from basin B4 drains to a rear lot area inlet at DP 14.

**Basin C1** ( $Q_5= 5.5\text{cfs}$ ,  $Q_{100}=11.4\text{cfs}$ ) is 2.62 acres and 68.7 percent impervious is comprised of single family residential lots, local roads, and an urban knuckle Runoff from basin C1 drains to a sump type R inlet located at design point 6.

**Basin C2** ( $Q_5= 12.0\text{cfs}$ ,  $Q_{100}=25.9\text{cfs}$ ) is 6.74 acres and 63 percent impervious is comprised of local roads, single-family residential lots, an urban knuckle, open space, and paved walks. Runoff from basin C2 drains to a type R sump inlet located at design point 5.

**Basin C3** ( $Q_5= 2.2\text{cfs}$ ,  $Q_{100}=9.9\text{cfs}$ ) is 3.77 acres and 10 percent impervious is comprised of single family residential lots, open space, and paved walks. Runoff from basin C3 drains to a swale on the western side of the site and into an area inlet located at design point 7.

**Basin C4** ( $Q_5= 4.6\text{cfs}$ ,  $Q_{100}=10.2\text{ cfs}$ ) is 3.79 acres and 54.7 percent impervious is comprised of open space single family residential lots. Runoff from basin B3 drains to an on-grade 15' type R inlet located at design point 8 in existing Sterling Ranch Road. In the 100 year event 0.8 cfs is by-passed to a sump inlet adjacent to the intersection of Sterling Ranch Road and Marksheffel Road. From there on the runoff is piped out falls into pond W-5.

roads and rear yards of

**Basin D1**( $Q_5= 0.3\text{cfs}$ ,  $Q_{100}=1.3\text{cfs}$ ) is 0.42 acres and 11.5 percent impervious is comprised of open space area. Runoff from basin D1 sheet flow to the, southeast and adjacent properties into Sandcreek as per the historic condition. Flows generated from this basin have been attributed to design point 28.

**Basin D2** ( $Q_5= 1.9\text{cfs}$ ,  $Q_{100}=10.5\text{ cfs}$ ) is 3.67 acres and 4.6 percent impervious is comprised of open space area. Runoff from basin D1 sheet flow to the southeast into Sandcreek as per the historic condition. Flows generated from this basin have been attributed to design point 29.

**Basin OS4** ( $Q_5= 2.8\text{cfs}$ ,  $Q_{100}=16.9\text{cfs}$ ) is 11.71 acres and 3.6 percent impervious and is located immediately north of Sterling Ranch Road and the eastern portion of the site. Runoff from this basin drains south into assumed existing storm sewer built with Filing 2 located at design point 2. Collected runoff is piped south to the existing detention pond built with Filing 2 and outfalls to Sand Creek.

**Basin OS6** ( $Q_5= 35.4\text{cfs}$ ,  $Q_{100}=72.2\text{cfs}$ ) is 18.38 acres and 54 percent impervious as is located northwest of the site in the Barbarick subdivision. Historic runoff from this basins drains south onto the site at design point 4. Detained flow from this basin will be piped through the site to the detention pond and will outfall to Sand Creek. Emergency overflow from this basin will be collected in a grated inlet at design point 4. Assumed pipe sizes will be confirmed with the FDR during final platting.

Any flows over the inlet capacity will sheet flow to Ennis Dr. (?)



**Basin OS7** ( $Q_5= 20.6\text{cfs}$ ,  $Q_{100}=60.4\text{cfs}$ ) is 33.07 Acres and 23 percent impervious and is located directly north of the site in the Barbarick subdivision. Historic runoff from this site drains south onto the site at design point 1. Detained flow from this basin will be piped through the site to the detention pond and will outfall to Sand Creek. Emergency overflow from this basin will be routed around the lots and into the school site. Assumed pipe and channel sizes will be confirmed with the FDR during final platting. Flows from the eastern portion of the basin travel overland towards design point 2.

### **INTERIM CONDITION PROPOSED SUB-BASIN DRAINAGE**

In the interim site condition, all the basins stay the same except basins A2, A3, A4, A6, A7, A8, A9 and A10 will remain undeveloped. The undeveloped basins are summarized below. An interim condition map can be found in Appendix F.

**Basin I1** ( $Q_5= 4.4 \text{ cfs}$ ,  $Q_{100}=31.2\text{cfs}$ ) 21.99 acres and 1 percent impervious is comprised of open space. The runoff from this basin sheet flows generally to the south and east into a temporary drainage channel where it is conveyed to an existing storm stub at design point I1.

**Basin I2** ( $Q_5= 0.7\text{cfs}$ ,  $Q_{100}=4.9\text{cfs}$ ) 3.47 acres and 0 percent impervious is comprised of open space. The runoff from this basin sheet flows to the south and east into an existing drainage swale where it eventually enters an existing storm stub provided from the Sterling Ranch Filing No 2. Project.

## **DRAINAGE DESIGN CRITERIA**

Provide discussion of design points, inlets and pipes.

### **DEVELOPMENT CRITERIA REFERENCE**

Storm drainage analysis and design criteria for this project were taken from the “*City of Colorado Springs/El Paso County Drainage Criteria Manual*” Volumes 1 and 2 (EPCDCM), dated October 12, 1994, the “*Urban Storm Drainage Criteria Manual*” Volumes 1 to 3 (USDCM) and Chapter 6 and Section 3.2.1 of Chapter 13 of the “*Colorado Springs Drainage Criteria Manual*” (CSDCM), dated May 2014, as adopted by El Paso County.

### **HYDROLOGIC CRITERIA**

All hydrologic data was obtained from the “*El Paso Drainage Criteria Manual*” Volumes 1 and 2, and the “*Urban Drainage and Flood Control District Urban Storm Drainage Criteria Manual*” Volumes 1, 2, and 3. Onsite drainage improvements were designed based on the 5 year (minor) storm event and the 100-year (major) storm event. Runoff was calculated using the Rational Method, and rainfall intensities for the 5-year and the 100-year storm return frequencies were obtained from Table 6-2 of the CSDCM. One hour point rainfall data for the storm events is identified in the chart below. Runoff coefficients were determined based on proposed land use and from data in Table 6-6 from the



CSDCM. Time of concentrations were developed using equations from CSDCM. All runoff calculations and applicable charts and graphs are included in the Appendices.

**Table 2 - 1-hr Point Rainfall Data**

<b>Storm</b>	<b>Rainfall (in.)</b>
5-year	1.50
100-year	2.52

## **HYDRAULIC CRITERIA**

The Rational Method and USDCM's SF-2 and SF-3 forms were used to determine the runoff from the minor and major storms on the site. Sump and on-grade inlets were sized using UDFCD UD-Inlet v4.05. StormCAD was used to model the proposed storm sewer system within the interim area and to analyze the proposed HGL calculations for the Construction Drawings. Autodesk Hydraflow express was used to size the overflow channel and the interim swale.

## **DRAINAGE FACILITY DESIGN**

---

### **GENERAL CONCEPT**

The proposed stormwater conveyance system was designed to convey the developed Sterling Ranch Phase 2 runoff to an existing (Filing 2) full spectrum water quality and detention pond via storm sewer. The proposed pond was designed to release at less than historic rates to minimize adverse impacts downstream. Treated water will outfall directly into the Sand Creek Drainage way, where it will eventually outfall into Fountain Creek. A proposed drainage map is presented in Appendix E showing locations of the pond. JR Engineering is working on a separate plan to stabilize Sand Creek directly adjacent to the site.

### **FOUR STEP PROCESS TO MINIMIZE ADVERSE IMPACTS OF URBANIZATION**

In accordance with the El Paso County Drainage Criteria Manual Volume 2, this site has implemented the four step process to minimize adverse impacts of urbanization. The four step process includes reducing runoff volumes, treating the water quality capture volume (WQCV), stabilizing drainage ways, and implementing long-term source controls.

**Step 1 – Reducing Runoff Volumes:** The Sterling Ranch Phase 2 development project consists of single-family homes with open spaces and lawn areas interspersed within the development which helps disconnect impervious areas and reduce runoff volumes. Roof drains from the structures will discharge to lawn areas, where feasible, to allow for infiltration and runoff volume reduction.

**Step 2 – Stabilize Drainageways:** The site lies within the Sand Creek Drainage Basin. Basin and bridge fees will be due at time of platting. These funds will be used for the channel stabilization being designed by JR Engineering adjacent to the site and on future projects within the basin to

stabilize drainageways. The site does not discharge directly into the open drainageway of Sand Creek, therefore no downstream stabilization will be accomplished with this project.

Step 3 – Treat the WQCV: Water Quality treatment for this site is provided in an existing full spectrum water quality detention pond (W5). The runoff from this site will be collected within inlets and conveyed to the proposed ponds via storm sewer. Upon entrance to the ponds, flows will be captured in a forebay designed to promote settlement of suspended solids. A trickle channel is also incorporated into the ponds to minimize the amount of standing water. The outlet structure has been designed to detain the water quality capture volume (WQCV) for 40 hours, and the extended urban runoff volume (EURV) for 72 hours. All flows released from the ponds will be reduced to less than historic rates.

Step 4 –BMPs will be utilized to minimize off-site contaminants and to protect the downstream receiving waters. The permanent erosion control BMPs include asphalt drives and parking, storm inlets and storm pipe, the full spectrum detention pond W-5 and permanent vegetation. Maintenance responsibilities and plans will be defined at the time of final platting.

**WATER QUALITY**

In accordance with Section 13.3.2.1 of the CCS/EPCDCM, full spectrum water quality and detention are provided for all developed basins. This site will drain into an existing Full Spectrum Drainage Pond W5 developed during the Sterling Ranch Filing No. 2 Project. Further details as well as all pond volume, water quality, and outfall calculations are included in the Sterling Ranch Filing 2 Final Drainage Report. Pond W5 corresponds to pond FSD6 from the Master Development Drainage Plan for Sterling Ranch", (MMDP) prepared by M&S Civil Consultants, Inc., dated October 24, 2018. ( $Q_5=7.6$  cfs,  $Q_{100}=149.7$  cfs) and is releasing less than the MDDP values in the proposed design. A summary of Pond W-5 has been included below for reference.

Table 3. Pond Volumes & Release Rates

	REQUIRED VOLUME (AC-FT)	VOLUME PROVIDED (AC-FT)	WQCV (AC-FT)	EURV (AC-FT)	5-YEAR RELEASE (CFS)	100-YEAR RELEASE (CFS)
POND W5	18.217	18.441	3.29	11.71	2.7	137.1

**EROSION CONTROL PLAN**

We respectfully request that the Erosion Control Plan and Cost Estimate be submitted in conjunction with the grading and erosion control plan and construction assurances posted prior to obtaining a grading permit.

Address ECM Step 4: "Consider Need for Industrial and Commercial BMPs" - If there are not proposed commercial or industrial uses on this site, state that.

**OPERATION & MAINTENANCE**

In order to ensure the function and effectiveness of the stormwater infrastructure, maintenance activities such as inspection, routine maintenance, restorative maintenance, rehabilitation and repair, are required. The district shall be responsible for the inspection, maintenance, rehabilitation and repair of stormwater and erosion control facilities located on the property unless another party accepts such responsibility in writing and responsibility is properly assigned through legal documentation. Access is provided from onsite facilities and easements for proposed infrastructure located offsite. We respectfully request that the Operation & Maintenance Manual be submitted in conjunction with the construction documents, prior to obtaining a grading permit. A maintenance road was provided for the existing pond W5 and information on the road can be found in the Final Drainage Report for Sterling Ranch Filing No. 2. The maintenance road access is off of Marksheffel Road and wraps around the top of the pond providing access to the inflow pipe wingwalls and outlet structure for the pond.

**DRAINAGE AND BRIDGE FEES**

The site lies within the Sand Creek Drainage Basin. Anticipated drainage and bridge fees are presented below and will be due at time of platting (depending on date of plat submittal):.

2021 DRAINAGE AND BRIDGE FEES – STERLING RANCH PHASE 2				
Impervious Acres (ac)	Drainage Fee (Per Imp. Acre)	Bridge Fee (Per Imp. Acre)	Sterling Ranch Drainage Fee	Sterling Ranch Bridge Fee
37	\$20,387	\$8,339	\$754,319	\$308,543

**SUMMARY**

---

The proposed Sterling Ranch Phase 2 drainage improvements were designed to meet or exceed the El Paso County Drainage Criteria. The proposed development will not adversely affect the offsite drainageways or surrounding development. This report is in conformance and meets the latest El Paso County Storm Drainage Criteria requirements for this site.


## REFERENCES

---

1. "El Paso County and City of Colorado Springs Drainage Criteria Manual, Vol I & II".
  2. Sand Creek Channel Design Report, prepared by JR Engineering, May 19, 2021 (not yet approved)
  3. "Master Development Drainage Plan for Sterling Ranch", (MMDP) prepared by M&S Civil Consultants, Inc., dated October 24, 2018.
  4. Sand Creek Drainage Basin Planning Study, prepared Kiowa Engineering Corporation, January 1993, revised March 1996.
  5. "Sterling Ranch Filing 2 Final Drainage Report", prepared by JR Engineering, dated May 2020 (not yet approved)
  6. Urban Storm Drainage Criteria Manual (Volumes 1, 2, and 3), Urban Drainage and Flood Control District, June 2001.
  7. Sand Creek Stabilization at Aspen Meadows Subdivision Filing No. 1 – 100% Design Plans, April 2020
-

**Appendix A**  
**Vicinity Map, Soil Descriptions, FEMA Floodplain Map**






# VICINITY MAP

N.T.S.



Hydrologic Soil Group—El Paso County Area, Colorado



Map Scale: 1:12,000 if printed on A landscape (11" x 8.5") sheet.



Map projection: Web Mercator Corner coordinates: WGS84 Edge tics: UTM Zone 13N WGS84



### MAP LEGEND

**Area of Interest (AOI)**









 Area of Interest (AOI)

**Soils**

**Soil Rating Polygons**





-  A
-  A/D
-  B
-  B/D
-  C
-  C/D
-  D
-  Not rated or not available

**Soil Rating Lines**

-  A
-  A/D
-  B
-  B/D
-  C
-  C/D
-  D
-  Not rated or not available

**Soil Rating Points**






-  A
-  A/D
-  B
-  B/D

-  C
-  C/D
-  D
-  Not rated or not available


**Water Features**

 Streams and Canals

**Transportation**

-  Rails
-  Interstate Highways
-  US Routes
-  Major Roads
-  Local Roads

**Background**

 Aerial Photography

### MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

**Warning:** Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service  
 Web Soil Survey URL:  
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: El Paso County Area, Colorado  
 Survey Area Data: Version 17, Sep 13, 2019

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Aug 19, 2018—May 26, 2019

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

## Hydrologic Soil Group

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
8	Blakeland loamy sand, 1 to 9 percent slopes	A	182.3	25.4%
9	Blakeland-Fluvaquentic Haplaquolls	A	36.8	5.1%
19	Columbine gravelly sandy loam, 0 to 3 percent slopes	A	307.5	42.9%
71	Pring coarse sandy loam, 3 to 8 percent slopes	B	188.4	26.3%
85	Stapleton-Bernal sandy loams, 3 to 20 percent slopes	B	1.2	0.2%
96	Truckton sandy loam, 0 to 3 percent slopes	A	0.6	0.1%
<b>Totals for Area of Interest</b>			<b>716.9</b>	<b>100.0%</b>

## Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

## Rating Options

*Aggregation Method:* Dominant Condition

*Component Percent Cutoff:* None Specified

*Tie-break Rule:* Higher

**NOTES TO USERS**

This map is for use in administering the National Flood Insurance Program. It does not necessarily identify all areas subject to flooding, particularly from local drainage sources of small size. The community map repository should be consulted for possible updated or additional flood hazard information.

To obtain more detailed information in areas where Base Flood Elevations (BFEs) and/or floodways have been determined, users are encouraged to consult the Flood Profiles and Floodway Data and/or Summary of Stillwater Elevations tables contained within the Flood Insurance Study (FIS) report that accompanies this FIRM. Users should be aware that BFEs shown on the FIRM represent rounded whole-foot elevations. These BFEs are intended for flood insurance rating purposes only and should not be used as the sole source of flood elevation information. Accordingly, flood elevation data presented in the FIS report should be utilized in conjunction with the FIRM for purposes of construction and/or floodplain management.

Coastal Base Flood Elevations shown on this map apply only landward of 0.0' North American Vertical Datum of 1988 (NAVD88). Users of this FIRM should be aware that coastal flood elevations are also provided in the Summary of Stillwater Elevations table in the Flood Insurance Study report for this jurisdiction. Elevations shown in the Summary of Stillwater Elevations table should be used for construction and/or floodplain management purposes when they are higher than the elevations shown on this FIRM.

Boundaries of the floodways were computed at cross sections and interpolated between cross sections. The floodways were based on hydraulic considerations with regard to requirements of the National Flood Insurance Program. Floodway widths and other pertinent floodway data are provided in the Flood Insurance Study report for this jurisdiction.

Certain areas not in Special Flood Hazard Areas may be protected by flood control structures. Refer to section 2.4 "Flood Protection Measures" of the Flood Insurance Study report for information on flood control structures in this jurisdiction.

The projection used in the preparation of this map was Universal Transverse Mercator (UTM) zone 13. The horizontal datum was NAD83. GRS80 spheroid. Differences in datum, spheroid, projection or UTM zones across users in the production of FIRMs for adjacent jurisdictions may result in slight positional differences in map features across jurisdiction boundaries. These differences do not affect the accuracy of this FIRM.

Flood elevations on this map are referenced to the North American Vertical Datum of 1988 (NAVD88). These flood elevations must be compared to structure and ground elevations referenced to the same vertical datum. For information regarding conversion between the National Geodetic Vertical Datum of 1929 and the North American Vertical Datum of 1988, visit the National Geodetic Survey website at <http://www.ngs.noaa.gov/> or contact the National Geodetic Survey at the following address:

NGS Information Services  
 NOAA, NNGS12  
 National Geodetic Survey  
 SSMC-3, #9222  
 1315 East-West Highway  
 Silver Spring, MD 20910-3282

To obtain current elevation, description, and/or location information for bench marks shown on this map, please contact the information Services Branch of the National Geodetic Survey at (202) 773-3242 or visit its website at <http://www.ngs.noaa.gov/>.

Base Map information shown on this FIRM was provided in digital format by El Paso County, Colorado Springs Utilities, and Anderson Consulting Engineers, Inc. These data are current as of 2008.

This map reflects more detailed and up-to-date stream channel configurations and floodplain delineations than those shown on the previous FIRM for this jurisdiction. The floodplains and floodways that were transferred from the previous FIRM may have been adjusted to conform to these new stream channel configurations. As a result, the Flood Profiles and Floodway Data tables in the Flood Insurance Study Report (which contains authoritative hydraulic data) may reflect stream channel distances that differ from what is shown on this map. The profile baselines depicted on this map represent the hydraulic modeling baselines that match the flood profiles and Floodway Data Tables if applicable in the FIS report. As a result, the profile baselines may deviate significantly from the new base map channel representation and may appear outside of the floodplain.

Corporate limits shown on this map are based on the best data available at the time of publication. Because changes due to annexations or de-annexations may have occurred after this map was published, map users should contact appropriate community officials to verify current corporate limit locations.

Please refer to the separately printed Map Index for an overview map of the county showing the layout of map panels, community map repository addresses, and a Listing of Communities table containing National Flood Insurance Program dates for each community as well as a listing of the panels on which each community is located.

Contact FEMA Map Service Center (MSC) via the FEMA Map Information eXchange (FMIX) 1-877-336-2627 for information on available products associated with this FIRM. Available products may include previously issued Letters of Map Change, a Flood Insurance Study Report, and/or digital versions of this map. The MSC may also be reached by Fax at 1-800-368-9620 and its website at <http://www.msc.fema.gov/>.


If you have questions about this map or questions concerning the National Flood Insurance Program in general, please call 1-877-FEMA MAP (1-877-336-2627) or visit the FEMA website at <http://www.fema.gov/business/inf>.

**El Paso County Vertical Datum Offset Table**

Flooding Source	Vertical Datum Offset (ft)


REFER TO SECTION 3.3 OF THE EL PASO COUNTY FLOOD INSURANCE STUDY FOR STREAM/STRAIN VERTICAL DATUM CONVERSION INFORMATION.

**Panel Location Map**



This Digital Flood Insurance Rate Map (DFIRM) was produced through a Cooperating Technical Plan (CTP) agreement between the State of Colorado Water Conservation Board (CWCB) and the Federal Emergency Management Agency (FEMA).

Additional Flood Hazard information and resources are available from local communities and the Colorado Water Conservation Board.



**LEGEND**

**SPECIAL FLOOD HAZARD AREAS (SFHAS) SUBJECT TO INUNDATION BY THE 1% ANNUAL CHANCE FLOOD**

The 1% annual chance flood (100-year flood), also known as the base flood, is the flood that has a 1% chance of being equaled or exceeded in any given year. The Special Flood Hazard Area is the area subject to flooding by the 1% annual chance flood. Areas of Special Flood Hazard include Zones A, AE, AH, AO, AR, AV, and VE. The Base Flood Elevation is the water-surface elevation of the 1% annual chance flood.

**ZONE A** No Base Flood Elevations determined.  
**ZONE AE** Base Flood Elevations determined.  
**ZONE AH** Flood depths of 1 to 3 feet (usually areas of ponding); Base Flood Elevations determined.  
**ZONE AO** Flood depths of 1 to 3 feet (usually sheet flow on sloping terrain); average depths determined. For areas of alluvial fan flooding, velocities also determined.  
**ZONE AR** Special Flood Hazard Area Formerly protected from the 1% annual chance flood by a flood control system that was previously determined. Zone AR indicates that the former flood control system is being retained to provide protection from the 1% annual chance or greater flood.  
**ZONE AV** Area to be protected from 1% annual chance flood by a Federal flood protection system under construction; no Base Flood Elevations determined.  
**ZONE V** Coastal flood zone with velocity hazard (wave action); no Base Flood Elevations determined.  
**ZONE VE** Coastal flood zone with velocity hazard (wave action); Base Flood Elevations determined.

**FLOODWAY AREAS IN ZONE AE**

The floodway is the channel of a stream plus any adjacent floodplain areas that must be kept free of encroachments so that the 1% annual chance flood can be carried without substantial increases in flood heights.

**OTHER FLOOD AREAS**

**ZONE X** Areas of 0.2% annual chance flood; areas of 1% annual chance flood with average depths of less than 1 foot or with velocities less than 1 square mile; and areas protected by levees from 1% annual chance flood.  
**OTHER AREAS**  
**ZONE X** Areas determined to be outside the 0.2% annual chance floodplain.  
**ZONE D** Areas in which flood hazards are undetermined, but possible.  
**COASTAL BARRIER PROTECTED SYSTEM (CBRS) AREAS**  
**OTHERWISE PROTECTED AREAS (OPA)**

CBRS areas and OPAs are normally located within or adjacent to Special Flood Hazard Areas.

Floodplain boundary  
 Floodway boundary  
 Zone D boundary  
 CBRS and OPA boundary

Boundary dividing Special Flood Hazard Areas of different Base Flood Elevations, flood depths or flood velocities.  
 Base Flood Elevation line and value, elevation in feet\* (EL 587)  
 Base Flood Elevation value where uniform within zone; otherwise in feet\*  
 \* Referenced to the North American Vertical Datum of 1988 (NAVD 88)

Cross section line  
 Transect line

97° 07' 30.00"  
 32° 22' 00.00"  
 1000-meter Universal Transverse Mercator grid ticks, zone 13  
 6000000 FT  
 5000-foot grid ticks; Colorado State Plane coordinate system, central zone (EPSRCO02), Lambert Conformal Conic Projection  
 Bench mark (see explanation in Notes to Users section of this FIS report)  
 M1.5  
 River file

**MAP REPOSITORIES**  
 Refer to Map Repository list on Map Index  
**EFFECTIVE DATE OF COUNTYWIDE FLOOD INSURANCE RATE MAP**  
 MARCH 17, 1997  
**EFFECTIVE DATE(S) OF REVISION(S) TO THIS PANEL**  
 DECEMBER 7, 2018 to update map information to change Base Flood Elevations and Special Flood Hazard Areas, to update map format, to add roads and road names, and to incorporate previously issued Letters of Map Change.

For community map revision history prior to courtswide mapping, refer to the Community Map History Table located in the Flood Insurance Study report for this jurisdiction.  
 To determine if flood insurance is available in this community, contact your insurance agent or call the National Flood Insurance Program at 1-800-433-6620.

**MAP SCALE 1" = 600'**

250 0 500 1000  
 FEET  
 150 0 300 450  
 METERS

NOTE: MAP AREA SHOWN ON THIS PANEL IS LOCATED WITHIN TOWNSHIP 12 SOUTH, RANGE 65 WEST, AND TOWNSHIP 13 SOUTH, RANGE 65 WEST.

**NATIONAL FLOOD INSURANCE PROGRAM**

**PANEL 0533G**

**FIRM**  
**FLOOD INSURANCE RATE MAP**  
**EL PASO COUNTY, COLORADO AND INCORPORATED AREAS**

**PANEL 533 OF 1300**  
 (SEE MAP INDEX FOR FIRM PANEL LAYOUT)

**CONTAINS:**

COMMUNITY	NUMBER	PANEL	SUFFIX
COLORADO SPRINGS CITY OF	08008	0033	G
EL PASO COUNTY	08008	0033	G

Notes to User: The Map Number shown below should be used when ordering map copies. The Community Number shown above should be used on insurance applications for the insured community.

**MAP NUMBER**  
 08041C0533G

**MAP REVISED**  
 DECEMBER 7, 2018

Federal Emergency Management Agency

## **Appendix B**

# **Hydrologic Calculations**

## COMPOSITE % IMPERVIOUS & COMPOSITE EXISTING RUNOFF COEFFICIENT CALCULATIONS

Subdivision: Sterling Ranch Subdivision- Existing  
 Location: El Paso County

Project Name: Sterling Ranch Phase 2  
 Project No.: 25188.02  
 Calculated By: CJD  
 Checked By: \_\_\_\_\_  
 Date: 5/4/21

Basin ID	Total Area (ac)	Streets (100% Impervious)				Residential (65% Impervious) Neighborhood Area (70% Impervious)				1 Acre lot Residential (20% Impervious) Light Commercial (80% Impervious)				Lawns (0% Impervious) School (55% Impervious)				Basins Total Weighted C Values		Basins Total Weighted % Imp.
		C <sub>5</sub>	C <sub>100</sub>	Area (ac)	Weighted % Imp.	C <sub>5</sub>	C <sub>100</sub>	Area (ac)	Weighted % Imp.	C <sub>5</sub>	C <sub>100</sub>	Area (ac)	Weighted % Imp.	C <sub>5</sub>	C <sub>100</sub>	Area (ac)	Weighted % Imp.	C <sub>5</sub>	C <sub>100</sub>	
A1	5.17	0.90	0.96	0.00	0.0%	0.45	0.59	0.00	0.0%	0.59	0.70	0.00	0.0%	0.08	0.35	5.17	2.0%	0.08	0.35	2.0%
A2	27.48	0.90	0.96	0.00	0.0%	0.45	0.59	0.00	0.0%	0.59	0.70	0.00	0.0%	0.08	0.35	27.48	0.0%	0.08	0.35	0.0%
A3	11.68	0.90	0.96	0.00	0.0%	0.45	0.59	0.00	0.0%	0.59	0.70	0.00	0.0%	0.08	0.35	11.68	0.0%	0.08	0.35	0.0%
B1	11.78	0.90	0.96	0.00	0.0%	0.45	0.59	0.00	0.0%	0.59	0.70	0.00	0.0%	0.08	0.35	11.78	0.0%	0.08	0.35	0.0%
OS1	9.27	0.90	0.96	2.85	30.7%	0.45	0.59	0.00	0.0%	0.30	0.40	2.85	6.1%	0.08	0.35	3.57	0.0%	0.40	0.55	36.9%
OS2	1.94	0.90	0.96	1.94	100.0%	0.45	0.59	0.00	0.0%	0.59	0.70	0.00	0.0%	0.08	0.35	0.00	0.0%	0.90	0.96	100.0%
OS3	2.36	0.90	0.96	2.36	100.0%	0.45	0.59	0.00	0.0%	0.59	0.70	0.00	0.0%	0.08	0.35	0.00	0.0%	0.90	0.96	100.0%
OS4	11.71	0.90	0.96	0.00	0.0%	0.45	0.59	0.65	3.6%	0.59	0.70	0.00	0.0%	0.08	0.35	11.06	0.0%	0.10	0.36	3.6%
OS5	3.46	0.90	0.96	0.00	0.0%	0.45	0.59	0.00	0.0%	0.59	0.70	0.00	0.0%	0.08	0.35	3.46	0.0%	0.08	0.35	0.0%
OS6	18.38	0.90	0.96	0.00	0.0%	0.45	0.59	0.00	0.0%	0.90	0.90	10.40	11.3%	0.08	0.35	7.98	0.0%	0.54	0.66	11.3%
OS7	33.07	0.90	0.96	0.00	0.0%	0.45	0.59	0.00	0.0%	0.90	0.90	7.91	19.1%	0.08	0.35	25.16	0.0%	0.28	0.48	19.1%
TOTAL (A1-B1)	56.11																			0.2%
TOTAL (OS1-OS7)	80.19																			20.6%
TOTAL	136.30																			12.2%

## EXISTING STANDARD FORM SF-2 TIME OF CONCENTRATION

Subdivision: Sterling Ranch Subdivision- Existing  
Location: El Paso County

Project Name: Sterling Ranch Phase 2  
Project No.: 25188.02  
Calculated By: CJD  
Checked By: \_\_\_\_\_  
Date: 5/4/21

SUB-BASIN						INITIAL/OVERLAND			TRAVEL TIME					t <sub>c</sub> CHECK			FINAL
DATA						(T <sub>i</sub> )			(T <sub>t</sub> )					(URBANIZED BASINS)			
BASIN ID	D.A. (ac)	Hydrologic Soils Group	Impervious (%)	C <sub>5</sub>	C <sub>100</sub>	L (ft)	S <sub>o</sub> (%)	t <sub>i</sub> (min)	L <sub>t</sub> (ft)	S <sub>t</sub> (%)	K	VEL. (ft/s)	t <sub>t</sub> (min)	COMP. t <sub>c</sub> (min)	TOTAL LENGTH (ft)	Urbanized t <sub>c</sub> (min)	t <sub>c</sub> (min)
A1	5.17	A	2%	0.08	0.35	212	2.0%	21.4	517	2.1%	10.0	1.4	6.0	27.4	729.0	32.1	27.4
A2	27.48	A	0%	0.08	0.35	297	2.5%	23.4	1475	2.4%	10.0	1.6	15.7	39.1	1772.0	43.5	39.1
A3	11.68	A	0%	0.08	0.35	121	5.4%	11.6	784	2.7%	10.0	1.7	7.9	19.5	905.0	34.8	19.5
B1	11.78	A	0%	0.08	0.35	297	2.9%	22.4	380	5.2%	10.0	2.3	2.8	25.2	677.0	29.1	25.2
OS1	9.27	A	37%	0.40	0.55	298	2.7%	15.7	737	2.4%	10.0	1.5	8.0	23.7	1035.0	25.4	23.7
OS2	1.94	A	100%	0.90	0.96	117	3.1%	2.7	1745	1.6%	20.0	2.5	11.5	14.2	1862.0	19.0	14.2
OS3	2.36	A	100%	0.90	0.96	41	2.5%	1.7	1681	1.8%	20.0	2.7	10.5	12.2	1722.0	18.1	12.2
OS4	11.71	A	4%	0.10	0.36	491	1.4%	36.0	940	5.6%	10.0	2.4	6.6	42.6	1431.0	32.4	32.4
OS5	3.46	A	0%	0.08	0.35	298	3.0%	22.1	784	2.4%	10.0	1.6	8.4	30.4	1082.0	35.3	30.4
OS6	18.38	A	11%	0.54	0.66	165	3.4%	8.6	612	2.7%	10.0	1.6	6.2	14.8	777.0	30.0	14.8
OS7	33.07	A	19%	0.28	0.48	298	3.0%	17.9	1664	2.7%	10.0	1.6	16.9	34.7	1962.0	37.2	34.7

NOTES:

$$t_c = t_i + t_t$$

Equation 6-2

$$t_i = \frac{0.395(1.1 - C_5)\sqrt{L}}{S_o^{0.33}}$$

Equation 6-3

Where:

t<sub>c</sub> = computed time of concentration (minutes)

t<sub>i</sub> = overland (initial) flow time (minutes)

t<sub>t</sub> = channelized flow time (minutes).

Where:

t<sub>i</sub> = overland (initial) flow time (minutes)

C<sub>5</sub> = runoff coefficient for 5-year frequency (from Table 6-4)

L<sub>i</sub> = length of overland flow (ft)

S<sub>o</sub> = average slope along the overland flow path (ft/ft).

Use a minimum t<sub>c</sub> value of 5 minutes for urbanized areas and a minimum t<sub>c</sub> value of 10 minutes for areas that are not considered urban. Use minimum values even when calculations result in a lesser time of concentration.

$$t_t = \frac{L_t}{60K\sqrt{S_o}} = \frac{L_t}{60V_t}$$

Equation 6-4  $t_t = (26 - 17i) + \frac{L_t}{60(14i + 9)\sqrt{S_t}}$

Equation 6-5

Where:

t<sub>t</sub> = channelized flow time (travel time, min)

L<sub>t</sub> = waterway length (ft)

S<sub>o</sub> = waterway slope (ft/ft)

V<sub>t</sub> = travel time velocity (ft/sec) = K√S<sub>o</sub>

K = NRCS conveyance factor (see Table 6-2).

Where:

t<sub>c</sub> = minimum time of concentration for first design point when less than t<sub>c</sub> from Equation 6-1.

L<sub>t</sub> = length of channelized flow path (ft)

i = imperviousness (expressed as a decimal)

S<sub>t</sub> = slope of the channelized flow path (ft/ft).

Table 6-2. NRCS Conveyance factors, K

Type of Land Surface	Conveyance Factor, K
Heavy meadow	2.5
Tillage/field	5
Short pasture and lawns	7
Nearly bare ground	10
Grassed waterway	15
Paved areas and shallow paved swales	20



**STANDARD FORM SF-3 - EXISTING**  
**STORM DRAINAGE SYSTEM DESIGN**  
 (RATIONAL METHOD PROCEDURE)

Subdivision: Sterling Ranch Subdivision- Existing  
 Location: El Paso County  
 Design Storm: 5-Year

Project Name: Sterling Ranch Phase 2  
 Project No.: 25188.02  
 Calculated By: CJD  
 Checked By: \_\_\_\_\_  
 Date: 5/4/21

STREET	Design Point	DIRECT RUNOFF							TOTAL RUNOFF				STREET/SWALE			PIPE				TRAVEL TIME			REMARKS	
		Basin ID	Area (Ac)	Runoff Coeff.	$t_c$ (min)	C*A (Ac)	I (in/hr)	Q (cfs)	$t_c$ (min)	C*A (ac)	I (in/hr)	Q (cfs)	$Q_{street/swale}$ (cfs)	C*A (ac)	Slope (%)	$Q_{pipe}$ (cfs)	C*A (ac)	Slope (%)	Pipe Size (inches)	Length (ft)	Velocity (fps)	$t_t$ (min)		
	1	A1	5.17	0.08	27.4	0.41	2.62	1.1																
	2	A2	27.48	0.08	39.1	2.20	2.08	4.6																Basin A2
	3	OS1	9.27	0.40	23.7	3.71	2.83	10.5																Basin A1
	4	OS5	3.46	0.08	30.4	0.28	2.46	0.7																Basin A4
	6	B1	11.78	0.08	25.2	0.94	2.74	2.6																Basin OS1
	7	OS2	1.94	0.90	14.2	1.75	3.60	6.3																Basin OS2
	8	OS3	2.36	0.90	12.2	2.12	3.83	8.1																Basin OS3
	9	OS4	11.71	0.10	32.4	1.18	2.37	2.8																Basin OS4
	10	OS6	18.38	0.54	14.8	10.00	3.54	35.4					10.0	3.4						998	1.8	9.1		Basin OS6 travel to design point 5.1
	11	OS7	33.07	0.28	34.7	9.13	2.26	20.6					9.13	3.2						936	1.8	8.7		Basin OS7 travel to design point 5.1
	5	A3	11.68	0.08	19.5	0.93	3.13	2.9																Basin A3
	5.1								19.5	20.06	3.13	62.7												Design point 5.1 fed by basins A3, OS6, and OS7

Notes:  
 Street and Pipe C\*A values are determined by Q/I using the catchment's intensity value.  
 All pipes are private and RCP unless otherwise noted. Pipe size shown in table column.

**STANDARD FORM SF-3 - EXISTING**  
**STORM DRAINAGE SYSTEM DESIGN**  
 (RATIONAL METHOD PROCEDURE)

Subdivision: Sterling Ranch Subdivision- Existing  
 Location: El Paso County  
 Design Storm: 100-Year

Project Name: Sterling Ranch Phase 2  
 Project No.: 25188.02  
 Calculated By: CJD  
 Checked By: \_\_\_\_\_  
 Date: 5/4/21

Description	Design Point	DIRECT RUNOFF							TOTAL RUNOFF				STREET/SWALE			PIPE			TRAVEL TIME			REMARKS			
		Basin ID	Area (ac)	Runoff Coeff.	t <sub>c</sub> (min)	C*A (ac)	I (in/hr)	Q (cfs)	t <sub>c</sub> (min)	C*A (ac)	I (in/hr)	Q (cfs)	Q <sub>street/swale</sub> (cfs)	C*A (ac)	Slope (%)	Q <sub>pipe</sub> (cfs)	C*A (ac)	Slope (%)	Pipe Size (inches)	Length (ft)	Velocity (fps)		t <sub>t</sub> (min)		
	1	A1	5.17	0.35	27.4	1.81	4.39	8.0																	
	2	A2	27.48	0.35	39.1	9.62	3.49	33.6																	Basin A2
	3	OS1	9.27	0.55	23.7	5.13	4.76	24.4																	Basin A1
	4	OS5	3.46	0.35	30.4	1.21	4.13	5.0																	Basin A4
	6	B1	11.78	0.35	25.2	4.12	4.60	19.0																	Basin OS1
	7	OS2	1.94	0.96	14.2	1.86	6.04	11.2																	Basin OS2
	8	OS3	2.36	0.96	12.2	2.27	6.44	14.6																	Basin OS3
	9	OS4	11.71	0.36	32.4	4.25	3.97	16.9																	Basin OS4
	10	OS6	18.38	0.66	14.8	12.15	5.94	72.2					12.2	3.4						998	1.8	9.1			Basin OS6 travel to design point 5.1
	11	OS7	33.07	0.48	34.7	15.93	3.79	60.4					15.93	3.2						936	1.8	8.7			Basin OS7 travel to design point 5.1
	5	A3	11.68	0.35	19.5	4.09	5.25	21.5																	Basin A3
	5.1								19.5	32.17	5.25	168.9													Design point 5.1 fed by basins A3, OS6, and OS7

Notes:  
 Street and Pipe C\*A values are determined by Q/I using the catchment's intensity value.  
 All pipes are private and RCP unless otherwise noted. Pipe size shown in table column.

STANDARD FORM SF-3 - EXISTING  
 STORM DRAINAGE SYSTEM DESIGN  
 (RATIONAL METHOD PROCEDURE)

Subdivision: Sterling Ranch Subdivision- Existing  
 Location: El Paso County  
 Design Storm: 100-Year

Project Name: Sterling Ranch Phase 2  
 Project No.: 25188.02  
 Calculated By: CJD  
 Checked By: \_\_\_\_\_  
 Date: 5/4/21

Description	Design Point	DIRECT RUNOFF						TOTAL RUNOFF			STREET/SWALE			PIPE			TRAVEL TIME			REMARKS		
		Basin ID	Area (ac)	Runoff Coeff.	$t_c$ (min)	$C^*A$ (ac)	$I$ (in/hr)	$Q$ (cfs)	$t_c$ (min)	$C^*A$ (ac)	$I$ (in/hr)	$Q$ (cfs)	$Q_{street/swale}$ (cfs)	$C^*A$ (ac)	Slope (%)	$Q_{pipe}$ (cfs)	$C^*A$ (ac)	Slope (%)	Pipe Size (inches)		Length (ft)	Velocity (fps)

## COMPOSITE % IMPERVIOUS & COMPOSITE PROPOSED RUNOFF COEFFICIENT CALCULATIONS

Subdivision: Sterling Ranch Subdivision- Interim  
 Location: El Paso County

Project Name: Sterling Ranch Phase 2  
 Project No.: 25188.02  
 Calculated By: CJD  
 Checked By: \_\_\_\_\_  
 Date: 5/4/20

Basin ID	Total Area (ac)	Streets (100% Impervious)				Residential (65% Impervious)				Light Industrial (80% Impervious) Commercial (95% Impervious)				Lawns (0% Impervious) School (55% Impervious)				Basins Total Weighted C Values		Basins Total Weighted % Imp.
		C <sub>5</sub>	C <sub>100</sub>	Area (ac)	Weighted % Imp.	C <sub>5</sub>	C <sub>100</sub>	Area (ac)	Weighted % Imp.	C <sub>5</sub>	C <sub>100</sub>	Area (ac)	Weighted % Imp.	C <sub>5</sub>	C <sub>100</sub>	Area (ac)	Weighted % Imp.	C <sub>5</sub>	C <sub>100</sub>	
A1	4.31	0.90	0.96	0.92	21.3%	0.45	0.59	2.79	42.1%	0.59	0.70	0.00	0.0%	0.08	0.35	0.60	0.0%	0.49	0.64	63.4%
A5	0.45	0.90	0.96	0.17	37.8%	0.45	0.59	0.28	40.4%	0.59	0.70	0.00	0.0%	0.08	0.35	0.00	0.0%	0.62	0.73	78.2%
I1	21.99	0.90	0.96	0.12	0.5%	0.45	0.59	0.00	0.0%	0.59	0.70	0.00	0.0%	0.08	0.35	21.87	0.0%	0.08	0.35	0.5%
I2	3.47	0.90	0.96	0.00	0.0%	0.45	0.59	0.00	0.0%	0.59	0.70	0.00	0.0%	0.08	0.35	3.47	0.0%	0.08	0.35	0.0%
B1	2.44	0.90	0.96	1.04	42.6%	0.45	0.59	1.40	37.3%	0.59	0.70	0.00	0.0%	0.08	0.35	0.00	0.0%	0.64	0.75	79.9%
B2	4.33	0.90	0.96	0.94	21.7%	0.45	0.59	3.39	50.9%	0.59	0.70	0.00	0.0%	0.08	0.35	0.00	0.0%	0.55	0.67	72.6%
C1	3.29	0.90	0.96	0.72	21.9%	0.45	0.59	1.66	32.8%	0.59	0.70	0.00	0.0%	0.08	0.35	0.91	0.0%	0.45	0.60	54.7%
C2	6.74	0.90	0.96	1.49	22.1%	0.45	0.59	4.21	40.6%	0.59	0.70	0.00	0.0%	0.08	0.35	1.04	0.0%	0.49	0.63	62.7%
C3	3.11	0.90	0.96	0.10	3.2%	0.45	0.59	0.37	7.7%	0.59	0.70	0.00	0.0%	0.08	0.35	2.64	0.0%	0.15	0.40	10.9%
B6	0.78	0.90	0.96	0.00	0.0%	0.45	0.59	0.53	44.2%	0.59	0.70	0.00	0.0%	0.08	0.35	0.25	0.0%	0.33	0.51	44.2%
B5	0.45	0.90	0.96	0.00	0.0%	0.45	0.59	0.35	50.6%	0.59	0.70	0.00	0.0%	0.08	0.35	0.10	0.0%	0.37	0.54	50.6%
B4	1.55	0.90	0.96	0.00	0.0%	0.45	0.59	1.35	56.6%	0.59	0.70	0.00	0.0%	0.08	0.35	0.20	0.0%	0.40	0.56	56.6%
B3	0.66	0.90	0.96	0.34	51.5%	0.45	0.59	0.12	11.8%	0.59	0.70	0.00	0.0%	0.08	0.35	0.20	0.0%	0.57	0.71	63.3%
C4	1.34	0.90	0.96	0.19	14.2%	0.45	0.59	0.80	38.8%	0.59	0.70	0.00	0.0%	0.08	0.35	0.35	0.0%	0.42	0.58	53.0%
D1	0.77	0.90	0.96	0.00	0.0%	0.45	0.59	0.00	0.0%	0.59	0.70	0.00	0.0%	0.08	0.35	0.77	0.0%	0.08	0.35	0.0%
D2	3.92	0.90	0.96	0.00	0.0%	0.45	0.59	0.00	0.0%	0.59	0.70	0.00	0.0%	0.08	0.35	3.92	0.0%	0.08	0.35	0.0%
OS6	18.38	0.90	0.96	0.00	0.0%	0.45	0.59	0.00	0.0%	0.90	0.90	10.40	53.8%	0.08	0.35	7.98	0.0%	0.54	0.66	53.8%
OS4	11.71	0.90	0.96	0.00	0.0%	0.45	0.59	0.65	3.6%	0.59	0.70	0.00	0.0%	0.58	0.68	11.06	51.9%	0.57	0.68	55.6%
OS7	33.07	0.90	0.96	0.00	0.0%	0.45	0.59	0.00	0.0%	0.90	0.90	7.91	22.7%	0.08	0.35	25.16	0.0%	0.28	0.48	22.7%
TOTAL (A1-C4)(I1-I2)	59.60																			28.9%
TOTAL (OS4 -OS7)	63.16																			37.8%
TOTAL	122.76																			33.5%

**PROPOSED  
STANDARD FORM SF-2  
TIME OF CONCENTRATION**

Subdivision: Sterling Ranch Subdivision- Interim  
Location: El Paso County

Project Name: Sterling Ranch Phase 2  
Project No.: 25188.02  
Calculated By: CJD  
Checked By: \_\_\_\_\_  
Date: 5/4/20

SUB-BASIN DATA						INITIAL/OVERLAND (T <sub>i</sub> )			TRAVEL TIME (T <sub>t</sub> )					t <sub>c</sub> CHECK (URBANIZED BASINS)			FINAL
BASIN ID	D.A. (ac)	Hydrologic Soils Group	Impervious (%)	C <sub>5</sub>	C <sub>100</sub>	L (ft)	S <sub>o</sub> (%)	t <sub>i</sub> (min)	L <sub>t</sub> (ft)	S <sub>t</sub> (%)	K	VEL. (ft/s)	t <sub>t</sub> (min)	COMP. t <sub>c</sub> (min)	TOTAL LENGTH (ft)	Urbanized t <sub>c</sub> (min)	t <sub>c</sub> (min)
A1	4.31	A	63%	0.49	0.64	79	1.7%	8.2	1007	3.7%	20.0	3.8	4.4	12.5	1086.0	20.1	12.5
A5	0.45	A	78%	0.62	0.73	54	3.7%	4.1	217	3.9%	20.0	4.0	0.9	5.0	271.0	13.6	5.0
I1	21.99	A	1%	0.08	0.35	793	3.1%	35.5	627	3.7%	10.0	1.9	5.4	41.0	1420.0	31.9	31.9
I2	3.47	A	0%	0.08	0.35	383	3.2%	24.6	394	1.0%	10.0	1.0	6.6	31.1	777.0	33.3	31.1
B1	2.44	A	80%	0.64	0.75	50	2.5%	4.3	1066	1.6%	20.0	2.5	7.1	11.4	1116.0	19.4	11.4
B2	4.33	A	73%	0.55	0.67	226	4.9%	8.8	346	0.7%	20.0	1.7	3.4	12.2	572.0	17.2	12.2
C1	3.29	A	55%	0.45	0.60	228	4.3%	11.0	393	1.8%	20.0	2.7	2.5	13.5	621.0	19.7	13.5
C2	6.74	A	63%	0.49	0.63	99	1.8%	9.0	796	1.7%	20.0	2.6	5.1	14.1	895.0	21.1	14.1
C3	3.11	A	11%	0.15	0.40	144	9.6%	9.8	255	3.5%	15.0	2.8	1.5	11.3	399.0	26.3	11.3
B6	0.78	A	44%	0.33	0.51	246	1.5%	19.1	0	1.0%	20.0	2.0	0.0	19.1	246.0	18.5	18.5
B5	0.45	A	51%	0.37	0.54	129	5.0%	8.8	0	1.0%	20.0	2.0	0.0	8.8	129.0	17.4	8.8
B4	1.55	B	57%	0.40	0.56	222	11.0%	8.5	914	1.1%	20.0	2.1	7.4	15.9	1136.0	25.1	15.9
B3	0.66	A	63%	0.57	0.71	165	3.4%	8.2	612	2.7%	10.0	1.6	6.2	14.4	777.0	18.7	14.4
C4	1.34	A	53%	0.42	0.58	298	3.0%	14.8	1664	2.7%	10.0	1.6	16.9	31.7	1962.0	27.3	27.3
D1	0.77	A	0%	0.08	0.35	16	2.0%	5.9	570	6.0%	10.0	2.4	3.9	9.7	586.0	30.3	9.7
D2	3.92	A	0%	0.08	0.35	105	25.0%	6.5	975	50.0%	15.0	10.6	1.5	8.1	1080.0	28.6	8.1
OS6	18.38	A	54%	0.54	0.66	165	3.4%	8.6	612	2.7%	10.0	1.6	6.2	14.8	777.0	20.6	14.8
OS4	11.71	A	56%	0.57	0.68	491	1.4%	19.0	940	5.6%	10.0	2.4	6.6	25.6	1431.0	20.5	20.5
OS7	33.07	A	23%	0.28	0.48	298	3.0%	17.9	1664	2.7%	10.0	1.6	16.9	34.7	1962.0	36.0	34.7

**NOTES:**

$$t_c = t_i + t_t$$

Where:

t<sub>c</sub> = computed time of concentration (minutes)

t<sub>i</sub> = overland (initial) flow time (minutes)

t<sub>t</sub> = channelized flow time (minutes)

$$t_t = \frac{L_t}{60K\sqrt{S_o}} = \frac{L_t}{60V}$$

Where:

t<sub>t</sub> = channelized flow time (travel time, min)

L<sub>t</sub> = waterway length (ft)

S<sub>o</sub> = waterway slope (ft/ft)

V = travel time velocity (ft/sec) = K<sup>0.5</sup>S<sub>o</sub><sup>0.5</sup>

K = NRCS conveyance factor (see Table 6-2)

Use a minimum t<sub>c</sub> value of 5 minutes for urbanized areas and a minimum t<sub>c</sub> value of 10 minutes for areas that are not considered urban. Use minimum values even when calculations result in a lesser time of concentration.

Equation 6-2

$$t_i = \frac{0.395(1 - C_1)\sqrt{L}}{S_o^{0.33}}$$

Where:

t<sub>i</sub> = overland (initial) flow time (minutes)

C<sub>1</sub> = runoff coefficient for 5-year frequency (from Table 6-4)

L = length of overland flow (ft)

S<sub>o</sub> = average slope along the overland flow path (ft/ft)

Equation 6-4

$$t_c = (26 - 17i) + \frac{L_t}{60(14i + 9)\sqrt{S_o}}$$

Where:

t<sub>c</sub> = minimum time of concentration for first design point when less than t<sub>i</sub> from Equation 6-1.

L<sub>t</sub> = length of channelized flow path (ft)

i = imperviousness (expressed as a decimal)

S<sub>o</sub> = slope of the channelized flow path (ft/ft)

Table 6-2. NRCS Conveyance factors, K

Type of Land Surface	Conveyance Factor, K
Heavy meadow	2.5
Tillage/field	5
Short pasture and lawns	7
Nearly bare ground	10
Grassed waterway	15
Paved areas and shallow paved swales	20

Equation 6-3

Equation 6-5

STANDARD FORM SF-3 - PROPOSED  
STORM DRAINAGE SYSTEM DESIGN  
(RATIONAL METHOD PROCEDURE)

Subdivision: Sterling Ranch Subdivision- Interim  
Location: El Paso County  
Design Storm: 5-Year

Project Name: Sterling Ranch Phase 2  
Project No.: 25188.02  
Calculated By: CJD  
Checked By:  
Date: 5/4/20

STREET	Design Point	DIRECT RUNOFF							TOTAL RUNOFF				STREET/SWALE			PIPE				TRAVEL TIME			REMARKS				
		Basin ID	Area (Ac)	Runoff Coeff.	t <sub>c</sub> (min)	C*A (Ac)	I (in/hr)	Q (cfs)	t <sub>c</sub> (min)	C*A (ac)	I (in/hr)	Q (cfs)	Q <sub>street/swale</sub> (cfs)	C*A (ac)	Slope (%)	Q <sub>pipe</sub> (cfs)	C*A (ac)	Slope (%)	Pipe Size (inches)	Length (ft)	Velocity (fps)	t <sub>t</sub> (min)					
	1	OS7	33.07	0.28	34.7	9.13	2.26	20.6											20.6	9.13	1.0	42	725	8.2	1.5	Offsite Barbarick Subdivision pond release Piped to DP 3	
	2	OS4	11.71	0.57	20.5	6.71	3.05	20.5											20.5	6.71	1.0	36	112	8.3	0.2	Offsite future school Piped to DP 3	
	3								36.2	15.84	2.20	34.8															Piped to existing storm sewer in Sterling Ranch Road
	4	OS6	18.38	0.54	14.8	10.00	3.54	35.4											35.4	10.00	1.0	48	800	9.4	1.4	Offsite subdivision pond release Piped to DP 7.1	
	5	C2	6.74	0.49	14.1	3.32	3.61	12.0											12.0	3.32	1.0	24	63	7.3	0.1	Sump Inlet Piped to DP 6.1	
	6	C1	3.29	0.45	13.5	1.47	3.68	5.4																		Sump Inlet Piped to DP 6.1	
	6.1								14.3	4.79	3.59	17.2							17.2	4.79	1.0	36	245	7.9	0.5	Piped to DP 7.1	
	7	C3	3.11	0.15	11.3	0.47	3.95	1.9																		Area Inlet Piped to DP 7.1	
	7.1								16.2	15.26	3.40	51.9															Piped to existing storm sewer in Sterling Ranch Road
	8	C4	1.34	0.42	27.3	0.56	2.62	1.5																			Offsite flow to existing inlet in Sterling Ranch Road Piped to existing storm sewer in Sterling Ranch Road
	9	B3	0.66	0.57	14.4	0.38	3.58	1.4																			Offsite flow to existing inlet in Sterling Ranch Road Piped to existing storm sewer in Sterling Ranch Road
	10	B4	1.55	0.40	15.9	0.62	3.43	2.1											2.1	0.62	1.0	12	380	4.7	1.3	Rear lot and area inlets Piped to DP 11.1	
	11	B5	0.45	0.37	8.8	0.17	4.31	0.7																			Area Inlet Piped to DP 14.1
	11.1								17.3	0.79	3.31	2.6							2.6	0.79	1.0	18	357	4.9	1.2	Piped to DP 14.1	
	12	B2	4.33	0.55	12.2	2.37	3.83	9.1											9.1	2.37	1.0	18	38	6.7	0.1	Sump Inlet Piped to DP 13.1	
	13	B1	2.44	0.64	11.4	1.57	3.93	6.2																			Sump Inlet Piped to DP 13.1
	13.1								12.3	3.94	3.82	15.0							15.0	3.94	1.0	24	125	7.7	0.3	Piped to DP 14.1	
	14	B6	0.78	0.33	18.5	0.26	3.21	0.8																			Area Inlet Piped to DP 14.1
	14.1								18.5	4.99	3.21	16.0							16.0	4.99	1.0	24	415	7.8	0.9	Piped to DP 15.1	

**STANDARD FORM SF-3 - PROPOSED**  
**STORM DRAINAGE SYSTEM DESIGN**  
 (RATIONAL METHOD PROCEDURE)

Subdivision: Sterling Ranch Subdivision- Interim  
 Location: El Paso County  
 Design Storm: 5-Year

Project Name: Sterling Ranch Phase 2  
 Project No.: 25188.02  
 Calculated By: CJD  
 Checked By: \_\_\_\_\_  
 Date: 5/4/20

STREET	Design Point	DIRECT RUNOFF							TOTAL RUNOFF				STREET/SWALE			PIPE				TRAVEL TIME			REMARKS
		Basin ID	Area (Ac)	Runoff Coeff.	t <sub>c</sub> (min)	C*A (Ac)	I (in/hr)	Q (cfs)	t <sub>c</sub> (min)	C*A (ac)	I (in/hr)	Q (cfs)	Q <sub>street/swale</sub> (cfs)	C*A (ac)	Slope (%)	Q <sub>pipe</sub> (cfs)	C*A (ac)	Slope (%)	Pipe Size (inches)	Length (ft)	Velocity (fps)	t <sub>t</sub> (min)	
	15	A1	4.31	0.49	12.5	2.13	3.79	8.1					0.7	0.18	1.6	7.4				230	2.5	1.5	On-grade Inlet Captured Flows piped to DP 15.1, Bypass flow to DP 17
	15.1								19.4	7.12	3.14	22.3				22.3	7.12	1.0	24	45	8.2	0.1	On-grade Inlet Captured Flows piped to DP 16.1
	16	A5	0.45	0.62	5.0	0.28	5.16	1.4															On-grade Inlet Captured Flows piped to DP 16.1
	16.1								19.5	7.40	3.13	23.2				23.2	7.40	1.0	24	125	8.2	0.3	FES release to drainage channel
	11	I1	21.99	0.08	31.9	1.86	2.39	4.4															FES
	11.1								31.9	9.26	2.39	22.1				22.1	9.26	0.4	42	62	6.1	0.2	Combined flow from DP11 & DP16.1 Piped to Existing 84" RCP
	12	I2	3.47	0.08	31.1	0.28	2.43	0.7															Piped to Existing 84" RCP

Notes:  
 Street and Pipe C\*A values are determined by Q/i using the catchment's intensity value.  
 All pipes are private and RCP unless otherwise noted. Pipe size shown in table column.

STANDARD FORM SF-3 - PROPOSED  
STORM DRAINAGE SYSTEM DESIGN  
(RATIONAL METHOD PROCEDURE)

Subdivision: Sterling Ranch Subdivision- Interim  
Location: El Paso County  
Design Storm: 100-Year

Project Name: Sterling Ranch Phase 2  
Project No.: 25188.02  
Calculated By: CJD  
Checked By: \_\_\_\_\_  
Date: 5/4/20

Description	Design Point	DIRECT RUNOFF							TOTAL RUNOFF				STREET/SWALE			PIPE				TRAVEL TIME			REMARKS
		Basin ID	Area (ac)	Runoff Coeff.	t <sub>c</sub> (min)	C*A (ac)	I (in/hr)	Q (cfs)	t <sub>c</sub> (min)	C*A (ac)	I (in/hr)	Q (cfs)	Q <sub>street/swale</sub> (cfs)	C*A (ac)	Slope (%)	Q <sub>pipe</sub> (cfs)	C*A (ac)	Slope (%)	Pipe Size (inches)	Length (ft)	Velocity (fps)	t <sub>r</sub> (min)	
	1	OS7	33.07	0.48	34.7	15.93	3.79	60.4							60.4	15.93	1.0	42	725	10.9	1.1	Offsite Barbarick Subdivision pond release Piped to DP 3	
	2	OS4	11.71	0.68	20.5	7.90	5.12	40.5							40.5	7.90	1.0	36	112	9.9	0.2	Offsite future school Piped to DP 3	
	3								35.9	23.83	3.71	88.5											Piped to existing storm sewer in Sterling Ranch Road
	4	OS6	18.38	0.66	14.8	12.15	5.94	72.2							72.2	12.15	1.0	48	800	11.4	1.2	Offsite subdivision pond release Piped to DP 7.1	
	5	C2	6.74	0.63	14.1	4.28	6.06	25.9							25.9	4.28	1.0	24	63	8.3	0.1	Sump Inlet Piped to DP 6.1	
	6	C1	3.29	0.60	13.5	1.99	6.18	12.3														Sump Inlet Piped to DP 6.1	
	6.1								14.3	6.27	6.04	37.8			37.8	6.27	1.0	36	245	9.7	0.4	Piped to DP 7.1	
	7	C3	3.11	0.40	11.3	1.24	6.63	8.2														Area Inlet Piped to DP 7.1	
	7.1								16.0	19.66	5.75	113.0											Piped to existing storm sewer in Sterling Ranch Road
	8	C4	1.34	0.58	27.3	0.78	4.40	3.4														Offsite flow to existing inlet in Sterling Ranch Road Piped to existing storm sewer in Sterling Ranch Road	
	9	B3	0.66	0.71	14.4	0.47	6.01	2.8														Offsite flow to existing inlet in Sterling Ranch Road Piped to existing storm sewer in Sterling Ranch Road	
	10	B4	1.55	0.56	15.9	0.87	5.76	5.0							5.0	0.87	1.0	12	380	6.4	1.0	Rear lot and area inlets Piped to DP 11.1	
	11	B5	0.45	0.54	8.8	0.24	7.24	1.7														Area Inlet Piped to DP 14.1	
	11.1								16.9	1.11	5.61	6.2			6.2	1.11	1.0	18	357	6.2	1.0	Piped to DP 14.1	
	12	B2	4.33	0.67	12.2	2.90	6.43	18.7							18.7	2.90	1.0	18	38	10.6	0.1	Sump Inlet Piped to DP 13.1	
	13	B1	2.44	0.75	11.4	1.82	6.60	12.0														Sump Inlet Piped to DP 13.1	
	13.1								12.3	4.72	6.42	30.3			30.3	4.72	1.0	24	125	9.7	0.2	Piped to DP 14.1	
	14	B6	0.78	0.51	18.5	0.40	5.38	2.2														Area Inlet Piped to DP 14.1	
	14.1								18.5	6.23	5.38	33.5			33.5	6.23	1.0	24	415	10.7	0.6	Piped to DP 15.1	
	15	A1	4.31	0.64	12.5	2.74	6.37	17.4					10.0	1.5777	7.4				230	2.5	1.5	On-grade Inlet Captured Flows piped to DP 15.1, Bypass flow to DP 17	
	15.1								19.1	8.97	5.30	47.5			47.5	8.97	1.0	24	45	15.1	0.0	On-grade Inlet Captured Flows piped to DP 16.1	



STANDARD FORM SF-3 - PROPOSED  
STORM DRAINAGE SYSTEM DESIGN  
(RATIONAL METHOD PROCEDURE)

Subdivision: Sterling Ranch Subdivision- Interim  
 Location: El Paso County  
 Design Storm: 100-Year

Project Name: Sterling Ranch Phase 2  
 Project No.: 25188.02  
 Calculated By: CJD  
 Checked By: \_\_\_\_\_  
 Date: 5/4/20

Description	Design Point	DIRECT RUNOFF							TOTAL RUNOFF				STREET/SWALE			PIPE				TRAVEL TIME			REMARKS
		Basin ID	Area (ac)	Runoff Coeff.	t <sub>c</sub> (min)	C*A (ac)	I (in/hr)	Q (cfs)	t <sub>c</sub> (min)	C*A (ac)	I (in/hr)	Q (cfs)	Q <sub>street/swale</sub> (cfs)	C*A (ac)	Slope (%)	Q <sub>pipe</sub> (cfs)	C*A (ac)	Slope (%)	Pipe Size (inches)	Length (ft)	Velocity (fps)	t <sub>r</sub> (min)	
	16	A5	0.45	0.73	5.0	0.33	8.66	2.9															On-grade Inlet Captured Flows piped to DP 16.1
	16.1								19.2	9.30	5.29	49.2			49.2	9.30	1.0	24	125	15.7	0.1	FES release to drainage channel FES	
	11	I1	21.99	0.35	31.9	7.77	4.01	31.2															Combined flow from DPI1 & DP16.1 Piped to Existing 84" RCP
	11.1								31.9	17.07	4.01	68.4			68.4	17.07	0.4	42	62	7.7	0.1	Piped to Existing 84" RCP	
	12	I2	3.47	0.35	31.1	1.21	4.07	4.9															Piped to Existing 84" RCP

Notes:  
 Street and Pipe C\*A values are determined by Q/i using the catchment's intensity value.  
 All pipes are private and RCP unless otherwise noted. Pipe size shown in table column.

## COMPOSITE % IMPERVIOUS & COMPOSITE PROPOSED RUNOFF COEFFICIENT CALCULATIONS

Subdivision: Sterling Ranch Subdivision -Proposed  
 Location: El Paso County

Project Name: Sterling Ranch Phase 2  
 Project No.: 25188.02  
 Calculated By: CJD  
 Checked By: \_\_\_\_\_  
 Date: 4/27/20

Basin ID	Total Area (ac)	Paved/Streets (100% Impervious)				Residential (65% Impervious)				Light Industrial (80% Impervious) Commercial (95% Impervious)				Lawns (0% Impervious) School (55% Impervious)				Basins Total Weighted C Values		Basins Total Weighted % Imp.
		C <sub>5</sub>	C <sub>100</sub>	Area (ac)	Weighted % Imp.	C <sub>5</sub>	C <sub>100</sub>	Area (ac)	Weighted % Imp.	C <sub>5</sub>	C <sub>100</sub>	Area (ac)	Weighted % Imp.	C <sub>5</sub>	C <sub>100</sub>	Area (ac)	Weighted % Imp.	C <sub>5</sub>	C <sub>100</sub>	
A1	4.31	0.90	0.96	0.92	21.3%	0.45	0.59	2.79	42.1%	0.59	0.70	0.00	0.0%	0.08	0.35	0.60	0.3%	0.49	0.64	63.7%
A2	1.41	0.90	0.96	0.22	15.6%	0.45	0.59	0.34	15.7%	0.59	0.70	0.00	0.0%	0.08	0.35	0.85	0.0%	0.30	0.50	31.3%
A3	3.68	0.90	0.96	0.71	19.3%	0.45	0.59	2.59	45.7%	0.59	0.70	0.00	0.0%	0.08	0.35	0.38	0.0%	0.50	0.64	65.1%
A4	3.94	0.90	0.96	0.67	17.0%	0.45	0.59	2.13	35.1%	0.59	0.70	0.00	0.0%	0.08	0.35	1.14	0.0%	0.42	0.58	52.1%
A5	0.45	0.90	0.96	0.17	37.8%	0.45	0.59	0.28	40.4%	0.59	0.70	0.00	0.0%	0.08	0.35	0.00	0.0%	0.62	0.73	78.2%
A6	7.60	0.90	0.96	1.76	23.2%	0.45	0.59	5.84	49.9%	0.59	0.70	0.00	0.0%	0.08	0.35	0.00	0.0%	0.55	0.68	73.1%
A7	1.43	0.90	0.96	0.43	29.8%	0.45	0.59	1.00	45.5%	0.59	0.70	0.00	0.0%	0.08	0.35	0.00	0.0%	0.58	0.70	75.3%
A8	4.22	0.90	0.96	0.12	2.8%	0.45	0.59	0.68	10.5%	0.59	0.70	0.00	0.0%	0.08	0.35	3.42	0.0%	0.16	0.41	13.3%
B1	2.44	0.90	0.96	1.04	42.6%	0.45	0.59	1.40	37.3%	0.59	0.70	0.00	0.0%	0.08	0.35	0.00	0.0%	0.64	0.75	79.9%
B2	4.33	0.90	0.96	0.94	21.7%	0.45	0.59	3.39	50.9%	0.59	0.70	0.00	0.0%	0.08	0.35	0.00	0.0%	0.55	0.67	72.6%
C1	2.62	0.90	0.96	0.72	27.5%	0.45	0.59	1.66	41.2%	0.59	0.70	0.00	0.0%	0.08	0.35	0.24	0.0%	0.54	0.67	68.7%
C2	6.74	0.90	0.96	1.49	22.1%	0.45	0.59	4.21	40.6%	0.59	0.70	0.00	0.0%	0.08	0.35	1.04	0.0%	0.49	0.63	62.7%
C3	3.77	0.90	0.96	0.13	3.4%	0.45	0.59	0.37	6.4%	0.59	0.70	0.00	0.0%	0.08	0.35	3.27	0.0%	0.14	0.39	9.8%
A9	2.02	0.90	0.96	0.06	3.0%	0.45	0.59	0.15	4.8%	0.59	0.70	0.00	0.0%	0.08	0.35	1.81	0.0%	0.13	0.39	7.8%
A10	3.23	0.90	0.96	0.14	4.3%	0.45	0.59	0.98	19.7%	0.59	0.70	0.00	0.0%	0.08	0.35	2.11	0.0%	0.23	0.45	24.1%
B6	0.78	0.90	0.96	0.00	0.0%	0.45	0.59	0.53	44.2%	0.59	0.70	0.00	0.0%	0.08	0.35	0.25	0.0%	0.33	0.51	44.2%
B5	0.45	0.90	0.96	0.00	0.0%	0.45	0.59	0.35	50.6%	0.59	0.70	0.00	0.0%	0.08	0.35	0.10	0.0%	0.37	0.54	50.6%
B4	1.80	0.90	0.96	0.05	2.6%	0.45	0.59	1.35	48.8%	0.59	0.70	0.00	0.0%	0.08	0.35	0.40	0.0%	0.38	0.55	51.3%
B3	2.36	0.90	0.96	1.37	57.9%	0.45	0.59	0.12	3.3%	0.59	0.70	0.00	0.0%	0.08	0.35	0.87	0.0%	0.57	0.72	61.2%
C4	3.79	0.90	0.96	1.55	41.0%	0.45	0.59	0.80	13.7%	0.59	0.70	0.00	0.0%	0.08	0.35	1.44	0.0%	0.49	0.65	54.7%
D1	0.42	0.90	0.96	0.05	11.5%	0.45	0.59	0.00	0.0%	0.59	0.70	0.00	0.0%	0.08	0.35	0.37	0.0%	0.17	0.42	11.5%
D2	3.67	0.90	0.96	0.17	4.6%	0.45	0.59	0.00	0.0%	0.59	0.70	0.00	0.0%	0.08	0.35	3.50	0.0%	0.12	0.38	4.6%
OS6	18.38	0.90	0.96	0.00	0.0%	0.45	0.59	0.00	0.0%	0.90	0.90	10.40	53.8%	0.08	0.35	7.98	0.0%	0.54	0.66	53.8%
OS4	11.71	0.90	0.96	0.00	0.0%	0.45	0.59	0.65	3.6%	0.59	0.70	0.00	0.0%	0.58	0.68	11.06	51.9%	0.57	0.68	55.6%
OS7	33.07	0.90	0.96	0.00	0.0%	0.45	0.59	0.00	0.0%	0.90	0.90	7.91	22.7%	0.08	0.35	25.16	0.0%	0.28	0.48	22.7%
TOTAL (A1-C4)	61.37																			53.2%
TOTAL (OS4 -OS7)	63.16																			37.8%
TOTAL	128.62																			44.1%

Basin ID	Total Area (ac)	Paved/Streets (100% Impervious)				Res
		C <sub>5</sub>	C <sub>100</sub>	Area (ac)	Weighted % Imp.	C <sub>5</sub>

Delete?

Basin ID	Total Area (ac)	Paved/Streets (100% Impervious)				Res
		C <sub>5</sub>	C <sub>100</sub>	Area (ac)	Weighted % Imp.	C <sub>5</sub>

Delete?

PROPOSED  
STANDARD FORM SF-2  
TIME OF CONCENTRATION

Subdivision: Sterling Ranch Subdivision -Proposed  
Location: El Paso County

Project Name: Sterling Ranch Phase 2  
Project No.: 25188.02  
Calculated By: CJD  
Checked By: \_\_\_\_\_  
Date: 4/27/20

SUB-BASIN						INITIAL/OVERLAND			TRAVEL TIME					t <sub>c</sub> CHECK			FINAL
DATA						(T <sub>i</sub> )			(T <sub>i</sub> )					(URBANIZED BASINS)			
BASIN ID	D.A. (ac)	Hydrologic Soils Group	Impervious (%)	C <sub>5</sub>	C <sub>100</sub>	L (ft)	S <sub>o</sub> (%)	t <sub>i</sub> (min)	L <sub>t</sub> (ft)	S <sub>t</sub> (%)	K	VEL. (ft/s)	t <sub>t</sub> (min)	COMP. t <sub>c</sub> (min)	TOTAL LENGTH (ft)	Urbanized t <sub>c</sub> (min)	
A1	4.31	A	64%	0.49	0.64	79	1.7%	8.2	1007	3.7%	20.0	3.8	4.4	12.5	1086.0	20.0	12.5
A2	1.41	A	31%	0.30	0.50	266	3.7%	15.4	141	1.5%	20.0	2.4	1.0	16.3	407.0	22.1	16.3
A3	3.68	A	65%	0.50	0.64	120	3.7%	7.7	1008	2.4%	20.0	3.1	5.5	13.2	1128.2	21.0	13.2
A4	3.94	A	52%	0.42	0.58	118	2.1%	10.5	814	1.9%	20.0	2.8	4.9	15.4	932.0	23.2	15.4
A5	0.45	A	78%	0.62	0.73	54	3.7%	4.1	217	3.9%	20.0	4.0	0.9	5.0	271.0	13.6	5.0
A6	7.60	A	73%	0.55	0.68	212	4.3%	8.9	723	1.4%	20.0	2.4	5.0	13.9	934.9	18.8	13.9
A7	1.43	A	75%	0.58	0.70	303	3.4%	10.9	367	1.2%	20.0	2.2	2.8	13.7	670.0	16.1	13.7
A8	4.22	A	13%	0.16	0.41	233	4.9%	15.3	307	0.9%	15.0	1.4	3.6	18.9	540.0	28.7	18.9
B1	2.44	A	80%	0.64	0.75	50	2.5%	4.3	1066	1.6%	20.0	2.5	7.1	11.4	1116.0	19.4	11.4
B2	4.33	A	73%	0.55	0.67	226	4.9%	8.8	346	0.7%	20.0	1.7	3.4	12.2	572.0	17.2	12.2
C1	2.62	A	69%	0.54	0.67	228	4.3%	9.5	393	1.8%	20.0	2.7	2.5	11.9	621.0	17.0	11.9
C2	6.74	A	63%	0.49	0.63	99	1.8%	9.0	796	1.7%	20.0	2.6	5.1	14.1	895.0	21.1	14.1
C3	3.77	A	10%	0.14	0.39	144	9.6%	9.8	255	3.5%	15.0	2.8	1.5	11.3	399.0	26.5	11.3
A9	2.02	A	8%	0.13	0.39	452	2.4%	27.8	108	2.6%	20.0	3.2	0.6	28.4	560.0	25.8	25.8
A10	3.23	A	24%	0.23	0.45	248	2.8%	17.6	0	1.0%	20.0	2.0	0.0	17.6	248.0	21.9	17.6
B6	0.78	A	44%	0.33	0.51	246	1.5%	19.1	0	1.0%	20.0	2.0	0.0	19.1	246.0	18.5	18.5
B5	0.45	A	51%	0.37	0.54	129	5.0%	8.8	0	1.0%	20.0	2.0	0.0	8.8	129.0	17.4	8.8
B4	1.80	B	51%	0.38	0.55	222	11.0%	8.8	914	1.1%	20.0	2.1	7.4	16.2	1136.0	26.4	16.2
B3	2.36	A	61%	0.57	0.72	165	3.4%	8.1	1595	1.5%	10.0	1.2	21.7	29.8	1760.0	27.9	27.9
C4	3.79	A	55%	0.49	0.65	298	3.0%	13.1	1664	1.5%	10.0	1.2	22.6	35.8	1962.0	30.3	30.3
D1	0.42	A	12%	0.17	0.42	16	2.0%	5.3	570	6.0%	10.0	2.4	3.9	9.2	586.0	27.7	9.2
D2	3.67	A	5%	0.12	0.38	105	25.0%	6.3	975	50.0%	15.0	10.6	1.5	7.8	1080.0	27.6	7.8
OS6	18.38	A	54%	0.54	0.66	165	3.4%	8.6	612	2.7%	10.0	1.6	6.2	14.8	777.0	20.6	14.8
OS4	11.71	A	56%	0.57	0.68	491	1.4%	19.0	940	5.6%	10.0	2.4	6.6	25.6	1431.0	20.5	20.5
OS7	33.07	A	23%	0.28	0.48	298	3.0%	17.9	1664	2.7%	10.0	1.6	16.9	34.7	1962.0	36.0	34.7

# PROPOSED STANDARD FORM SF-2 TIME OF CONCENTRATION

Subdivision: Sterling Ranch Subdivision -Proposed  
 Location: El Paso County

Project Name: Sterling Ranch Phase 2  
 Project No.: 25188.02  
 Calculated By: CJD  
 Checked By: \_\_\_\_\_  
 Date: 4/27/20

SUB-BASIN						INITIAL/OVERLAND			TRAVEL TIME					t <sub>c</sub> CHECK			FINAL
DATA						(T <sub>i</sub> )			(T <sub>t</sub> )					(URBANIZED BASINS)			
BASIN	D.A.	Hydrologic	Impervious	C <sub>5</sub>	C <sub>100</sub>	L	S <sub>o</sub>	t <sub>i</sub>	L <sub>t</sub>	S <sub>t</sub>	K	VEL.	t <sub>t</sub>	COMP. t <sub>c</sub>	TOTAL	Urbanized t <sub>c</sub>	t <sub>c</sub>

**NOTES:**

$$t_c = t_i + t_t \quad \text{Equation 6-2}$$

Where:

t<sub>c</sub> = computed time of concentration (minutes)

t<sub>i</sub> = overland (initial) flow time (minutes)

t<sub>t</sub> = channelized flow time (minutes).

$$t_t = \frac{L_t}{60K\sqrt{S_o}} = \frac{L_t}{60V_t} \quad \text{Equation 6-4}$$

Where:

t<sub>t</sub> = channelized flow time (travel time, min)  
 L<sub>t</sub> = waterway length (ft)  
 S<sub>o</sub> = waterway slope (ft/ft)  
 V<sub>t</sub> = travel time velocity (ft/sec) = K√S<sub>o</sub>  
 K = NRCS conveyance factor (see Table 6-2).

Use a minimum t<sub>c</sub> value of 5 minutes for urbanized areas and a minimum t<sub>c</sub> value of 10 minutes for areas that are not considered urban. Use minimum values even when calculations result in a lesser time of concentration.

$$t_i = \frac{0.395(1.1 - C_s)\sqrt{L_i}}{S_o^{0.33}} \quad \text{Equation 6-3}$$

Where:

t<sub>i</sub> = overland (initial) flow time (minutes)  
 C<sub>s</sub> = runoff coefficient for 5-year frequency (from Table 6-4)  
 L<sub>i</sub> = length of overland flow (ft)  
 S<sub>o</sub> = average slope along the overland flow path (ft/ft).

$$t_c = (26 - 17i) + \frac{L_t}{60(14i + 9)\sqrt{S_t}} \quad \text{Equation 6-5}$$

Where:

t<sub>c</sub> = minimum time of concentration for first design point when less than t<sub>c</sub> from Equation 6-1.  
 L<sub>t</sub> = length of channelized flow path (ft)  
 i = imperviousness (expressed as a decimal)  
 S<sub>t</sub> = slope of the channelized flow path (ft/ft).

**Table 6-2. NRCS Conveyance factors, K**

Type of Land Surface	Conveyance Factor, K
Heavy meadow	2.5
Tillage/field	5
Short pasture and lawns	7
Nearly bare ground	10
Grassed waterway	15
Paved areas and shallow paved swales	20

**STANDARD FORM SF-3 - PROPOSED**  
**STORM DRAINAGE SYSTEM DESIGN**  
**(RATIONAL METHOD PROCEDURE)**

Subdivision: Sterling Ranch Subdivision -Proposed  
 Location: El Paso County  
 Design Storm: 5-Year

Project Name: Sterling Ranch Phase 2  
 Project No.: 25188.02  
 Calculated By: CJD  
 Checked By: \_\_\_\_\_  
 Date: 4/27/20

STREET	Design Point	DIRECT RUNOFF							TOTAL RUNOFF				STREET/SWALE			PIPE				TRAVEL TIME			REMARKS
		Basin ID	Area (Ac)	Runoff Coeff.	t <sub>c</sub> (min)	C*A (Ac)	I (in/hr)	Q (cfs)	t <sub>c</sub> (min)	C*A (ac)	I (in/hr)	Q (cfs)	Q <sub>street/swale</sub> (cfs)	C*A (ac)	Slope (%)	Q <sub>pipe</sub> (cfs)	C*A (ac)	Slope (%)	Pipe Size (inches)	Length (ft)	Velocity (fps)	t <sub>t</sub> (min)	
	1	OS7	33.07	0.28	34.7	9.13	2.26	20.6							20.6	9.13	1.0	42	725	8.2	1.5	Offsite Barbarick Subdivision pond release Piped to DP 3	
	2	OS4	11.71	0.57	20.5	6.71	3.05	20.5							20.5	6.71	1.0	36	112	8.3	0.2	Offsite future school Piped to DP 3	
	3								36.2	15.84	2.20	34.8										Piped to existing storm sewer in Sterling Ranch Road	
	4	OS6	18.38	0.54	14.8	10.00	3.54	35.4							35.4	10.00	1.0	48	800	9.4	1.4	Offsite subdivision pond release Piped to DP 7.1	
	5	C2	6.74	0.49	14.1	3.32	3.61	12.0							12.0	3.32	1.0	24	63	7.3	0.1	Sump Inlet Piped to DP 6.1	
	6	C1	2.62	0.54	11.9	1.41	3.87	5.5														Sump Inlet Piped to DP 6.1	
	6.1								14.3	4.73	3.59	17.0			17.0	4.73	1.0	36	245	7.8	0.5	Piped to DP 7.1	
	7	C3	3.77	0.14	11.3	0.55	3.94	2.2														Area Inlet Piped to DP 7.1	
	7.1								16.2	15.28	3.40	52.0										Piped to existing storm sewer in Sterling Ranch Road	
	8	C4	3.79	0.49	30.3	1.87	2.47	4.6														Offsite flow to existing inlet in Sterling Ranch Road Piped to existing storm sewer in Sterling Ranch Road	
	9	B3	2.36	0.57	27.9	1.35	2.59	3.5														Offsite flow to existing inlet in Sterling Ranch Road Piped to existing storm sewer in Sterling Ranch Road	
	10	B4	1.80	0.38	16.2	0.68	3.41	2.3							2.3	0.68	1.0	12	380	4.8	1.3	Rear lot and area inlets Piped to DP 11.1	
	11	B5	0.45	0.37	8.8	0.17	4.31	0.7														Area Inlet Piped to DP 14.1	
	11.1								17.5	0.85	3.29	2.8			2.8	0.85	1.0	18	357	5.0	1.2	Piped to DP 14.1	
	12	B2	4.33	0.55	12.2	2.37	3.83	9.1							9.1	2.37	1.0	18	38	6.7	0.1	Sump Inlet Piped to DP 13.1	
	13	B1	2.44	0.64	11.4	1.57	3.93	6.2														Sump Inlet Piped to DP 13.1	
	13.1								12.3	3.94	3.82	15.0			15.0	3.94	1.0	24	125	7.7	0.3	Piped to DP 14.1	
	14	B6	0.78	0.33	18.5	0.26	3.21	0.8														Area Inlet Piped to DP 14.1	
	14.1								18.7	5.05	3.19	16.1			16.1	5.05	1.0	24	415	7.8	0.9	Piped to DP 15.1	

**STANDARD FORM SF-3 - PROPOSED**  
**STORM DRAINAGE SYSTEM DESIGN**  
**(RATIONAL METHOD PROCEDURE)**

Subdivision: Sterling Ranch Subdivision -Proposed  
 Location: El Paso County  
 Design Storm: 5-Year

Project Name: Sterling Ranch Phase 2  
 Project No.: 25188.02  
 Calculated By: CJD  
 Checked By:  
 Date: 4/27/20

STREET	Design Point	DIRECT RUNOFF						TOTAL RUNOFF				STREET/SWALE			PIPE				TRAVEL TIME			REMARKS	
		Basin ID	Area (Ac)	Runoff Coeff.	t <sub>c</sub> (min)	C*A (Ac)	I (in/hr)	Q (cfs)	t <sub>c</sub> (min)	C*A (ac)	I (in/hr)	Q (cfs)	Q <sub>street/swale</sub> (cfs)	C*A (ac)	Slope (%)	Q <sub>pipe</sub> (cfs)	C*A (ac)	Slope (%)	Pipe Size (inches)	Length (ft)	Velocity (fps)		t <sub>r</sub> (min)
	15	A1	4.31	0.49	12.5	2.13	3.79	8.1					0.7	0.18	1.6	7.4	1.95			230	2.5	1.5	On-grade Inlet Captured Flows piped to DP 15.1, Bypass flow to DP 17
	15.1								19.6	7.00	3.12	21.8				21.8	7.00	1.0	24	48	8.2	0.1	Captured Flows piped to DP 16.1
	16	A5	0.45	0.62	5.0	0.28	5.16	1.4					0.0	0	2.9	1.4							On-grade Inlet Captured Flows piped to DP 16.1
	16.1								19.7	7.28	3.11	22.7				22.7	7.28	1.0	24	280	8.2	0.6	Piped to DP 18.1
	17	A2	1.41	0.30	16.3	0.42	3.40	1.4	16.3	0.60	3.40	2.0	0.0	0		2.0	0.42	1.0	24	27	4.4	0.1	On-grade Inlet Piped to DP 18.1
	18.1								20.3	7.88	3.07	24.2				24.2	0.00	1.0	30	600	8.7	1.1	Piped to DP20.1
	19	A6	7.60	0.55	13.9	4.21	3.64	15.3					4.5	1.24	1.0	10.8	2.97	1.0	18	30	6.8	0.1	On-grade Inlet Captured Flows piped to DP 20.1, Bypass flow to DP 21
	20	A3	3.68	0.50	13.2	1.84	3.72	6.8					0.0	0	1.0	6.8	1.84	1.0	18	4	6.3	0.0	On-grade Inlet Captured Flows piped to DP 20.1
	20.1								21.4	12.69	2.99	37.9				37.9	12.69	1.0	36	220	9.7	0.4	Piped to DP23
	21	A7	1.43	0.58	13.7	0.83	3.66	3.0	14.0	2.07	3.63	7.5				7.5	2.07	1.0	18	60	6.4	0.2	Sump Inlet Piped to DP22.1
	22	A4	3.94	0.42	15.4	1.65	3.48	5.7	15.4	1.65	3.48	5.7											Sump Inlet Piped to DP22.1
	22.1								15.4	3.72	3.48	12.9				12.9	3.72	1.0	24	10	7.4	0.0	Piped to DP23
	23								21.8	16.41	2.96	48.6				48.6	16.41	1.0	42	145	10.3	0.2	Piped to DP26
	24	A8	4.22	0.16	18.9	0.69	3.17	2.2															Area Inlet Piped to EX 84" Storm Line Built w/ SR Filing 2 First Phase
	25	A9	2.02	0.13	25.8	0.27	2.71	0.7								0.7	0.27	1.0	18	30	3.4	0.1	EX FES Piped to EX 84" Storm Line Built w/ SR Filing 2 First Phase
	27	A10	3.23	0.23	17.6	0.74	3.28	2.4															Pervious area sheet flows into EX Pond W5
	28	D1	0.42	0.17	9.2	0.07	4.25	0.3															Pervious area sheet flows into Sand Creek
	29	D2	3.67	0.12	7.8	0.43	4.50	1.9															Pervious area sheet flows into Sand Creek

Notes:

Street and Pipe C\*A values are determined by Q/i using the catchment's intensity value.  
 All pipes are private and RCP unless otherwise noted. Pipe size shown in table column.



**STANDARD FORM SF-3 - PROPOSED  
STORM DRAINAGE SYSTEM DESIGN  
(RATIONAL METHOD PROCEDURE)**

Subdivision: Sterling Ranch Subdivision -Proposed  
Location: El Paso County  
Design Storm: 100-Year

Project Name: Sterling Ranch Phase 2  
Project No.: 25188.02  
Calculated By: CJD  
Checked By:  
Date: 4/27/20

Description	Design Point	DIRECT RUNOFF							TOTAL RUNOFF				STREET/SWALE			PIPE				TRAVEL TIME			REMARKS
		Basin ID	Area (ac)	Runoff Coeff.	t <sub>c</sub> (min)	C*A (ac)	I (in/hr)	Q (cfs)	t <sub>c</sub> (min)	C*A (ac)	I (in/hr)	Q (cfs)	Q <sub>street/swale</sub> (cfs)	C*A (ac)	Slope (%)	Q <sub>pipe</sub> (cfs)	C*A (ac)	Slope (%)	Pipe Size (inches)	Length (ft)	Velocity (fps)	t <sub>t</sub> (min)	
	1	OS7	33.07	0.48	34.7	15.93	3.79	60.4							60.4	15.93	1.0	42	725	10.9	1.1	Offsite Barbarick Subdivision pond release Piped to DP 3	
	2	OS4	11.71	0.68	20.5	7.90	5.12	40.5							40.5	7.90	1.0	36	112	9.9	0.2	Offsite future school Piped to DP 3	
	3								35.9	23.83	3.71	88.5										Piped to existing storm sewer in Sterling Ranch Road Offsite subdivision pond release	
	4	OS6	18.38	0.66	14.8	12.15	5.94	72.2							72.2	12.15	1.0	48	800	11.4	1.2	Piped to DP 7.1 Sump Inlet	
	5	C2	6.74	0.63	14.1	4.28	6.06	25.9							25.9	4.28	1.0	24	63	8.3	0.1	Piped to DP 6.1 Sump Inlet	
	6	C1	2.62	0.67	11.9	1.75	6.49	11.4														Piped to DP 6.1 Sump Inlet	
	6.1								14.3	6.03	6.04	36.4			36.4	6.03	1.0	36	245	9.6	0.4	Piped to DP 7.1 Area Inlet	
	7	C3	3.77	0.39	11.3	1.49	6.61	9.9														Piped to DP 7.1 Area Inlet	
	7.1								16.0	19.67	5.75	113.1										Piped to existing storm sewer in Sterling Ranch Road Offsite flow to existing inlet in Sterling Ranch Road	
	8	C4	3.79	0.65	30.3	2.47	4.14	10.2														Piped to existing storm sewer in Sterling Ranch Road Offsite flow to existing inlet in Sterling Ranch Road	
	9	B3	2.36	0.72	27.9	1.69	4.34	7.3														Piped to existing storm sewer in Sterling Ranch Road Offsite flow to existing inlet in Sterling Ranch Road	
	10	B4	1.80	0.55	16.2	0.98	5.72	5.6							5.6	0.98	1.0	12	380	7.2	0.9	Rear lot and area inlets Piped to DP 11.1	
	11	B5	0.45	0.54	8.8	0.24	7.24	1.7														Area Inlet Piped to DP 14.1	
	11.1								17.1	1.22	5.58	6.8			6.8	1.22	1.0	18	357	6.3	0.9	Piped to DP 14.1 Sump Inlet	
	12	B2	4.33	0.67	12.2	2.90	6.43	18.7							18.7	2.90	1.0	18	38	10.6	0.1	Piped to DP 13.1 Sump Inlet	
	13	B1	2.44	0.75	11.4	1.82	6.60	12.0														Piped to DP 13.1 Sump Inlet	
	13.1								12.3	4.72	6.42	30.3			30.3	4.72	1.0	24	125	9.7	0.2	Piped to DP 14.1 Area Inlet	
	14	B6	0.78	0.51	18.5	0.40	5.38	2.2														Piped to DP 14.1 Area Inlet	
	14.1								18.5	6.34	5.38	34.1			34.1	6.34	1.0	24	415	10.9	0.6	Piped to DP 15.1 On-grade Inlet	
	15	A1	4.31	0.64	12.5	2.74	6.37	17.4					5.0	0.7854	1.6	12.4	1.95		230	2.5	1.5	Captured Flows piped to DP 15.1, Bypass flow to DP 17	
	15.1								19.1	8.29	5.30	43.9			43.9	8.29	1.0	24	48	14.0	0.1	Captured Flows piped to DP 16.1	

STANDARD FORM SF-3 - PROPOSED  
STORM DRAINAGE SYSTEM DESIGN  
(RATIONAL METHOD PROCEDURE)

Subdivision: Sterling Ranch Subdivision -Proposed  
Location: El Paso County  
Design Storm: 100-Year

Project Name: Sterling Ranch Phase 2  
Project No.: 25188.02  
Calculated By: CJD  
Checked By:  
Date: 4/21/20

Description	Design Point	DIRECT RUNOFF							TOTAL RUNOFF				STREET/SWALE			PIPE				TRAVEL TIME			REMARKS	
		Basin ID	Area (ac)	Runoff Coeff.	$t_c$ (min)	C*A (ac)	I (in/hr)	Q (cfs)	$t_c$ (min)	C*A (ac)	I (in/hr)	Q (cfs)	$Q_{street/swale}$ (cfs)	C*A (ac)	Slope (%)	$Q_{pipe}$ (cfs)	C*A (ac)	Slope (%)	Pipe Size (inches)	Length (ft)	Velocity (fps)	$t_t$ (min)		
	16	A5	0.45	0.73	5.0	0.33	8.66	2.9					0.0	0	2.9									On-grade Inlet Captured Flows piped to DP 16.1
	16.1								19.2	8.62	5.29	45.6			45.6	8.62	1.0	24	280	14.5	0.3		Piped to DP 18.1	
	17	A2	1.41	0.50	16.3	0.71	5.70	4.0	16.3	1.50	5.70	8.5	0.9	0.1579	1.5	8.5	0.71	1.0	24	27	6.7	0.1	On-grade Inlet Piped to DP 18.1	
	18.1								19.5	10.12	5.25	53.1			53.1	10.12	1.0	30	600	10.8	0.9		Piped to DP20.1	
	19	A6	7.60	0.68	13.9	5.14	6.11	31.4					15.6	2.5552	1.0	15.8	2.58	1.0	18	30	8.9	0.1	On-grade Inlet Captured Flows piped to DP 20.1, Bypass flow to DP 21	
	20	A3	3.68	0.64	13.2	2.34	6.24	14.6					3.0	0.4809	1.0	11.6	1.86	1.0	18	4	6.6	0.0	On-grade Inlet Captured Flows piped to DP 20.1, Bypass flow to DP 22	
	20.1								20.4	14.56	5.13	74.7			74.7	14.56	1.0	36	220	10.6	0.3		Piped to DP23	
	21	A7	1.43	0.70	13.7	1.00	6.14	6.1	13.9	3.56	6.10	21.7			21.7	3.56	1.0	18	60	12.3	0.1	Sump Inlet Piped to DP22.1		
	22	A4	3.94	0.58	15.4	2.30	5.84	13.4	15.4	2.94	5.84	17.2											Sump Inlet Piped to DP22.1	
	22.1								15.4	6.49	5.84	37.9			37.9	6.49	1.0	24	10	12.1	0.0		Piped to DP23	
	23								20.8	21.06	5.09	107.2			107.2	21.06	1.0	42	145	11.8	0.2		Piped to DP26	
	24	A8	4.22	0.41	18.9	1.71	5.32	9.1															Area Inlet Piped to EX 84" Storm Line Built w/ SR Filing 2 First Phase	
	25	A9	2.02	0.39	25.8	0.78	4.55	3.5							3.5	0.78	1.0	18	30	5.4	0.1		EX FES Piped to EX 84" Storm Line Built w/ SR Filing 2 First Phase	
	27	A10	3.23	0.45	17.6	1.45	5.50	8.0															Pervious area sheet flows into EX Pond W5	
	28	D1	0.42	0.42	9.2	0.18	7.14	1.3															Pervious area sheet flows into Sand Creek	
	29	D2	3.67	0.38	7.8	1.39	7.55	10.5															Pervious area sheet flows into Sand Creek	

Notes:  
Street and Pipe C\*A values are determined by Q/i using the catchment's intensity value.  
All pipes are private and RCP unless otherwise noted. Pipe size shown in table column.

## **Appendix C**


### **Hydraulic Calculations**



**ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)**

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)


Project: \_\_\_\_\_  
 Inlet ID: \_\_\_\_\_  
Sterling Ranch Phase 2  
A1 - DP15



<b>Gutter Geometry (Enter data in the blue cells)</b>							
Maximum Allowable Width for Spread Behind Curb	$T_{BACK} = 5.5$ ft						
Side Slope Behind Curb (leave blank for no conveyance credit behind curb)	$S_{BACK} = 0.020$ ft/ft						
Manning's Roughness Behind Curb (typically between 0.012 and 0.020) <input type="checkbox"/>	$n_{BACK} = 0.013$						
Height of Curb at Gutter Flow Line	$H_{CURB} = 6.00$ inches						
Distance from Curb Face to Street Crown	$T_{CROWN} = 17.0$ ft						
Gutter Width	$W = 2.00$ ft						
Street Transverse Slope	$S_x = 0.020$ ft/ft						
Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)	$S_w = 0.083$ ft/ft						
Street Longitudinal Slope - Enter 0 for sump condition	$S_o = 0.033$ ft/ft						
Manning's Roughness for Street Section (typically between 0.012 and 0.020)	$n_{STREET} = 0.013$						
Max. Allowable Spread for Minor & Major Storm	<table border="1" style="display: inline-table; border-collapse: collapse;"> <thead> <tr> <th style="text-align: center;">Minor Storm</th> <th style="text-align: center;">Major Storm</th> <th></th> </tr> </thead> <tbody> <tr> <td style="text-align: center;">17.0</td> <td style="text-align: center;">17.0</td> <td style="text-align: right;">ft</td> </tr> </tbody> </table>	Minor Storm	Major Storm		17.0	17.0	ft
Minor Storm	Major Storm						
17.0	17.0	ft					
Max. Allowable Depth at Gutter Flowline for Minor & Major Storm	<table border="1" style="display: inline-table; border-collapse: collapse;"> <thead> <tr> <th style="text-align: center;">Minor Storm</th> <th style="text-align: center;">Major Storm</th> <th></th> </tr> </thead> <tbody> <tr> <td style="text-align: center;">6.0</td> <td style="text-align: center;">7.8</td> <td style="text-align: right;">inches</td> </tr> </tbody> </table>	Minor Storm	Major Storm		6.0	7.8	inches
Minor Storm	Major Storm						
6.0	7.8	inches					
Allow Flow Depth at Street Crown (leave blank for no) <input type="checkbox"/>	check = yes						
<b>MINOR STORM Allowable Capacity is based on Depth Criterion</b>							
<b>MAJOR STORM Allowable Capacity is based on Spread Criterion</b>							
Minor storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'	$Q_{allow} = 21.2$ cfs						
Major storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'	$Q_{allow} = 24.3$ cfs						

## INLET ON A CONTINUOUS GRADE

Version 4.05 Released March 2017




Design Information (Input)	MINOR	MAJOR	
Type of Inlet	CDOT Type R Curb Opening		
Local Depression (additional to continuous gutter depression 'a')	3.0	3.0	inches
Total Number of Units in the Inlet (Grate or Curb Opening)	1	1	
Length of a Single Unit Inlet (Grate or Curb Opening)	15.00	15.00	ft
Width of a Unit Grate (cannot be greater than W, Gutter Width)	N/A	N/A	ft
Clogging Factor for a Single Unit Grate (typical min. value = 0.5)	N/A	N/A	
Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.1)	0.10	0.10	
<b>Street Hydraulics: OK - Q &lt; Allowable Street Capacity*</b>			
Total Inlet Interception Capacity	7.8	12.4	cfs
Total Inlet Carry-Over Flow (flow bypassing inlet)	0.3	5.0	cfs
Capture Percentage = $Q_i/Q_o$ =	96	71	%

**ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)**

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project:  
Inlet ID:


Sterling Ranch Phase 2  
A2 - DP17



Gutter Geometry (Enter data in the blue cells)							
Maximum Allowable Width for Spread Behind Curb	T <sub>BACK</sub> = 8.8 ft						
Side Slope Behind Curb (leave blank for no conveyance credit behind curb)	S <sub>BACK</sub> = 0.020 ft/ft						
Manning's Roughness Behind Curb (typically between 0.012 and 0.020) <input type="checkbox"/> <input checked="" type="checkbox"/>	n <sub>BACK</sub> = 0.016						
Height of Curb at Gutter Flow Line	H <sub>CURB</sub> = 6.00 inches						
Distance from Curb Face to Street Crown	T <sub>CROWN</sub> = 17.0 ft						
Gutter Width	W = 1.17 ft						
Street Transverse Slope	S <sub>X</sub> = 0.020 ft/ft						
Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)	S <sub>W</sub> = 0.042 ft/ft						
Street Longitudinal Slope - Enter 0 for sump condition	S <sub>O</sub> = 0.026 ft/ft						
Manning's Roughness for Street Section (typically between 0.012 and 0.020)	n <sub>STREET</sub> = 0.016						
Max. Allowable Spread for Minor & Major Storm	<table border="1" style="display: inline-table; border-collapse: collapse;"> <thead> <tr> <th style="width: 50%;">Minor Storm</th> <th style="width: 50%;">Major Storm</th> </tr> </thead> <tbody> <tr> <td>T<sub>MAX</sub> = 15.8</td> <td>T<sub>MAX</sub> = 17.0</td> </tr> <tr> <td>d<sub>MAX</sub> = 4.6</td> <td>d<sub>MAX</sub> = 7.8</td> </tr> </tbody> </table>	Minor Storm	Major Storm	T <sub>MAX</sub> = 15.8	T <sub>MAX</sub> = 17.0	d <sub>MAX</sub> = 4.6	d <sub>MAX</sub> = 7.8
Minor Storm	Major Storm						
T <sub>MAX</sub> = 15.8	T <sub>MAX</sub> = 17.0						
d <sub>MAX</sub> = 4.6	d <sub>MAX</sub> = 7.8						
Max. Allowable Depth at Gutter Flowline for Minor & Major Storm	<table border="1" style="display: inline-table; border-collapse: collapse;"> <thead> <tr> <th style="width: 50%;">Minor Storm</th> <th style="width: 50%;">Major Storm</th> </tr> </thead> <tbody> <tr> <td>d<sub>MAX</sub> = 4.6</td> <td>d<sub>MAX</sub> = 7.8</td> </tr> </tbody> </table>	Minor Storm	Major Storm	d <sub>MAX</sub> = 4.6	d <sub>MAX</sub> = 7.8		
Minor Storm	Major Storm						
d <sub>MAX</sub> = 4.6	d <sub>MAX</sub> = 7.8						
Allow Flow Depth at Street Crown (leave blank for no)	check = yes						
<b>MINOR STORM Allowable Capacity is based on Spread Criterion</b>							
<b>MAJOR STORM Allowable Capacity is based on Depth Criterion</b>							
Minor storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'	<table border="1" style="display: inline-table; border-collapse: collapse;"> <thead> <tr> <th style="width: 50%;">Minor Storm</th> <th style="width: 50%;">Major Storm</th> </tr> </thead> <tbody> <tr> <td>Q<sub>allow</sub> = 13.3</td> <td>Q<sub>allow</sub> = 49.1</td> </tr> </tbody> </table>	Minor Storm	Major Storm	Q <sub>allow</sub> = 13.3	Q <sub>allow</sub> = 49.1		
Minor Storm	Major Storm						
Q <sub>allow</sub> = 13.3	Q <sub>allow</sub> = 49.1						
Major storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'							

## INLET ON A CONTINUOUS GRADE

Version 4.05 Released March 2017




Design Information (Input)	MINOR	MAJOR	
Type of Inlet	Type = CDOT Type R Curb Opening		
Local Depression (additional to continuous gutter depression 'a')	$a_{LOCAL} = 3.0$	$3.0$	inches
Total Number of Units in the Inlet (Grate or Curb Opening)	No = 1	1	
Length of a Single Unit Inlet (Grate or Curb Opening)	$L_o = 15.00$	15.00	ft
Width of a Unit Grate (cannot be greater than W, Gutter Width)	$W_o = N/A$	N/A	ft
Clogging Factor for a Single Unit Grate (typical min. value = 0.5)	$C_{r-G} = N/A$	N/A	
Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.1)	$C_{r-C} = 0.10$	0.10	
<b>Street Hydraulics: OK - Q &lt; Allowable Street Capacity*</b>			
Total Inlet Interception Capacity	$Q = 2.0$	7.6	cfs
Total Inlet Carry-Over Flow (flow bypassing inlet)	$Q_b = 0.0$	0.9	cfs
Capture Percentage = $Q_c/Q_o =$	$C\% = 100$	90	%

**ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)**

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project:  Sterling Ranch Phase 2   
 Inlet ID:  A4 - DP22




Gutter Geometry (Enter data in the blue cells)					
Maximum Allowable Width for Spread Behind Curb	T <sub>BACK</sub> = 8.0 ft				
Side Slope Behind Curb (leave blank for no conveyance credit behind curb)	S <sub>BACK</sub> = 0.020 ft/ft				
Manning's Roughness Behind Curb (typically between 0.012 and 0.020) <input type="checkbox"/>	n <sub>BACK</sub> = 0.016				
Height of Curb at Gutter Flow Line	H <sub>CURB</sub> = 6.00 inches				
Distance from Curb Face to Street Crown	T <sub>CROWN</sub> = 17.0 ft				
Gutter Width	W = 1.17 ft				
Street Transverse Slope	S <sub>x</sub> = 0.020 ft/ft				
Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)	S <sub>w</sub> = 0.083 ft/ft				
Street Longitudinal Slope - Enter 0 for sump condition	S <sub>O</sub> = 0.000 ft/ft				
Manning's Roughness for Street Section (typically between 0.012 and 0.020)	n <sub>STREET</sub> = 0.016				
Max. Allowable Spread for Minor & Major Storm	T <sub>MAX</sub> = <table border="1"><tr><th>Minor Storm</th><th>Major Storm</th></tr><tr><td>15.8</td><td>17.0</td></tr></table> ft	Minor Storm	Major Storm	15.8	17.0
Minor Storm	Major Storm				
15.8	17.0				
Max. Allowable Depth at Gutter Flowline for Minor & Major Storm	d <sub>MAX</sub> = <table border="1"><tr><th>Minor Storm</th><th>Major Storm</th></tr><tr><td>4.6</td><td>7.8</td></tr></table> inches	Minor Storm	Major Storm	4.6	7.8
Minor Storm	Major Storm				
4.6	7.8				
Check boxes are not applicable in SUMP conditions					
<b>MINOR STORM Allowable Capacity is based on Depth Criterion</b>					
<b>MAJOR STORM Allowable Capacity is based on Depth Criterion</b>					
Q <sub>allow</sub> =	<table border="1"><tr><th>Minor Storm</th><th>Major Storm</th></tr><tr><td>SUMP</td><td>SUMP</td></tr></table> cfs	Minor Storm	Major Storm	SUMP	SUMP
Minor Storm	Major Storm				
SUMP	SUMP				



## INLET IN A SUMP OR SAG LOCATION

Version 4.05 Released March 2017



Design Information (Input)	MINOR	MAJOR	
Type of Inlet	CDOT Type R Curb Opening		
Local Depression (additional to continuous gutter depression 'a' from above)	3.00	3.00	inches
Number of Unit Inlets (Grate or Curb Opening)	1	1	
Water Depth at Flowline (outside of local depression)	4.6	5.0	inches
<b>Grate Information</b>			
Length of a Unit Grate	N/A	N/A	feet
Width of a Unit Grate	N/A	N/A	feet
Area Opening Ratio for a Grate (typical values 0.15-0.90)	N/A	N/A	
Clogging Factor for a Single Grate (typical value 0.50 - 0.70)	N/A	N/A	
Grate Weir Coefficient (typical value 2.15 - 3.60)	N/A	N/A	
Grate Orifice Coefficient (typical value 0.60 - 0.80)	N/A	N/A	
<b>Curb Opening Information</b>			
Length of a Unit Curb Opening	15.00	15.00	feet
Height of Vertical Curb Opening in Inches	6.00	6.00	inches
Height of Curb Orifice Throat in Inches	6.00	6.00	inches
Angle of Throat (see USDCM Figure ST-5)	63.40	63.40	degrees
Side Width for Depression Pan (typically the gutter width of 2 feet)	1.17	1.17	feet
Clogging Factor for a Single Curb Opening (typical value 0.10)	0.10	0.10	
Curb Opening Weir Coefficient (typical value 2.3-3.7)	3.60	3.60	
Curb Opening Orifice Coefficient (typical value 0.60 - 0.70)	0.67	0.67	
<b>Low Head Performance Reduction (Calculated)</b>			
Depth for Grate Midwidth	N/A	N/A	ft
Depth for Curb Opening Weir Equation	0.29	0.32	ft
Combination Inlet Performance Reduction Factor for Long Inlets	0.43	0.47	
Curb Opening Performance Reduction Factor for Long Inlets	0.69	0.72	
Grated Inlet Performance Reduction Factor for Long Inlets	N/A	N/A	
<b>Total Inlet Interception Capacity (assumes clogged condition)</b>			
<b>Q<sub>a</sub></b>	<b>6.2</b>	<b>7.5</b>	<b>cfs</b>
<b>Q<sub>PEAK REQUIRED</sub></b>	<b>5.7</b>	<b>17.2</b>	<b>cfs</b>


WARNING: Inlet Capacity less than Q Peak for Major Storm

If this is intentional provide the overflow conveyance design and show on the drainage plan. Add a short description on this sheet.

**ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)**

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)


Project:  Sterling Ranch Phase 2   
 Inlet ID:  A6 - DP19



Gutter Geometry (Enter data in the blue cells)													
Maximum Allowable Width for Spread Behind Curb	$T_{BACK} = 8.8$ ft												
Side Slope Behind Curb (leave blank for no conveyance credit behind curb)	$S_{BACK} = 0.020$ ft/ft												
Manning's Roughness Behind Curb (typically between 0.012 and 0.020) <input type="checkbox"/>	$n_{BACK} = 0.016$												
Height of Curb at Gutter Flow Line	$H_{CURB} = 6.00$ inches												
Distance from Curb Face to Street Crown	$T_{CROWN} = 16.2$ ft												
Gutter Width	$W = 1.17$ ft												
Street Transverse Slope	$S_x = 0.020$ ft/ft												
Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)	$S_w = 0.042$ ft/ft												
Street Longitudinal Slope - Enter 0 for sump condition	$S_o = 0.010$ ft/ft												
Manning's Roughness for Street Section (typically between 0.012 and 0.020)	$n_{STREET} = 0.016$												
Max. Allowable Spread for Minor & Major Storm	<table border="1"> <thead> <tr> <th></th> <th>Minor Storm</th> <th>Major Storm</th> <th></th> </tr> </thead> <tbody> <tr> <td><math>T_{MAX} =</math></td> <td>15.8</td> <td>16.2</td> <td>ft</td> </tr> <tr> <td><math>d_{MAX} =</math></td> <td>4.6</td> <td>7.8</td> <td>inches</td> </tr> </tbody> </table>		Minor Storm	Major Storm		$T_{MAX} =$	15.8	16.2	ft	$d_{MAX} =$	4.6	7.8	inches
	Minor Storm	Major Storm											
$T_{MAX} =$	15.8	16.2	ft										
$d_{MAX} =$	4.6	7.8	inches										
Max. Allowable Depth at Gutter Flowline for Minor & Major Storm													
Allow Flow Depth at Street Crown (leave blank for no)	check = yes												
<b>MINOR STORM Allowable Capacity is based on Spread Criterion</b>													
<b>MAJOR STORM Allowable Capacity is based on Spread Criterion</b>													
	<table border="1"> <thead> <tr> <th></th> <th>Minor Storm</th> <th>Major Storm</th> <th></th> </tr> </thead> <tbody> <tr> <td><math>Q_{allow} =</math></td> <td>8.3</td> <td>8.7</td> <td>cfs</td> </tr> </tbody> </table>		Minor Storm	Major Storm		$Q_{allow} =$	8.3	8.7	cfs				
	Minor Storm	Major Storm											
$Q_{allow} =$	8.3	8.7	cfs										
<b>WARNING: MINOR STORM max. allowable capacity is less than the design flow given on sheet 'Inlet Management'</b>													
<b>WARNING: MAJOR STORM max. allowable capacity is less than the design flow given on sheet 'Inlet Management'</b>													

## INLET ON A CONTINUOUS GRADE

Version 4.05 Released March 2017




Design Information (Input)	MINOR	MAJOR	
Type of Inlet	CDOT Type R Curb Opening		
Local Depression (additional to continuous gutter depression 'a')	3.0	3.0	inches
Total Number of Units in the Inlet (Grate or Curb Opening)	1	1	
Length of a Single Unit Inlet (Grate or Curb Opening)	15.00	15.00	ft
Width of a Unit Grate (cannot be greater than W, Gutter Width)	N/A	N/A	ft
Clogging Factor for a Single Unit Grate (typical min. value = 0.5)	N/A	N/A	
Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.1)	0.10	0.10	
<b>Street Hydraulics: WARNING: Q &gt; ALLOWABLE Q FOR MINOR &amp; MAJOR STORM</b>			
Total Inlet Interception Capacity	10.8	15.8	cfs
Total Inlet Carry-Over Flow (flow bypassing inlet)	4.5	15.6	cfs
Capture Percentage = $Q_i/Q_o$ =	71	50	%

**ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)**

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)


Project:  Sterling Ranch Phase 2   
 Inlet ID:  A5 - DP16



Gutter Geometry (Enter data in the blue cells)							
Maximum Allowable Width for Spread Behind Curb	$T_{BACK} = 8.0$ ft						
Side Slope Behind Curb (leave blank for no conveyance credit behind curb)	$S_{BACK} = 0.020$ ft/ft						
Manning's Roughness Behind Curb (typically between 0.012 and 0.020) <input type="checkbox"/> <input checked="" type="checkbox"/>	$n_{BACK} = 0.016$						
Height of Curb at Gutter Flow Line	$H_{CURB} = 6.00$ inches						
Distance from Curb Face to Street Crown	$T_{CROWN} = 17.0$ ft						
Gutter Width	$W = 1.17$ ft						
Street Transverse Slope	$S_X = 0.020$ ft/ft						
Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)	$S_W = 0.083$ ft/ft						
Street Longitudinal Slope - Enter 0 for sump condition	$S_O = 0.029$ ft/ft						
Manning's Roughness for Street Section (typically between 0.012 and 0.020)	$n_{STREET} = 0.016$						
Max. Allowable Spread for Minor & Major Storm	<table border="1"> <thead> <tr> <th>Minor Storm</th> <th>Major Storm</th> <th>ft</th> </tr> </thead> <tbody> <tr> <td><math>T_{MAX} = 15.8</math></td> <td><math>T_{MAX} = 17.0</math></td> <td></td> </tr> </tbody> </table>	Minor Storm	Major Storm	ft	$T_{MAX} = 15.8$	$T_{MAX} = 17.0$	
Minor Storm	Major Storm	ft					
$T_{MAX} = 15.8$	$T_{MAX} = 17.0$						
Max. Allowable Depth at Gutter Flowline for Minor & Major Storm	<table border="1"> <thead> <tr> <th>Minor Storm</th> <th>Major Storm</th> <th>inches</th> </tr> </thead> <tbody> <tr> <td><math>d_{MAX} = 4.6</math></td> <td><math>d_{MAX} = 7.8</math></td> <td></td> </tr> </tbody> </table>	Minor Storm	Major Storm	inches	$d_{MAX} = 4.6$	$d_{MAX} = 7.8$	
Minor Storm	Major Storm	inches					
$d_{MAX} = 4.6$	$d_{MAX} = 7.8$						
Allow Flow Depth at Street Crown (leave blank for no)	check = yes						
<b>MINOR STORM Allowable Capacity is based on Depth Criterion</b>							
<b>MAJOR STORM Allowable Capacity is based on Depth Criterion</b>							
Minor storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'	<table border="1"> <thead> <tr> <th>Minor Storm</th> <th>Major Storm</th> <th>cfs</th> </tr> </thead> <tbody> <tr> <td><math>Q_{allow} = 13.6</math></td> <td><math>Q_{allow} = 40.2</math></td> <td></td> </tr> </tbody> </table>	Minor Storm	Major Storm	cfs	$Q_{allow} = 13.6$	$Q_{allow} = 40.2$	
Minor Storm	Major Storm	cfs					
$Q_{allow} = 13.6$	$Q_{allow} = 40.2$						
Major storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'							

## INLET ON A CONTINUOUS GRADE

Version 4.05 Released March 2017




Design Information (Input)	MINOR	MAJOR	
Type of Inlet	CDOT Type R Curb Opening		
Local Depression (additional to continuous gutter depression 'a')	3.0	3.0	inches
Total Number of Units in the Inlet (Grate or Curb Opening)	1	1	
Length of a Single Unit Inlet (Grate or Curb Opening)	10.00	10.00	ft
Width of a Unit Grate (cannot be greater than W, Gutter Width)	N/A	N/A	ft
Clogging Factor for a Single Unit Grate (typical min. value = 0.5)	N/A	N/A	
Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.1)	0.10	0.10	
<b>Street Hydraulics: OK - Q &lt; Allowable Street Capacity*</b>			
Total Inlet Interception Capacity	1.4	2.9	cfs
Total Inlet Carry-Over Flow (flow bypassing inlet)	0.0	0.0	cfs
Capture Percentage = $Q_i/Q_o$ =	100	100	%

**ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)**

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)


Project:  Sterling Ranch Phase 2   
 Inlet ID:  A3 - DP 20



Gutter Geometry (Enter data in the blue cells)							
Maximum Allowable Width for Spread Behind Curb	$T_{BACK} = 7.0$ ft						
Side Slope Behind Curb (leave blank for no conveyance credit behind curb)	$S_{BACK} = 0.020$ ft/ft						
Manning's Roughness Behind Curb (typically between 0.012 and 0.020) <input type="checkbox"/>	$n_{BACK} = 0.016$						
Height of Curb at Gutter Flow Line	$H_{CURB} = 6.00$ inches						
Distance from Curb Face to Street Crown	$T_{CROWN} = 26.0$ ft						
Gutter Width	$W = 2.00$ ft						
Street Transverse Slope	$S_x = 0.020$ ft/ft						
Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)	$S_w = 0.083$ ft/ft						
Street Longitudinal Slope - Enter 0 for sump condition	$S_o = 0.007$ ft/ft						
Manning's Roughness for Street Section (typically between 0.012 and 0.020)	$n_{STREET} = 0.016$						
Max. Allowable Spread for Minor & Major Storm	<table border="1"> <tr> <th>Minor Storm</th> <th>Major Storm</th> <th>ft</th> </tr> <tr> <td>19.3</td> <td>26.0</td> <td></td> </tr> </table>	Minor Storm	Major Storm	ft	19.3	26.0	
Minor Storm	Major Storm	ft					
19.3	26.0						
Max. Allowable Depth at Gutter Flowline for Minor & Major Storm	<table border="1"> <tr> <th>Minor Storm</th> <th>Major Storm</th> <th>inches</th> </tr> <tr> <td>6.0</td> <td>7.7</td> <td></td> </tr> </table>	Minor Storm	Major Storm	inches	6.0	7.7	
Minor Storm	Major Storm	inches					
6.0	7.7						
Allow Flow Depth at Street Crown (leave blank for no)	check = yes						
<b>MINOR STORM Allowable Capacity is based on Depth Criterion</b>							
<b>MAJOR STORM Allowable Capacity is based on Depth Criterion</b>							
Minor storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'	<table border="1"> <tr> <th>Minor Storm</th> <th>Major Storm</th> <th>cfs</th> </tr> <tr> <td>11.5</td> <td>26.7</td> <td></td> </tr> </table>	Minor Storm	Major Storm	cfs	11.5	26.7	
Minor Storm	Major Storm	cfs					
11.5	26.7						
Major storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'							

## INLET ON A CONTINUOUS GRADE

Version 4.05 Released March 2017




Design Information (Input)	MINOR	MAJOR	
Type of Inlet	CDOT Type R Curb Opening		
Local Depression (additional to continuous gutter depression 'a')	3.0	3.0	inches
Total Number of Units in the Inlet (Grate or Curb Opening)	1	1	
Length of a Single Unit Inlet (Grate or Curb Opening)	15.00	15.00	ft
Width of a Unit Grate (cannot be greater than W, Gutter Width)	N/A	N/A	ft
Clogging Factor for a Single Unit Grate (typical min. value = 0.5)	N/A	N/A	
Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.1)	0.10	0.10	
<b>Street Hydraulics: OK - Q &lt; Allowable Street Capacity*</b>			
Total Inlet Interception Capacity	6.8	11.6	cfs
Total Inlet Carry-Over Flow (flow bypassing inlet)	0.0	3.0	cfs
Capture Percentage = $Q_i/Q_o$ =	100	79	%

**ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)**

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project: \_\_\_\_\_  
 Inlet ID: \_\_\_\_\_  
Sterling Ranch Phase 2  
A7 - DP21




<b>Gutter Geometry (Enter data in the blue cells)</b>							
Maximum Allowable Width for Spread Behind Curb	$T_{BACK} = 15.0$ ft						
Side Slope Behind Curb (leave blank for no conveyance credit behind curb)	$S_{BACK} = 0.020$ ft/ft						
Manning's Roughness Behind Curb (typically between 0.012 and 0.020) <input type="checkbox"/>	$n_{BACK} = 0.016$						
Height of Curb at Gutter Flow Line	$H_{CURB} = 6.00$ inches						
Distance from Curb Face to Street Crown	$T_{CROWN} = 17.0$ ft						
Gutter Width	$W = 1.17$ ft						
Street Transverse Slope	$S_x = 0.020$ ft/ft						
Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)	$S_w = 0.083$ ft/ft						
Street Longitudinal Slope - Enter 0 for sump condition	$S_o = 0.000$ ft/ft						
Manning's Roughness for Street Section (typically between 0.012 and 0.020)	$n_{STREET} = 0.016$						
Max. Allowable Spread for Minor & Major Storm	<table border="1" style="display: inline-table; border-collapse: collapse;"> <thead> <tr> <th style="padding: 2px;">Minor Storm</th> <th style="padding: 2px;">Major Storm</th> <th style="padding: 2px;">ft</th> </tr> </thead> <tbody> <tr> <td style="padding: 2px;"><math>T_{MAX} = 15.8</math></td> <td style="padding: 2px;"><math>T_{MAX} = 17.0</math></td> <td style="padding: 2px;"></td> </tr> </tbody> </table>	Minor Storm	Major Storm	ft	$T_{MAX} = 15.8$	$T_{MAX} = 17.0$	
Minor Storm	Major Storm	ft					
$T_{MAX} = 15.8$	$T_{MAX} = 17.0$						
Max. Allowable Depth at Gutter Flowline for Minor & Major Storm	<table border="1" style="display: inline-table; border-collapse: collapse;"> <thead> <tr> <th style="padding: 2px;">Minor Storm</th> <th style="padding: 2px;">Major Storm</th> <th style="padding: 2px;">inches</th> </tr> </thead> <tbody> <tr> <td style="padding: 2px;"><math>d_{MAX} = 4.6</math></td> <td style="padding: 2px;"><math>d_{MAX} = 12.0</math></td> <td style="padding: 2px;"></td> </tr> </tbody> </table>	Minor Storm	Major Storm	inches	$d_{MAX} = 4.6$	$d_{MAX} = 12.0$	
Minor Storm	Major Storm	inches					
$d_{MAX} = 4.6$	$d_{MAX} = 12.0$						
Check boxes are not applicable in SUMP conditions							
<b>MINOR STORM Allowable Capacity is based on Depth Criterion</b>							
<b>MAJOR STORM Allowable Capacity is based on Depth Criterion</b>	<table border="1" style="display: inline-table; border-collapse: collapse;"> <thead> <tr> <th style="padding: 2px;">Minor Storm</th> <th style="padding: 2px;">Major Storm</th> <th style="padding: 2px;">cfs</th> </tr> </thead> <tbody> <tr> <td style="padding: 2px;"><math>Q_{allow} = \text{SUMP}</math></td> <td style="padding: 2px;"><math>Q_{allow} = \text{SUMP}</math></td> <td style="padding: 2px;"></td> </tr> </tbody> </table>	Minor Storm	Major Storm	cfs	$Q_{allow} = \text{SUMP}$	$Q_{allow} = \text{SUMP}$	
Minor Storm	Major Storm	cfs					
$Q_{allow} = \text{SUMP}$	$Q_{allow} = \text{SUMP}$						



## INLET IN A SUMP OR SAG LOCATION

Version 4.05 Released March 2017




Design Information (Input)	MINOR	MAJOR	
Type of Inlet	CDOT Type R Curb Opening		
Local Depression (additional to continuous gutter depression 'a' from above)	3.00	3.00	inches
Number of Unit Inlets (Grate or Curb Opening)	1	1	
Water Depth at Flowline (outside of local depression)	6.0	12.0	inches
<b>Grate Information</b>	MINOR	MAJOR	<input checked="" type="checkbox"/> Override
Length of a Unit Grate	N/A	N/A	feet
Width of a Unit Grate	N/A	N/A	feet
Area Opening Ratio for a Grate (typical values 0.15-0.90)	N/A	N/A	
Clogging Factor for a Single Grate (typical value 0.50 - 0.70)	N/A	N/A	
Grate Weir Coefficient (typical value 2.15 - 3.60)	N/A	N/A	
Grate Orifice Coefficient (typical value 0.60 - 0.80)	N/A	N/A	
<b>Curb Opening Information</b>	MINOR	MAJOR	
Length of a Unit Curb Opening	15.00	15.00	feet
Height of Vertical Curb Opening in Inches	6.00	6.00	inches
Height of Curb Orifice Throat in Inches	6.00	6.00	inches
Angle of Throat (see USDCM Figure ST-5)	63.40	63.40	degrees
Side Width for Depression Pan (typically the gutter width of 2 feet)	1.17	1.17	feet
Clogging Factor for a Single Curb Opening (typical value 0.10)	0.10	0.10	
Curb Opening Weir Coefficient (typical value 2.3-3.7)	3.60	3.60	
Curb Opening Orifice Coefficient (typical value 0.60 - 0.70)	0.67	0.67	
<b>Low Head Performance Reduction (Calculated)</b>	MINOR	MAJOR	
Depth for Grate Midwidth	N/A	N/A	ft
Depth for Curb Opening Weir Equation	0.40	0.90	ft
Combination Inlet Performance Reduction Factor for Long Inlets	0.57	1.00	
Curb Opening Performance Reduction Factor for Long Inlets	0.79	1.00	
Grated Inlet Performance Reduction Factor for Long Inlets	N/A	N/A	
<b>Total Inlet Interception Capacity (assumes clogged condition)</b>	MINOR	MAJOR	
<b>Q<sub>a</sub></b>	11.9	39.1	cfs
Q <sub>PEAK REQUIRED</sub>	7.5	21.7	cfs

**Inlet Capacity IS GOOD for Minor and Major Storms(>Q PEAK)**

**ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)**

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)


Project: \_\_\_\_\_  
 Inlet ID: \_\_\_\_\_  
 Sterling Ranch Phase 2  
 B1- DP12



Gutter Geometry (Enter data in the blue cells)													
Maximum Allowable Width for Spread Behind Curb	$T_{BACK} = 17.0$ ft												
Side Slope Behind Curb (leave blank for no conveyance credit behind curb)	$S_{BACK} = 0.020$ ft/ft												
Manning's Roughness Behind Curb (typically between 0.012 and 0.020)	$n_{BACK} = 0.016$												
Height of Curb at Gutter Flow Line	$H_{CURB} = 6.00$ inches												
Distance from Curb Face to Street Crown	$T_{CROWN} = 17.0$ ft												
Gutter Width	$W = 1.17$ ft												
Street Transverse Slope	$S_x = 0.020$ ft/ft												
Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)	$S_w = 0.083$ ft/ft												
Street Longitudinal Slope - Enter 0 for sump condition	$S_o = 0.000$ ft/ft												
Manning's Roughness for Street Section (typically between 0.012 and 0.020)	$n_{STREET} = 0.016$												
Max. Allowable Spread for Minor & Major Storm	<table border="1"> <thead> <tr> <th></th> <th>Minor Storm</th> <th>Major Storm</th> <th></th> </tr> </thead> <tbody> <tr> <td><math>T_{MAX} =</math></td> <td>17.0</td> <td>17.0</td> <td>ft</td> </tr> <tr> <td><math>d_{MAX} =</math></td> <td>6.0</td> <td>12.0</td> <td>inches</td> </tr> </tbody> </table>		Minor Storm	Major Storm		$T_{MAX} =$	17.0	17.0	ft	$d_{MAX} =$	6.0	12.0	inches
	Minor Storm	Major Storm											
$T_{MAX} =$	17.0	17.0	ft										
$d_{MAX} =$	6.0	12.0	inches										
Max. Allowable Depth at Gutter Flowline for Minor & Major Storm													
Check boxes are not applicable in SUMP conditions													
<b>MINOR STORM Allowable Capacity is based on Depth Criterion</b>													
<b>MAJOR STORM Allowable Capacity is based on Depth Criterion</b>													
	<table border="1"> <thead> <tr> <th></th> <th>Minor Storm</th> <th>Major Storm</th> <th></th> </tr> </thead> <tbody> <tr> <td><math>Q_{allow} =</math></td> <td>SUMP</td> <td>SUMP</td> <td>cfs</td> </tr> </tbody> </table>		Minor Storm	Major Storm		$Q_{allow} =$	SUMP	SUMP	cfs				
	Minor Storm	Major Storm											
$Q_{allow} =$	SUMP	SUMP	cfs										

## INLET IN A SUMP OR SAG LOCATION

Version 4.05 Released March 2017




Design Information (Input)	MINOR	MAJOR	
Type of Inlet	CDOT Type R Curb Opening		
Local Depression (additional to continuous gutter depression 'a' from above)	3.00	3.00	inches
Number of Unit Inlets (Grate or Curb Opening)	1	1	
Water Depth at Flowline (outside of local depression)	5.0	12.0	inches
<b>Grate Information</b>	MINOR	MAJOR	<input checked="" type="checkbox"/> Override
Length of a Unit Grate	N/A	N/A	feet
Width of a Unit Grate	N/A	N/A	feet
Area Opening Ratio for a Grate (typical values 0.15-0.90)	N/A	N/A	
Clogging Factor for a Single Grate (typical value 0.50 - 0.70)	N/A	N/A	
Grate Weir Coefficient (typical value 2.15 - 3.60)	N/A	N/A	
Grate Orifice Coefficient (typical value 0.60 - 0.80)	N/A	N/A	
<b>Curb Opening Information</b>	MINOR	MAJOR	
Length of a Unit Curb Opening	15.00	15.00	feet
Height of Vertical Curb Opening in Inches	6.00	6.00	inches
Height of Curb Orifice Throat in Inches	6.00	6.00	inches
Angle of Throat (see USDCM Figure ST-5)	63.40	63.40	degrees
Side Width for Depression Pan (typically the gutter width of 2 feet)	1.17	1.17	feet
Clogging Factor for a Single Curb Opening (typical value 0.10)	0.10	0.10	
Curb Opening Weir Coefficient (typical value 2.3-3.7)	3.60	3.60	
Curb Opening Orifice Coefficient (typical value 0.60 - 0.70)	0.67	0.67	
<b>Low Head Performance Reduction (Calculated)</b>	MINOR	MAJOR	
Depth for Grate Midwidth	N/A	N/A	ft
Depth for Curb Opening Weir Equation	0.32	0.90	ft
Combination Inlet Performance Reduction Factor for Long Inlets	0.47	1.00	
Curb Opening Performance Reduction Factor for Long Inlets	0.72	1.00	
Grated Inlet Performance Reduction Factor for Long Inlets	N/A	N/A	
<b>Total Inlet Interception Capacity (assumes clogged condition)</b>	MINOR	MAJOR	
<b>Q<sub>a</sub></b>	<b>7.5</b>	<b>39.1</b>	<b>cfs</b>
Q <sub>PEAK REQUIRED</sub>	6.2	12.0	cfs

Inlet Capacity IS GOOD for Minor and Major Storms(>Q PEAK)

**ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)**

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)


Project: \_\_\_\_\_  
 Inlet ID: \_\_\_\_\_  
 Sterling Ranch Phase 2  
 B2 - DP13



Gutter Geometry (Enter data in the blue cells)							
Maximum Allowable Width for Spread Behind Curb	$T_{BACK} = 17.0$ ft						
Side Slope Behind Curb (leave blank for no conveyance credit behind curb)	$S_{BACK} = 0.020$ ft/ft						
Manning's Roughness Behind Curb (typically between 0.012 and 0.020)	$n_{BACK} = 0.016$						
Height of Curb at Gutter Flow Line	$H_{CURB} = 6.00$ inches						
Distance from Curb Face to Street Crown	$T_{CROWN} = 17.0$ ft						
Gutter Width	$W = 1.17$ ft						
Street Transverse Slope	$S_X = 0.020$ ft/ft						
Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)	$S_W = 0.083$ ft/ft						
Street Longitudinal Slope - Enter 0 for sump condition	$S_O = 0.000$ ft/ft						
Manning's Roughness for Street Section (typically between 0.012 and 0.020)	$n_{STREET} = 0.016$						
Max. Allowable Spread for Minor & Major Storm	<table border="1"> <thead> <tr> <th>Minor Storm</th> <th>Major Storm</th> <th>ft</th> </tr> </thead> <tbody> <tr> <td>17.0</td> <td>17.0</td> <td></td> </tr> </tbody> </table>	Minor Storm	Major Storm	ft	17.0	17.0	
Minor Storm	Major Storm	ft					
17.0	17.0						
Max. Allowable Depth at Gutter Flowline for Minor & Major Storm	<table border="1"> <thead> <tr> <th>Minor Storm</th> <th>Major Storm</th> <th>inches</th> </tr> </thead> <tbody> <tr> <td>6.0</td> <td>12.0</td> <td></td> </tr> </tbody> </table>	Minor Storm	Major Storm	inches	6.0	12.0	
Minor Storm	Major Storm	inches					
6.0	12.0						
Check boxes are not applicable in SUMP conditions							
<b>MINOR STORM Allowable Capacity is based on Depth Criterion</b>							
<b>MAJOR STORM Allowable Capacity is based on Depth Criterion</b>							
$Q_{allow} =$	<table border="1"> <thead> <tr> <th>Minor Storm</th> <th>Major Storm</th> <th>cfs</th> </tr> </thead> <tbody> <tr> <td>SUMP</td> <td>SUMP</td> <td></td> </tr> </tbody> </table>	Minor Storm	Major Storm	cfs	SUMP	SUMP	
Minor Storm	Major Storm	cfs					
SUMP	SUMP						

## INLET IN A SUMP OR SAG LOCATION

Version 4.05 Released March 2017




Design Information (Input)	MINOR	MAJOR	
Type of Inlet	CDOT Type R Curb Opening		
Local Depression (additional to continuous gutter depression 'a' from above)	3.00	3.00	inches
Number of Unit Inlets (Grate or Curb Opening)	1	1	
Water Depth at Flowline (outside of local depression)	5.6	12.0	inches
<b>Grate Information</b>	MINOR	MAJOR	<input checked="" type="checkbox"/> Override
Length of a Unit Grate	N/A	N/A	feet
Width of a Unit Grate	N/A	N/A	feet
Area Opening Ratio for a Grate (typical values 0.15-0.90)	N/A	N/A	
Clogging Factor for a Single Grate (typical value 0.50 - 0.70)	N/A	N/A	
Grate Weir Coefficient (typical value 2.15 - 3.60)	N/A	N/A	
Grate Orifice Coefficient (typical value 0.60 - 0.80)	N/A	N/A	
<b>Curb Opening Information</b>	MINOR	MAJOR	
Length of a Unit Curb Opening	20.00	20.00	feet
Height of Vertical Curb Opening in Inches	6.00	6.00	inches
Height of Curb Orifice Throat in Inches	6.00	6.00	inches
Angle of Throat (see USDCM Figure ST-5)	63.40	63.40	degrees
Side Width for Depression Pan (typically the gutter width of 2 feet)	1.17	1.17	feet
Clogging Factor for a Single Curb Opening (typical value 0.10)	0.10	0.10	
Curb Opening Weir Coefficient (typical value 2.3-3.7)	3.60	3.60	
Curb Opening Orifice Coefficient (typical value 0.60 - 0.70)	0.67	0.67	
<b>Low Head Performance Reduction (Calculated)</b>	MINOR	MAJOR	
Depth for Grate Midwidth	N/A	N/A	ft
Depth for Curb Opening Weir Equation	0.37	0.90	ft
Combination Inlet Performance Reduction Factor for Long Inlets	0.53	1.00	
Curb Opening Performance Reduction Factor for Long Inlets	0.76	1.00	
Grated Inlet Performance Reduction Factor for Long Inlets	N/A	N/A	
<b>Total Inlet Interception Capacity (assumes clogged condition)</b>	MINOR	MAJOR	
<b>Q<sub>a</sub></b>	13.1	52.7	cfs
<b>Q<sub>PEAK REQUIRED</sub></b>	9.1	18.7	cfs

Inlet Capacity IS GOOD for Minor and Major Storms(>Q PEAK)

**ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)**

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)


Project: \_\_\_\_\_  
 Inlet ID: \_\_\_\_\_  
 Sterling Ranch Phase 2  
 C1 - DP 6



Gutter Geometry (Enter data in the blue cells)													
Maximum Allowable Width for Spread Behind Curb	$T_{BACK} = 7.0$ ft												
Side Slope Behind Curb (leave blank for no conveyance credit behind curb)	$S_{BACK} = 0.020$ ft/ft												
Manning's Roughness Behind Curb (typically between 0.012 and 0.020) <input type="checkbox"/>	$n_{BACK} = 0.016$												
Height of Curb at Gutter Flow Line	$H_{CURB} = 6.00$ inches												
Distance from Curb Face to Street Crown	$T_{CROWN} = 26.0$ ft												
Gutter Width	$W = 2.00$ ft												
Street Transverse Slope	$S_x = 0.020$ ft/ft												
Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)	$S_w = 0.083$ ft/ft												
Street Longitudinal Slope - Enter 0 for sump condition	$S_o = 0.000$ ft/ft												
Manning's Roughness for Street Section (typically between 0.012 and 0.020)	$n_{STREET} = 0.016$												
Max. Allowable Spread for Minor & Major Storm	<table border="1"> <thead> <tr> <th></th> <th>Minor Storm</th> <th>Major Storm</th> <th></th> </tr> </thead> <tbody> <tr> <td><math>T_{MAX} =</math></td> <td>19.3</td> <td>26.0</td> <td>ft</td> </tr> <tr> <td><math>d_{MAX} =</math></td> <td>6.0</td> <td>7.7</td> <td>inches</td> </tr> </tbody> </table>		Minor Storm	Major Storm		$T_{MAX} =$	19.3	26.0	ft	$d_{MAX} =$	6.0	7.7	inches
	Minor Storm	Major Storm											
$T_{MAX} =$	19.3	26.0	ft										
$d_{MAX} =$	6.0	7.7	inches										
Max. Allowable Depth at Gutter Flowline for Minor & Major Storm													
Check boxes are not applicable in SUMP conditions													
<b>MINOR STORM Allowable Capacity is based on Depth Criterion</b>													
<b>MAJOR STORM Allowable Capacity is based on Depth Criterion</b>													
	<table border="1"> <thead> <tr> <th></th> <th>Minor Storm</th> <th>Major Storm</th> <th></th> </tr> </thead> <tbody> <tr> <td><math>Q_{allow} =</math></td> <td>SUMP</td> <td>SUMP</td> <td>cfs</td> </tr> </tbody> </table>		Minor Storm	Major Storm		$Q_{allow} =$	SUMP	SUMP	cfs				
	Minor Storm	Major Storm											
$Q_{allow} =$	SUMP	SUMP	cfs										

## INLET IN A SUMP OR SAG LOCATION

Version 4.05 Released March 2017




Design Information (Input)	MINOR	MAJOR	
Type of Inlet	CDOT Type R Curb Opening		
Local Depression (additional to continuous gutter depression 'a' from above)	3.00	3.00	inches
Number of Unit Inlets (Grate or Curb Opening)	1	1	
Water Depth at Flowline (outside of local depression)	6.0	7.7	inches
<b>Grate Information</b>	MINOR	MAJOR	
Length of a Unit Grate	N/A	N/A	feet
Width of a Unit Grate	N/A	N/A	feet
Area Opening Ratio for a Grate (typical values 0.15-0.90)	N/A	N/A	
Clogging Factor for a Single Grate (typical value 0.50 - 0.70)	N/A	N/A	
Grate Weir Coefficient (typical value 2.15 - 3.60)	N/A	N/A	
Grate Orifice Coefficient (typical value 0.60 - 0.80)	N/A	N/A	
<b>Curb Opening Information</b>	MINOR	MAJOR	
Length of a Unit Curb Opening	15.00	15.00	feet
Height of Vertical Curb Opening in Inches	6.00	6.00	inches
Height of Curb Orifice Throat in Inches	6.00	6.00	inches
Angle of Throat (see USDCM Figure ST-5)	63.40	63.40	degrees
Side Width for Depression Pan (typically the gutter width of 2 feet)	2.00	2.00	feet
Clogging Factor for a Single Curb Opening (typical value 0.10)	0.10	0.10	
Curb Opening Weir Coefficient (typical value 2.3-3.7)	3.60	3.60	
Curb Opening Orifice Coefficient (typical value 0.60 - 0.70)	0.67	0.67	
<b>Low Head Performance Reduction (Calculated)</b>	MINOR	MAJOR	
Depth for Grate Midwidth	N/A	N/A	ft
Depth for Curb Opening Weir Equation	0.33	0.48	ft
Combination Inlet Performance Reduction Factor for Long Inlets	0.57	0.73	
Curb Opening Performance Reduction Factor for Long Inlets	0.79	0.88	
Grated Inlet Performance Reduction Factor for Long Inlets	N/A	N/A	
<b>Total Inlet Interception Capacity (assumes clogged condition)</b>	MINOR	MAJOR	
<b>Q<sub>a</sub></b>	9.7	18.5	cfs
Q <sub>PEAK REQUIRED</sub>	5.4	12.3	cfs

Inlet Capacity IS GOOD for Minor and Major Storms(>Q PEAK)

**ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)**

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project: \_\_\_\_\_  
 Inlet ID: \_\_\_\_\_  
 Sterling Ranch Phase 2  
 C2 - DP5




Gutter Geometry (Enter data in the blue cells)					
Maximum Allowable Width for Spread Behind Curb	T <sub>BACK</sub> = 9.0 ft				
Side Slope Behind Curb (leave blank for no conveyance credit behind curb)	S <sub>BACK</sub> = 0.020 ft/ft				
Manning's Roughness Behind Curb (typically between 0.012 and 0.020) <input type="checkbox"/> <input type="checkbox"/>	n <sub>BACK</sub> = 0.016				
Height of Curb at Gutter Flow Line	H <sub>CURB</sub> = 6.00 inches				
Distance from Curb Face to Street Crown	T <sub>CROWN</sub> = 26.0 ft				
Gutter Width	W = 2.00 ft				
Street Transverse Slope	S <sub>x</sub> = 0.020 ft/ft				
Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)	S <sub>w</sub> = 0.083 ft/ft				
Street Longitudinal Slope - Enter 0 for sump condition	S <sub>O</sub> = 0.000 ft/ft				
Manning's Roughness for Street Section (typically between 0.012 and 0.020)	n <sub>STREET</sub> = 0.016				
Max. Allowable Spread for Minor & Major Storm	T <sub>MAX</sub> = <table border="1" style="display: inline-table;"><tr><th>Minor Storm</th><th>Major Storm</th></tr><tr><td>19.3</td><td>26.0</td></tr></table> ft	Minor Storm	Major Storm	19.3	26.0
Minor Storm	Major Storm				
19.3	26.0				
Max. Allowable Depth at Gutter Flowline for Minor & Major Storm	d <sub>MAX</sub> = <table border="1" style="display: inline-table;"><tr><th>Minor Storm</th><th>Major Storm</th></tr><tr><td>6.0</td><td>7.7</td></tr></table> inches	Minor Storm	Major Storm	6.0	7.7
Minor Storm	Major Storm				
6.0	7.7				
Check boxes are not applicable in SUMP conditions					
<b>MINOR STORM Allowable Capacity is based on Depth Criterion</b>					
<b>MAJOR STORM Allowable Capacity is based on Depth Criterion</b>					
Q <sub>allow</sub> =	<table border="1" style="display: inline-table;"><tr><th>Minor Storm</th><th>Major Storm</th></tr><tr><td>SUMP</td><td>SUMP</td></tr></table> cfs	Minor Storm	Major Storm	SUMP	SUMP
Minor Storm	Major Storm				
SUMP	SUMP				



## INLET IN A SUMP OR SAG LOCATION

Version 4.05 Released March 2017




Design Information (Input)	MINOR	MAJOR	
Type of Inlet	CDOT Type R Curb Opening		
Local Depression (additional to continuous gutter depression 'a' from above)	3.00	3.00	inches
Number of Unit Inlets (Grate or Curb Opening)	3	3	
Water Depth at Flowline (outside of local depression)	6.0	8.0	inches
<b>Grate Information</b>	MINOR	MAJOR	<input checked="" type="checkbox"/> Override
Length of a Unit Grate	N/A	N/A	feet
Width of a Unit Grate	N/A	N/A	feet
Area Opening Ratio for a Grate (typical values 0.15-0.90)	N/A	N/A	
Clogging Factor for a Single Grate (typical value 0.50 - 0.70)	N/A	N/A	
Grate Weir Coefficient (typical value 2.15 - 3.60)	N/A	N/A	
Grate Orifice Coefficient (typical value 0.60 - 0.80)	N/A	N/A	
<b>Curb Opening Information</b>	MINOR	MAJOR	
Length of a Unit Curb Opening	5.00	5.00	feet
Height of Vertical Curb Opening in Inches	6.00	6.00	inches
Height of Curb Orifice Throat in Inches	6.00	6.00	inches
Angle of Throat (see USDCM Figure ST-5)	63.40	63.40	degrees
Side Width for Depression Pan (typically the gutter width of 2 feet)	2.00	2.00	feet
Clogging Factor for a Single Curb Opening (typical value 0.10)	0.10	0.10	
Curb Opening Weir Coefficient (typical value 2.3-3.7)	3.60	3.60	
Curb Opening Orifice Coefficient (typical value 0.60 - 0.70)	0.67	0.67	
<b>Low Head Performance Reduction (Calculated)</b>	MINOR	MAJOR	
Depth for Grate Midwidth	N/A	N/A	ft
Depth for Curb Opening Weir Equation	0.33	0.50	ft
Combination Inlet Performance Reduction Factor for Long Inlets	0.57	0.75	
Curb Opening Performance Reduction Factor for Long Inlets	0.79	0.89	
Grated Inlet Performance Reduction Factor for Long Inlets	N/A	N/A	
<b>Total Inlet Interception Capacity (assumes clogged condition)</b>	MINOR	MAJOR	
<b>Q<sub>a</sub></b>	13.5	27.9	cfs
<b>Q<sub>PEAK REQUIRED</sub></b>	12.0	25.9	cfs

**Inlet Capacity IS GOOD for Minor and Major Storms(>Q PEAK)**

**ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)**

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)


Project:  Sterling Ranch Phase 2   
 Inlet ID:  C4 - DP8



Gutter Geometry (Enter data in the blue cells)					
Maximum Allowable Width for Spread Behind Curb	T <sub>BACK</sub> = 5.0 ft				
Side Slope Behind Curb (leave blank for no conveyance credit behind curb)	S <sub>BACK</sub> = 0.020 ft/ft				
Manning's Roughness Behind Curb (typically between 0.012 and 0.020)	n <sub>BACK</sub> = 0.016				
Height of Curb at Gutter Flow Line	H <sub>CURB</sub> = 6.00 inches				
Distance from Curb Face to Street Crown	T <sub>CROWN</sub> = 30.0 ft				
Gutter Width	W = 2.00 ft				
Street Transverse Slope	S <sub>X</sub> = 0.020 ft/ft				
Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)	S <sub>W</sub> = 0.083 ft/ft				
Street Longitudinal Slope - Enter 0 for sump condition	S <sub>O</sub> = 0.015 ft/ft				
Manning's Roughness for Street Section (typically between 0.012 and 0.020)	n <sub>STREET</sub> = 0.016				
Max. Allowable Spread for Minor & Major Storm	T <sub>MAX</sub> = <table border="1"><tr><th>Minor Storm</th><th>Major Storm</th></tr><tr><td>15.0</td><td>30.0</td></tr></table> ft	Minor Storm	Major Storm	15.0	30.0
Minor Storm	Major Storm				
15.0	30.0				
Max. Allowable Depth at Gutter Flowline for Minor & Major Storm	d <sub>MAX</sub> = <table border="1"><tr><th>Minor Storm</th><th>Major Storm</th></tr><tr><td>6.0</td><td>6.0</td></tr></table> inches	Minor Storm	Major Storm	6.0	6.0
Minor Storm	Major Storm				
6.0	6.0				
Allow Flow Depth at Street Crown (leave blank for no)	<input type="checkbox"/> <input type="checkbox"/> check = yes				
<b>MINOR STORM Allowable Capacity is based on Spread Criterion</b>					
<b>MAJOR STORM Allowable Capacity is based on Depth Criterion</b>					
Minor storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'	Q <sub>allow</sub> = <table border="1"><tr><th>Minor Storm</th><th>Major Storm</th></tr><tr><td>9.8</td><td>16.9</td></tr></table> cfs	Minor Storm	Major Storm	9.8	16.9
Minor Storm	Major Storm				
9.8	16.9				
Major storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'					

## INLET ON A CONTINUOUS GRADE

Version 4.05 Released March 2017




Design Information (Input)	MINOR	MAJOR	
Type of Inlet	CDOT Type R Curb Opening		
Local Depression (additional to continuous gutter depression 'a')	3.0	3.0	inches
Total Number of Units in the Inlet (Grate or Curb Opening)	3	3	
Length of a Single Unit Inlet (Grate or Curb Opening)	5.00	5.00	ft
Width of a Unit Grate (cannot be greater than W, Gutter Width)	N/A	N/A	ft
Clogging Factor for a Single Unit Grate (typical min. value = 0.5)	N/A	N/A	
Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.1)	0.10	0.10	
<b>Street Hydraulics: OK - Q &lt; Allowable Street Capacity*</b>			
Total Inlet Interception Capacity	4.6	9.4	cfs
Total Inlet Carry-Over Flow (flow bypassing inlet)	0.0	0.8	cfs
Capture Percentage = $Q_i/Q_o$ =	100	92	%

**ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)**

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)


Project: \_\_\_\_\_  
 Inlet ID: \_\_\_\_\_  
 Sterling Ranch Phase 2  
 B3 - DP9



<b>Gutter Geometry (Enter data in the blue cells)</b>							
Maximum Allowable Width for Spread Behind Curb	$T_{BACK} = 5.0$ ft						
Side Slope Behind Curb (leave blank for no conveyance credit behind curb)	$S_{BACK} = 0.020$ ft/ft						
Manning's Roughness Behind Curb (typically between 0.012 and 0.020)	$n_{BACK} = 0.016$						
Height of Curb at Gutter Flow Line	$H_{CURB} = 6.00$ inches						
Distance from Curb Face to Street Crown	$T_{CROWN} = 30.0$ ft						
Gutter Width	$W = 2.00$ ft						
Street Transverse Slope	$S_x = 0.020$ ft/ft						
Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)	$S_w = 0.083$ ft/ft						
Street Longitudinal Slope - Enter 0 for sump condition	$S_o = 0.015$ ft/ft						
Manning's Roughness for Street Section (typically between 0.012 and 0.020)	$n_{STREET} = 0.016$						
Max. Allowable Spread for Minor & Major Storm	<table border="1"> <thead> <tr> <th>Minor Storm</th> <th>Major Storm</th> <th>ft</th> </tr> </thead> <tbody> <tr> <td>15.0</td> <td>30.0</td> <td></td> </tr> </tbody> </table>	Minor Storm	Major Storm	ft	15.0	30.0	
Minor Storm	Major Storm	ft					
15.0	30.0						
Max. Allowable Depth at Gutter Flowline for Minor & Major Storm	<table border="1"> <thead> <tr> <th>Minor Storm</th> <th>Major Storm</th> <th>inches</th> </tr> </thead> <tbody> <tr> <td>6.0</td> <td>6.0</td> <td></td> </tr> </tbody> </table>	Minor Storm	Major Storm	inches	6.0	6.0	
Minor Storm	Major Storm	inches					
6.0	6.0						
Allow Flow Depth at Street Crown (leave blank for no)	<input type="checkbox"/> <input type="checkbox"/> check = yes						
<b>MINOR STORM Allowable Capacity is based on Spread Criterion</b>							
<b>MAJOR STORM Allowable Capacity is based on Depth Criterion</b>							
Minor storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'	<table border="1"> <thead> <tr> <th>Minor Storm</th> <th>Major Storm</th> <th>cfs</th> </tr> </thead> <tbody> <tr> <td>9.8</td> <td>16.9</td> <td></td> </tr> </tbody> </table>	Minor Storm	Major Storm	cfs	9.8	16.9	
Minor Storm	Major Storm	cfs					
9.8	16.9						
Major storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'							

## INLET ON A CONTINUOUS GRADE

Version 4.05 Released March 2017



Design Information (Input)	MINOR	MAJOR	
Type of Inlet	CDOT Type R Curb Opening		
Local Depression (additional to continuous gutter depression 'a')	3.0	3.0	inches
Total Number of Units in the Inlet (Grate or Curb Opening)	3	3	
Length of a Single Unit Inlet (Grate or Curb Opening)	5.00	5.00	ft
Width of a Unit Grate (cannot be greater than W, Gutter Width)	N/A	N/A	ft
Clogging Factor for a Single Unit Grate (typical min. value = 0.5)	N/A	N/A	
Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.1)	0.10	0.10	
<b>Street Hydraulics: OK - Q &lt; Allowable Street Capacity*</b>			
Total Inlet Interception Capacity	3.5	7.3	cfs
Total Inlet Carry-Over Flow (flow bypassing inlet)	0.0	0.0	cfs
Capture Percentage = $Q_i/Q_o$ =	100	100	%

# Channel Report

## Barbarick FSD Overflow Channel

### Trapezoidal


Bottom Width (ft) = 3.00  
Side Slopes (z:1) = 3.00, 3.00  
Total Depth (ft) = 3.00  
Invert Elev (ft) = 7013.00  
Slope (%) = 0.75  
N-Value = 0.013

### Highlighted

Depth (ft) = 1.37  
Q (cfs) = 84.40  
Area (sqft) = 9.74  
Velocity (ft/s) = 8.66  
Wetted Perim (ft) = 11.66  
Crit Depth, Yc (ft) = 1.75  
Top Width (ft) = 11.22  
EGL (ft) = 2.54

### Calculations

Compute by: Known Q  
Known Q (cfs) = 84.40



# Channel Report

## Interim Channel - DP I1

### Triangular

Side Slopes (z:1) = 4.00, 4.00  
Total Depth (ft) = 3.00


Invert Elev (ft) = 6970.00  
Slope (%) = 0.88  
N-Value = 0.025

### Calculations

Compute by: Known Q  
Known Q (cfs) = 31.20


### Highlighted

Depth (ft) = 1.36  
Q (cfs) = 31.20  
Area (sqft) = 7.40  
Velocity (ft/s) = 4.22  
Wetted Perim (ft) = 11.21  
Crit Depth, Yc (ft) = 1.31  
Top Width (ft) = 10.88  
EGL (ft) = 1.64



Scenario: 100 Year


Interim condition?



← Also provide final condition



# Scenario: 100 Year



Scenario: 100 Year  
 Current Time Step: 0.000 h  
 FlexTable: Conduit Table

Label	Flow (cfs)	Diameter (in)	Length (User Defined) (ft)	Slope (Calculated) (ft/ft)	Manning's n	Velocity (ft/s)	Capacity (Full Flow) (cfs)	Hydraulic Grade Line (In) (ft)	Hydraulic Grade Line (Out) (ft)	Notes
C-11	1.40	18.0	109.7	0.027	0.013	5.84	17.13	7,013.59	7,010.88	12' RCP
C-10	2.80	18.0	45.0	0.016	0.013	5.99	13.38	7,010.87	7,009.97	12' RCP
C-9	4.20	18.0	199.1	0.015	0.013	6.50	12.83	7,005.26	7,002.09	12' RCP
C-5	18.70	18.0	34.0	0.010	0.013	10.58	10.66	7,003.46	7,002.36	18' RCP
C-4	30.30	24.0	126.1	0.019	0.013	11.20	30.88	7,002.17	6,999.57	24' RCP
C-8	5.60	18.0	275.2	0.010	0.013	3.17	10.65	6,999.20	6,998.41	12' RCP
C-3	34.10	30.0	416.6	0.003	0.013	6.95	22.47	6,995.28	6,992.40	24' RCP
C-6	6.80	18.0	355.0	0.003	0.013	3.85	5.77	6,998.10	6,996.61	18' RCP
C-7	5.60	18.0	101.9	0.011	0.013	3.17	11.16	6,998.40	6,998.11	12' RCP
C-2	43.90	30.0	45.6	0.003	0.013	8.94	22.73	6,992.34	6,991.82	24' RCP
C-1	45.60	30.0	93.8	0.003	0.013	9.29	22.46	6,991.19	6,989.88	30' RCP

X:\2510000.all\2518800\StormCAD\Sterling Ranch PH 2\Sterling Ranch PH-2.stsw

Capacities less than flows

Provide calculations for the "C" basins also - inlets 5 and 6 to MH 7.1 and DP4 to MH7.1.

**Scenario: 5 Year**  
**Current Time Step: 0.000 h**  
**FlexTable: Conduit Table**


Label	Flow (cfs)	Diameter (in)	Length (User Defined) (ft)	Slope (Calculated) (ft/ft)	Manning's n	Velocity (ft/s)	Capacity (Full Flow) (cfs)	Hydraulic Grade Line (In) (ft)	Hydraulic Grade Line (Out) (ft)	Notes
C-11	0.57	18.0	109.7	0.027	0.013	4.49	17.13	7,013.43	7,010.64	12' RCP
C-10	1.15	18.0	45.0	0.016	0.013	4.63	13.38	7,010.63	7,009.80	12' RCP
C-9	1.73	18.0	199.1	0.015	0.013	5.06	12.83	7,004.96	7,001.87	12' RCP
C-5	9.10	18.0	34.0	0.010	0.013	6.78	10.66	7,002.42	7,001.97	18' RCP
C-4	15.00	24.0	126.1	0.019	0.013	9.76	30.88	7,001.70	6,998.93	24' RCP
C-8	2.30	18.0	275.2	0.010	0.013	4.81	10.65	6,997.07	6,994.26	12' RCP
C-3	16.10	30.0	416.6	0.003	0.013	4.98	22.47	6,992.02	6,990.93	24' RCP
C-6	2.80	18.0	355.0	0.003	0.013	3.24	5.77	6,993.26	6,992.70	18' RCP
C-7	2.30	18.0	101.9	0.011	0.013	4.97	11.16	6,994.24	6,993.27	12' RCP
C-2	21.80	30.0	45.6	0.003	0.013	5.27	22.73	6,990.91	6,990.55	24' RCP
C-1	22.70	30.0	93.8	0.003	0.013	5.22	22.46	6,989.85	6,989.26	30' RCP

X:\2510000.all\2518800\StormCAD\Sterling Ranch PH 2\Sterling Ranch PH-2.stsw

## **Appendix D**

### **Reference Material**

**SAND CREEK DRAINAGE BASIN PLANNING STUDY**  
**PRELIMINARY DESIGN REPORT**  
**CITY OF COLORADO SPRINGS, EL PASO COUNTY, COLORADO**



**PREPARED FOR:**

City of Colorado Springs  
Department of Comprehensive Planning, Development and Finance  
Engineering Division  
30 S. Nevada  
Colorado Springs, Colorado 80903

**PREPARED BY:**

Kiowa Engineering Corporation  
1011 North Weber  
Colorado Springs, CO 80903

## II. STUDY AREA DESCRIPTION

---

The Sand Creek drainage basin is a left-bank tributary to the Fountain Creek lying in the west-central portions of El Paso County. Sand Creek's drainage area at Fountain Creek is approximately 54 square miles of which approximately 18.8 square miles are inside the City of Colorado Springs corporate limits. The basin is divided into five major sub-basins, the Sand Creek mainstem, the East Fork Sand Creek, the Central Tributary to East Fork, the West Fork, and the East Fork Subtributary. Figure II-1 shows the location of the Sand Creek basin.

### Basin Description

The Sand Creek basin covers a total of 54 square miles in unincorporated El Paso County and Colorado Springs, Colorado. Of this total, approximately 28 square miles is encompassed by the Sand Creek basin, and 26 square miles for the East Fork Sand Creek basin. The basin trends in generally a south to southwesterly direction, entering the Fountain Creek approximately two miles upstream of the Academy Boulevard bridge over Fountain Creek. Two main tributaries drain the basin, those being the mainstem of Sand Creek and East Fork Sand Creek. Development presence is most evident along the mainstream. At this time, approximately 25 percent of the basin is developed. This alternative evaluation focuses upon the Sand Creek basin only.

The maximum basin elevation is approximately 7,620 feet above mean sea level, and falls to approximately 5,790 feet at the confluence with Fountain Creek. The headwaters of the basin originate in the conifer covered areas of The Black Forest. The middle eastern portions of the basin are typified by rolling range land with fair to good vegetative cover associated with semi-arid climates.

### Climate

This area of El Paso County can be described, in general as high plains, with total precipitation amounts typical of a semi-arid region. Winters are generally cold and dry. Precipitation ranges from 14 to 16 inches per year, with the majority of this precipitation occurring in spring and summer in the form of rainfall. Thunderstorms are common during the summer months, and are typified by quick-moving low pressure cells which draw moisture from the Gulf of Mexico into the region. Average temperatures range from about 30°F in the winter

to 75° in the summer. The relative humidity ranges from about 25 percent in the summer to 45 percent in the winter.

### Soils and Geology


Soils within the Sand Creek basin vary between soil types A through D, as identified by the U. S. Department of Agriculture, Soil Conservation Service. The predominant soil groupings are in the Truckton and Bresser soil associations. The soils consist of deep, well drained soils that formed in alluvium and residuum, derived from sedimentary rock. The soils have high to moderate infiltration rates, and are extremely susceptible to wind and water erosion where poor vegetation cover exists. In undeveloped areas, the predominance of Type A and B soils give this basin a lower runoff per unit area as compared to basins with soils dominated by Types C and D. Presented on Figure II-2 is the Hydrologic Soil distribution map for the Sand Creek basin.

### Property Ownership and Impervious Land Densities


Property ownership along the major drainageway within the Sand Creek basin vary from public to private. Along the developed reaches, drainage right-of-ways and greenbelts have been dedicated during the development of the adjacent residential and commercial land. Where development has not occurred, the drainageways remain under private ownership with no delineated drainage right-of-way or easements. There are several public parks which abut the mainstem of Sand Creek. Roadway and utility easements abutting or crossing the major drainageways occur most frequently in the developed portions of the basin.

Land use information for the existing and future conditions were reviewed as part of the planning effort. This information is used in the hydrologic analysis to predict runoff rates and volumes for the purposes of facility evaluation. The identification of land uses abutting the drainageways is also useful in the identification of feasible plans for stabilization and aesthetic treatment of the creek. Presented on Figure II-3 is the proposed land use map used in the evaluation of impervious land densities discussed in the hydrologic section of this report. Figure II-3 is not intended to reflect the future zoning or land use policies of the City or the County.

The land use information within the Banning-Lewis Ranch property was obtained from Aries Properties during the time the draft East Fork Sand Creek Drainage Basin Planning Study was being prepared. The land use information was again reviewed with the City of Colorado Springs Department of Planning and was found to be appropriate for use in the estimation of hydrology for the East Fork Basin. The location of future arterial streets and roadways within



Kiowa Engineering Corporation  
 419 W. Bijou Street  
 Colorado Springs, Colorado  
 80905-1308



SAND CREEK DRAINAGE  
 BASIN PLANNING STUDY  
 REGIONAL SUB-BASINS

Project No	90-04-09
Date:	11/90
Design:	
Drawn:	EAK
Check:	
Revisions:	





Label this (Barbarick pond...?)

---

### Worksheet for FSD Outlet Orifice Plate

---

#### Project Description

Solve For                      Diameter

#### Input Data

Discharge	45.90	ft <sup>3</sup> /s	(16.5 H <sub>15</sub> + 29.4 P <sub>2cc</sub> )
Headwater Elevation	4.70	ft	
Centroid Elevation	0.00	ft	
Tailwater Elevation	0.00	ft	
Discharge Coefficient	0.60		

#### Results

Diameter	2.37	ft	
Headwater Height Above Centroid	4.70	ft	
Tailwater Height Above Centroid	0.00	ft	
Flow Area	4.40	ft <sup>2</sup>	
Velocity	10.43	ft/s	

Label this (Barbarick pond...?)

### Worksheet for FSD Overflow - Pass

#### Project Description

Solve For Discharge

#### Input Data

Headwater Elevation		0.90	ft
Crest Elevation		0.00	ft
Tailwater Elevation		0.00	ft
Crest Surface Type	Gravel		
Crest Breadth		12.00	ft
Crest Length		36.00	ft

#### Results

Discharge	86.22	ft <sup>3</sup> /s
Headwater Height Above Crest	0.90	ft
Tailwater Height Above Crest	0.00	ft
Weir Coefficient	2.80	US
Submergence Factor	1.00	
Adjusted Weir Coefficient	2.80	US
Flow Area	32.40	ft <sup>2</sup>
Velocity	2.66	ft/s
Wetted Perimeter	37.80	ft
Top Width	36.00	ft

$(55 \text{ DU} + 29.4 \text{ pass} = 84.4 \text{ cfs})$

Duplicate?

---

### Worksheet for FSD Overflow - Pass

---

#### Project Description


Solve For Discharge

#### Input Data

Headwater Elevation	0.90	ft
Crest Elevation	0.00	ft
Tailwater Elevation	0.00	ft
Crest Surface Type	Gravel	
Crest Breadth	12.00	ft
Crest Length	36.00	ft

#### Results

Discharge	86.22	ft <sup>3</sup> /s	(55 DVI + 29.4 pipe = 84.4 cfs)
Headwater Height Above Crest	0.90	ft	
Tailwater Height Above Crest	0.00	ft	
Weir Coefficient	2.80	US	
Submergence Factor	1.00		
Adjusted Weir Coefficient	2.80	US	
Flow Area	32.40	ft <sup>2</sup>	
Velocity	2.66	ft/s	
Wetted Perimeter	37.80	ft	
Top Width	36.00	ft	



BASIN DETERMINATION PER WOODMAN VIEW STORAGE FINAL DRAINAGE REPORT JULY 2010

O2	11.2	16.7	30.3
----	------	------	------

BASIN DETERMINATION PER PRELIMINARY AND FINAL DRAINAGE PLAN FOR BARBARICK SUBDIVISION JANUARY 2005.

O3	7.03	13.7	35.5
----	------	------	------

**FSD POND**  
 $V_{100} = 0.203$  AC-FT  
 $WQ WSE = 20.03$   
 $V_A = 0.673$  AC-FT  
 $5\text{-YR WSE} = 21.50$   
 $V_{100} = 1.261$  AC-FT  
 $100\text{-YR WSE} = 22.76$   
 $Q_A \text{ RELEASE} = 45.9$  CFS  
 $Q_{100} \text{ RELEASE} = 0.677$  AC-FT  
 $EURV \text{ ELEV} = 21.50$

**SAND FILTER POND**  
 $V_{100} = 0.039$  AC-FT  
 $WQ WSE = 23.37$   
 $EURV WQ = 0.181$   
 $EURV \text{ ELEV} = 24.52$   
 $100\text{-YR WSE} = 0.394$  AC-FT  
 $100\text{-YR WSE} = 23.63$   
 $Q_A \text{ RELEASE} = 0.1$  CFS  
 $Q_{100} \text{ RELEASE} = 3.6$  CFS


**BARBARICK DRAINAGE SUMMARY TABLE**

BASIN	AREA (AC.)	Q(5) (CFS)	Q(100) (CFS)	% IMP.	COMMENT
D1	11.40	25.7	56.0	57%	D1 BASIN TO FSD +02; PASS THROUGH POND RELEASE + D2
D2	1.21	0.8	3.0	2%	HISTORIC
D3	3.13	4.1	11.6	57%	D3 BASIN TO SFB
O2	11.12	16.7	30.3		POND RELEASE + O3. PIPE PASS THROUGH
O3	7.03	13.7	35.5		

DESIGN POINT	AREA (AC.)	Q(100) (CFS)	COMMENT
D1	11.40	85.4	D1 BASIN TO FSD +02; PASS THROUGH POND RELEASE + D2
D2	22.52	48.9	D3 BASIN TO SFB
D3	3.13	11.6	POND RELEASE + O3. PIPE PASS THROUGH
D4	10.16	39.1	

**PROJECT SITE**



**VICINITY MAP**  
N.T.S.

**LEGEND**

- SUB-BASIN BOUNDARY
- - - EXISTING CONTOUR
- - - PHASE 3A FILING LIMITS
- - - TEMPORARY DIVERSION SWALE
- - - LOT LINE
- △ DESIGN POINT
- XX SUB BASIN DESIGNATION
- 99.9 SUB BASIN PERCENT IMPERVIOUS
- 0.99 SUB BASIN AREA (AC.)
- 80 5 - YEAR STORM EVENT PEAK FLOW (CFS)
- 80 100 - YEAR STORM EVENT PEAK FLOW (CFS)
- PROPOSED FLOW DIRECTION
- EXISTING FLOW DIRECTION

NO.	DATE	DESCRIPTION	BY
REVISIONS			
BENCHMARK DATA (ELEV.)			
(DATUM)			
(DESCRIPTION/LOCATION)			

**VERTICAL BENCHMARK**  
 THE VERTICAL BENCHMARK DATA FOR THIS MAP IS BASED ON THE NATIONAL GEODETIC SURVEY DATUM OF 1983 AND THE 1980 SUPPLEMENTARY ADJUSTMENT BEING A ROUND 3.2" ALUMINUM CAP IN A ROAD BOX DESIGNATED AS FACILITIES INFORMATION MANAGEMENT SYSTEM (FIMS) MONUMENT "E" 69' AND HAVING PUBLISHED ELEVATION OF 6975.62 FEET WAS USED TO BACK SIGHT TO THE BENCHMARK. THE BENCHMARK IS LOCATED AT THE CORNER OF THE SCHMIDT CONSTRUCTION COMPANY DRIVEWAY, ABOUT 1.55 MILES SOUTH OF OLD RANCH ROAD, JUST SOUTH OF THE SCHMIDT AND THE MOST SOUTHERLY GUARDRAIL POST IS 25.7 FEET TO THE NORTH.

**BASIS OF MEASUREMENT**  
 THIS MAP IS THE NORTH LINE OF BARBARICK SUBDIVISION ACCORDING TO THE OFFICIAL MAP THEREOF RECORDED FEBRUARY 12, 2008 IN THE OFFICE OF THE PASO COUNTY CLERK AND RECORDER UNDER RECEPTION NUMBER 208712754 AND LINE MONUMENTED ON THE WEST END BY A FOUND 5/8" REBAR AND ON THE EAST BY A FOUND 1/8" REBAR WITH 1" CAP END BEING A POINT ON THE NORTH LINE BEARING NORTH 89°12'41" EAST 187.25 FEET FROM THE WEST END THEREOF.

DESIGNED BY				SCALE			
DRAWN BY				HORIZ			
CHECKED BY				VERT			
DATE ISSUED				SHEET NO.			
APRIL 2016				1 OF 2 SHEETS			

**Matrix DESIGN GROUP**  
 2435 Research Parkway, Suite 300  
 Colorado Springs, CO 80920  
 Phone 719-575-0100  
 Fax 719-575-0208

PREPARED UNDER MY DIRECT SUPERVISION AND ON BEHALF OF MATRIX DESIGN GROUP, INC.

**BARBARICK SUBDIVISION LOTS 1-4**

**PROPOSED DRAINAGE PLAN**

NAME: S:\115\88\001\T1\Lines\DWG\DD\Drainage\20160505-DP01.dwg  
 PLOT DATE: Tue Jun 07 2016 12:46pm



**DESIGN POINT**

DP	Q5 Total	Q100 Total
1	4.4	9.4
2	1.9	3.9
3	11.1	24.7
4	3.7	7.4
5	4.1	19.6
6	3.3	6.7
6A	2.2	4.1
7	27.5	60.6
8	3.0	12.5
9	1.9	4.8
10	9.2	17.3
11	9.5	19.9
12	1.9	9.5
13	15.7	34.6
14	16.0	37.9
15	5.4	11.7
16	4.4	9.6
17	1.4	4.7
18	4.3	14.0
19	38.8	85.4
20	7.1	13.4
21	7.4	15.2
22	2.7	15.4
23	8.8	15.8
24	11.5	20.6
25	61.0	310.0
26	4.2	21.9
27	8.3	14.4
28	8.4	16.7
29	3.1	16.3
30	0.9	6.4
31	2.0	15.0
32	1.4	10.0
3.0	6.0	10.3
1.1	12.6	19.7
1.2	17.6	28.2
1.3	25.9	46.9
1.3A	5.0	8.7
1.4	52.5	105.9
1.5	55.1	103.9
1.6	56.4	107.7
1.7	17.3	25.3
1.8	68.8	125.0
2.0	23.2	74.5
2.1	38.1	106.6
2.2	56.9	138.7
2.3	9.6	17.2
2.4	63.7	151.9
2.5	96.6	250.7
2.6	97.8	250.4
2.7	162.0	336.8
2.8	189.8	424.4
2.9	14.2	22.5
3.0	189.8	424.4
3.1	14.2	22.5
3.2	187.5	428.2
4.0	18.4	26.1
4.1	56.2	264.7
4.2	16.0	31.0
4.3	49.9	293.1
4.4	3.1	3.1
4.5	51.2	51.2
4.6	56.7	245.8
4.7	58.5	248.6
4.8	59.9	320.3
OS2	17.0	70.9
OS3	17.6	48.9
OS4	5.08	8.5

**Basin Summary Table**

Tributary Sub-basin	Area (acres)	Percent Impervious	C <sub>s</sub>	C <sub>100</sub>	t <sub>c</sub> (min)	Q <sub>s</sub> (cfs)	Q <sub>100</sub> (cfs)
A1	2.06	66%	0.51	0.65	9.7	4.4	9.4
A2	0.82	69%	0.53	0.66	9.1	1.9	3.9
A3	6.76	60%	0.47	0.62	15.0	11.1	24.7
A4	1.51	77%	0.60	0.71	10.2	3.7	7.4
A5	1.70	76%	0.59	0.70	9.3	4.1	8.3
A6	1.37	75%	0.58	0.70	10.0	3.3	6.6
A6A	0.53	95%	0.81	0.88	5.0	2.2	4.1
A7	19.00	65%	0.45	0.59	18.3	27.5	60.6
A8	1.48	63%	0.56	0.70	13.9	3.0	6.3
A9	0.61	79%	0.73	0.83	8.7	1.9	3.7
A10	2.61	86%	0.79	0.88	7.9	9.2	17.3
A11	2.89	83%	0.76	0.86	8.7	9.5	18.1
A12	3.87	8%	0.13	0.38	11.9	1.9	9.5
A13	9.65	65%	0.45	0.59	14.0	15.7	34.6
A14	11.76	55%	0.39	0.55	15.3	16.0	37.9
A15	2.91	54%	0.52	0.68	14.9	5.4	11.7
A16	2.34	56%	0.54	0.69	14.7	4.4	9.6
A17	1.76	24%	0.21	0.44	13.7	1.4	4.7
A18	5.27	21%	0.24	0.47	16.4	4.3	14.0
A19	31.85	67%	0.45	0.59	25.8	38.8	85.4
A20	1.83	89%	0.81	0.89	8.0	6.6	12.2
A21	1.93	90%	0.82	0.90	8.7	6.8	12.6
A22	8.68	5%	0.11	0.37	23.3	2.7	15.4
B1	2.98	100%	0.90	0.96	17.6	8.8	15.8
B2	3.89	100%	0.90	0.96	17.6	11.5	20.6
B3	2.05	100%	0.90	0.96	9.4	7.8	14.0
B4	1.94	100%	0.90	0.96	9.4	7.4	13.2
B5	2.91	5%	0.08	0.35	13.1	0.9	6.4
C1	8.01	95%	0.81	0.88	9.9	2.0	15.0
C2	5.06	95%	0.81	0.88	7.9	1.4	10.0
OS20	308.00	9%	0.13	0.40	68.9	61.0	310.0
OS21A	20.26	12%	0.13	0.40	53.5	4.2	21.9
OS21B	8.71	12%	0.13	0.40	24.5	3.1	16.3
OS2	17.00	70%	0.49	0.62	36.0	13.8	39.1
OS3	28.70	70%	0.49	0.62	52.6	17.6	48.9
OS4	5.08	15%	0.20	0.40	29.5	2.6	8.5

- LEGEND:**
- PROPOSED STORM SEWER
  - 5000 FUTURE RD MAJOR CONTOUR
  - 5000 FUTURE RD MINOR CONTOUR
  - PROPOSED MAJOR CONTOUR
  - PROPOSED MINOR CONTOUR
  - 5000 EXISTING MAJOR CONTOUR
  - EXISTING MINOR CONTOUR
  - DRAINAGE BASIN
  - A  
○ B  
○ C  
○ D
  - △ DESIGN POINT
  - HP HIGH POINT
  - LP LOW POINT
  - DRAINAGE ARROW
  - ← EXISTING DRAINAGE ARROW
  - PROPOSED DRAINAGE SWALE

DRAINAGE MAP  
 STERLING RANCH FILING 2  
 JOB NO. 25188.01  
 4/16/21  
 SHEET 1 OF 6

**J-R ENGINEERING**  
 A Westrian Company

Centennial 303-740-9393 • Colorado Springs 719-593-2593  
 Fort Collins 970-491-9888 • www.jrengineering.com

RAO INVESTMENTS, LLC  
 5300000709


ORIGINAL SCALE: 1" = 70'

## **Appendix E**

### **Drainage Maps**




# STERLING RANCH PHASE 2 EXISTING DRAINAGE MAP



### LEGEND


BASIN ID  
 A: BASIN LABEL  
 B: AREA  
 C: C -100 YR  
 D: C-5 YR



DESIGN POINT



EXISTING FLOW DIRECTION



BASIN DRAINAGE AREA




EXISTING STORM SEWER




SITE BOUNDARY




EXISTING PROPERTY LINE




ROW EXISTING




FL EXISTING




SIDEWALK EXISTING



DRAINAGE ACCESS & MAINTENANCE  
 EASEMENT



EXISTING



**BASIN SUMMARY TABLE**


Tributary Sub-basin	Area (acres)	Percent Impervious	C <sub>s</sub>	C <sub>100</sub>	t <sub>c</sub> (min)	Q <sub>s</sub> (cfs)	Q <sub>100</sub> (cfs)
A1	5.17	2%	0.08	0.35	27.4	1.1	8.0
A2	27.48	0%	0.08	0.35	39.1	4.6	33.6
A3	11.68	0%	0.08	0.35	19.5	2.9	21.5
B1	11.78	0%	0.08	0.35	25.2	2.6	19.0
OS1	9.27	37%	0.40	0.55	23.7	10.5	24.4
OS2	5.00	100%	0.90	0.96	14.2	6.3	11.2
OS3	2.36	100%	0.90	0.96	12.2	8.1	14.6
OS4	11.71	4%	0.10	0.36	32.4	2.8	16.9
OS5	3.46	0%	0.08	0.35	30.4	0.7	5.0
OS6	18.38	11%	0.54	0.66	14.8	35.4	72.2
OS7	33.07	19%	0.28	0.48	34.7	20.6	60.4

**DESIGN POINT**

DP	Q <sub>5</sub>	Q <sub>100</sub>
	Total	Total
1	1.1	8.0
2	4.6	33.6
3	10.5	24.4
4	0.7	5.0
6	2.6	19.0
7	6.3	11.2
8	8.1	14.6
9	2.8	16.9
10	35.4	72.2
11	20.6	60.4
5	2.9	21.5
5.1	62.7	168.9

### TITLE

EXISTING GRADING ASSUMES FILING 2, STERLING RANCH ROAD, & MARKSHEFFEL ROAD ARE BUILT.




STERLING RANCH PHASE 2  
 EXISTING DRAINAGE MAP  
 JOB NO. 25188.02  
 04/26/21  
 SHEET 1 OF 1



Centennial 303-740-9393 • Colorado Springs 719-593-2593  
 Fort Collins 970-491-9888 • www.jrengineering.com

# STERLING RANCH PHASE 2 PROPOSED DRAINAGE MAP



## LEGEND

- BASIN ID  
A: BASIN LABEL  
B: AREA  
C: C-100 YR  
D: C-5 YR
- DESIGN POINT  
PROPOSED FLOW DIRECTION
- BASIN DRAINAGE AREA
- EXISTING STORM SEWER
- STORM SEWER PROPOSED
- PROPOSED R.O.W
- PROPOSED PROPERTY LINES
- PROPOSED SIDEWALK
- EXISTING PROPERTY LINE
- ROW EXISTING
- FL EXISTING
- SIDEWALK EXISTING
- DRAINAGE ACCESS & MAINTENANCE EASEMENT




DP	Q5		Q100				
	Total	Total	Total	Total			
1	20.6	60.4					
2	20.5	40.5					
3	34.8	88.5					
4	35.4	72.2					
5	12.0	25.9					
6	5.5	11.4					
6.1	17.0	36.4					
7	2.2	9.9					
7.1	52.0	113.1					
8	4.6	10.2					
9	3.5	7.3					
10	2.3	5.6					
11	0.7	1.7					
11.1	2.8	6.8					
12	9.1	18.7					
13	6.2	12.0					
13.1	15.0	30.3					
14	0.8	2.2					
14.1	16.1	34.1					
15	8.1	17.4					
15.1	21.8	43.9					
16	1.4	2.9					
16.1	22.7	45.6					
17	2.0	8.5					
18.1	24.2	53.1					
19	15.3	31.4					
20	6.8	14.6					
20.1	37.9	74.7					
21	7.5	21.7					
22	5.7	17.2					
22.1	12.9	37.9					
23	48.6	107.2					
24	2.2	9.1					
25	0.7	3.5					
27	2.4	8.0					
D1	0.42	1.13					
D2	3.67	10.5					
OS6	18.38	54.4	0.54	0.66	14.8	35.4	72.2
OS4	11.71	56.6	0.57	0.68	20.5	20.5	40.5
OS7	1.9	10.3	0.28	0.48	34.7	20.6	60.4



## BASIN SUMMARY TABLE

Tributary Sub-basin	Area (acres)	Percent Impervious	C <sub>s</sub>	C <sub>100</sub>	t <sub>c</sub> (min)	Q <sub>s</sub> (cfs)	Q <sub>100</sub> (cfs)
A1	4.31	64%	0.49	0.64	12.5	8.1	17.4
A2	1.41	31%	0.30	0.50	16.3	1.4	4.0
A3	3.68	65%	0.50	0.64	13.2	6.8	14.6
A4	3.94	52%	0.42	0.58	15.4	5.7	13.4
A5	0.45	78%	0.62	0.73	5.0	1.4	2.9
A6	7.60	73%	0.55	0.68	13.9	15.3	31.4
A7	1.43	75%	0.58	0.70	13.7	3.0	6.1
A8	4.22	13%	0.16	0.41	18.9	2.2	9.1
A9	2.02	8%	0.13	0.39	25.8	0.7	3.5
A10	3.23	24%	0.23	0.45	17.6	2.4	8.0
B1	2.44	80%	0.64	0.75	11.4	6.2	12.0
B2	4.33	73%	0.55	0.67	12.2	9.1	18.7
C1	2.62	69%	0.54	0.67	11.9	5.5	11.4
C2	6.74	63%	0.49	0.63	14.1	12.0	25.9
C3	3.77	10%	0.14	0.39	11.3	2.2	9.9
A9	2.02	8%	0.13	0.39	25.8	0.7	3.5
B5	0.45	51%	0.37	0.54	8.8	0.7	1.7
B4	1.80	51%	0.38	0.55	16.2	2.3	5.6
B3	2.36	61%	0.57	0.72	27.9	3.5	7.3
C4	3.79	55%	0.49	0.65	30.3	4.6	10.2
D1	0.42	12%	0.17	0.42	9.2	0.3	1.3
D2	3.67	5%	0.12	0.38	7.8	1.9	10.5
OS6	18.38	54%	0.54	0.66	14.8	35.4	72.2
OS4	11.71	56%	0.57	0.68	20.5	20.5	40.5
OS7	1.9	10.3	0.28	0.48	34.7	20.6	60.4



SECTION AA  
OVERFLOW DITCH CROSS SECTION

OVERFLOW = 84.4 CFS  
VELOCITY = 8.66 FT/S  
SHEAR STRESS = 4.05 LB/FT<sup>2</sup>

STERLING RANCH PHASE 2  
PROPOSED DRAINAGE MAP  
JOB NO. 25188.00  
04/27/21  
SHEET 1 OF 2



Centennial 303-740-9393 • Colorado Springs 719-593-2593  
Fort Collins 970-491-9888 • www.jrengineering.com


SEE SHEET 2



# STERLING RANCH PHASE 2 PROPOSED DRAINAGE MAP

## LEGEND

BASIN ID  
A: BASIN LABEL  
B: AREA  
C: C - 100 YR  
D: C - 5 YR



DESIGN POINT



PROPOSED FLOW DIRECTION



BASIN DRAINAGE AREA




EXISTING STORM SEWER




STORM SEWER PROPOSED




PROPOSED R.O.W




PROPOSED PROPERTY LINES




PROPOSED SIDEWALK




EXISTING PROPERTY LINE



ROW EXISTING



FL EXISTING




SIDEWALK EXISTING






DRAINAGE ACCESS & MAINTENANCE EASEMENT



EXISTING



PROPOSED




STERLING RANCH PHASE 2  
PROPOSED DRAINAGE MAP  
JOB NO. 25188.00  
04/27/21  
SHEET 2 OF 2

**J-R ENGINEERING**  
A Westrian Company

Centennial 303-740-9393 • Colorado Springs 719-593-2593  
Fort Collins 970-491-9888 • www.jrengineering.com

# STERLING RANCH PHASE 2 INTERIM - PROPOSED DRAINAGE MAP



**LEGEND**

BASIN ID  
 A: BASIN LABEL  
 B: AREA  
 C: C - 100 YR  
 D: C - 5 YR

DESIGN POINT  
 PROPOSED FLOW DIRECTION

BASIN DRAINAGE AREA  
 EXISTING STORM SEWER  
 STORM SEWER PROPOSED  
 PROPOSED R.O.W  
 PROPOSED PROPERTY LINES  
 PROPOSED SIDEWALK  
 EXISTING PROPERTY LINE  
 ROW EXISTING  
 FL EXISTING  
 SIDEWALK EXISTING  
 DRAINAGE ACCESS & MAINTENANCE EASEMENT

EXISTING      PROPOSED


6100      6100

**BASIN SUMMARY TABLE**

Tributary Sub-basin	Area (acres)	Percent Impervious	C <sub>s</sub>	C <sub>100</sub>	t <sub>c</sub> (min)	Q <sub>5</sub> (cfs)	Q <sub>100</sub> (cfs)
I1	21.99	1%	0.08	0.35	31.9	4.4	31.2
I2	3.47	0%	0.08	0.35	31.1	0.7	4.9

**DESIGN POINT**

DP	Q5		Q100	
	Total	Total	Total	Total
I1	4.4	31.2		
I1.1	22.1	68.4		
I2	0.7	4.9		



STERLING RANCH PHASE 2  
 INTERIM CONDITION DRAINAGE MAP  
 JOB NO. 25188.00  
 10/01/20  
 SHEET 1 OF 1



Centennial 303-740-9393 • Colorado Springs 719-593-2593  
 Fort Collins 970-491-9888 • www.jrengineering.com