



El Paso County Conservation District

5610 Industrial Place, Ste 100, Colorado Springs, CO 80916, Phone (719)600-4706

EPCDistrict@yahoo.com

<http://www.EPCCD.org>

Board of Supervisors

Kenneth Barker, President
John Eastlake, Vice President
Katie Miller, Secretary/Treasurer

Daniel Bush, Supervisor
Roger Rasner, Supervisor
Pamela Davison, District Manager

Copart Special Use

Topsoil should be stripped to a depth of 6 inches and all stock piles should have side slopes no steeper than 3:1 and seeded. All disturbed areas should be seeded and mulched with weed free hay mulch at 4,000 lbs. /acre. All disturbed areas should be reseeded between the planting dates of Nov. 1-April 30th. Grass seed should be drilled at a depth of ¼ to ½ inch deep. Your plan mentioned using a native seed mix but it appears just for ornamental planting only. Your soils in the disturbed area is a Sandy Foothill range site. Please utilize the attached El Paso County CD Native Shotgun mix and recommended seed rates that was developed and approved by a NRCS Rangeland Management Specialist for best results for your site.

Silt fences or other forms of erosion barriers should be planned and need to be installed as a temporary sediment control device used on construction sites to protect water quality.

Noxious weeds are a major resource concern for the El Paso County Conservation District and weeds need to be managed and controlled prior to going to seed either by chemical, mechanical, or biological control. Please contact the El Paso County Conservation District for fact sheets on specific weed control measures for each noxious weed present on the site.

Vehicle tracking control stations need to be installed at all entrance and exit points on the site. The station should consist of a pad of 3 to 6-inch rock or a vehicle control pad/mat to strip mud from tires prior to vehicles leaving the construction site to prevent spreading of noxious weeds.

Kenneth Barker

EPCCD Board President
Kenneth Barker