



Master Development Drainage Plan and  
Preliminary Drainage Report

**Peerless Farms**  
**16975 Falcon Hwy**  
**Peyton, CO 80831**

Prepared for (Owner):  
**Robert S Williams**  
**4075 Golf Club Dr.**  
**Colorado Springs CO, 80922**  
**Contact: Robert S Williams**  
**(460) 438-1874**


Prepared by:  
**Kimley-Horn and Associates, Inc.**  
**2 North Nevada Avenue, Suite 300**  
**Colorado Springs, Colorado 80903**  
**Contact: Mitchell Hess, P.E.**  
**(719) 453-0180**

Project #: 19611400

PCD File No. SP-21-7

Prepared: June 15th, 2023

**Kimley»Horn**



**CERTIFICATION**

***ENGINEERS STATEMENT***

The attached drainage plan and report were prepared under my direction and supervision and are correct to the best of my knowledge and belief. Said drainage report has been prepared according to the criteria established by the County for drainage reports and said report is in conformity with the applicable master plan of the drainage basin. I accept responsibility for any liability caused by any negligent acts, errors or omissions on my part in preparing this report.

SIGNATURE (Affix Seal): \_\_\_\_\_  
Mitchell Hess, Colorado P.E. No. 53916 Date

***DEVELOPER'S STATEMENT***

I, the owner/developer have read and will comply with all of the requirements specified in this drainage report and plan.

\_\_\_\_\_  
Name of Developer

\_\_\_\_\_  
Authorized Signature Date

\_\_\_\_\_  
Printed Name

\_\_\_\_\_  
Title

\_\_\_\_\_  
Address:

***EL PASO COUNTY***

Please revise to  
"Joshua Palmer,  
P.E."

Filed in accordance with the requirements of the Drainage Criteria Manual, Volumes 1 and 2, El Paso County Engineering Criteria Manual and Land Development Code as amended.

\_\_\_\_\_  
Jennifer Irvine, P.E.  
County Engineer / ECM Administrator

\_\_\_\_\_  
Date

Conditions:

**TABLE OF CONTENTS**

**CERTIFICATION ..... 1**

ENGINEERS STATEMENT ..... 1

DEVELOPER’S STATEMENT ..... 1

EL PASO COUNTY..... 1

**INTRODUCTION ..... 4**

PURPOSE AND SCOPE OF STUDY..... 4

GENERAL PROJECT DESCRIPTION ..... 4

**PROJECT CHARACTERISTICS ..... 4**

DRAINAGE BASIN PLANNING STUDY INFRASTRUCTURE AND ANALYSIS ..... 5

SOILS CONDITIONS ..... 5

**DRAINAGE DESIGN CRITERIA..... 5**

REGULATIONS ..... 5

DEVELOPMENT DESIGN CRITERIA REFERENCE AND CONSTRAINTS ..... 5

HYDROLOGIC CRITERIA..... 5

HYDRAULIC CRITERIA ..... 5

VARIANCES FROM CRITERIA ..... 6

**EXISTING DRAINAGE CONDITIONS ..... 6**

EXISTING DRAINAGE BASIN ..... 6

*Sub-Basin EX1* ..... 6

*Sub-Basin EX2* ..... 6

*Sub-Basin EX3*..... 6

**PROPOSED DRAINAGE CONDITIONS..... 6**

*Sub-Basin 1*..... 6

*Sub-Basin 2*..... 6

*Sub-Basin 3*..... 7

*Sub-Basin 4*..... 7

*Sub-Basin 5*..... 7

*Sub-Basin 6*..... 7

*Sub-Basin 7*..... 7

*Sub-Basin EX3*..... 7

CONFORMANCE WITH THE DBPS ..... 8

EMERGENCY OVERFLOW ROUTING ..... 8

HYDRAULIC ANALYSIS METHODOLOGY..... 8

*Four-Step Process*..... 8

WATER QUALITY AND DETENTION REQUIREMENTS ..... 9

**EROSION CONTROL PLAN ..... 10**

**FLOODPLAIN STATEMENT ..... 10**

**FEES DEVELOPMENT ..... 10**

APPLICABLE FEES..... 10

CONSTRUCTION COST OPINION..... 10

MAINTENANCE AND OPERATIONS..... 10

GROUNDWATER CONSIDERATIONS ..... 11

**SUMMARY .....11**  
    COMPLIANCE WITH STANDARDS.....11

**REFERENCES .....12**

**APPENDIX .....13**  
APPENDIX A – VICINITY MAP  
APPENDIX B – SOILS MAP AND FEMA FIRM PANEL  
APPENDIX C – HYDROLOGIC CALCULATIONS  
APPENDIX D – HYDRAULIC CALCULATIONS  
APPENDIX E – EOPCC  
APPENDIX F – UNNAMED DRAINAGEWAY PHOTOGRAPHS  
APPENDIX G – EXCERPTS FROM THE DBPS  
APPENDIX H – DRAINAGE EXHIBITS

## INTRODUCTION

### **PURPOSE AND SCOPE OF STUDY**

The purpose of this final drainage report is to outline the drainage facilities for 16975 Falcon Hwy Peyton, CO (the “Property”), El Paso County, Colorado (the “County”). This final drainage report identifies drainage patterns and infrastructure for the Site and proposes to safely route storm water to adequate outfalls. The Property is 40 acres in size.

The Property is located in the Haegler Ranch major drainage basin and is tributary to Black Squirrel Creek. The Site is discussed in the *Haegler Ranch Basin Drainage Basin Planning Study*, dated May 2009 and prepared by URS (“DBPS”).

### **GENERAL PROJECT DESCRIPTION**

The project improvements consist of the construction of a single public road (60’ ROW), two private driveways, and private utilities (the “Project”) within the Property (the “Site”). The Project will be processed through El Paso County.

The Project is located in a portion of the northwest quarter of Section 13, Township 13 south, Range 64 west of the 6th P.M., County of El Paso, State of Colorado (see Vicinity Map in Appendix A). More specifically, the site is located at 16975 Falcon Hwy Peyton, CO 80831. The Property is bounded by Falcon Hwy to the north, privately owned pastures to the west and south, and Sagecreek South Filing No. 1 to the east. The Property is mostly vacant but contains two single family houses, one large barn and some small chicken coops and sheds. The Site is to be replatted as 7 individual lots approximately 5-6 acres each with two private driveways connected to a public access road branching from Falcon Hwy. Stormwater will ultimately outfall to Black Squirrel Creek after initially discharging into an unnamed vegetated creek along the western portion of the Property.

A field survey was completed by Centennial Surveying, dated January 2021, and is the basis for design for the drainage improvements.

## PROJECT CHARACTERISTICS

The Project Site is 40 acres in size. The Project involves the construction of a public road with two private driveways, roadside ditches, and culverts. The Site will be subdivided into large-lot residential lots for future single-family residences. The proposed impervious area consists of 0.66 acres for the public/paved roadway in addition to any future single-family residences constructed as part of the development.

The existing Project Site generally slopes from east to west as well as from the southeast to the north at grades of approximately 1.5 – 3.5%. The historical drainage patterns will be generally maintained. The Site consists of two single-family homes, a large barn and some small chicken coops and sheds. The Site does not have any existing stormwater infrastructure with the exception of a 24” culvert beneath Falcon Highway that allows the unnamed drainageway to drain from the north side of Falcon Highway to the Site.

## ***DRAINAGE BASIN PLANNING STUDY INFRASTRUCTURE AND ANALYSIS***

The Project Site is contained within the Haegler Ranch Basin and is discussed within the DBPS. Haegler Ranch Drainage Basin consists of 16.6 square miles in unincorporated El Paso County. The basin mostly consists of residential lots greater than 2-acres in size and large agricultural parcels. According to the DBPS, "...the subregional detention alternative is preferred and recommended for implementation" as the drainage basin continues to develop and more dense zoning uses are developed. The DBPS does not recommend that a subregional detention basin be constructed on the subject Site. The DBPS recommends that the existing storm drain culvert that is beneath Falcon Highway which discharges stormwater onto the property be upsized to a 66" RCP Culvert. As no improvements are proposed for Falcon Highway, this culvert will not be upsized as part of this Project.

## ***SOILS CONDITIONS***

NRCS soil data is available for this Site and it has been noted that onsite soils are primarily USCS Type A. The NRCS Soils map has been provided in Appendix B.

## ***DRAINAGE DESIGN CRITERIA***

### ***REGULATIONS***

The proposed development does not propose any deviations from The City of Colorado Springs/El Paso County Drainage Criteria Manual, dated October 12, 1994 or any subsequent revisions.

### ***DEVELOPMENT DESIGN CRITERIA REFERENCE AND CONSTRAINTS***

The custom Flood Insurance Rate Map (FIRM) map listed in Appendix B shows the western portion of the Site to be located inside the 100-year flood plain. The proposed private storm facilities follow The City of Colorado Springs/El Paso County Drainage Criteria Manual (the "CRITERIA"), El Paso County Engineering Criteria Manual (the "ECM), and the Urban Storm Drainage Criteria Manual (the "MANUAL"). Site drainage is not significantly impacted by constraints such as utilities or existing development. Further detail regarding onsite drainage patterns has been provided in the Proposed Drainage Conditions Section.

### ***HYDROLOGIC CRITERIA***

The 5-year and 100-year design storm events were used in determining rainfall and runoff for the proposed drainage system per Chapter 6 of the CRITERIA. Table 6-2 of the CRITERIA is the source for rainfall data for the 5-year and 100-year design storm events. Design runoff was calculated using the Rational Method for developed conditions as established in the CRITERIA and MANUAL. Runoff coefficients for the proposed development were determined using Table 6-6 of the CRITERIA by calculating weighted impervious values for each specific site sub-basin.

### ***HYDRAULIC CRITERIA***

The proposed drainage facilities are designed in accordance with the CRITERIA and MANUAL. Floodplain identification was determined using a custom FIRMette map by FEMA and information provided in the CRITERIA. Results of hydraulic calculations are summarized in Appendix D.

## VARIANCES FROM CRITERIA

Due to existing grades and to match the historical flows presented at the Site, some drainage will be directed back to the county ROW. This is an existing condition. Besides this condition, no variances from the CRITERIA have been proposed for this development.

### EXISTING DRAINAGE CONDITION

#### EXISTING DRAINAGE BASIN

##### Sub-Basin EX1

Sub-basin EX1 is 35.36 acres with a basin impervious value of 2% and consists of agricultural fields, gravel driveways, single-family residences and multiple agricultural barns and sheds. The existing runoff within this sub-basin drains directly to the unnamed drainageway. Runoff during the 5-year and 100-year storm events is anticipated to be 5.99 and 38.94 cfs respectively.

##### Sub-Basin EX2

Sub-basin EX2 is 4.64 acres with a basin impervious value of 4% and consists of agricultural fields, gravel driveways and a portion of an agricultural barn. The existing runoff within this sub-basin drains to an existing roadside ditch within Sub-Basin EX3 before flowing into the unnamed drainageway. Runoff during the 5-year and 100-year storm events is anticipated to be 1.03 and 6.07 cfs respectively.

##### Sub-Basin EX3

Sub-Basin EX3 consists of a portion of the northern property frontage within the ROW that drains to the property. Sub-Basin EX3 is 2.63 acres with a basin impervious value of 27% and 5-year and 100-year storm event direct runoff values of 2.18 and 7.47 cfs respectively. Stormwater runoff within Sub-Basin EX2 will continue to follow its historical path.

### PROPOSED DRAINAGE CONDITIONS

The developed runoff from the Project will generally be collected by means of roadside ditches located adjacent to the proposed public road and private gravel driveways. The runoff collected in the roadside ditches will be conveyed to the unnamed drainageway, following historical runoff patterns. **The Property has been divided into 2 sub-basins, Sub-Basin 1 and Sub-Basin EX2.** The proposed conditions map is provided in Appendix H.

##### Sub-Basin 1

Sub-basin 1 is 29.06 acres with a basin impervious value of 10% and consists of the unnamed drainageway as well as future single-family residential lots. The runoff developed within this sub-basin drains directly to the unnamed drainageway. Developed runoff during the 5-year and 100-year storm events will be 9.03 and 39.34 cfs respectively. Stormwater runoff within Sub-Basin 1 will continue to generally follow its historical path.

##### Sub-Basin 2

Sub-basin 2 is 1.78 acres with a basin impervious value of 17% and consists primarily of a portion of a gravel driveway and driveway drainage ditch. The runoff developed within this sub-basin will be collected within a proposed driveway ditch before flowing into the unnamed drainageway.

Unresolved Review 1 Comment:

- The report is missing a discussion of off-site flows. Please elaborate discussion to account for offsite flows. Refer to Sagecreek South Drainage (SF85026) Map for off-site flows.

EX3

Please revise statement since the property has been divided into more than 2 basins.

Provide channel (ditch) calculations and sizing specifications.

Discuss the combined flow from sub-basin 3 and provide identify total flows.

Developed runoff during the 5-year and 100-year storm events will be 0.87 and 3.24 cfs respectively. Stormwater runoff within Sub-Basin 2 will continue to generally follow its historical path.

**Sub-Basin 3**

Sub-basin 3 is 0.78 acres with a basin impervious value of 31% and consists primarily of a portion of a gravel driveway and driveway drainage ditch. The runoff developed within this sub-basin will be collected within a proposed driveway ditch before flowing into a drainage ditch within Sub-Basin 2 and being routed to the unnamed drainageway. Developed runoff during the 5-year and 100-year storm events will be 0.86 and 2.48 cfs respectively. Stormwater runoff within Sub-Basin 3 will continue to generally follow its historical path.

**Sub-Basin 4**

Sub-basin 4 is 0.42 acres with a basin impervious value of 57% and consists of a portion of the proposed public road. The runoff developed within this sub-basin will be collected within a proposed roadside ditch before flowing into a driveway ditch within Sub-Basin 6 and being routed to the unnamed drainageway. Developed runoff during the 5-year and 100-year storm events will be 1.03 and 2.21 cfs respectively. Stormwater runoff within Sub-Basin 4 will continue to generally follow its historical path.

Please revise/elaborate direction of flow for sub-basin 4. It appears flows would go towards EX3.

**Sub-Basin 5**

Sub-basin 5 is 0.85 acres with a basin impervious value of 40% and consists of a portion of the proposed public road, a portion of a gravel driveway and a driveway ditch. The runoff developed within this sub-basin will be collected within proposed roadside and driveway ditches before flowing into a drainage ditch within Sub-Basin 6 and being routed to the unnamed drainageway. Developed runoff during the 5-year and 100-year storm events will be 1.12 and 2.84 cfs respectively. Stormwater runoff within Sub-Basin 5 will continue to generally follow its historical path.

Basins do not include any proposed public road. Please remove

**Sub-Basin 6**


Sub-basin 6 is 5.55 acres with a basin impervious value of 13% and consists of a portion of the proposed public road, a portion of a gravel driveway, a driveway ditch and future single-family lots. The runoff developed within this sub-basin will be collected within proposed roadside and driveway ditches before flowing into the unnamed drainageway. Developed runoff during the 5-year and 100-year storm events will be 2.32 and 9.26 cfs respectively. Stormwater runoff within Sub-Basin 6 will continue to generally follow its historical path.

**Sub-Basin 7**

Sub-basin 7 is 1.57 acres with a basin impervious value of 6% and consists of a portion of the proposed public road, roadside ditches and a future single-family lot. The runoff developed within this sub-basin will be collected within an existing roadside ditch within Sub-Basin EX3 before flowing into the unnamed drainageway. Developed runoff during the 5-year and 100-year storm events will be 0.54 and 2.77 cfs respectively. Stormwater runoff within Sub-Basin 7 will continue to follow its historical path.

**Sub-Basin EX3**

Sub-Basin EX3 consists of a portion of the northern property frontage within the ROW that drains to the property. Sub-Basin EX3 is 2.63 acres with a basin impervious value of 27% and 5-year and 100-year storm event direct runoff values of 2.18 and 7.47 cfs respectively. Stormwater runoff within Sub-Basin EX2 will continue to follow its historical path.



The report indicates runoff from other sub-basins will flow into EX3. Discuss how sub-basin EX3's flows are remaining the same in existing and proposed conditions.

orn



Under drainage fees, lists %impervious for the site as being 12%. Revise so % impervious is consistent throughout report.

Please discuss where these values are obtained. The map summary table has 15.77 and 62.14 cfs.

**CONFORMANCE WITH THE DBPS**

The proposed Project includes single-family lots which are all greater than 5-acres in size. The impervious value of 7% was used for the total site (see ECM, Appendix L – Drainage Criteria Manual 1 Addendum Table 3-1). The 5-year and 100-year storm event direct runoff for the site will be 2.07 and 19.06 cfs respectively. The proposed development is in general conformance with the DBPS and will not negatively affect downstream drainage.

**EMERGENCY OVERFLOW ROUTING**

All overflow routing will be directed to the existing unnamed drainageway that is located on the western side of the site. This flow path matches the historical stormwater runoff path.

**HYDRAULIC ANALYSIS METHODOLOGY**

The proposed drainage facilities were designed in accordance with the CRITERIA and MANUAL. Floodplain identification was determined using a custom FIRMette map by FEMA and information provided in the CRITERIA. Apart from road culverts, no underground storm drain pipes as proposed for the development. Culvert sizing calculations were computed using Flow master and are included in Appendix D. There are no proposed variances from the City of Colorado Springs/El Paso County Criteria for the proposed development.

No inlets have been proposed as part of the Project. Stormwater runoff will be routed above ground through roadside ditches and culverts beneath the public roadway and private driveways.

**Four-Step Process**

The Site was designed in accordance with the four-step process to minimize adverse impacts of urbanization, as outlined in Section I.7.2 BMP Selection of the CRITERIA. The four-step process per the CRITERIA provides guidance and requirements for the selection of siting of structural Best Management Practices (BMPs) for new development and significant redevelopment.

**Step 1: Employ Runoff Reduction Practices**

Currently the site is mostly vacant land. Development of the site will increase current runoff conditions due to increased imperviousness values. The increase in impervious area is minimal though due to the Site size of 40-acres and the proposed large residential lot sizes.

As discussed in Section I.7.1B of Appendix I of the ECM, water-quality facilities are not required for the Project as the development consists of 5-acre residential lots. Water quality treatment will be provided for the Proposed Public ROW though through means of runoff reduction. Stormwater within the Public ROW will drain to vegetated roadside ditches which will promote stormwater infiltration. A 94% WQVC reduction will be achieved to accomplish the requirements of the 60% Runoff Reduction Standard as outlined by the County’s MS4. Calculations showing the runoff reduction amounts have been included in Appendix C.

The Site was designed to conserve as much of the existing vegetation as possible and to minimize the extent of paved areas. Additionally, the Site was designed to eliminate underground storm drains and storm drain culverts will only be used to route water beneath the public road and private driveways, allowing more opportunities for stormwater to infiltrate into the ground.

**Step 2: Stabilize Drainageways**

An existing unnamed drainageway flows through the western portion of the Site. During a Site visit, it was found that the drainageway is currently well-stabilized and extremely vegetated. Site visit photos of the drainageway have been included in Appendix F. As the drainageway

is currently stable and the development of the large-lot subdivision will only minimally increase the stormwater runoff it has been determined that leaving the unnamed drainageway as-is, currently stabilized and vegetated, will allow the channel to remain stabilized. As discussed in the DBPS, “The disturbance of the native vegetation and failure to properly revegetate areas impacted by site development, utility, roadway and landscape construction activities have in some cases negatively affected downstream areas.” Furthermore, as noted in Chapter 1, Section 1.4 of the CRITERIA, “Natural channel systems, primarily the designated Major Drainageways and Primary outfalls, serve to store flood waters, enhance water quality, provide for ground water recharge and preserve riparian corridors. The use of historical channels to convey storm water runoff from developed and developing areas is acceptable. However, if historical storm water flows are increased, or if historical channels are unstable in their natural conditions, these channels must be adequately stabilized to prevent excessive erosion.” Additionally, Chapter 2, Section 2.2 of the CRITERIA states, “A stable natural channel reaches ‘equilibrium’ over many years. Therefore, channel modifications should be minimal.” Because the existing drainageway is properly stabilized, it is felt that attempts to change the natural channel may lead to destabilization of the drainageway and therefore, no changes to the unnamed drainageway, with the exception of stabilization at the location of the proposed ditches, are recommended.

increased by  
(%) from  
itions.  
e channel, at  
will need to be  
now the  
e channel with  
oposed flows.

provide riprap  
outlet  
protection  
calcs.

The proposed Project involves construction of roadside ditches which will discharge into the unnamed drainageway. To reduce the opportunity for erosion where the ditches outfall, riprap will be added to dissipate energy from stormwater runoff.

IF the gravel drives are to remain driveways: add that the portion of the driveway that falls within the property line must be included as part of the 10% impervious area on the lot.

### Step 3: Provide Water Quality Capture Volume (WQCV)

The proposed Project development includes large-lot single-family lots which include minimal impervious areas. The single-family lots will be restricted to a maximum impervious value of 10% per lot. As discussed above in Step 1, the residential lots are exempt from WQCV requirements and the Public ROW will meet County MS4 requirements by using runoff reduction methods which will meet the 60% runoff reduction standard.

See Planner's  
comment on the  
Prelim. Plan.

### Step 4: Consider Need for Industrial and Commercial BMPs

IF the gravel drives are roadways, they will need WQ.

The proposed Project consists of a single-family subdivision. No industrial and commercial uses or developments are anticipated as part of the proposed development.

## WATER QUALITY AND DETENTION REQUIREMENTS

The proposed Project development includes large-lot single-family lots which include minimal impervious areas. As discussed above in Step 1 of the Four-Step Process, the residential lots are exempt from WQCV requirements and the Public ROW will meet County MS4 requirements by using runoff reduction methods which will meet the 60% runoff reduction standard.

The Project does not include a proposed detention pond for this development. Large-Lot Residential Developments, especially those in excess of 5-acre lots, do not increase post-development stormwater flows as substantially as smaller-lot residential and non-residential developments. Stormwater flows collected from this development will drain to the existing unnamed drainageway. As documented in the DBPS, the unnamed drainageway is made up of the combination of the T3-02 and T4 Tributaries which both cross Falcon Highway using corrugated metal pipes known as Facility Numbers 609 and 610. The proposed 100-year flows for these tributaries at these locations are 460 cfs and 570 cfs respectively. Therefore, the unnamed drainageway is expected to have proposed 100-year storm event flows of 1,030 cfs.

by  
be  
lysis  
rom  
s  
f a  
ty, Fr  
ns  
d

The Project currently contributes 7.02 cfs and 45.01 cfs to the unnamed drainageway during the 5-year and 100-year storm events respectively, and it is proposed that 15.77 cfs and 62.14 cfs

will discharge to the unnamed drainageway in the redeveloped condition and during the 5-year and 100-year storm events respectively. The existing stormwater flows for the Site account for 4.37% of the total flows in the unnamed drainageway. The proposed stormwater flows for the Site will account for 6.03% of the total flows in the unnamed drainageway which results in a difference of 1.66%.

Due to the minimal increase of stormwater flows caused by the redevelopment, the large 5-acre and larger residential lot configuration, the recommendations of the DBPS for regional detention ponds as opposed to private onsite detention and the negligible impact to the unnamed drainageway, no stormwater detention has been proposed for this Project.

## **EROSION CONTROL PLAN**

Erosion Control Plans will be submitted separately as a standalone construction document.

## **FLOODPLAIN STATEMENT**

The western portion of the Site is within Area AE, special flood hazard areas with base flood elevations and Zone X, 0.2% annual chance flood hazard, areas of 1% annual chance flood with average depth less than one foot or with drainage areas of less than one square mile.

The remaining portion of the Site is located outside of the 100-year floodplain as determined by the custom FIRMette map created on April 20, 2021 and contained with Appendix B.

## **FEES DEVELOPMENT**

### ***APPLICABLE FEES***

Drainage and Bridge Fees are required to be paid at the time of Final Plat recording for the Project. The Site is within the Haeger Drainage Basin. Drainage Fees are based on the number of impervious acres for the development. The 2023 Drainage and Bridge Fees are \$12,985 and \$1,916, respective, per impervious acre.

Total Acreage (40-acres) x Total Development (inclusive of Prop. Public ROW) Impervious Value (12%) = Impervious Acres (4.8)

Drainage Basins Fees = 4.8-acres x (\$12,985 + \$1,916) = \$71,524.80

25% Reduction for 5-acre lots


Final Fee = 0.75 x \$71,524.80 = **\$53,643.60**

### ***CONSTRUCTION COST OPINION***

An opinion of probable construction cost for the construction of the private drainage facilities for the Project has been included in Appendix E. There are no public drainage ponds or permanent control measures proposed as part of the Project.

### ***MAINTENANCE AND OPERATIONS***

No detention has been proposed as part of this Project. The public roadside ditches and culverts within the proposed Public ROW which provide water quality treatment will be maintained by El Paso County. Other proposed ditches, swales and culverts located outside of the proposed Public

 upon acceptance.

ROW will be maintained by property owners of the development. Easements will be provided over the shared driveways and ditches to allow all property owners the ability to access and maintain ditches and culverts as needed.

### **GROUNDWATER CONSIDERATIONS**

A Geotechnical Evaluation by RMG and dated 4/14/2021 was performed for the Site. According to the Geotechnical Evaluation, “Groundwater was encountered in all three test borings at depths ranging from between 11.0 feet to 18.0 feet below the existing ground surface at the time of boring. When checked five days subsequent to drilling, groundwater was encountered at depths ranging between 4.0 feet to 18.6 feet. Groundwater levels are anticipated to have sufficient separation from the bottom of proposed crawlspace and basement foundation components on Lots 2, 4, 6 and 7. Due to the shallow groundwater conditions encountered near the unnamed intermittent creek, the use of basements on Lots 1 and 5 may be limited. Groundwater conditions should be considered in the site-specific soils investigations and OWTS designs.”

### **SUMMARY**

#### **COMPLIANCE WITH STANDARDS**

The drainage design presented within this report for the Peerless Farms Large-Lot Single-Family Development conforms to the City of Colorado Springs/El Paso County Storm Drainage Criteria and the Urban Drainage and Flood Control District Manual. Additionally, the Site runoff and private storm sewer facilities will not adversely affect the downstream and surrounding developments or waterways. This report and its findings are consistent with the drainage requirements documented in the DBPS.

Discuss temporary sediment basins shown on the GEC plan and provide sizing calculations.

Discuss the amount of land disturbance for the proposed road and infrastructure.

## REFERENCES

1. The City of Colorado Springs Drainage Criteria Manual, May 2014
2. El Paso County Drainage Criteria Manual, Vol. 1 and 2, October 1994
3. Urban Drainage and Flood Control District Drainage Criteria Manual (UDFCDCM), Vol. 1, prepared by Wright-McLaughlin Engineers, June 2001, with latest revisions.
4. Flood Insurance Rate Map, El Paso County, Colorado and Incorporated Areas, Map Number 08041C0553G, Effective Date December 7, 2018, prepared by the Federal Emergency Management Agency (FEMA).
5. Haegler Ranch Basin Drainage Basin Planning Study. Prepared by URS, May 2009.
6. Geotechnical Evaluation prepared by RMG. April 14, 2021.

**APPENDIX**

***APPENDIX A - VICINITY MAP***






***APPENDIX B - SOILS MAP AND FEMA FIRM PANEL***



A product of the National Cooperative Soil Survey, a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local participants

# Custom Soil Resource Report for El Paso County Area, Colorado



# Preface

---

Soil surveys contain information that affects land use planning in survey areas. They highlight soil limitations that affect various land uses and provide information about the properties of the soils in the survey areas. Soil surveys are designed for many different users, including farmers, ranchers, foresters, agronomists, urban planners, community officials, engineers, developers, builders, and home buyers. Also, conservationists, teachers, students, and specialists in recreation, waste disposal, and pollution control can use the surveys to help them understand, protect, or enhance the environment.

Various land use regulations of Federal, State, and local governments may impose special restrictions on land use or land treatment. Soil surveys identify soil properties that are used in making various land use or land treatment decisions. The information is intended to help the land users identify and reduce the effects of soil limitations on various land uses. The landowner or user is responsible for identifying and complying with existing laws and regulations.

Although soil survey information can be used for general farm, local, and wider area planning, onsite investigation is needed to supplement this information in some cases. Examples include soil quality assessments (<http://www.nrcs.usda.gov/wps/portal/nrcs/main/soils/health/>) and certain conservation and engineering applications. For more detailed information, contact your local USDA Service Center (<https://offices.sc.egov.usda.gov/locator/app?agency=nrcs>) or your NRCS State Soil Scientist ([http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/contactus/?cid=nrcs142p2\\_053951](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/contactus/?cid=nrcs142p2_053951)).

Great differences in soil properties can occur within short distances. Some soils are seasonally wet or subject to flooding. Some are too unstable to be used as a foundation for buildings or roads. Clayey or wet soils are poorly suited to use as septic tank absorption fields. A high water table makes a soil poorly suited to basements or underground installations.

The National Cooperative Soil Survey is a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local agencies. The Natural Resources Conservation Service (NRCS) has leadership for the Federal part of the National Cooperative Soil Survey.

Information about soils is updated periodically. Updated information is available through the NRCS Web Soil Survey, the site for official soil survey information.

The U.S. Department of Agriculture (USDA) prohibits discrimination in all its programs and activities on the basis of race, color, national origin, age, disability, and where applicable, sex, marital status, familial status, parental status, religion, sexual orientation, genetic information, political beliefs, reprisal, or because all or a part of an individual's income is derived from any public assistance program. (Not all prohibited bases apply to all programs.) Persons with disabilities who require

alternative means for communication of program information (Braille, large print, audiotape, etc.) should contact USDA's TARGET Center at (202) 720-2600 (voice and TDD). To file a complaint of discrimination, write to USDA, Director, Office of Civil Rights, 1400 Independence Avenue, S.W., Washington, D.C. 20250-9410 or call (800) 795-3272 (voice) or (202) 720-6382 (TDD). USDA is an equal opportunity provider and employer.

# Contents

---

<b>Preface</b> .....	2
<b>How Soil Surveys Are Made</b> .....	5
<b>Soil Map</b> .....	8
Soil Map.....	9
Legend.....	10
Map Unit Legend.....	11
Map Unit Descriptions.....	11
El Paso County Area, Colorado.....	13
8—Blakeland loamy sand, 1 to 9 percent slopes.....	13
9—Blakeland-Fluvaquentic Haplaquolls.....	14
95—Truckton loamy sand, 1 to 9 percent slopes.....	16
<b>Soil Information for All Uses</b> .....	18
Soil Properties and Qualities.....	18
Soil Erosion Factors.....	18
K Factor, Whole Soil.....	18
Wind Erodibility Group.....	21
Soil Qualities and Features.....	24
Hydrologic Soil Group.....	24
<b>References</b> .....	29

# How Soil Surveys Are Made

---

Soil surveys are made to provide information about the soils and miscellaneous areas in a specific area. They include a description of the soils and miscellaneous areas and their location on the landscape and tables that show soil properties and limitations affecting various uses. Soil scientists observed the steepness, length, and shape of the slopes; the general pattern of drainage; the kinds of crops and native plants; and the kinds of bedrock. They observed and described many soil profiles. A soil profile is the sequence of natural layers, or horizons, in a soil. The profile extends from the surface down into the unconsolidated material in which the soil formed or from the surface down to bedrock. The unconsolidated material is devoid of roots and other living organisms and has not been changed by other biological activity.

Currently, soils are mapped according to the boundaries of major land resource areas (MLRAs). MLRAs are geographically associated land resource units that share common characteristics related to physiography, geology, climate, water resources, soils, biological resources, and land uses (USDA, 2006). Soil survey areas typically consist of parts of one or more MLRA.

The soils and miscellaneous areas in a survey area occur in an orderly pattern that is related to the geology, landforms, relief, climate, and natural vegetation of the area. Each kind of soil and miscellaneous area is associated with a particular kind of landform or with a segment of the landform. By observing the soils and miscellaneous areas in the survey area and relating their position to specific segments of the landform, a soil scientist develops a concept, or model, of how they were formed. Thus, during mapping, this model enables the soil scientist to predict with a considerable degree of accuracy the kind of soil or miscellaneous area at a specific location on the landscape.

Commonly, individual soils on the landscape merge into one another as their characteristics gradually change. To construct an accurate soil map, however, soil scientists must determine the boundaries between the soils. They can observe only a limited number of soil profiles. Nevertheless, these observations, supplemented by an understanding of the soil-vegetation-landscape relationship, are sufficient to verify predictions of the kinds of soil in an area and to determine the boundaries.

Soil scientists recorded the characteristics of the soil profiles that they studied. They noted soil color, texture, size and shape of soil aggregates, kind and amount of rock fragments, distribution of plant roots, reaction, and other features that enable them to identify soils. After describing the soils in the survey area and determining their properties, the soil scientists assigned the soils to taxonomic classes (units). Taxonomic classes are concepts. Each taxonomic class has a set of soil characteristics with precisely defined limits. The classes are used as a basis for comparison to classify soils systematically. Soil taxonomy, the system of taxonomic classification used in the United States, is based mainly on the kind and character of soil properties and the arrangement of horizons within the profile. After the soil

## Custom Soil Resource Report

scientists classified and named the soils in the survey area, they compared the individual soils with similar soils in the same taxonomic class in other areas so that they could confirm data and assemble additional data based on experience and research.

The objective of soil mapping is not to delineate pure map unit components; the objective is to separate the landscape into landforms or landform segments that have similar use and management requirements. Each map unit is defined by a unique combination of soil components and/or miscellaneous areas in predictable proportions. Some components may be highly contrasting to the other components of the map unit. The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The delineation of such landforms and landform segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, onsite investigation is needed to define and locate the soils and miscellaneous areas.

Soil scientists make many field observations in the process of producing a soil map. The frequency of observation is dependent upon several factors, including scale of mapping, intensity of mapping, design of map units, complexity of the landscape, and experience of the soil scientist. Observations are made to test and refine the soil-landscape model and predictions and to verify the classification of the soils at specific locations. Once the soil-landscape model is refined, a significantly smaller number of measurements of individual soil properties are made and recorded. These measurements may include field measurements, such as those for color, depth to bedrock, and texture, and laboratory measurements, such as those for content of sand, silt, clay, salt, and other components. Properties of each soil typically vary from one point to another across the landscape.

Observations for map unit components are aggregated to develop ranges of characteristics for the components. The aggregated values are presented. Direct measurements do not exist for every property presented for every map unit component. Values for some properties are estimated from combinations of other properties.

While a soil survey is in progress, samples of some of the soils in the area generally are collected for laboratory analyses and for engineering tests. Soil scientists interpret the data from these analyses and tests as well as the field-observed characteristics and the soil properties to determine the expected behavior of the soils under different uses. Interpretations for all of the soils are field tested through observation of the soils in different uses and under different levels of management. Some interpretations are modified to fit local conditions, and some new interpretations are developed to meet local needs. Data are assembled from other sources, such as research information, production records, and field experience of specialists. For example, data on crop yields under defined levels of management are assembled from farm records and from field or plot experiments on the same kinds of soil.

Predictions about soil behavior are based not only on soil properties but also on such variables as climate and biological activity. Soil conditions are predictable over long periods of time, but they are not predictable from year to year. For example, soil scientists can predict with a fairly high degree of accuracy that a given soil will have a high water table within certain depths in most years, but they cannot predict that a high water table will always be at a specific level in the soil on a specific date.

After soil scientists located and identified the significant natural bodies of soil in the survey area, they drew the boundaries of these bodies on aerial photographs and

## Custom Soil Resource Report

identified each as a specific map unit. Aerial photographs show trees, buildings, fields, roads, and rivers, all of which help in locating boundaries accurately.



# Soil Map

---

The soil map section includes the soil map for the defined area of interest, a list of soil map units on the map and extent of each map unit, and cartographic symbols displayed on the map. Also presented are various metadata about data used to produce the map, and a description of each soil map unit.

# Custom Soil Resource Report Soil Map



Map Scale: 1:6,130 if printed on A landscape (11" x 8.5") sheet.

0 50 100 200 300 Meters

0 250 500 1000 1500 Feet

Map projection: Web Mercator Corner coordinates: WGS84 Edge tics: UTM Zone 13N WGS84

### MAP LEGEND

**Area of Interest (AOI)**

 Area of Interest (AOI)

**Soils**

 Soil Map Unit Polygons

 Soil Map Unit Lines


 Soil Map Unit Points

**Special Point Features**






-  Blowout
-  Borrow Pit
-  Clay Spot
-  Closed Depression
-  Gravel Pit
-  Gravelly Spot
-  Landfill
-  Lava Flow
-  Marsh or swamp
-  Mine or Quarry
-  Miscellaneous Water
-  Perennial Water
-  Rock Outcrop
-  Saline Spot
-  Sandy Spot
-  Severely Eroded Spot
-  Sinkhole
-  Slide or Slip
-  Sodic Spot

-  Spoil Area
-  Stony Spot
-  Very Stony Spot
-  Wet Spot
-  Other
-  Special Line Features

**Water Features**

 Streams and Canals

**Transportation**

-  Rails
-  Interstate Highways
-  US Routes
-  Major Roads
-  Local Roads

**Background**

 Aerial Photography

### MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service  
 Web Soil Survey URL:  
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: El Paso County Area, Colorado  
 Survey Area Data: Version 18, Jun 5, 2020

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Sep 11, 2018—Oct 20, 2018

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

## Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
8	Blakeland loamy sand, 1 to 9 percent slopes	13.9	7.4%
9	Blakeland-Fluvaquentic Haplaquolls	75.0	39.7%
95	Truckton loamy sand, 1 to 9 percent slopes	99.9	52.9%
<b>Totals for Area of Interest</b>		<b>188.9</b>	<b>100.0%</b>

## Map Unit Descriptions

The map units delineated on the detailed soil maps in a soil survey represent the soils or miscellaneous areas in the survey area. The map unit descriptions, along with the maps, can be used to determine the composition and properties of a unit.

A map unit delineation on a soil map represents an area dominated by one or more major kinds of soil or miscellaneous areas. A map unit is identified and named according to the taxonomic classification of the dominant soils. Within a taxonomic class there are precisely defined limits for the properties of the soils. On the landscape, however, the soils are natural phenomena, and they have the characteristic variability of all natural phenomena. Thus, the range of some observed properties may extend beyond the limits defined for a taxonomic class. Areas of soils of a single taxonomic class rarely, if ever, can be mapped without including areas of other taxonomic classes. Consequently, every map unit is made up of the soils or miscellaneous areas for which it is named and some minor components that belong to taxonomic classes other than those of the major soils.

Most minor soils have properties similar to those of the dominant soil or soils in the map unit, and thus they do not affect use and management. These are called noncontrasting, or similar, components. They may or may not be mentioned in a particular map unit description. Other minor components, however, have properties and behavioral characteristics divergent enough to affect use or to require different management. These are called contrasting, or dissimilar, components. They generally are in small areas and could not be mapped separately because of the scale used. Some small areas of strongly contrasting soils or miscellaneous areas are identified by a special symbol on the maps. If included in the database for a given area, the contrasting minor components are identified in the map unit descriptions along with some characteristics of each. A few areas of minor components may not have been observed, and consequently they are not mentioned in the descriptions, especially where the pattern was so complex that it was impractical to make enough observations to identify all the soils and miscellaneous areas on the landscape.

The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The objective of mapping is not to delineate pure taxonomic classes but rather to separate the landscape into landforms or

## Custom Soil Resource Report

landform segments that have similar use and management requirements. The delineation of such segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, however, onsite investigation is needed to define and locate the soils and miscellaneous areas.

An identifying symbol precedes the map unit name in the map unit descriptions. Each description includes general facts about the unit and gives important soil properties and qualities.

Soils that have profiles that are almost alike make up a *soil series*. Except for differences in texture of the surface layer, all the soils of a series have major horizons that are similar in composition, thickness, and arrangement.

Soils of one series can differ in texture of the surface layer, slope, stoniness, salinity, degree of erosion, and other characteristics that affect their use. On the basis of such differences, a soil series is divided into *soil phases*. Most of the areas shown on the detailed soil maps are phases of soil series. The name of a soil phase commonly indicates a feature that affects use or management. For example, Alpha silt loam, 0 to 2 percent slopes, is a phase of the Alpha series.

Some map units are made up of two or more major soils or miscellaneous areas. These map units are complexes, associations, or undifferentiated groups.

A *complex* consists of two or more soils or miscellaneous areas in such an intricate pattern or in such small areas that they cannot be shown separately on the maps. The pattern and proportion of the soils or miscellaneous areas are somewhat similar in all areas. Alpha-Beta complex, 0 to 6 percent slopes, is an example.

An *association* is made up of two or more geographically associated soils or miscellaneous areas that are shown as one unit on the maps. Because of present or anticipated uses of the map units in the survey area, it was not considered practical or necessary to map the soils or miscellaneous areas separately. The pattern and relative proportion of the soils or miscellaneous areas are somewhat similar. Alpha-Beta association, 0 to 2 percent slopes, is an example.

An *undifferentiated group* is made up of two or more soils or miscellaneous areas that could be mapped individually but are mapped as one unit because similar interpretations can be made for use and management. The pattern and proportion of the soils or miscellaneous areas in a mapped area are not uniform. An area can be made up of only one of the major soils or miscellaneous areas, or it can be made up of all of them. Alpha and Beta soils, 0 to 2 percent slopes, is an example.

Some surveys include *miscellaneous areas*. Such areas have little or no soil material and support little or no vegetation. Rock outcrop is an example.

## El Paso County Area, Colorado

### 8—Blakeland loamy sand, 1 to 9 percent slopes

#### Map Unit Setting

*National map unit symbol:* 369v  
*Elevation:* 4,600 to 5,800 feet  
*Mean annual precipitation:* 14 to 16 inches  
*Mean annual air temperature:* 46 to 48 degrees F  
*Frost-free period:* 125 to 145 days  
*Farmland classification:* Not prime farmland

#### Map Unit Composition

*Blakeland and similar soils:* 98 percent  
*Minor components:* 2 percent  
*Estimates are based on observations, descriptions, and transects of the mapunit.*

#### Description of Blakeland

##### Setting

*Landform:* Hills, flats  
*Landform position (three-dimensional):* Side slope, talf  
*Down-slope shape:* Linear  
*Across-slope shape:* Linear  
*Parent material:* Alluvium derived from sedimentary rock and/or eolian deposits derived from sedimentary rock

##### Typical profile

*A - 0 to 11 inches:* loamy sand  
*AC - 11 to 27 inches:* loamy sand  
*C - 27 to 60 inches:* sand

##### Properties and qualities

*Slope:* 1 to 9 percent  
*Depth to restrictive feature:* More than 80 inches  
*Drainage class:* Somewhat excessively drained  
*Runoff class:* Low  
*Capacity of the most limiting layer to transmit water (Ksat):* High to very high (5.95 to 19.98 in/hr)  
*Depth to water table:* More than 80 inches  
*Frequency of flooding:* None  
*Frequency of ponding:* None  
*Calcium carbonate, maximum content:* 5 percent  
*Available water capacity:* Low (about 4.5 inches)

##### Interpretive groups

*Land capability classification (irrigated):* 3e  
*Land capability classification (nonirrigated):* 6e  
*Hydrologic Soil Group:* A  
*Ecological site:* R049XB210CO - Sandy Foothill  
*Hydric soil rating:* No

#### Minor Components

##### Pleasant

*Percent of map unit:* 1 percent

## Custom Soil Resource Report

*Landform:* Depressions  
*Hydric soil rating:* Yes

### **Other soils**

*Percent of map unit:* 1 percent  
*Hydric soil rating:* No

## **9—Blakeland-Fluvaquentic Haplaquolls**

### **Map Unit Setting**

*National map unit symbol:* 36b6  
*Elevation:* 3,500 to 5,800 feet  
*Mean annual precipitation:* 13 to 17 inches  
*Mean annual air temperature:* 46 to 55 degrees F  
*Frost-free period:* 110 to 165 days  
*Farmland classification:* Not prime farmland

### **Map Unit Composition**

*Blakeland and similar soils:* 60 percent  
*Fluvaquentic haplaquolls and similar soils:* 38 percent  
*Minor components:* 2 percent  
*Estimates are based on observations, descriptions, and transects of the mapunit.*

### **Description of Blakeland**

#### **Setting**

*Landform:* Hills, flats  
*Landform position (three-dimensional):* Side slope, talf  
*Down-slope shape:* Linear  
*Across-slope shape:* Linear  
*Parent material:* Sandy alluvium derived from arkose and/or eolian deposits  
derived from arkose

#### **Typical profile**

*A - 0 to 11 inches:* loamy sand  
*AC - 11 to 27 inches:* loamy sand  
*C - 27 to 60 inches:* sand

#### **Properties and qualities**

*Slope:* 1 to 9 percent  
*Depth to restrictive feature:* More than 80 inches  
*Drainage class:* Somewhat excessively drained  
*Runoff class:* Low  
*Capacity of the most limiting layer to transmit water (Ksat):* High to very high (5.95 to 19.98 in/hr)  
*Depth to water table:* More than 80 inches  
*Frequency of flooding:* None  
*Frequency of ponding:* None  
*Calcium carbonate, maximum content:* 5 percent  
*Available water capacity:* Low (about 4.5 inches)

**Interpretive groups**

*Land capability classification (irrigated): 3e*  
*Land capability classification (nonirrigated): 6e*  
*Hydrologic Soil Group: A*  
*Ecological site: R049XB210CO - Sandy Foothill*  
*Hydric soil rating: No*

**Description of Fluvaquentic Haplaquolls**

**Setting**

*Landform: Swales*  
*Down-slope shape: Linear*  
*Across-slope shape: Linear*  
*Parent material: Alluvium*

**Typical profile**

*H1 - 0 to 12 inches: variable*

**Properties and qualities**

*Slope: 1 to 2 percent*  
*Depth to restrictive feature: More than 80 inches*  
*Drainage class: Poorly drained*  
*Runoff class: Very high*  
*Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high*  
*(0.20 to 6.00 in/hr)*  
*Depth to water table: About 0 to 24 inches*  
*Frequency of flooding: Occasional*  
*Frequency of ponding: None*  
*Maximum salinity: Nonsaline to slightly saline (0.0 to 4.0 mmhos/cm)*

**Interpretive groups**

*Land capability classification (irrigated): 6w*  
*Land capability classification (nonirrigated): 6w*  
*Hydrologic Soil Group: D*  
*Hydric soil rating: Yes*

**Minor Components**

**Other soils**

*Percent of map unit: 1 percent*  
*Hydric soil rating: No*

**Pleasant**

*Percent of map unit: 1 percent*  
*Landform: Depressions*  
*Hydric soil rating: Yes*



## 95—Truckton loamy sand, 1 to 9 percent slopes

### Map Unit Setting

*National map unit symbol:* 36bd  
*Elevation:* 6,000 to 7,000 feet  
*Mean annual precipitation:* 14 to 16 inches  
*Mean annual air temperature:* 46 to 50 degrees F  
*Frost-free period:* 125 to 145 days  
*Farmland classification:* Not prime farmland

### Map Unit Composition

*Truckton and similar soils:* 95 percent  
*Minor components:* 5 percent  
*Estimates are based on observations, descriptions, and transects of the mapunit.*

### Description of Truckton

#### Setting

*Landform:* Hills, flats  
*Landform position (three-dimensional):* Side slope, talf  
*Down-slope shape:* Linear  
*Across-slope shape:* Linear  
*Parent material:* Arkosic alluvium derived from sedimentary rock and/or arkosic residuum weathered from sedimentary rock

#### Typical profile

*A - 0 to 8 inches:* loamy sand  
*Bt - 8 to 24 inches:* sandy loam  
*C - 24 to 60 inches:* coarse sandy loam

#### Properties and qualities

*Slope:* 1 to 9 percent  
*Depth to restrictive feature:* More than 80 inches  
*Drainage class:* Well drained  
*Runoff class:* Low  
*Capacity of the most limiting layer to transmit water (Ksat):* High (1.98 to 6.00 in/hr)  
*Depth to water table:* More than 80 inches  
*Frequency of flooding:* None  
*Frequency of ponding:* None  
*Available water capacity:* Low (about 5.4 inches)

#### Interpretive groups

*Land capability classification (irrigated):* 4e  
*Land capability classification (nonirrigated):* 6e  
*Hydrologic Soil Group:* A  
*Ecological site:* R049XB210CO - Sandy Foothill  
*Hydric soil rating:* No

## Custom Soil Resource Report

### Minor Components

#### Other soils

*Percent of map unit:* 4 percent

*Hydric soil rating:* No

#### Pleasant

*Percent of map unit:* 1 percent

*Landform:* Depressions

*Hydric soil rating:* Yes

# **Soil Information for All Uses**

---

## **Soil Properties and Qualities**

The Soil Properties and Qualities section includes various soil properties and qualities displayed as thematic maps with a summary table for the soil map units in the selected area of interest. A single value or rating for each map unit is generated by aggregating the interpretive ratings of individual map unit components. This aggregation process is defined for each property or quality.

## **Soil Erosion Factors**

Soil Erosion Factors are soil properties and interpretations used in evaluating the soil for potential erosion. Example soil erosion factors can include K factor for the whole soil or on a rock free basis, T factor, wind erodibility group and wind erodibility index.


### **K Factor, Whole Soil**

Erosion factor K indicates the susceptibility of a soil to sheet and rill erosion by water. Factor K is one of six factors used in the Universal Soil Loss Equation (USLE) and the Revised Universal Soil Loss Equation (RUSLE) to predict the average annual rate of soil loss by sheet and rill erosion in tons per acre per year. The estimates are based primarily on percentage of silt, sand, and organic matter and on soil structure and saturated hydraulic conductivity (Ksat). Values of K range from 0.02 to 0.69. Other factors being equal, the higher the value, the more susceptible the soil is to sheet and rill erosion by water.

"Erosion factor Kw (whole soil)" indicates the erodibility of the whole soil. The estimates are modified by the presence of rock fragments.

Factor K does not apply to organic horizons and is not reported for those layers.

Custom Soil Resource Report  
Map—K Factor, Whole Soil



Map Scale: 1:6,130 if printed on A landscape (11" x 8.5") sheet.

0 50 100 200 300 Meters

0 250 500 1000 1500 Feet


Map projection: Web Mercator Corner coordinates: WGS84 Edge tics: UTM Zone 13N WGS84



# Custom Soil Resource Report
















## MAP LEGEND

### Area of Interest (AOI)





 Area of Interest (AOI)










### Soils

#### Soil Rating Polygons
















-  .02
-  .05
-  .10
-  .15
-  .17
-  .20
-  .24
-  .28
-  .32
-  .37
-  .43
-  .49
-  .55
-  .64
-  Not rated or not available

#### Soil Rating Lines








-  .02
-  .05
-  .10
-  .15
-  .17
-  .20

-  .24
-  .28
-  .32
-  .37
-  .43
-  .49
-  .55
-  .64
-  Not rated or not available

#### Soil Rating Points

-  .02
-  .05
-  .10
-  .15
-  .17
-  .20
-  .24
-  .28
-  .32
-  .37
-  .43
-  .49
-  .55
-  .64
-  Not rated or not available

#### Water Features

-  Streams and Canals
- Transportation**
-  Rails
-  Interstate Highways
-  US Routes
-  Major Roads
-  Local Roads
- Background**
-  Aerial Photography

## MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service  
 Web Soil Survey URL:  
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: El Paso County Area, Colorado  
 Survey Area Data: Version 18, Jun 5, 2020

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Sep 11, 2018—Oct 20, 2018

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

**Table—K Factor, Whole Soil**

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
8	Blakeland loamy sand, 1 to 9 percent slopes	.10	13.9	7.4%
9	Blakeland-Fluvaquentic Haplaquolls	.10	75.0	39.7%
95	Truckton loamy sand, 1 to 9 percent slopes	.17	99.9	52.9%
<b>Totals for Area of Interest</b>			<b>188.9</b>	<b>100.0%</b>

**Rating Options—K Factor, Whole Soil**

*Aggregation Method:* Dominant Condition

*Component Percent Cutoff:* None Specified



*Tie-break Rule:* Higher

*Layer Options (Horizon Aggregation Method):* Surface Layer (Not applicable)

**Wind Erodibility Group**


A wind erodibility group (WEG) consists of soils that have similar properties affecting their susceptibility to wind erosion in cultivated areas. The soils assigned to group 1 are the most susceptible to wind erosion, and those assigned to group 8 are the least susceptible.

# Custom Soil Resource Report Map—Wind Erodibility Group













### MAP LEGEND

**Area of Interest (AOI)**











 Area of Interest (AOI)

**Soils**











**Soil Rating Polygons**

	1
	2
	3
	4
	4L
	5
	6
	7
	8
	Not rated or not available


**Soil Rating Lines**

	1
	2
	3
	4
	4L
	5
	6
	7
	8
	Not rated or not available


**Soil Rating Points**


	1
	2
	3
	4
	4L
	5
	6
	7
	8
	Not rated or not available


**Water Features**


 Streams and Canals


**Transportation**

 Rails


 Interstate Highways

 US Routes

 Major Roads

 Local Roads

**Background**

 Aerial Photography

### MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service  
 Web Soil Survey URL:  
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: El Paso County Area, Colorado  
 Survey Area Data: Version 18, Jun 5, 2020

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Sep 11, 2018—Oct 20, 2018

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.



**Table—Wind Erodibility Group**

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
8	Blakeland loamy sand, 1 to 9 percent slopes	2	13.9	7.4%
9	Blakeland-Fluvaquentic Haplaquolls	2	75.0	39.7%
95	Truckton loamy sand, 1 to 9 percent slopes	2	99.9	52.9%
<b>Totals for Area of Interest</b>			<b>188.9</b>	<b>100.0%</b>

### Rating Options—Wind Erodibility Group

*Aggregation Method:* Dominant Condition

*Component Percent Cutoff:* None Specified

*Tie-break Rule:* Lower

### Soil Qualities and Features

Soil qualities are behavior and performance attributes that are not directly measured, but are inferred from observations of dynamic conditions and from soil properties. Example soil qualities include natural drainage, and frost action. Soil features are attributes that are not directly part of the soil. Example soil features include slope and depth to restrictive layer. These features can greatly impact the use and management of the soil.

### Hydrologic Soil Group

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained

## Custom Soil Resource Report


soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

# Custom Soil Resource Report Map—Hydrologic Soil Group



Map Scale: 1:6,130 if printed on A landscape (11" x 8.5") sheet.

0 50 100 200 300 Meters


0 250 500 1000 1500 Feet

Map projection: Web Mercator Corner coordinates: WGS84 Edge tics: UTM Zone 13N WGS84



### MAP LEGEND

**Area of Interest (AOI)**









 Area of Interest (AOI)

**Soils**

**Soil Rating Polygons**





-  A
-  A/D
-  B
-  B/D
-  C
-  C/D
-  D
-  Not rated or not available

**Soil Rating Lines**


-  A
-  A/D
-  B
-  B/D
-  C
-  C/D
-  D
-  Not rated or not available

**Soil Rating Points**






-  A
-  A/D
-  B
-  B/D

-  C
-  C/D
-  D
-  Not rated or not available


**Water Features**

 Streams and Canals

**Transportation**

-  Rails
-  Interstate Highways
-  US Routes
-  Major Roads
-  Local Roads

**Background**

 Aerial Photography

### MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service  
 Web Soil Survey URL:  
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: El Paso County Area, Colorado  
 Survey Area Data: Version 18, Jun 5, 2020

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Sep 11, 2018—Oct 20, 2018

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

**Table—Hydrologic Soil Group**

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
8	Blakeland loamy sand, 1 to 9 percent slopes	A	13.9	7.4%
9	Blakeland-Fluvaquentic Haplaquolls	A	75.0	39.7%
95	Truckton loamy sand, 1 to 9 percent slopes	A	99.9	52.9%
<b>Totals for Area of Interest</b>			<b>188.9</b>	<b>100.0%</b>

**Rating Options—Hydrologic Soil Group**

*Aggregation Method: Dominant Condition*

*Component Percent Cutoff: None Specified*

*Tie-break Rule: Higher*

# References

---

- American Association of State Highway and Transportation Officials (AASHTO). 2004. Standard specifications for transportation materials and methods of sampling and testing. 24th edition.
- American Society for Testing and Materials (ASTM). 2005. Standard classification of soils for engineering purposes. ASTM Standard D2487-00.
- Cowardin, L.M., V. Carter, F.C. Golet, and E.T. LaRoe. 1979. Classification of wetlands and deep-water habitats of the United States. U.S. Fish and Wildlife Service FWS/OBS-79/31.
- Federal Register. July 13, 1994. Changes in hydric soils of the United States.
- Federal Register. September 18, 2002. Hydric soils of the United States.
- Hurt, G.W., and L.M. Vasilas, editors. Version 6.0, 2006. Field indicators of hydric soils in the United States.
- National Research Council. 1995. Wetlands: Characteristics and boundaries.
- Soil Survey Division Staff. 1993. Soil survey manual. Soil Conservation Service. U.S. Department of Agriculture Handbook 18. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2\\_054262](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_054262)
- Soil Survey Staff. 1999. Soil taxonomy: A basic system of soil classification for making and interpreting soil surveys. 2nd edition. Natural Resources Conservation Service, U.S. Department of Agriculture Handbook 436. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2\\_053577](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053577)
- Soil Survey Staff. 2010. Keys to soil taxonomy. 11th edition. U.S. Department of Agriculture, Natural Resources Conservation Service. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2\\_053580](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053580)
- Tiner, R.W., Jr. 1985. Wetlands of Delaware. U.S. Fish and Wildlife Service and Delaware Department of Natural Resources and Environmental Control, Wetlands Section.
- United States Army Corps of Engineers, Environmental Laboratory. 1987. Corps of Engineers wetlands delineation manual. Waterways Experiment Station Technical Report Y-87-1.
- United States Department of Agriculture, Natural Resources Conservation Service. National forestry manual. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/home/?cid=nrcs142p2\\_053374](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/home/?cid=nrcs142p2_053374)
- United States Department of Agriculture, Natural Resources Conservation Service. National range and pasture handbook. <http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/landuse/rangepasture/?cid=stelprdb1043084>

## Custom Soil Resource Report

United States Department of Agriculture, Natural Resources Conservation Service. National soil survey handbook, title 430-VI. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/scientists/?cid=nrcs142p2\\_054242](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/scientists/?cid=nrcs142p2_054242)



United States Department of Agriculture, Natural Resources Conservation Service. 2006. Land resource regions and major land resource areas of the United States, the Caribbean, and the Pacific Basin. U.S. Department of Agriculture Handbook 296. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2\\_053624](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053624)

United States Department of Agriculture, Soil Conservation Service. 1961. Land capability classification. U.S. Department of Agriculture Handbook 210. [http://www.nrcs.usda.gov/Internet/FSE\\_DOCUMENTS/nrcs142p2\\_052290.pdf](http://www.nrcs.usda.gov/Internet/FSE_DOCUMENTS/nrcs142p2_052290.pdf)

# National Flood Hazard Layer FIRMette



104°31'16"W 38°55'35"N



Basemap: USGS National Map: Orthoimagery: Data refreshed October, 2020

BFE's shown on this exhibit need to be included on drainage maps, preliminary plan and GEC plans.

## Legend

SEE FIS REPORT FOR DETAILED LEGEND AND INDEX MAP FOR FIRM PANEL LAYOUT

SPECIAL FLOOD HAZARD AREAS		Without Base Flood Elevation (BFE) Zone A, V, A99
		With BFE or Depth Zone AE, AO, AH, VE, AR
		Regulatory Floodway

OTHER AREAS OF FLOOD HAZARD		0.2% Annual Chance Flood Hazard, Areas of 1% annual chance flood with average depth less than one foot or with drainage areas of less than one square mile Zone X
		Future Conditions 1% Annual Chance Flood Hazard Zone X
		Area with Reduced Flood Risk due to Levee. See Notes. Zone X
		Area with Flood Risk due to Levee Zone D

OTHER AREAS		NO SCREEN Area of Minimal Flood Hazard Zone X
		Effective LOMRs
GENERAL STRUCTURES		Area of Undetermined Flood Hazard Zone D
		Channel, Culvert, or Storm Sewer
		Levee, Dike, or Floodwall

OTHER FEATURES		20.2 Cross Sections with 1% Annual Chance
		17.5 Water Surface Elevation
		Coastal Transect
		Base Flood Elevation Line (BFE)
		Limit of Study
		Jurisdiction Boundary
OTHER FEATURES		Coastal Transect Baseline
		Profile Baseline
		Hydrographic Feature

MAP PANELS		Digital Data Available
		No Digital Data Available
		Unmapped
		The pin displayed on the map is an approximate point selected by the user and does not represent an authoritative property location.



This map complies with FEMA's standards for the use of digital flood maps if it is not void as described below. The basemap shown complies with FEMA's basemap accuracy standards

The flood hazard information is derived directly from the authoritative NFHL web services provided by FEMA. This map was exported on 4/20/2021 at 4:13 PM and does not reflect changes or amendments subsequent to this date and time. The NFHL and effective information may change or become superseded by new data over time.

This map image is void if the one or more of the following map elements do not appear: basemap imagery, flood zone labels, legend, scale bar, map creation date, community identifiers, FIRM panel number, and FIRM effective date. Map images for unmapped and unmodernized areas cannot be used for regulatory purposes.



***APPENDIX C - HYDROLOGIC CALCULATIONS***



**EXISTING  
RUNOFF COEFFICIENTS - IMPERVIOUS CALCULATION**

PROJECT NAME: Peerless Farms  
 PROJECT NUMBER: 196114000  
 CALCULATED BY: MOH  
 CHECKED BY: MOH

DATE: 6/15/2023

SOIL:

LAND USE:	Roof AREA	Landscape AREA	Pavement AREA	Gravel AREA
2-YEAR COEFF.	0.71	0.02	0.89	0.57
5-YEAR COEFF.	0.73	0.08	0.90	0.59
10-YEAR COEFF.	0.75	0.15	0.92	0.63
100-YEAR COEFF.	0.81	0.35	0.96	0.70
IMPERVIOUS %	90%	0%	100%	80%

DESIGN BASIN	DESIGN POINT	Roof AREA (AC)	Landscape AREA (AC)	Pavement AREA (AC)	Gravel AREA (AC)	TOTAL AREA (AC)	C(2)	C(5)	C(10)	C(100)	Imp %
<b>On-Site Basins</b>											
EX1	EX1	0.26	34.58	0.06	0.46	35.36	0.03	0.09	0.16	0.36	2%
EX2	EX2	0.09	4.45	0.00	0.10	4.64	0.05	0.10	0.17	0.37	4%
<b>BASIN SUBTOTAL</b>		<b>0.35</b>	<b>39.03</b>	<b>0.06</b>	<b>0.56</b>	<b>40.00</b>	<b>0.04</b>	<b>0.09</b>	<b>0.16</b>	<b>0.36</b>	<b>2%</b>
<b>Off-Site Basins</b>											
EX3	EX3	0.00	1.93	0.70	0.00	2.63	0.25	0.30	12.02	0.51	27%
<b>BASIN SUBTOTAL</b>		<b>0.00</b>	<b>1.93</b>	<b>0.70</b>	<b>0.00</b>	<b>2.63</b>	<b>0.25</b>	<b>0.30</b>	<b>12.02</b>	<b>0.51</b>	<b>27%</b>

**EXISTING  
Time of Concentration**

PROJECT NAME: Peerless Farms  
 PROJECT NUMBER: 196114000  
 CALCULATED BY: MOH  
 CHECKED BY: MOH

DATE: 6/15/2023

SUB-BASIN DATA			INITIAL TIME (T <sub>i</sub> )			TRAVEL TIME (T <sub>t</sub> )					T <sub>c</sub> CHECK (URBANIZED BASINS)				FINAL T <sub>c</sub>	
DESIGN BASIN (1)	AREA Ac (2)	C <sub>s</sub> (3)	LENGTH Ft (4)	SLOPE % (5)	T <sub>i</sub> Min. (6)	LENGTH Ft (7)	SLOPE % (8)	C <sub>v</sub> (9)	VEL fps (11)	T <sub>t</sub> Min. (12)	COMP. t <sub>c</sub> (13)	TOTAL LENGTH (14)	TOTAL SLOPE (15)	TOTAL IMP. (16)	T <sub>c</sub> Min. (17)	Min.
<b>On-Site Basins</b>																
EX1	35.36	0.093	300	1.6%	27.3	1,618	3.4%	2.5	0.5	58.5	85.8	1918	3.1%	2%	45.2	45.2
EX2	5	0.104	300	2.8%	22.4	569	1.9%	2.5	0.3	27.5	50.0	869	2.2%	4%	35.7	35.7
<b>Off-Site Basins</b>																
EX3	2.63	0.30	40	2.5%	6.9	1,500	1.9%	20.0	2.8	9.1	15.9	1540	1.9%	27%	36.1	15.9

$$t_i = \frac{0.395(1.1 - C_s)\sqrt{L_i}}{S_o^{0.33}}$$

$$t_t = \frac{L_t}{60K\sqrt{S_o}} = \frac{L_t}{60V_t}$$

$$t_c = (26 - 17i) + \frac{L_t}{60(14i + 9)\sqrt{S_o}}$$







PROJECT NAME: Peerless Farms  
PROJECT NUMBER: 196114000  
CALCULATED BY: MOH  
CHECKED BY: MOH

DATE: 6/15/2023

**EXISTING RATIONAL CALCULATIONS SUMMARY**

DESIGN POINT	TRIBUTARY BASINS	TRIBUTARY AREA (AC)	IMPERVIOUSNESS %	PEAK FLOWS (CFS)	
				Q5	Q100
<b>On-Site Basins</b>					
EX1	EX1	35.36	2%	5.99	38.94
EX2	EX2	4.64	4%	1.03	6.07
<b>TOTAL</b>		<b>40.00</b>	<b>2%</b>	<b>7.02</b>	<b>45.01</b>
<b>Off-Site Basins</b>					
EX3	EX3	2.63	27%	2.18	7.47
<b>TOTAL</b>		<b>2.63</b>	<b>27%</b>	<b>2.18</b>	<b>7.47</b>



**PROPOSED  
RUNOFF COEFFICIENTS - IMPERVIOUS CALCULATION**

PROJECT NAME: Peerless Farms  
 PROJECT NUMBER: 196114000  
 CALCULATED BY: MOH  
 CHECKED BY: MOH

DATE: 6/15/2023

SOIL:											
		Roof	Landscape	Pavement	Gravel						
LAND USE:		AREA	AREA	AREA	AREA						
2-YEAR COEFF.		0.71	0.02	0.89	0.57						
5-YEAR COEFF.		0.73	0.08	0.90	0.59						
10-YEAR COEFF.		0.75	0.15	0.92	0.63						
100-YEAR COEFF.		0.81	0.35	0.96	0.70						
IMPERVIOUS %		90%	0%	100%	80%						
DESIGN BASIN	DESIGN POINT	Roof AREA (AC)	Landscape AREA (AC)	Pavement AREA (AC)	Gravel AREA (AC)	TOTAL AREA (AC)	C(2)	C(5)	C(10)	C(100)	Imp %
<b>On-Site Basins</b>											
1	1	3.34	25.67	0.00	0.05	29.06	0.10	0.16	0.22	0.40	10%
2	2	0.00	1.43	0.09	0.26	1.78	0.14	0.20	0.26	0.43	17%
3	3	0.00	0.49	0.04	0.26	0.78	0.24	0.29	0.35	0.50	31%
4	4	0.00	0.18	0.24	0.00	0.42	0.51	0.55	0.59	0.70	57%
5	5	0.00	0.47	0.16	0.22	0.85	0.33	0.37	0.42	0.56	40%
6	6	0.56	4.70	0.06	0.23	5.55	0.12	0.18	0.24	0.42	13%
7	7	0.00	1.48	0.09	0.00	1.57	0.07	0.13	0.19	0.38	6%
<b>BASIN SUBTOTAL</b>		<b>10%</b>	<b>86%</b>	<b>2%</b>	<b>3%</b>	<b>100%</b>	<b>0.12</b>	<b>0.17</b>	<b>0.23</b>	<b>0.41</b>	<b>12%</b>
<b>Off-Site Basins</b>											
EX3	EX3	0.00	1.93	0.70	0.00	2.63	0.25	0.30	12.02	0.51	27%
<b>BASIN SUBTOTAL</b>		<b>0%</b>	<b>73%</b>	<b>27%</b>	<b>0%</b>	<b>100%</b>					

**PROPOSED  
Time of Concentration**

PROJECT NAME: Peerless Farms  
 PROJECT NUMBER: 196114000  
 CALCULATED BY: MOH  
 CHECKED BY: MOH

DATE: 6/15/2023

SUB-BASIN DATA			INITIAL TIME (T <sub>i</sub> )			TRAVEL TIME (T <sub>t</sub> )					T <sub>c</sub> CHECK (URBANIZED BASINS)				FINAL T <sub>c</sub>	
DESIGN BASIN (1)	AREA Ac (2)	C5 (3)	LENGTH Ft (4)	SLOPE % (5)	T <sub>i</sub> Min. (6)	LENGTH Ft (7)	SLOPE % (8)	C <sub>v</sub> (9)	VEL fps (11)	T <sub>t</sub> Min. (12)	COMP. t <sub>c</sub> (13)	TOTAL LENGTH (14)	TOTAL SLOPE (15)	TOTAL IMP. (16)	T <sub>c</sub> Min. (17)	Min. (18)
<b>On-Site Basins</b>																
1	29.06	0.16	300	6.0%	16.5	1,090	1.1%	5.0	0.5	34.6	51.1	1390	2.2%	10%	39.3	39.3
2	1.78	0.20	300	2.5%	21.1	1,243	3.2%	20.0	3.6	5.8	26.9	1543	3.1%	17%	36.1	26.9
3	0.78	0.29	61	5.0%	6.8	981	2.9%	20.0	3.4	4.8	11.6	1042	3.0%	31%	28.2	11.6
4	0.42	0.55	61	5.0%	4.6	477	1.7%	20.0	2.6	3.0	7.7	538	2.1%	57%	20.0	7.7
5	0.85	0.37	61	5.0%	6.1	1,056	1.5%	20.0	2.4	7.2	13.3	1117	1.7%	40%	29.1	13.3
6	5.55	0.18	300	2.0%	23.3	1,036	2.0%	20.0	2.8	6.1	29.4	1336	2.0%	13%	38.2	29.4
7	1.57	0.13	260	2.0%	22.9	5	3.0%	5.0	0.9	0.1	23.0	265	2.0%	6%	28.2	23.0
<b>Off-Site Basins</b>																
EX3	2.63	0.30	40	2.5%	6.9	1,500	1.9%	20.0	2.8	9.1	15.9	1540	1.9%	27%	36.1	15.9
$t_i = \frac{0.395(1.1 - C_s)\sqrt{L_i}}{S_o^{0.33}}$ $t_t = \frac{L_i}{60K\sqrt{S_o}} = \frac{L_i}{60V_t}$ $t_c = (26 - 17i) + \frac{L_i}{60(14i + 9)\sqrt{S_i}}$																









PROJECT NAME: Peerless Farms  
PROJECT NUMBER: 196114000  
CALCULATED BY: MOH  
CHECKED BY: MOH

DATE: 6/15/2023

**PROPOSED RATIONAL CALCULATIONS SUMMARY**

DESIGN POINT	TRIBUTARY BASINS	TRIBUTARY AREA (AC)	IMPERVIOUSNESS %	PEAK FLOWS (CFS)	
				Q5	Q100
<b>On-Site Basins</b>					
1	1	29.06	10%	9.03	39.34
2	2	1.78	17%	0.87	3.24
3	3	0.78	31%	0.86	2.48
4	4	0.42	57%	1.03	2.21
5	5	0.85	40%	1.12	2.84
6	6	5.55	13%	2.32	9.26
7	7	1.57	6%	0.54	2.77
<b>TOTAL</b>		<b>40.00</b>	<b>12%</b>	<b>15.77</b>	<b>62.14</b>
<b>Off-Site Basins</b>					
EX3	EX3	2.63	27%	2.18	7.47
<b>TOTAL</b>		<b>2.63</b>	<b>27%</b>	<b>2.18</b>	<b>7.47</b>

**Design Procedure Form: Runoff Reduction**

UD-BMP (Version 3.07, March 2018)

Sheet 1 of 1

**Designer:** Mitchell Hess  
**Company:** Kimley-Horn  
**Date:** June 15, 2023  
**Project:** Peerless Farms  
**Location:** Proposed Public ROW

**SITE INFORMATION (User Input in Blue Cells)**

will review UIA:RPA areas with the next submittal and updated figure

WQCV Rainfall Depth = 0.60 inches  
 Depth of Average Runoff Producing Storm,  $d_6$  = 0.43 inches (for Watersheds Outside of the Denver Region, Figure 3-1 in USDCM Vol. 3)

Area Type	UIA:RPA	UIA:RPA	UIA:RPA	UIA:RPA	UIA:RPA	UIA:RPA	UIA:RPA	SPA				
Area ID	A	B	C	D	E	F	G	H				
Downstream Design Point ID	A	B	C	D	E	F	G	H				
Downstream BMP Type	None	None	None	None	None	None	None	None				
DCIA (ft <sup>2</sup> )	--	--	--	--	--	--	--	--				
UIA (ft <sup>2</sup> )	1,903	1,903	10,435	2,144	6,606	3,553	999	--				
RPA (ft <sup>2</sup> )	1,189	1,190	4,982	1,093	3,013	538	122	--				
SPA (ft <sup>2</sup> )	--	--	--	--	--	--	--	5,523				
HSG A (%)	100%	100%	100%	100%	100%	100%	100%	100%				
HSG B (%)	0%	0%	0%	0%	0%	0%	0%	0%				
HSG C/D (%)	0%	0%	0%	0%	0%	0%	0%	0%				
Average Slope of RPA (ft/ft)	0.330	0.330	0.330	0.330	0.330	0.330	0.330	--				
UIA:RPA Interface Width (ft)	119.00	119.00	545.00	118.00	314.00	125.00	19.00	--				

**CALCULATED RUNOFF RESULTS**

please adjust ratio so that you dont get an error here. this error inflates the actual runoff reduction %

Area ID	A	B	C	D	E	F	G	H				
UIA:RPA Area (ft <sup>2</sup> )	3,092	3,093	15,417	3,237	9,619	4,091	1,121	--				
L / W Ratio	0.22	0.22	0.06	0.23	0.10	0.26	3.11	--				
UIA / Area	0.6155	0.6153	0.6769	0.6623	0.6868	0.8685	0.8912	--				
Runoff (in)	0.00	0.00	0.00	0.00	0.00	0.15	0.20	0.00				
Runoff (ft <sup>3</sup> )	0	0	0	0	0	52	18	0				
Runoff Reduction (ft <sup>3</sup> )	79	79	435	89	275	96	23	276				

**CALCULATED WQCV RESULTS**

Area ID	A	B	C	D	E	F	G	H				
WQCV (ft <sup>3</sup> )	79	79	435	89	275	148	42	0				
WQCV Reduction (ft <sup>3</sup> )	79	79	435	89	275	96	23	0				
WQCV Reduction (%)	100%	100%	100%	100%	100%	65%	56%	0%				
Untreated WQCV (ft <sup>3</sup> )	0	0	0	0	0	52	18	0				

**CALCULATED DESIGN POINT RESULTS (sums results from all columns with the same Downstream Design Point ID)**

Downstream Design Point ID	A	B	C	D	E	F	G	H				
DCIA (ft <sup>2</sup> )	0	0	0	0	0	0	0	0				
UIA (ft <sup>2</sup> )	1,903	1,903	10,435	2,144	6,606	3,553	999	0				
RPA (ft <sup>2</sup> )	1,189	1,190	4,982	1,093	3,013	538	122	0				
SPA (ft <sup>2</sup> )	0	0	0	0	0	0	0	5,523				
Total Area (ft <sup>2</sup> )	3,092	3,093	15,417	3,237	9,619	4,091	1,121	5,523				
Total Impervious Area (ft <sup>2</sup> )	1,903	1,903	10,435	2,144	6,606	3,553	999	0				
WQCV (ft <sup>3</sup> )	79	79	435	89	275	148	42	0				
WQCV Reduction (ft <sup>3</sup> )	79	79	435	89	275	96	23	0				
WQCV Reduction (%)	100%	100%	100%	100%	100%	65%	56%	0%				
Untreated WQCV (ft <sup>3</sup> )	0	0	0	0	0	52	18	0				

**CALCULATED SITE RESULTS (sums results from all columns in worksheet)**


Total Area (ft <sup>2</sup> )	45,193
Total Impervious Area (ft <sup>2</sup> )	27,543
WQCV (ft <sup>3</sup> )	1,148
WQCV Reduction (ft <sup>3</sup> )	1,077
WQCV Reduction (%)	94%
Untreated WQCV (ft <sup>3</sup> )	71

***APPENDIX D - HYDRAULIC CALCULATIONS***

## Culvert 1 Sizing

Project Description	
Friction Method	Manning Formula
Solve For	Full Flow Diameter
Input Data	
Roughness Coefficient	0.013
Channel Slope	0.005 ft/ft
Normal Depth	11.4 in
Diameter	11.4 in
Discharge	2.21 cfs
Results	
Diameter	11.4 in
Normal Depth	11.4 in
Flow Area	0.7 ft <sup>2</sup>
Wetted Perimeter	3.0 ft
Hydraulic Radius	2.9 in
Top Width	0.00 ft
Critical Depth	7.7 in
Percent Full	100.0 %
Critical Slope	0.008 ft/ft
Velocity	3.10 ft/s
Velocity Head	0.15 ft
Specific Energy	1.10 ft
Froude Number	(N/A)
Maximum Discharge	2.38 cfs
Discharge Full	2.21 cfs
Slope Full	0.005 ft/ft
Flow Type	Subcritical
GVF Input Data	
Downstream Depth	0.0 in
Length	0.0 ft
Number Of Steps	0
GVF Output Data	
Upstream Depth	0.0 in
Profile Description	N/A
Profile Headloss	0.00 ft
Average End Depth Over Rise	0.0 %
Normal Depth Over Rise	30.0 %
Downstream Velocity	Infinity ft/s
Upstream Velocity	Infinity ft/s
Normal Depth	11.4 in
Critical Depth	7.7 in
Channel Slope	0.005 ft/ft
Critical Slope	0.008 ft/ft

The drawing indicates this is a 18in culvert. Please revise.



# Culvert 1 Sizing

Notes:

Flows from Sub-Basin 4.

## Culvert 2 Sizing

Project Description	
Friction Method	Manning Formula
Solve For	Full Flow Diameter
Input Data	
Roughness Coefficient	0.013
Channel Slope	0.005 ft/ft
Normal Depth	12.6 in
Diameter	12.6 in
Discharge	2.84 cfs
Results	
Diameter	12.6 in
Normal Depth	12.6 in
Flow Area	0.9 ft <sup>2</sup>
Wetted Perimeter	3.3 ft
Hydraulic Radius	3.1 in
Top Width	0.00 ft
Critical Depth	8.6 in
Percent Full	100.0 %
Critical Slope	0.008 ft/ft
Velocity	3.31 ft/s
Velocity Head	0.17 ft
Specific Energy	1.22 ft
Froude Number	(N/A)
Maximum Discharge	3.05 cfs
Discharge Full	2.84 cfs
Slope Full	0.005 ft/ft
Flow Type	Supercritical
GVF Input Data	
Downstream Depth	0.0 in
Length	0.0 ft
Number Of Steps	0
GVF Output Data	
Upstream Depth	0.0 in
Profile Description	N/A
Profile Headloss	0.00 ft
Average End Depth Over Rise	0.0 %
Normal Depth Over Rise	55.2 %
Downstream Velocity	Infinity ft/s
Upstream Velocity	Infinity ft/s
Normal Depth	12.6 in
Critical Depth	8.6 in
Channel Slope	0.005 ft/ft
Critical Slope	0.008 ft/ft

The drawing indicates this is a 18in culvert. Please revise.





# Culvert 2 Sizing


Notes:

Flows from Sub-Basin 5.

## Culvert 3 Sizing

Project Description	
Friction Method	Manning Formula
Solve For	Full Flow Diameter
Input Data	
Roughness Coefficient	0.013
Channel Slope	0.005 ft/ft
Normal Depth	23.0 in
Diameter	23.0 in
Discharge	14.31 cfs
Results	
Diameter	23.0 in
Normal Depth	23.0 in
Flow Area	2.9 ft <sup>2</sup>
Wetted Perimeter	6.0 ft
Hydraulic Radius	5.8 in
Top Width	0.00 ft
Critical Depth	16.5 in
Percent Full	100.0 %
Critical Slope	0.007 ft/ft
Velocity	4.95 ft/s
Velocity Head	0.38 ft
Specific Energy	2.30 ft
Froude Number	(N/A)
Maximum Discharge	15.39 cfs
Discharge Full	14.31 cfs
Slope Full	0.005 ft/ft
Flow Type	Supercritical
GVF Input Data	
Downstream Depth	0.0 in
Length	0.0 ft
Number Of Steps	0
GVF Output Data	
Upstream Depth	0.0 in
Profile Description	N/A
Profile Headloss	0.00 ft
Average End Depth Over Rise	0.0 %
Normal Depth Over Rise	55.2 %
Downstream Velocity	Infinity ft/s
Upstream Velocity	Infinity ft/s
Normal Depth	23.0 in
Critical Depth	16.5 in
Channel Slope	0.005 ft/ft
Critical Slope	0.007 ft/ft

The drawing indicates this is a 24in culvert. Please revise.



# Culvert 3 Sizing

Notes:

Flows from Sub-Basin 4, 5, and 6.

## Culvert 4 Sizing

Project Description	
Friction Method	Manning Formula
Solve For	Full Flow Diameter
Input Data	
Roughness Coefficient	0.013
Channel Slope	0.005 ft/ft
Normal Depth	11.9 in
Diameter	11.9 in
Discharge	2.48 cfs
Results	
Diameter	11.9 in
Normal Depth	11.9 in
Flow Area	0.8 ft <sup>2</sup>
Wetted Perimeter	3.1 ft
Hydraulic Radius	3.0 in
Top Width	0.00 ft
Critical Depth	8.1 in
Percent Full	100.0 %
Critical Slope	0.008 ft/ft
Velocity	3.19 ft/s
Velocity Head	0.16 ft
Specific Energy	1.15 ft
Froude Number	(N/A)
Maximum Discharge	2.67 cfs
Discharge Full	2.48 cfs
Slope Full	0.005 ft/ft
Flow Type	Supercritical
GVF Input Data	
Downstream Depth	0.0 in
Length	0.0 ft
Number Of Steps	0
GVF Output Data	
Upstream Depth	0.0 in
Profile Description	N/A
Profile Headloss	0.00 ft
Average End Depth Over Rise	0.0 %
Normal Depth Over Rise	55.2 %
Downstream Velocity	Infinity ft/s
Upstream Velocity	Infinity ft/s
Normal Depth	11.9 in
Critical Depth	8.1 in
Channel Slope	0.005 ft/ft
Critical Slope	0.008 ft/ft

The drawing indicates this is a 18in culvert. Please revise.

# Culvert 4 Sizing

Notes:

Flows from Sub-Basin 3

## Typical Ditch and Swale Cross-Section

Project Description	
Friction Method	Manning Formula
Solve For	Normal Depth
Input Data	
Roughness Coefficient	0.030
Channel Slope	0.025 ft/ft
Left Side Slope	4.000 H:V
Right Side Slope	4.000 H:V
Discharge	62.14 cfs
Results	
Normal Depth	18.6 in
Flow Area	9.6 ft <sup>2</sup>
Wetted Perimeter	12.8 ft
Hydraulic Radius	9.0 in
Top Width	12.39 ft
Critical Depth	20.6 in
Critical Slope	0.014 ft/ft
Velocity	6.47 ft/s
Velocity Head	0.65 ft
Specific Energy	2.20 ft
Froude Number	1.296
Flow Type	Supercritical
GVF Input Data	
Downstream Depth	0.0 in
Length	0.0 ft
Number Of Steps	0
GVF Output Data	
Upstream Depth	0.0 in
Profile Description	N/A
Profile Headloss	0.00 ft
Downstream Velocity	Infinity ft/s
Upstream Velocity	Infinity ft/s
Normal Depth	18.6 in
Critical Depth	20.6 in
Channel Slope	0.025 ft/ft
Critical Slope	0.014 ft/ft

velocities this high require bermuda grass or sodded grass

swales must have a minimum of 1ft freeboard

The discharge for the entire site was used to show that 2-ft deep drainage ditches and swales can accommodate the entire site's 100-year stormwater runoff. Please note though that this amount of runoff is not anticipated to ever be in just one ditch/swale.

***APPENDIX E - EOPCC***



Kimley-Horn & Associates, Inc.

Opinion of Probable Construction Cost

<b>Client:</b> Robert S. Williams	<b>Date:</b> 7/19/2021
<b>Project:</b> Peerless Farms, El Paso County, CO	<b>Prepared By:</b> MH
<b>KHA No.:</b> 196114000	<b>Checked By:</b>

<b>Sheet:</b> 1 of 1
----------------------

This OPC is not intended for basing financial decisions, or securing funding. Review all notes and assumptions. Since Kimley-Horn & Associates, Inc. has no control over the cost of labor, materials, equipment, or services furnished by others, or over methods of determining price, or over competitive bidding or market conditions, any and all opinions as to the cost herein, including but not limited to opinions as to the costs of construction materials, shall be made on the basis of experience and best available data. Kimley-Horn & Associates, Inc. cannot and does not guarantee that proposals, bids, or actual costs will not vary from the opinions on costs shown herein. The total costs and other numbers in this Opinion of Probable Cost have been rounded.

Item No.	Item Description	Quantity	Unit	Unit Price	Item Cost
1	<b>Private Storm Sewer (Non-Reimbursible)</b> 18" RCP Storm Pipe  <div style="border: 1px solid blue; background-color: cyan; padding: 5px; display: inline-block;">Include 24" RCP, riprap, FES.</div>	146	LF	\$67.00	\$9,782
Subtotal:					\$9,782
Contingency (%,+/-)				10%	\$978
<b>Project Total:</b>					<b>\$10,760</b>

**Basis for Cost Projection:**

- No Design Completed
- Preliminary Design
- Final Design

Design Engineer:

---

Mitchell O. Hess  
Registered Professional Engineer, State of Colorado No. 53916



***APPENDIX F – UNNAMED DRAINAGEWAY PHOTOGRAPHS***



**Figure 1: Storm Drain Culver Beneath Falcon Highway**



**Figure 2: Looking East Towards the Unnamed Drainageway**



**Figure 3: Looking East Towards the Unnamed Drainageway**



**Figure 4: Looking North Towards Falcon Highway**



**Figure 5: Looking Southeast at the Unnamed Drainageway**



**Figure 6: Unnamed Drainageway**



**Figure 7: Looking North at the Unnamed Drainageway**



**Figure 8: Looking East at the Unnamed Drainageway at the South End of the Site**

***APPENDIX G – EXCERPTS FROM DBPS***

**Table 6-5 Regional Detention Pond Summary**

Pond	Volume (AF)	Peak Inflow (cfs)		Peak Outflow (cfs)	
		2-yr	100-yr	2-yr	100-yr
RG-01	9.02	100	320	11	63
RG-02	170	600	4800	150	2200
RG-03	0.04	3	70	2	9
RG-04	1.07	19	140	1	55
RG-05	0.03	12	120	11	3

For the 100-year peak flow, flood impacts downstream from the regional detention pond will not increase.

**6.3.1.1. Channels**

Channels upstream of the regional detention ponds need to be sized for the future undetained 100-year peak flow rates from development, while culverts and channels downstream of regional ponds are sized for the existing 100-year peak flow rates. Proposed channel improvements along the corresponding reaches are summarized in Table 6-6.

**Table 6-6 Channel Designs for Regional Detention Alternative**

Channel	Existing 100-yr Flow (cfs)	Proposed 100-yr Flow (cfs)	Design Flow (cfs)	Channel Length (ft)	Material
Main Stem (MS-04)	1700	3400	3500	7140	Riprap
Main Stem (MS-05)	1500	3000	3000	11100	Grass
Main Stem (MS-06)	590	890	900	7330	Grass
Main Stem (MS-06)	660	930	1000	3170	Grass
Main Stem (MS-06)	720	1500	1500	4450	Grass
Main Stem (MS-06)	750	1600	2000	3330	Grass
Tributary 3 (T3-01)	720	1500	1500	10710	Grass
Tributary 4 (T4)	200	570	600	1840	Grass
Tributary 5 (T5)	150	240	300	930	Grass
Tributary 5 (T5)	270	410	500	7770	Grass
Tributary 6 (T6)	200	440	500	4270	Grass
Tributary 6 (T6)	240	570	600	3940	Grass

**6.3.1.2. Culverts**

As with the channels, culverts upstream of a regional detention pond need to be sized for the future undetained 100-year peak flow rates, while culverts and channels downstream are sized for the existing 100-year peak flow rates. Proposed culvert improvements along the corresponding reaches are summarized in Table 6-7 for the Regional Detention Alternative.

**Table 6-7 Culvert Designs for Regional Detention**

Facility Number	Road Crossing	Channel	Existing Size	Proposed 100-yr Flow (cfs)	Deficiency	Necessary Facility for Proposed 100-year Flow
405	Murr Road	Main Stem (MS-04)	66" RCP	3,400	Overtops	6-10'X6' RCBs
507	Peerless Farms Road	Tributary 3 (T3-01)	60" CMP	1200	Overtops	2-10'X6' RCBs
609	Falcon Highway	Tributary 3 (T3-02)	18" CMP	460	Overtops	2-66" RCPs
610	Falcon Highway	Tributary 4 (T4)	24" CMP	570	Overtops	2-72" RCPs
612	Falcon Highway	Tributary 5 (T5)	24" CMP	240	Overtops	72" RCP
628	Falcon Highway	Main Stem (MS-05)	2-60" CMPs	2,200	Overtops	4-10'X6' RCBs
702	Curtis Road	Tributary 6 (T6)	36" CMP	140	Overtops	60" RCP
703	Curtis Road	Main Stem (MS-06)	24" CMP	890	Overtops	2-8'X6' RCBs
704	Judge Orr Road	Main Stem (MS-06)	Blocked Culvert	830	Overtops	2-8'X6' RCBs
1001	Future Pastura Street	Main Stem (MS-06)	N/A	930	Future Road	2-8'X6' RCBs
1002	Future Arroyo Hondo Blvd. N.	Main Stem (MS-06)	N/A	930	Future Road	2-8'X6' RCBs
1003	Future Arroyo Hondo Blvd. S.	Main Stem (MS-06)	N/A	1500	Future Road	3-8'X6' RCBs
1004	Future Pastura Street	Tributary 6 (T6)	N/A	440	Future Road	2-66" RCPs
1005	Future El Vado Road	Tributary 6 (T6)	N/A	440	Future Road	2-66" RCPs
1006	Future Socorro Trail	Tributary 6 (T6)	N/A	440	Future Road	2-66" RCPs

Note: Changes recommended to other culverts under existing conditions still apply

**6.3.2. Subregional Detention**

For this alternative, subregional detention ponds are located and sized to address development as it will occur. Locations of proposed subregional detention ponds are shown in Figure 6-2 and are summarized in Table 6-8. A connectivity diagram for the sub-regional HEC-HMS model is shown in Figure 6-3.

***APPENDIX H – DRAINAGE EXHIBITS***



K:\COS\_LA\196114000 - Peerless Farms\CADD\Exhibits\Existing Drainage Map.dwg


**LEGEND**

- SITE PROPERTY LINE
- 10- EXISTING MAJOR CONTOURS
- 11- EXISTING MINOR CONTOURS
- DRAINAGE BASIN BOUNDARY
- EXISTING STORM SEWER CULVERT

A = BASIN DESIGNATION  
 B = AREA IN ACRES  
 C = 5-YR RUNOFF COEFFICIENT  
 D = 100-YR RUNOFF COEFFICIENT

# = DESIGN POINT DESIGNATION

X.XX% EXISTING GRADE SLOPE / FLOW DIRECTION



PRIVATE RESIDENTIAL (REESE, ROBERT L JR)  
 6460 PEERLESS FARMS RD  
 ~4.75 ACRES, RR-5  
 PLAT NO. 7450, LOT 1

PRIVATE RESIDENTIAL (ASHBY, ERIN L)  
 6420 PEERLESS FARMS RD  
 ~5 ACRES, RR-5  
 PLAT NO. 7450, LOT 2

PRIVATE RESIDENTIAL (CALEY, ROBERT A JR)  
 6320 PEERLESS FARMS RD  
 ~5 ACRES, RR-5  
 PLAT NO. 7450, LOT 3

PRIVATE RESIDENTIAL/AGRICULTURAL (CASE, R A)  
 119 N WAHSATCH AVE  
 ~80 ACRES, RR-2.5  
 PLAT NO. 1-2.5  
 (E2NE4 SEC 14-13-64)


PRIVATE RESIDENTIAL/AGRICULTURAL (TUTTLE, ARLENE)  
 119 N WAHSATCH AVE  
 ~283.25 ACRES, RR-2.5  
 PLAT NO. 7450, SECS 13 & 24-13-64

**Unresolved Review 1**  
 Comment:  
 - Any offsite flow from this general area? From Sagecreek South Drainage (Proj # SF85026) Map it looks like there may be some flow from here.

**Kimley»Horn**

PROJECT NAME: Peerless Farms DATE: 6/15/2023  
 PROJECT NUMBER: 196114000  
 CALCULATED BY: MOH  
 CHECKED BY: MOH

DESIGN POINT	TRIBUTARY BASINS	TRIBUTARY AREA (AC)	IMPERVIOUSNESS %	PEAK FLOWS (CFS)	
				Q5	Q100
<b>On-Site Basins</b>					
EX1	EX1	35.36	2%	5.99	38.94
EX2	EX2	4.64	4%	1.03	6.07
<b>TOTAL</b>		<b>40.00</b>	<b>2%</b>	<b>7.02</b>	<b>45.01</b>
<b>Off-Site Basins</b>					
EX3	EX3	2.63	27%	2.18	7.47
<b>TOTAL</b>		<b>2.63</b>	<b>27%</b>	<b>2.18</b>	<b>7.47</b>



EXISTING DRAINAGE MAP  
 PEERLESS FARMS  
 06/15/2023

**Kimley»Horn**

© 2023 KIMLEY-HORN AND ASSOCIATES, INC.  
 2 N NEVADA AVE., SUITE 900, COLORADO SPRINGS, 80903  
 PHONE: 719-453-0180

not shown on figure but included on UD-BMP Spreadsheet

K:\COS\_LA\196114000 - Peerless Farms\CADD\Exhibits\Drainage Map.dwg

Show riprap outlet protection. Calculations will need to be provided with final drainage report.

Label UIA/RPA and SPA areas to correlate with UD-BMP Spreadsheet. you may want to create a new figure so that you can show dimensions and not clutter this figure.

Provide calculations for this culvert.

### LEGEND

- SITE PROPERTY LINE
- 10--- PROPOSED MAJOR CONTOURS
- 11--- PROPOSED MINOR CONTOURS
- 10--- EXISTING MAJOR CONTOURS
- 11--- EXISTING MINOR CONTOURS
- DRAINAGE BASIN BOUNDARY
- PROPOSED STORM SEWER CULVERT
- EXISTING STORM SEWER CULVERT
- PROPOSED PRIVATE GRAVEL DRIVEWAY
- PROPOSED UNCONNECTED IMPERVIOUS AREA
- PROPOSED RECEIVING PERVIOUS AREA
- PROPOSED SEPARATE PERVIOUS AREA

A = BASIN DESIGNATION  
 B = AREA IN ACRES  
 C = 5-YR RUNOFF COEFFICIENT  
 D = 100-YR RUNOFF COEFFICIENT

# = DESIGN POINT DESIGNATION

X.XX% EXISTING GRADE SLOPE / FLOW DIRECTION  
 X.XX% PROPOSED GRADE SLOPE / FLOW DIRECTION


Label High points & low points

Recommend revising basin boundary line work so that the boundary of sub-basin 3 can be visible.

Label contours, it does not appear flows would be in this direction


This area should be a separate basin

Show and label base flood elevations provided by FEMA.



**Kimley»Horn**  
 PROJECT NAME: Peerless Farms DATE: 6/15/2023  
 PROJECT NUMBER: 196114000  
 CALCULATED BY: MOH  
 CHECKED BY: MOH

PROPOSED RATIONAL CALCULATIONS SUMMARY					
DESIGN POINT	TRIBUTARY BASINS	TRIBUTARY AREA (AC)	IMPERVIOUSNESS %	PEAK FLOWS (CFS)	
				Q5	Q100
<b>On-Site Basins</b>					
1	1	29.06	10%	9.03	39.34
2	2	1.78	17%	0.87	3.24
3	3	0.78	31%	0.86	2.48
4	4	0.42	57%	1.03	2.21
5	5	0.85	40%	1.12	2.84
6	6	5.55	13%	2.32	9.26
7	7	1.57	6%	0.54	2.77
<b>TOTAL</b>		<b>40.00</b>	<b>12%</b>	<b>15.77</b>	<b>62.14</b>
<b>Off-Site Basins</b>					
EX3	EX3	2.83	27%	2.18	7.47
<b>TOTAL</b>		<b>2.83</b>	<b>27%</b>	<b>2.18</b>	<b>7.47</b>



PROPOSED DRAINAGE MAP  
 PEERLESS FARMS  
 06/15/2023

**Kimley»Horn**  
 © 2023 KIMLEY-HORN AND ASSOCIATES, INC.  
 2 N NEVADA AVE., SUITE 900, COLORADO SPRINGS, 80903  
 PHONE: 719-453-0180


# V2\_Drainage Report - Preliminary.pdf Markup Summary

## Callout (22)



**Subject:** Callout  
**Page Label:** 2  
**Author:** Carlos  
**Date:** 8/2/2023 4:54:19 PM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

Please revise to "Joshua Palmer, P.E."




**Subject:** Callout  
**Page Label:** 8  
**Author:** Carlos  
**Date:** 8/3/2023 8:27:59 AM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

EX3




**Subject:** Callout  
**Page Label:** 9  
**Author:** Carlos  
**Date:** 8/3/2023 8:32:20 AM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

Please discuss where these values are obtained.  
The map summary table has 15.77 and 62.14 cfs.




**Subject:** Callout  
**Page Label:** 7  
**Author:** Carlos  
**Date:** 8/3/2023 8:30:34 AM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

EX3




**Subject:** Callout  
**Page Label:** 62  
**Author:** Carlos  
**Date:** 8/3/2023 9:15:38 AM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

The drawing indicates this is a 18in culvert. Please revise.




**Subject:** Callout  
**Page Label:** 64  
**Author:** Carlos  
**Date:** 8/3/2023 9:15:48 AM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

The drawing indicates this is a 18in culvert. Please revise.



**Subject:** Callout  
**Page Label:** 66  
**Author:** Carlos  
**Date:** 8/3/2023 9:16:37 AM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

The drawing indicates this is a 24in culvert. Please revise.



**Subject:** Callout  
**Page Label:** 68  
**Author:** Carlos  
**Date:** 8/3/2023 9:17:21 AM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

The drawing indicates this is a 18in culvert. Please revise.



**Subject:** Callout  
**Page Label:** 82  
**Author:** Carlos  
**Date:** 8/3/2023 9:30:31 AM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

Recommend revising basin boundary linework so that the boundary of sub-basin 3 can be visible.




**Subject:** Callout  
**Page Label:** 82  
**Author:** Carlos  
**Date:** 8/3/2023 10:19:41 AM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

Label contours, it does not appear flows would be in this direction



**Subject:** Callout  
**Page Label:** 82  
**Author:** Christina Prete  
**Date:** 8/7/2023 8:56:49 AM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

Label UIA:RPA and SPA areas to correlate with UD-BMP Spreadsheet. you may want to create a new figure so that you can show dimensions and not clutter this figure.




**Subject:** Callout  
**Page Label:** 60  
**Author:** Christina Prete  
**Date:** 8/7/2023 8:57:07 AM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

please adjust ratio so that you dont get an error here. this error inflates the actual runoff reduction %




**Subject:** Callout  
**Page Label:** 82  
**Author:** Christina Prete  
**Date:** 8/7/2023 8:57:46 AM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

not shown on figure but included on UD-BMP Spreadsheet




**Subject:** Callout  
**Page Label:** 10  
**Author:** Christina Prete  
**Date:** 8/7/2023 10:11:40 AM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

IF the gravel drives are roadways, they will need WQ.




**Subject:** Callout  
**Page Label:** 10  
**Author:** Christina Prete  
**Date:** 8/7/2023 10:12:10 AM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

See Planner's comment on the Prelim. Plan.




**Subject:** Callout  
**Page Label:** 8  
**Author:** CDurham  
**Date:** 8/9/2023 10:45:34 AM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

Basins do not include any proposed public road. Please remove




**Subject:** Callout  
**Page Label:** 10  
**Author:** CDurham  
**Date:** 8/9/2023 11:07:08 AM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

Flows have increased by 17.13 cfs (38%) from existing conditions. Analysis of the channel, at a minimum, will need to be provided to show the stability of the channel with existing vs proposed flows.




**Subject:** Callout  
**Page Label:** 10  
**Author:** CDurham  
**Date:** 8/9/2023 2:47:39 PM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

Flows have increased by 17.13 cfs (38%) from existing conditions. Detention will need to be provided, or some analysis showing that the flow from the development meets design requirements of a channel (Depth, velocity, Fr #, etc). Temp Sed basins could be converted and utilized as detention basins.




**Subject:** Callout  
**Page Label:** 9  
**Author:** CDurham  
**Date:** 8/9/2023 11:10:31 AM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

Under drainage fees, lists %impervious for the site as being 12%. Revise so % impervious is consistent throughout report.




**Subject:** Callout  
**Page Label:** 11  
**Author:** CDurham  
**Date:** 8/9/2023 11:11:44 AM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

, upon acceptance.



**Subject:** Callout  
**Page Label:** 82  
**Author:** CDurham  
**Date:** 8/9/2023 12:51:17 PM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**


Show culvert



**Subject:** Callout  
**Page Label:** 82  
**Author:** CDurham  
**Date:** 8/9/2023 2:49:41 PM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**


This area should be a separate basin

## Highlight (7)




**Subject:** Highlight  
**Page Label:** 7  
**Author:** Carlos  
**Date:** 8/2/2023 5:13:45 PM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

. The Property has been divided into 2 sub-basins, Sub-Basin 1 and Sub-Basin EX2



**Subject:** Highlight  
**Page Label:** 9  
**Author:** Carlos  
**Date:** 8/3/2023 8:29:01 AM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

e 2.07 and 19.06 cfs respectivel




**Subject:** Highlight  
**Page Label:** 82  
**Author:** Christina Prete  
**Date:** 8/7/2023 8:57:55 AM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

0.014 ft/1  
6.47 ft/s  
0.65 ft

**Subject:** Highlight  
**Page Label:** 70  
**Author:** Christina Prete  
**Date:** 8/7/2023 9:38:25 AM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

6.47



**Subject:** Highlight  
**Page Label:** 10  
**Author:** Christina Prete  
**Date:** 8/7/2023 10:06:59 AM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

channels to convey storm water runoff from developed and developing areas is acceptable. However, if historical storm water flows are increased, or if historical channels are unstable in their natural conditions, these channels must be adequately stabilized to prevent excessive erosion.



**Subject:** Highlight  
**Page Label:** 10  
**Author:** Christina Prete  
**Date:** 8/7/2023 10:05:46 AM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

, with the exception of stabilization at the location of the proposed ditches, are recommended.




**Subject:** Highlight  
**Page Label:** 10  
**Author:** CDurham  
**Date:** 8/9/2023 11:03:30 AM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

do not increase post-development stormwater flows

---

## PolyLine (1)



**Subject:** PolyLine  
**Page Label:** 82  
**Author:** CDurham  
**Date:** 8/9/2023 2:49:11 PM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**


Stormwater Comments Color (1)

**Subject:** Stormwater Comments Color  
**Page Label:** 1  
**Author:** Christina Prete  
**Date:** 8/7/2023 9:51:10 AM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**




Text Box (23)

**Subject:** Text Box  
**Page Label:** 81  
**Author:** Carlos  
**Date:** 8/2/2023 5:05:29 PM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**




Unresolved Review 1 Comment:  
- Any offsite flow from this general area? From Sagecreek South Drainage (Proj # SF85026) Map it looks like there may be some flow from here.

**Subject:** Text Box  
**Page Label:** 7  
**Author:** Carlos  
**Date:** 8/2/2023 5:07:13 PM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**




Unresolved Review 1 Comment:  
- The report is missing a discussion of off-site flows. Please elaborate discussion to account for offsite flows. Refer to Sagecreek South Drainage (SF85026) Map for off-site flows.

**Subject:** Text Box  
**Page Label:** 7  
**Author:** Carlos  
**Date:** 8/2/2023 5:14:11 PM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**




Please revise statement since the property has been divided into more than 2 basins.

**Subject:** Text Box  
**Page Label:** 82  
**Author:** Carlos  
**Date:** 8/2/2023 5:16:10 PM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**



Show and label base flood elevations provided by FEMA.

**Subject:** Text Box  
**Page Label:** 7  
**Author:** Carlos  
**Date:** 8/2/2023 5:19:41 PM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**



Provide channel (ditch) calculations and sizing specifications.



Discusses the combined flow from sub-basin 3 and provide identify total flows.

**Subject:** Text Box  
**Page Label:** 8  
**Author:** Carlos  
**Date:** 8/2/2023 5:20:09 PM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

Discuss the combined flow from sub-basin 3 and provide identify total flows.

Please revise/elaborate direction of flow for sub-basin 4. It appears flows would go towards EX3.

**Subject:** Text Box  
**Page Label:** 8  
**Author:** Carlos  
**Date:** 8/2/2023 5:22:40 PM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

Please revise/elaborate direction of flow for sub-basin 4. It appears flows would go towards EX3.

The report indicates runoff from other sub-basins will flow into EX3. Discuss how sub-basin EX3's flows are remaining the same in existing and proposed conditions.


**Subject:** Text Box  
**Page Label:** 8  
**Author:** Carlos  
**Date:** 8/3/2023 8:32:08 AM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

The report indicates runoff from other sub-basins will flow into EX3. Discuss how sub-basin EX3's flows are remaining the same in existing and proposed conditions.

Item No. Item Description  
1 Private Storm Sewer (Non-Reimbursable) 18" RCP Storm Pipe  
Include 24" RCP, riprap, FES.  
Basis for Cost Projection:

**Subject:** Text Box  
**Page Label:** 72  
**Author:** Carlos  
**Date:** 8/3/2023 9:20:00 AM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

Include 24" RCP, riprap, FES.



**Subject:** Text Box  
**Page Label:** 82  
**Author:** Carlos  
**Date:** 8/3/2023 9:29:07 AM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

Provide calculations for this culvert.

Discuss temporary sediment basins shown on the GEC plan and provide sizing calculations.

**Subject:** Text Box  
**Page Label:** 12  
**Author:** Carlos  
**Date:** 8/3/2023 9:51:07 AM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**


Discuss temporary sediment basins shown on the GEC plan and provide sizing calculations.

Which answer best describes the effect of the disturbance and succession process on the ecosystem? The response and knowledge are consistent with the average performance level in 2023.

View of the annotated and highlighted text in the document.

**Subject:** Text Box  
**Page Label:** 12  
**Author:** Carlos  
**Date:** 8/3/2023 10:20:35 AM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

Discuss the amount of land disturbance for the proposed road and infrastructure.



**Subject:** Text Box  
**Page Label:** 10  
**Author:** Christina Prete  
**Date:** 8/7/2023 10:10:44 AM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

IF the gravel drives are to remain driveways: add that the portion of the driveway that falls within the property line must be included as part of the 10% impervious area on the lot.

100000 (1/1/2023 11:27:30 AM)

DATE	DESCRIPTION	AMOUNT	BALANCE
11/1/2022	OPENING BALANCE	100000	100000
11/1/2022	SALES	10000	110000
11/1/2022	PAYROLL	(10000)	100000
11/1/2022	RENT	(10000)	90000
11/1/2022	UTILITIES	(5000)	85000
11/1/2022	DEPRECIATION	(5000)	80000
11/1/2022	INVESTMENT	50000	130000
11/1/2022	SALES	10000	140000
11/1/2022	PAYROLL	(10000)	130000
11/1/2022	RENT	(10000)	120000
11/1/2022	UTILITIES	(5000)	115000
11/1/2022	DEPRECIATION	(5000)	110000
11/1/2022	INVESTMENT	50000	160000
11/1/2022	SALES	10000	170000
11/1/2022	PAYROLL	(10000)	160000
11/1/2022	RENT	(10000)	150000
11/1/2022	UTILITIES	(5000)	145000
11/1/2022	DEPRECIATION	(5000)	140000
11/1/2022	INVESTMENT	50000	190000
11/1/2022	SALES	10000	200000
11/1/2022	PAYROLL	(10000)	190000
11/1/2022	RENT	(10000)	180000
11/1/2022	UTILITIES	(5000)	175000
11/1/2022	DEPRECIATION	(5000)	170000
11/1/2022	INVESTMENT	50000	220000
11/1/2022	SALES	10000	230000
11/1/2022	PAYROLL	(10000)	220000
11/1/2022	RENT	(10000)	210000
11/1/2022	UTILITIES	(5000)	205000
11/1/2022	DEPRECIATION	(5000)	200000
11/1/2022	INVESTMENT	50000	250000
11/1/2022	SALES	10000	260000
11/1/2022	PAYROLL	(10000)	250000
11/1/2022	RENT	(10000)	240000
11/1/2022	UTILITIES	(5000)	235000
11/1/2022	DEPRECIATION	(5000)	230000
11/1/2022	INVESTMENT	50000	280000
11/1/2022	SALES	10000	290000
11/1/2022	PAYROLL	(10000)	280000
11/1/2022	RENT	(10000)	270000
11/1/2022	UTILITIES	(5000)	265000
11/1/2022	DEPRECIATION	(5000)	260000
11/1/2022	INVESTMENT	50000	310000
11/1/2022	SALES	10000	320000
11/1/2022	PAYROLL	(10000)	310000
11/1/2022	RENT	(10000)	300000
11/1/2022	UTILITIES	(5000)	295000
11/1/2022	DEPRECIATION	(5000)	290000
11/1/2022	INVESTMENT	50000	340000
11/1/2022	SALES	10000	350000
11/1/2022	PAYROLL	(10000)	340000
11/1/2022	RENT	(10000)	330000
11/1/2022	UTILITIES	(5000)	325000
11/1/2022	DEPRECIATION	(5000)	320000
11/1/2022	INVESTMENT	50000	370000
11/1/2022	SALES	10000	380000
11/1/2022	PAYROLL	(10000)	370000
11/1/2022	RENT	(10000)	360000
11/1/2022	UTILITIES	(5000)	355000
11/1/2022	DEPRECIATION	(5000)	350000
11/1/2022	INVESTMENT	50000	400000
11/1/2022	SALES	10000	410000
11/1/2022	PAYROLL	(10000)	400000
11/1/2022	RENT	(10000)	390000
11/1/2022	UTILITIES	(5000)	385000
11/1/2022	DEPRECIATION	(5000)	380000
11/1/2022	INVESTMENT	50000	430000
11/1/2022	SALES	10000	440000
11/1/2022	PAYROLL	(10000)	430000
11/1/2022	RENT	(10000)	420000
11/1/2022	UTILITIES	(5000)	415000
11/1/2022	DEPRECIATION	(5000)	410000
11/1/2022	INVESTMENT	50000	460000
11/1/2022	SALES	10000	470000
11/1/2022	PAYROLL	(10000)	460000
11/1/2022	RENT	(10000)	450000
11/1/2022	UTILITIES	(5000)	445000
11/1/2022	DEPRECIATION	(5000)	440000
11/1/2022	INVESTMENT	50000	490000
11/1/2022	SALES	10000	500000
11/1/2022	PAYROLL	(10000)	490000
11/1/2022	RENT	(10000)	480000
11/1/2022	UTILITIES	(5000)	475000
11/1/2022	DEPRECIATION	(5000)	470000
11/1/2022	INVESTMENT	50000	520000
11/1/2022	SALES	10000	530000
11/1/2022	PAYROLL	(10000)	520000
11/1/2022	RENT	(10000)	510000
11/1/2022	UTILITIES	(5000)	505000
11/1/2022	DEPRECIATION	(5000)	500000
11/1/2022	INVESTMENT	50000	550000
11/1/2022	SALES	10000	560000
11/1/2022	PAYROLL	(10000)	550000
11/1/2022	RENT	(10000)	540000
11/1/2022	UTILITIES	(5000)	535000
11/1/2022	DEPRECIATION	(5000)	530000
11/1/2022	INVESTMENT	50000	580000
11/1/2022	SALES	10000	590000
11/1/2022	PAYROLL	(10000)	580000
11/1/2022	RENT	(10000)	570000
11/1/2022	UTILITIES	(5000)	565000
11/1/2022	DEPRECIATION	(5000)	560000
11/1/2022	INVESTMENT	50000	610000
11/1/2022	SALES	10000	620000
11/1/2022	PAYROLL	(10000)	610000
11/1/2022	RENT	(10000)	600000
11/1/2022	UTILITIES	(5000)	595000
11/1/2022	DEPRECIATION	(5000)	590000
11/1/2022	INVESTMENT	50000	640000
11/1/2022	SALES	10000	650000
11/1/2022	PAYROLL	(10000)	640000
11/1/2022	RENT	(10000)	630000
11/1/2022	UTILITIES	(5000)	625000
11/1/2022	DEPRECIATION	(5000)	620000
11/1/2022	INVESTMENT	50000	670000
11/1/2022	SALES	10000	680000
11/1/2022	PAYROLL	(10000)	670000
11/1/2022	RENT	(10000)	660000
11/1/2022	UTILITIES	(5000)	655000
11/1/2022	DEPRECIATION	(5000)	650000
11/1/2022	INVESTMENT	50000	700000
11/1/2022	SALES	10000	710000
11/1/2022	PAYROLL	(10000)	700000
11/1/2022	RENT	(10000)	690000
11/1/2022	UTILITIES	(5000)	685000
11/1/2022	DEPRECIATION	(5000)	680000
11/1/2022	INVESTMENT	50000	730000
11/1/2022	SALES	10000	740000
11/1/2022	PAYROLL	(10000)	730000
11/1/2022	RENT	(10000)	720000
11/1/2022	UTILITIES	(5000)	715000
11/1/2022	DEPRECIATION	(5000)	710000
11/1/2022	INVESTMENT	50000	760000
11/1/2022	SALES	10000	770000
11/1/2022	PAYROLL	(10000)	760000
11/1/2022	RENT	(10000)	750000
11/1/2022	UTILITIES	(5000)	745000
11/1/2022	DEPRECIATION	(5000)	740000
11/1/2022	INVESTMENT	50000	790000
11/1/2022	SALES	10000	800000
11/1/2022	PAYROLL	(10000)	790000
11/1/2022	RENT	(10000)	780000
11/1/2022	UTILITIES	(5000)	775000
11/1/2022	DEPRECIATION	(5000)	770000
11/1/2022	INVESTMENT	50000	820000
11/1/2022	SALES	10000	830000
11/1/2022	PAYROLL	(10000)	820000
11/1/2022	RENT	(10000)	810000
11/1/2022	UTILITIES	(5000)	805000
11/1/2022	DEPRECIATION	(5000)	800000
11/1/2022	INVESTMENT	50000	850000
11/1/2022	SALES	10000	860000
11/1/2022	PAYROLL	(10000)	850000
11/1/2022	RENT	(10000)	840000
11/1/2022	UTILITIES	(5000)	835000
11/1/2022	DEPRECIATION	(5000)	830000
11/1/2022	INVESTMENT	50000	880000
11/1/2022	SALES	10000	890000
11/1/2022	PAYROLL	(10000)	880000
11/1/2022	RENT	(10000)	870000
11/1/2022	UTILITIES	(5000)	865000
11/1/2022	DEPRECIATION	(5000)	860000
11/1/2022	INVESTMENT	50000	910000
11/1/2022	SALES	10000	920000
11/1/2022	PAYROLL	(10000)	910000
11/1/2022	RENT	(10000)	900000
11/1/2022	UTILITIES	(5000)	895000
11/1/2022	DEPRECIATION	(5000)	890000
11/1/2022	INVESTMENT	50000	940000
11/1/2022	SALES	10000	950000
11/1/2022	PAYROLL	(10000)	940000
11/1/2022	RENT	(10000)	930000
11/1/2022	UTILITIES	(5000)	925000
11/1/2022	DEPRECIATION	(5000)	920000
11/1/2022	INVESTMENT	50000	970000
11/1/2022	SALES	10000	980000
11/1/2022	PAYROLL	(10000)	970000
11/1/2022	RENT	(10000)	960000
11/1/2022	UTILITIES	(5000)	955000
11/1/2022	DEPRECIATION	(5000)	950000
11/1/2022	INVESTMENT	50000	1000000

**Subject:** Text Box  
**Page Label:** 60  
**Author:** Christina Prete  
**Date:** 8/7/2023 8:56:12 AM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

will review UIA:RPA areas with the next submittal and updated figure

11 velocities this high require bermuda grass or sodded grass.

**Subject:** Text Box  
**Page Label:** 70  
**Author:** Christina Prete  
**Date:** 8/7/2023 9:41:49 AM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

velocities this high require bermuda grass or sodded grass

4 swales must have a minimum of 1ft freeboard

**Subject:** Text Box  
**Page Label:** 70  
**Author:** Christina Prete  
**Date:** 8/7/2023 9:50:57 AM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

swales must have a minimum of 1ft freeboard

3 provide riprap outlet protection calcs.

**Subject:** Text Box  
**Page Label:** 10  
**Author:** Christina Prete  
**Date:** 8/7/2023 10:06:47 AM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

provide riprap outlet protection calcs.



BFE's shown on this exhibit need to be included on drainage maps, preliminary plan and GEC plans.

**Subject:** Text Box  
**Page Label:** 48  
**Author:** CDurham  
**Date:** 8/9/2023 11:14:32 AM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**


BFE's shown on this exhibit need to be included on drainage maps, preliminary plan and GEC plans.

Label High points & low points

**Subject:** Text Box  
**Page Label:** 82  
**Author:** CDurham  
**Date:** 8/9/2023 12:51:03 PM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**


Label High points & low points

State flows at this crossing and where they came from (FEMA, DBPS, etc)



**Subject:** Text Box  
**Page Label:** 81  
**Author:** CDurham  
**Date:** 8/9/2023 12:57:38 PM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

State flows at this crossing and where they came from (FEMA, DBPS, etc)



Include BFE's

**Subject:** Text Box  
**Page Label:** 81  
**Author:** CDurham  
**Date:** 8/9/2023 12:58:00 PM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

Include BFE's

Label High & Low points

**Subject:** Text Box  
**Page Label:** 81  
**Author:** CDurham  
**Date:** 8/9/2023 12:59:26 PM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

Label High & Low points

Show riprap outlet protection. Calculations will need to be provided with final drainage report.

**Subject:** Text Box  
**Page Label:** 82  
**Author:** CDurham  
**Date:** 8/9/2023 1:02:17 PM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

Show riprap outlet protection. Calculations will need to be provided with final drainage report.