

**PRELIMINARY DRAINAGE REPORT
for
FALCON MARKETPLACE**

El Paso County, Colorado

September 27, 2018

Prepared for:

LG HI Falcon, LLC.
3953 Maple Ave, #290
Dallas, TX 75219
Contact: Ben Hummel
(214) 416-9820

Prepared by:

Drexel, Barrell & Co.
3 South 7th Street
Colorado Springs, CO 80905
Contact: Tim McConnell, P.E.
(719) 260-0887

TABLE OF CONTENTS

1.0	CERTIFICATION STATEMENTS	III
2.0	PURPOSE	1
3.0	GENERAL SITE DESCRIPTION.....	1
4.0	DBPS ANALYSIS	3
5.0	EXISTING CONDITION HYDROLOGY SUMMARY	7
6.0	PROPOSED HYDROLOGY (RATIONAL METHOD) & HYDRAULIC SUMMARY	8
7.0	PROPOSED DETENTION/WATER QUALITY FACILITIES.....	11
8.0	FOUR-STEP PROCESS.....	11
9.0	GEOTECHNICAL HAZARDS	12
10.0	EXISTING ONSITE UTILITY INFRASTRUCTURE	12
11.0	CONDITIONAL LETTER OF MAP REVISION (CLOMR)	13
12.0	DRAINAGE/BIDGE FEES	13
13.0	CONCLUSIONS.....	14
14.0	REFERENCES	14

APPENDICES

VICINITY MAP
SOILS MAP
FLOODPLAIN MAP
HYDROLOGY CALCULATIONS
HYDRAULIC CALCULATIONS
DBPS EXCERPTS
CLOMR EXCERPTS
CLOMR APPROVAL
DRAINAGE MAPS

PRELIMINARY DRAINAGE REPORT
for
FALCON MARKETPLACE
Falcon, Colorado

1.0 CERTIFICATION STATEMENTS

ENGINEER'S STATEMENT

The attached drainage plan and report were prepared under my direction and supervision and are correct to the best of my knowledge and belief. Said drainage report has been prepared according to the criteria established by El Paso County for drainage reports, and said report is in conformity with the master plan of the drainage basin. I accept responsibility for any liability caused by any negligent acts, errors or omission on my part in preparing this report.

Tim D. McConnell, P.E.
Colorado P.E. License No. 33797
For and on Behalf of Drexel, Barrell & Co.



9-4-18

DEVELOPER'S STATEMENT

I, the developer have read and will comply with all the requirements specified in this drainage report and plan.

Business Name: LG HI Falcon, LLC.

By:


Ben Hummel
Owner
3953 Maple Ave, #290
Dallas, TX 75219

8-31-18

Title:

Address:

EL PASO COUNTY

Filed in accordance with the requirements of the El Paso County Land Development Code, Drainage Criteria Manual Volumes 1 and 2, and the Engineering Criteria Manual, as amended.

For the County Engineer
CONDITIONS:

Approved by Elizabeth Nijkamp El Paso County Planning and Community Development on behalf of Jennifer Irvine, County Engineer, ECM Administrator	Date
10/09/2018 9:48:07 AM	



PRELIMINARY DRAINAGE REPORT
for
FALCON MARKETPLACE
Falcon, Colorado

2.0 PURPOSE

This report is prepared by Drexel, Barrel & Co in support of the Falcon Marketplace project. The purpose of this report is to identify onsite and offsite drainage patterns, storm sewer, inlet locations, and areas tributary to the site, and to safely route developed storm water runoff to adequate outfall facilities.

3.0 GENERAL SITE DESCRIPTION

Location

The site is located at the northwest corner of E. Woodmen Road and Meridian Road - the SE 1/4 of the SE 1/4 of Section 1, Township 13 S, Range 65 W of the 6th P.M., El Paso County, Colorado.

There is one existing home on the site, and several out buildings. The site is bounded on the north by Falcon Ranchettes single family residential, the west by Courtyards at Woodmen Hills West single family residential, the east by Meridian Road, and on the south by E. Woodmen Road.

There are no existing irrigation facilities on the project site.

Existing Site Conditions

The site is approximately 35.7 acres in size and is proposed as commercial use, with one large anchor lot and several smaller outlying lots. The majority of the site is currently undeveloped and is covered with native grass and vegetation. It is gently sloping from the north to south. Offsite flows concentrate into the Unnamed Tributary to Black Squirrel Creek (UTBSC) through the center of the site, and on to a double set of triple 48" diameter culverts under E. Woodmen Road.

Proposed Site Conditions

Falcon Marketplace is a proposed commercial development, consisting of a main anchor, junior anchor and several outlying lots. Falcon Market Place bisects the project, providing access from E. Woodmen Road, Woodmen Frontage Road and Eastonville Road to the north east.

Soils

According to the Soil Survey of El Paso County Area, Colorado, prepared by the U.S. Department of Agriculture Soil Conservation Service, the site is partially underlain by the Blakeland loamy sand (Soil No. 8), and predominantly by the Blakeland-Fluvaquentic Haplaquolis (Soil No. 9), and the Columbine gravelly sandy loam (Soil No. 19). All soils are type 'A' hydrologic soil group. See appendix for map.

Climate

This area of El Paso County can be described as the foothills, with total precipitation amounts typical of a semi-arid region. Winters are generally cold and dry, and summers relatively warm and dry. Precipitation ranges from 12 to 14 inches per year, with the majority of this moisture occurring in the spring and summer in the form of rainfall. Thunderstorms are common during the summer months.

Floodplain Statement

The effective floodplain, Zone A limits, for the Unnamed Tributary to Black Squirrel Creek (UTBSC), in the vicinity of the Falcon Marketplace project, are defined on the FIRM for El Paso County, Colorado and Unincorporated Areas, Map Number 8041CO575F, Effective Date March 17, 1997.

The effective floodplain, Zone A limits, for the UTBSC, in the vicinity of the Falcon Marketplace development, were modified by a LOMR, Case No. 12-08-0579P, Woodmen Road Widening Project – Powers Boulevard to US-24, Effective Date February 28, 2013.

FEMA issued Preliminary FIS and FIRM documents for El Paso County, Colorado and Incorporated Areas dated July 29, 2015. The preliminary FIRM, Map Number 08041CO553G, incorporates the LOMR revised Zone A floodplain identified above. See appendix for supporting information.

A CLOMR to modify the effective floodplain was approved by FEMA, Case No. 17-08-0074R (May 26, 2017).

Previous Drainage Studies

The site is located within the Middle Tributary Basin of the Falcon Drainage Basin, as studied in the Falcon Drainage Basin Planning Study, prepared by Matrix Design Group, September, 2015. DBPS recommendations are presented later in this report.

4.0 DBPS ANALYSIS

Existing Conditions

The Falcon DBPS completed hydrologic analysis for the Falcon Basin Watershed, using HEC-HMS v.3.5 software, for historical, existing and future land use conditions by applying a 24-hour storm event with 2-, 5-, 10-, 25-, 50-, and 100-year recurrence intervals and current drainage conveyance infrastructure.

As mentioned earlier, offsite flows from two unnamed tributaries to Black Squirrel Creek (West Branch and East Branch) converge and combine with onsite flows from the Falcon Marketplace site, and travel on to a double set of triple 48" diameter culverts under E. Woodmen Road.

The following table details the HEC-HMS analysis of existing conditions across the Falcon Marketplace development.

Peak Discharges for the Existing Condition at Points of Interest in vicinity of Falcon Marketplace Development (DBPS)

Location	Existing Conditions (source: Falcon Basin, Drainage Planning Study, HEC-HMS model)							
	HEC-HMS Element	Area (sq mi)	Basin/ Design Point	Peak Flow (cfs)				
				2-yr	5-yr	10-yr	25-yr	50-yr
West Branch at North Property Line of Falcon Marketplace	RMT062	0.29	1	1	11	25	62	110
East Branch at North Property Line of Falcon Marketplace	RMT064	0.67	2	50	140	230	390	490
Local Basin	MT060	0.19	MT060	8	21	33	62	80
Convergence of West and East Branch at Falcon Marketplace	JMT060	1.16	3	54	160	250	450	560
Local Basin	MT070	0.2	MT070	10	23	34	61	77
E. Woodmen Road, South Property Line of Falcon Marketplace	JMT070	1.36	4	61	180	280	510	630
								760

The DBPS flow rates shown in the table above were used as the basis of the existing condition analysis of the Falcon Marketplace development. Site specific basins have been allocated, and referenced on the existing conditions map in the appendix.

Future Conditions

The DBPS also studied the future condition, with the existing drainage infrastructure currently in place. To accommodate the future condition, the DBPS recommends drainage infrastructure improvements, including Sub-Regional Pond SR4 which was identified to be installed on the Falcon Marketplace property. Pond SR4 will be renamed Pond #1 for the purposes of this report, and was conceptually sized with the parameters shown below:

Falcon DBPS, Pond #1 (SR4) – Sizing Parameters

Parameter	Value
100-year storage volume	19 ac-ft
Q _{2in}	130 cfs
Q _{2out}	27 cfs
Q _{100in}	1,000 cfs
Q _{100out}	730 cfs

The DBPS model was updated to reflect the proposed site design and Pond #1's stage/storage/discharge characteristics were updated using Urban Drainage UD-Detention software. This analysis was then input into the HEC-HMS hydrologic model.

Peak Discharges for the Future Developed Conditions at Points of Interest in vicinity of Falcon Marketplace Development (DBPS)

Location	Future Conditions, with existing drainage infrastructure and Pond SR4 (Pond #1) (source: Falcon Basin, DBPS, HEC-HMS model)							
	HEC-HMS Element	Area (sq mi)	Basin/Design Point	Peak Flow (cfs)				
				2-yr	5-yr	10-yr	25-yr	50-yr
West Branch at North Property Line of Falcon Marketplace	RMT062	0.29	1	5	21	34	64	81
East Branch at North Property Line of Falcon Marketplace	RMT064	0.67	2	121	273	373	591	712
Local Basin	MT060	0.19	MT060	30	59	83	137	167
Sub Regional Pond SR4 (Pond #1) Inflow		1.16		133	310	431	697	847
Sub Regional Pond SR4 (Pond #1) Outflow	JMT060	1.16	3	27	142	246	467	595
Local Basin	MT070	0.2	MT070	25	50	69	114	139
E. Woodmen Road, South Property Line of Falcon Marketplace	JMT070	1.36	4	31	162	281	535	685
								844

As shown in the above table, the 100-year discharge to E. Woodmen Road at the south property line, with pond #1 is 844-cfs. To be in conformance with the DBPS recommendations, the allowable 100-year discharge from the Falcon Marketplace development can be no greater than 844-cfs.

Proposed Development & CLOMR Study

On October 17, 2016 a CLOMR, prepared by Drexel, Barrell & Co., was submitted to FEMA. The CLOMR specifically details how the Falcon Marketplace development proposes filling the site and rerouting the UTBSC. This will be accomplished by intercepting the existing creek at the north property line and conveying it via a rundown into a sub-regional detention pond (SR4 - Pond #1), as recommended by the DBPS.

Pond #1 Inflow/Outflow/Stage/Storage Parameters

Recurrence Interval	Pond Inflow (cfs)	Pond Outflow (cfs)	Water Surface Elevation (ft)	Storage Volume (ac-ft)
100-year	1,016	644	6897.0	26.6
50-year	847	481	6896.4	24.5
25-year	697	338	6895.8	22.5
10-year	431	106	6894.6	18.3
5-year	310	52	6894.2	17.0
2-year	133	12	6891.8	10.0

Peak discharges resulting from proposed Pond #1 are summarized above.

Pond #1 will discharge to a new 96" RCP storm drainage system which will flow from south to east across the property and discharge to a section of grass-lined channel that parallels the south perimeter of the property.

Onsite runoff generated from the site, represented as a portion of MT070 in the HEC-HMS model, will be conveyed via curb and gutter, and storm sewer to proposed water quality basins at the south end of the site. The water quality basins will discharge into the open grass-lined channel along the south perimeter of the site.

Specific developed runoff quantities for the site were determined using the Rational Method and are discussed further in section 5.0 of this report.

The open grass-lined channel will then discharge into two sets of existing triple 48" culverts under E. Woodmen Road. Detention pond #1, 96" pipe and open channel are all designed to convey the full 100-year discharge.

No changes to the existing culverts under E. Woodmen Road are proposed. HY-8 software was used to quantify a 765-cfs total capacity of the existing culverts with the culvert headwater at the elevation of the north edge of the roadway pavement.

Specific developed runoff quantities for the site were determined using the Rational Method and are discussed further in section 5.0 of this report.

Peak Discharges at Points of Interest of Falcon Marketplace

Location	Future Conditions, with existing drainage infrastructure + Falcon Marketplace Development (Source: Falcon Marketplace, HEC-HMS model)							
	HEC-HMS Element	Area (sq mi)	Peak Flow (cfs)					
			2-yr	5-yr	10-yr	25-yr	50-yr	100-yr
West branch at North Property Line of Falcon Marketplace	RMT062	0.29	5	21	34	64	81	99
East branch at North Property Line of Falcon Marketplace	RMT064	0.67	121	273	373	591	712	847
Local Basin	MT060	0.19	30	59	83	137	167	199
Sub Regional Pond SR4 Inflow	-	1.16	133	310	431	697	847	1016
Sub Regional Pond SR4 Outflow	JMT060	1.16	12	52	106	338	481	644
Local Basin	MT070	0.20	30	57	79	129	157	186
E. Woodmen Road, South Property Line of Falcon Marketplace	JMT070	1.36	32	62	119	398	562	757

Per the above table, the 100-year discharge at the south property line is 757-cfs, which is less than the capacity of the existing culverts (765-cfs), and also less than the maximum allowable 100-year discharge (844-cfs) identified by the DBPS.

5.0 EXISTING CONDITION HYDROLOGY SUMMARY

In addition to the DBPS, a site specific analysis of the existing conditions was completed. The flows determined by the DBPS for the creek tributary entering the site from the north, were used in combination with rational method analysis for the surrounding onsite/offsite flows.

O1 represents 32.5 acres of 5-acre lots to the north of the Courtyards at Woodmen Hills West, northwest of the Falcon Marketplace site. A swale along the northern boundary of the Courtyards at Woodmen Hills West development is proposed to capture runoff from the north. Runoff rates of $Q_5=10.3$ cfs and $Q_{100}=30.2$ cfs discharge on to the northwest corner of the Falcon Marketplace site. This flow is to be routed into the proposed pond SR4.

O1A represents the easterly boundary of the Courtyards at Woodmen Hills West and is currently graded to discharge to the east, onto the Falcon Marketplace site as overland flow.

Basin O2 covers the westerly lanes of Meridian Road that discharge into a roadside swale and travel southerly towards a curb cut. The curb cut discharges into the SE corner of the Falcon Marketplace site.

Existing storm sewer infrastructure in the median of Meridian Road was identified as part of this project. Currently, flows generated in the Meridian Road median travel in open landscaped swales, and culverts under roadway intersections, from Woodmen Hills Road to approximately 500 ft north of E. Woodmen Road. The flow approaching E. Woodmen Road is intercepted by a Type D inlet and piped to the south.

Basin O3 generates flows along E. Woodmen Road adjacent to the Falcon Marketplace project site, and from a high point approximately 500 ft to the west, traveling easterly via roadside ditch towards the existing triple 48" culverts.

Existing Design Point 1 combines the flows, to result in $Q_5=196.7$ cfs and $Q_{100}=780.4$ cfs culminating at the existing triple 48" culverts under E. Woodmen Road. This value is comparable to the DBPS determined $Q_{100}=757$ cfs determined for the same location.

The two sets of existing triple 48" RCP culverts discharge to the south across E. Woodmen Road, into an existing storm sewer system. A Type D grate inlet in the median of E. Woodmen Road intercepts median flows and also discharges to the south.

6.0 PROPOSED HYDROLOGY (RATIONAL METHOD) & HYDRAULIC SUMMARY

For the purposes of site specific analysis, the project site has been divided into several grouped drainage basins as shown on the proposed drainage plan. Five Design Points have been analyzed for sizing of the drainage facilities.

The Rational Method was used to determine runoff quantities for the 5- and 100-year storm recurrence intervals. Urban Drainage UD-Detention, UD-Inlet and HydraFlow were also used to identify pond and storm system sizing (see appendix for calculations), and below for a summary runoff table.

Rational Method Runoff Summary

BASIN	Area (Ac.)	Q ₅ (CFS)	Q ₁₀₀ (CFS)
A1	0.69	0.2	1.4
A2	1.50	5.2	10.2
A3	4.82	1.2	8.8
A4	1.52	5.6	10.2
B1	0.54	2.4	4.3
B2	1.18	4.9	8.9
B3	1.17	4.3	7.9
B4	3.32	9.6	17.6
B5	0.32	1.5	2.6
B6	0.31	1.4	2.5
B7	0.72	3.0	5.4
B8	0.17	0.8	1.4
B9	2.25	8.8	16.1
B10	0.18	0.8	1.5
B11	0.20	0.9	1.6
B12	1.76	6.1	11.2
B13	0.21	1.0	1.7
B14	4.34	16.2	29.6
B15	0.16	0.7	1.3
B16	0.34	1.5	2.6

BASIN	Area (Ac.)	Q ₅ (CFS)	Q ₁₀₀ (CFS)
B17	2.16	8.9	16.2
B18	2.90	11.3	20.7
B19	2.02	5.4	11.1
B20	1.65	0.4	3.3
C1	4.88	8.2	19.1
C2	0.24	1.1	2.0
C3	0.64	0.5	1.7
C4	0.09	0.0	0.2
C5	0.12	0.5	1.0
C6	0.16	0.7	1.3
C7	1.13	2.9	6.1
C8	3.33	5.0	11.8
DP	Area (Ac.)	Q ₅ (CFS)	Q ₁₀₀ (CFS)
DP1	2.89	10.9	19.8
DP2	1.03	4.4	8.0
DP3	2.43	9.6	16.1
DP4	25.90	66.3	124.3
DP5	45.02	-	754.0

A-group basins represent flows at the northern portion of the site that will be intercepted by Pond #1, and the 96" outfall. Flows generated from offsite basins have already been established by the aforementioned CLOMR study.

At-grade 10' Type R Inlet IA1 is located at the NW corner of the Meridian Road and Eastonville Road intersection, and is sized to intercept flows from Basin A2. Bypass flows from Inlet IA1, combine with flow from Basin A1 and continue on to 10' Type R sump Inlet IA2. Type C Area Inlet IA3 is designed to intercept runoff generated by the depressed roundabout circle, the intention is to utilize the circle for snow stockpiling during winter storms.

As discussed, a 10' swale along the Courtyards at Woodmen Hills West northern boundary discharges offsite flows ($Q_5=8.9$ cfs and $Q_{100}=21.8$ cfs) onto the Falcon Marketplace site. These flows will be directed into the sub-regional pond #1 via concrete swale rundown.

B-group basins represent the bulk of the site, with flows generally travelling southwards via curb and gutter, and storm sewer towards Pond #2. Pond #2 has been designed as a 1.1 ac-ft basin, sufficient to detain and release the WQCV generated by the site.

DP1 ($Q_5 = 10.9$ cfs, $Q_{100} = 19.8$ cfs) is located at the confluence of basins B1-B3 to determine the required size of at-grade 10' Type R Inlet IB1. At-grade 10' Type R Inlet IB2 intercepts flow from Basin B5.

DP2 ($Q_5 = 4.4$ cfs, $Q_{100} = 8.0$ cfs, is located further south down Falcon Market Place, and along with bypass flow from Inlet IB1, is used to determine at-grade 10' Type R Inlet IB3 sizing. At-grade 10' Type R Inlet IB4 intercepts flow from Basin B8, and bypass flow from Inlet IB2.

DP3 ($Q_5 = 9.6$ cfs, $Q_{100} = 16.1$ cfs) is used to determine 10' Type R sump Inlet sizing, and 24" storm stub sizing to the north. 10' Type R sump Inlet IB6 intercepts flows from Basin B11 and bypass from Inlet IB3. 10' Type R at-grade inlet IB7 with a 24" storm stub to the north, intercepts flow from Basin B12 and B13. 10' Type R sump inlet IB8 with a 24" storm stub to the north, intercepts bypass from Inlet IB7 and flow from Basin B14 and B15. 10' Type R sump Inlet IB9 intercepts flow from Basin B16. Flows continue via storm sewer system on to Water Quality Pond #2 to the south. DP4 ($Q_5 = 66.3$ cfs, $Q_{100} = 124.3$ cfs) is located at Water Quality Pond #2.

Flows generated by Meridian Road, basin B19 ($Q_5 = 5.4$ cfs, $Q_{100} = 11.1$ cfs) will be intercepted via a relocated curb cut, and directed to Pond #2 via riprap swale/rundown.

C-group basins cover the western and southern portions of the site, along with flows off E. Woodmen Road that will discharge into the open channel. Flows from Basin C1 converge at a small water quality basin (Pond #3 - 0.20 ac-ft). Basin C2 flows will be intercepted by a 10' Type R sump Inlet IC1 that will discharge into Pond #3.

Runoff from Basin C3 will be intercepted by an open 18" FES, discharging into Pond #3 for Water Quality. Outflow from Pond #3 enters a 24" RCP storm sewer and discharges into the 96" line, ultimately reaching the open channel. Type C area Inlet IC3 is located in the depressed roundabout circle, as with the roundabout to the NE the intention is to utilize the circle for snow stockpiling during winter storms. 5' Type R at-grade Inlet IC4 collects flow from Basin C5, and 10' Type R sump Inlet IC5 intercepts flows from Basin C6. Both inlets discharge to the east.

The HEC-HMS study determined that allowable flow generated by the site (B & C-group basins) cannot exceed $Q_{100}=113$ -cfs. This represents the difference between the open channel flow and discharge from the 96" pipe (757 cfs – 644 cfs = 113 cfs).

Design Point 5 ($Q_{100} = 754.0$ cfs) represents the entirety of the site flow reaching the culverts under E. Woodmen Road. Outflow from the 96" storm pipe, and discharge from Ponds 2 & 3 are combined with basins C3-6, to generate flows of 754 cfs. This flow is within the HEC-HMS design parameter of 757 cfs and as such will not negatively impact the downstream facilities.

HY-8 software was used to analyze the hydraulic performance of the existing culverts. The table below lists the discharge/headwater relationship for the two sets of culverts, and identifies the assumed maximum allowable discharge through each of the two sets of culverts assuming the maximum allowable headwater elevation is equal to the elevation of the edge of roadway asphalt along the north side of E. Woodmen Road.

E. Woodmen Road Culverts, Headwater/Discharge Data

West Set of 3-48" RCP Culverts		East Set of 3-48" RCP Culverts	
Headwater Elevation (ft)	Total Discharge (cfs)	Headwater Elevation (ft)	Total Discharge (cfs)
6871.20	0	6867.80	0
6873.04	50	6869.44	50
6873.88	100	6870.26	100
6874.60	150	6870.95	150
6875.27	200	6871.58	200
6875.96	250	6872.41	250
6876.84	300	6873.01	300
6877.87	350	6873.88	350
6877.99	355	6875.00	400
6878.0*	355.5*	6875.12	405
6878.59	450	6875.2*	408.4*
6878.80	500	6875.78	500

* maximum allowable discharge through each of the two sets of culverts assuming the maximum allowable headwater elevation is equal to the elevation of the edge of roadway asphalt along the north side of E. Woodmen Road.

The proposed grass-lined channel, which parallels the south property line, contains a check dam, located immediately downstream (east) of the westerly set of 3-48" culverts under E. Woodmen Road. The check dam will help to more evenly divide flows between the westerly and easterly sets of 3-48" culverts. The check dam will be constructed of earthen material armored with riprap. The check dam was modeled as an obstruction at CLOMR XS535 with a crest elevation of 6875.9 which was chosen to maximize flow to the westerly set of culverts without exceeding the allowable headwater elevation. The HEC-RAS model results indicate that of the total 100-year discharge = 757 cfs, in the main channel, 351 cfs is diverted to the westerly set of culverts and 406 cfs remain in the main channel. See appendix for supporting information.

In addition to the onsite storm sewer system, a proposed 24" RCP line is to be installed between the existing grate inlet at the Meridian Road/Eastonville Road intersection and the existing grate inlet approximately 600 ft to the south. Median grading in Meridian Road necessitates replacing the existing landscaped median flow with pipe in this location. The southerly inlet will be replaced with a storm sewer manhole.

Private maintenance agreements will be established for the private storm system, prior to Final Plat.

7.0 PROPOSED DETENTION/WATER QUALITY FACILITIES

As previously mentioned, three separate detention/water quality facilities are proposed with this development:

Pond #1 (DBPS – SR4), a 26.7 ac-ft sub-regional detention facility is proposed along the northern boundary of the project site, to intercept flows from the UTBSC, and release it at a reduced flow rate into the 96" pipe. In accordance with El Paso County criteria, a 12'x8' modified type D outlet structure with a permanent micropool will release the WQCV over a 40-hour period. A gravel maintenance access road will be constructed in to, and around the entire perimeter of the pond. Pond #1 will be owned and maintained by El Paso County.

Pond #2, a 1.1 ac-ft water-quality basin will intercept the flows generated by the site, south of the proposed sub-regional pond #1. As with pond #1, in accordance with El Paso County criteria, an outlet structure with permanent micropool will release the WQCV over a 40-hour period, to the open channel along E. Woodmen Road. A gravel maintenance access road will be constructed in to, and around the southern perimeter of the pond.

Pond #3, is a small 0.20 ac-ft water-quality basin intended to intercept the flows generated by the western portion of the site. As with pond #1, in accordance with El Paso County criteria, an outlet structure with permanent micropool will release the WQCV over a 40-hour period. Flows will discharge into the 96" RCP, and ultimately reach the open channel along E. Woodmen Road.

Private maintenance agreements and O&M manuals will be established for Ponds 2 and 3, prior to Final Plat.

8.0 FOUR-STEP PROCESS

In conformance with the Four-Step Process, outlined in the DCM, Volume 2, the site development design is focused on reducing runoff volumes, treating the water quality capture volume, and creating stabilized drainage ways. Methods will be discussed further in the Final Drainage Report.

Proposed sub-regional pond SR4 (Pond #1), and both onsite water quality facilities (Ponds #2 & #3) will capture and slowly release the WQCV, aiding in water quality treatment.

Construction and stabilization of a natural channel along E. Woodmen Road will also take place, allowing water quality benefits, through infiltration and vegetation pollutant uptake. A proposed grade structure will also reduce channel velocities and assist in preventing bed and bank erosion.

Future individual lot owners will be required to address the four-step process, and implement further water quality features as necessary.

9.0 GEOTECHNICAL HAZARDS

In accordance with geotechnical recommendations, the project design is intended to direct runoff away from structures, and into the receiving water quality basins. This will be accomplished by a variety of means, i.e. curb and gutter and storm sewer. The individual building pads will be developed by others, and further analysis will need to be addressed in the lot-specific geotechnical reports for those lots.

After consulting with the State of Colorado Dam Safety Branch, it was determined that the design of Pond #1 (SR4) allows for the structure to be considered non-jurisdictional. Given the length of the buried outlet, the downstream toe is to be used as the datum for measuring dam height.

During construction of the embankment, settlement monitoring plates will be installed. Regular measurements will be recorded, documenting the amount of settlement in the embankment, and when it becomes negligible.

Groundwater mitigation measures for the pond, will consist of installation of a 12-inch thick impervious clay liner, to resolve the potential for vertical groundwater seepage. Liner specifications will be based on the Colorado Department of Natural Resources specifications.

10.0 EXISTING ONSITE UTILITY INFRASTRUCTURE

Along the southern site boundary, a number of existing utilities are being considered as part of the final project design. Utility providers have been consulted and communication will continue as the project design progresses.

Mountain View Electric

An existing overhead transmission line runs along Meridian Road, and continues underground along E. Woodmen Road. These lines, both overhead and underground are proposed to be relocated through the project site, following the proposed main access road.

Woodmen Hills Metropolitan District

An existing 10" sanitary sewer line runs along E. Woodmen Road, and an existing 12" sanitary sewer line runs along Meridian Road, but both are minimally impacted by the project development.

An existing 10" water main, and 6" non-potable raw water main run along the southern boundary of the site. These lines will be relocated along the project main road through the site. Existing lines will be removed when encountered during grading of the open channel.

Nustar Energy

An existing 10" high-pressure petroleum pipeline also runs along the southern boundary of the site. It is anticipated that this line will remain in place.

11.0 CONDITIONAL LETTER OF MAP REVISION (CLOMR)

As mentioned above, a Conditional Letter of Map Revision (CLOMR) was approved by FEMA (Case No. 17-08-0074R) on May 26, 2017. The CLOMR takes a large portion of the project site out of the floodplain, by constructing a sub-regional detention pond, and open channel along E. Woodmen Road.

Referenced portions of the CLOMR are included in the appendix.

12.0 DRAINAGE/BRIDGE FEES

Drainage and Bridge Fees

The project lies within the Falcon Drainage Basin, and is previously unplatted. The following fees are required:

The percent imperviousness for this subdivision is calculated as follows:

27.7 Acres Commercial	95% Impervious
<u>8.7 Acres Open Space</u>	<u>0% Impervious</u>
Weighted Average	72.3% Impervious

$$36.4 \text{ Acres at } 72.3\% \text{ Impervious} = 26.3 \text{ Impervious Acres}$$

The following calculations are based on the 2018 drainage/bridge fees for the Falcon Basin:

Drainage Fees

$$\$27,762 \times 26.3 \text{ Impervious Ac} = \$730,140.60^*$$

Bridge Fees

$$\$3,814 \times 26.3 \text{ Impervious Ac.} = \$101,018.30^*$$

***Pond Reimbursement**

Full reimbursement for construction of the sub-regional detention pond (Pond #1 – SR4) and outfall in accordance with DCM Section 3.3, is anticipated. Construction costs will be established in the Final Drainage Report and the drainage basin fee will be requested to be adjusted accordingly. Fees will be based upon the Final Plat submittal date.

13.0 CONCLUSIONS

The Falcon Marketplace project has been designed in accordance with El Paso County criteria. The detention pond and water quality basins have been designed to limit the release of storm runoff to historic flows. This development will not negatively impact the downstream facilities.

A portion of the site will remain in the 100-year floodplain after grading is complete. A LOMR will be submitted to FEMA after construction to revise the FIRM map and remove the majority of the site from the floodplain. Future buildings will not be constructed in the floodplain, or downstream of the Pond SR4 spillway in the potential overtopping inundation area.

14.0 REFERENCES

The sources of information used in the development of this study are listed below:


1. City of Colorado Springs/El Paso County Drainage Criteria Manual, May 2014.
2. Urban Storm Drainage Criteria Manuals, Urban Drainage and Flood Control District. June 2001, Revised April 2008.
3. Request for Conditional Letter of Map Revision, Unnamed Tributary to Black Squirrel Creek, Falcon Marketplace. Prepared by Drexel, Barrell & Co., October 17, 2016.
4. Final Drainage & Erosion Control Plan for The Courtyards at Woodmen Hills West. Prepared by JDS-Hydro, December 1, 2003.
5. Natural Resources Conservation Service (NRCS) Web Soil Survey
6. Federal Emergency Management Agency, Flood Insurance Rate Map, El Paso County, Colorado and Unincorporated Areas, Map Number 8041CO575F, Effective Date March 17, 1997.
7. El Paso County Board Resolution No 15-042: El Paso County adoption of Chapter 6 and Section 3.2.1, Chapter 13 of the City of Colorado Springs Drainage Criteria Manual, May 2014.
8. Falcon Drainage Basin Planning Study. Prepared by Matrix Design Group, September 2015.
9. Preliminary Geotechnical Investigation. Prepared by Ground Engineering, August 25, 2015, with Addenda #1, dated March 17, 2017.
10. Colorado Department of Natural Resources – Pond Liner Specifications.
11. PSI Pond Liner Memo, June 23, 2017.

Vicinity Map



Vicinity Map

NTS



**FALCON MARKETPLACE
VICINITY MAP**

Drexel, Barrell & Co.
Engineers • Surveyors

DATE: 8/18/16 DWG. NO.

JOB NO:

20988-00

VMAP

SHEET 1 OF 1

Soils Map


Custom Soil Resource Report
Soil Map



Custom Soil Resource Report

MAP LEGEND

Area of Interest (AOI)



Area of Interest (AOI)

Soils



Soil Map Unit Polygons



Soil Map Unit Lines



Soil Map Unit Points

Special Point Features



Blowout



Borrow Pit



Clay Spot



Closed Depression



Gravel Pit



Gravelly Spot



Landfill



Lava Flow



Marsh or swamp



Mine or Quarry



Miscellaneous Water



Perennial Water



Rock Outcrop



Saline Spot



Sandy Spot



Severely Eroded Spot



Sinkhole



Slide or Slip



Sodic Spot

Spoil Area

Stony Spot

Very Stony Spot

Wet Spot

Other

Special Line Features

Water Features

Streams and Canals

Transportation

Rails

Interstate Highways

US Routes

Major Roads

Local Roads

Background

Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
Web Soil Survey URL: <http://websoilsurvey.nrcs.usda.gov>
Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: El Paso County Area, Colorado
Survey Area Data: Version 13, Sep 22, 2015

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Apr 15, 2011—Sep 22, 2011

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Map Unit Legend

El Paso County Area, Colorado (CO625)			
Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
8	Blakeland loamy sand, 1 to 9 percent slopes	1.2	3.2%
9	Blakeland-Fluvaquentic Haplaquolls	16.3	43.9%
19	Columbine gravelly sandy loam, 0 to 3 percent slopes	19.6	52.9%
Totals for Area of Interest		37.1	100.0%

Map Unit Descriptions

The map units delineated on the detailed soil maps in a soil survey represent the soils or miscellaneous areas in the survey area. The map unit descriptions, along with the maps, can be used to determine the composition and properties of a unit.

A map unit delineation on a soil map represents an area dominated by one or more major kinds of soil or miscellaneous areas. A map unit is identified and named according to the taxonomic classification of the dominant soils. Within a taxonomic class there are precisely defined limits for the properties of the soils. On the landscape, however, the soils are natural phenomena, and they have the characteristic variability of all natural phenomena. Thus, the range of some observed properties may extend beyond the limits defined for a taxonomic class. Areas of soils of a single taxonomic class rarely, if ever, can be mapped without including areas of other taxonomic classes. Consequently, every map unit is made up of the soils or miscellaneous areas for which it is named and some minor components that belong to taxonomic classes other than those of the major soils.

Most minor soils have properties similar to those of the dominant soil or soils in the map unit, and thus they do not affect use and management. These are called noncontrasting, or similar, components. They may or may not be mentioned in a particular map unit description. Other minor components, however, have properties and behavioral characteristics divergent enough to affect use or to require different management. These are called contrasting, or dissimilar, components. They generally are in small areas and could not be mapped separately because of the scale used. Some small areas of strongly contrasting soils or miscellaneous areas are identified by a special symbol on the maps. If included in the database for a given area, the contrasting minor components are identified in the map unit descriptions along with some characteristics of each. A few areas of minor components may not have been observed, and consequently they are not mentioned in the descriptions, especially where the pattern was so complex that it was impractical to make enough observations to identify all the soils and miscellaneous areas on the landscape.

The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The objective of mapping is not to delineate pure taxonomic classes but rather to separate the landscape into landforms or landform segments that have similar use and management requirements. The delineation of such segments

Custom Soil Resource Report

on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, however, onsite investigation is needed to define and locate the soils and miscellaneous areas.

An identifying symbol precedes the map unit name in the map unit descriptions. Each description includes general facts about the unit and gives important soil properties and qualities.

Soils that have profiles that are almost alike make up a *soil series*. Except for differences in texture of the surface layer, all the soils of a series have major horizons that are similar in composition, thickness, and arrangement.

Soils of one series can differ in texture of the surface layer, slope, stoniness, salinity, degree of erosion, and other characteristics that affect their use. On the basis of such differences, a soil series is divided into *soil phases*. Most of the areas shown on the detailed soil maps are phases of soil series. The name of a soil phase commonly indicates a feature that affects use or management. For example, Alpha silt loam, 0 to 2 percent slopes, is a phase of the Alpha series.

Some map units are made up of two or more major soils or miscellaneous areas. These map units are complexes, associations, or undifferentiated groups.

A *complex* consists of two or more soils or miscellaneous areas in such an intricate pattern or in such small areas that they cannot be shown separately on the maps. The pattern and proportion of the soils or miscellaneous areas are somewhat similar in all areas. Alpha-Beta complex, 0 to 6 percent slopes, is an example.

An *association* is made up of two or more geographically associated soils or miscellaneous areas that are shown as one unit on the maps. Because of present or anticipated uses of the map units in the survey area, it was not considered practical or necessary to map the soils or miscellaneous areas separately. The pattern and relative proportion of the soils or miscellaneous areas are somewhat similar. Alpha-Beta association, 0 to 2 percent slopes, is an example.

An *undifferentiated group* is made up of two or more soils or miscellaneous areas that could be mapped individually but are mapped as one unit because similar interpretations can be made for use and management. The pattern and proportion of the soils or miscellaneous areas in a mapped area are not uniform. An area can be made up of only one of the major soils or miscellaneous areas, or it can be made up of all of them. Alpha and Beta soils, 0 to 2 percent slopes, is an example.

Some surveys include *miscellaneous areas*. Such areas have little or no soil material and support little or no vegetation. Rock outcrop is an example.

El Paso County Area, Colorado

8—Blakeland loamy sand, 1 to 9 percent slopes

Map Unit Setting

National map unit symbol: 369v

Elevation: 4,600 to 5,800 feet

Mean annual precipitation: 14 to 16 inches

Mean annual air temperature: 46 to 48 degrees F

Frost-free period: 125 to 145 days

Farmland classification: Not prime farmland

Map Unit Composition

Blakeland and similar soils: 85 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Blakeland

Setting

Landform: Flats, hills

Landform position (three-dimensional): Side slope, talus

Down-slope shape: Linear

Across-slope shape: Linear

Parent material: Alluvium derived from sedimentary rock and/or eolian deposits derived from sedimentary rock

Typical profile

A - 0 to 11 inches: loamy sand

AC - 11 to 27 inches: loamy sand

C - 27 to 60 inches: sand

Properties and qualities

Slope: 1 to 9 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Somewhat excessively drained

Runoff class: Low

Capacity of the most limiting layer to transmit water (Ksat): High to very high (5.95 to 19.98 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Calcium carbonate, maximum in profile: 5 percent

Available water storage in profile: Low (about 4.5 inches)

Interpretive groups

Land capability classification (irrigated): 3e

Land capability classification (nonirrigated): 6e

Hydrologic Soil Group: A

Ecological site: Sandy Foothill (R049BY210CO)

Minor Components

Other soils

Percent of map unit:

Pleasant

Percent of map unit:

Landform: Depressions

9—Blakeland-Fluvaquentic Haplaquolls

Map Unit Setting

National map unit symbol: 36b6

Elevation: 3,500 to 5,800 feet

Mean annual precipitation: 13 to 17 inches

Mean annual air temperature: 46 to 55 degrees F

Frost-free period: 110 to 165 days

Farmland classification: Not prime farmland

Map Unit Composition

Blakeland and similar soils: 60 percent

Fluvaquentic haplaquolls and similar soils: 30 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Blakeland

Setting

Landform: Flats, hills

Landform position (three-dimensional): Side slope, talus

Down-slope shape: Linear

Across-slope shape: Linear

Parent material: Sandy alluvium derived from arkose and/or eolian deposits derived from arkose

Typical profile

A - 0 to 11 inches: loamy sand

AC - 11 to 27 inches: loamy sand

C - 27 to 60 inches: sand

Properties and qualities

Slope: 1 to 9 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Somewhat excessively drained

Runoff class: Low

Capacity of the most limiting layer to transmit water (Ksat): High to very high (5.95 to 19.98 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Calcium carbonate, maximum in profile: 5 percent

Available water storage in profile: Low (about 4.5 inches)

Interpretive groups

Land capability classification (irrigated): 3e

Land capability classification (nonirrigated): 6e

Hydrologic Soil Group: A
Ecological site: Sandy Foothill (R049BY210CO)

Description of Fluvaquentic Haplaquolls

Setting

Landform: Swales
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Alluvium

Typical profile

H1 - 0 to 12 inches: variable

Properties and qualities

Slope: 1 to 2 percent
Depth to restrictive feature: More than 80 inches
Natural drainage class: Poorly drained
Runoff class: Very high
Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high (0.20 to 6.00 in/hr)
Depth to water table: About 0 to 24 inches
Frequency of flooding: Occasional
Frequency of ponding: None
Salinity, maximum in profile: Nonsaline to slightly saline (0.0 to 4.0 mmhos/cm)

Interpretive groups

Land capability classification (irrigated): 6w
Land capability classification (nonirrigated): 6w
Hydrologic Soil Group: D

Minor Components

Other soils

Percent of map unit:

Pleasant

Percent of map unit:
Landform: Depressions

19—Columbine gravelly sandy loam, 0 to 3 percent slopes

Map Unit Setting

National map unit symbol: 367p
Elevation: 6,500 to 7,300 feet
Mean annual precipitation: 14 to 16 inches
Mean annual air temperature: 46 to 50 degrees F
Frost-free period: 125 to 145 days
Farmland classification: Not prime farmland

Map Unit Composition

Columbine and similar soils: 85 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Columbine

Setting

Landform: Fans, flood plains, fan terraces

Down-slope shape: Linear

Across-slope shape: Linear

Parent material: Alluvium

Typical profile

A - 0 to 14 inches: gravelly sandy loam

C - 14 to 60 inches: very gravelly loamy sand

Properties and qualities

Slope: 0 to 3 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Well drained

Runoff class: Very low

Capacity of the most limiting layer to transmit water (Ksat): High to very high (5.95 to 19.98 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Available water storage in profile: Very low (about 2.5 inches)

Interpretive groups

Land capability classification (irrigated): 4e

Land capability classification (nonirrigated): 6e

Hydrologic Soil Group: A

Ecological site: Gravelly Foothill (R049BY214CO)

Minor Components

Fluvaquentic haplaquolls

Percent of map unit:

Landform: Swales

Other soils

Percent of map unit:

Pleasant

Percent of map unit:

Landform: Depressions

Floodplain Map

Hydrology Calculations

PROJECT INFORMATION

PROJECT: Falcon Marketplace
 PROJECT NO: 20988-00CSCV
 DESIGN BY: KGV
 REV. BY: TDM
 AGENCY: El Paso County
 REPORT TYPE: Preliminary
 DATE: 9/25/2018



Drexel, Barrell & Co.

	C2*	C5*	C10*	C100*	% IMPERV
Commercial Development		0.81		0.88	95
5-acre residential		0.20		0.35	20
Open Space		0.08		0.35	0
Asphalt Roadway		0.90		0.96	100

*C-Values and Basin Imperviousness based on Table 5-1, City of Colorado Springs and El Paso County "Drainage Criteria Manual"

SUB-BASIN	SURFACE DESIGNATION	AREA ACRE	COMPOSITE RUNOFF COEFFICIENTS				% IMPERV
			C2	C5	C10	C100	
O1	Commercial Development	0.00		0.81		0.88	95
	5-acre residential	32.50		0.20		0.35	20
	Asphalt Roadway	0.00		0.90		0.96	100
TOTAL O1	WEIGHTED AVERAGE	32.50		0.20		0.35	20
O1A	Commercial Development	0.00		0.81		0.88	95
	Open Space	2.06		0.08		0.35	0
	Asphalt Roadway	0.00		0.90		0.96	100
TOTAL O1A	WEIGHTED AVERAGE	2.06		0.08		0.35	0
O2	Commercial Development	0.00		0.81		0.88	95
	Open Space	0.00		0.08		0.35	0
	Asphalt Roadway	2.21		0.90		0.96	100
TOTAL O2	WEIGHTED AVERAGE	2.21		0.90		0.96	100
O3	Commercial Development	0.00		0.81		0.88	95
	Open Space	0.00		0.08		0.35	0
	Asphalt Roadway	4.46		0.90		0.96	100
TOTAL O3	WEIGHTED AVERAGE	4.46		0.90		0.96	100
E1	Commercial Development	0.00		0.81		0.88	95
	Open Space	35.70		0.08		0.35	0
	Asphalt Roadway	0.00		0.90		0.96	100
TOTAL E1	WEIGHTED AVERAGE	35.70		0.08		0.35	0

PROJECT INFORMATION

PROJECT: Falcon Marketplace
 PROJECT NO: 20988-00CSCV
 DESIGN BY: KGV
 REV. BY: TDM
 AGENCY: El Paso County
 REPORT TYPE: Preliminary
 DATE: 9/25/2018



Drexel, Barrell & Co.

RATIONAL METHOD CALCULATIONS FOR STORM WATER RUNOFF

EXISTING

SUB-BASIN DATA				INITIAL/OVERLAND TIME (t_i)			TRAVEL TIME (t_t)					TIME OF CONC.		FINAL t_c
BASIN	DESIGN PT:	C_5	C_{100}	AREA	LENGTH	SLOPE	t_i	LENGTH	SLOPE	VEL.	t_t	COMP.	<i>MINIMUM</i>	
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)*	(11)	(12)	(13)	(14)		
O1		0.20	0.35	32.50	1000	2.0	42.2	1800	2.0	2.1	14.3	56.5	5.0	56.5
O1A		0.08	0.35	2.06	80	5.0	10.0	0	0.0	0.0	0.0	10.0	5.0	10.0
O2		0.90	0.96	2.21	50	2.0	2.1	1700	2.0	2.1	13.4	15.5	5.0	15.5
O3		0.90	0.96	4.46	50	2.0	2.1	1500	2.0	2.1	11.8	13.9	5.0	13.9
E1		0.08	0.35	35.70	200	1.0	27.0	1100	2.0	2.8	6.5	33.5	5.0	33.5

PROJECT INFORMATION

PROJECT: Falcon Marketplace
 PROJECT NO: 20988-00CSCV
 DESIGN BY: KGV
 REV. BY: TDM
 AGENCY: El Paso County
 REPORT TYPE: Preliminary
 DATE: 9/25/2018



Drexel, Barrell & Co.

RATIONAL METHOD CALCULATIONS FOR STORM WATER RUNOFF

EXISTING BASIN (S)	RUNOFF		5 YR		STORM		P1=		TOTAL RUNOFF			
	DESIGN POINT (2)	AREA (AC) (3)	DIRECT RUNOFF						t _c (MIN) (10)	S (C * A) (11)	I (IN/HR) (12)	Q (CFS) (13)
			RUNOFF COEFF (5)	t _c (MIN) (6)	C * A (7)	I (IN/HR) (8)	Q (CFS) (9)					
O1		32.50	0.20	56.5	6.50	1.58	10.3					
O1A		2.06	0.08	10.0	0.16	4.06	0.7					
O2		2.21	0.90	15.5	1.99	3.36	6.7					
O3		4.46	0.90	13.9	4.01	3.53	14.2					
E1		35.70	0.08	33.5	2.86	2.21	6.3					
DBPS OFFSITE NORTH (MT060)	DP1							310.0				
							348.1					

PROJECT INFORMATION

PROJECT: Falcon Marketplace
 PROJECT NO: 20988-00CSCV
 DESIGN BY: KGV
 REV. BY: TDM
 AGENCY: El Paso County
 REPORT TYPE: Preliminary
 DATE: 9/25/2018



Drexel, Barrell & Co.

RATIONAL METHOD CALCULATIONS FOR STORM WATER RUNOFF

EXISTING BASIN (S)	RUNOFF		100 YR		STORM			TOTAL RUNOFF			P1= 2.52	
			DIRECT RUNOFF									
	DESIGN POINT (2)	AREA (3)	AREA (AC) (4)	RUNOFF COEFF (5)	t _c (MIN) (6)	C * A (7)	I (IN/HR) (8)	Q (CFS) (9)	t _c (MIN) (10)	S (C * A) (11)	I (IN/HR) (12)	Q (CFS) (13)
O1			32.50	0.35	56.5	11.38	2.65	30.2				
O1A			2.06	0.35	10.0	0.72	6.82	4.9				
O2			2.21	0.96	15.5	2.12	5.64	12.0				
O3			4.46	0.96	13.9	4.28	5.93	25.4				
E1			35.70	0.35	33.5	12.50	3.70	46.3				
DBPS OFFSITE NORTH (MT060)		DP1						1016.0				
								1134.7				

PROJECT INFORMATION

PROJECT:
PROJECT NO:
DESIGN BY:
REV. BY:
AGENCY:
REPORT TYPE:
DATE:

Falcon Marketplace
20988-00CSCV
KGV
TDM
El Paso County
Preliminary
3/21/2017



Drexel, Barrell & Co.

	C2*	C5*	C10*	C100*	% IMPERV
Commercial Development		0.81		0.88	95
Open Space		0.08		0.35	0
Asphalt Roadway		0.90		0.96	100

*C-Values and Basin Imperviousness based on Table 5-1, City of Colorado Springs and El Paso County "Drainage Criteria Manual"

SUB-BASIN	SURFACE DESIGNATION	AREA ACRE	COMPOSITE RUNOFF COEFFICIENTS				% IMPERV
			C2	C5	C10	C100	
A1	Commercial Development	0.00		0.81		0.88	95
	Open Space	0.69		0.08		0.35	0
	Asphalt Roadway	0.00		0.90		0.96	100
TOTAL A1	WEIGHTED AVERAGE	0.69		0.08		0.35	0
A2	Commercial Development	0.00		0.81		0.88	95
	Open Space	0.40		0.08		0.35	0
	Asphalt Roadway	1.10		0.90		0.96	100
TOTAL A2	WEIGHTED AVERAGE	1.50		0.68		0.80	73
A3	Commercial Development	0.00		0.81		0.88	95
	Open Space	4.82		0.08		0.35	0
	Asphalt Roadway	0.00		0.90		0.96	100
TOTAL A3	WEIGHTED AVERAGE	4.82		0.08		0.35	0
A4	Commercial Development	1.52		0.81		0.88	95
	Open Space	0.00		0.08		0.35	0
	Asphalt Roadway	0.00		0.90		0.96	100
TOTAL A4	WEIGHTED AVERAGE	1.52		0.81		0.88	95
B1	Commercial Development	0.00		0.81		0.88	95
	Open Space	0.00		0.08		0.35	0
	Asphalt Roadway	0.54		0.90		0.96	100
TOTAL B1	WEIGHTED AVERAGE	0.54		0.90		0.96	100
B2	Commercial Development	1.18		0.81		0.88	95
	Open Space	0.00		0.08		0.35	0
	Asphalt Roadway	0.00		0.90		0.96	100
TOTAL B2	WEIGHTED AVERAGE	1.18		0.81		0.88	95
B3	Commercial Development	1.17		0.81		0.88	95
	Open Space	0.00		0.08		0.35	0
	Asphalt Roadway	0.00		0.90		0.96	100
TOTAL B3	WEIGHTED AVERAGE	1.17		0.81		0.88	95
B4	Commercial Development	3.32		0.81		0.88	95
	Open Space	0.00		0.08		0.35	0
	Asphalt Roadway	0.00		0.90		0.96	100
TOTAL B4	WEIGHTED AVERAGE	3.32		0.81		0.88	95
B5	Commercial Development	0.00		0.81		0.88	95
	Open Space	0.00		0.08		0.35	0
	Asphalt Roadway	0.32		0.90		0.96	100
TOTAL B5	WEIGHTED AVERAGE	0.32		0.90		0.96	100
B6	Commercial Development	0.00		0.81		0.88	95
	Open Space	0.00		0.08		0.35	0
	Asphalt Roadway	0.31		0.90		0.96	100
TOTAL B6	WEIGHTED AVERAGE	0.31		0.90		0.96	100
B7	Commercial Development	0.72		0.81		0.88	95

PROJECT INFORMATION

PROJECT:
PROJECT NO:
DESIGN BY:
REV. BY:
AGENCY:
REPORT TYPE:
DATE:

Falcon Marketplace
20988-00CSCV
KGV
TDM
El Paso County
Preliminary
3/21/2017



Drexel, Barrell & Co.

	C2*	C5*	C10*	C100*	% IMPERV
Commercial Development		0.81		0.88	95
Open Space		0.08		0.35	0
Asphalt Roadway		0.90		0.96	100

*C-Values and Basin Imperviousness based on Table 5-1, City of Colorado Springs and El Paso County "Drainage Criteria Manual"

	Open Space	0.00	0.08	0.35	0
	Asphalt Roadway	0.00	0.90	0.96	100
TOTAL B7	WEIGHTED AVERAGE	0.72	0.81	0.88	95
B8	Commercial Development	0.00	0.81	0.88	95
	Open Space	0.00	0.08	0.35	0
	Asphalt Roadway	0.17	0.90	0.96	100
TOTAL B8	WEIGHTED AVERAGE	0.17	0.90	0.96	100
B9	Commercial Development	2.25	0.81	0.88	95
	Open Space	0.00	0.08	0.35	0
	Asphalt Roadway	0.00	0.90	0.96	100
TOTAL B9	WEIGHTED AVERAGE	2.25	0.81	0.88	95
B10	Commercial Development	0.00	0.81	0.88	95
	Open Space	0.00	0.08	0.35	0
	Asphalt Roadway	0.18	0.90	0.96	100
TOTAL B10	WEIGHTED AVERAGE	0.18	0.90	0.96	100
B11	Commercial Development	0.00	0.81	0.88	95
	Open Space	0.00	0.08	0.35	0
	Asphalt Roadway	0.20	0.90	0.96	100
TOTAL B11	WEIGHTED AVERAGE	0.20	0.90	0.96	100
B12	Commercial Development	1.76	0.81	0.88	95
	Open Space	0.00	0.08	0.35	0
	Asphalt Roadway	0.00	0.90	0.96	100
TOTAL B12	WEIGHTED AVERAGE	1.76	0.81	0.88	95
B13	Commercial Development	0.00	0.81	0.88	95
	Open Space	0.00	0.08	0.35	0
	Asphalt Roadway	0.21	0.90	0.96	100
TOTAL B13	WEIGHTED AVERAGE	0.21	0.90	0.96	100
B14	Commercial Development	4.34	0.81	0.88	95
	Open Space	0.00	0.08	0.35	0
	Asphalt Roadway	0.00	0.90	0.96	100
TOTAL B14	WEIGHTED AVERAGE	4.34	0.81	0.88	95
B15	Commercial Development	0.00	0.81	0.88	95
	Open Space	0.00	0.08	0.35	0
	Asphalt Roadway	0.16	0.90	0.96	100
TOTAL B15	WEIGHTED AVERAGE	0.16	0.90	0.96	100
B16	Commercial Development	0.00	0.81	0.88	95
	Open Space	0.00	0.08	0.35	0
	Asphalt Roadway	0.34	0.90	0.96	100
TOTAL B16	WEIGHTED AVERAGE	0.34	0.90	0.96	100
B17	Commercial Development	2.16	0.81	0.88	95
	Open Space	0.00	0.08	0.35	0
	Asphalt Roadway	0.00	0.90	0.96	100
TOTAL B17	WEIGHTED AVERAGE	2.16	0.81	0.88	95
B18	Commercial Development	2.90	0.81	0.88	95

PROJECT INFORMATION

PROJECT: Falcon Marketplace
 PROJECT NO: 20988-00CSCV
 DESIGN BY: KGV
 REV. BY: TDM
 AGENCY: El Paso County
 REPORT TYPE: Preliminary
 DATE: 3/21/2017



Drexel, Barrell & Co.

	C2*	C5*	C10*	C100*	% IMPERV
Commercial Development		0.81		0.88	95
Open Space		0.08		0.35	0
Asphalt Roadway		0.90		0.96	100

*C-Values and Basin Imperviousness based on Table 5-1, City of Colorado Springs and El Paso County "Drainage Criteria Manual"

	Open Space	0.00	0.08	0.35	0
	Asphalt Roadway	0.00	0.90	0.96	100
TOTAL B18	<i>WEIGHTED AVERAGE</i>	2.90	0.81	0.88	95
B19	Commercial Development	0.00	0.81	0.88	95
	Open Space	0.73	0.08	0.35	0
	Asphalt Roadway	1.29	0.90	0.96	100
TOTAL B19	<i>WEIGHTED AVERAGE</i>	2.02	0.60	0.74	64
B20	Commercial Development	0.00	0.81	0.88	95
	Open Space	1.63	0.08	0.35	0
	Asphalt Roadway	0.00	0.90	0.96	100
TOTAL B20	<i>WEIGHTED AVERAGE</i>	1.63	0.08	0.35	0
C1	Commercial Development	2.75	0.81	0.88	95
	Open Space	2.05	0.08	0.35	0
	Asphalt Roadway	0.00	0.90	0.96	100
TOTAL C1	<i>WEIGHTED AVERAGE</i>	4.80	0.50	0.65	54
C2	Commercial Development	0.00	0.81	0.88	95
	Open Space	0.25	0.08	0.35	0
	Asphalt Roadway	0.09	0.90	0.96	100
TOTAL C2	<i>WEIGHTED AVERAGE</i>	0.34	0.30	0.51	26
C3	Commercial Development	0.00	0.81	0.88	95
	Open Space	0.27	0.08	0.35	0
	Asphalt Roadway	0.70	0.90	0.96	100
TOTAL C3	<i>WEIGHTED AVERAGE</i>	0.97	0.67	0.79	72
C4	Commercial Development	0.00	0.81	0.88	95
	Open Space	0.00	0.08	0.35	0
	Asphalt Roadway	0.45	0.90	0.96	100
TOTAL C4	<i>WEIGHTED AVERAGE</i>	0.45	0.90	0.96	100
C5	Commercial Development	0.00	0.81	0.88	95
	Open Space	2.17	0.08	0.35	0
	Asphalt Roadway	1.94	0.90	0.96	100
TOTAL C5	<i>WEIGHTED AVERAGE</i>	4.11	0.47	0.64	47

PROJECT INFORMATION

PROJECT: Falcon Marketplace
 PROJECT NO: 20988-00CSCV
 DESIGN BY: KGV
 REV. BY: TDM
 AGENCY: El Paso County
 REPORT TYPE: Preliminary
 DATE: 3/21/2017



Drexel, Barrell & Co.

RATIONAL METHOD CALCULATIONS FOR STORM WATER RUNOFF

DEVELOPED TIME OF CONCENTRATION STANDARD FORM SF-2

SUB-BASIN DATA				INITIAL/OVERLAND TIME (t_i)			TRAVEL TIME (t_t)				TIME OF CONC. t_c		FINAL t_c
BASIN	DESIGN PT:	C_5	C_{100}	AREA	LENGTH	SLOPE	t_i		SLOPE	C_v	t_t	COMP.	MINIMUM
				Ac	Ft	%	Min		%	COEFF	Min	t_c	t_c
(1)	(2)	(3)	(4)	(5)	(6)			(8)	(10)	(11)	(12)	(13)	(14)
A1		0.08	0.35	0.69	65	2.0	12.2		2.0	20	3.3	15.5	5.0
A2		0.68	0.80	1.50	50	2.7	4.0	2	2.7	10	0.8	4.7	5.0
A3	POND 1	0.08	0.35	4.82	70	25.0	5.5		0.5	15	12.6	18.0	5.0
A4		0.81	0.88	1.52	50	0.7	4.3	2	0.7	20	3.1	7.4	5.0
B1		0.90	0.96	0.54	30	1.8	1.7	11	1.8	20	3.7	5.4	5.0
B2		0.81	0.88	1.18	50	20.0	1.4	4	1.1	20	2.7	4.1	5.0
B3		0.81	0.88	1.17	50	0.5	4.8	3	1.1	20	2.4	7.2	5.0
B4		0.81	0.88	3.32	50	0.5	4.8	2	0.3	20	8.7	13.5	5.0
B5		0.90	0.96	0.32	40	20.0	0.9	6	1.6	20	2.4	3.3	5.0
B6		0.90	0.96	0.31	25	2.0	1.5	4	1.3	20	2.4	3.9	5.0
B7		0.81	0.88	0.72	0	1.0	0.0	2	1.0	20	1.7	1.7	5.0
B8		0.90	0.96	0.17	30	2.0	1.6	4	1.7	20	1.5	3.1	5.0
B9		0.81	0.88	2.25	25	2.0	2.2	9	1.6	20	3.8	6.0	5.0
													6.0

B10		0.90	0.96	0.18	25	2.0	1.5	4	1.8	20	1.4	2.9	5.0	5.0
B11		0.90	0.96	0.20	25	2.0	1.5	4	1.6	20	1.6	3.1	5.0	5.0
B12		0.81	0.88	1.76	30	0.5	3.7	8	1.2	20	4.9	8.6	5.0	8.6
B13		0.90	0.96	0.21	25	2.0	1.5	5	2.0	20	1.5	3.0	5.0	5.0
B14		0.81	0.88	4.34	30	1.0	3.0	10	1.6	20	4.0	7.0	5.0	7.0
B15		0.90	0.96	0.16	25	2.0	1.5	2	1.0	20	1.7	3.2	5.0	5.0
B16		0.90	0.96	0.34	25	2.0	1.5	6	1.0	20	4.7	6.2	5.0	6.2
B17		0.81	0.88	2.16	50	20.0	1.4	3	1.1	20	2.3	3.7	5.0	5.0
B18		0.81	0.88	2.90	30	2.0	2.4	5	1.1	20	3.7	6.0	5.0	6.0
B19		0.60	0.74	2.02	50	2.0	5.2		2.5	20	2.7	7.9	5.0	7.9
B20	POND 2	0.08	0.35	1.63	50	25.0	4.6	0	0.5	20	10.6	15.2	5.0	15.2
C1		0.50	0.65	4.80	100	10.0	5.2	15	1.7	20	0.1	5.4	5.0	5.4
C2		0.30	0.51	0.34	50	2.0	8.4	1	5.0	20	1.6	10.0	5.0	10.0
C3		0.67	0.79	0.97	50	2.0	4.5	4	1.0	20	3.0	7.5	5.0	7.5
C4		0.90	0.96	0.45	25	2.0	1.5	4	1.1	20	7.9	9.4	5.0	9.4
C5	CHANNEL	0.47	0.64	4.11	100	10.0	5.5		1.0	15	9.3	14.8	5.0	14.8

DP1	B1+B2+B3	0.83	0.89	2.89										7.2
DP2	B6+B7	0.84	0.90	1.03										5.0
DP3	B9+B10	0.82	0.89	2.43										6.0
DP4	Pond 2	0.76	0.84	25.88		B4	13.5		1.0		1.7	15.2	5.0	15.2
DP5	Channel	0.62	0.74	45.08										5.0

PROJECT INFORMATION

PROJECT: Falcon Marketplace
 PROJECT NO: 20988-00CSCV
 DESIGN BY: KGV
 REV. BY: TDM
 AGENCY: El Paso County
 REPORT TYPE: Preliminary
 DATE: 3/21/2017



Drexel, Barrell & Co.

RATIONAL METHOD CALCULATIONS FOR STORM WATER RUNOFF

BASIN (S)	DIRECT RUNOFF								TOTAL RUNOFF			
	DESIGN POINT	AREA	AREA (AC)	RUNOFF COEFF	t_c (MIN)	$C * A$	I (IN/HR)	Q (CFS)	t_c (MIN)	$S (C * A)$	I (IN/HR)	Q (CFS)
A1			0.69	0.08	15.5	0.06	3.35	0.2				
A2			1.50	0.68	5.0	1.02	5.09	5.2				
A3			4.82	0.08	18.0	0.39	3.11	1.2				
A4			1.52	0.81	7.4	1.23	4.53	5.6				
B1			0.54	0.90	5.4	0.49	4.99	2.4				
B2			1.18	0.81	5.0	0.96	5.09	4.9				
B3			1.17	0.81	7.2	0.95	4.57	4.3				
B1+B2+B3	DP1	2.89		0.83					7.2	2.4	4.6	10.9
B4			3.32	0.81	13.5	2.69	3.58	9.6				
B5			0.32	0.90	5.0	0.29	5.09	1.5				
B6			0.31	0.90	5.0	0.28	5.09	1.4				
B7			0.72	0.81	5.0	0.58	5.09	3.0				
B6+B7	DP2	1.03		0.84					5.0	0.9	5.1	4.4
B8			0.17	0.90	5.0	0.15	5.09	0.8				
B9			2.25	0.81	6.0	1.82	4.84	8.8				
B10			0.18	0.90	5.0	0.16	5.09	0.8				

B9+B10	DP3	2.43		0.82						6.0	2.0	4.8	9.6
B11			0.20	0.90	5.0	0.18	5.09	0.9					
B12			1.76	0.81	8.6	1.43	4.29	6.1					
B13			0.21	0.90	5.0	0.19	5.09	1.0					
B14			4.34	0.81	7.0	3.52	4.61	16.2					
B15			0.16	0.90	5.0	0.14	5.09	0.7					
B16			0.34	0.90	6.2	0.31	4.79	1.5					
B17			2.16	0.81	5.0	1.75	5.09	8.9					
B18			2.90	0.81	6.0	2.35	4.83	11.3					
B19			2.02	0.60	7.9	1.22	4.42	5.4					
B20			1.63	0.08	15.2	0.13	3.38	0.4					
(POND 2)	DP4	25.88		0.76						15.2	19.6	3.4	66.3
C1			4.80	0.50	5.4	2.39	5.00	11.9					
C2			0.34	0.30	10.0	0.10	4.06	0.4					
C3			0.97	0.67	7.5	0.65	4.51	2.9					
C5			0.45	0.90	9.4	0.41	4.16	1.7					
C6			4.11	0.47	14.8	1.92	3.42	6.6					
(CHANNEL)	DP5	45.08		0.62									0.0

PROJECT INFORMATION

PROJECT: Falcon Marketplace
 PROJECT NO: 20988-00CSCV
 DESIGN BY: KGV
 REV. BY: TDM
 AGENCY: El Paso County
 REPORT TYPE: Preliminary
 DATE: 3/21/2017



Drexel, Barrell & Co.


RATIONAL METHOD CALCULATIONS FOR STORM WATER RUNOFF

BASIN (S)	DIRECT RUNOFF								TOTAL RUNOFF			
	DESIGN POINT	AREA	AREA (AC)	RUNOFF COEFF	t_c (MIN)	$C * A$	I (IN/HR)	Q (CFS)	t_c (MIN)	$S (C * A)$	I (IN/HR)	Q (CFS)
A1			0.69	0.35	15.5	0.24	5.63	1.4				
A2			1.50	0.80	5.0	1.20	8.55	10.2				
A3			4.82	0.35	18.0	1.69	5.23	8.8				
A4			1.52	0.88	7.4	1.34	7.61	10.2				
B1			0.54	0.96	5.4	0.52	8.38	4.3				
B2			1.18	0.88	5.0	1.04	8.55	8.9				
B3			1.17	0.88	7.2	1.03	7.67	7.9				
B1+B2+B3	DP1	2.89		0.89					7.2	2.6	7.7	19.8
B4			3.32	0.88	13.5	2.92	6.01	17.6				
B5			0.32	0.96	5.0	0.31	8.55	2.6				
B6			0.31	0.96	5.0	0.30	8.55	2.5				
B7			0.72	0.88	5.0	0.63	8.55	5.4				
B6+B7	DP2	1.03		0.90					5.0	0.9	8.5	8.0
B8			0.17	0.96	5.0	0.16	8.55	1.4				
B9			2.25	0.88	6.0	1.98	8.13	16.1				
B10			0.18	0.96	5.0	0.17	8.55	1.5				

B9+B10	DP3	2.43		0.82						6.0	2.0	8.1	16.1
B11			0.20	0.96	5.0	0.19	8.55	1.6					
B12			1.76	0.88	8.6	1.55	7.21	11.2					
B13			0.21	0.96	5.0	0.20	8.55	1.7					
B14			4.34	0.88	7.0	3.82	7.75	29.6					
B15			0.16	0.96	5.0	0.15	8.55	1.3					
B16			0.34	0.96	6.2	0.33	8.06	2.6					
B17			2.16	0.88	5.0	1.90	8.55	16.2					
B18			2.90	0.88	6.0	2.55	8.11	20.7					
B19			2.02	0.74	7.9	1.49	7.42	11.1					
B20			1.63	0.35	15.2	0.57	5.68	3.2					
(POND 2)	DP4	25.88		0.84						15.2	21.8	5.7	124.2
C1			4.80	0.65	5.4	3.14	8.39	26.3					
C2			0.34	0.51	10.0	0.17	6.82	1.2					
C3			0.97	0.79	7.5	0.77	7.57	5.8					
C5			0.45	0.96	9.4	0.43	7.00	3.0					
C6			4.11	0.64	14.8	2.62	5.75	15.1					
(CHANNEL)	DP5	45.08		0.74									754.0

Hydraulic Calculations

Hydraflow Storm Sewers Extension for Autodesk® AutoCAD® Civil 3D® Plan



Project File: FM 3-7-17 HF.stm

Number of lines: 18

Date: 3/16/2017

Storm Sewer Inventory Report

Line No.	Alignment				Flow Data				Physical Data								Line ID
	Dnstr Line No.	Line Length (ft)	Defl angle (deg)	Junc Type	Known Q (cfs)	Drng Area (ac)	Runoff Coeff (C)	Inlet Time (min)	Invert El Dn (ft)	Line Slope (%)	Invert El Up (ft)	Line Size (in)	Line Shape	N Value (n)	J-Loss Coeff (K)	Inlet/Rim El (ft)	
1	End	25.128	-89.363	MH	0.00	0.00	0.00	0.0	6874.00	0.99	6874.25	48	Cir	0.012	1.00	6882.05	PB16
2	1	146.947	-0.786	MH	0.00	0.00	0.00	0.0	6874.25	1.00	6875.72	48	Cir	0.012	0.84	6883.35	PB13
3	2	51.602	53.397	Curb	14.30	0.00	0.00	0.0	6876.22	1.01	6876.74	42	Cir	0.012	1.25	6883.20	PB7
4	3	44.332	-53.375	Curb	11.20	0.00	0.00	0.0	6877.24	0.99	6877.68	36	Cir	0.012	1.50	6883.20	PB6
5	4	131.739	88.983	None	0.00	0.00	0.00	0.0	6877.68	1.00	6879.00	36	Cir	0.012	0.77	6884.84	PB5B
6	5	92.553	-46.653	Curb	1.40	0.00	0.00	0.0	6879.00	0.99	6879.92	36	Cir	0.012	1.17	6886.62	PB5A
7	6	276.549	-42.201	Curb	2.60	0.00	0.00	0.0	6880.42	1.00	6883.19	30	Cir	0.012	1.50	6890.30	PB3
8	7	245.950	0.000	None	0.00	0.00	0.00	0.0	6883.69	1.00	6886.15	24	Cir	0.012	0.84	6893.40	PB1B
9	8	16.464	-53.625	None	17.60	0.00	0.00	0.0	6886.15	0.97	6886.31	24	Cir	0.012	1.00	6893.70	PB1A
10	7	44.336	89.981	Curb	9.30	0.00	0.00	0.0	6884.19	0.99	6884.63	18	Cir	0.012	1.00	6890.30	PB2
11	2	52.706	-53.988	Curb	9.40	0.00	0.00	0.0	6876.22	1.01	6876.75	42	Cir	0.012	1.26	6883.04	PB12
12	11	44.330	54.116	Curb	9.40	0.00	0.00	0.0	6877.25	0.99	6877.69	36	Cir	0.012	1.50	6883.04	PB11
13	12	255.617	-89.979	Curb	1.70	0.00	0.00	0.0	6878.69	1.00	6881.25	24	Cir	0.012	1.50	6885.40	PB9
14	13	10.167	89.940	None	11.20	0.00	0.00	0.0	6881.25	0.98	6881.35	24	Cir	0.012	1.00	6885.60	PB8
15	6	44.335	47.813	Curb	9.10	0.00	0.00	0.0	6881.42	0.99	6881.86	18	Cir	0.012	1.00	6886.88	PB4
16	1	266.443	89.475	None	20.70	0.00	0.00	0.0	6876.25	1.00	6878.92	24	Cir	0.012	1.00	6882.04	PB15
17	12	10.167	-0.039	None	29.60	0.00	0.00	0.0	6878.19	0.98	6878.29	30	Cir	0.012	1.00	6883.24	PB10
18	1	269.817	-90.576	None	16.20	0.00	0.00	0.0	6876.25	1.00	6878.95	24	Cir	0.012	1.00	6882.06	PB14

Project File: FM 3-7-17 HF.stm

Number of lines: 18

Date: 3/16/2017

Structure Report

Struct No.	Structure ID	Junction Type	Rim Elev (ft)	Structure			Line Out			Line In		
				Shape	Length (ft)	Width (ft)	Size (in)	Shape	Invert (ft)	Size (in)	Shape	Invert (ft)
1	MB2	Manhole	6882.05	Cir	6.00	6.00	48	Cir	6874.25	48	Cir	6874.25
										24	Cir	6876.25
										24	Cir	6876.25
2	MB1	Manhole	6883.35	Cir	5.00	5.00	48	Cir	6875.72	42	Cir	6876.22
										42	Cir	6876.22
3	IB6	Curb-	6883.20	Cir	4.00	4.00	42	Cir	6876.74	36	Cir	6877.24
4	IB5	Curb-	6883.20	Cir	4.00	4.00	36	Cir	6877.68	36	Cir	6877.68
5	NB3	None	6884.84	n/a	n/a	n/a	36	Cir	6879.00	36	Cir	6879.00
6	IB4	Curb-	6886.62	Cir	2.00	2.00	36	Cir	6879.92	30	Cir	6880.42
										18	Cir	6881.42
7	IB2	Curb-	6890.30	Cir	4.00	4.00	30	Cir	6883.19	24	Cir	6883.69
										18	Cir	6884.19
8	NB2	None	6893.40	n/a	n/a	n/a	24	Cir	6886.15	24	Cir	6886.15
9	NB1	None	6893.70	n/a	n/a	n/a	24	Cir	6886.31			
10	IB1	Curb-	6890.30	Cir	2.00	2.00	18	Cir	6884.63			
11	IB9	Curb-	6883.04	Cir	4.00	4.00	42	Cir	6876.75	36	Cir	6877.25
12	IB8	Curb-	6883.04	Cir	2.00	2.00	36	Cir	6877.69	24	Cir	6878.69
										30	Cir	6878.19
13	IB7	Curb-	6885.40	Cir	4.00	4.00	24	Cir	6881.25	24	Cir	6881.25
14	NB4	None	6885.60	n/a	n/a	n/a	24	Cir	6881.35			
15	IB3	Curb-	6886.88	Cir	2.00	2.00	18	Cir	6881.86			
16	NB7	None	6882.04	n/a	n/a	n/a	24	Cir	6878.92			
17	NB5	None	6883.24	n/a	n/a	n/a	30	Cir	6878.29			
18	NB6	None	6882.06	n/a	n/a	n/a	24	Cir	6878.95			

Project File: FM 3-7-17 HF.stm

Number of Structures: 18

Run Date: 3/16/2017

Storm Sewer Summary Report

Line No.	Line ID	Flow rate (cfs)	Line Size (in)	Line shape	Line length (ft)	Invert EL Dn (ft)	Invert EL Up (ft)	Line Slope (%)	HGL Down (ft)	HGL Up (ft)	Minor loss (ft)	HGL Junct (ft)	Dns Line No.	Junction Type
1	PB16	163.7	48	Cir	25.128	6874.00	6874.25	0.995	6877.69	6877.94	n/a	6877.94	End	Manhole
2	PB13	126.8	48	Cir	146.947	6874.25	6875.72	1.001	6877.94	6879.10	1.64	6879.10	1	Manhole
3	PB7	65.50	42	Cir	51.602	6876.22	6876.74	1.008	6879.10	6879.28	1.50	6879.28	2	Curb-
4	PB6	51.20	36	Cir	44.332	6877.24	6877.68	0.992	6879.28	6880.01	n/a	6880.01	3	Curb-
5	PB5B	40.00	36	Cir	131.739	6877.68	6879.00	1.002	6880.01	6881.06	n/a	6881.06 j	4	None
6	PB5A	40.00	36	Cir	92.553	6879.00	6879.92	0.994	6881.06	6881.98	n/a	6881.98	5	Curb-
7	PB3	29.50	30	Cir	276.549	6880.42	6883.19	1.002	6881.98	6885.04	1.34	6885.04	6	Curb-
8	PB1B	17.60	24	Cir	245.950	6883.69	6886.15	1.000	6885.04	6887.66	n/a	6887.66	7	None
9	PB1A	17.60	24	Cir	16.464	6886.15	6886.31	0.973	6887.66	6887.82	n/a	6887.82	8	None
10	PB2	9.30	18	Cir	44.336	6884.19	6884.63	0.992	6885.22	6885.81	n/a	6885.81	7	Curb-
11	PB12	61.30	42	Cir	52.706	6876.22	6876.75	1.005	6879.10	6879.20	n/a	6879.20	2	Curb-
12	PB11	51.90	36	Cir	44.330	6877.25	6877.69	0.992	6879.20	6880.03	n/a	6880.03	11	Curb-
13	PB9	12.90	24	Cir	255.617	6878.69	6881.25	1.002	6880.03	6882.54	n/a	6882.54 j	12	Curb-
14	PB8	11.20	24	Cir	10.167	6881.25	6881.35	0.985	6882.54	6882.55	n/a	6882.55	13	None
15	PB4	9.10	18	Cir	44.335	6881.42	6881.86	0.992	6882.44	6883.03	0.59	6883.03	6	Curb-
16	PB15	20.70	24	Cir	266.443	6876.25	6878.92	1.002	6877.94	6880.55	n/a	6880.55 j	1	None
17	PB10	29.60	30	Cir	10.167	6878.19	6878.29	0.985	6880.03	6880.14	0.89	6880.14	12	None
18	PB14	16.20	24	Cir	269.817	6876.25	6878.95	1.001	6877.94	6880.40	n/a	6880.40 j	1	None
Project File: FM 3-7-17 HF.stm									Number of lines: 18			Run Date: 3/16/2017		
NOTES: Known Qs only ; j - Line contains hyd. jump.														

Storm Sewer Tabulation

Station		Len	Drng Area		Rnoff coeff	Area x C		Tc		Rain (I)	Total flow	Cap full	Vel	Pipe		Invert Elev		HGL Elev		Grnd / Rim Elev		Line ID
Line	To Line		Incr (ac)	Total (ac)		(C)	Incr	Total	Inlet (min)	Syst (min)				Size (in)	Slope (%)	Dn (ft)	Up (ft)	Dn (ft)	Up (ft)	Dn (ft)	Up (ft)	
1	End	25.128	0.00	0.00	0.00	0.00	0.0	2.7	0.0	163.7	155.2	13.51	48	0.99	6874.00	6874.25	6877.69	6877.94	6878.66	6882.05	PB16	
2	1	146.947	0.00	0.00	0.00	0.00	0.0	2.4	0.0	126.8	155.7	10.84	48	1.00	6874.25	6875.72	6877.94	6879.10	6882.05	6883.35	PB13	
3	2	51.602	0.00	0.00	0.00	0.00	0.0	2.3	0.0	65.50	109.4	8.26	42	1.01	6876.22	6876.74	6879.10	6879.28	6883.35	6883.20	PB7	
4	3	44.332	0.00	0.00	0.00	0.00	0.0	2.2	0.0	51.20	71.98	9.37	36	0.99	6877.24	6877.68	6879.28	6880.01	6883.20	6883.20	PB6	
5	4	131.739	0.00	0.00	0.00	0.00	0.0	1.8	0.0	40.00	72.32	7.27	36	1.00	6877.68	6879.00	6880.01	6881.06	6883.20	6884.84	PB5B	
6	5	92.553	0.00	0.00	0.00	0.00	0.0	1.5	0.0	40.00	72.03	7.74	36	0.99	6879.00	6879.92	6881.06	6881.98	6884.84	6886.62	PB5A	
7	6	276.549	0.00	0.00	0.00	0.00	0.0	0.8	0.0	29.50	44.47	8.38	30	1.00	6880.42	6883.19	6881.98	6885.04	6886.62	6890.30	PB3	
8	7	245.950	0.00	0.00	0.00	0.00	0.0	0.0	0.0	17.60	24.50	7.36	24	1.00	6883.69	6886.15	6885.04	6887.66	6890.30	6893.40	PB1B	
9	8	16.464	0.00	0.00	0.00	0.00	0.0	0.0	0.0	17.60	24.17	6.92	24	0.97	6886.15	6886.31	6887.66	6887.82	6893.40	6893.70	PB1A	
10	7	44.336	0.00	0.00	0.00	0.00	0.0	0.0	0.0	9.30	11.33	6.70	18	0.99	6884.19	6884.63	6885.22	6885.81	6890.30	6890.30	PB2	
11	2	52.706	0.00	0.00	0.00	0.00	0.0	1.2	0.0	61.30	109.3	7.88	42	1.01	6876.22	6876.75	6879.10	6879.20	6883.35	6883.04	PB12	
12	11	44.330	0.00	0.00	0.00	0.00	0.0	1.1	0.0	51.90	71.98	9.72	36	0.99	6877.25	6877.69	6879.20	6880.03	6883.04	6883.04	PB11	
13	12	255.617	0.00	0.00	0.00	0.00	0.0	0.0	0.0	12.90	24.52	5.89	24	1.00	6878.69	6881.25	6880.03	6882.54	6883.04	6885.40	PB9	
14	13	10.167	0.00	0.00	0.00	0.00	0.0	0.0	0.0	11.20	24.31	5.46	24	0.98	6881.25	6881.35	6882.54	6882.55	6885.40	6885.60	PB8	
15	6	44.335	0.00	0.00	0.00	0.00	0.0	0.0	0.0	9.10	11.33	6.65	18	0.99	6881.42	6881.86	6882.44	6883.03	6886.62	6886.88	PB4	
16	1	266.443	0.00	0.00	0.00	0.00	0.0	0.0	0.0	20.70	24.53	7.43	24	1.00	6876.25	6878.92	6877.94	6880.55	6882.05	6882.04	PB15	
17	12	10.167	0.00	0.00	0.00	0.00	0.0	0.0	0.0	29.60	44.09	7.61	30	0.98	6878.19	6878.29	6880.03	6880.14	6883.04	6883.24	PB10	
18	1	269.817	0.00	0.00	0.00	0.00	0.0	0.0	0.0	16.20	24.51	6.18	24	1.00	6876.25	6878.95	6877.94	6880.40	6882.05	6882.06	PB14	
Project File: FM 3-7-17 HF.stm														Number of lines: 18				Run Date: 3/16/2017				
NOTES:Known Qs only ; c = cir e = ellip b = box																						

Inlet Report

Line No	Inlet ID	Q = CIA (cfs)	Q carry (cfs)	Q capt (cfs)	Q Byp (cfs)	Junc Type	Curb Inlet		Grate Inlet			Gutter							Inlet			Byp Line No
							Ht (in)	L (ft)	Area (sqft)	L (ft)	W (ft)	So (ft/ft)	W (ft)	Sw (ft/ft)	Sx (ft/ft)	n	Depth (ft)	Spread (ft)	Depth (ft)	Spread (ft)	Depr (in)	
1	MB2	0.00	0.00	0.00	0.00	MH	0.0	0.00	0.00	0.00	0.00	Sag	0.00	0.000	0.000	0.013	0.00	0.00	0.00	0.00	0.0	Off
2	MB1	0.00	0.00	0.00	0.00	MH	0.0	0.00	0.00	0.00	0.00	Sag	0.00	0.000	0.000	0.013	0.00	0.00	0.00	0.00	0.0	Off
3	IB6	14.30*	0.00	14.30	0.00	Curb	6.0	10.00	0.00	0.00	0.00	Sag	2.00	0.083	0.020	0.013	0.61	24.20	0.61	24.20	0.0	Off
4	IB5	11.20*	0.00	11.20	0.00	Curb	6.0	10.00	0.00	0.00	0.00	Sag	2.00	0.083	0.020	0.013	0.52	19.62	0.52	19.62	0.0	Off
5	NB3	0.00	0.00	0.00	0.00	None	0.0	0.00	0.00	0.00	0.00	0.000	0.00	0.000	0.000	0.013	0.00	0.00	0.00	0.00	0.0	Off
6	IB4	1.40*	0.00	1.40	0.00	Curb	6.0	10.00	0.00	0.00	0.00	0.010	2.00	0.083	0.020	0.013	0.25	5.95	0.01	0.12	0.0	Off
7	IB2	2.60*	0.00	2.31	0.29	Curb	6.0	10.00	0.00	0.00	0.00	0.010	2.00	0.083	0.020	0.013	0.29	8.35	0.15	1.81	0.0	Off
8	NB2	0.00	0.00	0.00	0.00	None	0.0	0.00	0.00	0.00	0.00	0.000	0.00	0.000	0.000	0.013	0.00	0.00	0.00	0.00	0.0	Off
9	NB1	17.60*	0.00	0.00	17.60	None	0.0	0.00	0.00	0.00	0.00	0.000	0.00	0.000	0.000	0.013	0.00	0.00	0.00	0.00	0.0	Off
10	IB1	9.30*	0.00	4.91	4.39	Curb	6.0	10.00	0.00	0.00	0.00	0.010	2.00	0.083	0.020	0.013	0.42	14.70	0.34	10.70	0.0	Off
11	IB9	9.40*	0.00	9.40	0.00	Curb	6.0	10.00	0.00	0.00	0.00	Sag	2.00	0.050	0.020	0.013	0.46	20.06	0.46	20.06	0.0	Off
12	IB8	9.40*	0.00	9.40	0.00	Curb	6.0	10.00	0.00	0.00	0.00	Sag	2.00	0.083	0.020	0.013	0.46	16.76	0.46	16.76	0.0	Off
13	IB7	1.70*	0.00	1.67	0.03	Curb	6.0	10.00	0.00	0.00	0.00	0.010	2.00	0.083	0.020	0.013	0.26	6.70	0.07	0.84	0.0	Off
14	NB4	11.20*	0.00	0.00	11.20	None	0.0	0.00	0.00	0.00	0.00	0.000	0.00	0.000	0.000	0.013	0.00	0.00	0.00	0.00	0.0	Off
15	IB3	9.10*	0.00	4.85	4.25	Curb	6.0	10.00	0.00	0.00	0.00	0.010	2.00	0.083	0.020	0.013	0.42	14.55	0.34	10.70	0.0	Off
16	NB7	20.70*	0.00	0.00	20.70	None	0.0	0.00	0.00	0.00	0.00	0.000	0.00	0.000	0.000	0.013	0.00	0.00	0.00	0.00	0.0	Off
17	NB5	29.60*	0.00	0.00	29.60	None	0.0	0.00	0.00	0.00	0.00	0.000	0.00	0.000	0.000	0.013	0.00	0.00	0.00	0.00	0.0	Off
18	NB6	16.20*	0.00	0.00	16.20	None	0.0	0.00	0.00	0.00	0.00	0.000	0.00	0.000	0.000	0.013	0.00	0.00	0.00	0.00	0.0	Off

Project File: FM 3-7-17 HF.stm

Number of lines: 18

Run Date: 3/16/2017

NOTES: Inlet N-Values = 0.016; Known Qs only; * Indicates Known Q added. All curb inlets are throat.

FL-DOT Report

Line No	To Line	Type of struc	n - Value	Len (ft)	Drainage Area			Time of conc (min)	Time of Flow in sect (min)	Inten (I) (in/hr)	Total CA	Add Q (cfs)	Inlet elev (ft)	Elev of HGL			Rise	HGL	ADD		Date: 3/16/2017										
					C1 = 0.2 C2 = 0.5 C3 = 0.9									Total Flow			Elev of Crown			Span	Pipe	Full Flow		Frequency: (n/a)							
					Increment (ac)									Elev of Invert			Up (ft)		Down (ft)	Fall (ft)	Size (in)	Slope (%)	Vel (ft/s)	Cap (cfs)	Proj: FM 3-7-17 HF.stm						
																								Line description							
1	End	MH	0.012	25.128	0.00 0.00 0.00	0.00 0.00 0.00	0.00	2.68	0.03	0.00	0.00	0.00 163.7	6882.05	6877.94 6878.25 6878.00 6874.25 6874.00	6877.69 6878.00 6878.25 6874.25	0.25 0.25	48 48 Cir	0.99 0.99	13.51 12.35	163.7 155.2	PB16										
2	1	MH	0.012	146.947	0.00 0.00 0.00	0.00 0.00 0.00	0.00	2.44	0.24	0.00	0.00	0.00 126.8	6883.35	6879.10 6879.72 6875.72 6874.25	6877.94 6878.25 6874.25	1.16 1.47	48 48 Cir	0.79 1.00	10.84 12.39	126.8 155.7	PB13										
3	2	Curb	0.012	51.602	0.00 0.00 0.00	0.00 0.00 0.00	0.00	2.31	0.13	0.00	0.00	14.30 65.50	6883.20	6879.28 6880.24 6876.74 6876.22	6879.10 6879.72 6876.22	0.18 0.52	42 42 Cir	0.35 1.01	8.26 11.37	65.50 109.4	PB7										
4	3	Curb	0.012	44.332	0.00 0.00 0.00	0.00 0.00 0.00	0.00	2.21	0.10	0.00	0.00	11.20 51.20	6883.20	6880.01 6880.68 6877.68 6877.24	6879.28 6880.24 6877.24	0.73 0.44	36 36 Cir	1.65 0.99	9.37 10.18	51.20 71.98	PB6										
5	4	None	0.012	131.739	0.00 0.00 0.00	0.00 0.00 0.00	0.00	1.82	0.39	0.00	0.00	0.00 40.00	6884.84	6881.06 6882.00 6879.00 6877.68	6880.01 6880.68 6877.68	1.05 1.32	36 36 Cir	0.80 1.00	7.27 10.23	40.00 72.32	PB5B										
6	5	Curb	0.012	92.553	0.00 0.00 0.00	0.00 0.00 0.00	0.00	1.55	0.27	0.00	0.00	1.40 40.00	6886.62	6881.98 6882.92 6879.92 6879.00	6881.06 6882.00 6879.00	0.92 0.92	36 36 Cir	0.99 0.99	7.74 10.19	40.00 72.03	PB5A										
7	6	Curb	0.012	276.549	0.00 0.00 0.00	0.00 0.00 0.00	0.00	0.78	0.77	0.00	0.00	2.60 29.50	6890.30	6885.04 6885.69 6883.19 6880.42	6881.98 6882.92 6883.19 6880.42	3.06 2.77	30 30 Cir	1.11 1.00	8.38 9.06	29.50 44.47	PB3										
8	7	None	0.012	245.950	0.00 0.00 0.00	0.00 0.00 0.00	0.00	0.05	0.73	0.00	0.00	0.00 17.60	6893.40	6887.66 6888.15 6886.15 6883.69	6885.04 6885.69 6883.69	2.62 2.46	24 24 Cir	1.07 1.00	7.36 7.80	17.60 24.50	PB1B										
9	8	None	0.012	16.464	0.00 0.00 0.00	0.00 0.00 0.00	0.00	0.05	0.05	0.00	0.00	17.60 17.60	6893.70	6887.82 6888.31 6886.31 6886.15	6887.66 6888.15 6886.31 6886.15	0.16 0.16	24 24 Cir	0.97 0.97	6.92 7.69	17.60 24.17	PB1A										
10	7	Curb	0.012	44.336	0.00 0.00 0.00	0.00 0.00 0.00	0.00	0.00	0.14	0.00	0.00	9.30 9.30	6890.30	6885.81 6886.13 6884.63 6884.19	6885.22 6885.69 6884.19	0.58 0.44	18 18 Cir	1.32 0.99	6.70 6.41	9.30 11.33	PB2										

NOTES: Known Qs only ; Time of flow in section is based on full flow.

Project File: FM 3-7-17 HF.stm

FL-DOT Report

Page 2

Line No	To Line	Type of struc	n - Value	Len (ft)	Drainage Area			Time of conc (min)	Time of Flow in sect (min)	Inten (I) (in/hr)	Total CA	Add Q (cfs)	Inlet elev (ft)	Elev of HGL			Rise	HGL	ADD		Date: 3/16/2017						
					C1 = 0.2 C2 = 0.5 C3 = 0.9									Total Flow			Span	Pipe	Full Flow		Frequency: (n/a)						
					Increment (ac)	Sub-Total (ac)	Sum CA							Elev of Invert					Up (ft)		Down (ft)	Fall (ft)	Size (in)	Slope (%)	Vel (ft/s)	Cap (cfs)	Proj: FM 3-7-17 HF.stm
														Q	(cfs)	(ft)								Line description			
11	2	Curb	0.012	52.706	0.00 0.00 0.00	0.00 0.00 0.00	0.00 0.00 0.00	1.19	0.14	0.00	0.00	9.40 61.30	6883.04	6879.20 6880.25 6879.72 6876.75 6876.22	6879.10 6879.72 6876.22	0.11 0.53	42 42 Cir	0.20 1.01	7.88 11.36	61.30 109.3	PB12						
12	11	Curb	0.012	44.330	0.00 0.00 0.00	0.00 0.00 0.00	0.00 0.00 0.00	1.09	0.10	0.00	0.00	9.40 51.90	6883.04	6880.03 6880.69 6880.25 6877.69 6877.25	6879.20 6880.69 6880.25 6877.69	0.83 0.44	36 36 Cir	1.87 0.99	9.72 10.18	51.90 71.98	PB11						
13	12	Curb	0.012	255.617	0.00 0.00 0.00	0.00 0.00 0.00	0.00 0.00 0.00	0.05	1.04	0.00	0.00	1.70 12.90	6885.40	6882.54 6883.25 6880.69 6881.25 6878.69	6880.03 6883.25 6880.69 6881.25 6878.69	2.51 2.56	24 24 Cir	0.98 1.00	5.89 7.81	12.90 24.52	PB9						
14	13	None	0.012	10.167	0.00 0.00 0.00	0.00 0.00 0.00	0.00 0.00 0.00	0.00	0.05	0.00	0.00	11.20 11.20	6885.60	6882.55 6883.35 6883.25 6881.35 6881.25	6882.54 6883.35 6883.25 6881.35 6881.25	0.01 0.10	24 24 Cir	0.08 0.98	5.46 7.74	11.20 24.31	PB8						
15	6	Curb	0.012	44.335	0.00 0.00 0.00	0.00 0.00 0.00	0.00 0.00 0.00	0.00	0.14	0.00	0.00	9.10 9.10	6886.88	6883.03 6883.36 6882.92 6881.86 6881.42	6882.44 6883.36 6882.92 6881.86 6881.42	0.59 0.44	18 18 Cir	1.33 0.99	6.65 6.41	9.10 11.33	PB4						
16	1	None	0.012	266.443	0.00 0.00 0.00	0.00 0.00 0.00	0.00 0.00 0.00	0.00	0.67	0.00	0.00	20.70 20.70	6882.04	6880.55 6880.92 6878.25 6878.92 6876.25	6877.94 6878.25 6876.25	2.61 2.67	24 24 Cir	0.98 1.00	7.43 7.81	20.70 24.53	PB15						
17	12	None	0.012	10.167	0.00 0.00 0.00	0.00 0.00 0.00	0.00 0.00 0.00	0.00	0.03	0.00	0.00	29.60 29.60	6883.24	6880.14 6880.79 6880.69 6878.29 6878.19	6880.03 6880.79 6880.69 6878.29 6878.19	0.11 0.10	30 30 Cir	1.11 0.98	7.61 8.98	29.60 44.09	PB10						
18	1	None	0.012	269.817	0.00 0.00 0.00	0.00 0.00 0.00	0.00 0.00 0.00	0.00	0.87	0.00	0.00	16.20 16.20	6882.06	6880.40 6880.95 6878.25 6878.95 6876.25	6877.94 6878.25 6876.25	2.46 2.70	24 24 Cir	0.91 1.00	6.18 7.80	16.20 24.51	PB14						

NOTES: Known Qs only ; Time of flow in section is based on full flow.

Project File: FM 3-7-17 HF.stm

MyReport

Line No.	Area Dn	Area Up	Byp Ln No	Coeff C1	Coeff C2	Coeff C3	Capac Full	Crit Depth	Cross Sl, Sw	Cross Sl, Sx	Curb Len	Defl Ang	Depth Dn	Depth Up	DnStm Ln No	Drng Area	Easting X	EGL Dn	EGL Up	Energy Loss	
	(sqft)	(sqft)		(C)	(C)	(C)	(cfs)	(ft)	(ft/ft)	(ft)	(ft)	(Deg)	(ft)	(ft)	(ac)	(ft)	(ft)	(ft)	(ft)		
1	12.12	12.11	n/a	0.20	0.50	0.90	155.22	3.69	-89.363	3.69	3.69**	Outfall	0.00	9422.28	6880.53	6880.78	0.000	
2	11.31	11.31	n/a	0.20	0.50	0.90	155.66	3.37	-0.786	3.69	3.37**	1	0.00	9421.90	6879.89	6881.05	0.000	
3	7.46	7.46	Sag	0.20	0.50	0.90	109.41	2.53	0.083	0.020	10.00	53.397	2.87	2.54**	2	0.00	9463.25	6880.29	6880.47	0.000	
4	5.11	5.88	Sag	0.20	0.50	0.90	71.98	2.33	0.083	0.020	10.00	-53.375	2.04	2.33**	3	0.00	9463.15	6880.46	6881.19	0.000	
5	5.17	5.17	n/a	0.20	0.50	0.90	72.32	2.06	88.983	2.33	2.06**	4	0.00	9594.86	6880.94	6881.99	0.000	
6	5.17	5.17	Offsite	0.20	0.50	0.90	72.03	2.06	0.083	0.020	10.00	-46.653	2.06	2.06**	5	0.00	9657.03	6881.99	6882.91	0.000	
7	3.21	3.89	Offsite	0.20	0.50	0.90	44.47	1.85	0.083	0.020	10.00	-42.201	1.56	1.85**	6	0.00	9657.04	6882.87	6885.93	0.000	
8	2.26	2.55	n/a	0.20	0.50	0.90	24.50	1.51	0.000	1.35	1.51**	7	0.00	9657.05	6885.78	6888.40	0.000	
9	2.55	2.55	n/a	0.20	0.50	0.90	24.17	1.51	-53.625	1.51	1.51**	8	0.00	9643.80	6888.40	6888.56	0.000	
10	1.30	1.49	Offsite	0.20	0.50	0.90	11.33	1.18	0.083	0.020	10.00	89.981	1.03	1.18**	7	0.00	9701.38	6885.83	6886.42	0.000	
11	7.20	7.20	Sag	0.20	0.50	0.90	109.27	2.45	0.050	0.020	10.00	-53.988	2.87	2.45**	2	0.00	9379.19	6880.22	6880.33	0.000	
12	4.87	5.92	Sag	0.20	0.50	0.90	71.98	2.34	0.083	0.020	10.00	54.116	1.95	2.34**	11	0.00	9379.17	6880.40	6881.23	0.000	
13	2.14	2.14	Offsite	0.20	0.50	0.90	24.52	1.29	0.083	0.020	10.00	-89.979	1.34	1.29**	12	0.00	9123.56	6880.59	6883.10	0.000	
14	1.97	1.97	n/a	0.20	0.50	0.90	24.31	1.20	89.940	1.29	1.20**	13	0.00	9123.54	6883.05	6883.05	0.000	
15	1.28	1.47	Offsite	0.20	0.50	0.90	11.33	1.17	0.083	0.020	10.00	47.813	1.02	1.17**	6	0.00	9701.37	6883.03	6883.62	0.000	
16	2.74	2.74	n/a	0.20	0.50	0.90	24.53	1.63	89.475	1.69	1.63**	1	0.00	9688.73	6878.83	6881.44	0.000	
17	3.87	3.90	n/a	0.20	0.50	0.90	44.09	1.85	-0.039	1.84	1.85**	12	0.00	9379.16	6880.93	6881.04	0.000	
18	2.44	2.44	n/a	0.20	0.50	0.90	24.51	1.45	-90.576	1.69	1.45**	1	0.00	9152.47	6878.63	6881.09	0.000	

Project File: FM 3-7-17 HF.stm

Number of lines: 18

Date: 3/16/2017

NOTES: ** Critical depth

MyReport

Flow Rate (cfs)	Sf Ave (ft/ft)	Sf Dn (ft/ft)	Grate Area (sqft)	Grate Len (ft)	Grate Width (ft)	Gnd/Rim El Dn (ft)	Gnd/Rim El Up (ft)	Gutter Depth (ft)	Gutter Slope (ft/ft)	Gutter Spread (ft)	Gutter Width (ft)	HGL Dn (ft)	HGL Up (ft)	HGL Jnct (ft)	HGL Jmp Dn (ft)	HGL Jmp Up (ft)	Incr Cx A (cfs)	Incr Q (ft)	Inlet Depth (ft)	Inlet Eff (%)
163.70	0.000	0.000	6878.66	6882.05	6877.69	6877.94	6877.94	0.00	0.00
126.80	0.000	0.000	6882.05	6883.35	6877.94	6879.10	6879.10	0.00	0.00
65.50	0.000	0.000	6883.35	6883.20	0.61	Sag	24.20	2.00	6879.10	6879.28	6879.28	0.00	14.30	0.61	100
51.20	0.000	0.000	6883.20	6883.20	0.52	Sag	19.62	2.00	6879.28	6880.01	6880.01	0.00	11.20	0.52	100
40.00	0.000	0.000	6883.20	6884.84	6880.01	6881.06 j	6881.06	6879.88	6879.75	0.00	0.00
40.00	0.000	0.000	6884.84	6886.62	0.25	0.010	5.95	2.00	6881.06	6881.98	6881.98	0.00	1.40	0.25	100
29.50	0.000	0.000	6886.62	6890.30	0.29	0.010	8.35	2.00	6881.98	6885.04	6885.04	0.00	2.60	0.29	89
17.60	0.000	0.000	6890.30	6893.40	6885.04	6887.66	6887.66	0.00	0.00
17.60	0.000	0.000	6893.40	6893.70	6887.66	6887.82	6887.82	0.00	17.60
9.30	0.000	0.000	6890.30	6890.30	0.42	0.010	14.70	2.00	6885.22	6885.81	6885.81	0.00	9.30	0.42	53
61.30	0.000	0.000	6883.35	6883.04	0.46	Sag	20.06	2.00	6879.10	6879.20	6879.20	0.00	9.40	0.46	100
51.90	0.000	0.000	6883.04	6883.04	0.46	Sag	16.76	2.00	6879.20	6880.03	6880.03	0.00	9.40	0.46	100
12.90	0.000	0.000	6883.04	6885.40	0.26	0.010	6.70	2.00	6880.03	6882.54 j	6882.54	6880.24	6880.10	0.00	1.70	0.26	98
11.20	0.000	0.000	6885.40	6885.60	6882.54	6882.55	6882.55	0.00	11.20
9.10	0.000	0.000	6886.62	6886.88	0.42	0.010	14.55	2.00	6882.44	6883.03	6883.03	0.00	9.10	0.42	53
20.70	0.000	0.000	6882.05	6882.04	6877.94	6880.55 j	6880.55	6878.15	6878.06	0.00	20.70
29.60	0.000	0.000	6883.04	6883.24	6880.03	6880.14	6880.14	0.00	29.60
16.20	0.000	0.000	6882.05	6882.06	6877.94	6880.40 j	6880.40	6877.97	6877.83	0.00	16.20

Project File: FM 3-7-17 HF.stm

Number of lines: 18

Date: 3/16/2017

NOTES: ** Critical depth

MyReport

Inlet ID	Inlet Loc		Inlet Time	i Sys	i Inlet	Invert Dn	Invert Up	Jump Loc	Jump Len	Vel Hd Jmp Dn	Vel Hd Jmp Up	J-Loss Coeff	Junct Type	Known Q	Cost RCP	Cost CMP	Cost PVC	Line ID	
		(ft)	(min)	(in/hr)	(in/hr)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)			(cfs)					
MB2	Sag		0.0	0.00	0.00	6874.00	6874.25	0.00	0.00	1.00 z	MH	0.00	1,646	1,481	1,399	PB16	
MB1	Sag		0.0	0.00	0.00	6874.25	6875.72	0.00	0.00	0.84 z	MH	0.00	9,506	8,555	8,080	PB13	
IB6	Sag		0.0	0.00	0.00	6876.22	6876.74	0.00	0.00	1.25 z	Curb	14.30	3,323	2,991	2,825	PB7	
IB5	Sag		0.0	0.00	0.00	6877.24	6877.68	0.00	0.00	1.50 z	Curb	11.20	2,408	2,167	2,047	PB6	
NB3	On Grade		0.0	0.00	0.00	6877.68	6879.00	13.17	10.32	0.92	1.21	0.77 z	None	0.00	6,958	6,262	5,914	PB5B	
IB4	On Grade		0.0	0.00	0.00	6879.00	6879.92	0.00	0.00	1.17 z	Curb	1.40	5,544	4,990	4,712	PB5A	
IB2	On Grade		0.0	0.00	0.00	6880.42	6883.19	0.00	0.00	1.50 z	Curb	2.60	15,614	14,053	13,272	PB3	
NB2	On Grade		0.0	0.00	0.00	6883.69	6886.15	0.00	0.00	0.84 z	None	0.00	12,896	11,606	10,962	PB1B	
NB1	On Grade		0.0	0.00	0.00	6886.15	6886.31	0.00	0.00	1.00 z	None	17.60	962	866	818	PB1A	
IB1	On Grade		0.0	0.00	0.00	6884.19	6884.63	0.00	0.00	1.00 z	Curb	9.30	1,935	1,742	1,645	PB2	
IB9	Sag		0.0	0.00	0.00	6876.22	6876.75	0.00	0.00	1.26 z	Curb	9.40	3,385	3,047	2,877	PB12	
IB8	Sag		0.0	0.00	0.00	6877.25	6877.69	0.00	0.00	1.50 z	Curb	9.40	2,408	2,167	2,047	PB11	
IB7	On Grade		0.0	0.00	0.00	6878.69	6881.25	25.56	6.46	0.56	0.86	1.50 z	Curb	1.70	11,362	10,226	9,658	PB9	
NB4	On Grade		0.0	0.00	0.00	6881.25	6881.35	0.00	0.00	1.00 z	None	11.20	560	504	476	PB8	
IB3	On Grade		0.0	0.00	0.00	6881.42	6881.86	0.00	0.00	1.00 z	Curb	9.10	1,880	1,692	1,598	PB4	
NB7	On Grade		0.0	0.00	0.00	6876.25	6878.92	26.64	8.15	0.89	1.11	1.00 z	None	20.70	11,104	9,994	9,438	PB15	
NB5	On Grade		0.0	0.00	0.00	6878.19	6878.29	0.00	0.00	1.00 z	None	29.60	600	540	510	PB10	
NB6	On Grade		0.0	0.00	0.00	6876.25	6878.95	26.98	7.25	0.69	0.97	1.00 z	None	16.20	11,246	10,121	9,559	PB14	

Project File: FM 3-7-17 HF.stm

Number of lines: 18

Date: 3/16/2017

NOTES: Known Qs only. ; ** Critical depth

MyReport

Page 4

Line Length (ft)	Line Size (in)	Line Slope (%)	Line Type	Local Depr (in)	n-val Gutter	n-val Pipe	Minor Loss	Northing Y (ft)	Pipe Travel (min)	Q Byp (cfs)	Q Capt (cfs)	Q Carry (cfs)	Line Rise (in)	Runoff Coeff (C)	Line Span (in)	Area A1 (ac)	Area A2 (ac)	Area A3 (ac)	Tc (min)	Throat Ht (in)	Total Area (ac)	Total CxA
25.128	48	0.99	Cir	0.012	n/a	15205.44	0.03	48	0.00	48	0.00	0.00	0.00	2.7	0.00	0.00
146.947	48	1.00	Cir	0.012	1.64	15352.39	0.24	48	0.00	48	0.00	0.00	0.00	2.4	0.00	0.00
51.602	42	1.01	Cir	0.0	0.012	1.50	15383.27	0.13	0.00	14.30	0.00	42	0.00	42	0.00	0.00	0.00	2.3	6.0	0.00	0.00
44.332	36	0.99	Cir	0.0	0.012	n/a	15427.60	0.10	0.00	11.20	0.00	36	0.00	36	0.00	0.00	0.00	2.2	6.0	0.00	0.00
131.739	36	1.00	Cir	0.012	n/a	15430.23	0.39	36	0.00	36	0.00	0.00	0.00	1.8	0.00	0.00
92.553	36	0.99	Cir	0.0	0.013	0.012	n/a	15498.79	0.27	0.00	1.40	0.00	36	0.00	36	0.00	0.00	0.00	1.5	6.0	0.00	0.00
276.549	30	1.00	Cir	0.0	0.013	0.012	1.34	15775.34	0.77	0.29	2.31	0.00	30	0.00	30	0.00	0.00	0.00	0.8	6.0	0.00	0.00
245.950	24	1.00	Cir	0.012	n/a	16021.29	0.73	24	0.00	24	0.00	0.00	0.00	0.0	0.00	0.00
16.464	24	0.97	Cir	0.012	n/a	16031.05	0.05	24	0.00	24	0.00	0.00	0.00	0.0	0.00	0.00
44.336	18	0.99	Cir	0.0	0.013	0.012	n/a	15775.35	0.14	4.39	4.91	0.00	18	0.00	18	0.00	0.00	0.00	0.0	6.0	0.00	0.00
52.706	42	1.01	Cir	0.0	0.012	n/a	15383.27	0.14	0.00	9.40	0.00	42	0.00	42	0.00	0.00	0.00	1.2	6.0	0.00	0.00
44.330	36	0.99	Cir	0.0	0.012	n/a	15427.60	0.10	0.00	9.40	0.00	36	0.00	36	0.00	0.00	0.00	1.1	6.0	0.00	0.00
255.617	24	1.00	Cir	0.0	0.013	0.012	n/a	15427.60	1.04	0.03	1.67	0.00	24	0.00	24	0.00	0.00	0.00	0.0	6.0	0.00	0.00
10.167	24	0.98	Cir	0.012	n/a	15437.77	0.05	24	0.00	24	0.00	0.00	0.00	0.0	0.00	0.00
44.335	18	0.99	Cir	0.0	0.013	0.012	0.59	15498.78	0.14	4.25	4.85	0.00	18	0.00	18	0.00	0.00	0.00	0.0	6.0	0.00	0.00
266.443	24	1.00	Cir	0.012	n/a	15204.93	0.67	24	0.00	24	0.00	0.00	0.00	0.0	0.00	0.00
10.167	30	0.98	Cir	0.012	0.89	15437.77	0.03	30	0.00	30	0.00	0.00	0.00	0.0	0.00	0.00
269.817	24	1.00	Cir	0.012	n/a	15205.73	0.87	24	0.00	24	0.00	0.00	0.00	0.0	0.00	0.00

Project File: FM 3-7-17 HF.stm

Number of lines: 18

Date: 3/16/2017

NOTES: ** Critical depth

MyReport

Total Runoff	Vel Ave	Vel Dn	Vel Hd Dn	Vel Hd Up	Vel Up	Cover Dn	Cover Up	Storage	
(cfs)	(ft/s)	(ft/s)	(ft)	(ft)	(ft/s)	(ft)	(ft)	(cft)	
0.00	13.51	13.51	2.84	2.84	13.51	0.66	3.80	304.43	
0.00	10.84	10.47	1.95	1.95	11.21	3.80	3.63	1723.89	
0.00	8.26	7.75	1.20	1.20	8.78	3.63	2.96	411.33	
0.00	9.37	10.03	1.18	1.18	8.71	2.96	2.52	243.81	
0.00	7.27	6.80	0.93	0.93	7.74	2.52	2.84	728.38	
0.00	7.74	7.74	0.93	0.93	7.74	2.84	3.70	478.15	
0.00	8.38	9.18	0.89	0.89	7.57	3.70	4.61	984.74	
0.00	7.36	7.80	0.74	0.74	6.92	4.61	5.25	590.95	
0.00	6.92	6.92	0.74	0.74	6.92	5.25	5.39	41.90	
0.00	6.70	7.16	0.61	0.61	6.25	4.61	4.17	61.86	
0.00	7.88	7.25	1.13	1.13	8.52	3.63	2.79	413.49	
0.00	9.72	10.66	1.20	1.20	8.77	2.79	2.35	239.62	
0.00	5.89	5.76	0.56	0.56	6.02	2.35	2.15	560.42	
0.00	5.46	5.22	0.50	0.50	5.70	2.15	2.25	20.90	
0.00	6.65	7.13	0.59	0.59	6.17	3.70	3.52	61.05	
0.00	7.43	7.31	0.89	0.89	7.55	3.80	1.12	742.30	
0.00	7.61	7.64	0.89	0.89	7.59	2.35	2.45	39.52	
0.00	6.18	5.72	0.69	0.69	6.64	3.80	1.11	712.62	

Project File: FM 3-7-17 HF.stm

Number of lines: 18

Date: 3/16/2017

NOTES: ** Critical depth

Storm Sewer Inlet Time Tabulation

Line No.	Line ID	Tc Method	Sheet Flow					Shallow Concentrated Flow					Channel Flow							Total Travel Time (min)
			n-Value	flow Length (ft)	2-yr 24h P (in)	Land Slope (%)	Travel Time (min)	flow Length (ft)	Water Slope (%)	Surf Descr	Ave Vel (ft/s)	Travel Time (min)	X-sec Area (sqft)	Wetted Perim (ft)	Chan Slope (%)	n-Value	Vel	flow Length (ft)	Travel Time (min)	
1	PB16	User																		0.00
2	PB13	User																		0.00
3	PB7	User																		0.00
4	PB6	User																		0.00
5	PB5B	User																		0.00
6	PB5A	User																		0.00
7	PB3	User																		0.00
8	PB1B	User																		0.00
9	PB1A	User																		0.00
10	PB2	User																		0.00
11	PB12	User																		0.00
12	PB11	User																		0.00
13	PB9	User																		0.00
14	PB8	User																		0.00
15	PB4	User																		0.00
16	PB15	User																		0.00
17	PB10	User																		0.00
18	PB14	User																		0.00

Project File: FM 3-7-17 HF.stm

Min. Tc used for intensity calculations = 5 min

Number of lines: 18

Date: 3/16/2017

Hydraulic Grade Line Computations

Line (1)	Size (in) (2)	Q (cfs) (3)	Downstream							Len (ft) (12)	Upstream							Check		JL coeff (K) (23)	Minor loss (ft) (24)		
			Invert elev (ft) (4)	HGL elev (ft) (5)	Depth (ft) (6)	Area (sqft) (7)	Vel (ft/s) (8)	Vel head (ft) (9)	EGL elev (ft) (10)		Invert elev (ft) (13)	HGL elev (ft) (14)	Depth (ft) (15)	Area (sqft) (16)	Vel (ft/s) (17)	Vel head (ft) (18)	EGL elev (ft) (19)	Sf (%) (20)	Ave Sf (%) (21)	Energy loss (ft) (22)			
1	48	163.7	6874.00	6877.69	3.69	12.12	13.51	2.84	6880.53	0.000	25.128	6874.25	6877.94	3.69**	12.11	13.51	2.84	6880.78	0.000	0.000	n/a	1.00	n/a
2	48	126.8	6874.25	6877.94	3.69	11.31	10.47	1.95	6879.89	0.000	146.947	6875.72	6879.10	3.37**	11.31	11.21	1.95	6881.05	0.000	0.000	n/a	0.84	1.64
3	42	65.50	6876.22	6879.10	2.87	7.46	7.75	1.20	6880.29	0.000	51.602	6876.74	6879.28	2.54**	7.46	8.78	1.20	6880.47	0.000	0.000	n/a	1.25	1.50
4	36	51.20	6877.24	6879.28	2.04	5.11	10.03	1.18	6880.46	0.000	44.332	6877.68	6880.01	2.33**	5.88	8.71	1.18	6881.19	0.000	0.000	n/a	1.50	n/a
5	36	40.00	6877.68	6880.01	2.33	5.17	6.80	0.93	6880.94	0.000	131.739	6879.00	6881.06j	2.06**	5.17	7.74	0.93	6881.99	0.000	0.000	n/a	0.77	n/a
6	36	40.00	6879.00	6881.06	2.06*	5.17	7.74	0.93	6881.99	0.000	92.553	6879.92	6881.98	2.06**	5.17	7.74	0.93	6882.91	0.000	0.000	n/a	1.17	n/a
7	30	29.50	6880.42	6881.98	1.56	3.21	9.18	0.89	6882.87	0.000	276.549	6883.19	6885.04	1.85**	3.89	7.57	0.89	6885.93	0.000	0.000	n/a	1.50	1.34
8	24	17.60	6883.69	6885.04	1.35	2.26	7.80	0.74	6885.78	0.000	245.950	6886.15	6887.66	1.51**	2.55	6.92	0.74	6888.40	0.000	0.000	n/a	0.84	n/a
9	24	17.60	6886.15	6887.66	1.51*	2.55	6.92	0.74	6888.40	0.000	16.464	6886.31	6887.82	1.51**	2.55	6.92	0.74	6888.56	0.000	0.000	n/a	1.00	n/a
10	18	9.30	6884.19	6885.22	1.03*	1.30	7.16	0.61	6885.83	0.000	44.336	6884.63	6885.81	1.18**	1.49	6.25	0.61	6886.42	0.000	0.000	n/a	1.00	n/a
11	42	61.30	6876.22	6879.10	2.87	7.20	7.25	1.13	6880.22	0.000	52.706	6876.75	6879.20	2.45**	7.20	8.52	1.13	6880.33	0.000	0.000	n/a	1.26	n/a
12	36	51.90	6877.25	6879.20	1.95	4.87	10.66	1.20	6880.40	0.000	44.330	6877.69	6880.03	2.34**	5.92	8.77	1.20	6881.23	0.000	0.000	n/a	1.50	n/a
13	24	12.90	6878.69	6880.03	1.34	2.14	5.76	0.56	6880.59	0.000	255.617	6881.25	6882.54j	1.29**	2.14	6.02	0.56	6883.10	0.000	0.000	n/a	1.50	0.84
14	24	11.20	6881.25	6882.54	1.29	1.97	5.22	0.50	6883.05	0.000	10.167	6881.35	6882.55	1.20**	1.97	5.70	0.50	6883.05	0.000	0.000	n/a	1.00	n/a
15	18	9.10	6881.42	6882.44	1.02*	1.28	7.13	0.59	6883.03	0.000	44.335	6881.86	6883.03	1.17**	1.47	6.17	0.59	6883.62	0.000	0.000	n/a	1.00	0.59
16	24	20.70	6876.25	6877.94	1.69	2.74	7.31	0.89	6878.83	0.000	266.443	6878.92	6880.55j	1.63**	2.74	7.55	0.89	6881.44	0.000	0.000	n/a	1.00	n/a
17	30	29.60	6878.19	6880.03	1.84	3.87	7.64	0.89	6880.93	0.000	10.167	6878.29	6880.14	1.85**	3.90	7.59	0.89	6881.04	0.000	0.000	n/a	1.00	0.89
18	24	16.20	6876.25	6877.94	1.69	2.44	5.72	0.69	6878.63	0.000	269.817	6878.95	6880.40j	1.45**	2.44	6.64	0.69	6881.09	0.000	0.000	n/a	1.00	n/a

Project File: FM 3-7-17 HF.stm

Number of lines: 18

Run Date: 3/16/2017

Notes: * depth assumed; ** Critical depth.; j-Line contains hyd. jump ; c = cir e = ellip b = box

Hydraflow HGL Computation Procedure

General Procedure:

Hydraflow computes the HGL using the Bernoulli energy equation. Manning's equation is used to determine energy losses due to pipe friction. In a standard step, iterative procedure, Hydraflow assumes upstream HGLs until the energy equation balances. If the energy equation cannot balance, supercritical flow exists and critical depth is temporarily assumed at the upstream end. A supercritical flow Profile is then computed using the same procedure in a downstream direction using momentum principles.

- Col. 1 The line number being computed. Calculations begin at Line 1 and proceed upstream.
- Col. 2 The line size. In the case of non-circular pipes, the line rise is printed above the span.
- Col. 3 Total flow rate in the line.
- Col. 4 The elevation of the downstream invert.
- Col. 5 Elevation of the hydraulic grade line at the downstream end. This is computed as the upstream HGL + Minor loss of this line's downstream line.
- Col. 6 The downstream depth of flow inside the pipe (HGL - Invert elevation) but not greater than the line size.
- Col. 7 Cross-sectional area of the flow at the downstream end.
- Col. 8 The velocity of the flow at the downstream end, (Col. 3 / Col. 7).
- Col. 9 Velocity head (Velocity squared / 2g).
- Col. 10 The elevation of the energy grade line at the downstream end, HGL + Velocity head, (Col. 5 + Col. 9).
- Col. 11 The friction slope at the downstream end (the S or Slope term in Manning's equation).
- Col. 12 The line length.
- Col. 13 The elevation of the upstream invert.
- Col. 14 Elevation of the hydraulic grade line at the upstream end.
- Col. 15 The upstream depth of flow inside the pipe (HGL - Invert elevation) but not greater than the line size.
- Col. 16 Cross-sectional area of the flow at the upstream end.
- Col. 17 The velocity of the flow at the upstream end, (Col. 3 / Col. 16).
- Col. 18 Velocity head (Velocity squared / 2g).
- Col. 19 The elevation of the energy grade line at the upstream end, HGL + Velocity head, (Col. 14 + Col. 18).
- Col. 20 The friction slope at the upstream end (the S or Slope term in Manning's equation).
- Col. 21 The average of the downstream and upstream friction slopes.
- Col. 22 Energy loss. Average $S_f/100 \times \text{Line Length}$ (Col. 21/100 x Col. 12). Equals $(\text{EGL upstream} - \text{EGL downstream}) +/- \text{tolerance}$.
- Col. 23 The junction loss coefficient (K).
- Col. 24 Minor loss. (Col. 23 x Col. 18). Is added to upstream HGL and used as the starting HGL for the next upstream line(s).

ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)


(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project:

FALCON MARKETPLACE

Inlet ID:

IB1

**Gutter Geometry (Enter data in the blue cells)**

Maximum Allowable Width for Spread Behind Curb

 $T_{BACK} = 7.0$ ft

Side Slope Behind Curb (leave blank for no conveyance credit behind curb)

 $S_{BACK} = 0.020$ ft/ft

Manning's Roughness Behind Curb (typically between 0.012 and 0.020)

 $n_{BACK} = 0.020$

Height of Curb at Gutter Flow Line

 $H_{CURB} = 6.00$ inches

Distance from Curb Face to Street Crown

 $T_{CROWN} = 20.0$ ft

Gutter Width

 $W = 2.00$ ft

Street Transverse Slope

 $S_x = 0.020$ ft/ft

Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)

 $S_w = 0.083$ ft/ft

Street Longitudinal Slope - Enter 0 for sump condition

 $S_o = 0.010$ ft/ft

Manning's Roughness for Street Section (typically between 0.012 and 0.020)

 $n_{STREET} = 0.013$

Max. Allowable Spread for Minor & Major Storm

Minor Storm

Major Storm

 $T_{MAX} = 20.0 \quad 20.0$ ft

Max. Allowable Depth at Gutter Flowline for Minor & Major Storm

 $d_{MAX} = 6.0 \quad 7.5$ inches

Allow Flow Depth at Street Crown (leave blank for no)

 check = yes

MINOR STORM Allowable Capacity is based on Depth Criterion

Minor Storm

Major Storm

 $Q_{allow} = 17.0 \quad 20.1$ cfs


MAJOR STORM Allowable Capacity is based on Spread Criterion

Minor storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'

Major storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'

INLET ON A CONTINUOUS GRADE

Version 4.04 Released November 2016



Design Information (Input)		CDOT Type R Curb Opening																	
Type of Inlet																			
Local Depression (additional to continuous gutter depression 'a')																			
Total Number of Units in the Inlet (Grate or Curb Opening)																			
Length of a Single Unit Inlet (Grate or Curb Opening)																			
Width of a Unit Grate (cannot be greater than W, Gutter Width)																			
Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.5)																			
Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.1)																			
Street Hydraulics: OK - Q < Allowable Street Capacity'																			
Total Inlet Interception Capacity																			
Total Inlet Carry-Over Flow (flow bypassing inlet)																			
Capture Percentage = $Q_a/Q_o =$																			
<table border="1" style="margin-left: auto; margin-right: 0;"> <thead> <tr> <th style="text-align: center;">MINOR</th> <th style="text-align: center;">MAJOR</th> </tr> </thead> <tbody> <tr> <td style="text-align: center;">Type = CDOT Type R Curb Opening</td> <td style="text-align: center;"></td> </tr> <tr> <td style="text-align: center;">a_{LOCAL} = 3.0</td> <td style="text-align: center;">3.0</td> </tr> <tr> <td style="text-align: center;">N_o = 1</td> <td style="text-align: center;">1</td> </tr> <tr> <td style="text-align: center;">L_o = 10.00</td> <td style="text-align: center;">10.00</td> </tr> <tr> <td style="text-align: center;">W_o = N/A</td> <td style="text-align: center;">N/A</td> </tr> <tr> <td style="text-align: center;">C_rG = N/A</td> <td style="text-align: center;">N/A</td> </tr> <tr> <td style="text-align: center;">C_rC = 0.10</td> <td style="text-align: center;">0.10</td> </tr> </tbody> </table>				MINOR	MAJOR	Type = CDOT Type R Curb Opening		a _{LOCAL} = 3.0	3.0	N _o = 1	1	L _o = 10.00	10.00	W _o = N/A	N/A	C _r G = N/A	N/A	C _r C = 0.10	0.10
MINOR	MAJOR																		
Type = CDOT Type R Curb Opening																			
a _{LOCAL} = 3.0	3.0																		
N _o = 1	1																		
L _o = 10.00	10.00																		
W _o = N/A	N/A																		
C _r G = N/A	N/A																		
C _r C = 0.10	0.10																		
<table border="1" style="margin-left: auto; margin-right: 0;"> <thead> <tr> <th style="text-align: center;">MINOR</th> <th style="text-align: center;">MAJOR</th> </tr> </thead> <tbody> <tr> <td style="text-align: center;">Q = 7.0</td> <td style="text-align: center;">9.3</td> </tr> <tr> <td style="text-align: center;">Q_b = 3.9</td> <td style="text-align: center;">10.5</td> </tr> <tr> <td style="text-align: center;">C% = 64</td> <td style="text-align: center;">47</td> </tr> </tbody> </table>				MINOR	MAJOR	Q = 7.0	9.3	Q _b = 3.9	10.5	C% = 64	47								
MINOR	MAJOR																		
Q = 7.0	9.3																		
Q _b = 3.9	10.5																		
C% = 64	47																		

ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)


(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project:

FALCON MARKETPLACE

Inlet ID:

IB2

**Gutter Geometry (Enter data in the blue cells)**

Maximum Allowable Width for Spread Behind Curb

T_{BACK} = ft

Side Slope Behind Curb (leave blank for no conveyance credit behind curb)

S_{BACK} = ft/ft

Manning's Roughness Behind Curb (typically between 0.012 and 0.020)

n_{BACK} =

Height of Curb at Gutter Flow Line

H_{CURB} = inches

Distance from Curb Face to Street Crown

T_{CROWN} = ft

Gutter Width

W = ft

Street Transverse Slope

S_x = ft/ft

Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)

S_w = ft/ft

Street Longitudinal Slope - Enter 0 for sump condition

S_o = ft/ft

Manning's Roughness for Street Section (typically between 0.012 and 0.020)

n_{STREET} =

Max. Allowable Spread for Minor & Major Storm

Minor Storm ft

Max. Allowable Depth at Gutter Flowline for Minor & Major Storm

Major Storm ft

Allow Flow Depth at Street Crown (leave blank for no)

d_{MAX} = inches check = yes

MINOR STORM Allowable Capacity is based on Depth Criterion

Minor Storm cfs

MAJOR STORM Allowable Capacity is based on Spread Criterion


Major Storm cfs

Minor storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'

Major storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'

INLET ON A CONTINUOUS GRADE

Version 4.04 Released November 2016



Design Information (Input)		CDOT Type R Curb Opening	
Type of Inlet			
Local Depression (additional to continuous gutter depression 'a')			
Total Number of Units in the Inlet (Grate or Curb Opening)			
Length of a Single Unit Inlet (Grate or Curb Opening)			
Width of a Unit Grate (cannot be greater than W, Gutter Width)			
Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.5)			
Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.1)			
Street Hydraulics: OK - Q < Allowable Street Capacity'			
Total Inlet Interception Capacity			
Total Inlet Carry-Over Flow (flow bypassing inlet)			
Capture Percentage = $Q_a/Q_o =$			
	MINOR	MAJOR	
Type =	CDOT Type R Curb Opening		
a_{LOCAL} =	3.0	3.0	inches
N_o =	1	1	
L_o =	10.00	10.00	ft
W_o =	N/A	N/A	ft
C_rG =	N/A	N/A	
C_rC =	0.10	0.10	
	MINOR	MAJOR	
Q =	1.5	2.6	cfs
Q_b =	0.0	0.0	cfs
$C\%$ =	100	100	%

ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)


(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project:

FALCON MARKETPLACE

Inlet ID:

IB3

**Gutter Geometry (Enter data in the blue cells)**

Maximum Allowable Width for Spread Behind Curb

 $T_{BACK} = 7.0$ ft

Side Slope Behind Curb (leave blank for no conveyance credit behind curb)

 $S_{BACK} = 0.020$ ft/ft

Manning's Roughness Behind Curb (typically between 0.012 and 0.020)

 $n_{BACK} = 0.020$

Height of Curb at Gutter Flow Line

 $H_{CURB} = 6.00$ inches

Distance from Curb Face to Street Crown

 $T_{CROWN} = 20.0$ ft

Gutter Width

 $W = 2.00$ ft

Street Transverse Slope

 $S_x = 0.020$ ft/ft

Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)

 $S_w = 0.083$ ft/ft

Street Longitudinal Slope - Enter 0 for sump condition

 $S_o = 0.010$ ft/ft

Manning's Roughness for Street Section (typically between 0.012 and 0.020)

 $n_{STREET} = 0.013$

Max. Allowable Spread for Minor & Major Storm

Minor Storm Major Storm

 $T_{MAX} = 20.0 \quad 20.0$ ft

Max. Allowable Depth at Gutter Flowline for Minor & Major Storm

 $d_{MAX} = 6.0 \quad 7.5$ inches

Allow Flow Depth at Street Crown (leave blank for no)

 check = yes

MINOR STORM Allowable Capacity is based on Depth Criterion

Minor Storm Major Storm

 $Q_{allow} = 17.0 \quad 20.1$ cfs


MAJOR STORM Allowable Capacity is based on Spread Criterion

Minor storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'

Major storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'

INLET ON A CONTINUOUS GRADE

Version 4.04 Released November 2016



Design Information (Input)		CDOT Type R Curb Opening	
Type of Inlet	CDOT Type R Curb Opening		
Local Depression (additional to continuous gutter depression 'a')			
Total Number of Units in the Inlet (Grate or Curb Opening)			
Length of a Single Unit Inlet (Grate or Curb Opening)			
Width of a Unit Grate (cannot be greater than W, Gutter Width)			
Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.5)			
Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.1)			
Street Hydraulics: OK - Q < Allowable Street Capacity'			
Total Inlet Interception Capacity	MINOR MAJOR		
Total Inlet Carry-Over Flow (flow bypassing inlet)	Q = 6.2	9.1	cfs
Capture Percentage = $Q_b/Q_o =$	Q _b = 2.3	10.0	cfs
	C% = 73	48	%

ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)


(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project:

FALCON MARKETPLACE

Inlet ID:

IB4

**Gutter Geometry (Enter data in the blue cells)**

Maximum Allowable Width for Spread Behind Curb

 $T_{BACK} = 7.0$ ft

Side Slope Behind Curb (leave blank for no conveyance credit behind curb)

 $S_{BACK} = 0.020$ ft/ft

Manning's Roughness Behind Curb (typically between 0.012 and 0.020)

 $n_{BACK} = 0.020$

Height of Curb at Gutter Flow Line

 $H_{CURB} = 6.00$ inches

Distance from Curb Face to Street Crown

 $T_{CROWN} = 20.0$ ft

Gutter Width

 $W = 2.00$ ft

Street Transverse Slope

 $S_x = 0.020$ ft/ft

Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)

 $S_w = 0.083$ ft/ft

Street Longitudinal Slope - Enter 0 for sump condition

 $S_o = 0.010$ ft/ft

Manning's Roughness for Street Section (typically between 0.012 and 0.020)

 $n_{STREET} = 0.013$

Max. Allowable Spread for Minor & Major Storm

Minor Storm

Major Storm

 $T_{MAX} = 20.0$ ft

Max. Allowable Depth at Gutter Flowline for Minor & Major Storm

 $d_{MAX} = 6.0$ inches

7.5 inches

Allow Flow Depth at Street Crown (leave blank for no)

 check = yes

MINOR STORM Allowable Capacity is based on Depth Criterion

Minor Storm

Major Storm

MAJOR STORM Allowable Capacity is based on Spread Criterion


 $Q_{allow} = 17.0$ cfs

Minor storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'

Major storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'

INLET ON A CONTINUOUS GRADE

Version 4.04 Released November 2016



Design Information (Input)		CDOT Type R Curb Opening	
Type of Inlet	CDOT Type R Curb Opening		
Local Depression (additional to continuous gutter depression 'a')			
Total Number of Units in the Inlet (Grate or Curb Opening)			
Length of a Single Unit Inlet (Grate or Curb Opening)			
Width of a Unit Grate (cannot be greater than W, Gutter Width)			
Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.5)			
Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.1)			
Street Hydraulics: OK - Q < Allowable Street Capacity'			
Total Inlet Interception Capacity	MINOR MAJOR		
Total Inlet Carry-Over Flow (flow bypassing inlet)	Q = 0.8	1.4	cfs
Capture Percentage = $Q_a/Q_o =$	Q _a = 0.0	0.0	cfs
	C% = 100	100	%

ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)


(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project:

FALCON MARKETPLACE

Inlet ID:

IB5

**Gutter Geometry (Enter data in the blue cells)**

Maximum Allowable Width for Spread Behind Curb

T_{BACK} = ft

Side Slope Behind Curb (leave blank for no conveyance credit behind curb)

S_{BACK} = ft/ft

Manning's Roughness Behind Curb (typically between 0.012 and 0.020)

n_{BACK} =

Height of Curb at Gutter Flow Line

H_{CURB} = inches

Distance from Curb Face to Street Crown

T_{CROWN} = ft

Gutter Width

W = ft

Street Transverse Slope

S_x = ft/ft

Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)

S_w = ft/ft

Street Longitudinal Slope - Enter 0 for sump condition

S_o = ft/ft

Manning's Roughness for Street Section (typically between 0.012 and 0.020)

n_{STREET} =

Max. Allowable Spread for Minor & Major Storm

Minor Storm Major Storm

T_{MAX} = ft

Max. Allowable Depth at Gutter Flowline for Minor & Major Storm

d_{MAX} = inches

Allow Flow Depth at Street Crown (leave blank for no)

 check = yes

MINOR STORM Allowable Capacity is based on Depth Criterion


Minor Storm Major Storm

MAJOR STORM Allowable Capacity is based on Depth Criterion

Q_{allow} = cfs

INLET IN A SUMP OR SAG LOCATION

Version 4.04 Released November 2016



Design Information (Input)	CDOT Type R Curb Opening				
Type of Inlet Local Depression (additional to continuous gutter depression 'a' from 'Q-Allow') Number of Unit Inlets (Grate or Curb Opening) Water Depth at Flowline (outside of local depression)					
Grate Information Length of a Unit Grate Width of a Unit Grate Area Opening Ratio for a Grate (typical values 0.15-0.90) Clogging Factor for a Single Grate (typical value 0.50 - 0.70) Grate Weir Coefficient (typical value 2.15 - 3.60) Grate Orifice Coefficient (typical value 0.60 - 0.80)					
Curb Opening Information Length of a Unit Curb Opening Height of Vertical Curb Opening in Inches Height of Curb Orifice Throat in Inches Angle of Throat (see USDCM Figure ST-5) Side Width for Depression Pan (typically the gutter width of 2 feet) Clogging Factor for a Single Curb Opening (typical value 0.10) Curb Opening Weir Coefficient (typical value 2.3-3.7) Curb Opening Orifice Coefficient (typical value 0.60 - 0.70)					
Low Head Performance Reduction (Calculated) Depth for Grate Midwidth Depth for Curb Opening Weir Equation Combination Inlet Performance Reduction Factor for Long Inlets Curb Opening Performance Reduction Factor for Long Inlets Grated Inlet Performance Reduction Factor for Long Inlets					
Total Inlet Interception Capacity (assumes clogged condition) WARNING: Inlet Capacity less than Q Peak for Major Storm					
Type = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr></table>					
a _{local} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr></table>					
No = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr></table>					
Ponding Depth = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr></table>					
L _o (G) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr></table>					
W _P = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr></table>					
A _{ratio} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr></table>					
C _r (G) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr></table>					
C _w (G) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr></table>					
C _o (G) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr></table>					
L _o (C) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr></table>					
H _{vert} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr></table>					
H _{throat} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr></table>					
Theta = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr></table>					
W _P = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr></table>					
C _r (C) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr></table>					
C _w (C) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr></table>					
C _o (C) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr></table>					
MINOR MAJOR					
d _{Grate} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr></table>					
d _{Curb} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr></table>					
RF _{Combination} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr></table>					
RF _{Curb} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr></table>					
RF _{Grate} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr></table>					
MINOR MAJOR					
Q _a = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr></table>					
Q _{PEAK REQUIRED} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr><tr><td style="width: 50px; height: 20px; background-color: #0070C0;"></td><td style="width: 50px; height: 20px; background-color: #0070C0;"></td></tr></table>					
cfs cfs					

ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)


(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project:

FALCON MARKETPLACE

Inlet ID:

IB6

**Gutter Geometry (Enter data in the blue cells)**

Maximum Allowable Width for Spread Behind Curb

 $T_{BACK} = 7.0$ ft

Side Slope Behind Curb (leave blank for no conveyance credit behind curb)

 $S_{BACK} = 0.020$ ft/ft

Manning's Roughness Behind Curb (typically between 0.012 and 0.020)

 $n_{BACK} = 0.020$

Height of Curb at Gutter Flow Line

 $H_{CURB} = 6.00$ inches

Distance from Curb Face to Street Crown

 $T_{CROWN} = 20.0$ ft

Gutter Width

 $W = 2.00$ ft

Street Transverse Slope

 $S_x = 0.020$ ft/ft

Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)

 $S_w = 0.083$ ft/ft

Street Longitudinal Slope - Enter 0 for sump condition

 $S_o = 0.000$ ft/ft

Manning's Roughness for Street Section (typically between 0.012 and 0.020)

 $n_{STREET} = 0.013$

Max. Allowable Spread for Minor & Major Storm

	Minor Storm	Major Storm
T_{MAX}	20.0	20.0
d_{MAX}	6.0	7.5

Max. Allowable Depth at Gutter Flowline for Minor & Major Storm

inches

Allow Flow Depth at Street Crown (leave blank for no)



check = yes

MINOR STORM Allowable Capacity is based on Depth Criterion

Minor Storm

Major Storm


MAJOR STORM Allowable Capacity is based on Depth Criterion

 $Q_{allow} = \boxed{\text{SUMP}}$ $\boxed{\text{SUMP}}$

cfs

INLET IN A SUMP OR SAG LOCATION

Version 4.04 Released November 2016



Design Information (Input)	CDOT Type R Curb Opening												
Type of Inlet													
Local Depression (additional to continuous gutter depression 'a' from 'Q-Allow')													
Number of Unit Inlets (Grate or Curb Opening)													
Water Depth at Flowline (outside of local depression)													
Grate Information													
Length of a Unit Grate	Type = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>CDOT Type R Curb Opening</td><td></td></tr><tr><td>3.00</td><td>3.00</td></tr><tr><td></td><td></td></tr></table> inches					MINOR	MAJOR	CDOT Type R Curb Opening		3.00	3.00		
MINOR	MAJOR												
CDOT Type R Curb Opening													
3.00	3.00												
Width of a Unit Grate	a _{local} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>1</td><td>1</td></tr><tr><td></td><td></td></tr></table> feet					1	1						
1	1												
Area Opening Ratio for a Grate (typical values 0.15-0.90)	No = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>6.0</td><td>7.5</td></tr><tr><td></td><td></td></tr></table> inches					6.0	7.5						
6.0	7.5												
Clogging Factor for a Single Grate (typical value 0.50 - 0.70)	Ponding Depth = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td></td><td></td></tr></table> feet					MINOR	MAJOR	N/A	N/A	N/A	N/A		
MINOR	MAJOR												
N/A	N/A												
N/A	N/A												
Grate Weir Coefficient (typical value 2.15 - 3.60)	L _o (G) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td></td><td></td></tr></table> feet					MINOR	MAJOR	N/A	N/A	N/A	N/A		
MINOR	MAJOR												
N/A	N/A												
N/A	N/A												
Grate Orifice Coefficient (typical value 0.60 - 0.80)	W _o = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td></td><td></td></tr></table> feet					MINOR	MAJOR	N/A	N/A	N/A	N/A		
MINOR	MAJOR												
N/A	N/A												
N/A	N/A												
Curb Opening Information													
Length of a Unit Curb Opening	A _{ratio} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td></td><td></td></tr></table> feet					MINOR	MAJOR	N/A	N/A	N/A	N/A		
MINOR	MAJOR												
N/A	N/A												
N/A	N/A												
Height of Vertical Curb Opening in Inches	C _r (G) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td></td><td></td></tr></table> inches					MINOR	MAJOR	N/A	N/A	N/A	N/A		
MINOR	MAJOR												
N/A	N/A												
N/A	N/A												
Height of Curb Orifice Throat in Inches	C _w (G) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td></td><td></td></tr></table> inches					MINOR	MAJOR	N/A	N/A	N/A	N/A		
MINOR	MAJOR												
N/A	N/A												
N/A	N/A												
Angle of Throat (see USDCM Figure ST-5)	C _o (G) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td></td><td></td></tr></table> degrees					MINOR	MAJOR	N/A	N/A	N/A	N/A		
MINOR	MAJOR												
N/A	N/A												
N/A	N/A												
Side Width for Depression Pan (typically the gutter width of 2 feet)	L _o (C) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>10.00</td><td>10.00</td></tr><tr><td>6.00</td><td>6.00</td></tr><tr><td></td><td></td></tr></table> feet					MINOR	MAJOR	10.00	10.00	6.00	6.00		
MINOR	MAJOR												
10.00	10.00												
6.00	6.00												
Clogging Factor for a Single Curb Opening (typical value 0.10)	H _{vert} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>6.00</td><td>6.00</td></tr><tr><td>6.00</td><td>6.00</td></tr><tr><td></td><td></td></tr></table> inches					MINOR	MAJOR	6.00	6.00	6.00	6.00		
MINOR	MAJOR												
6.00	6.00												
6.00	6.00												
Curb Opening Weir Coefficient (typical value 2.3-3.7)	H _{throat} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>63.40</td><td>63.40</td></tr><tr><td>63.40</td><td>63.40</td></tr><tr><td></td><td></td></tr></table> degrees					MINOR	MAJOR	63.40	63.40	63.40	63.40		
MINOR	MAJOR												
63.40	63.40												
63.40	63.40												
Curb Opening Orifice Coefficient (typical value 0.60 - 0.70)	Theta = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>2.00</td><td>2.00</td></tr><tr><td>2.00</td><td>2.00</td></tr><tr><td></td><td></td></tr></table> feet					MINOR	MAJOR	2.00	2.00	2.00	2.00		
MINOR	MAJOR												
2.00	2.00												
2.00	2.00												
Low Head Performance Reduction (Calculated)													
Depth for Grate Midwidth	W _p = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>0.10</td><td>0.10</td></tr><tr><td>3.60</td><td>3.60</td></tr><tr><td></td><td></td></tr></table> feet					MINOR	MAJOR	0.10	0.10	3.60	3.60		
MINOR	MAJOR												
0.10	0.10												
3.60	3.60												
Depth for Curb Opening Weir Equation	C _r (C) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>0.10</td><td>0.10</td></tr><tr><td>0.57</td><td>0.71</td></tr><tr><td></td><td></td></tr></table> ft					MINOR	MAJOR	0.10	0.10	0.57	0.71		
MINOR	MAJOR												
0.10	0.10												
0.57	0.71												
Combination Inlet Performance Reduction Factor for Long Inlets	RF _{Combination} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>0.93</td><td>1.00</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td></td><td></td></tr></table> ft					MINOR	MAJOR	0.93	1.00	N/A	N/A		
MINOR	MAJOR												
0.93	1.00												
N/A	N/A												
Curb Opening Performance Reduction Factor for Long Inlets	RF _{Curb} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>0.93</td><td>1.00</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td></td><td></td></tr></table> ft					MINOR	MAJOR	0.93	1.00	N/A	N/A		
MINOR	MAJOR												
0.93	1.00												
N/A	N/A												
Grated Inlet Performance Reduction Factor for Long Inlets	RF _{Grate} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td></td><td></td></tr></table> ft					MINOR	MAJOR	N/A	N/A	N/A	N/A		
MINOR	MAJOR												
N/A	N/A												
N/A	N/A												
Total Inlet Interception Capacity (assumes clogged condition)													
Inlet Capacity IS GOOD for Minor and Major Storms(>Q PEAK)	Q _a = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>8.3</td><td>14.3</td></tr><tr><td>3.2</td><td>11.6</td></tr><tr><td></td><td></td></tr></table> cfs					MINOR	MAJOR	8.3	14.3	3.2	11.6		
MINOR	MAJOR												
8.3	14.3												
3.2	11.6												
	Q _{PEAK REQUIRED} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td></td><td></td></tr><tr><td></td><td></td></tr><tr><td></td><td></td></tr></table> cfs					MINOR	MAJOR						
MINOR	MAJOR												

ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)


(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project:

FALCON MARKETPLACE

Inlet ID:

IB7

**Gutter Geometry (Enter data in the blue cells)**

Maximum Allowable Width for Spread Behind Curb

 $T_{BACK} = 7.0$ ft

Side Slope Behind Curb (leave blank for no conveyance credit behind curb)

 $S_{BACK} = 0.020$ ft/ft

Manning's Roughness Behind Curb (typically between 0.012 and 0.020)

 $n_{BACK} = 0.020$

Height of Curb at Gutter Flow Line

 $H_{CURB} = 6.00$ inches

Distance from Curb Face to Street Crown

 $T_{CROWN} = 20.0$ ft

Gutter Width

 $W = 2.00$ ft

Street Transverse Slope

 $S_x = 0.020$ ft/ft

Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)

 $S_w = 0.083$ ft/ft

Street Longitudinal Slope - Enter 0 for sump condition

 $S_o = 0.010$ ft/ft

Manning's Roughness for Street Section (typically between 0.012 and 0.020)

 $n_{STREET} = 0.013$

Max. Allowable Spread for Minor & Major Storm

Minor Storm	Major Storm
$T_{MAX} = 20.0$	20.0 ft

Max. Allowable Depth at Gutter Flowline for Minor & Major Storm

$d_{MAX} = 6.0$	7.5 inches
-----------------	--------------

Allow Flow Depth at Street Crown (leave blank for no)

 check = yes

MINOR STORM Allowable Capacity is based on Depth Criterion

Minor Storm

MAJOR STORM Allowable Capacity is based on Spread Criterion

Major Storm


 $Q_{allow} = 17.0$ cfs

Minor storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'

Major storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'

INLET ON A CONTINUOUS GRADE

Version 4.04 Released November 2016



Design Information (Input)		CDOT Type R Curb Opening	
Type of Inlet	CDOT Type R Curb Opening		
Local Depression (additional to continuous gutter depression 'a')			
Total Number of Units in the Inlet (Grate or Curb Opening)			
Length of a Single Unit Inlet (Grate or Curb Opening)			
Width of a Unit Grate (cannot be greater than W, Gutter Width)			
Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.5)			
Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.1)			
Street Hydraulics: OK - Q < Allowable Street Capacity'			
Total Inlet Interception Capacity	MINOR MAJOR		
Total Inlet Carry-Over Flow (flow bypassing inlet)	Q = 1.0	1.7	cfs
Capture Percentage = $Q_a/Q_o =$	Q _a = 0.0	0.0	cfs
	C% = 100	100	%

ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)


(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project:

FALCON MARKETPLACE

Inlet ID:

IB8

**Gutter Geometry (Enter data in the blue cells)**

Maximum Allowable Width for Spread Behind Curb

 $T_{BACK} = 7.0$ ft

Side Slope Behind Curb (leave blank for no conveyance credit behind curb)

 $S_{BACK} = 0.020$ ft/ft

Manning's Roughness Behind Curb (typically between 0.012 and 0.020)

 $n_{BACK} = 0.020$

Height of Curb at Gutter Flow Line

 $H_{CURB} = 6.00$ inches

Distance from Curb Face to Street Crown

 $T_{CROWN} = 20.0$ ft

Gutter Width

 $W = 2.00$ ft

Street Transverse Slope

 $S_x = 0.020$ ft/ft

Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)

 $S_w = 0.083$ ft/ft

Street Longitudinal Slope - Enter 0 for sump condition

 $S_o = 0.000$ ft/ft

Manning's Roughness for Street Section (typically between 0.012 and 0.020)

 $n_{STREET} = 0.013$

Max. Allowable Spread for Minor & Major Storm

	Minor Storm	Major Storm
T_{MAX}	20.0	20.0
d_{MAX}	6.0	7.5

Max. Allowable Depth at Gutter Flowline for Minor & Major Storm

inches

Allow Flow Depth at Street Crown (leave blank for no)



check = yes

MINOR STORM Allowable Capacity is based on Depth Criterion

Minor Storm

Major Storm

MAJOR STORM Allowable Capacity is based on Depth Criterion


SUMP

SUMP

cfs

INLET IN A SUMP OR SAG LOCATION

Version 4.04 Released November 2016



Design Information (Input)	CDOT Type R Curb Opening												
Type of Inlet													
Local Depression (additional to continuous gutter depression 'a' from 'Q-Allow')													
Number of Unit Inlets (Grate or Curb Opening)													
Water Depth at Flowline (outside of local depression)													
Grate Information													
Length of a Unit Grate	Type = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>CDOT Type R Curb Opening</td><td></td></tr><tr><td>3.00</td><td>3.00</td></tr><tr><td></td><td></td></tr></table> inches					MINOR	MAJOR	CDOT Type R Curb Opening		3.00	3.00		
MINOR	MAJOR												
CDOT Type R Curb Opening													
3.00	3.00												
Width of a Unit Grate	a _{local} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>1</td><td>1</td></tr><tr><td></td><td></td></tr></table> feet					1	1						
1	1												
Area Opening Ratio for a Grate (typical values 0.15-0.90)	No = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>6.0</td><td>6.3</td></tr><tr><td></td><td></td></tr></table> inches					6.0	6.3						
6.0	6.3												
Clogging Factor for a Single Grate (typical value 0.50 - 0.70)	Ponding Depth = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td></td><td></td></tr></table> feet					MINOR	MAJOR	N/A	N/A	N/A	N/A		
MINOR	MAJOR												
N/A	N/A												
N/A	N/A												
Grate Weir Coefficient (typical value 2.15 - 3.60)	L _o (G) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>6.0</td><td>6.3</td></tr><tr><td></td><td></td></tr></table> feet					6.0	6.3						
6.0	6.3												
Grate Orifice Coefficient (typical value 0.60 - 0.80)	W _o = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td></td><td></td></tr></table> feet					N/A	N/A	N/A	N/A				
N/A	N/A												
N/A	N/A												
Curb Opening Information													
Length of a Unit Curb Opening	A _{ratio} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td></td><td></td></tr></table> feet					N/A	N/A	N/A	N/A				
N/A	N/A												
N/A	N/A												
Height of Vertical Curb Opening in Inches	C _r (G) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td></td><td></td></tr></table> degrees					N/A	N/A	N/A	N/A				
N/A	N/A												
N/A	N/A												
Height of Curb Orifice Throat in Inches	C _w (G) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td></td><td></td></tr></table> feet					N/A	N/A	N/A	N/A				
N/A	N/A												
N/A	N/A												
Angle of Throat (see USDCM Figure ST-5)	C _o (G) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td></td><td></td></tr></table> feet					N/A	N/A	N/A	N/A				
N/A	N/A												
N/A	N/A												
Side Width for Depression Pan (typically the gutter width of 2 feet)	L _o (C) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>10.00</td><td>10.00</td></tr><tr><td></td><td></td></tr></table> feet					10.00	10.00						
10.00	10.00												
Clogging Factor for a Single Curb Opening (typical value 0.10)	H _{vert} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>6.00</td><td>6.00</td></tr><tr><td></td><td></td></tr></table> inches					6.00	6.00						
6.00	6.00												
Curb Opening Weir Coefficient (typical value 2.3-3.7)	H _{throat} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>6.00</td><td>6.00</td></tr><tr><td></td><td></td></tr></table> inches					6.00	6.00						
6.00	6.00												
Curb Opening Orifice Coefficient (typical value 0.60 - 0.70)	Theta = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>63.40</td><td>63.40</td></tr><tr><td></td><td></td></tr></table> degrees					63.40	63.40						
63.40	63.40												
Low Head Performance Reduction (Calculated)													
Depth for Grate Midwidth	W _p = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>2.00</td><td>2.00</td></tr><tr><td></td><td></td></tr></table> feet					2.00	2.00						
2.00	2.00												
Depth for Curb Opening Weir Equation	C _r (C) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>0.10</td><td>0.10</td></tr><tr><td></td><td></td></tr></table> ft					0.10	0.10						
0.10	0.10												
Combination Inlet Performance Reduction Factor for Long Inlets	C _w (C) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>3.60</td><td>3.60</td></tr><tr><td></td><td></td></tr></table> ft					3.60	3.60						
3.60	3.60												
Curb Opening Performance Reduction Factor for Long Inlets	C _o (C) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>0.67</td><td>0.67</td></tr><tr><td></td><td></td></tr></table> ft					0.67	0.67						
0.67	0.67												
Total Inlet Interception Capacity (assumes clogged condition)													
Inlet Capacity IS GOOD for Minor and Major Storms(>Q PEAK)	Q _a = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>8.3</td><td>9.4</td></tr><tr><td></td><td></td></tr></table> cfs					8.3	9.4						
8.3	9.4												
	Q _{PEAK REQUIRED} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>2.1</td><td>6.4</td></tr><tr><td></td><td></td></tr></table> cfs					2.1	6.4						
2.1	6.4												

ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)


(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project:

FALCON MARKETPLACE

Inlet ID:

IB9

**Gutter Geometry (Enter data in the blue cells)**

Maximum Allowable Width for Spread Behind Curb

 $T_{BACK} = 7.0$ ft

Side Slope Behind Curb (leave blank for no conveyance credit behind curb)

 $S_{BACK} = 0.020$ ft/ft

Manning's Roughness Behind Curb (typically between 0.012 and 0.020)

 $n_{BACK} = 0.020$

Height of Curb at Gutter Flow Line

 $H_{CURB} = 6.00$ inches

Distance from Curb Face to Street Crown

 $T_{CROWN} = 20.0$ ft

Gutter Width

 $W = 2.00$ ft

Street Transverse Slope

 $S_x = 0.020$ ft/ft

Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)

 $S_w = 0.083$ ft/ft

Street Longitudinal Slope - Enter 0 for sump condition

 $S_o = 0.000$ ft/ft

Manning's Roughness for Street Section (typically between 0.012 and 0.020)

 $n_{STREET} = 0.013$

Max. Allowable Spread for Minor & Major Storm

	Minor Storm	Major Storm
T_{MAX}	20.0	20.0
d_{MAX}	6.0	7.5

Max. Allowable Depth at Gutter Flowline for Minor & Major Storm

inches

Allow Flow Depth at Street Crown (leave blank for no)



check = yes

MINOR STORM Allowable Capacity is based on Depth Criterion

Minor Storm

Major Storm

MAJOR STORM Allowable Capacity is based on Depth Criterion


SUMP

SUMP

cfs

INLET IN A SUMP OR SAG LOCATION

Version 4.04 Released November 2016



Design Information (Input)	CDOT Type R Curb Opening												
Type of Inlet													
Local Depression (additional to continuous gutter depression 'a' from 'Q-Allow')													
Number of Unit Inlets (Grate or Curb Opening)													
Water Depth at Flowline (outside of local depression)													
Grate Information													
Length of a Unit Grate	Type = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>CDOT Type R Curb Opening</td><td></td></tr><tr><td>3.00</td><td>3.00</td></tr><tr><td></td><td></td></tr></table> inches					MINOR	MAJOR	CDOT Type R Curb Opening		3.00	3.00		
MINOR	MAJOR												
CDOT Type R Curb Opening													
3.00	3.00												
Width of a Unit Grate	a _{local} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>1</td><td>1</td></tr><tr><td></td><td></td></tr></table> feet					1	1						
1	1												
Area Opening Ratio for a Grate (typical values 0.15-0.90)	No = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>6.0</td><td>6.3</td></tr><tr><td></td><td></td></tr></table> inches					6.0	6.3						
6.0	6.3												
Clogging Factor for a Single Grate (typical value 0.50 - 0.70)	Ponding Depth = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td></td><td></td></tr></table> feet					MINOR	MAJOR	N/A	N/A	N/A	N/A		
MINOR	MAJOR												
N/A	N/A												
N/A	N/A												
Grate Weir Coefficient (typical value 2.15 - 3.60)	L _o (G) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td></td><td></td></tr></table> feet					N/A	N/A						
N/A	N/A												
Grate Orifice Coefficient (typical value 0.60 - 0.80)	W _o = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td></td><td></td></tr></table> feet					N/A	N/A						
N/A	N/A												
Curb Opening Information													
Length of a Unit Curb Opening	A _{ratio} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td></td><td></td></tr></table> feet					N/A	N/A						
N/A	N/A												
Height of Vertical Curb Opening in Inches	C _r (G) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td></td><td></td></tr></table> degrees					N/A	N/A						
N/A	N/A												
Height of Curb Orifice Throat in Inches	C _w (G) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td></td><td></td></tr></table> feet					N/A	N/A						
N/A	N/A												
Angle of Throat (see USDCM Figure ST-5)	C _o (G) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td></td><td></td></tr></table> feet					N/A	N/A						
N/A	N/A												
Side Width for Depression Pan (typically the gutter width of 2 feet)	L _o (C) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>10.00</td><td>10.00</td></tr><tr><td></td><td></td></tr></table> feet					10.00	10.00						
10.00	10.00												
Clogging Factor for a Single Curb Opening (typical value 0.10)	H _{vert} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>6.00</td><td>6.00</td></tr><tr><td></td><td></td></tr></table> inches					6.00	6.00						
6.00	6.00												
Curb Opening Weir Coefficient (typical value 2.3-3.7)	H _{throat} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>6.00</td><td>6.00</td></tr><tr><td></td><td></td></tr></table> inches					6.00	6.00						
6.00	6.00												
Curb Opening Orifice Coefficient (typical value 0.60 - 0.70)	Theta = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>63.40</td><td>63.40</td></tr><tr><td></td><td></td></tr></table> degrees					63.40	63.40						
63.40	63.40												
Low Head Performance Reduction (Calculated)													
Depth for Grate Midwidth	W _p = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>2.00</td><td>2.00</td></tr><tr><td></td><td></td></tr></table> feet					2.00	2.00						
2.00	2.00												
Depth for Curb Opening Weir Equation	C _r (C) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>0.10</td><td>0.10</td></tr><tr><td></td><td></td></tr></table> ft					0.10	0.10						
0.10	0.10												
Combination Inlet Performance Reduction Factor for Long Inlets	C _w (C) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>3.60</td><td>3.60</td></tr><tr><td></td><td></td></tr></table> ft					3.60	3.60						
3.60	3.60												
Curb Opening Performance Reduction Factor for Long Inlets	C _o (C) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>0.67</td><td>0.67</td></tr><tr><td></td><td></td></tr></table> ft					0.67	0.67						
0.67	0.67												
Total Inlet Interception Capacity (assumes clogged condition)													
Inlet Capacity IS GOOD for Minor and Major Storms(>Q PEAK)	Q _a = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>8.3</td><td>9.4</td></tr><tr><td></td><td></td></tr></table> cfs					8.3	9.4						
8.3	9.4												
	Q _{PEAK REQUIRED} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>1.5</td><td>2.6</td></tr><tr><td></td><td></td></tr></table> cfs					1.5	2.6						
1.5	2.6												

ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)


(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project:

FALCON MARKETPLACE

Inlet ID:

IB10

**Gutter Geometry (Enter data in the blue cells)**

Maximum Allowable Width for Spread Behind Curb

 $T_{BACK} = 10.0$ ft

Side Slope Behind Curb (leave blank for no conveyance credit behind curb)

 $S_{BACK} = 0.020$ ft/ft

Manning's Roughness Behind Curb (typically between 0.012 and 0.020)

 $n_{BACK} = 0.020$

Height of Curb at Gutter Flow Line

 $H_{CURB} = 6.00$ inches

Distance from Curb Face to Street Crown

 $T_{CROWN} = 24.0$ ft

Gutter Width

 $W = 2.00$ ft

Street Transverse Slope

 $S_x = 0.020$ ft/ft

Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)

 $S_w = 0.083$ ft/ft

Street Longitudinal Slope - Enter 0 for sump condition

 $S_o = 0.010$ ft/ft

Manning's Roughness for Street Section (typically between 0.012 and 0.020)

 $n_{STREET} = 0.013$

Max. Allowable Spread for Minor & Major Storm

Minor Storm Major Storm

 $T_{MAX} = 24.0 \quad 24.0$ ft

Max. Allowable Depth at Gutter Flowline for Minor & Major Storm

 $d_{MAX} = 6.0 \quad 8.0$ inches

Allow Flow Depth at Street Crown (leave blank for no)

 check = yes

MINOR STORM Allowable Capacity is based on Depth Criterion

Minor Storm Major Storm

 $Q_{allow} = 17.0 \quad 32.3$ cfs


MAJOR STORM Allowable Capacity is based on Spread Criterion

Minor storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'

Major storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'

INLET ON A CONTINUOUS GRADE

Version 4.04 Released November 2016



Design Information (Input)		CDOT Type R Curb Opening	
Type of Inlet	CDOT Type R Curb Opening		
Local Depression (additional to continuous gutter depression 'a')			
Total Number of Units in the Inlet (Grate or Curb Opening)			
Length of a Single Unit Inlet (Grate or Curb Opening)			
Width of a Unit Grate (cannot be greater than W, Gutter Width)			
Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.5)			
Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.1)			
Street Hydraulics: OK - Q < Allowable Street Capacity'			
Total Inlet Interception Capacity	MINOR MAJOR		
Total Inlet Carry-Over Flow (flow bypassing inlet)	Q = 4.1	Q = 6.2	cfs cfs
Capture Percentage = $Q_c/Q_o =$	Q _b = 0.2	Q _b = 2.3	cfs cfs
	C% = 95	C% = 73	% %

ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)


(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project:

FALCON MARKETPLACE

Inlet ID:

IA1

**Gutter Geometry (Enter data in the blue cells)**

Maximum Allowable Width for Spread Behind Curb

 $T_{BACK} = 10.0$ ft

Side Slope Behind Curb (leave blank for no conveyance credit behind curb)

 $S_{BACK} = 0.020$ ft/ft

Manning's Roughness Behind Curb (typically between 0.012 and 0.020)

 $n_{BACK} = 0.020$

Height of Curb at Gutter Flow Line

 $H_{CURB} = 6.00$ inches

Distance from Curb Face to Street Crown

 $T_{CROWN} = 24.0$ ft

Gutter Width

 $W = 2.00$ ft

Street Transverse Slope

 $S_x = 0.020$ ft/ft

Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)

 $S_w = 0.083$ ft/ft

Street Longitudinal Slope - Enter 0 for sump condition

 $S_o = 0.010$ ft/ft

Manning's Roughness for Street Section (typically between 0.012 and 0.020)

 $n_{STREET} = 0.013$

Max. Allowable Spread for Minor & Major Storm

Minor Storm	Major Storm
$T_{MAX} = 24.0$	24.0
$d_{MAX} = 6.0$	8.0

Max. Allowable Depth at Gutter Flowline for Minor & Major Storm

inches

Allow Flow Depth at Street Crown (leave blank for no)

 check = yes

MINOR STORM Allowable Capacity is based on Depth Criterion

Minor Storm	Major Storm
17.0	32.3


MAJOR STORM Allowable Capacity is based on Spread Criterion

Minor storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'

Major storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'

INLET ON A CONTINUOUS GRADE

Version 4.04 Released November 2016



Design Information (Input)		CDOT Type R Curb Opening	
Type of Inlet	CDOT Type R Curb Opening		
Local Depression (additional to continuous gutter depression 'a')			
Total Number of Units in the Inlet (Grate or Curb Opening)			
Length of a Single Unit Inlet (Grate or Curb Opening)			
Width of a Unit Grate (cannot be greater than W, Gutter Width)			
Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.5)			
Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.1)			
Street Hydraulics: OK - Q < Allowable Street Capacity'			
Total Inlet Interception Capacity	MINOR MAJOR		
Total Inlet Carry-Over Flow (flow bypassing inlet)	Q = 2.4	4.7	cfs
Capture Percentage = $Q_a/Q_o =$	Q _a = 0.0	0.6	cfs
	C% = 100	89	%

ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)


(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project:

FALCON MARKETPLACE

Inlet ID:

IA2

**Gutter Geometry (Enter data in the blue cells)**

Maximum Allowable Width for Spread Behind Curb

 $T_{BACK} = 5.0$ ft

Side Slope Behind Curb (leave blank for no conveyance credit behind curb)

 $S_{BACK} = 0.020$ ft/ft

Manning's Roughness Behind Curb (typically between 0.012 and 0.020)

 $n_{BACK} = 0.020$

Height of Curb at Gutter Flow Line

 $H_{CURB} = 6.00$ inches

Distance from Curb Face to Street Crown

 $T_{CROWN} = 28.0$ ft

Gutter Width

 $W = 2.00$ ft

Street Transverse Slope

 $S_x = 0.020$ ft/ft

Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)

 $S_w = 0.083$ ft/ft

Street Longitudinal Slope - Enter 0 for sump condition

 $S_o = 0.000$ ft/ft

Manning's Roughness for Street Section (typically between 0.012 and 0.020)

 $n_{STREET} = 0.013$

Max. Allowable Spread for Minor & Major Storm

	Minor Storm	Major Storm
T_{MAX}	28.0	28.0
d_{MAX}	6.0	7.5

Max. Allowable Depth at Gutter Flowline for Minor & Major Storm

inches

Allow Flow Depth at Street Crown (leave blank for no)



check = yes

MINOR STORM Allowable Capacity is based on Depth Criterion

Minor Storm

Major Storm


MAJOR STORM Allowable Capacity is based on Depth Criterion

 $Q_{allow} = \boxed{\text{SUMP}}$ $\boxed{\text{SUMP}}$

cfs

INLET IN A SUMP OR SAG LOCATION

Version 4.04 Released November 2016



Design Information (Input)	CDOT Type R Curb Opening												
Type of Inlet													
Local Depression (additional to continuous gutter depression 'a' from 'Q-Allow')													
Number of Unit Inlets (Grate or Curb Opening)													
Water Depth at Flowline (outside of local depression)													
Grate Information													
Length of a Unit Grate	Type = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>CDOT Type R Curb Opening</td><td></td></tr><tr><td>3.00</td><td>3.00</td></tr><tr><td></td><td></td></tr></table> inches					MINOR	MAJOR	CDOT Type R Curb Opening		3.00	3.00		
MINOR	MAJOR												
CDOT Type R Curb Opening													
3.00	3.00												
Width of a Unit Grate	a _{local} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>1</td><td>1</td></tr><tr><td></td><td></td></tr></table> feet					1	1						
1	1												
Area Opening Ratio for a Grate (typical values 0.15-0.90)	No = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>6.0</td><td>7.5</td></tr><tr><td></td><td></td></tr></table> inches					6.0	7.5						
6.0	7.5												
Clogging Factor for a Single Grate (typical value 0.50 - 0.70)	Ponding Depth = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td></td><td></td></tr></table> feet					MINOR	MAJOR	N/A	N/A	N/A	N/A		
MINOR	MAJOR												
N/A	N/A												
N/A	N/A												
Grate Weir Coefficient (typical value 2.15 - 3.60)	L _o (G) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td></td><td></td></tr></table> feet					MINOR	MAJOR	N/A	N/A	N/A	N/A		
MINOR	MAJOR												
N/A	N/A												
N/A	N/A												
Grate Orifice Coefficient (typical value 0.60 - 0.80)	W _o = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td></td><td></td></tr></table> feet					MINOR	MAJOR	N/A	N/A	N/A	N/A		
MINOR	MAJOR												
N/A	N/A												
N/A	N/A												
Curb Opening Information													
Length of a Unit Curb Opening	A _{ratio} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td></td><td></td></tr></table> feet					MINOR	MAJOR	N/A	N/A	N/A	N/A		
MINOR	MAJOR												
N/A	N/A												
N/A	N/A												
Height of Vertical Curb Opening in Inches	C _r (G) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td></td><td></td></tr></table> inches					MINOR	MAJOR	N/A	N/A	N/A	N/A		
MINOR	MAJOR												
N/A	N/A												
N/A	N/A												
Height of Curb Orifice Throat in Inches	C _w (G) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td></td><td></td></tr></table> inches					MINOR	MAJOR	N/A	N/A	N/A	N/A		
MINOR	MAJOR												
N/A	N/A												
N/A	N/A												
Angle of Throat (see USDCM Figure ST-5)	C _o (G) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td></td><td></td></tr></table> degrees					MINOR	MAJOR	N/A	N/A	N/A	N/A		
MINOR	MAJOR												
N/A	N/A												
N/A	N/A												
Side Width for Depression Pan (typically the gutter width of 2 feet)	L _o (C) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>10.00</td><td>10.00</td></tr><tr><td>6.00</td><td>6.00</td></tr><tr><td></td><td></td></tr></table> feet					MINOR	MAJOR	10.00	10.00	6.00	6.00		
MINOR	MAJOR												
10.00	10.00												
6.00	6.00												
Clogging Factor for a Single Curb Opening (typical value 0.10)	H _{vert} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>6.00</td><td>6.00</td></tr><tr><td>6.00</td><td>6.00</td></tr><tr><td></td><td></td></tr></table> inches					MINOR	MAJOR	6.00	6.00	6.00	6.00		
MINOR	MAJOR												
6.00	6.00												
6.00	6.00												
Curb Opening Weir Coefficient (typical value 2.3-3.7)	H _{throat} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>63.40</td><td>63.40</td></tr><tr><td>63.40</td><td>63.40</td></tr><tr><td></td><td></td></tr></table> degrees					MINOR	MAJOR	63.40	63.40	63.40	63.40		
MINOR	MAJOR												
63.40	63.40												
63.40	63.40												
Curb Opening Orifice Coefficient (typical value 0.60 - 0.70)	Theta = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>2.00</td><td>2.00</td></tr><tr><td>2.00</td><td>2.00</td></tr><tr><td></td><td></td></tr></table> feet					MINOR	MAJOR	2.00	2.00	2.00	2.00		
MINOR	MAJOR												
2.00	2.00												
2.00	2.00												
Low Head Performance Reduction (Calculated)													
Depth for Grate Midwidth	W _p = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>0.10</td><td>0.10</td></tr><tr><td>3.60</td><td>3.60</td></tr><tr><td></td><td></td></tr></table> feet					MINOR	MAJOR	0.10	0.10	3.60	3.60		
MINOR	MAJOR												
0.10	0.10												
3.60	3.60												
Depth for Curb Opening Weir Equation	C _r (C) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>0.10</td><td>0.10</td></tr><tr><td>0.57</td><td>0.71</td></tr><tr><td></td><td></td></tr></table> ft					MINOR	MAJOR	0.10	0.10	0.57	0.71		
MINOR	MAJOR												
0.10	0.10												
0.57	0.71												
Combination Inlet Performance Reduction Factor for Long Inlets	RF _{Combination} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>0.93</td><td>1.00</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td></td><td></td></tr></table> ft					MINOR	MAJOR	0.93	1.00	N/A	N/A		
MINOR	MAJOR												
0.93	1.00												
N/A	N/A												
Curb Opening Performance Reduction Factor for Long Inlets	RF _{Curb} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>0.93</td><td>1.00</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td></td><td></td></tr></table> ft					MINOR	MAJOR	0.93	1.00	N/A	N/A		
MINOR	MAJOR												
0.93	1.00												
N/A	N/A												
Grated Inlet Performance Reduction Factor for Long Inlets	RF _{Grate} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td></td><td></td></tr></table> ft					MINOR	MAJOR	N/A	N/A	N/A	N/A		
MINOR	MAJOR												
N/A	N/A												
N/A	N/A												
Total Inlet Interception Capacity (assumes clogged condition)													
Inlet Capacity IS GOOD for Minor and Major Storms(>Q PEAK)	Q _a = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>8.3</td><td>14.3</td></tr><tr><td>2.0</td><td>4.6</td></tr><tr><td></td><td></td></tr></table> cfs					MINOR	MAJOR	8.3	14.3	2.0	4.6		
MINOR	MAJOR												
8.3	14.3												
2.0	4.6												
	Q _{PEAK REQUIRED} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td></td><td></td></tr><tr><td></td><td></td></tr><tr><td></td><td></td></tr></table> cfs					MINOR	MAJOR						
MINOR	MAJOR												

ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)


(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project:

FALCON MARKETPLACE

Inlet ID:

IC1

**Gutter Geometry (Enter data in the blue cells)**

Maximum Allowable Width for Spread Behind Curb

T_{BACK} = 10.0 ft

Side Slope Behind Curb (leave blank for no conveyance credit behind curb)

S_{BACK} = 0.200 ft/ft

Manning's Roughness Behind Curb (typically between 0.012 and 0.020)

n_{BACK} = 0.020

Height of Curb at Gutter Flow Line

H_{CURB} = 6.00 inches

Distance from Curb Face to Street Crown

T_{CROWN} = 20.0 ft

Gutter Width

W = 2.00 ft

Street Transverse Slope

S_x = 0.020 ft/ft

Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)

S_w = 0.083 ft/ft

Street Longitudinal Slope - Enter 0 for sump condition

S_o = 0.000 ft/ft

Manning's Roughness for Street Section (typically between 0.012 and 0.020)

n_{STREET} = 0.013

Max. Allowable Spread for Minor & Major Storm

	Minor Storm	Major Storm
T _{MAX} =	20.0	20.0
d _{MAX} =	6.0	8.0

Max. Allowable Depth at Gutter Flowline for Minor & Major Storm

inches

Allow Flow Depth at Street Crown (leave blank for no)



check = yes

MINOR STORM Allowable Capacity is based on Depth Criterion

Minor Storm


Major Storm

MAJOR STORM Allowable Capacity is based on Depth Criterion

Q_{allow} = SUMP SUMP cfs

INLET IN A SUMP OR SAG LOCATION

Version 4.04 Released November 2016



Design Information (Input)	CDOT Type R Curb Opening		
Type of Inlet			
Local Depression (additional to continuous gutter depression 'a' from 'Q-Allow')			
Number of Unit Inlets (Grate or Curb Opening)			
Water Depth at Flowline (outside of local depression)			
Grate Information			
Length of a Unit Grate	MINOR	MAJOR	<input checked="" type="checkbox"/> Override Depths
Width of a Unit Grate	3.00	3.00	
Area Opening Ratio for a Grate (typical values 0.15-0.90)	inches	inches	
Clogging Factor for a Single Grate (typical value 0.50 - 0.70)	1	1	
Grate Weir Coefficient (typical value 2.15 - 3.60)	6.0	7.5	
Grate Orifice Coefficient (typical value 0.60 - 0.80)	feet	feet	
Curb Opening Information			
Length of a Unit Curb Opening	N/A	N/A	<input checked="" type="checkbox"/> Override Depths
Height of Vertical Curb Opening in Inches	N/A	N/A	
Height of Curb Orifice Throat in Inches	N/A	N/A	
Angle of Throat (see USDCM Figure ST-5)	N/A	N/A	
Side Width for Depression Pan (typically the gutter width of 2 feet)	N/A	N/A	
Clogging Factor for a Single Curb Opening (typical value 0.10)	N/A	N/A	
Curb Opening Weir Coefficient (typical value 2.3-3.7)	15.00	15.00	<input checked="" type="checkbox"/> Override Depths
Curb Opening Orifice Coefficient (typical value 0.60 - 0.70)	6.00	6.00	
Depth for Grade Midwidth	6.00	6.00	
Depth for Curb Opening Weir Equation	6.00	6.00	
Combination Inlet Performance Reduction Factor for Long Inlets	63.40	63.40	
Curb Opening Performance Reduction Factor for Long Inlets	degrees	degrees	
Grated Inlet Performance Reduction Factor for Long Inlets	0.10	0.10	<input checked="" type="checkbox"/> Override Depths
Total Inlet Interception Capacity (assumes clogged condition)	MINOR	MAJOR	
WARNING: Inlet Capacity less than Q Peak for Major Storm	9.7	17.3	
	cfs	cfs	
	9.3	20.6	
	cfs	cfs	

ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)


(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project:

FALCON MARKETPLACE

Inlet ID:

IC2

**Gutter Geometry (Enter data in the blue cells)**

Maximum Allowable Width for Spread Behind Curb

 $T_{BACK} = 7.0$ ft

Side Slope Behind Curb (leave blank for no conveyance credit behind curb)

 $S_{BACK} = 0.020$ ft/ft

Manning's Roughness Behind Curb (typically between 0.012 and 0.020)

 $n_{BACK} = 0.020$

Height of Curb at Gutter Flow Line

 $H_{CURB} = 6.00$ inches

Distance from Curb Face to Street Crown

 $T_{CROWN} = 20.0$ ft

Gutter Width

 $W = 2.00$ ft

Street Transverse Slope

 $S_x = 0.020$ ft/ft

Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)

 $S_w = 0.083$ ft/ft

Street Longitudinal Slope - Enter 0 for sump condition

 $S_o = 0.000$ ft/ft

Manning's Roughness for Street Section (typically between 0.012 and 0.020)

 $n_{STREET} = 0.013$

Max. Allowable Spread for Minor & Major Storm

	Minor Storm	Major Storm
T_{MAX}	20.0	20.0
d_{MAX}	6.0	7.5

Max. Allowable Depth at Gutter Flowline for Minor & Major Storm

inches

Allow Flow Depth at Street Crown (leave blank for no)



check = yes

MINOR STORM Allowable Capacity is based on Depth Criterion

Minor Storm

Major Storm

MAJOR STORM Allowable Capacity is based on Depth Criterion


SUMP

SUMP

cfs

INLET IN A SUMP OR SAG LOCATION

Version 4.04 Released November 2016



Design Information (Input)	CDOT Type R Curb Opening												
Type of Inlet													
Local Depression (additional to continuous gutter depression 'a' from 'Q-Allow')													
Number of Unit Inlets (Grate or Curb Opening)													
Water Depth at Flowline (outside of local depression)													
Grate Information													
Length of a Unit Grate	Type = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>CDOT Type R Curb Opening</td><td></td></tr><tr><td>3.00</td><td>3.00</td></tr><tr><td>inches</td><td></td></tr></table>					MINOR	MAJOR	CDOT Type R Curb Opening		3.00	3.00	inches	
MINOR	MAJOR												
CDOT Type R Curb Opening													
3.00	3.00												
inches													
Width of a Unit Grate	a _{local} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>1</td><td>1</td></tr><tr><td>feet</td><td></td></tr></table>					1	1	feet					
1	1												
feet													
Area Opening Ratio for a Grate (typical values 0.15-0.90)	No = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>1</td><td>1</td></tr><tr><td>feet</td><td></td></tr></table>					1	1	feet					
1	1												
feet													
Clogging Factor for a Single Grate (typical value 0.50 - 0.70)	Ponding Depth = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>6.0</td><td>6.3</td></tr><tr><td>inches</td><td></td></tr></table>					6.0	6.3	inches					
6.0	6.3												
inches													
Grate Weir Coefficient (typical value 2.15 - 3.60)													
Grate Orifice Coefficient (typical value 0.60 - 0.80)													
Curb Opening Information													
Length of a Unit Curb Opening	L _o (G) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td>feet</td><td></td></tr></table>					N/A	N/A	feet					
N/A	N/A												
feet													
Height of Vertical Curb Opening in Inches	W _o = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td>feet</td><td></td></tr></table>					N/A	N/A	feet					
N/A	N/A												
feet													
Height of Curb Orifice Throat in Inches	A _{ratio} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td>feet</td><td></td></tr></table>					N/A	N/A	feet					
N/A	N/A												
feet													
Angle of Throat (see USDCM Figure ST-5)	C _r (G) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td>degrees</td><td></td></tr></table>					N/A	N/A	degrees					
N/A	N/A												
degrees													
Side Width for Depression Pan (typically the gutter width of 2 feet)	C _w (G) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td>feet</td><td></td></tr></table>					N/A	N/A	feet					
N/A	N/A												
feet													
Clogging Factor for a Single Curb Opening (typical value 0.10)	C _o (G) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td>feet</td><td></td></tr></table>					N/A	N/A	feet					
N/A	N/A												
feet													
Curb Opening Weir Coefficient (typical value 2.3-3.7)													
Curb Opening Orifice Coefficient (typical value 0.60 - 0.70)													
Low Head Performance Reduction (Calculated)													
Depth for Grate Midwidth	L _o (C) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>10.00</td><td>10.00</td></tr><tr><td>feet</td><td></td></tr></table>					10.00	10.00	feet					
10.00	10.00												
feet													
Depth for Curb Opening Weir Equation	H _{vert} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>6.00</td><td>6.00</td></tr><tr><td>inches</td><td></td></tr></table>					6.00	6.00	inches					
6.00	6.00												
inches													
Combination Inlet Performance Reduction Factor for Long Inlets	H _{throat} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>6.00</td><td>6.00</td></tr><tr><td>inches</td><td></td></tr></table>					6.00	6.00	inches					
6.00	6.00												
inches													
Curb Opening Performance Reduction Factor for Long Inlets	Theta = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>63.40</td><td>63.40</td></tr><tr><td>degrees</td><td></td></tr></table>					63.40	63.40	degrees					
63.40	63.40												
degrees													
Grated Inlet Performance Reduction Factor for Long Inlets	W _p = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>2.00</td><td>2.00</td></tr><tr><td>feet</td><td></td></tr></table>					2.00	2.00	feet					
2.00	2.00												
feet													
Total Inlet Interception Capacity (assumes clogged condition)													
Inlet Capacity IS GOOD for Minor and Major Storms(>Q PEAK)	d _{Grate} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td>ft</td><td></td></tr></table>					N/A	N/A	ft					
N/A	N/A												
ft													
	d _{Curb} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>0.33</td><td>0.36</td></tr><tr><td>ft</td><td></td></tr></table>					0.33	0.36	ft					
0.33	0.36												
ft													
	RF _{Combination} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>0.57</td><td>0.60</td></tr><tr><td></td><td></td></tr></table>					0.57	0.60						
0.57	0.60												
	RF _{Curb} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>0.93</td><td>0.95</td></tr><tr><td></td><td></td></tr></table>					0.93	0.95						
0.93	0.95												
	RF _{Grate} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td></td><td></td></tr></table>					N/A	N/A						
N/A	N/A												
	MINOR MAJOR												
	Q _a = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>8.3</td><td>9.4</td></tr><tr><td>cfs</td><td></td></tr></table>					8.3	9.4	cfs					
8.3	9.4												
cfs													
	Q _{PEAK REQUIRED} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>0.4</td><td>5.7</td></tr><tr><td>cfs</td><td></td></tr></table>					0.4	5.7	cfs					
0.4	5.7												
cfs													

ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)


(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project:

FALCON MARKETPLACE

Inlet ID:

IC3

**Gutter Geometry (Enter data in the blue cells)**

Maximum Allowable Width for Spread Behind Curb

 $T_{BACK} = 7.0$ ft

Side Slope Behind Curb (leave blank for no conveyance credit behind curb)

 $S_{BACK} = 0.020$ ft/ft

Manning's Roughness Behind Curb (typically between 0.012 and 0.020)

 $n_{BACK} = 0.020$

Height of Curb at Gutter Flow Line

 $H_{CURB} = 6.00$ inches

Distance from Curb Face to Street Crown

 $T_{CROWN} = 20.0$ ft

Gutter Width

 $W = 2.00$ ft

Street Transverse Slope

 $S_x = 0.020$ ft/ft

Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)

 $S_w = 0.083$ ft/ft

Street Longitudinal Slope - Enter 0 for sump condition

 $S_o = 0.000$ ft/ft

Manning's Roughness for Street Section (typically between 0.012 and 0.020)

 $n_{STREET} = 0.013$

Max. Allowable Spread for Minor & Major Storm

Minor Storm	Major Storm
$T_{MAX} = 20.0$	20.0 ft

Max. Allowable Depth at Gutter Flowline for Minor & Major Storm

$d_{MAX} = 6.0$	7.5 inches
-----------------	--------------

Allow Flow Depth at Street Crown (leave blank for no)

 check = yes

MINOR STORM Allowable Capacity is based on Depth Criterion

Minor Storm


MAJOR STORM Allowable Capacity is based on Depth Criterion

Major Storm

 $Q_{allow} = \boxed{\text{SUMP}}$ $\boxed{\text{SUMP}}$ cfs

INLET IN A SUMP OR SAG LOCATION

Version 4.04 Released November 2016




Design Information (Input)	CDOT Type R Curb Opening												
Type of Inlet													
Local Depression (additional to continuous gutter depression 'a' from 'Q-Allow')													
Number of Unit Inlets (Grate or Curb Opening)													
Water Depth at Flowline (outside of local depression)													
Grate Information													
Length of a Unit Grate	Type = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>CDOT Type R Curb Opening</td><td></td></tr><tr><td>3.00</td><td>3.00</td></tr><tr><td>inches</td><td></td></tr></table>					MINOR	MAJOR	CDOT Type R Curb Opening		3.00	3.00	inches	
MINOR	MAJOR												
CDOT Type R Curb Opening													
3.00	3.00												
inches													
Width of a Unit Grate	a _{local} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>1</td><td>1</td></tr><tr><td>feet</td><td></td></tr></table>					1	1	feet					
1	1												
feet													
Area Opening Ratio for a Grate (typical values 0.15-0.90)	No = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>6.0</td><td>6.3</td></tr><tr><td>inches</td><td></td></tr></table>					6.0	6.3	inches					
6.0	6.3												
inches													
Clogging Factor for a Single Grate (typical value 0.50 - 0.70)	Ponding Depth = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>MINOR</td><td>MAJOR</td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td>feet</td><td></td></tr></table>					MINOR	MAJOR	N/A	N/A	feet			
MINOR	MAJOR												
N/A	N/A												
feet													
Grate Weir Coefficient (typical value 2.15 - 3.60)	L _o (G) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td>feet</td><td></td></tr></table>					N/A	N/A	feet					
N/A	N/A												
feet													
Grate Orifice Coefficient (typical value 0.60 - 0.80)	W _o = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td>feet</td><td></td></tr></table>					N/A	N/A	feet					
N/A	N/A												
feet													
Curb Opening Information													
Length of a Unit Curb Opening	A _{ratio} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td>feet</td><td></td></tr></table>					N/A	N/A	feet					
N/A	N/A												
feet													
Height of Vertical Curb Opening in Inches	C _r (G) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td>inches</td><td></td></tr></table>					N/A	N/A	inches					
N/A	N/A												
inches													
Height of Curb Orifice Throat in Inches	C _w (G) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td>inches</td><td></td></tr></table>					N/A	N/A	inches					
N/A	N/A												
inches													
Angle of Throat (see USDCM Figure ST-5)	C _o (G) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>N/A</td><td>N/A</td></tr><tr><td>degrees</td><td></td></tr></table>					N/A	N/A	degrees					
N/A	N/A												
degrees													
Side Width for Depression Pan (typically the gutter width of 2 feet)	L _o (C) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>10.00</td><td>10.00</td></tr><tr><td>feet</td><td></td></tr></table>					10.00	10.00	feet					
10.00	10.00												
feet													
Clogging Factor for a Single Curb Opening (typical value 0.10)	H _{vert} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>6.00</td><td>6.00</td></tr><tr><td>inches</td><td></td></tr></table>					6.00	6.00	inches					
6.00	6.00												
inches													
Curb Opening Weir Coefficient (typical value 2.3-3.7)	H _{throat} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>6.00</td><td>6.00</td></tr><tr><td>inches</td><td></td></tr></table>					6.00	6.00	inches					
6.00	6.00												
inches													
Curb Opening Orifice Coefficient (typical value 0.60 - 0.70)	Theta = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>63.40</td><td>63.40</td></tr><tr><td>degrees</td><td></td></tr></table>					63.40	63.40	degrees					
63.40	63.40												
degrees													
Low Head Performance Reduction (Calculated)													
Depth for Grate Midwidth	W _p = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>2.00</td><td>2.00</td></tr><tr><td>feet</td><td></td></tr></table>					2.00	2.00	feet					
2.00	2.00												
feet													
Depth for Curb Opening Weir Equation	C _r (C) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>0.10</td><td>0.10</td></tr><tr><td>ft</td><td></td></tr></table>					0.10	0.10	ft					
0.10	0.10												
ft													
Combination Inlet Performance Reduction Factor for Long Inlets	C _w (C) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>3.60</td><td>3.60</td></tr><tr><td>ft</td><td></td></tr></table>					3.60	3.60	ft					
3.60	3.60												
ft													
Curb Opening Performance Reduction Factor for Long Inlets	C _o (C) = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>0.67</td><td>0.67</td></tr><tr><td>ft</td><td></td></tr></table>					0.67	0.67	ft					
0.67	0.67												
ft													
Total Inlet Interception Capacity (assumes clogged condition)													
Inlet Capacity IS GOOD for Minor and Major Storms(>Q PEAK)	Q _a = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>8.3</td><td>9.4</td></tr><tr><td>cfs</td><td></td></tr></table>					8.3	9.4	cfs					
8.3	9.4												
cfs													
	Q _{PEAK REQUIRED} = <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 50px; height: 20px;"></td><td style="width: 50px; height: 20px;"></td></tr><tr><td>2.1</td><td>3.7</td></tr><tr><td>cfs</td><td></td></tr></table>					2.1	3.7	cfs					
2.1	3.7												
cfs													

DETENTION VOLUME BY THE FULL SPECTRUM METHOD

Project: _____
 Basin ID: _____

Area of Watershed (acres) <input type="text" value="740.00"/> Subwatershed Imperviousness <input type="text" value="15.0%"/> Level of Minimizing Directly Connected Impervious Area (MDCIA) <input type="text" value="0"/> Effective Imperviousness ¹ <input type="text" value="15.0%"/> Hydrologic Soil Type <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th></th><th>Percentage of Area</th><th>Area (acres)</th></tr> </thead> <tbody> <tr> <td>Type A</td><td>100.0%</td><td>740.0</td></tr> <tr> <td>Type B</td><td></td><td>0.0</td></tr> <tr> <td>Type C or D</td><td></td><td>0.0</td></tr> </tbody> </table>		Percentage of Area	Area (acres)	Type A	100.0%	740.0	Type B		0.0	Type C or D		0.0	<small>* User input data shown in blue.</small>					
	Percentage of Area	Area (acres)																
Type A	100.0%	740.0																
Type B		0.0																
Type C or D		0.0																
Excess Urban Runoff Volume ⁴	Recommended Horton's Equation Parameters for CUHP <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th colspan="2">Infiltration (inches per hour)</th> <th rowspan="2">Decay Coefficient--α</th> </tr> <tr> <th>Initial-f_i</th> <th>Final-f_o</th> </tr> </thead> <tbody> <tr> <td>5</td> <td>1.0</td> <td>0.0007</td> </tr> </tbody> </table> Detention Volumes^{2,5} <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>(watershed inches)</th> <th>(acre-feet)</th> <th rowspan="2">Maximum Allowable Release Rate, cfs³</th> </tr> </thead> <tbody> <tr> <td>0.22</td> <td>13.30</td> <td>Design Outlet to Empty EURV in 72 Hours</td> </tr> <tr> <td>0.32</td> <td>19.72</td> <td>370.00</td> </tr> </tbody> </table>	Infiltration (inches per hour)		Decay Coefficient-- α	Initial- f_i	Final- f_o	5	1.0	0.0007	(watershed inches)	(acre-feet)	Maximum Allowable Release Rate, cfs ³	0.22	13.30	Design Outlet to Empty EURV in 72 Hours	0.32	19.72	370.00
Infiltration (inches per hour)		Decay Coefficient-- α																
Initial- f_i	Final- f_o																	
5	1.0	0.0007																
(watershed inches)	(acre-feet)	Maximum Allowable Release Rate, cfs ³																
0.22	13.30		Design Outlet to Empty EURV in 72 Hours															
0.32	19.72	370.00																
100-year Detention Volume Including WQCV ⁵																		




Notes:

- 1) Effective imperviousness is based on Figure ND-1 of the Urban Storm Drainage Criteria Manual (USDCM).
- 2) Results shown reflect runoff reduction from Level 1 or 2 MDCIA and are plotted at the watershed's total imperviousness value; the impact of MDCIA is reflected by the results being below the curves.
- 3) Maximum allowable release rates for 100-year event are based on Table SO-1. Outlet for the Excess Urban Runoff Volume (EURV) to be designed to empty out the EURV in 72 hours. Outlet design is similar to one for the WQCV outlet of an extended detention basin (i.e., perforated plate with a micro-pool) and extends to top of EURV water surface elevation.
- 4) EURV approximates the difference between developed and pre-developed runoff volume.
- 5) 100-yr detention volume includes EURV. No need to add more volume for WQCV or EURV

STAGE-STORAGE SIZING FOR DETENTION BASINS

Project: **FALCON MARKETPLACE**
Basin ID: **NORTH POND #1**



Design Information (Input):

Width of Basin Bottom, W = ft
Length of Basin Bottom, L = ft
Dam Side-slope (H:V), Z_d = ft/ft

Check Basin Shape

<u>Check Basic Shape</u>	
Right Triangle	OR... <input type="checkbox"/>
Isosceles Triangle	OR... <input type="checkbox"/>
Rectangle	OR... <input type="checkbox"/>
Circle / Ellipse	OR... <input type="checkbox"/>
Irregular	(Use <input type="checkbox"/>

(See Section 7000 of Title 36, USC.)

Stage-Storage Relationship:


	MIRROR	MASK
Storage Requirement from Sheet 'Modified FAA':		
Storage Requirement from Sheet 'Hydrograph':		
Storage Requirement from Sheet 'Full-Spectrum':	13.30	19.72

STAGE-STORAGE SIZING FOR DETENTION BASINS

Project: _____

Basin ID: _____

STAGE-STORAGE CURVE FOR THE POND



STAGE-DISCHARGE SIZING OF THE WATER QUALITY CAPTURE VOLUME (WQCV) OUTLET

Project: FALCON MARKETPLACE

Basin ID: NORTH POND #1


WQCV Design Volume (Input):

Catchment Imperviousness, I_o = percent
 Catchment Area, A = acres
 Depth at WQCV outlet above lowest perforation, H = feet
 Vertical distance between rows, h = inches
 Number of rows, N_L =
 Orifice discharge coefficient, C_D =
 Slope of Basin Trickle Channel, S = ft / ft
 Time to Drain the Pond = hours

Diameter of holes, D = inches
 Number of holes per row, N =
 OR
 Height of slot, H = inches
 Width of slot, W = inches

Watershed Design Information (Input):

Percent Soil Type A = %
 Percent Soil Type B = %
 Percent Soil Type C/D = %



Outlet Design Information (Output):

Excess Urban Runoff Volume (From 'Full-Spectrum Sheet') = watershed inches
 N/A
 Excess Urban Runoff Volume (From 'Full-Spectrum Sheet') = acre-feet
 Outlet area per row, Ao = square inches
 Total opening area at each row based on user-input above, Ao = square inches
 Total opening area at each row based on user-input above, Ao = square feet

Row	Central Elevations of Rows of Holes in feet																							Σ Flow	
	Row 1	Row 2	Row 3	Row 4	Row 5	Row 6	Row 7	Row 8	Row 9	Row 10	Row 11	Row 12	Row 13	Row 14	Row 15	Row 16	Row 17	Row 18	Row 19	Row 20	Row 21	Row 22	Row 23		
6885.00	6887.50	6890.00																							
6882.00	0.0000	0.0000	0.0000																						0.00
6883.00	0.0000	0.0000	0.0000																						0.00
6884.00	0.0000	0.0000	0.0000																						0.00
6885.00	0.0000	0.0000	0.0000																						0.00
6886.00	0.5457	0.0000	0.0000																						0.55
6887.00	0.7717	0.0000	0.0000																						0.77
6888.00	0.9452	0.3859	0.0000																						1.33
6889.00	1.0914	0.6683	0.0000																						1.76
6890.00	1.2202	0.8628	0.0000																						2.08
6891.00	1.3367	1.0209	0.5457																						2.90
6892.00	1.4438	1.1576	0.7717																						3.37
6893.00	1.5435	1.2798	0.9452																						3.77
6894.00	1.6371	1.3913	1.0914																						4.12
6895.00	1.7256	1.4945	1.2202																						4.44
6896.00	1.8099	1.5910	1.3367																						4.74
6896.50	1.8505	1.6371	1.3913																						4.88
6897.00	1.8904	1.6820	1.4438																						5.02
6897.50	1.9293	1.7256	1.4945																						5.15
6898.00	1.9675	1.7683	1.5435																						5.28
6899.00	2.0418	1.8505	1.6371																						5.53
6900.00	2.1135	1.9293	1.7256																						5.77
6901.00	2.1828	2.0050	1.8099																						6.00
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A																						#N/A
	#N/A	#N/A	#N/A		</																				


STAGE-DISCHARGE SIZING OF THE WATER QUALITY CAPTURE VOLUME (WQCV) OUTLET

Worksheet Protected

Project: FALCON MARKETPLACE

Basin ID: NORTH POND #1

STAGE-DISCHARGE CURVE FOR THE WQCV OUTLET STRUCTURE




STAGE-DISCHARGE SIZING OF THE WATER QUALITY CAPTURE VOLUME (WQCV) OUTLET

Worksheet Protected

Project: FALCON MARKETPLACE

Basin ID: NORTH POND #1


STAGE-DISCHARGE CURVE FOR THE WQCV OUTLET STRUCTURE



STAGE-DISCHARGE SIZING OF THE WEIRS AND ORIFICES (INLET CONTROL)


Project: Falcon Marketplace #1
Basin ID: NORTH POND #1

STAGE-DISCHARGE CURVE FOR THE OUTLET STRUCTURE



STAGE-DISCHARGE SIZING OF THE OUTLET CULVERT (INLET vs. OUTLET CONTROL WITH TAILWATER EFFECTS)

Project: FALCON MARKETPLACE
Basin ID: NORTH POND #1



Status: Culvert Data is valid!

Design Information (Input):

Circular Culvert: Barrel Diameter in Inches
Circular Culvert: Inlet Edge Type (choose from pull-down list)

OR:

Box Culvert: Barrel Height (Rise) in Feet

Box Culvert: Barrel Width (Span) in Feet

Box Culvert: Inlet Edge Type (choose from pull-down list)

Number of Barrels
Inlet Elevation at C
Outlet Elevation at O
Culvert Length in F
Manning's Roughness
Bend Loss Coefficient
Exit Loss Coefficient

D = 96 in

Height (Rise) =	<input type="text"/>	ft
Width (Span) =	<input type="text"/>	ft
Square Edge w/ 90-15 deg. Flared Wingwall		

No =	1	
I_{elev}	6881.97	ft. ele.
O_{elev}	6880.85	ft. ele.
L	78.0	ft.
n	0.0120	
K_b	0.00	
K_x =	1.00	

Design Information (calculated):


Entrance Loss Coefficient	$K_{\text{e}} =$	0.20
Friction Loss Coefficient	$K_f =$	0.12
Sum of All Loss Coefficients	$K_s =$	1.35
Orifice Inlet Condition Coefficient	$C_d =$	0.95
Minimum Energy Condition Coefficient	$KE_{\text{low}} =$	-0.04

Calculations of Culvert Capacity (output):

STAGE-DISCHARGE SIZING OF THE OUTLET CULVERT (INLET vs. OUTLET CONTROL WITH TAILWATER EFFECTS)


Project: FALCON MARKETPLACE
Basin ID: NORTH POND #1

STAGE-DISCHARGE CURVE FOR THE FINAL OUTLET PIPE CULVERT



STAGE-DISCHARGE SIZING OF THE SPILLWAY

Project: FALCON MARKETPLACE
Basin ID: NORTH POND #1



Design Information (input):

Bottom Length of Weir	L =	160.00	feet
Angle of Side Slope Weir	Angle =	75.96	degrees
Elev. for Weir Crest	EL. Crest =	6,898.00	feet
Coef. for Rectangular Weir	C _w =		
Coef. for Trapezoidal Weir	C _t =	3.50	

Calculation of Spillway Capacity (output):

PROJECT INFORMATION

PROJECT: Falcon Marketplace
PROJECT NO: 20988-00CSCV
DESIGN BY: KGV
REV. BY: TDM
AGENCY: El Paso County
REPORT TYPE: Preliminary
DATE: 6/19/2017



Drexel, Barrell & Co.

SPILLWAY CALCULATIONS


$$Q=CL(H^{(2/3)})$$

Weir coefficient C: 3.5
Depth H, ft: 1.5
Flowrate Q. cfs: 1016

Required L, ft: **158.01**

STAGE-DISCHARGE SIZING OF THE SPILLWAY


Project: FALCON MARKETPLACE
Basin ID: NORTH POND #1



Aluminum Bar Grating


RECTANGULAR BAR SWAGE-LOCKED 1-3/16" C/C Bearing Bars

19-SR-4



Cross Rods 4" C/C

19-SR-2




Cross Rods 2" C/C

NON-SERRATED & SERRATED

TRASH RACK GRATE AT FRONT OF BOX

PRESS-LOCKED 1-3/16" C/C Bearing Bars

19-AP-4



Cross Bars 4" C/C

19-AP-2



Cross Bars 2" C/C

LOAD & DEFLECTION TABLE

Bar Size	Symbol	Approx. Weight psf	Sec. Mod. Per Ft. of Width	SPAN (Direction of Bearing Bar)				
				24"	30"	36"	42"	48"
3/4" x 1/8"	19-SR-4	1.4	0.118	U	237	152	105	77
	19-SR-2	1.6		D	0.192	0.300	0.432	0.588
	19-AP-4	1.5		C	237	189	158	135
	19-AP-2	1.8		D	0.154	0.240	0.346	0.470
	19-SR-4	1.9		U	355	227	158	116
	19-SR-2	2.1		D	0.192	0.300	0.432	0.588
3/4" x 3/16"	19-AP-4	2.2	0.178	C	355	284	237	203
	19-AP-2	2.7		D	0.154	0.240	0.346	0.470
	19-SR-4	1.7		U	421	269	187	137
	19-SR-2	1.9		D	0.144	0.225	0.324	0.441
	19-AP-4	1.8		C	421	337	281	241
	19-AP-2	2.2		D	0.115	0.180	0.259	0.353
1" x 1/8"	19-SR-4	2.5	0.211	U	632	404	281	206
	19-SR-2	2.7		D	0.144	0.225	0.324	0.441
	19-AP-4	2.8		C	632	505	421	361
	19-AP-2	3.3		D	0.115	0.180	0.259	0.353
	19-SR-4	2.1		U	658	421	292	215
	19-SR-2	2.3		D	0.115	0.180	0.259	0.353
1" x 3/16"	19-AP-4	2.4	0.316	C	658	526	439	376
	19-AP-2	2.7		D	0.115	0.180	0.259	0.353
	19-SR-4	2.5		U	632	404	281	206
	19-SR-2	2.7		D	0.144	0.225	0.324	0.441
	19-AP-4	2.8		C	632	505	421	361
	19-AP-2	3.3		D	0.115	0.180	0.259	0.353
1-1/4" x 1/8"	19-SR-4	2.1	0.329	U	658	421	292	215
	19-SR-2	2.3		D	0.115	0.180	0.259	0.353
	19-AP-4	2.4		C	658	526	439	376
	19-AP-2	2.8		D	0.092	0.144	0.207	0.282
	19-SR-4	3.1		U	987	632	439	322
	19-SR-2	3.3		D	0.115	0.180	0.259	0.353
1-1/4" x 3/16"	19-AP-4	3.5	0.493	C	987	789	658	564
	19-AP-2	4.2		D	0.092	0.144	0.207	0.282
	19-SR-4	2.5		U	947	606	421	309
	19-SR-2	2.7		D	0.096	0.150	0.216	0.294
	19-AP-4	2.8		C	947	758	632	541
	19-AP-2	3.2		D	0.077	0.120	0.173	0.235
1-1/2" x 1/8"	19-SR-4	3.7	0.474	U	1421	909	632	464
	19-SR-2	3.9		D	0.096	0.150	0.216	0.294
	19-AP-4	4.1		C	1421	1137	947	812
	19-AP-2	4.8		D	0.077	0.120	0.173	0.235
	19-SR-4	4.2		U	1934	1238	860	632
	19-SR-2	4.4		D	0.082	0.129	0.185	0.252
1-1/2" x 3/16"	19-AP-4	4.7	0.711	C	1934	1547	1289	1105
	19-AP-2	5.3		D	0.066	0.103	0.148	0.202
	19-SR-4	4.8		U	2526	1617	1123	825
	19-SR-2	5.0		D	0.072	0.113	0.162	0.221
	19-AP-4	5.3		C	2526	2021	1684	1444
	19-AP-2	5.9		D	0.058	0.090	0.130	0.176
2" x 3/16"	19-SR-4	5.4	1.599	U	3197	2046	1421	1044
	19-SR-2	5.6		D	0.064	0.100	0.144	0.196
	19-AP-4	5.8		C	3197	2558	2132	1827
	19-AP-2	6.5		D	0.051	0.080	0.115	0.157
	19-SR-4	5.9		U	3947	2526	1754	1289
	19-SR-2	6.1		D	0.058	0.090	0.130	0.176
2-1/4" x 3/16"	19-AP-4	6.4	1.974	C	3947	3158	2632	2256
	19-AP-2	7.1		D	0.046	0.072	0.104	0.141

U = safe uniform load, psf (page 93)

C = safe concentrated load, psf (page 93)

D = deflection, inches

E = modulus of elasticity, 10,000,000 psi

F = fiber stress, 12,000 psi

Material: ASTM B-221, 6063 or 6061

Deflection: Spans and loads to the right of the bold line exceed 1/4" deflection for uniform load of 100 psf which provides safe pedestrian comfort. These can be exceeded for other types of loads with engineer's approval.

Serrated Bars: For serrated grating, the depth of grating required for a specified load is 1/4" deeper than that shown in the table.

General: Loads and deflections are theoretical and based on static loading.

Finish: Mill finish unless otherwise specified.

FALCON MARKETPLACE

15'-FT Head x 62-4 = 936 psf

SR/AP-19 PANEL WIDTH (inches)

No. of Bars	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16
1/8" Bar	1 ⁹ / ₁₆	2 ³ / ₄	3 ¹⁵ / ₁₆	5 ¹ / ₈	6 ⁵ / ₁₆	7 ¹ / ₂	8 ¹¹ / ₁₆	9 ⁷ / ₈	11 ¹ / ₁₆	12 ¹ / ₄	13 ⁷ / ₁₆	14 ⁵ / ₈	15 ¹³ / ₁₆	17	18 ³ / ₁₆
3/16" Bar	1 ⁵ / ₈	2 ¹³ / ₁₆	4	5 ³ / ₁₆	6 ³ / ₈	7 ⁹ / ₁₆	8 ³ / ₄	9 ¹⁵ / ₁₆	11 ¹ / ₈	12 ⁵ / ₁₆	13 ¹ / ₂	14 ¹¹ / ₁₆	15 ⁷ / ₈	17 ¹ / ₁₆	18 ¹ / ₄
No. of Bars	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31
1/8" Bar	19 ³ / ₈	20 ⁹ / ₁₆	21 ³ / ₄	22 ¹⁵ / ₁₆	24 ¹ / ₈	25 ⁵ / ₁₆	26 ¹ / ₂	27 ¹¹ / ₁₆	28 ⁷ / ₈	30 ¹ / ₁₆	31 ¹ / ₄	32 ⁷ / ₁₆	33 ⁵ / ₈	34 ¹³ / ₁₆	36
3/16" Bar	19 ⁷ / ₁₆	20 ⁵ / ₈	21 ¹³ / ₁₆	23	24 ³ / ₁₆	25 ³ / ₈	26 ⁹ / ₁₆	27 ³ / ₄	28 ¹⁵ / ₁₆	30 ¹ / ₈	31 ⁵ / ₁₆	32 ¹ / ₂	33 ¹¹ / ₁₆	34 ⁷ / ₈	36 ¹ / ₁₆

Flow depths entering Pond SR4

CLOMR

Min Ch El	6895.98
WS Elev	6898.75
Max flow depth (north)	2.8 ft

NORTHWEST SWALE

Assuming trapezoidal channelized flow at riprap entry

Q100	30.2 cfs
Width	8 ft
Side Slopes	5 :1
Slope	1.6 %
n	0.020


Calculated flow depth **0.5 ft**

Project: Falcon Marketplace
Project No.: 20988-00

HEC-RAS Data Output

Proposed Conditions Model, North (Drexel Barrell Model)

File: H:\20988-00CSV\Reports\Floodplain\HECRAS\PROPOSED\FALCON_FP.prj
Plan: FALCON_US



Date: 10/17/16

100-year Output, Standard Tabel 1

Cross Sections: 2926-2842

Reach	River Sta	Profile	Q Total (cfs)	Min Ch El (ft)	W.S. Elev (ft)	Crit W.S. (ft)	E.G. Elev (ft)	E.G. Slope (ft/ft)	Vel Chnl (ft/s)	Flow Area (sq ft)	Top Width (ft)	Froude # Chl
FALCON_US	2926	100-YR	1016	6895.98	6898.75	6898.75	6899.12	0.025538	6.71	306.22	403.31	0.91
FALCON_US	2842	100-YR	1016	6888.58	6897	6889.37	6897	0.000001	0.15	6775.42	897.89	0.01

Drexel, Barrell Co.

H:\20988-00CSV\Reports\Floodplain\CLOMR\Appendix 5 - HEC-RAS Modeling\parts\HEC-RAS Output 100YR_20988.xlsx


10/17/2016

Page 1 of 1

DETENTION BASIN STAGE-STORAGE TABLE BUILDER

UD-Detention, Version 3.07 (February 2017)

Project: Falcon Marketplace Pond #




Example Zone Configuration (Retention Pond)

Required Volume Calculation	
Selected BMP Type	EDB
Watershed Area	23.80
Watershed Length	1.000
Watershed Slope	0.020
Watershed Imperviousness	85.00%
Percentage Hydrologic Soil Group A	1.00
Percentage Hydrologic Soil Group B	0.09
Percentage Hydrologic Soil Groups C/D	0.09
Desired WWCV Drain Time	40.0
Location for 1-hr Rainfall Depth	User Input
Water Quality Capture Volume (WWCV)	0.718
Excess Urban Runoff Volume (EURV)	2.706
2-yr Runoff Volume ($P_1 = 0.95 \text{ in}$)	1.498
5-yr Runoff Volume ($P_1 = 1.22 \text{ in}$)	1.979
10-yr Runoff Volume ($P_1 = 1.48 \text{ in}$)	2.476
25-yr Runoff Volume ($P_1 = 1.86 \text{ in}$)	3.204
50-yr Runoff Volume ($P_1 = 2.19 \text{ in}$)	3.826
100-yr Runoff Volume ($P_1 = 2.54 \text{ in}$)	4.561
500-yr Runoff Volume ($P_1 = 3.46 \text{ in}$)	6.456
Approximate 2-yr Detention Volume	1.422
Approximate 5-yr Detention Volume	1.881
Approximate 10-yr Detention Volume	2.328
Approximate 25-yr Detention Volume	3.029
Approximate 50-yr Detention Volume	3.456
Approximate 100-yr Detention Volume	3.844

Stage-Storage Calculation	
Zone 1 Volume (WQCV) =	0.718 acre-feet
Select Zone 2 Storage Volume (Optional) =	acre-feet
Select Zone 3 Storage Volume (Optional) =	acre-feet
Total Detention Basin Volume =	0.718 acre-feet
Initial Surcharge Volume (ISV) =	user ft ³
Initial Surcharge Depth (ISD) =	user ft
Total Available Detention Depth (H_{TAD}) =	user ft
Depth of Trickle Channel (H_{TC}) =	user ft
Slope of Trickle Channel (S_{TC}) =	user ft/ft
Slopes of Main Basin Sides (S_{MBS}) =	user ft/V
Basin Length-to-Width Ratio ($R_{L/W}$) =	user
Initial Surcharge Area (A_{IS}) =	user ft ²
Surcharge Volume Length (L_{SVL}) =	user ft
Surcharge Volume Width (W_{SVL}) =	user ft
Depth of Basin Floor (H_{BDF}) =	user ft
Length of Basin Floor (L_{BDF}) =	user ft
Width of Basin Floor (W_{BDF}) =	user ft
Area of Basin Floor (A_{BDF}) =	user ft ²
Volume of Basin Floor (V_{BDF}) =	user ft ³
Depth of Main Basin (H_{MB}) =	user ft
Length of Main Basin (L_{MB}) =	user ft
Width of Main Basin (W_{MB}) =	user ft
Area of Main Basin (A_{MB}) =	user ft ²
Volume of Main Basin (V_{MB}) =	user ft ³
Calculated Total Basin Volume (V_{TBV}) =	user acre-feet


DETENTION BASIN STAGE-STORAGE TABLE BUILDER

UD-Detention, Version 3.07 (February 2017)



Detention Basin Outlet Structure Design

UD-Detention, Version 3.07 (February 2017)



Zone 1 (WQCV)	Stage (ft)	Zone Volume (ac-ft)	Outlet Type
Zone 2			Weir&Pipe (Circular)
Zone 3			
		0.718	Total
			Calculated Parameters for Underdrain

User Input: Orifice at Underdrain Outlet (typically used to drain WQCV in a Filtration BMP)

Underdrain Orifice Invert Depth =	N/A	ft (distance below the filtration media surface)
Underdrain Orifice Diameter =	N/A	inches

Underdrain Orifice Area =	N/A	ft ²
Underdrain Orifice Centroid =	N/A	feet

User Input: Orifice Plate with one or more orifices or Elliptical Slot Weir (typically used to drain WQCV and/or EURV in a sedimentation BMP)

Invert of Lowest Orifice =	0.00	ft (relative to basin bottom at Stage = 0 ft)
Depth at top of Zone using Orifice Plate =	3.38	ft (relative to basin bottom at Stage = 0 ft)
Orifice Plate: Orifice Vertical Spacing =	N/A	inches
Orifice Plate: Orifice Area per Row =	2.69	sq. inches (diameter = 1-13/16 inches)

WQ Orifice Area per Row =	1.868E-02	ft ²
Elliptical Half-Width =	N/A	feet
Elliptical Slot Centroid =	N/A	feet
Elliptical Slot Area =	N/A	ft ²

User Input: Stage and Total Area of Each Orifice Row (numbered from lowest to highest)

Row 1 (required)	Row 2 (optional)	Row 3 (optional)	Row 4 (optional)	Row 5 (optional)	Row 6 (optional)	Row 7 (optional)	Row 8 (optional)
Stage of Orifice Centroid (ft)	0.00	1.20	2.40				
Orifice Area (sq. inches)	2.69	2.69	2.69				

Row 9 (optional)	Row 10 (optional)	Row 11 (optional)	Row 12 (optional)	Row 13 (optional)	Row 14 (optional)	Row 15 (optional)	Row 16 (optional)
Stage of Orifice Centroid (ft)							
Orifice Area (sq. inches)							

User Input: Vertical Orifice (Circular or Rectangular)

Not Selected	Not Selected
Invert of Vertical Orifice =	
Depth at top of Zone using Vertical Orifice =	
Vertical Orifice Diameter =	
	inches

Calculated Parameters for Vertical Orifice

Not Selected	Not Selected
Vertical Orifice Area =	
Vertical Orifice Centroid =	

User Input: Overflow Weir (Dropbox) and Grate (Flat or Sloped)

Zone 2 Weir	Not Selected
Overflow Weir Front Edge Height, Ho =	3.38
Overflow Weir Front Edge Length =	7.00
Overflow Weir Slope =	0.00
Horiz. Length of Weir Sides =	5.00
Overflow Grate Open Area % =	70%
Debris Clogging % =	50%

Calculated Parameters for Overflow Weir

Zone 2 Weir	Not Selected
Height of Grate Upper Edge, H _t =	3.38
Over Flow Weir Slope Length =	5.00
Grate Open Area / 100-yr Orifice Area =	4.99
Overflow Grate Open Area w/o Debris =	24.50
Overflow Grate Open Area w/ Debris =	12.25

User Input: Outlet Pipe w/ Flow Restriction Plate (Circular Orifice, Restrictor Plate, or Rectangular Orifice)

Zone 2 Circular	Not Selected
Depth to Invert of Outlet Pipe =	0.00
Circular Orifice Diameter =	30.00

Calculated Parameters for Outlet Pipe w/ Flow Restriction Plate

Zone 2 Circular	Not Selected
Outlet Orifice Area =	4.91
Outlet Orifice Centroid =	1.25
Half-Central Angle of Restrictor Plate on Pipe =	N/A

User Input: Emergency Spillway (Rectangular or Trapezoidal)

Spillway Invert Stage=	5.10	ft (relative to basin bottom at Stage = 0 ft)
Spillway Crest Length =	120.00	feet
Spillway End Slopes =	5.00	H:V
Freeboard above Max Water Surface =	0.50	feet

Calculated Parameters for Spillway


Spillway Design Flow Depth=	0.40	feet
Stage at Top of Freeboard =	6.00	feet
Basin Area at Top of Freeboard =	1.00	acres

Routed Hydrograph Results

	WQCV	EURV	2 Year	5 Year	10 Year	25 Year	50 Year	100 Year	500 Year
Design Storm Return Period =									
One-Hour Rainfall Depth (in) =	0.53	1.07	0.95	1.22	1.48	1.86	2.19	2.54	3.46
Calculated Runoff Volume (acre-ft) =	0.718	2.706	1.498	1.979	2.476	3.204	3.826	4.561	6.456
OPTIONAL Override Runoff Volume (acre-ft) =	0.717	2.703	1.496	1.976	2.473	3.200	3.821	4.556	6.445
Predevelopment Unit Peak Flow, q (cfs/acre) =	0.00	0.00	0.00	0.01	0.01	0.03	0.26	0.65	1.56
Predevelopment Peak Q (cfs) =	0.0	0.0	0.0	0.1	0.3	0.8	6.2	15.4	37.2
Peak Inflow Q (cfs) =	14.9	55.3	30.8	40.6	50.6	65.3	77.7	92.3	129.6
Peak Outflow Q (cfs) =	0.4	35.1	13.8	22.2	31.2	41.3	43.6	46.3	103.3
Ratio Peak Outflow to Predevelopment Q =	N/A	N/A	N/A	165.0	95.6	51.7	7.0	3.0	2.8
Structure Controlling Flow =	Plate	Overflow Grate 1							
Max Velocity through Grate 1 (fps) =	N/A	1.43	0.53	0.9	1.3	1.7	1.8	1.9	1.9
Max Velocity through Grate 2 (fps) =	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Time to Drain 97% of Inflow Volume (hours) =	37	31	35	33	32	30	29	28	24
Time to Drain 99% of Inflow Volume (hours) =	40	38	40	39	37	36	35	33	
Maximum Ponding Depth (ft) =	3.29	4.15	3.78	3.94	4.09	4.30	4.65	5.09	5.38
Area at Maximum Ponding Depth (acres) =	0.53	0.67	0.61	0.64	0.66	0.70	0.76	0.84	0.89
Maximum Volume Stored (acre-ft) =	0.669	1.185	0.954	1.054	1.145	1.288	1.544	1.904	2.155

Detention Basin Outlet Structure Design

UD-Detention, Version 3.07 (February 2017)



S-A-V-D Chart Axis Override	X-axis	Left Y-Axis	Right Y-Axis
minimum bound			
maximum bound			

Detention Basin Outlet Structure Design

Outflow Hydrograph Workbook Filename:

Storm Inflow Hydrographs

UD-Detention, Version 3.07 (February 2017)

The user can override the calculated inflow hydrographs from this workbook with inflow hydrographs developed in a separate program.

Detention Basin Outlet Structure Design

UD-Detention, Version 3.07 (February 2017)

Summary Stage-Area-Volume-Discharge Relationships


The user can create a summary S-A-V-D by entering the desired stage increments and the remainder of the table will populate automatically.

The user should graphically compare the summary S-A-V-D table to the full S-A-V-D table in the chart to confirm it captures all key transition points.

DETENTION BASIN STAGE-STORAGE TABLE BUILDER

Project: FALCON MARKETPLACE

ID: POND #3



Example Zone Configuration (Retention Pond)


Required Volume Calculations

	Selected BMP Type	EDB
Watershed Area =	5.14	
Watershed Length =	1.000	
Watershed Slope =	0.020	
Watershed Imperviousness =	52.00%	
Percentage Hydrologic Soil Group A =	100.0%	
Percentage Hydrologic Soil Group B =	0.0%	
Percentage Hydrologic Soil Groups C/D =	0.0%	
Desired WUCFV DRAIN Time =	40.0	
Location for 1-h Rainfall Depths =	UDCFD Cell	
Water Quality Capture Volume (WQCV) =	0.091	
Excess Urban Runoff Volume (EURV) =	0.312	
2-yr Runoff Volume (P1 = 0.95 in.) =	0.160	
5-yr Runoff Volume (P1 = 1.34 in.) =	0.239	
10-yr Runoff Volume (P1 = 1.64 in.) =	0.323	
25-yr Runoff Volume (P1 = 2.02 in.) =	0.484	
50-yr Runoff Volume (P1 = 2.32 in.) =	0.591	
100-yr Runoff Volume (P1 = 2.61 in.) =	0.710	
500-yr Runoff Volume (P1 = 3.29 in.) =	0.986	
Approximate 2-yr Detention Volume =	0.152	
Approximate 5-yr Detention Volume =	0.228	
Approximate 10-yr Detention Volume =	0.308	
Approximate 25-yr Detention Volume =	0.380	
Approximate 50-yr Detention Volume =	0.422	
Approximate 100-yr Detention Volume =	0.495	


Stage-Storage Calculations

Zone 1 Total Volume (W _{OCV}) =	<input type="text" value="0.091"/>	acre-feet
Select Zone 2 Storage Volume (Optional) =	<input type="text"/>	acre-feet
Select Zone 3 Storage Volume (Optional) =	<input type="text"/>	acre-feet
Total Detention Basin Volume =	<input type="text" value="0.091"/>	acre-feet
Initial Surcharge Volume (SV) =	<input type="text"/>	ft ³
Initial Surcharge Depth (ISD) =	<input type="text"/>	ft
Total Available Depth (H _{total}) =	<input type="text"/>	ft
Depth of Trickle Channel (H _{Tc}) =	<input type="text"/>	ft
Slope of Trickle Channel (S _{Tc}) =	<input type="text"/>	ft/ft
Slopes of Main Basin Sides (S _{main}) =	<input type="text"/>	H/V
Basin Length-to-Width Ratio (R _{LW}) =	<input type="text"/>	
Initial Surcharge Area (A _{SV}) =	<input type="text"/>	ft ²
Surcharge Volume Length (L _{SV}) =	<input type="text"/>	ft
Surcharge Volume Width (W _{SV}) =	<input type="text"/>	ft
Depth of Basin Floor (H _{bottom}) =	<input type="text"/>	ft
Length of Basin Floor (L _{bottom}) =	<input type="text"/>	ft
Width of Basin Floor (W _{bottom}) =	<input type="text"/>	ft
Area of Basin Floor (A _{bottom}) =	<input type="text"/>	ft ²
Volume of Basin Floor (V _{bottom}) =	<input type="text"/>	ft ³
Depth of Main Basin (H _{main}) =	<input type="text"/>	ft
Length of Main Basin (L _{main}) =	<input type="text"/>	ft
Width of Main Basin (W _{main}) =	<input type="text"/>	ft
Area of Main Basin (A _{main}) =	<input type="text"/>	ft ²
Volume of Main Basin (V _{main}) =	<input type="text"/>	ft ³
Calculated Total Basin Volume (V _{total}) =	<input type="text"/>	acre-feet

DETENTION BASIN STAGE-STORAGE TABLE BUILDER



Detention Basin Outlet Structure Design



Zone	Stage (ft)	Zone Volume (ac-ft)	Outlet Type
Zone 1 (WQCV)	2.89	0.091	Orifice Plate
Zone 2			Weir&Pipe (Circular)
Zone 3			
		0.091	Total

User Input: Orifice at Underdrain Outlet (typically used to drain WQCV in a filtration BMP)

Underdrain Orifice Invert Depth = ft (distance below the filtration media surface)
Underdrain Orifice Diameter = inches

Calculated Parameters for Underdrain
Underdrain Orifice Area = ft²
Underdrain Orifice Centroid = feet

User Input: Orifice Plate with one or more orifices or Elliptical Slot Weir (typically used to drain WQCV and/or EURV in a sedimentation BMP)

Invert of Lowest Orifice = ft (relative to basin bottom at Stage = 0 ft)
Depth at top of Zone using Orifice Plate = ft (relative to basin bottom at Stage = 0 ft)
Orifice Plate: Orifice Vertical Spacing = inches
Orifice Plate: Orifice Area per Row = sq. inches (diameter = 3/4 inch)

Calculated Parameters for Plate
WQ Orifice Area per Row = ft²
Elliptical Half-Width = feet
Elliptical Slot Centroid = feet
Elliptical Slot Area = ft²

User Input: Stage and Total Area of Each Orifice Row (numbered from lowest to highest)

Row 1 (required)	Row 2 (optional)	Row 3 (optional)	Row 4 (optional)	Row 5 (optional)	Row 6 (optional)	Row 7 (optional)	Row 8 (optional)
Stage of Orifice Centroid (ft)	0.00	0.96	1.93				
Orifice Area (sq. inches)	0.43	0.43	0.43				
Stage of Orifice Centroid (ft)							
Orifice Area (sq. inches)							

User Input: Vertical Orifice (Circular or Rectangular)

Invert of Vertical Orifice = ft (relative to basin bottom at Stage = 0 ft)
Depth at top of Zone using Vertical Orifice = ft (relative to basin bottom at Stage = 0 ft)
Vertical Orifice Diameter = inches

Calculated Parameters for Vertical Orifice

Not Selected	Not Selected
Vertical Orifice Area = <input type="text" value="Not Selected"/>	ft ²
Vertical Orifice Centroid = <input type="text" value="Not Selected"/>	feet

User Input: Overflow Weir (Dropbox) and Grate (Flat or Sloped)

Zone 2 Weir	Not Selected
Overflow Weir Front Edge Height, Ho = <input type="text" value="3.00"/> ft (relative to basin bottom at Stage = 0 ft)	
Overflow Weir Front Edge Length = <input type="text" value="3.00"/> feet	
Overflow Weir Slope = <input type="text" value="0.00"/> H:V (enter zero for flat grate)	
Horiz. Length of Weir Sides = <input type="text" value="3.00"/> feet	
Overflow Grate Open Area % = <input type="text" value="70%"/> %, grate open area/total area	
Debris Clogging % = <input type="text" value="50%"/> %	

Calculated Parameters for Overflow Weir

Zone 2 Weir	Not Selected
Height of Grate Upper Edge, H _t = <input type="text" value="3.00"/> feet	
Over Flow Weir Slope Length = <input type="text" value="3.00"/> feet	
Grate Open Area / 100-yr Orifice Area = <input type="text" value="3.57"/> should be ≥ 4	
Overflow Grate Open Area w/o Debris = <input type="text" value="6.30"/> ft ²	
Overflow Grate Open Area w/ Debris = <input type="text" value="3.15"/> ft ²	

User Input: Outlet Pipe w/ Flow Restriction Plate (Circular Orifice, Restrictor Plate, or Rectangular Orifice)

Zone 2 Circular	Not Selected
Depth to Invert of Outlet Pipe = <input type="text" value="0.00"/> ft (distance below basin bottom at Stage = 0 ft)	
Circular Orifice Diameter = <input type="text" value="18.00"/> inches	

Calculated Parameters for Outlet Pipe w/ Flow Restriction Plate

Zone 2 Circular	Not Selected
Outlet Orifice Area = <input type="text" value="1.77"/> ft ²	
Outlet Orifice Centroid = <input type="text" value="0.75"/> feet	
Half-Central Angle of Restrictor Plate on Pipe = <input type="text" value="N/A"/> radians	

User Input: Emergency Spillway (Rectangular or Trapezoidal)

Spillway Invert Stage = <input type="text" value="3.75"/> ft (relative to basin bottom at Stage = 0 ft)
Spillway Crest Length = <input type="text" value="50.00"/> feet
Spillway End Slopes = <input type="text" value="4.00"/> H:V
Freeboard above Max Water Surface = <input type="text" value="1.00"/> feet


Calculated Parameters for Spillway

Spillway Design Flow Depth = <input type="text" value="0.19"/> feet
Stage at Top of Freeboard = <input type="text" value="4.94"/> feet
Basin Area at Top of Freeboard = <input type="text" value="0.10"/> acres

Routed Hydrograph Results

	WQCV	EURV	2 Year	5 Year	10 Year	25 Year	50 Year	100 Year	500 Year
Design Storm Return Period =									
One-Hour Rainfall Depth (in)	0.53	1.07	0.95	1.34	1.64	2.02	2.32	2.61	3.29
Calculated Runoff Volume (acre-ft) =	0.091	0.312	0.160	0.239	0.323	0.484	0.591	0.710	0.986
OPTIONAL Overline Runoff Volume (acre-ft) =	0.090	0.311	0.159	0.239	0.322	0.483	0.591	0.710	0.985
Inflow Hydrograph Volume (acre-ft) =	0.00	0.00	0.00	0.01	0.01	0.16	0.33	0.54	0.99
Predevelopment Unit Peak Flow, q (cfs/acre) =	0.00	0.00	0.00	0.0	0.1	0.8	1.7	2.8	5.1
Predevelopment Peak Q (cfs) =	0.0	0.0	0.0	0.0	0.1	0.8	1.7	2.8	5.1
Peak Inflow Q (cfs) =	1.6	5.5	2.8	4.2	5.7	8.6	10.5	12.6	17.4
Peak Outflow Q (cfs) =	0.1	4.9	1.3	3.4	5.6	8.4	10.6	13.8	19.4
Ratio Peak Outflow to Predevelopment Q =	N/A	N/A	N/A	81.9	81.7	10.4	6.3	5.0	3.8
Structure Controlling Flow =	Plate	Overflow Grate 1	Spillway						
Max Velocity through Grate 1 (fps) =	N/A	0.78	0.19	0.5	0.9	1.3	1.7	2.2	2.4
Max Velocity through Grate 2 (fps) =	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Time to Drain 97% of Inflow Volume (hours) =	37	34	38	36	34	29	27	26	22
Time to Drain 99% of Inflow Volume (hours) =	40	41	43	41	40	39	37	36	34
Maximum Ponding Depth (ft) =	2.71	3.33	3.13	3.25	3.36	3.47	3.55	3.71	3.84
Area at Maximum Ponding Depth (acres) =	0.05	0.06	0.06	0.06	0.06	0.07	0.07	0.07	0.07
Maximum Volume Stored (acre-ft) =	0.081	0.117	0.105	0.113	0.119	0.126	0.132	0.143	0.153

Detention Basin Outlet Structure Design



S-A-V-D Chart Axis Override	X-axis	Left Y-Axis	Right Y-Axis
minimum bound			
maximum bound			

Detention Basin Outlet Structure Design

Outflow Hydrograph Workbook Filename:

Storm Inflow Hydrographs

The user can override the calculated inflow hydrographs from this workbook with inflow hydrographs developed in a separate program.

Detention Basin Outlet Structure Design



Summary Stage-Area-Volume-Discharge Relationships

The user can create a summary S-A-V-D by entering the desired stage increments and the remainder of the table will populate automatically.


The user should graphically compare the summary S-A-V-D table to the full S-A-V-D table in the chart to confirm it captures all key transition points.

Falcon DBPS Excerpts

Sheet 6-23
Falcon DBPS
Conceptual Plan
Middle Tributary
El Paso County, CO




Matrix
DESIGN GROUP



Sheet 4-21

Middle Tributary Floodplain
Falcon DBPS
El Paso County, CO



Legend

- Approximate 100-yr Floodplain Existing
- Approximate 100-yr Floodplain Existing (Based on Assumed Split Flow Condition)
- Approximate 100-yr Floodplain Future
- Approximate 100-yr Floodplain Future (Based on Assumed Split Flow Condition)
- Shallow Flooding
- HEC-RAS Centerline
- XSCutLines (Middle Trib)
- FEMA Regulatory Floodplain (Effective as of 1999)*
- Study Limit

*Letters of Map Change completed after 1999 are not shown



0 100 200 400
Feet



Matrix DESIGN GROUP

Sheet 4-22

Middle Tributary Floodplain
Falcon DBPS
El Paso County, CO

Legend

- Approximate 100-yr Floodplain Existing
- Approximate 100-yr Floodplain Existing (Based on Assumed Split Flow Condition)
- Approximate 100-yr Floodplain Future
- Approximate 100-yr Floodplain Future (Based on Assumed Split Flow Condition)
- Shallow Flooding
- HEC-RAS Centerline
- XSCutLines (Middle Trib)
- FEMA Regulatory Floodplain (Effective as of 1999)*
- Study Limit


*Letters of Map Change completed after 1999 are not shown



0 100 200 400
Feet




Matrix DESIGN GROUP




CLOMR Excerpts

① Schematic




- ② USE FHWA HY-B software to check culvert capacity
- ③ Model input based on 3 sources of information
 - a) project surveys by DBC for Falcon Marketplace
email 9/26/16
 - b) design drawing from Regency Center
VRS 8/24/04
 - c) design drawing for culvert extension on
north side of Woodman
DMJM Harris/AECOM 9/11/2007
 - d) see HYB model output files
file: HY-B-Woodman Culverts.hyB
 - e) Design flow rate varied until allowable headwater elevation reached. Allowable headwater elevation = to north edge of Woodman Road Asphalt.

f) west culvert:



EAST CULVERT:



- g) The Woodman Road culverts discharge to large 84" culvert & 8'x8' culvert on the Regency center property that are @ a significantly lower elevation.

FALCON MARKET PLACE 20988-00 SAL 9/28/16

2/2

than the invert of the 48" Q pipes; therefore inlet control conditions are anticipated w/ no backwater from downstream

- ④ See H8-8 output

- a) West Culvert: $Q_{cap} = 355 \text{ cfs}$ w/ HWE 6877.99
 ≈ 6878

b) East Culverts $Q_{cap} = 405 \text{ cfs}$ w/ HWE 6875.12
 ≈ 6875.2

c) Total Capacity 760 cfs

d) Also looked @ capacity of both culverts with the lower allowable headwater elevation

WEST
CULVERTS

East Currents

A row of three small, circular depressions or pores arranged horizontally on a surface.

666

$$Q_{cup} = 600 \text{ cts}$$

HY-8 Culvert Analysis Report

Project Notes

Project Title:

Designer:

Project Date: Wednesday, September 28, 2016

Notes:

Project Units: U.S. Customary Units

Outlet Control Option: Profiles


Exit Loss Option: Standard Method

Crossing Notes: East Culvert


Table 1 - Summary of Culvert Flows at Crossing: East Culvert

Headwater Elevation (ft)	Total Discharge (cfs)	East Discharge (cfs)	Roadway Discharge (cfs)	Iterations
6867.80	0.00	0.00	0.00	1
6869.44	50.00	50.00	0.00	1
6870.26	100.00	100.00	0.00	1
6870.95	150.00	150.00	0.00	1
6871.58	200.00	200.00	0.00	1
6872.41	250.00	250.00	0.00	1
6873.01	300.00	300.00	0.00	1
6873.88	350.00	350.00	0.00	1
6875.00	400.00	400.00	0.00	1
6875.12	405.00	405.00	0.00	1
6875.78	500.00	432.38	67.60	5
6875.20	408.39	408.39	0.00	Overtopping

Rating Curve Plot for Crossing: East Culvert



Crossing Front View (Roadway Profile): East Culvert



Culvert Notes: East

Table 2 - Culvert Summary Table: East


Total Discharge (cfs)	Culvert Discharge (cfs)	Headwater Elevation (ft)	Inlet Control Depth (ft)	Outlet Control Depth (ft)	Flow Type	Normal Depth (ft)	Critical Depth (ft)	Outlet Depth (ft)	Tailwater Depth (ft)	Outlet Velocity (ft/s)	Tailwater Velocity (ft/s)
0.00	0.00	6867.80	0.000	0.0*	0-NF	0.000	0.000	0.000	0.000	0.000	0.000
50.00	50.00	6869.44	1.645	0.0*	1-S2n	1.114	1.197	1.117	0.745	5.778	8.385
100.00	100.00	6870.26	2.457	0.0*	1-S2n	1.620	1.708	1.622	1.169	6.978	10.692
150.00	150.00	6870.95	3.153	0.0*	1-S2n	2.042	2.114	2.043	1.532	7.747	12.238
200.00	200.00	6871.58	3.785	0.0*	1-S2n	2.445	2.461	2.445	1.864	8.280	13.414
250.00	250.00	6872.41	4.445	4.610	2-M2c	2.874	2.763	2.766	2.175	8.989	14.366
300.00	300.00	6873.01	5.196	5.208	2-M2c	3.464	3.018	3.030	2.473	9.792	15.165
350.00	350.00	6873.88	6.077	6.001	2-M2c	4.000	3.246	3.258	2.760	10.663	15.852
400.00	400.00	6875.00	7.109	7.200	7-M2c	4.000	3.420	3.447	3.039	11.579	16.454
405.00	405.00	6875.12	7.221	7.318	7-M2c	4.000	3.437	3.464	3.066	11.676	16.509
500.00	432.38	6875.78	7.861	7.984	7-M2c	4.000	3.533	3.544	3.578	12.241	17.466

* theoretical depth is impractical. Depth reported is corrected.


Inlet Elevation (invert): 6867.80 ft, Outlet Elevation (invert): 6866.90 ft

Culvert Length: 200.00 ft, Culvert Slope: 0.0045

Culvert Performance Curve Plot: East



Water Surface Profile Plot for Culvert: East



Site Data - East

Site Data Option: Culvert Invert Data

Inlet Station: 0.00 ft

Inlet Elevation: 6867.80 ft

Outlet Station: 200.00 ft

Outlet Elevation: 6866.90 ft

Number of Barrels: 3

Culvert Data Summary - East

Barrel Shape: Circular

Barrel Diameter: 4.00 ft

Barrel Material: Concrete

Embedment: 0.00 in

Barrel Manning's n: 0.0130

Inlet Type: Conventional

Inlet Edge Condition: Square Edge with Headwall

Inlet Depression: NONE

Table 3 - Downstream Channel Rating Curve (Crossing: East Culvert)

Flow (cfs)	Water Surface Elev (ft)	Depth (ft)	Velocity (ft/s)	Shear (psf)	Froude Number
0.00	6856.60	0.00	0.00	0.00	0.00
50.00	6857.35	0.75	8.39	0.47	1.71
100.00	6857.77	1.17	10.69	0.73	1.74
150.00	6858.13	1.53	12.24	0.96	1.74
200.00	6858.46	1.86	13.41	1.16	1.73
250.00	6858.78	2.18	14.37	1.36	1.72
300.00	6859.07	2.47	15.17	1.54	1.70
350.00	6859.36	2.76	15.85	1.72	1.68
400.00	6859.64	3.04	16.45	1.90	1.66
405.00	6859.67	3.07	16.51	1.91	1.66
500.00	6860.18	3.58	17.47	2.23	1.63

Tailwater Channel Data - East Culvert

Tailwater Channel Option: Rectangular Channel

Bottom Width: 8.00 ft


Channel Slope: 0.0100

Channel Manning's n: 0.0130

Channel Invert Elevation: 6856.60 ft

Tailwater Rating Curve Plot for Crossing: East Culvert

Downstream Channel Rating Curve



Roadway Data for Crossing: East Culvert

Roadway Profile Shape: Irregular Roadway Shape (coordinates)

Irregular Roadway Cross-Section:

Coord No.	Station (ft)	Elevation (ft)
0	0.00	6875.20
1	25.00	6875.20
2	50.00	6875.20

Roadway Surface: Paved

Roadway Top Width: 50.00 ft

HY-8 Culvert Analysis Report

Project Notes

Project Title:

Designer:

Project Date: Wednesday, September 28, 2016

Notes:

Project Units: U.S. Customary Units

Outlet Control Option: Profiles


Exit Loss Option: Standard Method

Crossing Notes: West Culvert


Table 1 - Summary of Culvert Flows at Crossing: West Culvert

Headwater Elevation (ft)	Total Discharge (cfs)	West Discharge (cfs)	Roadway Discharge (cfs)	Iterations
6871.20	0.00	0.00	0.00	1
6873.04	50.00	50.00	0.00	1
6873.88	100.00	100.00	0.00	1
6874.60	150.00	150.00	0.00	1
6875.27	200.00	200.00	0.00	1
6875.96	250.00	250.00	0.00	1
6876.84	300.00	300.00	0.00	1
6877.87	350.00	350.00	0.00	1
6877.99	355.00	355.00	0.00	1
6878.59	450.00	381.65	68.32	5
6878.80	500.00	390.91	108.90	4
6878.00	355.54	355.54	0.00	Overtopping

Rating Curve Plot for Crossing: West Culvert



Crossing Front View (Roadway Profile): West Culvert



Culvert Notes: West

Table 2 - Culvert Summary Table: West


Total Discharge (cfs)	Culvert Discharge (cfs)	Headwater Elevation (ft)	Inlet Control Depth (ft)	Outlet Control Depth (ft)	Flow Type	Normal Depth (ft)	Critical Depth (ft)	Outlet Depth (ft)	Tailwater Depth (ft)	Outlet Velocity (ft/s)	Tailwater Velocity (ft/s)
0.00	0.00	6871.20	0.000	0.0*	0-NF	0.000	0.000	0.000	0.000	0.000	0.000
50.00	50.00	6873.04	1.649	1.836	2-M2c	1.492	1.197	1.197	0.821	5.273	8.705
100.00	100.00	6873.88	2.463	2.685	2-M2c	2.228	1.708	1.716	1.297	6.473	11.017
150.00	150.00	6874.60	3.159	3.396	2-M2c	2.970	2.114	2.121	1.709	7.390	12.536
200.00	200.00	6875.27	3.791	4.071	2-M2c	4.000	2.461	2.465	2.090	8.203	13.674
250.00	250.00	6875.96	4.451	4.755	2-M2c	4.000	2.763	2.766	2.449	8.989	14.582
300.00	300.00	6876.84	5.202	5.642	7-M2c	4.000	3.018	3.030	2.795	9.792	15.335
350.00	350.00	6877.87	6.083	6.665	7-M2c	4.000	3.246	3.258	3.130	10.646	15.976
355.00	355.00	6877.99	6.179	6.787	7-M2c	4.000	3.264	3.278	3.163	10.735	16.035
450.00	381.65	6878.59	6.718	7.388	7-M2c	4.000	3.356	3.380	3.777	11.230	17.019
500.00	390.91	6878.80	6.916	7.602	7-M2c	4.000	3.388	3.413	4.093	11.410	17.453

* theoretical depth is impractical. Depth reported is corrected.

Inlet Elevation (invert): 6871.20 ft, Outlet Elevation (invert): 6870.90 ft

Culvert Length: 200.00 ft, Culvert Slope: 0.0015


Culvert Performance Curve Plot: West



Water Surface Profile Plot for Culvert: West

Crossing - West Culvert, Design Discharge - 355.0 cfs

Culvert - West, Culvert Discharge - 355.0 cfs



Site Data - West

Site Data Option: Culvert Invert Data

Inlet Station: 0.00 ft

Inlet Elevation: 6871.20 ft

Outlet Station: 200.00 ft

Outlet Elevation: 6870.90 ft

Number of Barrels: 3

Culvert Data Summary - West

Barrel Shape: Circular

Barrel Diameter: 4.00 ft

Barrel Material: Concrete

Embedment: 0.00 in

Barrel Manning's n: 0.0130

Inlet Type: Conventional

Inlet Edge Condition: Square Edge with Headwall

Inlet Depression: NONE

Table 3 - Downstream Channel Rating Curve (Crossing: West Culvert)

Flow (cfs)	Water Surface Elev (ft)	Depth (ft)	Velocity (ft/s)	Shear (psf)	Froude Number
0.00	6861.00	0.00	0.00	0.00	0.00
50.00	6861.82	0.82	8.71	0.51	1.69
100.00	6862.30	1.30	11.02	0.81	1.71
150.00	6862.71	1.71	12.54	1.07	1.69
200.00	6863.09	2.09	13.67	1.30	1.67
250.00	6863.45	2.45	14.58	1.53	1.64
300.00	6863.79	2.79	15.34	1.74	1.62
350.00	6864.13	3.13	15.98	1.95	1.59
355.00	6864.16	3.16	16.03	1.97	1.59
450.00	6864.78	3.78	17.02	2.36	1.54
500.00	6865.09	4.09	17.45	2.55	1.52

Tailwater Channel Data - West Culvert

Tailwater Channel Option: Rectangular Channel

Bottom Width: 7.00 ft


Channel Slope: 0.0100

Channel Manning's n: 0.0130

Channel Invert Elevation: 6861.00 ft

Tailwater Rating Curve Plot for Crossing: West Culvert

Downstream Channel Rating Curve



Roadway Data for Crossing: West Culvert


Roadway Profile Shape: Irregular Roadway Shape (coordinates)

Irregular Roadway Cross-Section:


Coord No.	Station (ft)	Elevation (ft)
0	0.00	6878.00
1	25.00	6878.00
2	50.00	6878.00


Roadway Surface: Paved

Roadway Top Width: 50.00 ft



EMERGENCY CENTER STORM DRAIN SYSTEM






SCALE:
1" = 40' HORIZONTAL
1" = 4' VERTICAL

Computer File Information		Sheet Revisions		WOODMEN ROAD		Project No./Code	
Creation Date:	01/20/06	Initials:	LPS	STORM SEWER PROFILE -		STU M240-062	
Last Modification Date:	01/17/2007	Initials:	LPS	WOODMEN RD. STA. 322+09.20		13263	
Full Path:	\4954\4954_0504\drainage\549PRTR5.dgn			Designer:	Clik	Structure Numbers	Sheet Number
Drafting Scale:	1=25	Units:	ENGLISH	Detailer:			DR45
VR Ver:	00.00.01.19	Vod:		Sheet SubSet:	DRANGE	SubSet Sheets:	DR45
						of 150	





10/10/2007 8:00:56 AM

CLOMR Approval



Federal Emergency Management Agency

Washington, D.C. 20472

May 26, 2017

CERTIFIED MAIL
RETURN RECEIPT REQUESTED

The Honorable Darryl Glenn
Chairman, El Paso County
Board of Commissioners
200 South Cascade Avenue, Suite 100
Colorado Springs, CO 80903

IN REPLY REFER TO:
Case No.: 17-08-0074R
Community Name: El Paso County, CO
Community No.: 080059

Dear Mr. Glenn:

The Flood Insurance Study Report and Flood Insurance Rate Map for your community have been revised by this Letter of Map Revision (LOMR). Please use the enclosed annotated map panel(s) revised by this LOMR for floodplain management purposes and for all flood insurance policies and renewals issued in your community.

Additional documents are enclosed that provide information regarding this LOMR. Please see the List of Enclosures below to determine which documents are included. Other attachments specific to this request may be included as referenced in the Determination Document. If you have any questions regarding floodplain management regulations for your community or the National Flood Insurance Program (NFIP) in general, please contact the Consultation Coordination Officer for your community. If you have any technical questions regarding this LOMR, please contact the Director, Mitigation Division of the Department of Homeland Security's Federal Emergency Management Agency (FEMA) in Denver, Colorado, at (303) 235-4830, or the FEMA Map Information eXchange (FMIX) toll free at 1-877-336-2627 (1-877-FEMA MAP). Additional information about the NFIP is available on our website at <http://www.fema.gov/national-flood-insurance-program>.

Sincerely,

Patrick "Rick" F. Sacbibit, P.E., Branch Chief
Engineering Services Branch
Federal Insurance and Mitigation Administration

List of Enclosures:

- Letter of Map Revision Determination Document
- Annotated Flood Insurance Rate Map
- Annotated Flood Insurance Study Report

cc: Mr. Keith Curtis, P.E., CFM
Floodplain Administrator
El Paso County

Mr. Steven Leslie, P.E., CFM
Project Engineer
Drexell, Barrell & CO



Federal Emergency Management Agency
Washington, D.C. 20472

**CONDITIONAL LETTER OF MAP REVISION
COMMENT DOCUMENT**

COMMUNITY INFORMATION		PROPOSED PROJECT DESCRIPTION	BASIS OF CONDITIONAL REQUEST
COMMUNITY	El Paso County Colorado (Unincorporated Areas)	CHANNELIZATION BRIDGE	HYDRAULIC ANALYSIS UPDATED TOPOGRAPHIC DATA HYDROLOGIC ANALYSIS
	COMMUNITY NO.: 080059		
IDENTIFIER	Falcon Marketplace	APPROXIMATE LATITUDE & LONGITUDE: 38.9426, -104.610 SOURCE: USGS QUADRANGLE DATUM: NAD 83	
AFFECTED MAP PANELS			
TYPE: FIRM*	NO.: 08041C0575F	DATE: March 17, 1997	* FIRM - Flood Insurance Rate Map

FLOODING SOURCE(S) AND REACH DESCRIPTION

Unnamed Tributary to Black Squirrel Creek- from Woodmen Road to approximately 2,280 feet upstream of Woodmen Road

PROPOSED PROJECT DESCRIPTION

Flooding Source	Proposed Project	Location of Proposed Project
Unnamed Tributary to Black Squirrel Creek	Channelization	From Woodmen Road to approximately 2,820 feet upstream of Woodmen Road
	Bridge Modification	At Woodmen Road

SUMMARY OF IMPACTS TO FLOOD HAZARD DATA

Flooding Source	Effective Flooding	Proposed Flooding	Increases	Decreases
Unnamed Tributary to Black Squirrel Creek	Zone A No BFEs	Zone AE BFEs	Yes Yes	Yes None

* BFEs - Base (1-percent-annual-chance) Flood Elevations

COMMENT

This document provides the Federal Emergency Management Agency's (FEMA's) comment regarding a request for a CLOMR for the project described above. This document is not a final determination; it only provides our comment on the proposed project in relation to the flood hazard information shown on the effective National Flood Insurance Program (NFIP) map. We reviewed the submitted data and the data used to prepare the effective flood hazard information for your community and determined that the proposed project meets the minimum floodplain management criteria of the NFIP. Your community is responsible for approving all floodplain development and for ensuring that all permits required by Federal or State/Commonwealth law have been received. State/Commonwealth, county, and community officials, based on their knowledge of local conditions and in the interest of safety, may set higher standards for construction in the Special Flood Hazard Area (SFHA), the area subject to inundation by the base flood). If the State/Commonwealth, county, or community has adopted more restrictive or comprehensive floodplain management criteria, these criteria take precedence over the minimum NFIP criteria.

This comment is based on the flood data presently available. If you have any questions about this document, please contact the FEMA Map Information eXchange (FMIX) toll free at 1-877-336-2627 (1-877-FEMA MAP) or by letter addressed to the LOMC Clearinghouse, 3601 Eisenhower Avenue, Suite 500, Alexandria, VA 22304-6426. Additional information about the NFIP is available on the FEMA website at <http://www.fema.gov/national-flood-insurance-program>.

Patrick "Rick" F. Sacbibit, P.E., Branch Chief
Engineering Services Branch
Federal Insurance and Mitigation Administration



Federal Emergency Management Agency
Washington, D.C. 20472

**CONDITIONAL LETTER OF MAP REVISION
COMMENT DOCUMENT (CONTINUED)**

COMMUNITY INFORMATION

USE PARAGRAPH BELOW WHEN REQUEST IS FOR ZONE A ONLY

To determine the changes in flood hazards that will be caused by the proposed project, we compared the hydraulic modeling reflecting the proposed project (referred to as the proposed conditions model) to the hydraulic modeling reflecting the existing conditions.

The table below shows the changes in the base flood water-surface elevations (WSELS).

Base Flood WSEL Comparison Table			
Flooding Source: Unnamed Tributary to Black Squirrel Creek		Base Flood WSEL Change (feet)	Location of maximum change
Proposed vs.	Maximum increase	None	N/A
Existing	Maximum decrease	7.3	Approximately 880 feet upstream of Woodmen Road

NFIP regulations Subparagraph 60.3(b)(7) requires communities to ensure that the flood-carrying capacity within the altered or relocated portion of any watercourse is maintained. This provision is incorporated into your community's existing floodplain management ordinances; therefore, responsibility for maintenance of the altered or relocated watercourse, including any related appurtenances such as bridges, culverts, and other drainage structures, rests with your community. We may request that your community submit a description and schedule of maintenance activities necessary to ensure this requirement.

This comment is based on the flood data presently available. If you have any questions about this document, please contact the FEMA Map Information eXchange (FMIX) toll free at 1-877-336-2627 (1-877-FEMA MAP) or by letter addressed to the LOMC Clearinghouse, 3601 Eisenhower Avenue, Suite 500, Alexandria, VA 22304-6426. Additional information about the NFIP is available on the FEMA website at <http://www.fema.gov/national-flood-insurance-program>.

Patrick "Rick" F. Sacubit, P.E., Branch Chief
Engineering Services Branch
Federal Insurance and Mitigation Administration



Federal Emergency Management Agency
Washington, D.C. 20472

**CONDITIONAL LETTER OF MAP REVISION
COMMENT DOCUMENT (CONTINUED)**

COMMUNITY INFORMATION (CONTINUED)

DATA REQUIRED FOR FOLLOW-UP LOMR

Upon completion of the project, your community must submit the data listed below and request that we make a final determination on revising the effective FIRM. If the project is built as proposed and the data below are received, a revision to the FIRM would be warranted.

- Detailed application and certification forms must be used for requesting final revisions to the maps. Therefore, when the map revision request for the area covered by this letter is submitted, Form 1, entitled "Overview and Concurrence Form," must be included. A copy of this form may be accessed at http://www.fema.gov/plan/prevent/fhm/dl_mt-2.shtm.
- The detailed application and certification forms listed below may be required if as-built conditions differ from the proposed plans. If required, please submit new forms, which may be accessed at http://www.fema.gov/plan/prevent/fhm/dl_mt-2.shtm, or annotated copies of the previously submitted forms showing the revised information.

Form 2, entitled "Riverine Hydrology and Hydraulics Form." Hydraulic analyses for as-built conditions of the base flood must be submitted with Form 2.

Form 3, entitled "Riverine Structures Form."

- A certified topographic work map showing the revised and effective base floodplain boundaries. Please ensure that the revised information ties-in with the current effective information at the downstream and upstream ends of the revised reach.
- An annotated copy of the FIRM, at the scale of the effective FIRM, that shows the revised base floodplain boundary delineations shown on the submitted work map and how they tie-in to the base floodplain boundary delineations shown on the current effective FIRM at the downstream and upstream ends of the revised reach.
- As-built plans, certified by a registered Professional Engineer, of all proposed project elements.
- Documentation of the individual legal notices sent to property owners who will be affected by any widening or shifting of the base floodplain and/or any BFE increases along the Unnamed Tributary to Black Squirrel Creek.

This comment is based on the flood data presently available. If you have any questions about this document, please contact the FEMA Map Information eXchange (FMIX) toll free at 1-877-336-2627 (1-877-FEMA MAP) or by letter addressed to the LOMC Clearinghouse, 3601 Eisenhower Avenue, Suite 500, Alexandria, VA 22304-6426. Additional Information about the NFIP is available on the FEMA website at <http://www.fema.gov/national-flood-insurance-program>.

Patrick "Rick" F. Sacubit, P.E., Branch Chief
Engineering Services Branch
Federal Insurance and Mitigation Administration



Federal Emergency Management Agency
Washington, D.C. 20472

**CONDITIONAL LETTER OF MAP REVISION
COMMENT DOCUMENT (CONTINUED)**

COMMUNITY INFORMATION (CONTINUED)

COMMUNITY REMINDERS

We have designated a Consultation Coordination Officer (CCO) to assist your community. The CCO will be the primary liaison between your community and FEMA. For information regarding your CCO, please contact:

Ms. Jeanine P. Petterson
Director, Mitigation Division
Federal Emergency Management Agency, Region VIII
Denver Federal Center, Building 710
P.O. Box 25267
Denver, CO 80225-0267
(303) 235-4830


WHEN PRELIMINARY STUDY HAS BEEN SUBMITTED TO COMMUNITY FOR REVIEW


A preliminary study is being conducted for El Paso County. Preliminary copies of the revised FIRM and FIS report were submitted to your community for review on July 29, 2015, and may become effective before the revision request following this CLOMR is submitted. Please ensure that the data submitted for the revision ties into the data effective at the time of the submittal.

This comment is based on the flood data presently available. If you have any questions about this document, please contact the FEMA Map Information eXchange (FMIX) toll free at 1-877-336-2627 (1-877-FEMA MAP) or by letter addressed to the LOMC Clearinghouse, 3601 Eisenhower Avenue, Suite 500, Alexandria, VA 22304-6426. Additional information about the NFIP is available on the FEMA website at <http://www.fema.gov/national-flood-insurance-program>.

Patrick "Rick" F. Sacbabit, P.E., Branch Chief
Engineering Services Branch
Federal Insurance and Mitigation Administration

Drainage Map






ASIN	Area (Ac.)	Q ₅ (CFS)	Q ₁₀₀ (CFS)	BASIN	Area (Ac.)	Q ₅ (CFS)	Q ₁₀₀ (CFS)
A1	0.69	0.2	1.4	B17	2.16	8.9	16.2
A2	1.50	5.2	10.2	B18	2.90	11.3	20.7
A3	4.82	1.2	8.8	B19	2.02	5.4	11.1
A4	1.52	5.6	10.2	B20	1.65	0.4	3.3
B1	0.54	2.4	4.3	C1	4.88	8.2	19.1
B2	1.18	4.9	8.9	C2	0.24	1.1	2.0
B3	1.17	4.3	7.9	C3	0.64	0.5	1.7
B4	3.32	9.6	17.6	C4	0.09	0.0	0.2
B5	0.32	1.5	2.6	C5	0.12	0.5	1.0
B6	0.31	1.4	2.5	C6	0.16	0.7	1.3
B7	0.72	3.0	5.4	C7	1.13	2.9	6.1
B8	0.17	0.8	1.4	O1	32.50	10.3	30.2
B9	2.25	8.8	16.1				
B10	0.18	0.8	1.5	DP	Area (Ac.)	Q ₅ (CFS)	Q ₁₀₀ (CFS)
B11	0.20	0.9	1.6	DP1	2.89	10.9	19.8
B12	1.76	6.1	11.2	DP2	1.03	4.4	8.0
B13	0.21	1.0	1.7	DP3	2.43	9.6	16.1
B14	4.34	16.2	29.6	DP4	25.90	66.3	124.3
B15	0.16	0.7	1.3	DP5	45.02	-	754.0
B16	0.34	1.5	2.6	DP-01	32.50	10.3	30.2

RUNOFF SUMMARY

LEGEND

PROPERTY LINE..... 

PREPARED BY:



EXEL, BARRELL & CO.
Engineers • Surveyors
3 SOUTH 7TH STREET
RADO SPGS, COLORADO 80905
FACT: TIM D. McCONNELL, P.E.
(719)260-0887
BOULDER • COLORADO SPRINGS

CLIENT:

IMEL INVESTMENTS, LLC

FALCON MARKETPLACE

FALCON, COLORADO

ISSUE	DATE
INITIAL ISSUE	1-17-17
REVISION	10-1-18

SIGNED BY:	TDM
DRAWN BY:	KGV
CHECKED BY:	TDM
NAME	

PREPARED UNDER MY DIRECT
SUPERVISION FOR AND ON BEHALF

DRAWING SCALE:
HORIZONTAL: 1"=100'

PROPOSED DRAINAGE CONDITIONS

CONDITIONS
JECT NO. 20988-00CSCV
WING NO.

D-1

PAGE: 1 OF 1