

FINAL DRAINAGE PLAN AND REPORT

16140 OLD DENVER ROAD

PART OF THE NW1/4 SEC. 26, T.11S., R.67W., 6th P.M.

EL PASO COUNTY

February 3, 2017

Revised
January 5, 2018

Revised
October 23, 2019

Revised
February 7, 2020

Prepared for

All About Outdoor Storage

PCD File No. PPR-16-037

Oliver E. Watts, Consulting Engineer, Inc.
Colorado Springs, Colorado

OLIVER E. WATTS, PE-LS
OLIVER E. WATTS, CONSULTING ENGINEER, INC.
CIVIL ENGINEERING AND SURVEYING
614 ELKTON DRIVE
COLORADO SPRINGS, COLORADO 80907
(719) 593-0173
Fax (719) 265-9660
olliewatts@aol.com
Celebrating over 40 years in business

February 7, 2020

El Paso County D.O.T.
2880 International Circle
Colorado Springs, CO 80910


ATTN: *Gilbert LaFarge*

SUBJECT: Drainage Plan and Report
All About Outdoor Storage PPR-16-037

Transmitted herewith for your review and approval is the drainage plan and report for All About Outdoor Storage at 16140 Old Denver Road in El Paso County. This report will accompany the change in use request for subject development, as requested in your review letter of January 6, 2017. It has been revised in accordance with our meeting with you and Elizabeth Nijkamp April 17, 2017, subsequent additional surveys performed at your request, and your comments of January 5, 2018 and January 28, 2020. This plan will reflect the anticipated ultimate development of the entire site.

Please contact me if I may provide any further information.

Oliver E. Watts, Consulting Engineer, Inc.

BY: 
Oliver E. Watts, President

Encl:

Drainage Report 7 pages
Computations, 11 pages
FEMA Map Panel No. 08041C0286 G
SCS Soils Map and Interpretation Sheet
Backup Information, 6 sheets
Vivid Report, 8 pages
Drainage Plan, Dwg 17-4958-03

1. ENGINEER'S STATEMENT:

The attached drainage plan and report were prepared under my direction and supervision and are correct to the best of my knowledge and belief. Said drainage report has been prepared according to the criteria established by the County for drainage reports and said report is in conformity with the applicable master plan of the drainage basin. I accept responsibility for any liability caused by any negligent acts, errors or omissions on my part in preparing this report.

Oliver E. Watts, Consulting Engineer, Inc.

Oliver E. Watts Colo. PE-LS No. 9853

2. OWNERS / DEVELOPER'S STATEMENT:

I the owner / developer have read and will comply with all of the requirements specified in this drainage report and plan.

All About Outdoor Storage

By: _____
16140 Old Denver Road
P.O. Box 73
Monument, CO 80132-0073

3. EL PASO COUNTY:

Filed in accordance with the requirements of the El Paso Land Development Code, Drainage Criteria Manual Volumes 1 and 2, and the Engineering Criteria Manual, as amended.

Jennifer Irvine, P.E., date
County Engineer / ECM Administrator

Conditions:

4. LOCATION AND DESCRIPTION:

All About Outdoor Storage is located at 16140 Old Denver Road adjacent to the Southerly City limits for the Town of Monument in Section 26, T.11S., R.67W. of the 6th P.M. in El Paso County. A change in land use from a landscape rock yard to a RV storage use was requested, and this report is a result of the 1st County review letter of January 6, 2017. The effect of this change in use is analyzed.

The site is located on Teachout Creek, and unstudied drainage basin lying south of Dirty Woman Creek. None of the requirements in the Dirty Woman Creek MDBPS affect this site. This and adjacent sites drain westerly to the Union Pacific Railroad right of way and southerly into the Teachout Creek creek crossing, which immediately discharges into Monument Creek. The drainage outfall from this site remains on private ground east of the railroad right of way.

The front portion of the total property is leased and used by All About Outdoor Storage, and the rear is used for equipment storage by another owner, as shown on the drainage plan. The existing detention pond near the southwest corner was constructed in 1986; however the County files could not be found. There is no history of drainage problems with the existing construction and it does not appear that the outlet works or spillway have discharged since construction.

5. FLOOD PLAIN STATEMENT:

This subdivision is not within the limits of a flood plain or flood hazard area, according to FEMA map panel number 08041C0286 G, dated December 7, 2018, a copy of which is enclosed for reference.

6. METHOD AND CRITERIA:

The method used for all computations is that specified in the City-County Drainage Criteria Manual, using the rational method for areas of the size of the development. Detention computations are based on UD-Detention work sheets, for existing and full spectrum detention conditions. All computations are enclosed for reference and review. The approach is to use as many of the existing facilities as possible, consistent with the referenced meetings with El Paso County personnel.

The soils in the subdivision have been mapped by the local USDA/SCS office, and a soils map and interpretation sheet are enclosed for reference. All soils in this area are of hydrologic group "B" within the affected area.

7. DESCRIPTION OF RUNOFF:

The major change in the development resulting from the proposed change of use is a change in the pavement over the storage site from gravel to a shaved asphalt surface, in order to mitigate dust. The site is totally graded and runoff is westerly to an existing detention pond in the southwest corner adjacent to the D&RG railroad right of way. Existing and proposed runoffs are computed contrasting the two pavement types and the detention pond is analyzed in accordance with its intended use as a full spectrum extended detention basin.

Basin A consists of the total All About Outdoor Storage property and sheet flows to the westerly boundary where the historic runoff of 15.9 cfs / 31.8 cfs (5-year / 100- year runoffs), increases to 22.7 cfs / 49.9 cfs. The historic gravel surface of this site is analyzed to represent total shaved asphaltic pavement, rolled and compacted in place over the entire property, including the entrance roadway. This runoff will sheet flow in the historic manner into the equipment storage portion of the site. No change in grading will be required, nor will drainage structures of any sort be required.

Basis B consists of the majority of the equipment storage portion of the property, and is anticipated to develop in similar manor to Basin A, consisting of a native gravel surface. It now has numerous pieces of

construction equipment in storage but will be configured for vehicle storage similar to that in Basin A. An existing metal building constructed in 1999 will remain in place. The total runoff will sheet flow to the existing detention pond in the southwest corner of the site. The combined historic runoff at the pond site of 19.1 cfs / 41.5 cfs will be increased to 22.4 cfs / 49.6 cfs, based on an anticipated total impervious ratio of 70%. No additional drainage provisions will be required other than normal maintenance of existing facilities.

The existing detention pond was originally constructed in 1986 as a detention basin for peak flow mitigation, along with those of similar structures on the two adjacent northerly lots. No design details are on file. For the required full spectrum pond a water quality capture volume (WQCV) of 0.238 Acre Feet (AF) would be required, along with a 100-year detention of 2.11 AF and other required volumes as shown on the enclosed Stage-storage builder computation sheet. Based on the as-built topography shown on the enclosed drainage plan, the pond extends to a total depth of over four feet to an existing spillway in the northwest corner of the pond. The total storage in the pond to the spillway is 0.155 acre feet, with 0.559 acre feet available to the top of the embankment. There are two 8-inch drains stubbed into the pond, exiting into a 5 foot diameter vertical RCP outlet works, with an 8- inch PVC outlet works, discharging onto the owner's property to the south. As shown on the computation sheet, this vertical outlet works and outfall pipe cannot accommodate the total 100-year runoff. The 8-inch PVC outlet pipe would require replacement by a 27" HDPE to fully contain the 100-year runoff.

The existing pond, however, shows no sign of erosion at the spillway or along the embankment, and there is no sign that the outlet pipe has ever carried runoff. It apparently has functioned adequately since its construction in 1986, giving it a current history of nearly 33 years adequate service. Because of this, an infiltration test was taken by Vivid geotechnical, the results of which are enclosed. The anticipated infiltration values are incorporated into the design sheets.

In order to contain the required WQCV, the pond invert is lowered one foot and enlarged to the point that the WQCV level roughly corresponds to the top of the 60" riser. The pond above this level is further enlarged to contain the 100-year detention. The inflow hydrographs were computed and routed through the pond as shown on the enclosed detention and infiltration design data sheets. The 100 year outflow is reduced to 37 cfs at a depth of 3.14 feet above pond bottom. Just above that level, a spillway is provided in the form of a trapezoidal channel on a 3:1 slope to pass the complete 100-year inflow as required, in case the outlet is totally plugged.

The outfall of the outlet pipe is within a small triangular portion of the boundary of this parcel as shown on the drainage plan. A channel runs southerly from there through a dense willow patch and outside the railroad right of way to the Teachout Creek channel that crosses the railroad into Monument Creek as shown on the enclosed FEMA map. Computations sheets are enclosed showing that the channel is stable through the willow thicket and needs no improvement.

The proposed grades shown on the drainage plan will provide adequate construction vehicular access to the pond for maintenance.

Basin "C" consists of an area adjacent to the D&RG right of way that was constructed to provide a dike routing the runoff into the pond, and is a range land type cover. The runoff is 0.1cfs /0.5cfs into the right of way

8. FOUR STEP PROCESS

The following process has been followed to minimize adverse impacts of urbanization

A. Runoff Reduction: The scope of the development has been minimized consistent with zoning requirements to present the minimum footprint in providing a commercial development. The pavements

Unresolved. The subheadings does not match Appendix I Section I.7.2.

Step 1 Employ Reduction Practices

Step 2 Stabilize Drainageways

Step 3 Provide Water Quality Capture Volume (WQCV)

Step 4 Consider Need for Industrial and Commercial BMPs

chosen create a minimum of runoff consistent with the requirement amount of protection. The undisturbed portions are to be landscaped to increase the pervious percent.

B. Treat and Slowly Release: The above described EDB is to be provided to provide water quality treatment and a reduced rate of discharge from the development as specified by County regulations. That portion to be graded at this time is below one acre. The two year storm will be totally contained within the detention pond and released into the underlying soil cover via a highly pervious native soil. Runoffs in excess of that value will be cycled through the pond to the maximum extent possible.

C. Channel Stabilizing: The site will be graded to route the runoff over improved installations to provide channel stabilizing in the natural erosive material over the site. Improvements above those shown on the approved plans will be made on an as-needed basis. Discharge from the site will be into a stable channel, being the historic discharge location. An analysis of this channel is included in the computations. There will be no adverse affect on downstream developments as a result of this subdivision

D. Source Controls: This is a commercial RV storage site, so source control problems will be a minimum. During construction, standard site specific state of the art BMP's will be employed to minimize and mitigate erosive problems.

9. COST ESTIMATE:

All items are private.

Item No.	Description	Quantity	Unit Cost	Cost
1	Pond Excavation	1708 CY	\$ 5.00	\$ 8540.00
2	Pond Embankment	186 CY	10.00	1860.00
3	Modify riser pipe	LS	300.00	300.00
4	27" HDPE	38 LF	20	760.00
Subtotal Construction Cost				\$ 11460.00
Engineering		10%		1146.00
Total Estimated Cost				\$ 12606.50

9. FEES:

Fees are not applicable

10. SUMMARY

The "All About Outdoor Storage" site is a 12.090 acre commercial RV storage site. The front (east) 7.002 acre portion is now in use for that purpose, and the rear remainder is vacant storage except for the existing detention pond in the Southwest corner. The proposed drainage facilities will adequately convey, detain and outfall runoff from the site to existing sufficient downstream facilities. These facilities are designed so that the total site may be used for RV storage without further revision to the drainage plan and facilities. Site runoff and storm drain and appurtenances will not adversely affect the downstream and surrounding developments.

The drainage analysis has been prepared in accordance with the current City of Colorado Springs and El Paso County Drainage Criteria Manual. Supporting information and calculations are included in this report.

References

1. City/ County Drainage Criteria Manuel, Volumes 1 and 2, May, 2014
2. El Paso County Engineering Criteria Manual.

[illegible]

3/16

Stormwater Detention and Infiltration Design Data Sheet

Workbook Protected

Worksheet Protected

Stormwater Facility Name: 16140 Old Denver Road, All About Outdoor Storage, El Paso County

Replace with UD-Detention. Pond design calculation will be reviewed on the resubmittal. Unresolved.

P

Location for 1-in Rainfall Depths (use dropdown):

User Input

WQCV Treatment Method = Extended Detention

Remove the SDI Worksheet from the drainage report and upload in the dedicated SDI Worksheet slot in the electronic submittal.



Unresolved

After completing and printing this worksheet to a pdf, go to:
<https://maperture.digitaldataservices.com/gvh/?viewer=cswdif>
 create a new stormwater facility, and
 attach the pdf of this worksheet to that record.

Routed Hydrograph Results

	WQCV	2 Year	5 Year	10 Year	50 Year	100 Year	
Design Storm Return Period =	0.53	1.19	1.50	1.75	2.25	2.52	in
One-Hour Rainfall Depth =	0.238	0.684	0.975	1.216	1.802	2.111	acre-ft
Calculated Runoff Volume =							acre-ft
OPTIONAL Override Runoff Volume =							hours
Inflow Hydrograph Volume =	0.238	0.683	0.974	1.216	1.802	2.110	hours
Time to Drain 97% of Inflow Volume =	7.4	5.8	5.1	5.0	4.4	4.3	WARNING!
Time to Drain 99% of Inflow Volume =	8.2	7.5	7.4	7.5	7.7	7.8	acres
Maximum Ponding Depth =	1.35	3.19	4.39	5.39	7.88	9.26	acre-ft
Maximum Poned Area =	0.091	0.155	0.181	0.181	0.181	0.181	
Maximum Volume Stored =	0.086	0.321	0.495	0.495	0.495	0.495	

Stormwater Detention and Infiltration Design Data Sheet



5/11

Copyright Protected

10-23-19



6786.0

-Mar
Bd 14

WDE = 8297
sm, Design Data 74860 = 8284

GA

Stormwater Detention and Infiltration Design Data Sheet



17
4958

HISTORIC POND

DETENTION

DECAINS 10/23/19

7/11

EXISTING ROAD STORAGE CURVE

	WSELE	X-SF	V-CF	INFILTRATION CFS
Loeef	6781.78	-0-	0	-0-
	82	2203.3	251.2	0.084
	83	5169.6	3726.4	0.190
LT	84	6266.5	5718.1	0.230
5/6 @ 84.75	85	7271.9	6769.2	0.267
Top	6786	8518.2	7895.0	0.312

INFILTRATION


SEE DIVD REPORT 4/24/19

$$INF = 48.3 \text{ CM/AR}$$

$$\div 30.48006 = 1.5846 \text{ "/AR}$$

$$= 0.00036682 \text{ FT/SEC}$$

OUTLET CAPACITY



$$Q = 3.1 L h^{3/2} \quad L = 15.71'$$

$$= 48.69 h^{3/2}$$

$$A = 0.3491$$

BL70
DOWNED

38.13 LF 8" RCP

$$\leq 0.948$$

Stage	WSELE	60" RCP h	Q	h:	8" POC V	Q	Q out CFS Total Q + INF
0	81.78	0	0	0	0	0	0.08
0.22	82	0	0	0	0	0	0.173
1.06	82.84	0	0	0	0	0	
1.22	83.0	0.16	3.12	2.26	10.37	3.62	3.31
2.22	84.0	1.16	60.83	3.26	12.45	4.35	4.58
3.22	85.0	2.16	194.6	4.26	14.24	4.97	5.24
4.22	86.0	3.16	273.5	5.26	15.82	5.52	5.84

CURVE No 50 P 1 & 7
Press A+B

$$A = 11.55 \text{ AC}$$

$$L = 100 + 650 + 330 = 1130' \quad H = 30'$$

$$\leq 2.6906$$

$$16.80 \text{ AC @ } 2008$$

$$+ 466 \text{ AC @ } 4008$$

$$= 1155 \text{ AC @ } 6480$$


ALL ABOUT OUTDOOR ST
17-4958

PROPOSED POND
AREA CAPACITY

QAW

10/23/19
1/10/18

8/11




$$* Q = 3.1 L h^{3/2} \quad L = 12^{57}$$

$$= 38.567 h^{3/2}$$

Use $Q_{\text{run}} + \text{Infiltration}$

STAGE	WS ELEV	60" RCP h	Q	27" RCP hi	V	Q
0.00	81.00 T_{in}		0			0
1.84			0			0
2.00	83.00	0.16	2.49	0.68	5.69	22.63
2.50	83.50	0.66	20.89	1.18	7.50	29.80
3.00	84.00	1.16	40.68	1.68	8.94	35.56
3.50	84.50	1.66	63.34	2.18	10.19	40.51
4.00	85.00	2.16	123.70	2.68	11.30	44.92
4.50	85.50	2.66	169.05	3.18	12.30	48.93
5.00	86.00 T_{out}	3.16	218.89	3.68	13.24	52.63



$$Q_{\text{100}} = 49.6 \text{ CFS } (Q_{\text{100}} \text{ In}) \quad FR = 1 @ dc = \frac{V}{\sqrt{g y}}$$

$$dc + \frac{V^2}{2g} = 0.9 \quad y = A/T$$

dc	A	T	y	$V^2/2g$	E
10	900	1200	0.75	0.48	1.48
15	1575	1500	1.05	0.16	1.66
18	2052	1600	1.28	0.09	1.89
19	2223	1740	1.23	0.08	1.93
0.45	20.96	60	0.35	0.09	0.44
0.41	23.87	59.46	0.40	0.06	0.47

$$V_{\text{se B}} = 57 \quad D = 0.50 \quad \text{top} = 60$$

$$\text{top Dike} = 84.14 + 0.47 + 2 = 86.61$$

17.4958

ALL ABOUT OUTDOOR STORAGE
DATE ALL CALCULATED STA 0+56.18

9/11

Worksheet for Irregular Section - 1**Project Description**

Flow Element: Irregular Section
 Friction Method: Manning Formula
 Solve For: Normal Depth

Input Data

Channel Slope: 0.02400 ft/ft
 Discharge: 37.00 ft³/s

Options

Current Roughness Weighted Meth: ImprovedLotters
 Open Channel Weighted Roughnes: ImprovedLotters
 Closed Channel Weighted Roughne: Hortons

Results

Roughness Coefficient: 0.100
 Water Surface Elevation: 78.16 ft
 Elevation Range: 76.69 to 78.62 ft
 Flow Area: 22.33 ft²
 Wetted Perimeter: 36.58 ft
 Top Width: 36.41 ft
 Normal Depth: 1.47 ft
 Critical Depth: 0.98 ft
 Critical Slope: 0.18613 ft/ft
 Velocity: 1.66 ft/s
 Velocity Head: 0.04 ft
 Specific Energy: 1.51 ft
 Froude Number: 0.37
 Flow Type: Subcritical

Segment Roughness

Start Station	End Station	Roughness Coefficient
(-0+22, 78.62)	(0+32, 78.42)	0.100

Section Geometry

Station	Elevation
-0+22	78.62
0+08	77.78

Discuss and analyze from the pond outfall and emergency spillway to the suitable outfall. See ECM Section 3.2.4 for suitable outfall location definition.

Unresolved. This will be reviewed once the UD-Detention worksheet has been submitted. Release rate might be different between the UD-Detention and this calculation.

Worksheet for Irregular Section - 1

Station	Elevation
0+22	76.69
0+32	78.42

11 / 11


17-4958 All About OS pond outfall section
Cross Section for Irregular Section - 1

Project Description

Flow Element: Irregular Section
Friction Method: Manning Formula
Solve For: Normal Depth

Section Data

Roughness Coefficient: 0.100
Channel Slope: 0.02400 ft/ft
Normal Depth: 1.47 ft
Elevation Range: 76.69 to 78.62 ft
Discharge: 37.00 ft³/s




V: 1
H: 1

National Flood Hazard Layer FIRMette



Legend

SEE FIS REPORT FOR DETAILED LEGEND AND INDEX MAP FOR FIRM PANEL LAYOUT




The pin displayed on the map is an approximate point selected by the user and does not represent an authoritative property location.

This map complies with FEMA's standards for the use of digital flood maps if it is not valid as described below. The basemap shown complies with FEMA's basemap accuracy standards

The flood hazard information is derived directly from the authoritative NFHL web services provided by FEMA. This map was exported on 10/24/2019 at 11:58:09 AM and does not reflect changes or amendments subsequent to this date and time. The NFHL and effective information may change or become superseded by new data over time.

This map image is valid if the one or more of the following map elements do not appear: basemap imagery, flood zone labels, legend, scale bar, map creation date, community identifiers, FIRM panel number, and FIRM effective date. Map images for unmapped and unmodernized areas cannot be used for regulatory purposes.

104°51'24.51"W




USGS The National Map: Orthoimagery, Data refreshed April, 2019.

39°34'3.61"N

1:6,000

Feet

0 250 500 1,000 1,500 2,000



OLIVER E. WATTS
CONSULTING ENGINEER, INC.
COLORADO SPRINGS

ALL ABOUT OUTDOOR STORAGE
SCS SOILS MAP
1"=2000'

TABLE 16.--SOIL AND WATER FEATURES--Continued

Soil name and map symbol	Hydro-logic group	Flooding			Bedrock		Potential frost action
		Frequency	Duration	Months	Depth	Hardness	
					In		
Manvel: 50-----	C	None-----	---	---	>60	---	High.
Manzanola: 51, 52, 53-----	C	None to rare	---	---	>60	---	Moderate.
Midway: 54-----	D	None-----	---	---	10-20	Rippable	Moderate.
Nederland: 55-----	B	None-----	---	---	>60	---	Moderate.
Nelson: 156: Nelson part----	B	None-----	---	---	20-40	Rippable	Low.
Tassel part----	D	None-----	---	---	10-20	Rippable	Low.
Neville: 57-----	B	None-----	---	---	>60	---	High.
158: Neville part----	B	None-----	---	---	>60	---	High.
Rednun part----	C	None-----	---	---	>60	---	Moderate.
Nunn: 59-----	C	None-----	---	---	>60	---	Moderate.
Olney: 60, 61-----	B	None-----	---	---	>60	---	Moderate.
162: Olney part----	B	None-----	---	---	>60	---	Moderate.
Vona part----	B	None-----	---	---	>60	---	Moderate.
Paunsaugunt: 163: Paunsaugunt part----	D	None-----	---	---	10-20	Hard	Moderate.
Rock outcrop part----	D	---	---	---	---	---	---
Penrose: 164: Penrose part----	D	None-----	---	---	10-20	Rippable	Low.
Manvel part----	C	None-----	---	---	>60	---	High.
Perrypark: 65-----	B	None-----	---	---	>60	---	Moderate.
Peyton: 66, 67-----	B	None-----	---	---	>60	---	Moderate.
168, 169: Peyton part----	B	None-----	---	---	>60	---	Moderate.
Pring part----	B	None-----	---	---	>60	---	Moderate.
Pits, gravel: 70-----	A	---	---	---	---	---	---
Pring: 71, 72-----	B	None-----	---	---	>60	---	Moderate.
Razor: 73, 74-----	C	None-----	---	---	20-40	Rippable	Moderate.

See footnote at end of table.

Table 6-6. Runoff Coefficients for Rational Method
(Source: UDFCD 2001)

Land Use or Surface Characteristics	Percent Impervious	Runoff Coefficients											
		2-year		5-year		10-year		25-year		50-year		100-year	
		HSG A&B	HSG C&D	HSG A&B	HSG C&D	HSG A&B	HSG C&D	HSG A&B	HSG C&D	HSG A&B	HSG C&D	HSG A&B	HSG C&D
Business													
Commercial Areas	95	0.79	0.80	0.81	0.82	0.83	0.84	0.85	0.87	0.87	0.88	0.88	0.89
Neighborhood Areas	70	0.45	0.49	0.49	0.53	0.53	0.57	0.58	0.62	0.60	0.65	0.62	0.68
Residential													
1/8 Acre or less	65	0.41	0.45	0.45	0.49	0.49	0.54	0.54	0.59	0.57	0.62	0.59	0.65
1/4 Acre	40	0.23	0.28	0.30	0.35	0.36	0.42	0.42	0.50	0.46	0.54	0.50	0.58
1/3 Acre	30	0.18	0.22	0.25	0.30	0.32	0.38	0.39	0.47	0.43	0.52	0.47	0.57
1/2 Acre	25	0.15	0.20	0.22	0.28	0.30	0.36	0.37	0.46	0.41	0.51	0.46	0.56
1 Acre	20	0.12	0.17	0.20	0.26	0.27	0.34	0.35	0.44	0.40	0.50	0.44	0.55
Industrial													
Light Areas	80	0.57	0.60	0.59	0.63	0.63	0.66	0.66	0.70	0.68	0.72	0.70	0.74
Heavy Areas	90	0.71	0.73	0.73	0.75	0.75	0.77	0.78	0.80	0.80	0.82	0.81	0.83
Parks and Cemeteries													
Parks	7	0.05	0.09	0.12	0.19	0.20	0.29	0.30	0.40	0.34	0.46	0.39	0.52
Playgrounds	13	0.07	0.13	0.16	0.23	0.24	0.31	0.32	0.42	0.37	0.48	0.41	0.54
Railroad Yard Areas	40	0.23	0.28	0.30	0.35	0.36	0.42	0.42	0.50	0.46	0.54	0.50	0.58
Undeveloped Areas													
Historic Flow Analysis-- Greenbelts, Agriculture	2	0.03	0.05	0.09	0.16	0.17	0.26	0.26	0.38	0.31	0.45	0.36	0.51
Pasture/Meadow	0	0.02	0.04	0.08	0.15	0.15	0.25	0.25	0.37	0.30	0.44	0.35	0.50
Forest	0	0.02	0.04	0.08	0.15	0.15	0.25	0.25	0.37	0.30	0.44	0.35	0.50
Exposed Rock	100	0.89	0.89	0.90	0.90	0.92	0.92	0.94	0.94	0.95	0.95	0.96	0.96
Offsite Flow Analysis (when landuse is undefined)	45	0.26	0.31	0.32	0.37	0.38	0.44	0.44	0.51	0.48	0.55	0.51	0.59
Streets													
Paved	100	0.89	0.89	0.90	0.90	0.92	0.92	0.94	0.94	0.95	0.95	0.96	0.96
Gravel	80	0.57	0.60	0.59	0.63	0.63	0.66	0.66	0.70	0.68	0.72	0.70	0.74
Drive and Walks													
Drive and Walks	100	0.89	0.89	0.90	0.90	0.92	0.92	0.94	0.94	0.95	0.95	0.96	0.96
Roofs	90	0.71	0.73	0.73	0.75	0.75	0.77	0.78	0.80	0.80	0.82	0.81	0.83
Lawns	0	0.02	0.04	0.08	0.15	0.15	0.25	0.25	0.37	0.30	0.44	0.35	0.50

3.2 Time of Concentration

One of the basic assumptions underlying the Rational Method is that runoff is a function of the average rainfall rate during the time required for water to flow from the hydraulically most remote part of the drainage area under consideration to the design point. However, in practice, the time of concentration can be an empirical value that results in reasonable and acceptable peak flow calculations.

For urban areas, the time of concentration (t_c) consists of an initial time or overland flow time (t_i) plus the travel time (t_f) in the storm sewer, paved gutter, roadside drainage ditch, or drainage channel. For non-urban areas, the time of concentration consists of an overland flow time (t_i) plus the time of travel in a concentrated form, such as a swale or drainageway. The travel portion (t_f) of the time of concentration can be estimated from the hydraulic properties of the storm sewer, gutter, swale, ditch, or drainageway. Initial time, on the other hand, will vary with surface slope, depression storage, surface cover, antecedent rainfall, and infiltration capacity of the soil, as well as distance of surface flow. The time of concentration is represented by Equation 6-7 for both urban and non-urban areas.

$$t_c = t_i + t_t \quad (\text{Eq. 6-7})$$

Where:

t_c = time of concentration (min)

t_i = overland (initial) flow time (min)

t_t = travel time in the ditch, channel, gutter, storm sewer, etc. (min)

3.2.1 Overland (Initial) Flow Time

The overland flow time, t_i , may be calculated using Equation 6-8.

$$t_i = \frac{0.395(1.1 - C_5)\sqrt{L}}{S^{0.33}} \quad (\text{Eq. 6-8})$$

Where:

t_i = overland (initial) flow time (min)

C_5 = runoff coefficient for 5-year frequency (see Table 6-6)

L = length of overland flow (300 ft maximum for non-urban land uses, 100 ft maximum for urban land uses)

S = average basin slope (ft/ft)

Note that in some urban watersheds, the overland flow time may be very small because flows quickly concentrate and channelize.

3.2.2 Travel Time

For catchments with overland and channelized flow, the time of concentration needs to be considered in combination with the travel time, t_t , which is calculated using the hydraulic properties of the swale, ditch, or channel. For preliminary work, the overland travel time, t_t , can be estimated with the help of Figure 6-25 or Equation 6-9 (Guo 1999).

$$V = C_v S_w^{0.5} \quad (\text{Eq. 6-9})$$

Where:

V = velocity (ft/s)

C_v = conveyance coefficient (from Table 6-7)

S_w = watercourse slope (ft/ft)

Table 6-7. Conveyance Coefficient, C_v

Type of Land Surface	C_v
Heavy meadow	2.5
Tillage/field	5
Riprap (not buried)*	6.5
Short pasture and lawns	7
Nearly bare ground	10
Grassed waterway	15
Paved areas and shallow paved swales	20

*For buried riprap, select C_v value based on type of vegetative cover.

The travel time is calculated by dividing the flow distance (in feet) by the velocity calculated using Equation 6-9 and converting units to minutes.

The time of concentration (t_c) is then the sum of the overland flow time (t_t) and the travel time (t_r) per Equation 6-7.

3.2.3 First Design Point Time of Concentration in Urban Catchments

Using this procedure, the time of concentration at the first design point (typically the first inlet in the system) in an urbanized catchment should not exceed the time of concentration calculated using Equation 6-10. The first design point is defined as the point where runoff first enters the storm sewer system.

$$t_c = \frac{L}{180} + 10 \quad (\text{Eq. 6-10})$$

Where:

t_c = maximum time of concentration at the first design point in an urban watershed (min)

L = waterway length (ft)

Equation 6-10 was developed using the rainfall-runoff data collected in the Denver region and, in essence, represents regional “calibration” of the Rational Method. Normally, Equation 6-10 will result in a lesser time of concentration at the first design point and will govern in an urbanized watershed. For subsequent design points, the time of concentration is calculated by accumulating the travel times in downstream drainageway reaches.


3.2.4 Minimum Time of Concentration

If the calculations result in a t_c of less than 10 minutes for undeveloped conditions, it is recommended that a minimum value of 10 minutes be used. The minimum t_c for urbanized areas is 5 minutes.

3.2.5 Post-Development Time of Concentration

As Equation 6-8 indicates, the time of concentration is a function of the 5-year runoff coefficient for a drainage basin. Typically, higher levels of imperviousness (higher 5-year runoff coefficients) correspond to shorter times of concentration, and lower levels of imperviousness correspond to longer times of

Figure 6-5. Colorado Springs Rainfall Intensity Duration Frequency



IDF Equations

$$I_{100} = -2.52 \ln(D) + 12.735$$

$$I_{50} = -2.25 \ln(D) + 11.375$$

$$I_{25} = -2.00 \ln(D) + 10.111$$

$$I_{10} = -1.75 \ln(D) + 8.847$$

$$I_5 = -1.50 \ln(D) + 7.583$$

$$I_2 = -1.19 \ln(D) + 6.035$$

Note: Values calculated by equations may not precisely duplicate values read from figure.

$$Q = \frac{0.463}{n} D^{8/3} S^{1/2}$$

$$Q = KS^{1/2}$$

DIAMETER - IN. -	AREA - FT ² -	D 8/3 - FT -	K			
			N=0.010	N=0.013	N=0.024	N=0.02
2	0.02182	0.008413	0.3895	---	---	---
4	0.08727	0.053420	2.4733	---	---	---
6	0.19630	0.157500	7.2922	5.609	---	---
8	0.34910	0.339200	15.7050	12.081	---	---
10	0.54540	0.615000	28.4745	21.903	---	---
12	0.78540	1.000000	46.3000	35.615	---	---
15	1.22720	1.813100	83.9465	64.574	---	---
18	1.76710	2.948300	136.5100	105.000	56.88	52.5
21	2.40530	4.447400	205.9100	158.400	85.80	79.2
24	3.14160	6.349600	293.9900	226.140	122.49	113.0
27	3.97610	8.692700	402.4700	309.590	167.70	154.7
30	4.90870	11.512600	533.0300	410.030	222.10	205.0
33	5.93960	14.844100	---	528.680	---	---
36	7.06860	18.720800	866.7700	666.700	361.20	333.3
39	8.29580	23.175100	---	825.400	---	---
42	9.62110	28.238900	---	1005.000	544.80	502.5
48	12.56640	40.317500	---	1436.000	777.80	718.0
54	15.90430	55.195000	---	1966.000	1065.00	983.0
60	19.63500	73.100400	---	2604.000	1410.00	1302.0
66	23.75830	94.254200	---	3357.000	1818.00	1678.0
72	28.27430	118.869400	---	4234.000	2293.00	2117.0
78	33.18310	147.152900	---	5241.000	2839.00	2620.0
84	38.48450	179.306000	---	6386.000	3459.00	3193.0
90	44.17860	215.524500	---	7676.000	4158.00	3838.0
96	50.26550	256.000000	---	9118.000	4939.00	4559.0
108	63.61730	350.466600	---	12480.000	6761.00	6140.0
120	78.53980	464.158900	---	16530.000	8954.00	8265.0

Oliver E. Watts
Consulting Engir
Colorado Springs



VIVID Engineering Group, Inc.

1053 Elkton Drive, Colorado Springs, CO 80907

April 24, 2019

Kelly McKoon
All About Outdoor Storage
16140 Old Denver Road, Monument, CO 80132
info@allaboutoutdoorstorage.com
levivankekerix@gmail.com

CC: Oliver E. Watts
Oliver E. Watts Consulting Engineer, Inc.
614 Elkton Drive, Colorado Springs, CO 80907
olliewatts@aol.com

Subject: Double-Ring Infiltration Test Results

Project: Proposed Detention Pond Facility, All About Outdoor Storage, 16140 Old Denver Road,
Monument, Colorado

Project No: D19-2-189

Dear Kelly:

Vivid Engineering Group, Inc. (VIVID) has performed a double-ring infiltration test in general accordance with ASTM D3385 for the proposed detention pond facility located at 16140 Old Denver Road, Monument, Colorado.

Our services consisted of performing a double-ring infiltration test within the existing detention pond area that is planned for expansion. This effort also included advancing a geotechnical boring to check for lateral drainage during the infiltration test, and obtaining a subgrade sample for soil gradation analysis testing. This letter transmits our results.

FIELD INVESTIGATION

On April 9, 2019, a test pit was excavated within the existing detention pond area by All About Outdoor Storage personnel to a depth of approximately 1.5 feet below the ground surface. This is the approximate depth of the bottom of the proposed detention pond. The double-ring infiltration test was performed on April 9, 2019 within the excavated test location. Photographs depicting the test pit area are presented in Appendix C to letter.

At the completion of the double-ring infiltration test, a boring (boring B-1) was performed within the test pit for the purpose of checking for lateral drainage that may have occurred during the test. The boring was advanced to a depth of approximately 5.5 feet below the existing ground surface using a 3-inch diameter hand auger. A bulk sample was taken of the cuttings from the boring.

Appendix A to this letter includes a boring log describing the subsurface conditions encountered in the profile boring.

SUBGRADE CONDITIONS

From the ground surface down, the general subsurface profile encountered in the boring consisted of olive-yellow poorly graded sand. Neither bedrock nor groundwater were encountered in the profile boring. The boring log in Appendix A should be reviewed for a more detailed description of the subsurface conditions encountered.

LABORATORY TESTING

A sample of the subgrade materials were taken from the profile boring. Geotechnical laboratory testing was conducted and included soil gradation. The poorly graded sand materials were judged to be non-plastic and have only 4 percent fines (percent passing the No. 200 sieve). This type of clean sand material generally exhibits high permeability. Results of the geotechnical laboratory testing are presented in Appendix B.

DOUBLE-RING INFILTRATION TESTING

The average infiltration rate obtained at the test location was approximately **48.3 cm/hour**. Water was not observed moving laterally around the test location, based on the hand excavation of a shallow bore hole adjacent the double-ring infiltrometer test location.

The double-ring infiltration test results are indicative of the granular (sand) soil encountered on the site.

LIMITATIONS

This work was performed in a manner consistent with that level of care and skill ordinarily exercised by other members of VIVID's profession practicing in the same locality, under similar conditions and at the date the services are provided. Our conclusions and opinions are based on a limited number of observations and data. Data or conclusions presented herein apply to the specific test pit and test locations only. It is likely that subsurface conditions will vary somewhat beyond the locations investigated. VIVID makes no other representation, guarantee, or warranty, express or implied, regarding the services, communication (oral or written), report, opinion, or instrument of service provided.

CLOSING

We appreciate this opportunity to serve you, and we look forward to working with you again. Should you have any questions concerning this report, please contact Bill Barreire at 719.491.2292 or wbarreire@vivideg.com, or Benjamin Moore at 720.461.3692 or bmoore@vivideg.com.

Sincerely,



William (Bill) J. Barreire, PE
Senior Geotechnical Engineer



Benjamin Moore, EIT
Staff Engineer

ATTACHMENTS:

FIGURE 1 – VICINITY MAP

FIGURE 2 – EXPLORATION LOCATION PLAN

APPENDIX A – LOG OF EXPLORATORY BORING

APPENDIX B – LABORATORY TEST RESULTS


APPENDIX C – SITE PHOTOS

APPENDIX D – IMPORTANT INFORMATION ABOUT THIS GEOTECHNICAL ENGINEERING REPORT

Figures




Not to Scale. Base image obtained from www.google.com/maps, 2019

	Project No: D19-2-189	VICINITY MAP	Figure 1
	Date: April 23, 2019		
	Drawn by: BM	Proposed Detention Pond Facility All About Outdoor Storage Monument, Colorado	
	Reviewed by:WJB		



LEGEND

 = APPROXIMATE LOCATION OF
DOUBLE-RING INFILTRATION TEST
AND EXPLORATORY PROFILE BORING



Not to Scale. Base image obtained from Google Earth Pro on June 9, 2017.



VIVID Engineering Group, Inc.
1053 Elkton Drive
Colorado Springs, Colorado 80907
719.896.4356

Project No: D19-2-189
Date: April 23, 2019
Drawn by: BM
Reviewed by: WJB

EXPLORATION LOCATION PLAN

Proposed Detention Pond Facility
All About Outdoor Storage
Monument, Colorado

Figure

Appendix A
Logs of Exploratory Borings



VIVID Engineering Group, Inc.
1053 Elkton Drive
Colorado Springs, Colorado 80907
Telephone: 719-896-4356
Fax: 719-896-4357

BORING NUMBER B-1

PAGE 1 OF 1

CLIENT	All About Outdoor Storage	PROJECT NAME	Proposed Detention Pond Facility
PROJECT NUMBER	D19-2-189	PROJECT LOCATION	Monument, CO
DATE STARTED	4/9/19	COMPLETED	4/9/19
DRILLING CONTRACTOR	VIVID Engineering Group (Hand Auger)	GROUND ELEVATION	
DRILLING METHOD	3" Hand Auger	HOLE SIZE	3 inches
LOGGED BY	Ben Moore	CHECKED BY	W. Barreire
NOTES			
		GROUND WATER LEVELS:	
		AT TIME OF DRILLING	---
		AT END OF DRILLING	---
		AFTER DRILLING	---

GENERAL BH / TP / WELL - GINT STD US LAB.GDT - 4/24/19 15:09 - F:\VIVID PROJECTS\D19-2-189 - ALL ABOUT OUTDOOR STORAGE DETENTION POND_GEO16 - DRAFTING\D19-2-189.GPJ

DEPTH (ft)	SAMPLE TYPE NUMBER	TESTS	GRAPHIC LOG	MATERIAL DESCRIPTION
0.0				
2.5				
5.0	GB	Fines = 4.0%		
5.5				

Bottom of borehole at 5.5 feet.

Appendix B

Geotechnical Laboratory Test Results



VIVID Engineering Group, Inc.
1053 Elkton Drive
Colorado Springs, Colorado 80907
Telephone: 719-896-4356
Fax: 719-896-4357


GRAIN SIZE DISTRIBUTION

CLIENT All About Outdoor Storage

PROJECT NAME See B-1

PROJECT NUMBER D19-2-189

PROJECT LOCATION Monument, CO



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

BOREHOLE	DEPTH	Classification					LL	PL	PI	Cc	Cu
● B-1	1.5	POORLY GRADED SAND(SP)								0.73	10.69
BOREHOLE	DEPTH	D100	D60	D30	D10	%Gravel	%Sand	%Silt		%Clay	
● B-1	1.5	19	1.711	0.447	0.16	10.5	85.5	4.0			

GRAIN SIZE - GINT STD US LAB.GDT - 4/24/19 15:11 - F:\VIVID PROJECTS\D19-2-189_ALL ABOUT OUTDOOR STORAGE DETENTION POND_GEO16 - DRAFTING\D19-2-189.GPJ

Appendix C

Site Photos



TEST LOCATION



TEST LOCATION WITH INFILTROMETER



Project No: D19-2-189

Date: April 23, 2019

Drawn by: BM

Reviewed by: WJB

SITE PHOTOS


Proposed Detention Pond Facility
All About Outdoor Storage
Monument, Colorado

Figure

C-1



INFILTROMETER AND PROFILE BORE HOLE

	Project No: D19-2-189	SITE PHOTOS	Figure C-2
	Date: April 23, 2019		
	Drawn by: BM	Proposed Detention Pond Facility All About Outdoor Storage Monument, Colorado	
	Reviewed by: WJB		

Appendix D

Important Information About This Geotechnical Engineering Report

Important Information about This Geotechnical-Engineering Report

Subsurface problems are a principal cause of construction delays, cost overruns, claims, and disputes.

While you cannot eliminate all such risks, you can manage them. The following information is provided to help.

The Geoprofessional Business Association (GBA) has prepared this advisory to help you – assumedly a client representative – interpret and apply this geotechnical-engineering report as effectively as possible. In that way, clients can benefit from a lowered exposure to the subsurface problems that, for decades, have been a principal cause of construction delays, cost overruns, claims, and disputes. If you have questions or want more information about any of the issues discussed below, contact your GBA-member geotechnical engineer. Active involvement in the Geoprofessional Business Association exposes geotechnical engineers to a wide array of risk-confrontation techniques that can be of genuine benefit for everyone involved with a construction project.

Geotechnical-Engineering Services Are Performed for Specific Purposes, Persons, and Projects

Geotechnical engineers structure their services to meet the specific needs of their clients. A geotechnical-engineering study conducted for a given civil engineer will not likely meet the needs of a civil-works constructor or even a different civil engineer. Because each geotechnical-engineering study is unique, each geotechnical-engineering report is unique, prepared *solely* for the client. *Those who rely on a geotechnical-engineering report prepared for a different client can be seriously misled.* No one except authorized client representatives should rely on this geotechnical-engineering report without first conferring with the geotechnical engineer who prepared it. *And no one – not even you – should apply this report for any purpose or project except the one originally contemplated.*

Read this Report in Full

Costly problems have occurred because those relying on a geotechnical-engineering report did not read it *in its entirety*. Do not rely on an executive summary. Do not read selected elements only. *Read this report in full.*

You Need to Inform Your Geotechnical Engineer about Change

Your geotechnical engineer considered unique, project-specific factors when designing the study behind this report and developing the confirmation-dependent recommendations the report conveys. A few typical factors include:

- the client's goals, objectives, budget, schedule, and risk-management preferences;
- the general nature of the structure involved, its size, configuration, and performance criteria;
- the structure's location and orientation on the site; and
- other planned or existing site improvements, such as retaining walls, access roads, parking lots, and underground utilities.

Typical changes that could erode the reliability of this report include those that affect:

- the site's size or shape;
- the function of the proposed structure, as when it's changed from a parking garage to an office building, or from a light-industrial plant to a refrigerated warehouse;
- the elevation, configuration, location, orientation, or weight of the proposed structure;
- the composition of the design team; or
- project ownership.

As a general rule, *always* inform your geotechnical engineer of project changes – even minor ones – and request an assessment of their impact. *The geotechnical engineer who prepared this report cannot accept responsibility or liability for problems that arise because the geotechnical engineer was not informed about developments the engineer otherwise would have considered.*

This Report May Not Be Reliable

Do not rely on this report if your geotechnical engineer prepared it:

- for a different client;
- for a different project;
- for a different site (that may or may not include all or a portion of the original site); or
- before important events occurred at the site or adjacent to it; e.g., man-made events like construction or environmental remediation, or natural events like floods, droughts, earthquakes, or groundwater fluctuations.

Note, too, that it could be unwise to rely on a geotechnical-engineering report whose reliability may have been affected by the passage of time, because of factors like changed subsurface conditions; new or modified codes, standards, or regulations; or new techniques or tools. *If your geotechnical engineer has not indicated an "apply-by" date on the report, ask what it should be, and, in general, if you are the least bit uncertain about the continued reliability of this report, contact your geotechnical engineer before applying it.* A minor amount of additional testing or analysis – if any is required at all – could prevent major problems.

Most of the "Findings" Related in This Report Are Professional Opinions

Before construction begins, geotechnical engineers explore a site's subsurface through various sampling and testing procedures. *Geotechnical engineers can observe actual subsurface conditions only at those specific locations where sampling and testing were performed.* The data derived from that sampling and testing were reviewed by your geotechnical engineer, who then applied professional judgment to form opinions about subsurface conditions throughout the site. Actual sitewide-subsurface conditions may differ – maybe significantly – from those indicated in this report. Confront that risk by retaining your geotechnical engineer to serve on the design team from project start to project finish, so the individual can provide informed guidance quickly, whenever needed.

This Report's Recommendations Are Confirmation-Dependent

The recommendations included in this report – including any options or alternatives – are confirmation-dependent. In other words, *they are not final*, because the geotechnical engineer who developed them relied heavily on judgment and opinion to do so. Your geotechnical engineer can finalize the recommendations *only after observing actual subsurface conditions* revealed during construction. If through observation your geotechnical engineer confirms that the conditions assumed to exist actually do exist, the recommendations can be relied upon, assuming no other changes have occurred. *The geotechnical engineer who prepared this report cannot assume responsibility or liability for confirmation-dependent recommendations if you fail to retain that engineer to perform construction observation.*

This Report Could Be Misinterpreted

Other design professionals' misinterpretation of geotechnical-engineering reports has resulted in costly problems. Confront that risk by having your geotechnical engineer serve as a full-time member of the design team, to:

- confer with other design-team members,
- help develop specifications,
- review pertinent elements of other design professionals' plans and specifications, and
- be on hand quickly whenever geotechnical-engineering guidance is needed.

You should also confront the risk of constructors misinterpreting this report. Do so by retaining your geotechnical engineer to participate in prebid and preconstruction conferences and to perform construction observation.

Give Constructors a Complete Report and Guidance

Some owners and design professionals mistakenly believe they can shift unanticipated-subsurface-conditions liability to constructors by limiting the information they provide for bid preparation. To help prevent the costly, contentious problems this practice has caused, include the complete geotechnical-engineering report, along with any attachments or appendices, with your contract documents, *but be certain to note conspicuously that you've included the material for informational purposes only*. To avoid misunderstanding, you may also want to note that "informational purposes" means constructors have no right to rely on the interpretations, opinions, conclusions, or recommendations in the report, but they may rely on the factual data relative to the specific times, locations, and depths/elevations referenced. Be certain that constructors know they may learn about specific project requirements, including options selected from the report, *only* from the design drawings and specifications. Remind constructors that they may

perform their own studies if they want to, and *be sure to allow enough time* to permit them to do so. Only then might you be in a position to give constructors the information available to you, while requiring them to at least share some of the financial responsibilities stemming from unanticipated conditions. Conducting prebid and preconstruction conferences can also be valuable in this respect.

Read Responsibility Provisions Closely

Some client representatives, design professionals, and constructors do not realize that geotechnical engineering is far less exact than other engineering disciplines. That lack of understanding has nurtured unrealistic expectations that have resulted in disappointments, delays, cost overruns, claims, and disputes. To confront that risk, geotechnical engineers commonly include explanatory provisions in their reports. Sometimes labeled "limitations," many of these provisions indicate where geotechnical engineers' responsibilities begin and end, to help others recognize their own responsibilities and risks. *Read these provisions closely*. Ask questions. Your geotechnical engineer should respond fully and frankly.

Geoenvironmental Concerns Are Not Covered

The personnel, equipment, and techniques used to perform an environmental study – e.g., a "phase-one" or "phase-two" environmental site assessment – differ significantly from those used to perform a geotechnical-engineering study. For that reason, a geotechnical-engineering report does not usually relate any environmental findings, conclusions, or recommendations; e.g., about the likelihood of encountering underground storage tanks or regulated contaminants. *Unanticipated subsurface environmental problems have led to project failures*. If you have not yet obtained your own environmental information, ask your geotechnical consultant for risk-management guidance. As a general rule, *do not rely on an environmental report prepared for a different client, site, or project, or that is more than six months old*.

Obtain Professional Assistance to Deal with Moisture Infiltration and Mold



While your geotechnical engineer may have addressed groundwater, water infiltration, or similar issues in this report, none of the engineer's services were designed, conducted, or intended to prevent uncontrolled migration of moisture – including water vapor – from the soil through building slabs and walls and into the building interior, where it can cause mold growth and material-performance deficiencies. Accordingly, *proper implementation of the geotechnical engineer's recommendations will not of itself be sufficient to prevent moisture infiltration*. Confront the risk of moisture infiltration by including building-envelope or mold specialists on the design team. *Geotechnical engineers are not building-envelope or mold specialists*.



GEOPROFESSIONAL
BUSINESS
ASSOCIATION

Telephone: 301/565-2733

e-mail: info@geoprofessional.org www.geoprofessional.org



WQCV

