



# Final Drainage Report

## High Forest Estates Subdivision Filing No. 1

Project No. 61188

PCD File No.

Add  
"VR2311"

May 3, 2023

Copyright © M.V.E., Inc., 2023

# Final Drainage Report

For

## High Forest Estates Subdivision Filing No. 1

**Project No. 61188**

**PCD File No. \_\_\_\_\_**

**May 3, 2023**

Prepared for

**Paula Donohoo, Mardelle Frazier and Brian Frazier**

8855 Walker Road

Colorado Springs, CO 80908

(213) 792-7163

Prepared by

**M.V.E., Inc.**

1903 Lelaray Street, Suite 200

Colorado Springs, CO 80909

(719) 635-5736

# Statements and Acknowledgments

## Engineer's Statement

The attached drainage plan and report were prepared under my direction and supervision and are correct to the best of my knowledge and belief. Said drainage report has been prepared according to the criteria established by the County for drainage reports and said report is in conformity with the applicable master plan of the drainage basin. I accept responsibility for any liability caused by any negligent acts, errors or omissions on my part in preparing this report.

---

David R. Gorman, P.E.

Colorado No. 31672

\_\_\_\_\_ Date

For and on Behalf of M.V.E., Inc.

## Developer's Statement

I, the owner/developer have read and will comply with all of the requirements specified in this drainage report and plan.

---

Paula Donohoo

8855 Walker Road

Colorado Springs, CO 80908

\_\_\_\_\_ Date

## El Paso County

Filed in accordance with the requirements of the Drainage Criteria Manual, Volumes 1 and 2, El Paso County Engineering Criteria Manual and Land Development Code as amended.

---

Joshua Palmer, P.E.

County Engineer / ECM Administrator

\_\_\_\_\_ Date

Conditions:

# Contents

<b>Statements and Acknowledgments</b> .....	i
<b>1. General Location and Description</b> .....	<b>1</b>
1.1. Location.....	1
1.2. Description of Property.....	1
<b>2. Drainage Basins and Sub-Basins</b> .....	<b>2</b>
2.1. Major Basin Description.....	2
2.2. Sub-Basin Description.....	3
2.2.1. Existing Drainage Patterns (Offsite).....	3
2.2.2. Existing Drainage Patterns (Onsite).....	3
<b>3. Drainage Design Criteria</b> .....	<b>4</b>
3.1. Development Criteria Reference.....	4
3.2. Previous Drainage Studies.....	4
3.3. Hydrologic Criteria.....	4
<b>4. Drainage Facility Design</b> .....	<b>5</b>
4.1. General Concept.....	5
4.2. Specific Details.....	5
4.2.1. Existing Main Stem Drainageway Hydrologic Conditions.....	5
4.2.2. Existing On-Site Hydrologic Conditions.....	6
4.2.3. Proposed On-Site Hydrologic Conditions.....	7
4.2.4. Proposed Main Stem Drainageway Hydrologic and Hydraulic Conditions.....	9
4.2.5. Detention Facilities.....	10
4.2.6. Drainageway Hydraulic Analysis.....	10
4.3. Erosion Control.....	11
4.4. Four Step Process.....	11
<b>5. Drainage and Bridge Fees</b> .....	<b>12</b>
<b>6. Conclusion</b> .....	<b>12</b>
<b>References</b> .....	<b>ii</b>
<b>7. Appendices</b> .....	<b>iii</b>
A. General Maps and Supporting Data.....	iii
B. Hydrologic Calculations.....	iv
C. Hydraulic Calculations.....	v
D. Report Maps.....	vi

# Final Drainage Report

The purpose of this Final Drainage Report is to identify drainage patterns and quantities within and affecting the proposed High Forest Estates Subdivision Filing No. 1 site. The development project is a large-lot rural residential subdivision zoned RR-5. The report will examine existing and proposed developed drainage conditions of the site and contributing off-site areas. The report and included maps present results of hydrologic and drainage facilities analyses. The report will discuss any recommended drainage improvements to the site and identify drainage requirements relative to the proposed project. This report has been prepared and submitted in accordance with the requirements of the El Paso County development approval process. An Appendix is included with this report with pertinent calculations and graphs used in the drainage analyses and design.

## 1. General Location and Description

### 1.1. Location

The proposed High Forest Estates Subdivision Filing No. 1 site is located within the southwest one-quarter of Section 10, Township 11 South, Range 65 West of the 6th principal meridian in El Paso County, Colorado. The property consists of Lot 1, Block 7, Willow Springs Estates having El Paso County Tax Schedule No. 5110001009. The current address of the site is 8855 Walker Road, Colorado Springs. The eastern portion of the site currently contains a residence, outbuilding, well and septic systems, and a gravel drive in the northern portion of the site connected to Walker Road. The site is 13.81± acres in area and is zoned RR-5 (Residential Rural – 5 Acre).

The site is situated on the east side of Walker Road, north of Lot 1, Block 6, Willow Springs Estates (Zoned RR-5) with existing single-family residential development and Barn. The site is south of Lot 2, Block 7, Willow Springs Estates (Zoned RR-5) with existing single-family residential development. Walker Road, a public road with 60 ft right-of-way, is adjacent to the western edge of the site on the east and an unplatted 200-acre agricultural property (Zoned RR-5) on the west. Lot 3, Block 7, Willow Springs Estates (Zone RR-5) is east of the site with existing single-family residential development.

A **Vicinity Map** is included in the **Appendix**. The site is located within the East Cherry Creek Drainage Basin.

### 1.2. Description of Property

The High Forest Estates Subdivision Filing No. 1 site is 13.81± acres and is zoned RR-5 (Residential Rural (5 Acres)). Proposed High Forest Estates Subdivision Filing No. 1 will create a total of two (2) rural residential lots. Lot 1, on the west portion of the site, will be 5.00± acres. Lot 2 will be 8.80± acres and located on the eastern portion of the site. The site is covered with native prairie grasses and weeds in good condition having approximately 90% ground coverage with sparse trees and shrubs scattered.

Natural drainage routes exist on the site, located in the southeastern, southcentral, and northwestern portions. The aforementioned natural drainage routes on-site comprise a drainageway, crossing the site from southeast to northwest with a stock pond located in the west-central portion of the site where seasonal ponding of water occurs. The existing pond embankment contains a 12" Corrugated Metal Pipe (CMP) and 12" grated inlet that are intended to drain ponded water in the drainageway following minor storms. Due to the location and size of the outlet pipe, and the magnitude of a 100 year storm, the inlet and pipe are largely ineffectual in draining flows from the pond in the 100 year storm conditions and can be ignored for hydrologic or hydraulic purposes. When the pond reaches capacity, overflows exit the pond at the opening provided at the south side of the embankment and continue west in the drainageway.

The existing site topography varies throughout the site. The northeastern portion of the site slopes southwesterly with grades that range from 3% to 8% with regions that reach 16% along the edge of the existing drainageway. The southeastern portion of the site slopes towards the existing drainageway, with the northerly portion sloping south and the southerly portion sloping north. The western portion of the site slopes northwesterly towards the existing 60" double CMP located approximately 120 feet south of the northwestern corner of the site, with grades that range from 2% to 10% with areas of extreme slope along the existing drainageway that reach 60%.

According to the National Resource Conservation Service, there is one (1) soil type in the High Forest Estates Subdivision Filing No. 1 site. Peyton-Pring complex (map unit 68) makes up the entirety of the site. Both major components of this complex (typically 40% Peyton and 30% Pring) are typically Deep and Well Drained, with Medium surface runoff and a Moderate hazard of erosion. Permeability for the Peyton component is moderate and the permeability of the Pring component is rapid. A portion of the Soil Map and data tables from the National Cooperative Soil Survey and relevant Soil Descriptions from the Soil Survey of El Paso County Area, Colorado are included in the **Appendix**.<sup>1 2</sup>

The current Flood Insurance Study of the region includes Flood Insurance Rate Maps (FIRM), effective on December 7, 2018.<sup>3</sup> The proposed subdivision is included in the Community Panels Numbered 08041C0310G of the Flood Insurance Rate Maps for the El Paso County. No part of the site is shown to be included in a 100-year flood hazard area as determined by FEMA. A portion of the current FEMA Flood Insurance Rate Maps with the site delineated is included in the **Appendix**.

## 2. Drainage Basins and Sub-Basins

### 2.1. Major Basin Description

The site for the proposed High Forest Estates Subdivision Filing No. 1 is located in the unstudied East Cherry Creek Drainage Basin (CYCY0200). A portion of the El Paso County Drainage Basins Map is provided in the **Appendix**.

---

<sup>1</sup> WSS

<sup>2</sup> OSD

<sup>3</sup> FIRM

## 2.2. Sub-Basin Description

The existing drainage patterns of the High Forest Estates Subdivision Filing No. 1 site are described by five (5) on-site drainage basins. All of these basins are previously undisturbed or developed to a degree as described below. The **Drainage Map (Existing)** depicts the existing topographic mapping, drainage basin delineations, drainage patterns, existing drives, drainage facilities, and runoff quantities with a data table including drainage areas and flow rates is included in the **Appendix**.

### 2.2.1. Existing Drainage Patterns (Offsite)

The High Forest Estates Subdivision Filing No. 1 site receives drainage flows from approximately 1.5 square miles of area to the south and east of the site that enters from drainage routes along the southern and eastern edges of the site. There are also three off-site basins that deposit flows onto the site at the northern edge of the site at design points DP-OS4 and DP-OS5 and the southwestern corner of the site at design point DP-OS1.

### 2.2.2. Existing Drainage Patterns (Onsite)

Existing Sub-basin EX-A1, located in the southwestern portion of the site, contains portions of existing Table Rock Road, an undeveloped grassed area on-site, portions of the existing drainageway, and stock pond. Offsite flows enter sub-basin EX-A1 at Design Point OS1 (DP-OS1) from the south through an 18" CMP culvert under Table Rock Road and combine with flows exiting the stock pond spillway to drain into sub-basin EX-A5.

Existing Sub-basin EX-A2, located in the south central portion of the site, contains an undeveloped grassed area and portions of the aforementioned drainageway and stock pond. Offsite flows enter sub-basin EX-A2 at Design Point OS2 (DP-OS2) from the south and combine with the runoff from the sub-basin in the stock pond.

Existing Sub-basin EX-A3, located in the southeastern portion of the site, contains the existing single-family residence and associated sheds, portions of the existing gravel drive, and portions of the aforementioned drainage way. Offsite flows enter sub-basin EX-A3 at Design Point OS3 (DP-OS3) from the east and combine with flows from the sub-basin in the aforementioned drainageway to enter sub-basin EX-A4.

Existing Sub-basin EX-A4, located in the northeastern portion of the site, contains portions of the existing gravel drive, and portions of the aforementioned stock pond. Offsite flows enter sub-basin EX-A4 at Design Point OS4 (DP-OS4) from the east and combine with flows from the sub-basin in the stock pond.

Existing Sub-basin EX-A5, located in the northwestern portion of the site, contains portions of the existing gravel drive, portions of existing Walker Road, and portions of the aforementioned drainageway. Flows from sub-basin EX-A5 combine with flows entering the sub-basin from the south through the stock pond spillway and flow northerly towards the site outfall at Design Point 2 (DP2). Offsite flows enter sub-basin EX-A5 at Design Point OS5 (DP-OS5) from the north and flow through 36" CMP culverts under the private gravel road on site, and flow onsite for approximately 100'± before exiting the site at Design Point 2 (DP2).

Design Point 2 (DP2), located at the northwestern portion of the site as shown on the Drainage Map (Existing), is the site outfall. All flows from the site and exit the site into the western adjacent site through the two (2) 60" CMP culverts under Walker Road located at Design Point 2 (DP2).

Per ECM 3.2.4 developed flows have to exit at a suitable outfall. Revise to include in the narrative the condition of the culverts and whether they can handle additional flows. Provide an analysis of the culverts.

These flows continue east through adjacent properties and eventually enter East Cherry Creek approximately 2 miles downstream of the site outfall.

### **3. Drainage Design Criteria**

#### **3.1. Development Criteria Reference**

This Final Drainage Report for High Forest Estates Subdivision Filing No. 1 has been prepared according to the report guidelines presented in the latest edition of *El Paso County Drainage Criteria Manual* (DCM)<sup>4</sup>. The County has also adopted portions of the *City of Colorado Springs Drainage Criteria Manual* Volumes 1 and 2, especially concerning the calculation of rainfall runoff flow rates.<sup>5 6</sup> The hydrologic analysis is based on a collection of data from the DCM, the NRCS Web Soil Survey<sup>7</sup>, and existing topographic data by Polaris Surveying, Inc.

#### **3.2. Previous Drainage Studies**

East Cherry Creek (CYCY0200) is not a studied Drainage Basin. The plat submittal for Willow Springs Estates does not list drainage plans or reports. No previous drainage report was found to address flows relevant to the project site, and so none were used in the drainage design for this site.

#### **3.3. Hydrologic Criteria**

For the on-site and local sub-basins in this Final Drainage Report, the Rational Method as described in the Drainage Criteria Manual has been used for all Storm Runoff calculations, as the development and all sub-basins are less than 130 acres in area. “Colorado Springs Rainfall Intensity Duration Frequency” curves, Figure 6-5 in the DCM, was used to obtain the design rainfall values; a copy is included in the Appendix. The “Overland (Initial) Flow Equation” (Eq. 6-8) in the DCM, and Manning’s equation with estimated depths were used in time of concentration calculations. “Runoff Coefficients for Rational Method”, Table 6-6 in the DCM, was utilized as a guide in estimating runoff coefficient and Percent Impervious values; a copy is included in the Appendix. Peak runoff discharges were calculated for each drainage sub-basin for both the 5-year storm event and the 100-year storm event with the Rational Method formula, (Eq. 6-5) in the DCM.<sup>8</sup>

For the overall site and large upstream basins flowing through the site in the drainage way, the NRCS Curve Number Loss and Dimensionless Unit Hydrograph Method as described in the (DCM) was applied to calculate the 5-year and 100-year peak storm runoff rates for each drainage sub-basin using the “Hydrologic Engineering Center - Hydrologic Modeling System” (HEC-HMS) Version 4.3 computer program by U.S. Army Corps of Engineers.<sup>9</sup>

Point Precipitation Frequency Estimates for the 2-year, 5-year, 10-year, and 100-year storm events were obtained for the site using the National Oceanic and Atmospheric Administration, Atlas 14 website.<sup>10</sup> The rainfall depth is applied to the NRCS 24-Hour Type II Rainfall Distribution

---

<sup>4</sup> County DCM Sections 4.3, 4.4

<sup>5</sup> City DCM Volume 1

<sup>6</sup> City DCM Volume 2

<sup>7</sup> WSS

<sup>8</sup> County DCM, Volume 1 Update, Chapter 6

<sup>9</sup> HEC-HMS

<sup>10</sup> NOAA

to produce a design storm with Depth-Area Reduction Factors (DARF) correction factors determined by the HEC-HMS program based on the return period of the storm and basin area.

The NRCS Curve Numbers used to calculate the volume of runoff from the 5-year and 100-year storm events in each sub-basin are estimated using the predominate Hydrologic Soil Group, discussed in the section above, the land cover, land use condition and the Antecedent Runoff Condition (ARC) of each basin. ARC II is used for all sub-basin Curve Numbers in this analysis. The NRCS Curve numbers for the individual sub-basins range from 69.5 to 73.6. The **Appendix** contains the NRCS Curve number calculations and summary.

Times of Concentration for sub-basin runoff is calculated using three flow components: Overland Flow Time, Shallow Concentrate Flow Time, and Concentrated Flow Time. The Overland Flow Component is calculated using the Overland Flow Equation as required (DCM Eq 6-15) with maximum overland flow length of 300 feet and the appropriate Manning's Roughness Coefficient according to the surface description (DCM Table 6-11). Shallow Concentrated Flow times are determined based on watercourse slope, ground cover and flow velocity using DCM Table 6-25. Concentrated flow velocities and times are estimated using the Manning' Equation with channel waterway characteristics taken from the basin mapping. The referenced equations, coefficients and tables are included in the appendix. Calculations for Times of Concentration and Lag Times are also included in the **Appendix**.

The Muskingum-Cunge method was utilized for hydrograph channel routing as applied in the HEC-HMS program using waterway course length, slope, channel shape, bottom width and side slopes as determined from the basin mapping.

## **4. Drainage Facility Design**

### **4.1. General Concept**

The intent of the drainage concept presented in this Final Drainage Report is to allow for the subdivision and future development of two (2) rural residential lots while maintaining the existing drainage patterns on the site. There will be no significant grading on the site and no public facilities constructed. The site will be in compliance with the County's Stormwater Management regulations without the need for permanent water quality treatment facilities due to the site being entirely large lot rural residential lots, which are excluded from water quality requirements. No roadways are being constructed and disturbance will be less than 1 acre. Major and minor storm flows will continue to be safely conveyed through the site and downstream.

The existing and proposed drainage hydrologic conditions are described in more detail below. Input data and results for all calculations are included in the Appendix. Drainage maps for hydrology are also included in the **Appendix**.

### **4.2. Specific Details**

#### **4.2.1. Existing Main Stem Drainageway Hydrologic Conditions**

The existing drainageway on-site flows from the southeastern portion of the site, through a stock pond located in the west-central portion of the site and continuing across to the northwestern portion of the site. The drainageway is comprised of natural drainage routes located in the southeastern, southcentral, and northwestern portions of the site. The site receives drainage flows from approximately 1.5 square miles of area south and east of the site that enters from drainage routes located along the southern and eastern edges of the site.

The existing pond embankment contains a 12" Corrugated Metal Pipe (CMP) and 12" grated inlet that are intended to drain ponded water in the drainageway following minor storms. Due to the location and size of the outlet pipe, and the magnitude of a 100 year storm, the inlet and pipe are largely ineffectual in draining flows from the pond in the 100 year storm conditions and can be ignored for hydrologic or hydraulic purposes. When the pond reaches capacity, overflows exit the pond at the opening provided at the south side of the embankment and continue west in the drainageway. The spillway's elevation is approximately 8± feet from the bottom elevation of the pond. Following major storms, when the stock pond contains pond water, flows exit the pond through the spillway.

Offsite flows entering the site from the southern edge at Design Point OS-2 (DP-OS2) have peak storm runoff discharges of  $Q_5 = 120.2$  cfs and  $Q_{100} = 597.1$  cfs (existing flows). These flows include flows from offsite sub-basins OS-1, OS-2, OS-3, OS-4, OS-5, OS-6, and OS-7.

Offsite flows entering the site from the eastern edge at Design Point OS-3 (DP-OS3) have peak storm runoff discharges of  $Q_5 = 74.8$  cfs and  $Q_{100} = 391.9$  cfs (existing flows). These flows include flows from offsite sub-basins OS-8, OS-9, OS-10, OS-11, OS-12, and OS-13.

These flows combine with flows from OS-14, entering the site at the northeastern corner at Design Point OS4 (DP-OS4) and having peak storm runoff discharges of  $Q_5 = 6.1$  cfs and  $Q_{100} = 40.6$  cfs (existing flows) and flows from OS-15, entering the site at the southwestern corner at Design Point OS1 (DP-OS1) and having peak storm runoff discharges of  $Q_5 = 19.8$  cfs and  $Q_{100} = 132.1$  cfs (existing flows) and drain to the stock pond located in the west-central portion of the site at Design Point 1 (DP1). DP1 has peak storm runoff discharges of  $Q_5 = 212.3$  cfs and  $Q_{100} = 1104.4$  cfs (existing flows).

Flows leave the stock pond to combine with flows from OS-16, entering the site at the northwestern corner at Design Point OS5 (DP-OS5) having peak storm runoff discharges of  $Q_5 = 6.6$  cfs and  $Q_{100} = 44.5$  cfs (existing flows), and exist the site at Design Point 2 (DP2), the site outfall. DP2 has peak storm runoff discharges of  $Q_5 = 215.6$  cfs and  $Q_{100} = 1126.0$  cfs (existing flows).

#### **4.2.2. Existing On-Site Hydrologic Conditions**

The High Forest Estates Subdivision Filing No. 1 site includes five (5) sub-basins. Runoff drains into a drainageway onsite that conveys the flows to an onsite stock pond. Flows leave the stock pond, combine with flows from offsite basin OS-16 and exit the site at the site outfall. These flows continue east through adjacent properties and eventually enter East Cherry Creek approximately 2 miles downstream of the site outfall.

Existing Sub-basin EX-A1 (1.16 acres) is located in the southwestern portion of the site and contains portions of existing Table Rock Road, an undeveloped grassed area on-site, and portions of the existing drainageway located in the southwestern portion of the site and stock pond. Located in the southwestern portion of the sub-basin is the spillway to the stock pond with elevation at approximately 8± feet from the bottom elevation. Runoff from the northern portion of the sub-basin drains southerly and combines with flows in the southern portion of the sub-basin to drain northwesterly and enter sub-basin EX-A5. Sub-basin EX-A1 produces peak discharges of  $Q_5 = 0.5$  cfs and  $Q_{100} = 2.8$  cfs (existing flows). Offsite flows enter this basin through an 18" CMP culvert under Table Rock Road and combine with flows from the northern portion of the sub-basin to drain into sub-basin EX-A5.

Existing Sub-basin EX-A2 (1.11 acres) is located in the south central portion of the site and contains an undeveloped grassed area and portions of the aforementioned drainageway and stock pond. Runoff in the western portion of this basin drain northeasterly into the drainage way and runoff in the eastern portion of the sub-basin drains westerly into the drainageway. Sub-basin EX-A2 produces peak discharges of  $Q_5 = 0.3$  cfs and  $Q_{100} = 2.5$  cfs (existing flows). Offsite flows enter this sub-basin at Design Point OS2 (DP-OS2) located south of the sub-basin as shown on the Drainage Map (Existing).

Existing Sub-basin EX-A3 (4.45 acres) is located in the southeastern portion of the site and contains the existing single-family residence and associated sheds, portions of the existing gravel drive, and portions of the aforementioned drainage way. Runoff in the southern portion of this basin drains northerly into the drainage way and runoff in the northern portion of this basin drains southerly into the drainage way. These flows exit the sub-basin through the aforementioned drainageway to enter sub-basin EX-A4. Sub-basin EX-A3 produces peak discharges of  $Q_5 = 1.5$  cfs and  $Q_{100} = 9.5$  cfs (existing flows). Offsite flows enter this sub-basin at Design Point OS3 (DP-OS3) located east of the sub-basin as shown on the Drainage Map (Existing).

Existing Sub-basin EX-A4 (4.08 acres) is located in the northeastern portion of the site and contains portions of the existing gravel drive, and portions of the aforementioned stock pond. Runoff in this basin drains southwesterly into the stock pond. Sub-basin EX-A4 produces peak discharges of  $Q_5 = 1.5$  cfs and  $Q_{100} = 9.0$  cfs (existing flows). Located at Design Point 1 (DP1) is a 12" grated inlet located with rim elevation at approximately  $7 \pm$  feet from the bottom elevation of the stock pond. Offsite flows enter this sub-basin at Design Point OS4 (DP-OS4) located north of the sub-basin as shown on the Drainage Map (Existing).

Design Point 1 (DP1) produces peak discharges of  $Q_5 = 212.3$  cfs and  $Q_{100} = 1104.4$  cfs (existing flows). Located in the southwestern portion of the site is the spillway to the stock pond with elevation at approximately  $8 \pm$  feet from the bottom elevation. Following major storms, when the stock pond contains ponded water, flows exit the spillway to enter sub-basin EX-A5.

Existing Sub-basin EX-A5 (3.56 acres) is located in the northwestern portion of the site and contains portions of the existing gravel drive, portions of existing Walker Road, and portions of the aforementioned drainage way. Runoff in the southern portion of this basin drains northerly into the drainage way and runoff in the northern portion of this basin drains southerly into the drainage way. Offsite flows enter sub-basin EX-A5 at Design Point OS5 (DP-OS5) from the north, flow through 36" CMP culverts under the private gravel road on site, flow onsite for approximately  $100' \pm$ , and exit the site at Design Point 2 (DP2). Offsite flows combine with all flows from the site at Design Point 2 (DP2) and exit the site to the west via the drainage way into the western adjacent site through two (2) 60" CMP culverts under Walker Road located at Design Point 2 (DP2). Sub-basin EX-A5 produces peak discharges of  $Q_5 = 1.7$  cfs and  $Q_{100} = 8.3$  cfs (existing flows).

Design Point 2 (DP2) produces peak discharges of  $Q_5 = 215.6$  cfs and  $Q_{100} = 1126.0$  cfs (existing flows). These flows continue east through adjacent properties and eventually enter East Cherry Creek approximately 2 miles downstream of the site outfall.

#### **4.2.3. Proposed On-Site Hydrologic Conditions**

The proposed drainage hydrologic conditions are described in more detail below. Input data and results for all calculations are included in the **Appendix**. The **Drainage Map (Proposed)** depicts the existing topographic mapping together with proposed contours, proposed drainage basin

delineations, proposed drainage patterns, drainage facilities, and runoff quantities with a data table including drainage areas and flow rates is included in the **Appendix**.

The proposed drainage basins for High Forest Estates Subdivision Filing No. 1 site mirror the existing basins as no changes will be made to the site that affect the layout of the basins. Five (5) sub-basins have been identified in the High Forest Estates Subdivision Filing No. 1 site for analysis of the developed drainage conditions. The site is to contain two (2) rural residential lots. Lot 1, on the west portion of the site, will be 5.00± acres. Lot 2 will be 8.80± acres and located on the eastern portion of the site. Access to all lots will be from the existing gravel road which extends from Walker Road along the northern edge of the site. Each of the lots are assumed to contain a 5,100 SF house footprint, 1,000 SF of exterior hardscape, and 200 foot long 12' wide gravel driveway. The resulting percent imperviousness was used in the hydrologic calculations. The sub-basins are described in more detail below.

Proposed Sub-basin A1 (1.16 acres), located in the southwestern portion of the site and containing portions of existing Table Rock Road, an undeveloped grassed area on-site. This basin contains portions of the existing drainageway and stock pond onsite; located in the southwestern portion of the sub-basin is the spillway to the stock pond with elevation at approximately 8± feet from the bottom elevation. Runoff from the northern portion of the sub-basin will continue to drain southerly and combine with flows in the southern portion of the sub-basin to drain northwesterly and enter sub-basin A5. Sub-basin A1 produces peak discharges of  $Q_5 = 0.5$  cfs and  $Q_{100} = 2.8$  cfs (proposed flows). Offsite flows will continue to enter this sub-basin through an 18" CMP culvert under Table Rock Road and combine with flows from the northern portion of the sub-basin to drain into sub-basin A5. This sub-basin is not expected to contain any further improvements.

Proposed Sub-basin A2 (1.11 acres), located in the south central portion of the site and containing an undeveloped grassed area and portions of the aforementioned drainageway and stock pond. Runoff in the western portion of this basin drain northeasterly into the drainage way and runoff in the eastern portion of the sub-basin drains westerly into the drainageway. Sub-basin EX-A2 produces peak discharges of  $Q_5 = 0.3$  cfs and  $Q_{100} = 2.5$  cfs (proposed flows). Offsite flows will continue to enter this sub-basin at Design Point OS2 (DP-OS2) located south of the sub-basin as shown on the Drainage Map (Proposed). This sub-basin is not expected to contain any further improvements.

Proposed Sub-basin A3 (4.45 acres), located in the southeastern portion of the site, contains the existing single-family residence and associated sheds, portions of the existing gravel drive, and portions of the aforementioned drainage way. Runoff in the southern portion of this basin will continue to drain northerly into the drainage way and runoff in the northern portion of this basin will continue to drain southerly into the drainage way. These flows exit the sub-basin through the aforementioned drainageway to enter sub-basin A4. Sub-basin A3 produces peak discharges of  $Q_5 = 1.5$  cfs and  $Q_{100} = 9.5$  cfs (proposed flows). Offsite flows will continue to enter this sub-basin at Design Point OS3 (DP-OS3) located east of the sub-basin as shown on the Drainage Map (Proposed). This sub-basin is not expected to contain any further improvements.

Proposed Sub-basin A4 (4.08 acres), located in the northeastern portion of the site, contains portions of the existing gravel drive, and portions of the aforementioned stock pond. Runoff in this basin will continue to drain southwestwardly into the stock pond. Sub-basin A4 produces peak discharges of  $Q_5 = 1.5$  cfs and  $Q_{100} = 9.0$  cfs (proposed flows). Located at Design Point 1 (DP1), in the existing pond embankment, is a 12" grated inlet located with rim elevation at approximately 7± feet from the bottom elevation of the stock pond. Due to the location and size of the outlet pipe,

and the magnitude of a 100 year storm, the inlet and pipe are largely ineffectual in draining flows from the pond in the 100 year storm conditions and can be ignored for hydrologic or hydraulic purposes. When the pond reaches capacity, overflows exit the pond at the opening provided at the south side of the embankment and continue west in the drainageway. The spillway's elevation is approximately 8± feet from the bottom elevation of the pond. Following major storms, when the stock pond contains pond water, flows exit the pond through the spillway. Offsite flows will continue to enter this sub-basin at Design Point OS4 (DP-OS4) located north of the sub-basin as shown on the Drainage Map (Proposed). This sub-basin is not expected to contain any further improvements.

Design Point 1 (DP1) produces peak discharges of  $Q_5 = 212.5$  cfs and  $Q_{100} = 1105.1$  cfs (proposed flows). Located in the southwestern portion of the site is the spillway to the stock pond with elevation at approximately 8± feet from the bottom elevation. Following major storms, when the stock pond contains ponded water, flows exit the spillway to enter sub-basin A5.

Proposed Sub-basin A5 (3.56 acres), located in the northwestern portion of the site, contains portions of the existing gravel drive, portions of existing Walker Road, and portions of the aforementioned drainage way. This basin is expected to be further developed to contain one (1) single family residence and driveway. Runoff in the southern portion of this basin will continue to drain northerly into the drainage way and runoff in the northern portion of this basin will continue to drain southerly into the drainage way. Offsite flows will continue to enter sub-basin A5 at Design Point OS5 (DP-OS5) from the north, flow through 36" CMP culverts under the private gravel road onsite, flow onsite for approximately 100'±, and exit the site at Design Point 2 (DP2). Offsite flows combine with all flows from the site at Design Point 2 (DP2) and exit the site to the west via the drainage way into the western adjacent site through two (2) 60" CMP culverts under Walker Road located at Design Point 2 (DP2). Sub-basin A5 produces peak discharges of  $Q_5 = 2.1$  cfs and  $Q_{100} = 8.9$  cfs (proposed flows).

Design Point 2 (DP2) produces peak discharges of  $Q_5 = 216.0$  cfs and  $Q_{100} = 1127.2$  cfs (proposed flows). These flows continue east through adjacent properties and eventually enter East Cherry Creek approximately 2 miles downstream of the site outfall.

#### **4.2.4. Proposed Main Stem Drainageway Hydrologic and Hydraulic Conditions**

A natural drainageway crosses the site from the southeastern portion of the site, through a stock pond located in the west-central portion of the site, to the northwestern portion of the site. The drainageway is comprised of natural drainage routes located in the southeastern, southcentral, and northwestern portions of the site. The site receives drainage flows from approximately 1.5 square miles of area south and east of the site that enters from drainage routes located along the southern and eastern edges of the site.

Offsite flows entering the site from the southern edge at Design Point OS-2 (DP-OS2) have peak storm runoff discharges of  $Q_5 = 120.3$  cfs and  $Q_{100} = 597.2$  cfs (proposed flows). These flows include flows from offsite sub-basins OS-1, OS-2, OS-3, OS-4, OS-5, OS-6, and OS-7.

Offsite flows entering the site from the eastern edge at Design Point OS-3 (DP-OS3) have peak storm runoff discharges of  $Q_5 = 74.8$  cfs and  $Q_{100} = 391.9$  cfs (proposed flows). These flows include flows from offsite sub-basins OS-8, OS-9, OS-10, OS-11, OS-12, and OS-13.

These flows combine with flows from OS-14, entering the site at the northeastern corner at Design Point OS4 (DP-OS4) and having peak storm runoff discharges of  $Q_5 = 6.1$  cfs and  $Q_{100} = 40.6$  cfs (proposed flows) and flows from OS-15, entering the site at the southwestern corner at Design

Point OS1 (DP-OS1) and having peak storm runoff discharges of  $Q_5 = 19.8$  cfs and  $Q_{100} = 132.1$  cfs (proposed flows) and drain to the stock pond located in the west-central portion of the site at Design Point 1 (DP1). DP1 has peak storm runoff discharges of  $Q_5 = 212.5$  cfs and  $Q_{100} = 1105.1$  cfs (proposed flows).

Flows leave the stock pond to combine with flows from OS-16, entering the site at the northwestern corner at Design Point OS5 (DP-OS5) having peak storm runoff discharges of  $Q_5 = 6.6$  cfs and  $Q_{100} = 44.5$  cfs (proposed flows), and exist the site at Design Point 2 (DP2), the site outfall. DP2 has peak storm runoff discharges of  $Q_5 = 216.0$  cfs and  $Q_{100} = 1127.2$  cfs (proposed flows).

Drainage easements and no-build areas are established in the final plat to contain this drainage way, existing ponds and the seasonably high ground water areas of the site. The boundary of the drainage easement was determined by a hydraulic analysis of the drainage way. Calculations and results of the analysis are included in the **Appendix**.

#### 4.2.5. Detention Facilities

The pond has an east-west facing embankment that is well vegetated and stable. The Pond overflows at the spillway opening provided at the south side of the embankment. No detention is required for this site and the pond is not designed to provide detention. The owners of the High Forest Estates Subdivision Filing No. 1 property, own the pond and are responsible for maintenance. In the developed and platted condition, ownership, access and maintenance of the pond will be according to the covenants signed with the subdivision plat. No additional access easements will be needed to access the pond.

A permanent detention facility is not recommended for this site. The proposed lots onsite are classified as large rural residential lots by both zoning and plat implementation. All proposed lots are at least 5 acres in size. No public or private roadways will be constructed. The development's effect on peak runoff discharges is negligible with an increase of 1.2 cfs in the 100-year rainfall event. Therefore, a permanent detention facility is not recommended.

#### 4.2.6. Drainageway Hydraulic Analysis

A hydraulic analysis of the significant drainageway flowing southeast to northwest through the site was conducted utilizing HEC-RAS computer modeling. Cross sections were sampled through the project site in approximately 50' intervals as well as a short distance upstream and downstream of the site. The drainageway exhibits minor winding and is vegetated by long and dense native grasses in the channel and overbanks. Manning's roughness coefficient of 0.037 is selected due to the channel characteristics, vegetation and flow depths. Channel velocities for the 100-year flow range from 0.4 fps to 9.8 fps with a mean average of 3.9 fps. All onsite cross sections exhibit velocities of less than 6 fps excluding three cross sections near the pond spillway and four cross sections located in the southeastern portion of the site. Several gathered sources note permissible flow velocities of up to 6 fps for channels lined with long native grasses for channel stability. The source is included in the **Appendix** of this report.

The drainageway was examined for signs of sedimentation or erosion by visual inspection of site photographs and aerial photography. It is found that the flow path is vegetated with thick natural grasses without signs of erosion within the site boundaries. One cross section near the pond spillway exhibited a velocity exceeding 6 fps, however, the pond spillway was verified by visual inspection to be vegetated and showing no indication of erosive damage. We, therefore, do not recommend any further improvement of the spillway or disturbance of the existing conditions in

Provide correspondence from State Dam Engineer's office to determine whether this embankment is jurisdictional or not. If applicant does not have rights to have embankment they might require it to be removed.

that portion of the site. Four onsite cross sections in the southeast portion of the site exhibit velocities that exceed 6 fps, however, the drainage routes at these cross sections were verified by visual inspection and observed to be vegetated with deep, thick native grasses and brush, showing no indication of erosion or sediment transport. The existing drainageway is in a stable condition and flows are only negligibly increased as a result of the development. We recommend no channel stabilization measures for the project site.

#### **4.3. Erosion Control**

There is no public infrastructure construction associated with this subdivision. Any required best management practices (BMP's) for the individual lot home construction will be handled on the BESQCP for each lot at time of building permit.

#### **4.4. Four Step Process**

El Paso County Engineering Criteria Manual, Appendix I, contains the policies and procedures for Stormwater Quality. Section I.7.1.B provides for exclusions to the requirements to provide Post Construction Stormwater Quality facilities. According to Section I.7.1.B.5, "A single-family residential lot, or agricultural zoned lands, greater than or equal to 2.5 acres in size per dwelling and having a total lot impervious area of less than 10 percent" is excluded. The total area of the site is 13.80± acres. All 13.80± acres is comprised of large lot single-family rural residential units. The total lot imperviousness for rural residential lots is less than 10%. This site is eligible for an exclusion to permanent stormwater quality management requirements by the Post-Construction Stormwater Management exclusion criteria for "Large Lot Single-Family Site" corresponding to MS4 permit Part I.E.4.a.i (E) as the subdivision will contain single-family residential lots, of more 2.5 acres/dwelling and having a total lot impervious area of less than 10 percent. No public roadway improvements are proposed. There are no activities or improvements that require permanent water quality facilities for this project.

The El Paso County Engineering Criteria Manual (Appendix I, Section I.7.2) requires the consideration of a "Four Step Process for receiving water protection that focuses on reducing runoff volumes, treating the water quality capture volume (WQCV), stabilizing drainageways, and implementing long term source controls". It is determined in the section above that this project is exempt from the requirements of Section I.7.1 to provide Post Construction Stormwater Management Facilities with Water Quality Capture Volume (WQCV). However, aspects of the Four Step Process are considered and implemented in the High Forest Estates Subdivision Filing No. 1 project.

- 1) Runoff Reduction Practices are employed in this project. Impervious surfaces have been reduced as much as practically possible. There is only minimal concrete or other hard surfaces proposed. Minimized Directly Connected Impervious Areas (MDCIA) is employed on the project because runoff passes through open space grassed areas before leaving the site.
- 2) All existing swales will remain covered with the existing natural grasses. All of the onsite swales are trapezoidal in shape with wide bottoms widths and flat side slopes. The vegetation for each swale includes medium height prairie grasses that are periodically mowed. It is not anticipated that any of the swales will be modified in the future. It can be safely assumed that the negligible increase in flow as a result of development will have minimal negative impacts on the existing onsite swales.

- 3) The project contains no potentially hazardous uses. The site is exempted from the use of WQCV BMPs by ECM 1.7.1.B.5 corresponding to MS4 permit Part I.E.4.a.i (E) by virtue of the large lot rural residential nature of the site having percent imperviousness of less than 10%.
- 4) The rural residential site is not anticipated to contain storage of potentially harmful substances or use of potentially harmful substances. No site specific or other source control BMPs are required.

## **5. Drainage and Bridge Fees**

The site is located within the East Cherry Creek Drainage Basin which is a no fee basin.

## **6. Conclusion**

This Final Drainage Report presents existing and proposed drainage conditions for the proposed High Forest Estates Subdivision Filing No. 1. The development will have negligible and inconsequential effects on the existing site drainage and drainage conditions downstream. The proposed project will not, with respect to stormwater runoff, negatively impact the adjacent properties and downstream properties.

## References

- City of Colorado Springs Engineering Division. (2014). *City of Colorado Springs Drainage Criteria Manual, Volume 1*. Colorado Springs.
- City of Colorado Springs Engineering Division. (2014). *City of Colorado Springs Drainage Criteria Manual, Volume 2: Stormwater Quality Policies, Procedures and Best Management Practices (BMPs)*. Colorado Springs.
- County Of El Paso. (Revised: October 14, 2020). *(ECM) Engineering Criteria Manual County Of El Paso*.
- County of El Paso; HDR Infrastructure, Inc.; City of Colorado Springs, Department of Public Works. (Revised October 31, 2018). *El Paso County Drainage Criteria Manual*. El Paso County, Department of Public Works.
- Entech Engineering, Inc. (2022). *Soil, Geology, and Geologic Hazard Study High Forest Estates Subdivision, Filing No. 1*. Colorado Springs, CO.
- FEMA. (2018). *(FIRM) Flood Insurance Rate Map*. Washington D.C.: Federal Emergency Management Agency.
- FEMA. (2018). *(FIS) Flood Insurance Study for El Paso County, Colorado and incorporated Areas*. Washington D.C.: Federal Emergency Management Agency.
- Larsen, L. S. (1981). *(SSEPC) Soil Survey of El Paso County Area, Colorado*. National Cooperative Soil Survey.
- National Oceanic And Atmospheric Administration. (2023, April 18). Retrieved from NOAA Atlas 14 Website: [https://hdsc.nws.noaa.gov/hdsc/pfds/pfds\\_map\\_cont.html](https://hdsc.nws.noaa.gov/hdsc/pfds/pfds_map_cont.html)
- NRCS. (2023, September). Retrieved from (WSS) NRCS Web Soil Survey: <https://websoilsurvey.sc.egov.usda.gov/App/WebSoilSurvey.aspx>
- U.S. Army Corps of Engineers. (2018). *Hydrologic Modeling System (HEC-HMS) Version 4.3*. Davis, CA.


## **7. Appendices**

### **A. General Maps and Supporting Data**

- I. Vicinity Map
- II. Portions of Flood Insurance Rate Map
- III. Portion of El Paso County Drainage Basins Map
- IV. NRCS Soil Map and Tables
- V. Soil Type Descriptions – Soil Survey of El Paso County
- VI. NOAA Atlas Point Precipitation Frequency Estimates

## I. Vicinity Map





# VICINITY MAP

NOT TO SCALE

## **II. Portions of Flood Insurance Rate Map**



# National Flood Hazard Layer FIRMette



104°39'58"W 39°6'17"N



## Legend

SEE FIS REPORT FOR DETAILED LEGEND AND INDEX MAP FOR FIRM PANEL LAYOUT

- |   |  |
|---|--|
| <p><b>SPECIAL FLOOD HAZARD AREAS</b></p>  | <ul style="list-style-type: none"> <li><span style="display: inline-block; width: 15px; height: 10px; background-color: cyan; border: 1px solid black; margin-right: 5px;"></span> Without Base Flood Elevation (BFE)<br/><i>Zone A, V, A99</i></li> <li><span style="display: inline-block; width: 15px; height: 10px; background-color: lightblue; border: 1px solid black; margin-right: 5px;"></span> With BFE or Depth <i>Zone AE, AO, AH, VE, AR</i></li> <li><span style="display: inline-block; width: 15px; height: 10px; background: repeating-linear-gradient(45deg, transparent, transparent 2px, red 2px, red 4px); border: 1px solid black; margin-right: 5px;"></span> Regulatory Floodway</li> </ul>   |
| <p><b>OTHER AREAS OF FLOOD HAZARD</b></p> | <ul style="list-style-type: none"> <li><span style="display: inline-block; width: 15px; height: 10px; background-color: orange; border: 1px solid black; margin-right: 5px;"></span> 0.2% Annual Chance Flood Hazard, Areas of 1% annual chance flood with average depth less than one foot or with drainage areas of less than one square mile <i>Zone X</i></li> <li><span style="display: inline-block; width: 15px; height: 10px; background: repeating-linear-gradient(-45deg, transparent, transparent 2px, gray 2px, gray 4px); border: 1px solid black; margin-right: 5px;"></span> Future Conditions 1% Annual Chance Flood Hazard <i>Zone X</i></li> <li><span style="display: inline-block; width: 15px; height: 10px; background: repeating-linear-gradient(-45deg, transparent, transparent 2px, orange 2px, orange 4px); border: 1px solid black; margin-right: 5px;"></span> Area with Reduced Flood Risk due to Levee. See Notes. <i>Zone X</i></li> <li><span style="display: inline-block; width: 15px; height: 10px; background: repeating-linear-gradient(-45deg, transparent, transparent 2px, yellow 2px, yellow 4px); border: 1px solid black; margin-right: 5px;"></span> Area with Flood Risk due to Levee <i>Zone D</i></li> </ul> |
| <p><b>OTHER AREAS</b></p>                 | <ul style="list-style-type: none"> <li><span style="display: inline-block; width: 15px; height: 10px; background-color: white; border: 1px solid black; margin-right: 5px;"></span> NO SCREEN Area of Minimal Flood Hazard <i>Zone X</i></li> <li><span style="display: inline-block; width: 15px; height: 10px; border: 2px solid blue; margin-right: 5px;"></span> Effective LOMRs</li> <li><span style="display: inline-block; width: 15px; height: 10px; background-color: lightorange; border: 1px solid black; margin-right: 5px;"></span> Area of Undetermined Flood Hazard <i>Zone D</i></li> </ul>  |
| <p><b>GENERAL STRUCTURES</b></p>          | <ul style="list-style-type: none"> <li><span style="display: inline-block; width: 15px; border-bottom: 2px dashed black; margin-right: 5px;"></span> Channel, Culvert, or Storm Sewer</li> <li><span style="display: inline-block; width: 15px; border-bottom: 2px dashed gray; margin-right: 5px;"></span> Levee, Dike, or Floodwall</li> </ul>   |
| <p><b>OTHER FEATURES</b></p>              | <ul style="list-style-type: none"> <li><span style="display: inline-block; width: 15px; border-bottom: 2px solid black; margin-right: 5px;"></span> Cross Sections with 1% Annual Chance Water Surface Elevation</li> <li><span style="display: inline-block; width: 15px; border-bottom: 2px dashed black; margin-right: 5px;"></span> Coastal Transect</li> <li><span style="display: inline-block; width: 15px; border-bottom: 2px dashed gray; margin-right: 5px;"></span> Base Flood Elevation Line (BFE)</li> <li><span style="display: inline-block; width: 15px; border-bottom: 2px solid red; margin-right: 5px;"></span> Limit of Study</li> <li><span style="display: inline-block; width: 15px; border-bottom: 2px solid yellow; margin-right: 5px;"></span> Jurisdiction Boundary</li> <li><span style="display: inline-block; width: 15px; border-bottom: 2px dashed black; margin-right: 5px;"></span> Coastal Transect Baseline</li> <li><span style="display: inline-block; width: 15px; border-bottom: 2px solid blue; margin-right: 5px;"></span> Profile Baseline</li> <li><span style="display: inline-block; width: 15px; border-bottom: 2px solid blue; margin-right: 5px;"></span> Hydrographic Feature</li> </ul>                   |
| <p><b>MAP PANELS</b></p>                  | <ul style="list-style-type: none"> <li><span style="display: inline-block; width: 15px; height: 10px; background-color: white; border: 1px solid black; border-style: dashed; margin-right: 5px;"></span> Digital Data Available</li> <li><span style="display: inline-block; width: 15px; height: 10px; background-color: white; border: 1px solid black; margin-right: 5px;"></span> No Digital Data Available</li> <li><span style="display: inline-block; width: 15px; height: 10px; background-color: white; border: 1px solid black; border-style: dotted; margin-right: 5px;"></span> Unmapped</li> </ul>   |



The pin displayed on the map is an approximate point selected by the user and does not represent an authoritative property location.


This map complies with FEMA's standards for the use of digital flood maps if it is not void as described below. The basemap shown complies with FEMA's basemap accuracy standards

The flood hazard information is derived directly from the authoritative NFHL web services provided by FEMA. This map was exported on **10/14/2022 at 12:49 PM** and does not reflect changes or amendments subsequent to this date and time. The NFHL and effective information may change or become superseded by new data over time.


This map image is void if the one or more of the following map elements do not appear: basemap imagery, flood zone labels, legend, scale bar, map creation date, community identifiers, FIRM panel number, and FIRM effective date. Map images for unmapped and unmodernized areas cannot be used for regulatory purposes.

### **III. Portion of El Paso County Drainage Basins Map**





1" = 2,000' 1:24,000



# *East Cherry Creek CYCY0200*

# SITE



to Ridge Hts

White Antelope Dr

S Blue Sage Cir

Campbell Rd

Black Forest Rd

Thoroughbred

Table Rock Rd

Highland Estates Dr

Clydesdale Rd

Colt Ct

Thompson Rd

Remington Rd

Collmer Rd

Winohester Rd

## **IV. NRCS Soil Map and Tables**






United States  
Department of  
Agriculture

**NRCS**

Natural  
Resources  
Conservation  
Service

A product of the National  
Cooperative Soil Survey,  
a joint effort of the United  
States Department of  
Agriculture and other  
Federal agencies, State  
agencies including the  
Agricultural Experiment  
Stations, and local  
participants

# Custom Soil Resource Report for El Paso County Area, Colorado



# Preface

---

Soil surveys contain information that affects land use planning in survey areas. They highlight soil limitations that affect various land uses and provide information about the properties of the soils in the survey areas. Soil surveys are designed for many different users, including farmers, ranchers, foresters, agronomists, urban planners, community officials, engineers, developers, builders, and home buyers. Also, conservationists, teachers, students, and specialists in recreation, waste disposal, and pollution control can use the surveys to help them understand, protect, or enhance the environment.

Various land use regulations of Federal, State, and local governments may impose special restrictions on land use or land treatment. Soil surveys identify soil properties that are used in making various land use or land treatment decisions. The information is intended to help the land users identify and reduce the effects of soil limitations on various land uses. The landowner or user is responsible for identifying and complying with existing laws and regulations.

Although soil survey information can be used for general farm, local, and wider area planning, onsite investigation is needed to supplement this information in some cases. Examples include soil quality assessments (<http://www.nrcs.usda.gov/wps/portal/nrcs/main/soils/health/>) and certain conservation and engineering applications. For more detailed information, contact your local USDA Service Center (<https://offices.sc.egov.usda.gov/locator/app?agency=nrcs>) or your NRCS State Soil Scientist ([http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/contactus/?cid=nrcs142p2\\_053951](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/contactus/?cid=nrcs142p2_053951)).

Great differences in soil properties can occur within short distances. Some soils are seasonally wet or subject to flooding. Some are too unstable to be used as a foundation for buildings or roads. Clayey or wet soils are poorly suited to use as septic tank absorption fields. A high water table makes a soil poorly suited to basements or underground installations.

The National Cooperative Soil Survey is a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local agencies. The Natural Resources Conservation Service (NRCS) has leadership for the Federal part of the National Cooperative Soil Survey.

Information about soils is updated periodically. Updated information is available through the NRCS Web Soil Survey, the site for official soil survey information.

The U.S. Department of Agriculture (USDA) prohibits discrimination in all its programs and activities on the basis of race, color, national origin, age, disability, and where applicable, sex, marital status, familial status, parental status, religion, sexual orientation, genetic information, political beliefs, reprisal, or because all or a part of an individual's income is derived from any public assistance program. (Not all prohibited bases apply to all programs.) Persons with disabilities who require

alternative means for communication of program information (Braille, large print, audiotape, etc.) should contact USDA's TARGET Center at (202) 720-2600 (voice and TDD). To file a complaint of discrimination, write to USDA, Director, Office of Civil Rights, 1400 Independence Avenue, S.W., Washington, D.C. 20250-9410 or call (800) 795-3272 (voice) or (202) 720-6382 (TDD). USDA is an equal opportunity provider and employer.

# Contents

---

<b>Preface</b> .....	2
<b>How Soil Surveys Are Made</b> .....	5
<b>Soil Map</b> .....	8
Soil Map.....	9
Legend.....	10
Map Unit Legend.....	11
Map Unit Descriptions.....	11
El Paso County Area, Colorado.....	13
68—Peyton-Pring complex, 3 to 8 percent slopes.....	13
<b>References</b> .....	15

# How Soil Surveys Are Made

---

Soil surveys are made to provide information about the soils and miscellaneous areas in a specific area. They include a description of the soils and miscellaneous areas and their location on the landscape and tables that show soil properties and limitations affecting various uses. Soil scientists observed the steepness, length, and shape of the slopes; the general pattern of drainage; the kinds of crops and native plants; and the kinds of bedrock. They observed and described many soil profiles. A soil profile is the sequence of natural layers, or horizons, in a soil. The profile extends from the surface down into the unconsolidated material in which the soil formed or from the surface down to bedrock. The unconsolidated material is devoid of roots and other living organisms and has not been changed by other biological activity.

Currently, soils are mapped according to the boundaries of major land resource areas (MLRAs). MLRAs are geographically associated land resource units that share common characteristics related to physiography, geology, climate, water resources, soils, biological resources, and land uses (USDA, 2006). Soil survey areas typically consist of parts of one or more MLRA.

The soils and miscellaneous areas in a survey area occur in an orderly pattern that is related to the geology, landforms, relief, climate, and natural vegetation of the area. Each kind of soil and miscellaneous area is associated with a particular kind of landform or with a segment of the landform. By observing the soils and miscellaneous areas in the survey area and relating their position to specific segments of the landform, a soil scientist develops a concept, or model, of how they were formed. Thus, during mapping, this model enables the soil scientist to predict with a considerable degree of accuracy the kind of soil or miscellaneous area at a specific location on the landscape.

Commonly, individual soils on the landscape merge into one another as their characteristics gradually change. To construct an accurate soil map, however, soil scientists must determine the boundaries between the soils. They can observe only a limited number of soil profiles. Nevertheless, these observations, supplemented by an understanding of the soil-vegetation-landscape relationship, are sufficient to verify predictions of the kinds of soil in an area and to determine the boundaries.

Soil scientists recorded the characteristics of the soil profiles that they studied. They noted soil color, texture, size and shape of soil aggregates, kind and amount of rock fragments, distribution of plant roots, reaction, and other features that enable them to identify soils. After describing the soils in the survey area and determining their properties, the soil scientists assigned the soils to taxonomic classes (units). Taxonomic classes are concepts. Each taxonomic class has a set of soil characteristics with precisely defined limits. The classes are used as a basis for comparison to classify soils systematically. Soil taxonomy, the system of taxonomic classification used in the United States, is based mainly on the kind and character of soil properties and the arrangement of horizons within the profile. After the soil

## Custom Soil Resource Report

scientists classified and named the soils in the survey area, they compared the individual soils with similar soils in the same taxonomic class in other areas so that they could confirm data and assemble additional data based on experience and research.

The objective of soil mapping is not to delineate pure map unit components; the objective is to separate the landscape into landforms or landform segments that have similar use and management requirements. Each map unit is defined by a unique combination of soil components and/or miscellaneous areas in predictable proportions. Some components may be highly contrasting to the other components of the map unit. The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The delineation of such landforms and landform segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, onsite investigation is needed to define and locate the soils and miscellaneous areas.

Soil scientists make many field observations in the process of producing a soil map. The frequency of observation is dependent upon several factors, including scale of mapping, intensity of mapping, design of map units, complexity of the landscape, and experience of the soil scientist. Observations are made to test and refine the soil-landscape model and predictions and to verify the classification of the soils at specific locations. Once the soil-landscape model is refined, a significantly smaller number of measurements of individual soil properties are made and recorded. These measurements may include field measurements, such as those for color, depth to bedrock, and texture, and laboratory measurements, such as those for content of sand, silt, clay, salt, and other components. Properties of each soil typically vary from one point to another across the landscape.

Observations for map unit components are aggregated to develop ranges of characteristics for the components. The aggregated values are presented. Direct measurements do not exist for every property presented for every map unit component. Values for some properties are estimated from combinations of other properties.

While a soil survey is in progress, samples of some of the soils in the area generally are collected for laboratory analyses and for engineering tests. Soil scientists interpret the data from these analyses and tests as well as the field-observed characteristics and the soil properties to determine the expected behavior of the soils under different uses. Interpretations for all of the soils are field tested through observation of the soils in different uses and under different levels of management. Some interpretations are modified to fit local conditions, and some new interpretations are developed to meet local needs. Data are assembled from other sources, such as research information, production records, and field experience of specialists. For example, data on crop yields under defined levels of management are assembled from farm records and from field or plot experiments on the same kinds of soil.

Predictions about soil behavior are based not only on soil properties but also on such variables as climate and biological activity. Soil conditions are predictable over long periods of time, but they are not predictable from year to year. For example, soil scientists can predict with a fairly high degree of accuracy that a given soil will have a high water table within certain depths in most years, but they cannot predict that a high water table will always be at a specific level in the soil on a specific date.

After soil scientists located and identified the significant natural bodies of soil in the survey area, they drew the boundaries of these bodies on aerial photographs and

## Custom Soil Resource Report

identified each as a specific map unit. Aerial photographs show trees, buildings, fields, roads, and rivers, all of which help in locating boundaries accurately.

# Soil Map

---

The soil map section includes the soil map for the defined area of interest, a list of soil map units on the map and extent of each map unit, and cartographic symbols displayed on the map. Also presented are various metadata about data used to produce the map, and a description of each soil map unit.

# Custom Soil Resource Report Soil Map



Map Scale: 1:1,610 if printed on A landscape (11" x 8.5") sheet.



Map projection: Web Mercator Corner coordinates: WGS84 Edge tics: UTM Zone 13N WGS84

### MAP LEGEND

**Area of Interest (AOI)**

 Area of Interest (AOI)

**Soils**

 Soil Map Unit Polygons

 Soil Map Unit Lines

 Soil Map Unit Points

**Special Point Features**

-  Blowout
-  Borrow Pit
-  Clay Spot
-  Closed Depression
-  Gravel Pit
-  Gravelly Spot
-  Landfill
-  Lava Flow
-  Marsh or swamp
-  Mine or Quarry
-  Miscellaneous Water
-  Perennial Water
-  Rock Outcrop
-  Saline Spot
-  Sandy Spot
-  Severely Eroded Spot
-  Sinkhole
-  Slide or Slip
-  Sodic Spot

-  Spoil Area
-  Stony Spot
-  Very Stony Spot
-  Wet Spot
-  Other
-  Special Line Features

**Water Features**

 Streams and Canals

**Transportation**

-  Rails
-  Interstate Highways
-  US Routes
-  Major Roads
-  Local Roads

**Background**

 Aerial Photography

### MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service  
 Web Soil Survey URL:  
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: El Paso County Area, Colorado  
 Survey Area Data: Version 19, Aug 31, 2021

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Jun 9, 2021—Jun 12, 2021

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

## Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
68	Peyton-Pring complex, 3 to 8 percent slopes	13.5	100.0%
<b>Totals for Area of Interest</b>		<b>13.5</b>	<b>100.0%</b>

## Map Unit Descriptions

The map units delineated on the detailed soil maps in a soil survey represent the soils or miscellaneous areas in the survey area. The map unit descriptions, along with the maps, can be used to determine the composition and properties of a unit.

A map unit delineation on a soil map represents an area dominated by one or more major kinds of soil or miscellaneous areas. A map unit is identified and named according to the taxonomic classification of the dominant soils. Within a taxonomic class there are precisely defined limits for the properties of the soils. On the landscape, however, the soils are natural phenomena, and they have the characteristic variability of all natural phenomena. Thus, the range of some observed properties may extend beyond the limits defined for a taxonomic class. Areas of soils of a single taxonomic class rarely, if ever, can be mapped without including areas of other taxonomic classes. Consequently, every map unit is made up of the soils or miscellaneous areas for which it is named and some minor components that belong to taxonomic classes other than those of the major soils.

Most minor soils have properties similar to those of the dominant soil or soils in the map unit, and thus they do not affect use and management. These are called noncontrasting, or similar, components. They may or may not be mentioned in a particular map unit description. Other minor components, however, have properties and behavioral characteristics divergent enough to affect use or to require different management. These are called contrasting, or dissimilar, components. They generally are in small areas and could not be mapped separately because of the scale used. Some small areas of strongly contrasting soils or miscellaneous areas are identified by a special symbol on the maps. If included in the database for a given area, the contrasting minor components are identified in the map unit descriptions along with some characteristics of each. A few areas of minor components may not have been observed, and consequently they are not mentioned in the descriptions, especially where the pattern was so complex that it was impractical to make enough observations to identify all the soils and miscellaneous areas on the landscape.

The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The objective of mapping is not to delineate pure taxonomic classes but rather to separate the landscape into landforms or landform segments that have similar use and management requirements. The delineation of such segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, however, onsite investigation is needed to define and locate the soils and miscellaneous areas.

## Custom Soil Resource Report

An identifying symbol precedes the map unit name in the map unit descriptions. Each description includes general facts about the unit and gives important soil properties and qualities.

Soils that have profiles that are almost alike make up a *soil series*. Except for differences in texture of the surface layer, all the soils of a series have major horizons that are similar in composition, thickness, and arrangement.

Soils of one series can differ in texture of the surface layer, slope, stoniness, salinity, degree of erosion, and other characteristics that affect their use. On the basis of such differences, a soil series is divided into *soil phases*. Most of the areas shown on the detailed soil maps are phases of soil series. The name of a soil phase commonly indicates a feature that affects use or management. For example, Alpha silt loam, 0 to 2 percent slopes, is a phase of the Alpha series.

Some map units are made up of two or more major soils or miscellaneous areas. These map units are complexes, associations, or undifferentiated groups.

A *complex* consists of two or more soils or miscellaneous areas in such an intricate pattern or in such small areas that they cannot be shown separately on the maps. The pattern and proportion of the soils or miscellaneous areas are somewhat similar in all areas. Alpha-Beta complex, 0 to 6 percent slopes, is an example.

An *association* is made up of two or more geographically associated soils or miscellaneous areas that are shown as one unit on the maps. Because of present or anticipated uses of the map units in the survey area, it was not considered practical or necessary to map the soils or miscellaneous areas separately. The pattern and relative proportion of the soils or miscellaneous areas are somewhat similar. Alpha-Beta association, 0 to 2 percent slopes, is an example.

An *undifferentiated group* is made up of two or more soils or miscellaneous areas that could be mapped individually but are mapped as one unit because similar interpretations can be made for use and management. The pattern and proportion of the soils or miscellaneous areas in a mapped area are not uniform. An area can be made up of only one of the major soils or miscellaneous areas, or it can be made up of all of them. Alpha and Beta soils, 0 to 2 percent slopes, is an example.

Some surveys include *miscellaneous areas*. Such areas have little or no soil material and support little or no vegetation. Rock outcrop is an example.

## El Paso County Area, Colorado

### 68—Peyton-Pring complex, 3 to 8 percent slopes

#### Map Unit Setting

*National map unit symbol:* 369f

*Elevation:* 6,800 to 7,600 feet

*Farmland classification:* Not prime farmland

#### Map Unit Composition

*Peyton and similar soils:* 40 percent

*Pring and similar soils:* 30 percent

*Estimates are based on observations, descriptions, and transects of the mapunit.*

#### Description of Peyton

##### Setting

*Landform:* Hills

*Landform position (three-dimensional):* Side slope

*Down-slope shape:* Linear

*Across-slope shape:* Linear

*Parent material:* Arkosic alluvium derived from sedimentary rock and/or arkosic residuum weathered from sedimentary rock

##### Typical profile

*A - 0 to 12 inches:* sandy loam

*Bt - 12 to 25 inches:* sandy clay loam

*BC - 25 to 35 inches:* sandy loam

*C - 35 to 60 inches:* sandy loam

##### Properties and qualities

*Slope:* 3 to 5 percent

*Depth to restrictive feature:* More than 80 inches

*Drainage class:* Well drained

*Runoff class:* Low

*Capacity of the most limiting layer to transmit water (Ksat):* Moderately high (0.20 to 0.60 in/hr)

*Depth to water table:* More than 80 inches

*Frequency of flooding:* None

*Frequency of ponding:* None

*Available water supply, 0 to 60 inches:* Moderate (about 7.3 inches)

##### Interpretive groups

*Land capability classification (irrigated):* None specified

*Land capability classification (nonirrigated):* 4c

*Hydrologic Soil Group:* B

*Ecological site:* R049XY216CO - Sandy Divide

*Hydric soil rating:* No

#### Description of Pring

##### Setting

*Landform:* Hills

*Landform position (three-dimensional):* Side slope

*Down-slope shape:* Linear

*Across-slope shape:* Linear

## Custom Soil Resource Report

*Parent material:* Arkosic alluvium derived from sedimentary rock

### Typical profile

*A - 0 to 14 inches:* coarse sandy loam

*C - 14 to 60 inches:* gravelly sandy loam

### Properties and qualities

*Slope:* 3 to 8 percent

*Depth to restrictive feature:* More than 80 inches

*Drainage class:* Well drained

*Runoff class:* Low

*Capacity of the most limiting layer to transmit water (Ksat):* High (2.00 to 6.00 in/hr)

*Depth to water table:* More than 80 inches

*Frequency of flooding:* None

*Frequency of ponding:* None

*Available water supply, 0 to 60 inches:* Low (about 6.0 inches)

### Interpretive groups

*Land capability classification (irrigated):* None specified

*Land capability classification (nonirrigated):* 3e

*Hydrologic Soil Group:* B

*Ecological site:* R048AY222CO - Loamy Park

*Hydric soil rating:* No

### Minor Components

#### Other soils

*Percent of map unit:*

*Hydric soil rating:* No

#### Pleasant

*Percent of map unit:*

*Landform:* Depressions

*Hydric soil rating:* Yes

# References

---

- American Association of State Highway and Transportation Officials (AASHTO). 2004. Standard specifications for transportation materials and methods of sampling and testing. 24th edition.
- American Society for Testing and Materials (ASTM). 2005. Standard classification of soils for engineering purposes. ASTM Standard D2487-00.
- Cowardin, L.M., V. Carter, F.C. Golet, and E.T. LaRoe. 1979. Classification of wetlands and deep-water habitats of the United States. U.S. Fish and Wildlife Service FWS/OBS-79/31.
- Federal Register. July 13, 1994. Changes in hydric soils of the United States.
- Federal Register. September 18, 2002. Hydric soils of the United States.
- Hurt, G.W., and L.M. Vasilas, editors. Version 6.0, 2006. Field indicators of hydric soils in the United States.
- National Research Council. 1995. Wetlands: Characteristics and boundaries.
- Soil Survey Division Staff. 1993. Soil survey manual. Soil Conservation Service. U.S. Department of Agriculture Handbook 18. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2\\_054262](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_054262)
- Soil Survey Staff. 1999. Soil taxonomy: A basic system of soil classification for making and interpreting soil surveys. 2nd edition. Natural Resources Conservation Service, U.S. Department of Agriculture Handbook 436. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2\\_053577](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053577)
- Soil Survey Staff. 2010. Keys to soil taxonomy. 11th edition. U.S. Department of Agriculture, Natural Resources Conservation Service. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2\\_053580](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053580)
- Tiner, R.W., Jr. 1985. Wetlands of Delaware. U.S. Fish and Wildlife Service and Delaware Department of Natural Resources and Environmental Control, Wetlands Section.
- United States Army Corps of Engineers, Environmental Laboratory. 1987. Corps of Engineers wetlands delineation manual. Waterways Experiment Station Technical Report Y-87-1.
- United States Department of Agriculture, Natural Resources Conservation Service. National forestry manual. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/home/?cid=nrcs142p2\\_053374](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/home/?cid=nrcs142p2_053374)
- United States Department of Agriculture, Natural Resources Conservation Service. National range and pasture handbook. <http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/landuse/rangepasture/?cid=stelprdb1043084>

## Custom Soil Resource Report

United States Department of Agriculture, Natural Resources Conservation Service. National soil survey handbook, title 430-VI. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/scientists/?cid=nrcs142p2\\_054242](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/scientists/?cid=nrcs142p2_054242)

United States Department of Agriculture, Natural Resources Conservation Service. 2006. Land resource regions and major land resource areas of the United States, the Caribbean, and the Pacific Basin. U.S. Department of Agriculture Handbook 296. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2\\_053624](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053624)

United States Department of Agriculture, Soil Conservation Service. 1961. Land capability classification. U.S. Department of Agriculture Handbook 210. [http://www.nrcs.usda.gov/Internet/FSE\\_DOCUMENTS/nrcs142p2\\_052290.pdf](http://www.nrcs.usda.gov/Internet/FSE_DOCUMENTS/nrcs142p2_052290.pdf)

## **V. Soil Type Descriptions – Soil Survey of El Paso County**



support a load and potential frost action on roads and streets. Roads and buildings can be designed to overcome these limitations. Capability subclass IVe.

**67—Peyton sandy loam, 5 to 9 percent slopes.** This deep, noncalcareous, well drained soil formed in alluvium and residuum derived from weathered arkosic sedimentary rock on uplands. Elevation ranges from 6,800 to 7,600 feet.

Typically, the surface layer is grayish brown sandy loam about 12 inches thick. The subsoil, about 23 inches thick, is pale brown sandy clay loam in the upper 13 inches and pale brown sandy loam in the lower 10 inches. The substratum is pale brown sandy loam to a depth of 60 inches.

Included with this soil in mapping are small areas of Holderness loam, 5 to 8 percent slopes; Pring coarse sandy loam, 3 to 8 percent slopes; and Tomah-Crowfoot loamy sands, 3 to 8 percent slopes.

Permeability of this soil is moderate. Effective rooting depth is 60 inches or more. Available water capacity is high. Surface runoff is medium, and the hazard of erosion is moderate. Gullies and rills are common.

Most of the acreage of this Peyton soil is used as rangeland. Some areas are used for wheat and oats. Stubble mulching or other crop residue management practices are needed to control water erosion. Wildlife habitat is also an important use.

This soil is well suited to the production of native vegetation suitable for grazing. The native vegetation is mainly mountain muhly, bluestem, mountain brome, needleandthread, and blue grama. This soil is subject to invasion by Kentucky bluegrass and Gambel oak. Minor amounts of forbs such as hairy goldenrod, geranium, milkvetch, low larkspur, fringed sage, and buckwheat are in the stand.

Proper location of livestock watering facilities helps to control grazing. Timely deferment of grazing is needed to protect the plant cover.

Windbreaks and environmental plantings generally are suited to this soil. Soil blowing is the main limitation to the establishment of trees and shrubs. This limitation can be overcome by cultivating only in the tree rows and leaving a strip of vegetation between the rows. Supplemental irrigation may be necessary when planting and during dry periods. Trees that are best suited and have good survival are Rocky Mountain juniper, eastern redcedar, ponderosa pine, Siberian elm, Russian-olive, and hackberry. Shrubs that are best suited are skunkbush sumac, lilac, and Siberian peashrub.

This soil is suited to habitat for openland and rangeland wildlife. Rangeland wildlife, such as pronghorn antelope, can be encouraged by developing livestock watering facilities, properly managing livestock grazing, and reseeding range where needed.

This soil has good potential for homesites. The main limitation is the limited ability to support a load and potential frost action. Buildings and roads can be designed to overcome these limitations. Capability subclass IVe.

**68—Peyton-Pring complex, 3 to 8 percent slopes.** These gently sloping to moderately sloping soils are on valley side slopes and on uplands. Elevation ranges from 6,800 to 7,600 feet. The average annual precipitation is about 17 inches, the average annual air temperature is about 43 degrees F, and the average frost-free period is about 120 days.

The Peyton soil makes up about 40 percent of the complex, the Pring soil about 30 percent, and other soils about 30 percent.

Included with these soils in mapping are areas of Holderness loam, 1 to 5 percent slopes; Holderness loam, 5 to 8 percent slopes; and Tomah-Crowfoot loamy sands, 3 to 8 percent slopes. In some places arkosic beds of sandstone and shale are at a depth of 0 to 40 inches.

The Peyton soil is commonly on the less sloping part of the landscape. It is deep, noncalcareous, and well drained. It formed in alluvium and residuum derived from weathered arkosic sedimentary rock. Typically, the surface layer is grayish brown sandy loam about 12 inches thick. The subsoil, about 23 inches thick, is pale brown sandy clay loam in the upper 13 inches and pale brown sandy loam in the lower 10 inches. The substratum is pale brown sandy loam to a depth of 60 inches or more.

Permeability of the Peyton soil is moderate. Effective rooting depth is 60 inches or more. Available water capacity is high. Surface runoff is medium, and the hazard of erosion is moderate.

The Pring soil is deep, noncalcareous, and well drained. It formed in sandy sediment derived from weathered arkosic sedimentary rock. Typically, the surface layer is dark grayish brown coarse sandy loam about 4 inches thick. The substratum is dark grayish brown coarse sandy loam about 10 inches thick over pale brown gravelly sandy loam that extends to a depth of 60 inches or more.

Permeability of the Pring soil is rapid. Effective rooting depth is 60 inches or more. Available water capacity is moderate. Surface runoff is medium, and the hazard of erosion is moderate.

These soils are used as rangeland, for wildlife habitat, and for homesites.

These soils are well suited to the production of native vegetation suitable for grazing. The dominant native species are mountain muhly, bluestem, needleandthread, and blue grama. These soils are subject to invasion of Kentucky bluegrass and Gambel oak. Common forbs are hairy goldenrod, geranium, milkvetch, low larkspur, fringed sage, and buckwheat.

Properly locating livestock watering facilities helps to control grazing. Timely deferment of grazing is needed to protect the plant cover.

Windbreaks and environmental plantings generally are suited to these soils. Soil blowing is the main limitation to the establishment of trees and shrubs. This limitation can be overcome by cultivating only in the tree rows and leaving a strip of vegetation between the rows. Supplemental irrigation may be needed when planting and during dry periods. Trees that are best suited and have good

survival are Rocky Mountain juniper, eastern redcedar, ponderosa pine, Siberian elm, Russian-olive, and hackberry. Shrubs that are best suited are skunkbush sumac, lilac, and Siberian peashrub.

These soils are suited to habitat for openland and rangeland wildlife. Rangeland wildlife, such as pronghorn antelope, can be encouraged by developing livestock watering facilities, properly managing livestock grazing, and reseeding range where needed.

These soils have a good potential for homesites. The main limitations, especially on the Peyton soil, are low bearing strength and frost-action potential. Buildings and roads can be designed to overcome these limitations. Access roads should have adequate cut-slope grade and be provided with drains to control surface runoff and keep soil losses to a minimum. Capability subclass VIe.

**69—Peyton-Pring complex, 8 to 15 percent slopes.** These gently to moderately sloping soils are on valley side slopes and on uplands. Elevation ranges from 6,800 to 7,600 feet. The average annual precipitation is about 17 inches, the average annual air temperature is about 43 degrees F, and the average frost-free period is about 120 days.

The Peyton soil makes up about 40 percent of the complex, the Pring soil about 30 percent, and other soils about 30 percent.

Included with these soils in mapping are areas of Holderness loam, 8 to 15 percent slopes; Tomah-Crowfoot loamy sands, 8 to 15 percent slopes; Kettle gravelly loamy sand, 8 to 40 percent slopes; and a few areas of Rock outcrop.

The Peyton soil is commonly on the less sloping part of the landscape. It is deep, noncalcareous, and well drained. It formed in alluvium and residuum derived from weathered, arkosic, sedimentary rock. Typically, the surface layer is grayish brown sandy loam about 12 inches thick. The subsoil, about 23 inches thick, is pale brown sandy clay loam in the upper 13 inches and pale brown sandy loam in the lower 10 inches. The substratum is pale brown sandy loam to a depth of 60 inches or more.

Permeability of the Peyton soil is moderate. Effective rooting depth is 60 inches or more. Available water capacity is high. Surface runoff is medium to rapid, and the hazard of erosion is moderate to high. Some gullies have developed along drainageways and livestock trails.

The Pring soil is deep, noncalcareous, and well drained. It formed in sandy sediment derived from weathered, arkosic, sedimentary rock. Typically, the surface layer is dark grayish brown coarse sandy loam about 4 inches thick. The substratum is dark grayish brown coarse sandy loam about 10 inches thick over pale brown gravelly sandy loam that extends to a depth of 60 inches or more.

Permeability of the Pring soil is rapid. Effective rooting depth is 60 inches or more. Available water capacity is moderate. Surface runoff is medium to rapid, and the hazard of erosion is moderate to high. Some gullies have developed along drainageways and livestock trails.

The soils in this complex are used as rangeland, for wildlife habitat, and for homesites.

These soils are well suited to the production of native vegetation suitable for grazing. The dominant native species are mountain muhly, bluestem grasses, needle-andthread, and blue grama. These soils are subject to invasion of Kentucky bluegrass and Gambel oak. Common forbs are hairy goldenrod, geranium, milkvetch, low larkspur, fringed sage, and buckwheat.

Properly locating livestock watering facilities helps to control grazing. Timely defoliation of grazing is needed to protect the plant cover.

Windbreaks and environmental plantings generally are suited to these soils. Soil blowing is the main limitation to the establishment of trees and shrubs. This limitation can be overcome by cultivating only in the tree rows and leaving a strip of vegetation between the rows. Supplemental irrigation may be needed when planting and during dry periods. Trees that are best suited and have good survival are Rocky Mountain juniper, eastern redcedar, ponderosa pine, Siberian elm, Russian-olive, and hackberry. Shrubs that are best suited are skunkbush sumac, lilac, and Siberian peashrub.

These soils are well suited to wildlife habitat. They are best suited to habitat for openland and rangeland wildlife. Rangeland wildlife, such as pronghorn antelope, can be encouraged by developing livestock watering facilities, properly managing livestock grazing, and reseeding range where needed.

These soils have good potential for use as homesites. The main limitations are steepness of slope, limited ability to support a load, and frost-action potential. Buildings and roads can be designed to overcome these limitations. These soils also require special site or building designs because of the slope. Access roads should have adequate cut-slope grade, and drains should be provided to control surface runoff and keep soil losses to a minimum. Capability subclass VIe.

**70—Pits, gravel.** Gravel pits are in nearly level to rolling areas. They are open excavations several feet deep and commonly 5 acres or less in size.

Gravel pits are very low in natural fertility and are highly susceptible to soil blowing. A cover of weeds or straw helps to control erosion.

Windbreaks and environmental plantings generally are not suited to these areas. Onsite investigation is needed to determine if plantings are feasible. Capability subclass VIIIs.

**71—Pring coarse sandy loam, 3 to 8 percent slopes.** This deep, noncalcareous, well drained soil formed in sandy sediment derived from arkosic sedimentary rock on valley side slopes and on uplands. Elevation ranges from 6,800 to 7,600 feet. The average annual precipitation is about 17 inches, the average annual air temperature is about 43 degrees F, and the average frost-free period is about 120 days.

Typically, the surface layer is dark grayish brown coarse sandy loam about 4 inches thick. The substratum is dark grayish brown coarse sandy loam about 10 inches thick over pale brown gravelly sandy loam that extends to a depth of 60 inches or more.

## **VI. NOAA Atlas 14 Point Precipitation Frequency Estimates**





**NOAA Atlas 14, Volume 8, Version 2**  
**Location name: Colorado Springs, Colorado, USA\***  
**Latitude: 39.1012°, Longitude: -104.6595°**  
**Elevation: m/ft\*\***  
 \* source: ESRI Maps  
 \*\* source: USGS



**POINT PRECIPITATION FREQUENCY ESTIMATES**

Sanja Perica, Deborah Martin, Sandra Pavlovic, Ishani Roy, Michael St. Laurent, Carl Trypaluk, Dale Unruh, Michael Yekta, Geoffery Bonnin

NOAA, National Weather Service, Silver Spring, Maryland

[PF\\_tabular](#) | [PF\\_graphical](#) | [Maps & aerals](#)

**PF tabular**

<b>PDS-based point precipitation frequency estimates with 90% confidence intervals (in inches)<sup>1</sup></b>										
Duration	Average recurrence interval (years)									
	1	2	5	10	25	50	100	200	500	1000
<b>5-min</b>	<b>0.238</b> (0.190-0.301)	<b>0.289</b> (0.230-0.366)	<b>0.378</b> (0.299-0.478)	<b>0.456</b> (0.359-0.579)	<b>0.569</b> (0.437-0.755)	<b>0.663</b> (0.495-0.887)	<b>0.761</b> (0.549-1.04)	<b>0.865</b> (0.598-1.21)	<b>1.01</b> (0.672-1.45)	<b>1.13</b> (0.727-1.64)
<b>10-min</b>	<b>0.349</b> (0.278-0.441)	<b>0.424</b> (0.337-0.535)	<b>0.553</b> (0.439-0.700)	<b>0.667</b> (0.526-0.848)	<b>0.834</b> (0.639-1.11)	<b>0.970</b> (0.725-1.30)	<b>1.11</b> (0.804-1.53)	<b>1.27</b> (0.876-1.78)	<b>1.48</b> (0.984-2.13)	<b>1.65</b> (1.07-2.40)
<b>15-min</b>	<b>0.426</b> (0.339-0.537)	<b>0.517</b> (0.411-0.653)	<b>0.675</b> (0.535-0.854)	<b>0.813</b> (0.641-1.03)	<b>1.02</b> (0.780-1.35)	<b>1.18</b> (0.884-1.58)	<b>1.36</b> (0.980-1.86)	<b>1.54</b> (1.07-2.17)	<b>1.80</b> (1.20-2.60)	<b>2.01</b> (1.30-2.92)
<b>30-min</b>	<b>0.604</b> (0.481-0.762)	<b>0.733</b> (0.583-0.926)	<b>0.955</b> (0.757-1.21)	<b>1.15</b> (0.907-1.46)	<b>1.44</b> (1.10-1.90)	<b>1.67</b> (1.25-2.23)	<b>1.91</b> (1.38-2.62)	<b>2.17</b> (1.50-3.05)	<b>2.53</b> (1.69-3.65)	<b>2.82</b> (1.82-4.10)
<b>60-min</b>	<b>0.764</b> (0.609-0.965)	<b>0.918</b> (0.730-1.16)	<b>1.19</b> (0.945-1.51)	<b>1.44</b> (1.13-1.83)	<b>1.81</b> (1.39-2.41)	<b>2.12</b> (1.59-2.85)	<b>2.45</b> (1.77-3.37)	<b>2.81</b> (1.95-3.95)	<b>3.31</b> (2.21-4.78)	<b>3.72</b> (2.40-5.41)
<b>2-hr</b>	<b>0.925</b> (0.741-1.16)	<b>1.10</b> (0.884-1.38)	<b>1.43</b> (1.14-1.79)	<b>1.73</b> (1.37-2.18)	<b>2.18</b> (1.70-2.89)	<b>2.57</b> (1.94-3.43)	<b>2.99</b> (2.18-4.08)	<b>3.44</b> (2.41-4.82)	<b>4.09</b> (2.75-5.87)	<b>4.61</b> (3.01-6.67)
<b>3-hr</b>	<b>1.01</b> (0.812-1.26)	<b>1.19</b> (0.960-1.49)	<b>1.54</b> (1.23-1.92)	<b>1.87</b> (1.49-2.34)	<b>2.37</b> (1.86-3.14)	<b>2.81</b> (2.14-3.75)	<b>3.29</b> (2.41-4.49)	<b>3.81</b> (2.69-5.34)	<b>4.57</b> (3.10-6.56)	<b>5.20</b> (3.40-7.48)
<b>6-hr</b>	<b>1.17</b> (0.950-1.45)	<b>1.37</b> (1.11-1.70)	<b>1.76</b> (1.42-2.18)	<b>2.13</b> (1.71-2.65)	<b>2.72</b> (2.15-3.59)	<b>3.24</b> (2.49-4.30)	<b>3.81</b> (2.83-5.18)	<b>4.45</b> (3.16-6.20)	<b>5.38</b> (3.67-7.67)	<b>6.14</b> (4.06-8.79)
<b>12-hr</b>	<b>1.37</b> (1.12-1.68)	<b>1.61</b> (1.31-1.97)	<b>2.04</b> (1.66-2.51)	<b>2.47</b> (1.99-3.04)	<b>3.14</b> (2.50-4.10)	<b>3.72</b> (2.88-4.90)	<b>4.37</b> (3.26-5.88)	<b>5.08</b> (3.64-7.02)	<b>6.12</b> (4.22-8.67)	<b>6.98</b> (4.65-9.91)
<b>24-hr</b>	<b>1.61</b> (1.32-1.96)	<b>1.89</b> (1.55-2.30)	<b>2.40</b> (1.97-2.93)	<b>2.88</b> (2.35-3.53)	<b>3.63</b> (2.90-4.68)	<b>4.26</b> (3.31-5.55)	<b>4.95</b> (3.72-6.60)	<b>5.71</b> (4.12-7.81)	<b>6.81</b> (4.72-9.55)	<b>7.70</b> (5.18-10.9)
<b>2-day</b>	<b>1.88</b> (1.55-2.26)	<b>2.22</b> (1.84-2.68)	<b>2.83</b> (2.33-3.42)	<b>3.38</b> (2.77-4.10)	<b>4.20</b> (3.37-5.34)	<b>4.89</b> (3.82-6.28)	<b>5.62</b> (4.24-7.40)	<b>6.41</b> (4.65-8.67)	<b>7.52</b> (5.25-10.4)	<b>8.41</b> (5.71-11.8)
<b>3-day</b>	<b>2.05</b> (1.70-2.45)	<b>2.44</b> (2.02-2.92)	<b>3.11</b> (2.57-3.74)	<b>3.71</b> (3.05-4.48)	<b>4.60</b> (3.69-5.80)	<b>5.32</b> (4.17-6.79)	<b>6.09</b> (4.62-7.97)	<b>6.91</b> (5.03-9.30)	<b>8.06</b> (5.65-11.1)	<b>8.98</b> (6.12-12.5)
<b>4-day</b>	<b>2.20</b> (1.83-2.62)	<b>2.61</b> (2.17-3.11)	<b>3.32</b> (2.75-3.97)	<b>3.95</b> (3.26-4.74)	<b>4.87</b> (3.92-6.12)	<b>5.63</b> (4.42-7.16)	<b>6.43</b> (4.88-8.38)	<b>7.28</b> (5.32-9.75)	<b>8.47</b> (5.96-11.7)	<b>9.41</b> (6.44-13.1)
<b>7-day</b>	<b>2.60</b> (2.18-3.08)	<b>3.03</b> (2.54-3.59)	<b>3.78</b> (3.15-4.49)	<b>4.44</b> (3.68-5.30)	<b>5.42</b> (4.39-6.75)	<b>6.22</b> (4.92-7.85)	<b>7.07</b> (5.41-9.16)	<b>7.98</b> (5.87-10.6)	<b>9.25</b> (6.55-12.7)	<b>10.3</b> (7.07-14.2)
<b>10-day</b>	<b>2.97</b> (2.50-3.50)	<b>3.42</b> (2.87-4.03)	<b>4.21</b> (3.52-4.97)	<b>4.91</b> (4.09-5.83)	<b>5.93</b> (4.82-7.35)	<b>6.77</b> (5.37-8.51)	<b>7.66</b> (5.88-9.87)	<b>8.61</b> (6.36-11.4)	<b>9.93</b> (7.07-13.6)	<b>11.0</b> (7.61-15.2)
<b>20-day</b>	<b>3.99</b> (3.38-4.65)	<b>4.58</b> (3.88-5.35)	<b>5.59</b> (4.71-6.55)	<b>6.45</b> (5.41-7.59)	<b>7.67</b> (6.25-9.36)	<b>8.64</b> (6.88-10.7)	<b>9.63</b> (7.44-12.3)	<b>10.7</b> (7.93-14.0)	<b>12.1</b> (8.66-16.3)	<b>13.2</b> (9.21-18.1)
<b>30-day</b>	<b>4.80</b> (4.08-5.57)	<b>5.53</b> (4.70-6.43)	<b>6.73</b> (5.70-7.84)	<b>7.72</b> (6.51-9.04)	<b>9.10</b> (7.43-11.0)	<b>10.2</b> (8.12-12.5)	<b>11.2</b> (8.70-14.2)	<b>12.3</b> (9.18-16.0)	<b>13.8</b> (9.90-18.5)	<b>14.9</b> (10.4-20.3)
<b>45-day</b>	<b>5.80</b> (4.96-6.70)	<b>6.69</b> (5.71-7.73)	<b>8.10</b> (6.89-9.39)	<b>9.25</b> (7.83-10.8)	<b>10.8</b> (8.83-12.9)	<b>12.0</b> (9.59-14.6)	<b>13.1</b> (10.2-16.4)	<b>14.2</b> (10.6-18.4)	<b>15.7</b> (11.3-20.9)	<b>16.8</b> (11.8-22.8)
<b>60-day</b>	<b>6.64</b> (5.69-7.63)	<b>7.64</b> (6.53-8.79)	<b>9.22</b> (7.86-10.6)	<b>10.5</b> (8.89-12.2)	<b>12.1</b> (9.95-14.5)	<b>13.4</b> (10.7-16.2)	<b>14.6</b> (11.3-18.1)	<b>15.7</b> (11.8-20.2)	<b>17.1</b> (12.4-22.7)	<b>18.2</b> (12.9-24.7)





<sup>1</sup> Precipitation frequency (PF) estimates in this table are based on frequency analysis of partial duration series (PDS). Numbers in parenthesis are PF estimates at lower and upper bounds of the 90% confidence interval. The probability that precipitation frequency estimates (for a given duration and average recurrence interval) will be greater than the upper bound (or less than the lower bound) is 5%. Estimates at upper bounds are not checked against probable maximum precipitation (PMP) estimates and may be higher than currently valid PMP values. Please refer to NOAA Atlas 14 document for more information.

[Back to Top](#)

**PF graphical**

### PDS-based depth-duration-frequency (DDF) curves


Latitude: 39.1012°, Longitude: -104.6595°



[Back to Top](#)

### Maps & aerials


Small scale terrain




Large scale terrain



Large scale map



Large scale aerial



[Back to Top](#)

---

[US Department of Commerce](#)  
[National Oceanic and Atmospheric Administration](#)  
[National Weather Service](#)  
[National Water Center](#)  
1325 East West Highway  
Silver Spring, MD 20910  
Questions?: [HDSC.Questions@noaa.gov](mailto:HDSC.Questions@noaa.gov)

[Disclaimer](#)

## **B. Hydrologic Calculations**

- I. Rational Method: Runoff Coefficients and Percent Imperviousness Table 6-6
- II. Rational Method: Colorado Springs Rainfall Intensity Duration Frequency Figure 6-5
- III. Rational Method: Rural Residential Imperviousness Assumptions
- IV. SCS Method: Curve Number
- V. SCS Method: Overland Flow  $n$
- VI. SCS Method: Shallow Flow  $n$
- VII. SCS Method: Concentrated Flow  $n$
- VIII. Hydrologic Calculations Summary Form SF-1 for Existing & Developed Conditions
- IX. Hydrologic Calculations Summary 5-yr Form SF-2 for Existing & Developed Conditions
- X. Hydrologic Calculations Summary 100-yr Form SF-2 for Existing & Developed Conditions
- XI. CN Calculations
- XII. Time of Concentration Calculations
- XIII. HEC-HMS Calculations Summary 5-yr Existing & Developed Conditions
- XIV. HEC-HMS Calculations Summary 100-yr Existing & Developed Conditions

## **I. Rational Method: Runoff Coefficients**

*Runoff Coefficients and Percent Imperviousness  
Table 6-6, El Paso County DCM*


## **II. Rational Method: Intensity Duration Frequency Curves**

*Rainfall Intensity Duration Frequency Figure 6-5, El  
Paso County DCM*

## **III. Rational Method: Rural Residential Imperviousness Assumptions**



Figure 6-5. Colorado Springs Rainfall Intensity Duration Frequency



**IDF Equations**

$$I_{100} = -2.52 \ln(D) + 12.735$$

$$I_{50} = -2.25 \ln(D) + 11.375$$

$$I_{25} = -2.00 \ln(D) + 10.111$$

$$I_{10} = -1.75 \ln(D) + 8.847$$

$$I_5 = -1.50 \ln(D) + 7.583$$

$$I_2 = -1.19 \ln(D) + 6.035$$

Note: Values calculated by equations may not precisely duplicate values read from figure.

**Table 6-6. Runoff Coefficients for Rational Method**  
(Source: UDFCD 2001)

Land Use or Surface Characteristics	Percent Impervious	Runoff Coefficients											
		2-year		5-year		10-year		25-year		50-year		100-year	
		HSG A&B	HSG C&D	HSG A&B	HSG C&D	HSG A&B	HSG C&D	HSG A&B	HSG C&D	HSG A&B	HSG C&D	HSG A&B	HSG C&D
Business													
Commercial Areas	95	0.79	0.80	0.81	0.82	0.83	0.84	0.85	0.87	0.87	0.88	0.88	0.89
Neighborhood Areas	70	0.45	0.49	0.49	0.53	0.53	0.57	0.58	0.62	0.60	0.65	0.62	0.68
Residential													
1/8 Acre or less	65	0.41	0.45	0.45	0.49	0.49	0.54	0.54	0.59	0.57	0.62	0.59	0.65
1/4 Acre	40	0.23	0.28	0.30	0.35	0.36	0.42	0.42	0.50	0.46	0.54	0.50	0.58
1/3 Acre	30	0.18	0.22	0.25	0.30	0.32	0.38	0.39	0.47	0.43	0.52	0.47	0.57
1/2 Acre	25	0.15	0.20	0.22	0.28	0.30	0.36	0.37	0.46	0.41	0.51	0.46	0.56
1 Acre	20	0.12	0.17	0.20	0.26	0.27	0.34	0.35	0.44	0.40	0.50	0.44	0.55
Industrial													
Light Areas	80	0.57	0.60	0.59	0.63	0.63	0.66	0.66	0.70	0.68	0.72	0.70	0.74
Heavy Areas	90	0.71	0.73	0.73	0.75	0.75	0.77	0.78	0.80	0.80	0.82	0.81	0.83
Parks and Cemeteries	7	0.05	0.09	0.12	0.19	0.20	0.29	0.30	0.40	0.34	0.46	0.39	0.52
Playgrounds	13	0.07	0.13	0.16	0.23	0.24	0.31	0.32	0.42	0.37	0.48	0.41	0.54
Railroad Yard Areas	40	0.23	0.28	0.30	0.35	0.36	0.42	0.42	0.50	0.46	0.54	0.50	0.58
Undeveloped Areas													
Historic Flow Analysis—Greenbelts, Agriculture	2	0.03	0.05	0.09	0.16	0.17	0.26	0.26	0.38	0.31	0.45	0.36	0.51
Pasture/Meadow	0	0.02	0.04	0.08	0.15	0.15	0.25	0.25	0.37	0.30	0.44	0.35	0.50
Forest	0	0.02	0.04	0.08	0.15	0.15	0.25	0.25	0.37	0.30	0.44	0.35	0.50
Exposed Rock	100	0.89	0.89	0.90	0.90	0.92	0.92	0.94	0.94	0.95	0.95	0.96	0.96
Offsite Flow Analysis (when landuse is undefined)	45	0.26	0.31	0.32	0.37	0.38	0.44	0.44	0.51	0.48	0.55	0.51	0.59
Streets													
Paved	100	0.89	0.89	0.90	0.90	0.92	0.92	0.94	0.94	0.95	0.95	0.96	0.96
Gravel	80	0.57	0.60	0.59	0.63	0.63	0.66	0.66	0.70	0.68	0.72	0.70	0.74
Drive and Walks	100	0.89	0.89	0.90	0.90	0.92	0.92	0.94	0.94	0.95	0.95	0.96	0.96
Roofs	90	0.71	0.73	0.73	0.75	0.75	0.77	0.78	0.80	0.80	0.82	0.81	0.83
Lawns	0	0.02	0.04	0.08	0.15	0.15	0.25	0.25	0.37	0.30	0.44	0.35	0.50

Typical Rural Residential Imperviousness Assumptions  
(Rational Method)

Lot Size	Impervious Percent	2-year		5-year		10-year		25-year		50-year		100-year	
		HSG A/B	HSG C/D	HSG A/B	HSG C/D								
2-1/2 Acre	11.00%	0.08	0.12	0.12	0.21	0.22	0.3	0.31	0.41	0.36	0.48	0.4	0.53
5 Acre	7.00%	0.06	0.09	0.10	0.19	0.2	0.28	0.29	0.4	0.34	0.46	0.38	0.52
10+ Acre	2.00%	0.03	0.06	0.09	0.16	0.17	0.26	0.26	0.38	0.31	0.45	0.36	0.51



#### **IV. SCS Method: Curve Number**

*NRCS Curve Numbers (Developed Conditions), Table 6-10, City of Colorado Springs DCM Volume 1*

#### **V. SCS Method: Overland Flow $n$**

*Roughness Coefficients (Manning's  $n$ ) for NRCS Overland Flow, Table 6-11, City of Colorado Springs DCM Volume 1*

#### **VI. SCS Method: Shallow Flow $n$**

*Estimate of Average Concentrated Shallow Flow, Figure 6-13, City of Colorado Springs DCM Volume 1*

#### **VII. SCS Method: Concentrated Flow $n$**

*Roughness Coefficients, Table 12-2, City of Colorado Springs DCM Volume 1*



**Table 6-10. NRCS Curve Numbers for Frontal Storms & Thunderstorms for Developed Conditions (ARCII)**

Fully Developed Urban Areas (vegetation established) <sup>1</sup>	Treatment	Hydrologic Condition	% I	Pre-Development CN				
				HSG A	HSG B	HSG C	HSG D	
Open space (lawns, parks, golf courses, cemeteries, etc.):								
Poor condition (grass cover < 50%)	-----	-----	---	68	79	86	89	
Fair condition (grass cover 50% to 75%)	-----	-----	---	49	69	79	84	
Good condition (grass cover > 75%)	-----	-----	---	39	61	74	80	
Impervious areas:								
Paved parking lots, roofs, driveways, etc. (excluding right-of-way)	-----	-----	---	98	98	98	98	
Streets and roads:								
Paved; curbs and storm sewers (excluding right-of-way)	-----	-----	---	98	98	98	98	
Paved; open ditches (including right-of-way)	-----	-----	---	83	89	92	93	
Gravel (including right-of-way)	-----	-----	---	76	85	89	91	
Dirt (including right-of-way)	-----	-----	---	72	82	87	89	
Western desert urban areas:								
Natural desert landscaping (pervious areas only)	-----	-----	---	63	77	85	88	
Artificial desert landscaping (impervious weed barrier, desert shrub with 1- to 2-inch sand or gravel mulch and basin borders)	-----	-----	---	96	96	96	96	
Urban districts:								
Commercial and business	-----	-----	85	89	92	94	95	
Industrial	-----	-----	72	81	88	91	93	
Residential districts by average lot size:								
1/8 acre or less (town houses)	-----	-----	65	77	85	90	92	
1/4 acre	-----	-----	38	61	75	83	87	
1/3 acre	-----	-----	30	57	72	81	86	
1/2 acre	-----	-----	25	54	70	80	85	
1 acre	-----	-----	20	51	68	79	84	
2 acres	-----	-----	12	46	65	77	82	
<b>Developing Urban Areas<sup>1</sup></b>	<b>Treatment<sup>2</sup></b>	<b>Hydrologic Condition<sup>3</sup></b>	<b>% I</b>	<b>HSG A</b>	<b>HSG B</b>	<b>HSG C</b>	<b>HSG D</b>	
Newly graded areas (pervious areas only, no vegetation)	-----	-----	---	77	86	91	94	
<b>Cultivated Agricultural Lands<sup>1</sup></b>	<b>Treatment</b>	<b>Hydrologic Condition</b>	<b>% I</b>	<b>HSG A</b>	<b>HSG B</b>	<b>HSG C</b>	<b>HSG D</b>	
Fallow	Bare soil	-----	---	77	86	91	94	
	Crop residue cover (CR)	Poor	---	76	85	90	93	
Row crops	Straight row (SR)	Good	---	74	83	88	90	
		Poor	---	72	81	88	91	
	SR + CR	Good	---	67	78	85	89	
		Poor	---	71	80	87	90	
	Contoured (C)	Good	---	64	75	82	85	
		Poor	---	70	79	84	88	
	C + CR	Good	---	65	75	82	86	
		Poor	---	69	78	83	87	
	Contoured & terraced (C&T)	Good	---	64	74	81	85	
		Poor	---	66	74	80	82	
	C&T+ CR	Good	---	62	71	78	81	
		Poor	---	65	73	79	81	
	Small grain	SR	Good	---	61	70	77	80
			Poor	---	65	76	84	88
SR + CR		Good	---	63	75	83	87	
		Poor	---	64	75	83	86	
C		Good	---	60	72	80	84	
		Poor	---	63	74	82	85	
C + CR Poor		Good	---	61	73	81	84	
		Poor	---	62	73	81	84	
C&T		Good	---	60	72	80	83	
		Poor	---	61	72	79	82	
C&T+ CR		Good	---	59	70	78	81	
		Poor	---	60	71	78	81	
				---	58	69	77	80

**Table 6-10. (continued)**

Other Agricultural Lands <sup>1</sup>	Treatment	Hydrologic Condition	% I	HSG A	HSG B	HSG C	HSG D
Pasture, grassland, or range—continuous forage for grazing <sup>4</sup>	-----	Poor	---	68	79	86	89
	-----	Fair	---	49	69	79	84
	-----	Good	---	39	61	74	80
Meadow—continuous grass, protected from grazing and generally mowed for hay	-----	-----	---	30	58	71	78
Brush—brush-weed-grass mixture with brush the major element <sup>5</sup>	-----	Poor	---	48	67	77	83
	-----	Fair	---	35	56	70	77
	-----	Good	---	30	48	65	73
Woods—grass combination (orchard or tree farm) <sup>6</sup>	-----	Poor	---	57	73	82	86
	-----	Fair	---	43	65	76	82
	-----	Good	---	32	58	72	79
Woods <sup>7</sup>	-----	Poor	---	45	66	77	83
	-----	Fair	---	36	60	73	79
	-----	Good	---	30	55	70	77
Farmsteads—buildings, lanes, driveways, and surrounding lots	-----	-----	---	59	74	82	86
Arid and Semi-arid Rangelands <sup>1</sup>	Treatment	Hydrologic Condition <sup>8</sup>	% I	HSG A	HSG B	HSG C	HSG D
Herbaceous—mixture of grass, weeds, and low-growing brush, with brush the minor element	-----	Poor	---	-----	80	87	93
	-----	Fair	---	-----	71	81	89
	-----	Good	---	-----	62	74	85
Oak-aspen—mountain brush mixture of oak brush, aspen, mountain mahogany, bitter brush, maple, and other brush	-----	Poor	---	-----	66	74	79
	-----	Fair	---	-----	48	57	63
	-----	Good	---	-----	30	41	48
Pinyon-juniper—pinyon, juniper, or both; grass understory	-----	Poor	---	-----	75	85	89
	-----	Fair	---	-----	58	73	80
	-----	Good	---	-----	41	61	71
Sagebrush with grass understory	-----	Poor	---	-----	67	80	85
	-----	Fair	---	-----	51	63	70
	-----	Good	---	-----	35	47	55
Desert shrub—major plants include saltbush, greasewood, creosotebush, blackbrush, bursage, palo verde, mesquite, and cactus	-----	Poor	---	63	77	85	88
	-----	Fair	---	55	72	81	86
	-----	Good	---	49	68	79	84

$t_{la} = 0.1 S$

<sup>2</sup> Crop residue cover applies only if residue is on at least 5% of the surface throughout the year.

<sup>3</sup> Hydraulic condition is based on combination factors that affect infiltration and runoff, including (a) density and canopy of vegetative areas, (b) amount of year-round cover, (c) amount of grass or close-seeded legumes, (d) percent of residue cover on the land surface (good ≥ 20%), and (e) degree of surface roughness. Poor: Factors impair infiltration and tend to increase runoff. Good: Factors encourage average and better than average infiltration and tend to decrease runoff.

<sup>4</sup> Poor: <50% ground cover or heavily grazed with no mulch. Fair: 50 to 75% ground cover and not heavily grazed. Good: > 75% ground cover and lightly or only occasional

<sup>5</sup> Poor: <50% ground cover. Fair: 50 to 75% ground cover. Good: >75% ground cover.

<sup>6</sup> CN's shown were computed for areas with 50% woods and 50% grass (pasture) cover. Other combinations of conditions may be computed from the CN's for woods

<sup>7</sup> Poor: Forest litter, small trees, and brush are destroyed by heavy grazing or regular burning. Fair: Woods are grazed but not burned, and some forest litter covers the soil. Good: Woods are protected from grazing, and litter and brush adequately cover the soil.

<sup>8</sup> Poor: <30% ground cover (litter, grass, and brush overstory). Fair: 30 to 70% ground cover. Good: > 70% ground cover.

### 4.6 Lag Time

While the NRCS curve numbers are used to calculate the volume of runoff and magnitude of losses, to transform the volume of runoff into a hydrograph using the NRCS dimensionless unit hydrograph, the lag time must be specified. The lag time is defined as the time from the centroid of the rainfall distribution of a storm to the peak discharge produced by the watershed. For this Manual, the lag time is defined as a fraction of the time of concentration ( $t_c$ ) as shown in Equation 6-13.

$$t_{lag} = 0.6 \cdot t_c \tag{Eq. 6-13}$$

### 4.6.1 Overland Flow Time for NRCS Method

The overland flow time represents the time for runoff to travel over the upper most portion of a drainage basin before there is enough flow to become concentrated into identifiable flow paths. This travel time can be estimated using the slope of the ground and the type of ground cover. Overland flow lengths should not exceed 100 feet for urban areas and 300 feet for undeveloped areas.

$$T_i = 0.007(nL)^{0.8} / (P_2)^{0.5} S^{0.4} \quad (\text{Eq. 6-15})$$

Where:

- $T_i$  = overland flow time (hr)
- $n$  = Manning's roughness coefficient
- $L$  = flow length (ft)
- $P_2$  = 2-year, 24-hour rainfall (in)
- $S$  = slope of hydraulic grade line (ft/ft)

Typical roughness coefficients for the overland flow portion of the drainage basin are provided in Table 6-11. Be aware that Manning's roughness coefficients for overland flow are different from Manning's  $n$  values for open channels and conduits. Manning's  $n$  values for channels and conduits should not be used for overland flow.

**Table 6-11. Roughness Coefficients (Manning's  $n$ ) for NRCS Overland Flow**

Surface description	$n^1$
Smooth surfaces (concrete, asphalt, gravel, bare soil, etc.)	0.011
Fallow (no residue)	0.05
Cultivated Soils:	
Residue cover <20%	0.06
Residue cover >20%	0.17
Grass:	
Short grass prairie	0.15
Dense grasses <sup>2</sup>	0.24
Bermuda grass	0.41
Range (natural)	0.13
Woods <sup>3</sup>	
Light underbrush	0.40
Dense underbrush	0.80

4. <sup>1</sup>The values are a composite of information compiled by Engman (1986).
5. <sup>2</sup>Includes species such as weeping lovegrass, bluegrass, buffalograss, blue gramma grass, native grass mixtures.
6. <sup>3</sup>When selecting  $n$ , consider cover to a height of about 0.1 feet. This is the only part of the plant cover that will obstruct sheet flow.

Figure 6-13. Estimate of Average Concentrated Shallow Flow




Table 12-2. Roughness Coefficients

Channel Description	Roughness Coefficient (n)		
	Minimum	Typical	Maximum
Natural Streams (top width at flood stage <100 feet)			
1. Streams on Plain			
a. Clean, straight, full stage, no rifts or deep pools	0.025	0.030	0.033
b. Same as above, but more stones and weeds	0.030	0.035	0.040
c. Clean, winding, some pools and shoals	0.033	0.040	0.045
d. Same as above, but some weeds and stones	0.035	0.045	0.050
e. Same as above, lower stages, more ineffective slopes and sections	0.040	0.048	0.055
f. Same as c, but more stones	0.045	0.050	0.060
g. Sluggish reaches, weedy, deep pools	0.050	0.070	0.080
h. Very weedy reaches, deep pools, or floodways with heavy stand of timber and underbrush	0.075	0.100	0.150
2. Mountain Streams, no vegetation in channel, banks usually steep, trees and brush along banks submerged at high stages			
a. Bottom: gravels, cobbles, and few boulders	See Jarrett's equation*		
b. Bottom: cobbles with large boulders	See Jarrett's equation*		
Major Streams (top width at flood stage > 100 feet)			
1. Regular section with no boulders or brush	0.025		0.060
2. Irregular and rough section	0.035		0.100
Grass Areas **	**Flow Depth = 0.1-1.5 ft		Flow Depth > 3.0 ft
1. Bermuda grass, buffalo grass, Kentucky bluegrass			
a. Mowed to 2 inches	0.035		0.030
b. Length = 4 to 6 inches	0.040		0.030
2. Good Stand, any grass			
a. Length = 12 inches	0.070		0.035
b. Length = 24 inches	0.100		0.035
3. Fair Stand, any grass			
a. Length = 12 inches	0.060		0.035
b. Length = 24 inches	0.070		0.035

\*Jarrett's equation:  $n = 0.39 S_f^{0.38} R^{-0.16}$ , where  $S_f$  equals friction slope and  $R$  equals the hydraulic radius.

\*\* The  $n$  values shown for the grassed channel at the 0.1- to 1.5-ft depths represent average values for this depth range. Actual  $n$  values vary significantly within this depth range. For more information, see the *Handbook of Channel Design for Soil and Water Conservation* (SCS 1954).

## 2.2 HEC-RAS Analysis

Hydraulic analyses necessary to confirm that design criteria are satisfied can be complicated and often involve variable boundary conditions, various flow rates, a varying water surface profile, irregular channel geometry and crossing structures. Most project conditions require using the USACE's HEC-RAS computer software, which is available free from their website, to adequately assess project conditions. The application of the HEC-RAS computer software shall use model parameters described in this Manual or in the program documentation or justification shall be provided for values used that are not consistent with these documents.

**VIII. Hydrologic Calculations Summary Form SF-1 for Existing & Developed Conditions**

**IX. Hydrologic Calculations Summary 5-yr Form SF-2 for Existing & Developed Conditions**

**X. Hydrologic Calculations Summary 100-yr Form SF-2 for Existing & Developed**



Job No.: **61188**  
 Project: **High Forest Estates**

Date: **5/1/2023 13:56**  
 Calcs By: **O. Ali**  
 Checked By: \_\_\_\_\_

**Time of Concentration** (Modified from Standard Form SF-1)

Sub-Basin	Sub-Basin Data				Overland			Shallow Channel				Channelized				t <sub>c</sub> Check		t <sub>c</sub> (min)
	Area (Acres)	C <sub>5</sub>	C <sub>100</sub> /CN	% Imp.	L <sub>0</sub> (ft)	S <sub>0</sub> (%)	t <sub>i</sub> (min)	L <sub>0t</sub> (ft)	S <sub>0t</sub> (ft/ft)	v <sub>0sc</sub> (ft/s)	t <sub>t</sub> (min)	L <sub>0c</sub> (ft)	S <sub>0c</sub> (ft/ft)	v <sub>0c</sub> (ft/s)	t <sub>c</sub> (min)	L (min)	t <sub>c,alt</sub> (min)	
OS-14	20.95	0.09	0.36	2%	100	3%	12.7	1422	0.082	2.0	11.8	0	0.000	0.0	0.0	1522	18.5	18.5
OS-15	82.59	0.09	0.36	2%	100	1%	18.2	2969	0.039	1.4	35.6	0	0.000	0.0	0.0	3069	27.1	27.1
OS-16	24.31	0.09	0.36	2%	100	1%	18.2	1843	0.075	1.9	16.0	0	0.000	0.0	0.0	1943	20.8	20.8
EX-A1	1.16	0.12	0.38	6%	100	3%	12.3	145	0.048	1.5	1.6	158	0.025	1.7	1.6	403	12.2	12.2
EX-A2	1.11	0.08	0.35	0%	100	10%	8.6	107	0.084	2.0	0.9	168	0.006	1.1	2.5	375	12.1	12.0
EX-A3	4.45	0.10	0.36	3%	100	7%	9.5	630	0.044	1.5	7.1	238	0.017	2.7	1.4	968	15.4	15.4
EX-A4	4.08	0.10	0.36	3%	100	5%	10.6	364	0.036	1.3	4.6	260	0.058	4.3	1.0	724	14.0	14.0
EX-A5	3.56	0.13	0.38	8%	100	5%	10.3	514	0.047	1.5	5.7	118	0.076	4.7	0.4	732	14.1	14.1
A1	1.16	0.12	0.38	6%	100	3%	12.3	145	0.048	1.5	1.6	158	0.025	1.7	1.6	403	12.2	12.2
A2	1.11	0.08	0.35	0%	100	10%	8.6	107	0.084	2.0	0.9	168	0.006	1.1	2.5	375	12.1	12.0
A3	4.45	0.10	0.36	3%	100	7%	9.5	630	0.044	1.5	7.1	238	0.017	2.7	1.4	968	15.4	15.4
A4	4.08	0.10	0.36	3%	100	5%	10.6	364	0.036	1.3	4.6	260	0.058	4.3	1.0	724	14.0	14.0
A5	3.56	0.17	0.41	13%	100	5%	9.9	514	0.047	1.5	5.7	118	0.076	4.8	0.4	732	14.1	14.1



Job No.: **61188**  
 Project: **High Forest Estates**  
 Design Storm: **100-Year Storm (1% Probability)**  
 Jurisdiction: **DCM**

Date: **5/1/2023 13:56**  
 Calcs By: **O. Ali**  
 Checked By: \_\_\_\_\_

**Sub-Basin and Combined Flows** (Modified from Standard Form SF-2)

DP	Sub-Basin	Area (Acres)	C100	Direct Runoff				Combined Runoff				Streetflow			Pipe Flow					Travel Time		
				t <sub>c</sub> (min)	CA (Acres)	I100 (in/hr)	Q100 (cfs)	t <sub>c</sub> (min)	CA (Acres)	I100 (in/hr)	Q100 (cfs)	Slope (%)	Length (ft)	Q (cfs)	Q (cfs)	Slope (%)	Mnngs n	Length (ft)	D <sub>Pipe</sub> (in)	Length (ft)	V <sub>0.5c</sub> (ft/s)	t <sub>t</sub> (min)
	OS-14	20.95	0.36	18.5	7.54	5.39	40.63															
	OS-15	82.59	0.36	27.1	29.85	4.42	132.08															
	OS-16	24.31	0.36	20.8	8.75	5.09	44.52															
	EX-A1	1.16	0.38	12.2	0.44	6.42	2.81															
	EX-A2	1.11	0.35	12.0	0.39	6.47	2.52															
	EX-A3	4.45	0.36	15.4	1.62	5.85	9.46															
	EX-A4	4.08	0.36	14.0	1.48	6.08	9.01															
	EX-A5	3.56	0.38	14.1	1.37	6.07	8.32															
	A1	1.16	0.38	12.2	0.44	6.42	2.81															
	A2	1.11	0.35	12.0	0.39	6.47	2.52															
	A3	4.45	0.36	15.4	1.62	5.85	9.46															
	A4	4.08	0.36	14.0	1.48	6.08	9.01															
	A5	3.56	0.41	14.1	1.46	6.07	8.85															

DCM:  $I = C1 * \ln(tc) + C2$   
 C1: 2.52  
 C1: 12.735

## Sub-Basin OS-14 Runoff Calculations

Job No.: 61188  
 Project: High Forest Estates  
 Jurisdiction: DCM  
 Runoff Coefficient: Surface Type

Date: 5/1/2023 13:56  
 Calcs by: O. Ali  
 Checked by: \_\_\_\_\_  
 Soil Type: B  
 Urbanization: Urban

### Basin Land Use Characteristics

Surface	Area		Runoff Coefficient						% Imperv.
	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	
5 Acre	-	0.00	0.06	0.1	0.2	0.29	0.34	0.38	7%
10+ Acre	912,380	20.95	0.03	0.09	0.17	0.26	0.31	0.36	2%
<b>Combined</b>	<b>912,380</b>	<b>20.95</b>	<b>0.03</b>	<b>0.09</b>	<b>0.17</b>	<b>0.26</b>	<b>0.31</b>	<b>0.36</b>	<b>2.0%</b>

912,380

### Basin Travel Time

	Shallow Channel	Ground Cover	Short Pasture/Lawns				
	$L_{max,Overland}$	100 ft	$C_v$	7			
	L (ft)	$\Delta Z_0$ (ft)	$S_0$ (ft/ft)	v (ft/s)	t (min)	$t_{Alt}$ (min)	
Total	1,522	120	-	-	-	-	
Initial Time	100	3	0.030	-	12.7	18.5	DCM Eq. 6-8
Shallow Channel	1,422	117	0.082	2.0	11.8	-	DCM Eq. 6-9
Channelized			0.000	0.0	0.0	-	Trap Ditch
				$t_c$	<b>18.5 min.</b>		

### Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
<b>Intensity (in/hr)</b>	2.57	3.21	3.75	4.28	4.82	5.39
<b>Runoff (cfs)</b>	1.6	<b>6.1</b>	13.3	23.3	31.3	<b>40.6</b>
<b>Release Rates (cfs/ac)</b>	-	-	-	-	-	-
<b>Allowed Release (cfs)</b>	1.6	<b>6.1</b>	13.3	23.3	31.3	<b>40.6</b>

DCM:  $I = C1 * \ln(tc) + C2$

C1	1.19	1.5	1.75	2	2.25	2.52
C2	6.035	7.583	8.847	10.111	11.375	12.735

### Notes

## Sub-Basin OS-15 Runoff Calculations

Job No.: 61188  
 Project: High Forest Estates  
 Jurisdiction: DCM  
 Runoff Coefficient: Surface Type

Date: 5/1/2023 13:56  
 Calcs by: O. Ali  
 Checked by: \_\_\_\_\_  
 Soil Type: B  
 Urbanization: Urban

### Basin Land Use Characteristics

Surface	Area		Runoff Coefficient						% Imperv.
	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	
5 Acre	252,685	5.80	0.06	0.1	0.2	0.29	0.34	0.38	7%
10+ Acre	3,345,087	76.79	0.03	0.09	0.17	0.26	0.31	0.36	2%
<b>Combined</b>	<b>3,597,772</b>	<b>82.59</b>	<b>0.03</b>	<b>0.09</b>	<b>0.17</b>	<b>0.26</b>	<b>0.31</b>	<b>0.36</b>	<b>2.4%</b>

3,597,772

### Basin Travel Time

	Shallow Channel	Ground Cover	Short Pasture/Lawns				
	$L_{max,Overland}$	100 ft	$C_v$	7			
	L (ft)	$\Delta Z_0$ (ft)	$S_0$ (ft/ft)	v (ft/s)	t (min)	$t_{Alt}$ (min)	
Total	3,069	118	-	-	-	-	
Initial Time	100	1	0.010	-	18.2	27.1	DCM Eq. 6-8
Shallow Channel	2,969	117	0.039	1.4	35.6	-	DCM Eq. 6-9
Channelized			0.000	0.0	0.0	-	Trap Ditch
				$t_c$	<b>27.1 min.</b>		

### Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
<b>Intensity (in/hr)</b>	2.11	2.64	3.08	3.52	3.96	4.42
<b>Runoff (cfs)</b>	5.6	<b>19.8</b>	43.7	76.1	102.0	<b>132.1</b>
<b>Release Rates (cfs/ac)</b>	-	-	-	-	-	-
<b>Allowed Release (cfs)</b>	5.6	<b>19.8</b>	43.7	76.1	102.0	<b>132.1</b>

DCM:  $I = C1 * \ln(tc) + C2$

C1	1.19	1.5	1.75	2	2.25	2.52
C2	6.035	7.583	8.847	10.111	11.375	12.735

### Notes

## Sub-Basin OS-16 Runoff Calculations

Job No.: 61188  
 Project: High Forest Estates  
 Jurisdiction: DCM  
 Runoff Coefficient: Surface Type

Date: 5/1/2023 13:56  
 Calcs by: O. Ali  
 Checked by: \_\_\_\_\_  
 Soil Type: B  
 Urbanization: Urban

### Basin Land Use Characteristics

Surface	Area		Runoff Coefficient						% Imperv.
	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	
5 Acre	-	0.00	0.06	0.1	0.2	0.29	0.34	0.38	7%
10+ Acre	1,058,946	24.31	0.03	0.09	0.17	0.26	0.31	0.36	2%
<b>Combined</b>	<b>1,058,946</b>	<b>24.31</b>	<b>0.03</b>	<b>0.09</b>	<b>0.17</b>	<b>0.26</b>	<b>0.31</b>	<b>0.36</b>	<b>2.0%</b>

1,058,946

### Basin Travel Time

	Shallow Channel	Ground Cover	Short Pasture/Lawns				
	$L_{max,Overland}$	100 ft	$C_v$	7			
	$L$ (ft)	$\Delta Z_0$ (ft)	$S_0$ (ft/ft)	$v$ (ft/s)	$t$ (min)	$t_{Alt}$ (min)	
Total	1,943	140	-	-	-	-	
Initial Time	100	1	0.010	-	18.2	20.8	DCM Eq. 6-8
Shallow Channel	1,843	139	0.075	1.9	16.0	-	DCM Eq. 6-9
Channelized			0.000	0.0	0.0	-	Trap Ditch
				$t_c$	<b>20.8 min.</b>		

### Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
<b>Intensity (in/hr)</b>	2.42	3.03	3.54	4.04	4.55	5.09
<b>Runoff (cfs)</b>	1.8	<b>6.6</b>	14.6	25.5	34.3	<b>44.5</b>
<b>Release Rates (cfs/ac)</b>	-	-	-	-	-	-
<b>Allowed Release (cfs)</b>	1.8	<b>6.6</b>	14.6	25.5	34.3	<b>44.5</b>

DCM:  $I = C1 * \ln(tc) + C2$

C1	1.19	1.5	1.75	2	2.25	2.52
C2	6.035	7.583	8.847	10.111	11.375	12.735

### Notes

## Sub-Basin EX-A1 Runoff Calculations

Job No.: 61188  
 Project: High Forest Estates  
 Jurisdiction: DCM  
 Runoff Coefficient: Surface Type

Date: 5/1/2023 13:56  
 Calcs by: O. Ali  
 Checked by: \_\_\_\_\_  
 Soil Type: B  
 Urbanization: Urban

### Basin Land Use Characteristics

Surface	Area		Runoff Coefficient						% Imperv.
	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	
Pasture/Meadow	46,789	1.07	0.02	0.08	0.15	0.25	0.3	0.35	0%
Gravel	3,862	0.09	0.57	0.59	0.63	0.66	0.68	0.7	80%
<b>Combined</b>	<b>50,651</b>	<b>1.16</b>	<b>0.06</b>	<b>0.12</b>	<b>0.19</b>	<b>0.28</b>	<b>0.33</b>	<b>0.38</b>	<b>6.1%</b>

50,651

### Basin Travel Time

	Shallow Channel	Ground Cover	Short Pasture/Lawns				
$L_{max,Overland}$	100	ft	$C_v$	7			
$L$ (ft)	$\Delta Z_0$ (ft)	$S_0$ (ft/ft)	$v$ (ft/s)	$t$ (min)	$t_{Alt}$ (min)		
Total	403	14	-	-	-		
Initial Time	100	3	0.030	-	12.3	12.2	DCM Eq. 6-8
Shallow Channel	145	7	0.048	1.5	1.6	-	DCM Eq. 6-9
Channelized	158	4	0.025	1.7	1.6	-	V-Ditch
				$t_c$	<b>12.2 min.</b>		

### Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
Intensity (in/hr)	3.05	3.83	4.46	5.10	5.74	6.42
Runoff (cfs)	0.2	<b>0.5</b>	1.0	1.7	2.2	<b>2.8</b>
Release Rates (cfs/ac)	-	-	-	-	-	-
Allowed Release (cfs)	0.2	<b>0.5</b>	1.0	1.7	2.2	<b>2.8</b>

DCM:  $I = C1 * \ln(tc) + C2$

C1	1.19	1.5	1.75	2	2.25	2.52
C2	6.035	7.583	8.847	10.111	11.375	12.735

### Notes

## Sub-Basin EX-A2 Runoff Calculations

Job No.: 61188  
 Project: High Forest Estates  
 Jurisdiction: DCM  
 Runoff Coefficient: Surface Type

Date: 5/1/2023 13:56  
 Calcs by: O. Ali  
 Checked by: \_\_\_\_\_  
 Soil Type: B  
 Urbanization: Urban

### Basin Land Use Characteristics

Surface	Area		Runoff Coefficient						% Imperv.
	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	
Pasture/Meadow	48,478	1.11	0.02	0.08	0.15	0.25	0.3	0.35	0%
<b>Combined</b>	<b>48,478</b>	<b>1.11</b>	<b>0.02</b>	<b>0.08</b>	<b>0.15</b>	<b>0.25</b>	<b>0.30</b>	<b>0.35</b>	<b>0.0%</b>

### Basin Travel Time

	Shallow Channel Ground Cover		Short Pasture/Lawns			
	$L_{max,Overland}$	100 ft			$C_v$	7
	L (ft)	$\Delta Z_0$ (ft)	$S_0$ (ft/ft)	v (ft/s)	t (min)	$t_{Alt}$ (min)
Total	375	20	-	-	-	-
Initial Time	100	10	0.100	-	8.6	12.1 DCM Eq. 6-8
Shallow Channel	107	9	0.084	2.0	0.9	- DCM Eq. 6-9
Channelized	168	1	0.006	1.1	2.5	- V-Ditch
				$t_c$	<b>12.0 min.</b>	

### Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
<b>Intensity (in/hr)</b>	3.08	3.85	4.50	5.14	5.78	6.47
<b>Runoff (cfs)</b>	0.1	<b>0.3</b>	0.8	1.4	1.9	<b>2.5</b>
<b>Release Rates (cfs/ac)</b>	-	-	-	-	-	-
<b>Allowed Release (cfs)</b>	0.1	<b>0.3</b>	0.8	1.4	1.9	<b>2.5</b>

DCM:  $I = C1 * \ln(tc) + C2$

C1	1.19	1.5	1.75	2	2.25	2.52
C2	6.035	7.583	8.847	10.111	11.375	12.735

### Notes

## Sub-Basin EX-A3 Runoff Calculations

Job No.: 61188  
 Project: High Forest Estates  
 Jurisdiction: DCM  
 Runoff Coefficient: Surface Type

Date: 5/1/2023 13:56  
 Calcs by: O. Ali  
 Checked by: \_\_\_\_\_  
 Soil Type: B  
 Urbanization: Urban

### Basin Land Use Characteristics

Surface	Area		Runoff Coefficient						% Imperv.
	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	
Pasture/Meadow	188,150	4.32	0.02	0.08	0.15	0.25	0.3	0.35	0%
Roofs	4,693	0.11	0.71	0.73	0.75	0.78	0.8	0.81	90%
Gravel	1,123	0.03	0.57	0.59	0.63	0.66	0.68	0.7	80%
<b>Combined</b>	<b>193,966</b>	<b>4.45</b>	<b>0.04</b>	<b>0.10</b>	<b>0.17</b>	<b>0.27</b>	<b>0.31</b>	<b>0.36</b>	<b>2.6%</b>

193,966

### Basin Travel Time

	Shallow Channel Ground Cover		Short Pasture/Lawns			
	$L_{max,Overland}$	100 ft			$C_v$	7
	L (ft)	$\Delta Z_0$ (ft)	$S_0$ (ft/ft)	v (ft/s)	t (min)	$t_{Alt}$ (min)
Total	968	39	-	-	-	-
Initial Time	100	7	0.070	-	9.5	15.4 DCM Eq. 6-8
Shallow Channel	630	28	0.044	1.5	7.1	- DCM Eq. 6-9
Channelized	238	4	0.017	2.7	1.4	- V-Ditch
				$t_c$	<b>15.4 min.</b>	

### Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
<b>Intensity (in/hr)</b>	2.78	3.48	4.06	4.65	5.23	5.85
<b>Runoff (cfs)</b>	0.5	1.5	3.0	5.5	7.3	9.5
<b>Release Rates (cfs/ac)</b>	-	-	-	-	-	-
<b>Allowed Release (cfs)</b>	0.5	1.5	3.0	5.5	7.3	9.5

DCM:  $I = C1 * \ln(tc) + C2$

C1	1.19	1.5	1.75	2	2.25	2.52
C2	6.035	7.583	8.847	10.111	11.375	12.735

### Notes

## Sub-Basin EX-A4 Runoff Calculations

Job No.: 61188  
 Project: High Forest Estates  
 Jurisdiction: DCM  
 Runoff Coefficient: Surface Type

Date: 5/1/2023 13:56  
 Calcs by: O. Ali  
 Checked by: \_\_\_\_\_  
 Soil Type: B  
 Urbanization: Urban

### Basin Land Use Characteristics

Surface	Area		Runoff Coefficient						% Imperv.
	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	
Pasture/Meadow	171,167	3.93	0.02	0.08	0.15	0.25	0.3	0.35	0%
Gravel	6,659	0.15	0.57	0.59	0.63	0.66	0.68	0.7	80%
<b>Combined</b>	<b>177,826</b>	<b>4.08</b>	<b>0.04</b>	<b>0.10</b>	<b>0.17</b>	<b>0.27</b>	<b>0.31</b>	<b>0.36</b>	<b>3.0%</b>

177,826

### Basin Travel Time

	Shallow Channel Ground Cover		Short Pasture/Lawns				
	$L_{max,Overland}$ (ft)	$\Delta Z_0$ (ft)	$S_0$ (ft/ft)	$v$ (ft/s)	$t$ (min)	$t_{Alt}$ (min)	
Total	724	33	-	-	-	-	
Initial Time	100	5	0.050	-	10.6	14.0	DCM Eq. 6-8
Shallow Channel	364	13	0.036	1.3	4.6	-	DCM Eq. 6-9
Channelized	260	15	0.058	4.3	1.0	-	V-Ditch
				$t_c$	<b>14.0 min.</b>		

### Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
Intensity (in/hr)	2.89	3.62	4.23	4.83	5.43	6.08
Runoff (cfs)	0.5	1.5	2.9	5.2	7.0	9.0
Release Rates (cfs/ac)	-	-	-	-	-	-
Allowed Release (cfs)	0.5	1.5	2.9	5.2	7.0	9.0

DCM:  $I = C1 * \ln(tc) + C2$

C1	1.19	1.5	1.75	2	2.25	2.52
C2	6.035	7.583	8.847	10.111	11.375	12.735

### Notes

## Sub-Basin EX-A5 Runoff Calculations

Job No.: 61188  
 Project: High Forest Estates  
 Jurisdiction: DCM  
 Runoff Coefficient: Surface Type

Date: 5/1/2023 13:56  
 Calcs by: O. Ali  
 Checked by: \_\_\_\_\_  
 Soil Type: B  
 Urbanization: Urban

### Basin Land Use Characteristics

Surface	Area		Runoff Coefficient						% Imperv.
	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	
Pasture/Meadow	139,638	3.21	0.02	0.08	0.15	0.25	0.3	0.35	0%
Gravel	15,451	0.35	0.57	0.59	0.63	0.66	0.68	0.7	80%
<b>Combined</b>	<b>155,089</b>	<b>3.56</b>	<b>0.07</b>	<b>0.13</b>	<b>0.20</b>	<b>0.29</b>	<b>0.34</b>	<b>0.38</b>	<b>8.0%</b>

155,089

### Basin Travel Time

	Shallow Channel	Ground Cover	Short Pasture/Lawns				
$L_{max,Overland}$	100	ft	$C_v$	7			
$L$ (ft)	$\Delta Z_0$ (ft)	$S_0$ (ft/ft)	$v$ (ft/s)	$t$ (min)	$t_{Alt}$ (min)		
Total	732	38	-	-	-		
Initial Time	100	5	0.050	-	10.3	14.1	DCM Eq. 6-8
Shallow Channel	514	24	0.047	1.5	5.7	-	DCM Eq. 6-9
Channelized	118	9	0.076	4.7	0.4	-	V-Ditch
				$t_c$	<b>14.1 min.</b>		

### Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
Intensity (in/hr)	2.89	3.62	4.22	4.82	5.43	6.07
Runoff (cfs)	0.8	1.7	3.0	5.0	6.5	8.3
Release Rates (cfs/ac)	-	-	-	-	-	-
Allowed Release (cfs)	0.8	1.7	3.0	5.0	6.5	8.3

DCM:  $I = C1 * \ln(tc) + C2$

C1	1.19	1.5	1.75	2	2.25	2.52
C2	6.035	7.583	8.847	10.111	11.375	12.735

### Notes

## Sub-Basin A1 Runoff Calculations

Job No.: 61188  
 Project: High Forest Estates  
 Jurisdiction: DCM  
 Runoff Coefficient: Surface Type

Date: 5/1/2023 13:56  
 Calcs by: O. Ali  
 Checked by: \_\_\_\_\_  
 Soil Type: B  
 Urbanization: Urban

### Basin Land Use Characteristics

Surface	Area		Runoff Coefficient						% Imperv.
	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	
Pasture/Meadow	46,789	1.07	0.02	0.08	0.15	0.25	0.3	0.35	0%
Gravel	3,862	0.09	0.57	0.59	0.63	0.66	0.68	0.7	80%
<b>Combined</b>	<b>50,651</b>	<b>1.16</b>	<b>0.06</b>	<b>0.12</b>	<b>0.19</b>	<b>0.28</b>	<b>0.33</b>	<b>0.38</b>	<b>6.1%</b>

50,651

### Basin Travel Time

	Shallow Channel	Ground Cover	Short Pasture/Lawns				
$L_{max,Overland}$	100	ft	$C_v$	7			
$L$ (ft)	$\Delta Z_0$ (ft)	$S_0$ (ft/ft)	$v$ (ft/s)	$t$ (min)	$t_{Alt}$ (min)		
Total	403	14	-	-	-		
Initial Time	100	3	0.030	-	12.3	12.2	DCM Eq. 6-8
Shallow Channel	145	7	0.048	1.5	1.6	-	DCM Eq. 6-9
Channelized	158	4	0.025	1.7	1.6	-	V-Ditch
				$t_c$	<b>12.2 min.</b>		

### Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
Intensity (in/hr)	3.05	3.83	4.46	5.10	5.74	6.42
Runoff (cfs)	0.2	<b>0.5</b>	1.0	1.7	2.2	<b>2.8</b>
Release Rates (cfs/ac)	-	-	-	-	-	-
Allowed Release (cfs)	0.2	<b>0.5</b>	1.0	1.7	2.2	<b>2.8</b>

DCM:  $I = C1 * \ln(tc) + C2$

C1	1.19	1.5	1.75	2	2.25	2.52
C2	6.035	7.583	8.847	10.111	11.375	12.735

### Notes

## Sub-Basin A2 Runoff Calculations

Job No.: 61188  
 Project: High Forest Estates  
 Jurisdiction: DCM  
 Runoff Coefficient: Surface Type

Date: 5/1/2023 13:56  
 Calcs by: O. Ali  
 Checked by: \_\_\_\_\_  
 Soil Type: B  
 Urbanization: Urban

### Basin Land Use Characteristics

Surface	Area		Runoff Coefficient						% Imperv.
	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	
Pasture/Meadow	48,478	1.11	0.02	0.08	0.15	0.25	0.3	0.35	0%
<b>Combined</b>	<b>48,478</b>	<b>1.11</b>	<b>0.02</b>	<b>0.08</b>	<b>0.15</b>	<b>0.25</b>	<b>0.30</b>	<b>0.35</b>	<b>0.0%</b>

48,478

### Basin Travel Time

	Shallow Channel	Ground Cover	Short Pasture/Lawns			
	$L_{max,Overland}$	100 ft			$C_v$	7
	L (ft)	$\Delta Z_0$ (ft)	$S_0$ (ft/ft)	v (ft/s)	t (min)	$t_{Alt}$ (min)
Total	375	20	-	-	-	-
Initial Time	100	10	0.100	-	8.6	12.1 DCM Eq. 6-8
Shallow Channel	107	9	0.084	2.0	0.9	- DCM Eq. 6-9
Channelized	168	1	0.006	1.1	2.5	- V-Ditch
				$t_c$	<b>12.0 min.</b>	

### Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
<b>Intensity (in/hr)</b>	3.08	3.85	4.50	5.14	5.78	6.47
<b>Runoff (cfs)</b>	0.1	<b>0.3</b>	0.8	1.4	1.9	<b>2.5</b>
<b>Release Rates (cfs/ac)</b>	-	-	-	-	-	-
<b>Allowed Release (cfs)</b>	0.1	<b>0.3</b>	0.8	1.4	1.9	<b>2.5</b>

DCM:  $I = C1 * \ln(tc) + C2$

C1	1.19	1.5	1.75	2	2.25	2.52
C2	6.035	7.583	8.847	10.111	11.375	12.735

### Notes

## Sub-Basin A3 Runoff Calculations

Job No.: 61188  
 Project: High Forest Estates  
 Jurisdiction: DCM  
 Runoff Coefficient: Surface Type

Date: 5/1/2023 13:56  
 Calcs by: O. Ali  
 Checked by: \_\_\_\_\_  
 Soil Type: B  
 Urbanization: Urban

### Basin Land Use Characteristics

Surface	Area		Runoff Coefficient						% Imperv.
	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	
Pasture/Meadow	188,150	4.32	0.02	0.08	0.15	0.25	0.3	0.35	0%
Roofs	4,693	0.11	0.71	0.73	0.75	0.78	0.8	0.81	90%
Gravel	1,123	0.03	0.57	0.59	0.63	0.66	0.68	0.7	80%
<b>Combined</b>	<b>193,966</b>	<b>4.45</b>	<b>0.04</b>	<b>0.10</b>	<b>0.17</b>	<b>0.27</b>	<b>0.31</b>	<b>0.36</b>	<b>2.6%</b>

193,966

### Basin Travel Time

	Shallow Channel Ground Cover		Short Pasture/Lawns			
	$L_{max,Overland}$	100 ft	$C_v$	7		
	L (ft)	$\Delta Z_0$ (ft)	$S_0$ (ft/ft)	v (ft/s)	t (min)	$t_{Alt}$ (min)
Total	968	39	-	-	-	-
Initial Time	100	7	0.070	-	9.5	15.4 DCM Eq. 6-8
Shallow Channel	630	28	0.044	1.5	7.1	- DCM Eq. 6-9
Channelized	238	4	0.017	2.7	1.4	- V-Ditch
<b><math>t_c</math></b>					<b>15.4 min.</b>	

### Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
<b>Intensity (in/hr)</b>	2.78	3.48	4.06	4.65	5.23	5.85
<b>Runoff (cfs)</b>	0.5	1.5	3.0	5.5	7.3	9.5
<b>Release Rates (cfs/ac)</b>	-	-	-	-	-	-
<b>Allowed Release (cfs)</b>	0.5	1.5	3.0	5.5	7.3	9.5

DCM:  $I = C1 * \ln(tc) + C2$

C1	1.19	1.5	1.75	2	2.25	2.52
C2	6.035	7.583	8.847	10.111	11.375	12.735

### Notes

## Sub-Basin A4 Runoff Calculations

Job No.: 61188  
 Project: High Forest Estates  
 Jurisdiction: DCM  
 Runoff Coefficient: Surface Type

Date: 5/1/2023 13:56  
 Calcs by: O. Ali  
 Checked by: \_\_\_\_\_  
 Soil Type: B  
 Urbanization: Urban

### Basin Land Use Characteristics

Surface	Area		Runoff Coefficient						% Imperv.
	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	
Pasture/Meadow	171,167	3.93	0.02	0.08	0.15	0.25	0.3	0.35	0%
Gravel	6,659	0.15	0.57	0.59	0.63	0.66	0.68	0.7	80%
<b>Combined</b>	<b>177,826</b>	<b>4.08</b>	<b>0.04</b>	<b>0.10</b>	<b>0.17</b>	<b>0.27</b>	<b>0.31</b>	<b>0.36</b>	<b>3.0%</b>

177,826

### Basin Travel Time

	Shallow Channel Ground Cover		Short Pasture/Lawns				
	$L_{max,Overland}$	100 ft	$C_v$	7			
	L (ft)	$\Delta Z_0$ (ft)	$S_0$ (ft/ft)	v (ft/s)	t (min)	$t_{Alt}$ (min)	
Total	724	33	-	-	-	-	
Initial Time	100	5	0.050	-	10.6	14.0	DCM Eq. 6-8
Shallow Channel	364	13	0.036	1.3	4.6	-	DCM Eq. 6-9
Channelized	260	15	0.058	4.3	1.0	-	V-Ditch
				$t_c$	<b>14.0 min.</b>		

### Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
<b>Intensity (in/hr)</b>	2.89	3.62	4.23	4.83	5.43	6.08
<b>Runoff (cfs)</b>	0.5	1.5	2.9	5.2	7.0	9.0
<b>Release Rates (cfs/ac)</b>	-	-	-	-	-	-
<b>Allowed Release (cfs)</b>	0.5	1.5	2.9	5.2	7.0	9.0

DCM:  $I = C1 * \ln(tc) + C2$

C1	1.19	1.5	1.75	2	2.25	2.52
C2	6.035	7.583	8.847	10.111	11.375	12.735

### Notes

## Sub-Basin A5 Runoff Calculations

Job No.: 61188  
 Project: High Forest Estates  
 Jurisdiction: DCM  
 Runoff Coefficient: Surface Type

Date: 5/1/2023 13:56  
 Calcs by: O. Ali  
 Checked by: \_\_\_\_\_  
 Soil Type: B  
 Urbanization: Urban

### Basin Land Use Characteristics

Surface	Area		Runoff Coefficient						% Imperv.
	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	
Pasture/Meadow	131,138	3.01	0.02	0.08	0.15	0.25	0.3	0.35	0%
Gravel	15,451	0.35	0.57	0.59	0.63	0.66	0.68	0.7	80%
Roofs	5,100	0.12	0.71	0.73	0.75	0.78	0.8	0.81	90%
Gravel	2,400	0.06	0.57	0.59	0.63	0.66	0.68	0.7	80%
Paved	1,000	0.02	0.89	0.9	0.92	0.94	0.95	0.96	100%
<b>Combined</b>	<b>155,089</b>	<b>3.56</b>	<b>0.11</b>	<b>0.17</b>	<b>0.23</b>	<b>0.32</b>	<b>0.36</b>	<b>0.41</b>	<b>12.8%</b>

155,089

### Basin Travel Time

	Shallow Channel	Ground Cover	Short Pasture/Lawns				
$L_{max,Overland}$	100	ft	$C_v$	7			
$L$ (ft)	$\Delta Z_0$ (ft)	$S_0$ (ft/ft)	$v$ (ft/s)	$t$ (min)	$t_{Alt}$ (min)		
Total	732	38	-	-	-		
Initial Time	100	5	0.050	-	9.9	14.1	DCM Eq. 6-8
Shallow Channel	514	24	0.047	1.5	5.7	-	DCM Eq. 6-9
Channelized	118	9	0.076	4.8	0.4	-	V-Ditch
				$t_c$	<b>14.1 min.</b>		

### Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
<b>Intensity (in/hr)</b>	2.89	3.62	4.22	4.82	5.43	6.07
<b>Runoff (cfs)</b>	1.1	2.1	3.5	5.5	7.0	8.9
<b>Release Rates (cfs/ac)</b>	-	-	-	-	-	-
<b>Allowed Release (cfs)</b>	1.1	2.1	3.5	5.5	7.0	8.9

DCM:  $I = C1 * \ln(tc) + C2$

C1	1.19	1.5	1.75	2	2.25	2.52
C2	6.035	7.583	8.847	10.111	11.375	12.735

### Notes

## **XI. CN Calculations**

## **XII. Time of Concentration Calculations**





High Forest Estates Subdivision  
 Off-Site Basins  
 M.V.E., Inc.  
 April 19, 2023

NRCS Curve Number Calculations

Basin	Basin Area (Sq Mi)	Basin Area (Ac)	Predominant Soil Type	Land Use (Type)	Land Use (Ac)	Land Use (CN)	Land Use (Type)	Land Use (Ac)	Land Use (CN)	Composite (CN)	Initial Abstraction (in)
1	0.112	71.7	B	5 acre	20.34	74	10+ acre	51.40	69	70.4	0.42
2	0.225	143.8	B	5 acre	74.42	74	10+ acre	69.41	69	71.6	0.40
3	0.066	41.9	B	5 acre	22.30	74	10+ acre	19.64	69	71.7	0.40
4	0.226	144.6	B	5 acre	132.84	74	10+ acre	11.75	69	73.6	0.36
5	0.071	45.3	B	5 acre	12.89	74	10+ acre	32.36	69	70.4	0.42
6	0.043	27.7	B	5 acre	4.51	74	10+ acre	23.15	69	69.8	0.43
7	0.042	27.2	B	5 acre	5.77	74	10+ acre	21.39	69	70.1	0.43
8	0.076	48.6	B	5 acre	38.15	74	10+ acre	10.46	69	72.9	0.37
9	0.143	91.8	B	5 acre	59.26	74	10+ acre	32.57	69	72.2	0.38
10	0.091	58.2	B	5 acre	17.02	74	10+ acre	41.13	69	70.5	0.42
11	0.141	90.1	B	5 acre	26.26	74	10+ acre	63.81	69	70.5	0.42
12	0.035	22.7	B	5 acre	2.32	74	10+ acre	20.36	69	69.5	0.44
13	0.077	49.5	B	5 acre	18.11	74	10+ acre	31.34	69	70.8	0.41
14	0.039	25.0	B	5 acre	0.00	74	10+ acre	25.03	69	69.0	0.45
15	0.131	83.8	B	5 acre	5.80	74	10+ acre	77.96	69	69.3	0.44
16	0.044	27.9	B	5 acre	0.00	74	10+ acre	27.87	69	69.0	0.45

999.6 Total AC.

Weighted Average CN = 71.2



High Forest Estates Subdivision  
 Off-Site Basins  
 M.V.E., Inc.  
 April 19, 2023

NRCS Curve Number Calculations

**DEVELOPED**

Basin	Basin Area (Sq Mi)	Basin Area (Ac)	Predominant Soil Type	Land Use (Type)	Land Use (Ac)	Land Use (CN)	Land Use (Type)	Land Use (Ac)	Land Use (CN)	Composite (CN)	Initial Abstraction (in)
1	0.112	71.7	B	5 acre	20.34	74	10+ acre	51.40	69	70.4	0.42
2	0.225	143.8	B	5 acre	74.42	74	10+ acre	69.41	69	71.6	0.40
3	0.066	41.9	B	5 acre	22.30	74	10+ acre	19.64	69	71.7	0.40
4	0.226	144.6	B	5 acre	132.84	74	10+ acre	11.75	69	73.6	0.36
5	0.071	45.3	B	5 acre	12.89	74	10+ acre	32.36	69	70.4	0.42
6	0.043	27.7	B	5 acre	4.98	74	10+ acre	22.68	69	69.9	0.43
7	0.042	27.2	B	5 acre	6.15	74	10+ acre	21.01	69	70.1	0.43
8	0.076	48.6	B	5 acre	38.15	74	10+ acre	10.46	69	72.9	0.37
9	0.143	91.8	B	5 acre	59.26	74	10+ acre	32.57	69	72.2	0.38
10	0.091	58.2	B	5 acre	17.02	74	10+ acre	41.13	69	70.5	0.42
11	0.141	90.1	B	5 acre	26.26	74	10+ acre	63.81	69	70.5	0.42
12	0.035	22.7	B	5 acre	2.32	74	10+ acre	20.36	69	69.5	0.44
13	0.077	49.5	B	5 acre	18.11	74	10+ acre	31.34	69	70.8	0.41
14	0.039	25.0	B	5 acre	1.07	74	10+ acre	23.95	69	69.2	0.44
15	0.131	83.8	B	5 acre	6.95	74	10+ acre	76.81	69	69.4	0.44
16	0.044	27.9	B	5 acre	3.34	74	10+ acre	24.53	69	69.6	0.44

999.6	Total AC.
-------	-----------

Weighted Average CN =	71.2
-----------------------	------



High Forest Estates Subdivision  
 Offsite Basins  
 M.V.E., Inc.  
 April 24, 2023

Time of Concentration/Lag Time Calculations

Basin	Basin Area (Sq Mi)	Basin Area (Ac)	Overland Flow					Shallow Concentrated Flow				
			Manning's n	Length (ft)	P2 (in)	Slope (ft/ft)	Ti (hr)	Cover Type	Length (ft)	Slope (%)	V (fps)	Tsc (hr)
1	0.112	71.7	0.200	300	2.1	0.063	0.39	Woodlands	1745	4.4	1.0	0.48
2	0.225	143.8	0.200	300	2.1	0.057	0.40	Woodlands	1711	5.2	1.2	0.41
3	0.065	41.9	0.200	300	2.1	0.023	0.58	Woodlands	1023	2.8	0.8	0.34
4	0.226	144.6	0.200	300	2.1	0.093	0.33	Woodlands	1475	3.5	0.9	0.45
5	0.071	45.2	0.150	214	2.1	0.093	0.20	Pasture	1334	4.3	1.5	0.25
6	0.043	27.7	0.150	235	2.1	0.094	0.22	Pasture	1063	5.6	1.7	0.17
7	0.043	27.2	0.150	255	2.1	0.118	0.21	Pasture	828	5.2	1.6	0.14
8	0.076	48.6	0.200	300	2.1	0.037	0.48	Woodlands	1957	4.1	0.9	0.60
9	0.143	91.8	0.200	300	2.1	0.020	0.61	Woodlands	1941	3.4	0.9	0.60
10	0.091	58.1	0.200	300	2.1	0.027	0.54	Woodlands	1632	3.6	1.0	0.48
11	0.141	90.1	0.150	300	2.1	0.027	0.43	Pasture	1702	3.3	1.4	0.35
12	0.035	22.7	0.150	300	2.1	0.067	0.30	Pasture	354	8.8	2.1	0.05
13	0.077	49.4	0.200	300	2.1	0.153	0.27	Woodlands	1904	5.7	1.0	0.53
14	0.039	25.0	0.200	300	2.1	0.133	0.29	Woodlands	1291	6.5	1.1	0.33
15	0.131	83.8	0.150	300	2.1	0.057	0.32	Pasture	1680	3.6	1.4	0.34
16	0.044	27.9	0.200	300	2.1	0.120	0.30	Pasture	1263	7.1	1.8	0.19



High Forest Estates Subdivision  
 Offsite Basins  
 M.V.E., Inc.  
 April 24, 2023

Time of Concentration/Lag Time Calculations

Basin	Concentrated Flow												Total Time of Conc Tc (hr)	Lag Time (Min)
	Length (ft)	Slope (%)	Manning's n	Bot Width (ft)	Side Slopes	Est Flow (cfs)	Est d (ft)	Calc Q (cfs)	Calc A (ft)	Calc P (ft)	V (fps)	Tcf (hr)		
1	1307	2.5	0.033	25	13	112	0.95	150	23.8	26.9	6.6	0.06	0.93	33
2	2280	2.0	0.060	25	13	205	1.40	154	34.9	27.8	4.1	0.16	0.97	35
3	2172	1.5	0.033	25	13	66	0.83	89	20.8	26.7	4.7	0.13	1.05	38
4	3235	2.1	0.060	25	13	196	1.34	145	33.4	27.7	4.1	0.22	1.00	36
5	1333	2.6	0.033	25	6	75	0.77	102	19.3	26.5	5.9	0.06	0.51	18
6	1459	2.2	0.040	25	6	47	0.63	52	15.8	26.3	3.9	0.10	0.49	18
7	2096	2.0	0.040	25	6	43	0.62	47	15.4	26.2	3.7	0.16	0.51	18
8	861	2.3	0.033	25	10	80	0.82	107	20.4	26.6	5.7	0.04	1.12	40
9	1725	2.8	0.033	25	10	137	1.03	185	25.8	27.1	7.3	0.07	1.28	46
10	1369	3.2	0.033	25	10	92	0.81	123	20.1	26.6	6.7	0.06	1.08	39
11	1919	3.0	0.040	25	10	135	1.00	149	25.0	27.0	6.1	0.09	0.87	31
12	1713	2.3	0.040	20	7	40	0.58	35	11.5	21.2	3.8	0.13	0.47	17
13	1059	1.7	0.040	20	7	80	0.89	70	17.7	21.8	4.2	0.07	0.87	31
14	558	5.7	0.040	20	7	46	0.60	59	11.9	21.2	6.1	0.03	0.64	23
15	1494	3.6	0.033	20	7	131	0.94	138	18.8	21.9	7.8	0.05	0.71	26
16	488	3.7	0.040	20	7	52	0.54	39	10.7	21.1	4.6	0.03	0.52	19

**XIII. HEC-HMS Global Summary Results for 5-yr Storm  
(Existing & Developed Condition)**

**XIV. HEC-HMS Global Summary Results for 100-yr Storm  
(Existing & Developed Condition)**



Project: 8855 Walker Road Simulation Run: 5yr\_Existing

Start of Run: 01Jan2000, 00:00 Basin Model: High-Forest-Existing  
 End of Run: 02Jan2000, 00:00 Meteorologic Model: 5-yr  
 Compute Time: 01May2023, 14:56:57 Control Specifications: 24-hr

Show Elements: All Elements Volume Units:  IN  ACRE-FT Sorting: Hydrologic

Hydrologic Element	Drainage Area (MI <sup>2</sup> )	Peak Discharge (CFS)	Time of Peak	Volume (IN)
OS-9	0.143	20.3	01Jan2000, 12:45	0.57
OS-10	0.091	11.6	01Jan2000, 12:38	0.48
OS-8	0.076	13.0	01Jan2000, 12:37	0.61
Junction-4	0.310	44.5	01Jan2000, 12:41	0.55
Reach-4	0.310	44.5	01Jan2000, 12:45	0.55
OS-11	0.141	21.2	01Jan2000, 12:28	0.49
Junction-5	0.451	62.1	01Jan2000, 12:39	0.53
Reach-5	0.451	62.1	01Jan2000, 12:43	0.53
OS-13	0.077	12.1	01Jan2000, 12:28	0.50
OS-12	0.035	6.8	01Jan2000, 12:13	0.44
Junction-6	0.563	74.8	01Jan2000, 12:39	0.52
OS-2	0.225	36.1	01Jan2000, 12:32	0.54
OS-1	0.112	15.9	01Jan2000, 12:31	0.48
Junction-1	0.337	51.9	01Jan2000, 12:32	0.52
Reach-1	0.337	51.9	01Jan2000, 12:39	0.52
OS-4	0.226	44.9	01Jan2000, 12:32	0.65
OS-5	0.071	15.4	01Jan2000, 12:13	0.48
OS-3	0.066	10.1	01Jan2000, 12:36	0.55
Junction-2	0.700	113.0	01Jan2000, 12:35	0.56
Reach-2	0.700	113.0	01Jan2000, 12:39	0.56
OS-6	0.043	8.5	01Jan2000, 12:13	0.45
OS-7	0.042	8.7	01Jan2000, 12:13	0.47
Junction-3	0.785	120.2	01Jan2000, 12:38	0.55
Reach-3	0.785	120.2	01Jan2000, 12:38	0.55
Reach-6	0.563	74.8	01Jan2000, 12:40	0.52
OS-15	0.131	18.4	01Jan2000, 12:23	0.43
OS-14	0.039	5.7	01Jan2000, 12:20	0.41
Junction-7	1.518	212.3	01Jan2000, 12:37	0.52
Reach-7	1.518	212.1	01Jan2000, 12:40	0.52
OS-16	0.044	7.3	01Jan2000, 12:15	0.41
Junction-8	1.562	215.6	01Jan2000, 12:39	0.52



Project: 8855 Walker Road Simulation Run: 5yr\_Developed

Start of Run: 01Jan2000, 00:00 Basin Model: High-Forest-Developed  
 End of Run: 02Jan2000, 00:00 Meteorologic Model: 5-yr  
 Compute Time: 01May2023, 14:57:50 Control Specifications: 24-hr

Show Elements:  Volume Units:  IN  ACRE-FT Sorting:

Hydrologic Element	Drainage Area (MI <sup>2</sup> )	Peak Discharge (CFS)	Time of Peak	Volume (IN)
OS-2	0.225	36.1	01Jan2000, 12:32	0.54
OS-1	0.112	15.9	01Jan2000, 12:31	0.48
Junction-1	0.337	51.9	01Jan2000, 12:32	0.52
Reach-1	0.337	51.9	01Jan2000, 12:39	0.52
OS-4	0.226	44.9	01Jan2000, 12:32	0.65
OS-5	0.071	15.4	01Jan2000, 12:13	0.48
OS-3	0.066	10.1	01Jan2000, 12:36	0.55
Junction-2	0.700	113.0	01Jan2000, 12:35	0.56
Reach-2	0.700	113.0	01Jan2000, 12:39	0.56
OS-6	0.043	8.6	01Jan2000, 12:13	0.46
OS-7	0.042	8.7	01Jan2000, 12:13	0.47
Junction-3	0.785	120.3	01Jan2000, 12:38	0.55
Reach-3	0.785	120.2	01Jan2000, 12:38	0.55
OS-9	0.143	20.3	01Jan2000, 12:45	0.57
OS-10	0.091	11.6	01Jan2000, 12:38	0.48
OS-8	0.076	13.0	01Jan2000, 12:37	0.61
Junction-4	0.310	44.5	01Jan2000, 12:41	0.55
Reach-4	0.310	44.5	01Jan2000, 12:45	0.55
OS-11	0.141	21.2	01Jan2000, 12:28	0.49
Junction-5	0.451	62.1	01Jan2000, 12:39	0.53
Reach-5	0.451	62.1	01Jan2000, 12:43	0.53
OS-13	0.077	12.1	01Jan2000, 12:28	0.50
OS-12	0.035	6.8	01Jan2000, 12:13	0.44
Junction-6	0.563	74.8	01Jan2000, 12:39	0.52
Reach-6	0.563	74.8	01Jan2000, 12:40	0.52
OS-15	0.131	18.7	01Jan2000, 12:23	0.43
OS-14	0.039	5.8	01Jan2000, 12:20	0.42
Junction-7	1.518	212.5	01Jan2000, 12:37	0.52
Reach-7	1.518	212.4	01Jan2000, 12:40	0.52
OS-16	0.044	7.9	01Jan2000, 12:15	0.43
Junction-8	1.562	216.0	01Jan2000, 12:39	0.52



Project: 8855 Walker Road Simulation Run: 100yr\_Existing

Start of Run: 01Jan2000, 00:00 Basin Model: High-Forest-Existing  
 End of Run: 02Jan2000, 00:00 Meteorologic Model: 100-yr  
 Compute Time:01May2023, 14:58:33 Control Specifications:24-hr

Show Elements: All Elements Volume Units:  IN  ACRE-FT Sorting: Hydrologic

Hydrologic Element	Drainage Area (MI <sup>2</sup> )	Peak Discharge (CFS)	Time of Peak	Volume (IN)
OS-9	0.143	98.2	01Jan2000, 12:41	2.28
OS-10	0.091	64.7	01Jan2000, 12:33	2.11
OS-8	0.076	59.8	01Jan2000, 12:34	2.36
Junction-4	0.310	220.7	01Jan2000, 12:36	2.25
Reach-4	0.310	220.7	01Jan2000, 12:41	2.24
OS-11	0.141	118.3	01Jan2000, 12:25	2.11
Junction-5	0.451	320.1	01Jan2000, 12:35	2.20
Reach-5	0.451	320.0	01Jan2000, 12:37	2.20
OS-13	0.077	65.6	01Jan2000, 12:25	2.14
OS-12	0.035	41.7	01Jan2000, 12:10	2.02
Junction-6	0.563	391.9	01Jan2000, 12:34	2.18
OS-2	0.225	183.2	01Jan2000, 12:29	2.22
OS-1	0.112	89.4	01Jan2000, 12:27	2.10
Junction-1	0.337	272.3	01Jan2000, 12:28	2.18
Reach-1	0.337	272.1	01Jan2000, 12:34	2.18
OS-4	0.226	198.2	01Jan2000, 12:30	2.43
OS-5	0.071	85.7	01Jan2000, 12:11	2.11
OS-3	0.066	50.9	01Jan2000, 12:32	2.23
Junction-2	0.700	556.6	01Jan2000, 12:31	2.26
Reach-2	0.700	556.5	01Jan2000, 12:34	2.25
OS-6	0.043	50.3	01Jan2000, 12:11	2.05
OS-7	0.042	49.9	01Jan2000, 12:11	2.08
Junction-3	0.785	597.1	01Jan2000, 12:33	2.23
Reach-3	0.785	597.1	01Jan2000, 12:33	2.23
Reach-6	0.563	391.7	01Jan2000, 12:34	2.18
OS-15	0.131	116.4	01Jan2000, 12:19	1.99
OS-14	0.039	37.1	01Jan2000, 12:16	1.96
Junction-7	1.518	1104.4	01Jan2000, 12:31	2.19
Reach-7	1.518	1103.3	01Jan2000, 12:32	2.18
OS-16	0.044	47.5	01Jan2000, 12:12	1.97
Junction-8	1.562	1126.0	01Jan2000, 12:32	2.18



Project: 8855 Walker Road Simulation Run: 100yr\_Developed

Start of Run: 01Jan2000, 00:00 Basin Model: High-Forest-Developed  
 End of Run: 02Jan2000, 00:00 Meteorologic Model: 100-yr  
 Compute Time: 01May2023, 14:59:15 Control Specifications: 24-hr

Show Elements: All Elements

Volume Units:  IN  ACRE-FT

Sorting: Hydrologic

Hydrologic Element	Drainage Area (MI2)	Peak Discharge (CFS)	Time of Peak	Volume (IN)
OS-2	0.225	183.2	01Jan2000, 12:29	2.22
OS-1	0.112	89.4	01Jan2000, 12:27	2.10
Junction-1	0.337	272.3	01Jan2000, 12:28	2.18
Reach-1	0.337	272.1	01Jan2000, 12:34	2.18
OS-4	0.226	198.2	01Jan2000, 12:30	2.43
OS-5	0.071	85.7	01Jan2000, 12:11	2.11
OS-3	0.066	50.9	01Jan2000, 12:32	2.23
Junction-2	0.700	556.6	01Jan2000, 12:31	2.26
Reach-2	0.700	556.5	01Jan2000, 12:34	2.25
OS-6	0.043	50.5	01Jan2000, 12:11	2.06
OS-7	0.042	49.9	01Jan2000, 12:11	2.08
Junction-3	0.785	597.2	01Jan2000, 12:33	2.23
Reach-3	0.785	597.2	01Jan2000, 12:33	2.23
OS-9	0.143	98.2	01Jan2000, 12:41	2.28
OS-10	0.091	64.7	01Jan2000, 12:33	2.11
OS-8	0.076	59.8	01Jan2000, 12:34	2.36
Junction-4	0.310	220.7	01Jan2000, 12:36	2.25
Reach-4	0.310	220.7	01Jan2000, 12:41	2.24
OS-11	0.141	118.3	01Jan2000, 12:25	2.11
Junction-5	0.451	320.1	01Jan2000, 12:35	2.20
Reach-5	0.451	320.0	01Jan2000, 12:37	2.20
OS-13	0.077	65.6	01Jan2000, 12:25	2.14
OS-12	0.035	41.7	01Jan2000, 12:10	2.02
Junction-6	0.563	391.9	01Jan2000, 12:34	2.18
Reach-6	0.563	391.7	01Jan2000, 12:34	2.18
OS-15	0.131	116.9	01Jan2000, 12:19	2.00
OS-14	0.039	37.4	01Jan2000, 12:16	1.98
Junction-7	1.518	1105.1	01Jan2000, 12:31	2.19
Reach-7	1.518	1103.9	01Jan2000, 12:32	2.18
OS-16	0.044	48.8	01Jan2000, 12:12	2.01
Junction-8	1.562	1127.2	01Jan2000, 12:32	2.18



## **C. Hydraulic Calculations**

- I. HEC-RAS Cross Sections Map
- II. HEC-RAS Profile
- III. HEC-RAS Summary Table
- IV. HEC-RAS Cross Sections
- V. HEC-RAS Detailed Report
- VI. Permissible Shear and Velocity for Selected Lining Materials

## **I. HEC-RAS Cross Sections Map**






## II. HEC-RAS Profiles




HEC-RAS Model Plan: Default 5/3/2023

Donahoo East



HEC-RAS Model Plan: Default 5/3/2023

Donahoo South




**Legend**

- EG 100yr
- WS 100yr
- Crit 100yr
- Ground

HEC-RAS Model Plan: Default 5/3/2023

Donahoo West



**Legend**

- EG 100yr
- Crit 100yr
- WS 100yr
- Ground

### **III. HEC-RAS Summary Table**



HEC-RAS Plan: Default River: Donahoo Reach: East

Reach	River Sta	Profile	Q Total (cfs)	Min Ch El (ft)	W.S. Elev (ft)	Crit W.S. (ft)	E.G. Elev (ft)	E.G. Slope (ft/ft)	Max Chl Dpth (ft)	Hydr Depth C (ft)	Flow Area (sq ft)	Top Width (ft)	Vel Chnl (ft/s)	Froude # Chl	Shear Chan (lb/sq ft)
East	728	100yr	391.90	7373.00	7374.60	7374.62	7375.30	0.019389	1.60	1.33	58.18	43.65	6.74	1.03	1.60
East	728	5yr	74.80	7373.00	7373.56	7373.56	7373.84	0.026162	0.56	0.52	17.85	34.33	4.19	1.02	0.85
East	676	100yr	391.90	7371.00	7372.51	7372.90	7373.85	0.040244	1.51	1.25	42.28	33.88	9.27	1.46	3.10
East	676	5yr	74.80	7371.00	7371.56	7371.68	7372.04	0.047445	0.56	0.51	13.46	26.43	5.56	1.37	1.50
East	624	100yr	391.90	7370.00	7372.78	7372.19	7373.16	0.006551	2.78	1.90	79.40	41.89	4.94	0.63	0.77
East	624	5yr	74.80	7370.00	7371.35	7370.99	7371.46	0.005582	1.34	0.88	27.19	30.78	2.75	0.52	0.31
East	572	100yr	391.90	7370.00	7372.03	7371.89	7372.66	0.013720	2.03	1.60	61.46	40.14	6.38	0.89	1.35
East	572	5yr	74.80	7370.00	7370.80	7371.02	7371.02	0.014274	0.80	0.70	19.94	28.67	3.75	0.79	0.62
East	520	100yr	391.90	7369.00	7371.07	7371.07	7371.84	0.017753	2.07	1.54	55.38	36.59	7.08	1.00	1.69
East	520	5yr	74.80	7369.00	7369.89	7369.84	7370.17	0.019173	0.89	0.66	17.79	26.86	4.20	0.91	0.79
East	468	100yr	391.90	7368.00	7369.86	7370.00	7370.78	0.023807	1.86	1.39	51.09	36.71	7.67	1.15	2.05
East	468	5yr	74.80	7368.00	7368.75	7368.75	7369.08	0.023466	0.75	0.64	16.43	25.65	4.55	1.00	0.93
East	416	100yr	391.90	7366.00	7367.48	7367.94	7368.96	0.052396	1.48	1.10	40.14	36.39	9.76	1.64	3.58
East	416	5yr	74.80	7366.00	7366.57	7366.75	7367.17	0.064055	0.57	0.48	12.01	24.94	6.23	1.58	1.92
East	364	100yr	391.90	7365.00	7367.94	7366.74	7368.12	0.002511	2.94	2.26	114.33	50.66	3.43	0.40	0.35
East	364	5yr	74.80	7365.00	7366.13	7365.67	7366.20	0.003554	1.13	0.89	33.86	38.03	2.21	0.41	0.20
East	312	100yr	391.90	7364.00	7367.90		7368.02	0.001035	3.90	3.23	142.41	48.59	2.79	0.27	0.20
East	312	5yr	74.80	7364.00	7366.12		7366.14	0.000413	2.12	1.70	64.97	38.21	1.15	0.16	0.04
East	260	100yr	391.90	7363.00	7367.91		7367.98	0.000425	4.90	4.50	197.94	62.93	2.23	0.19	0.12
East	260	5yr	74.80	7363.00	7366.12		7366.13	0.000102	3.12	2.71	100.39	46.68	0.78	0.08	0.02
East	210	100yr	391.90	7361.00	7367.93		7367.95	0.000115	6.93	5.34	332.96	95.48	1.30	0.10	0.04
East	210	5yr	74.80	7361.00	7366.12		7366.12	0.000019	5.12	3.54	189.09	56.92	0.40	0.04	0.00
East	159	100yr	391.90	7360.00	7367.93		7367.94	0.000051	7.93	6.69	481.58	112.94	1.01	0.07	0.02
East	159	5yr	74.80	7360.00	7366.12		7366.12	0.000007	6.12	4.87	294.38	94.87	0.31	0.02	0.00
East	109	100yr	391.90	7359.00	7367.93		7367.94	0.000025	8.93	7.64	632.15	128.16	0.77	0.05	0.01
East	109	5yr	74.80	7359.00	7366.12		7366.12	0.000003	7.12	5.83	415.34	110.86	0.22	0.02	0.00
East	53	100yr	391.90	7359.00	7367.93		7367.94	0.000019	8.93	6.81	695.40	137.40	0.63	0.04	0.01
East	53	5yr	74.80	7359.00	7366.12		7366.12	0.000002	7.12	5.00	463.95	117.97	0.17	0.01	0.00
East	14	100yr	391.90	7358.00	7367.93		7367.94	0.000014	9.93	8.32	802.08	162.67	0.60	0.04	0.01
East	14	5yr	74.80	7358.00	7366.12		7366.12	0.000001	8.12	6.50	521.49	146.94	0.17	0.01	0.00
East	-49	100yr	391.90	7357.00	7367.94		7367.94	0.000006	10.93	9.54	1047.48	165.13	0.45	0.03	0.00
East	-49	5yr	74.80	7357.00	7366.12		7366.12	0.000001	9.12	7.73	761.66	149.42	0.12	0.01	0.00

HEC-RAS Plan: Default River: Donahoo Reach: South







Reach	River Sta	Profile	Q Total (cfs)	Min Ch El (ft)	W.S. Elev (ft)	Crit W.S. (ft)	E.G. Elev (ft)	E.G. Slope (ft/ft)	Max Chl Dpth (ft)	Hydr Depth C (ft)	Flow Area (sq ft)	Top Width (ft)	Vel Chnl (ft/s)	Froude # Chl	Shear Chan (lb/sq ft)
South	220	100yr	597.20	7362.00	7367.91	7364.76	7367.98	0.000407	5.91	4.79	299.89	95.56	2.28	0.18	0.12
South	220	5yr	120.30	7362.00	7366.12	7363.10	7366.13	0.000098	4.12	3.00	153.56	66.79	0.82	0.08	0.02
South	166	100yr	597.20	7361.00	7367.92		7367.96	0.000181	6.92	5.91	442.10	155.28	1.75	0.13	0.07
South	166	5yr	120.30	7361.00	7366.12		7366.13	0.000035	5.12	4.11	223.61	86.72	0.60	0.05	0.01
South	111	100yr	597.20	7360.00	7367.93		7367.95	0.000081	7.93	6.16	642.74	209.56	1.20	0.09	0.03
South	111	5yr	120.30	7360.00	7366.12		7366.12	0.000014	6.12	4.35	347.93	131.84	0.40	0.03	0.00
South	57	100yr	597.20	7358.00	7367.93		7367.94	0.000042	9.93	6.18	862.35	277.09	0.87	0.06	0.02
South	57	5yr	120.30	7358.00	7366.12		7366.12	0.000008	8.12	4.37	433.38	151.86	0.29	0.02	0.00
South	0	100yr	597.20	7357.00	7367.93		7367.94	0.000027	10.93	8.26	1028.47	301.55	0.83	0.05	0.01
South	0	5yr	120.30	7357.00	7366.12		7366.12	0.000004	9.12	6.45	546.81	198.54	0.28	0.02	0.00
South	-68	100yr	597.20	7357.00	7367.93		7367.94	0.000010	10.93	7.39	1548.16	361.83	0.49	0.03	0.00
South	-68	5yr	120.30	7357.00	7366.12		7366.12	0.000002	9.12	5.58	934.05	293.37	0.16	0.01	0.00


HEC-RAS Plan: Default River: Donahoo Reach: West





Reach	River Sta	Profile	Q Total (cfs)	Min Ch El (ft)	W.S. Elev (ft)	Crit W.S. (ft)	E.G. Elev (ft)	E.G. Slope (ft/ft)	Max Chl Dpth (ft)	Hydr Depth C (ft)	Flow Area (sq ft)	Top Width (ft)	Vel Chnl (ft/s)	Froude # Chl	Shear Chan (lb/sq ft)
West	980	100yr	1105.10	7355.00	7367.94		7367.94	0.000004	12.93	10.16	3393.73	495.10	0.37	0.02	0.00
West	980	5yr	212.50	7355.00	7366.12		7366.12	0.000000	11.12	8.34	2553.62	429.51	0.09	0.01	0.00
West	975	100yr	1105.10	7355.00	7367.94		7367.94	0.000004	12.94	10.39	3649.52	529.78	0.36	0.02	0.00
West	975	5yr	212.50	7355.00	7366.12		7366.12	0.000000	11.12	8.57	2751.16	457.13	0.09	0.01	0.00
West	965	100yr	1105.10	7356.00	7367.94		7367.94	0.000004	11.93	10.45	3290.98	427.84	0.38	0.02	0.00
West	965	5yr	212.50	7356.00	7366.12		7366.12	0.000000	10.12	8.64	2558.33	376.15	0.09	0.01	0.00
West	708	100yr	1105.10	7364.00	7367.92		7367.93	0.000174	3.92	3.70	1071.56	408.36	1.26	0.12	0.04
West	708	5yr	212.50	7364.00	7366.11		7366.12	0.000179	2.11	1.90	364.94	380.19	0.82	0.11	0.02
West	696	100yr	1105.10	7365.00	7367.36	7366.95	7367.88	0.008056	2.36	2.03	193.16	106.69	5.78	0.71	1.02
West	696	5yr	212.50	7365.00	7365.94		7366.10	0.007636	0.94	0.86	66.34	77.43	3.20	0.81	0.42
West	691	100yr	1105.10	7365.00	7366.94	7366.94	7367.76	0.017131	1.94	1.64	151.52	92.40	7.29	1.00	1.75
West	691	5yr	212.50	7365.00	7365.67	7365.67	7365.99	0.023282	0.67	0.64	46.96	73.90	4.52	1.00	0.92
West	674	100yr	1105.10	7364.00	7366.35	7366.35	7366.88	0.007677	8.35	1.76	293.20	413.43	5.12	0.88	0.84
West	674	5yr	212.50	7364.00	7365.00	7365.00	7365.30	0.024109	7.00	0.60	48.09	365.12	4.42	1.01	0.90
West	603	100yr	1105.10	7363.00	7365.30	7365.28	7365.66	0.008398	7.29	1.66	269.74	386.95	5.16	0.71	0.87
West	603	5yr	212.50	7363.00	7363.93	7363.93	7364.23	0.024188	5.93	0.59	48.43	328.41	4.39	1.01	0.89
West	577	100yr	1105.10	7358.00	7364.15	7364.50	7365.52	0.228423	6.15	0.34	117.58	343.92	9.41	2.83	4.90
West	577	5yr	212.50	7358.00	7363.60	7363.76	7364.14	0.056161	5.60	0.49	36.08	313.10	5.89	1.49	1.71
West	551	100yr	1105.10	7356.00	7363.26	7363.57	7364.38	0.148661	7.26	0.41	131.53	331.19	8.55	2.35	3.80
West	551	5yr	212.50	7356.00	7362.79	7363.09	7363.70	0.085443	6.79	0.53	27.80	284.37	7.65	1.86	2.80
West	434	100yr	1105.10	7353.00	7360.01	7356.57	7360.05	0.000223	7.01	5.94	779.60	250.56	1.95	0.14	0.08
West	434	5yr	212.50	7353.00	7355.42	7354.41	7355.55	0.002653	2.42	1.66	73.74	44.38	2.88	0.39	0.27
West	334	100yr	1105.10	7352.00	7360.01		7360.03	0.000080	8.01	7.34	1017.00	234.31	1.35	0.09	0.04
West	334	5yr	212.50	7352.00	7355.47		7355.48	0.000130	3.47	2.80	237.59	99.81	0.91	0.10	0.02
West	293	100yr	1105.10	7351.00	7359.98		7360.03	0.000152	8.98	7.75	790.94	206.51	1.92	0.12	0.07
West	293	5yr	212.50	7351.00	7355.44		7355.47	0.000258	4.44	3.21	158.37	64.11	1.39	0.14	0.05
West	219	100yr	1127.20	7351.19	7359.99	7354.55	7360.01	0.000070	8.80	7.10	1305.19	418.86	1.23	0.08	0.03
West	219	5yr	216.00	7351.19	7355.44	7352.70	7355.45	0.000181	4.25	2.54	217.06	95.59	1.00	0.11	0.03
West	183		Culvert												
West	142	100yr	1127.20	7350.00	7353.73	7353.73	7354.88	0.013976	3.73	2.48	133.08	62.13	8.64	0.97	2.14
West	142	5yr	216.00	7350.00	7351.81	7351.75	7352.29	0.017121	1.81	1.09	38.97	35.64	5.54	0.93	1.16
West	102	100yr	1127.20	7350.00	7352.22	7352.69	7353.99	0.032702	2.22	1.79	105.90	59.11	10.64	1.40	3.62
West	102	5yr	216.00	7350.00	7351.07	7351.07	7351.48	0.021961	1.07	0.81	41.83	51.55	5.16	1.01	1.11
West	60	100yr	1127.20	7349.00	7351.48	7351.67	7352.70	0.022508	2.48	1.80	127.13	70.79	8.87	1.17	2.51
West	60	5yr	216.00	7349.00	7350.45	7350.19	7350.66	0.008714	1.45	0.97	58.80	60.47	3.67	0.66	0.53
West	2	100yr	1127.20	7348.00	7350.82	7350.84	7351.63	0.017727	2.82	1.56	156.92	100.27	7.18	1.01	1.72
West	2	5yr	216.00	7348.00	7349.65	7349.58	7349.95	0.018718	1.65	0.71	49.47	69.57	4.37	0.91	0.83


## **IV. HEC-RAS Cross Sections**

































HEC-RAS Model Plan: Default 5/3/2023

River = Donahoo Reach = West RS = 60



HEC-RAS Model Plan: Default 5/3/2023

River = Donahoo Reach = West RS = 2



## **V. HEC-RAS Detailed Report**



HEC-RAS HEC-RAS 5.0.7 March 2019  
U.S. Army Corps of Engineers  
Hydrologic Engineering Center  
609 Second Street  
Davis, California

```
X   X  XXXXXX   XXXX   XXXX   XX   XXXX
X   X  X       X   X   X   X   X   X   X
X   X  X       X       X   X   X   X   X
XXXXXXXX XXXX   X       XXX XXXX XXXXXX XXXX
X   X  X       X       X   X   X   X   X
X   X  X       X   X   X   X   X   X   X
X   X  XXXXXX   XXXX   X   X   X   X XXXXX
```

PROJECT DATA

Project Title: HEC-RAS Model  
Project File : Donohoo-Updated.prj  
Run Date and Time: 5/3/2023 3:18:20 PM

Project in English units

PLAN DATA

Plan Title: Default  
Plan File : C:\Users\tomw\Desktop\Donohoo-Updated.p02

Geometry Title: Default Geometry  
Geometry File : C:\Users\tomw\Desktop\Donohoo-Updated.g01

Flow Title : Default Steady Flow  
Flow File : C:\Users\tomw\Desktop\Donohoo-Updated.f01

Plan Description:  
Default Scenario

Plan Summary Information:

Number of:	Cross Sections =	40	Multiple Openings =	0
	Culverts =	1	Inline Structures =	0
	Bridges =	0	Lateral Structures =	0

Computational Information

Water surface calculation tolerance =	0.01
Critical depth calculation tolerance =	0.01
Maximum number of iterations =	20
Maximum difference tolerance =	0.33
Flow tolerance factor =	0.001

Computation Options

Critical depth computed only where necessary	
Conveyance Calculation Method:	At breaks in n values only
Friction Slope Method:	Average Conveyance
Computational Flow Regime:	Mixed Flow

FLOW DATA

Flow Title: Default Steady Flow  
Flow File : C:\Users\tomw\Desktop\Donohoo-Updated.f01

Flow Data (cfs)

River	Reach	RS	100yr	5yr
Donahoo	East	728	391.9	74.8
Donahoo	South	220	597.2	120.3
Donahoo	West	980	1105.1	212.5
Donahoo	West	219	1127.2	216

Boundary Conditions

River	Reach	Profile	Upstream	Downstream
Donahoo	East	100yr	Normal S = 0.019395	
Donahoo	East	5yr	Normal S = 0.019395	
Donahoo	South	100yr	Normal S = 0.022568	
Donahoo	South	5yr	Normal S = 0.022568	
Donahoo	West	100yr		Normal S = 0.018699
Donahoo	West	5yr		Normal S = 0.018699

GEOMETRY DATA

Geometry Title: Default Geometry  
 Geometry File : C:\Users\tomw\Desktop\Donahoo-Updated.g01

Reach Connection Table

River	Reach	Upstream Boundary	Downstream Boundary
Donahoo	East		Junction 1
Donahoo	South		Junction 1
Donahoo	West	Junction 1	

JUNCTION INFORMATION

Name: Junction 1  
 Description:  
 Energy computation Method

Length across River	Junction Reach	Tributary River	Reach	Length	Angle
Donahoo	East	to Donahoo	West	101.05	0
Donahoo	South	to Donahoo	West	83.49	0

CROSS SECTION

RIVER: Donahoo  
 REACH: East RS: 728

INPUT

Description:

Station	Elevation	Data	num=	22					
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	7382	1.06	7382	10.25	7381	19.24	7380	26.56	7379
33.69	7378	41.64	7377	51.84	7376	76.87	7375	81.28	7374
86.59	7373	115.73	7373	119.64	7374	124.11	7375	129.14	7376
139.31	7377	147.95	7378	156.86	7379	166.3	7380	172.4	7381
180.61	7382	200	7382						

Manning's n	Values	num=	3
Sta	n Val	Sta	n Val
0	.037	76.87	.037
124.11			.037

Bank Sta:	Left	Right	Lengths:	Left	Channel	Right	Coeff	Contr.	Expan.
	76.87	124.11		51.56	51.56	51.56		.1	.3

CROSS SECTION

RIVER: Donahoo  
REACH: East RS: 676

INPUT

Description:

Station	Elevation	Data	num=	26						
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	
0	7377	4.24	7377	13.74	7376	30.72	7375	66.42	7374	
77.55	7374	81.73	7373	85.81	7372	90.47	7371	112.39	7371	
115.84	7372	119.3	7373	121.95	7374	124.4	7375	128.03	7376	
132.32	7377	142.43	7378	148.57	7379	155	7380	161.57	7381	
169.18	7382	176.33	7383	183.56	7384	192.03	7385	199.88	7386	
200	7386									

Manning's n Values		num=	3
Sta	n Val	Sta	n Val
0	.037	77.55	.037

Bank Sta:	Left	Right	Lengths:	Left	Channel	Right	Coeff	Contr.	Expan.
	77.55	121.95		51.56	51.56	51.56		.1	.3

CROSS SECTION

RIVER: Donahoo  
REACH: East RS: 624

INPUT

Description:

Station	Elevation	Data	num=	26						
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	
0	7376	.03	7376	11.83	7375	19.11	7374	30.54	7373	
79	7373	83.51	7372	87.76	7371	98.2	7370	104.24	7370	
115.81	7371	119.49	7372	122.56	7373	125.37	7374	128.17	7375	
130.98	7376	135.13	7377	140.09	7378	146.27	7379	153.13	7380	
159.95	7381	165.11	7382	172.44	7383	179.54	7384	189.87	7385	
200	7385									

Manning's n Values		num=	3
Sta	n Val	Sta	n Val
0	.037	79	.037

Bank Sta:	Left	Right	Lengths:	Left	Channel	Right	Coeff	Contr.	Expan.
	79	122.56		51.56	51.56	51.56		.1	.3

CROSS SECTION

RIVER: Donahoo  
REACH: East RS: 572

INPUT

Description:

Station	Elevation	Data	num=	24						
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	
0	7375	7.27	7375	16.14	7374	24.13	7373	82.3	7372	
87.08	7371	91.52	7370	112.74	7370	117.62	7371	120.74	7372	
123.54	7373	126.64	7374	129.55	7375	132.59	7376	138.22	7377	
147.93	7378	154.17	7379	159.55	7380	164.19	7381	169.22	7382	
174.38	7383	177.38	7384	182.17	7385	200	7385			

Manning's n Values		num=	3
Sta	n Val	Sta	n Val
0	.037	82.3	.037

Bank Sta:	Left	Right	Lengths:	Left	Channel	Right	Coeff	Contr.	Expan.
	82.3	120.74		51.56	51.56	51.56		.1	.3

CROSS SECTION

RIVER: Donahoo  
REACH: East RS: 520

INPUT

Description:

Station	Elevation	Data	num=	22						
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	
0	7376	6.04	7376	14.73	7375	24.07	7374	31.76	7373	
67.95	7372	76.77	7371	81.56	7370	94.52	7369	107.59	7369	
110.11	7370	112.62	7371	115.16	7372	117.71	7373	123.25	7374	
134.23	7375	143.81	7376	152.59	7377	161.97	7378	171.75	7379	
186.9	7380	200	7380							

Manning's n Values

Sta	n Val	Sta	n Val	Sta	n Val
0	.037	76.77	.037	112.62	.037

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
76.77 112.62 51.56 51.56 51.56 .1 .3

CROSS SECTION

RIVER: Donahoo  
REACH: East RS: 468

INPUT

Description:

Station	Elevation	Data	num=	27						
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	
0	7382	3.82	7382	9.58	7381	15.73	7380	21.86	7379	
27.16	7378	31.92	7377	37.44	7376	42.77	7375	48.75	7374	
54.41	7373	61.35	7372	71.57	7371	79.58	7370	83.77	7369	
87.55	7368	105.57	7368	111.93	7369	117.64	7370	124.39	7371	
135.79	7372	147.88	7373	158.96	7374	168	7375	178.42	7376	
189.64	7377	200	7377							

Manning's n Values

Sta	n Val	Sta	n Val	Sta	n Val
0	.037	79.58	.037	117.64	.037

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
79.58 117.64 51.56 51.56 51.56 .1 .3

CROSS SECTION

RIVER: Donahoo  
REACH: East RS: 416

INPUT

Description:

Station	Elevation	Data	num=	35						
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	
0	7386	5.3	7386	12.61	7385	17.73	7384	22.36	7383	
26.84	7382	30.72	7381	34.61	7380	38.76	7379	42.93	7378	
46.74	7377	50.68	7376	55.57	7375	61.13	7374	66.41	7373	
70.74	7372	74.24	7371	76.55	7370	78.71	7369	80.69	7368	
83.72	7367	87.58	7366	105.05	7366	114.38	7367	123.29	7368	
129.19	7369	138.06	7370	148.12	7371	158.58	7372	168.66	7373	
177	7373.94	177.54	7374	184.81	7375	192.77	7376	200	7376	

Manning's n Values

Sta	n Val	Sta	n Val	Sta	n Val
0	.037	80.69	.037	123.29	.037

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
80.69 123.29 51.56 51.56 51.56 .1 .3

CROSS SECTION

RIVER: Donahoo  
 REACH: East RS: 364

INPUT  
 Description:

Station Elevation Data		num= 38							
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	7387	5.26	7387	12.29	7386	18.71	7385	24.01	7384
29.25	7383	34.29	7382	39.16	7381	43.81	7380	48.45	7379
53.12	7378	57.9	7377	62.54	7376	67.59	7375	70.37	7374
72.09	7373	73.79	7372	75.51	7371	77.24	7370	79.07	7369
81.24	7368	83.42	7367	85.46	7366	90.73	7365	111.77	7365
122.57	7366	127.71	7367	132.32	7368	137.4	7369	144.71	7370
152.24	7371	160.53	7372	168.92	7373	175.64	7373.88	176.62	7374
183.81	7375	191.82	7376	200	7376				

Manning's n Values		num= 3	
Sta	n Val	Sta	n Val
0	.037	81.24	.037
		132.32	.037

Bank Sta:	Left	Right	Lengths:	Left	Channel	Right	Coeff	Contr.	Expan.
	81.24	132.32		51.56	51.56	51.56		.1	.3

CROSS SECTION

RIVER: Donahoo  
 REACH: East RS: 312

INPUT  
 Description:

Station Elevation Data		num= 36							
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	7383	2.47	7383	8.96	7382	14	7381	19.64	7380
26.15	7379	31.03	7378	35.79	7377	40.55	7376	45.2	7375
49.95	7374	55.6	7373	61.31	7372	67.66	7371	73.81	7370
79.99	7369	83.38	7368	86.07	7367	88.83	7366	91.07	7365
94.5	7364	114.95	7364	122.56	7365	126.35	7366	129.42	7367
132.53	7368	136.4	7369	142.76	7370	147.98	7371	155.77	7372
163.92	7373	171.91	7374	180.8	7375	188.48	7376	195.79	7377
200	7377								

Manning's n Values		num= 3	
Sta	n Val	Sta	n Val
0	.037	86.07	.037
		129.42	.037

Bank Sta:	Left	Right	Lengths:	Left	Channel	Right	Coeff	Contr.	Expan.
	86.07	129.42		51.56	51.56	51.56		.1	.3

CROSS SECTION

RIVER: Donahoo  
 REACH: East RS: 260

INPUT  
 Description:

Station Elevation Data		num= 33							
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	7380	.19	7380	5.89	7379	11.41	7378	16.58	7377
21.37	7376	26.18	7375	30.94	7374	35.69	7373	40.72	7372
46.3	7371	52.67	7370	59.28	7369	65.49	7368	70.95	7367
76.62	7366	84.86	7365	88.89	7364	92.69	7363	113.59	7363
116.17	7364	119.27	7365	122.29	7366	125.2	7367	129.33	7368
136.13	7369	145.49	7370	154.4	7371	163.76	7372	172.99	7373
181.85	7374	191.51	7375	200	7375				

Manning's n Values		num= 3	
Sta	n Val	Sta	n Val

0 .037 84.86 .037 119.27 .037

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
84.86 119.27 49.2 49.2 49.2 .1 .3

CROSS SECTION

RIVER: Donahoo  
REACH: East RS: 210

INPUT

Description:

Station	Elevation	Data	num=	34						
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta
0	7380	2.38	7380	9.48	7379	16.1	7378	22.09	7377	7377
27.72	7376	33.89	7375	39.78	7374	45.41	7373	51.07	7372	7372
56.69	7371	61.93	7370	66.74	7369	72.45	7368	78.7	7367	7367
86.01	7366	88.88	7365	92.15	7364	95.48	7363	98.54	7362	7362
111.11	7361.33	117.21	7361	124.2	7361	127.31	7362	130.3	7363	7363
133.42	7364	136.32	7365	139.42	7366	161.31	7367	168.95	7368	7368
183.23	7369	192.81	7370	204.05	7371	210.86	7371			

Manning's n Values

Sta	n Val	Sta	n Val	Sta	n Val
0	.037	86.01	.037	139.42	.037

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
86.01 139.42 51.1 51.1 51.1 .1 .3

CROSS SECTION

RIVER: Donahoo  
REACH: East RS: 159

INPUT

Description:

Station	Elevation	Data	num=	33						
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta
0	7379	12.66	7379	21.87	7378	28.78	7377	35.32	7376	7376
42.32	7375	49.01	7374	54.89	7373	61.1	7372	67.24	7371	7371
73.36	7370	80.44	7369	83.55	7368	86.18	7367	87.74	7366	7366
89.44	7365	91.47	7364	93.45	7363	95.39	7362	99.01	7361	7361
104.82	7360	107.39	7360	116.65	7361	123.73	7362	131.14	7363	7363
160.24	7364	171.81	7365	181.56	7366	188.74	7367	197.25	7368	7368
205.81	7369	210.84	7370	214.49	7370					

Manning's n Values

Sta	n Val	Sta	n Val	Sta	n Val
0	.037	93.45	.037	131.14	.037

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
93.45 131.14 49.3 49.3 49.3 .1 .3

CROSS SECTION

RIVER: Donahoo  
REACH: East RS: 109

INPUT

Description:

Station	Elevation	Data	num=	34						
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta
0	7375	43.02	7375	51.1	7374	57.87	7373	61.19	7372	7372
62.73	7371	64.23	7370	65.66	7369	67.13	7368	68.61	7367	7367
70.13	7366	71.65	7365	73.19	7364	75.36	7363	78.06	7362	7362
80.61	7361	83.87	7360	88.37	7359	92.47	7359	104.49	7360	7360
108.42	7361	119.87	7362	142.86	7363	160.62	7364	171.63	7365	7365
179.82	7366	188.01	7367	195.91	7368	204.22	7369	210.61	7370	7370

216.12 7371 222.5 7372 230.09 7373 230.81 7373

Manning's n Values num= 3  
Sta n Val Sta n Val  
0 .037 78.06 .037 119.87 .037

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
78.06 119.87 55.64 55.64 55.64 .1 .3

CROSS SECTION

RIVER: Donahoo  
REACH: East RS: 53

INPUT  
Description:  
Station Elevation Data num= 29  
Sta Elev Sta Elev Sta Elev Sta Elev Sta Elev  
0 7371 12.75 7371 22.14 7370 24.08 7369 25.86 7368  
27.81 7367 29.76 7366 31.65 7365 33.41 7364 35.37 7363  
38.24 7362 41.06 7361 43.77 7360 47.09 7359 60.24 7359  
64.77 7360 70.66 7361 90.92 7362 115.21 7363 128.99 7364  
137.84 7365 146.44 7366 155.15 7367 163.98 7368 171.15 7369  
178.06 7370 184.49 7371 191.1 7372 195.51 7372

Manning's n Values num= 3  
Sta n Val Sta n Val  
0 .037 35.37 .037 115.21 .037

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
35.37 115.21 39.8 39.8 39.8 .1 .3

CROSS SECTION

RIVER: Donahoo  
REACH: East RS: 14

INPUT  
Description:  
Station Elevation Data num= 25  
Sta Elev Sta Elev Sta Elev Sta Elev Sta Elev  
0 7366 25.46 7366 29.75 7365 31.45 7364 33.56 7363  
35.81 7362 38.15 7361 40.86 7360 46.11 7359 51.54 7358  
59.75 7358 69.17 7359 76.85 7360 85.14 7361 94.3 7362  
108.6 7363 125.43 7364 135.71 7365 145.89 7366 154.58 7367  
163.25 7368 171.72 7369 178.21 7370 185.21 7371 186.69 7371

Manning's n Values num= 3  
Sta n Val Sta n Val  
0 .037 35.81 .037 94.3 .037

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
35.81 94.3 62.95 62.95 62.95 .1 .3

CROSS SECTION

RIVER: Donahoo  
REACH: East RS: -49

INPUT  
Description:  
Station Elevation Data num= 24  
Sta Elev Sta Elev Sta Elev Sta Elev Sta Elev  
34.45 7363 40.19 7362 44.99 7361 49.27 7360 53.43 7359  
56.86 7358 63.58 7357 78 7357 89.44 7357.87 92.97 7358  
100.01 7359 106.3 7360 114.36 7361 126.57 7362 141.64 7363  
156.66 7364 172.66 7365 182.73 7366 192.15 7367 200.1 7368  
206.07 7369 213.47 7370 221.74 7371 235.98 7372

Manning's n Values num= 3  
 Sta n Val Sta n Val  
 34.45 .037 44.99 .037 114.36 .037

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
 44.99 114.36 0 0 0 .1 .3

CROSS SECTION

RIVER: Donahoo  
 REACH: South RS: 220

INPUT

Description:  
 Station Elevation Data num= 17  
 Sta Elev Sta Elev Sta Elev Sta Elev Sta Elev  
 0 7368 42.06 7368 49.88 7367 60.89 7366 74.49 7365  
 83.35 7364 87.43 7363 91.46 7362 106.89 7362 111.87 7363  
 116.91 7364 122.12 7365 125.65 7366 131.72 7367 182.34 7374  
 190.73 7375 200 7375

Manning's n Values num= 3  
 Sta n Val Sta n Val  
 0 .037 74.49 .037 122.12 .037

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
 74.49 122.12 54.51 54.51 54.51 .1 .3

CROSS SECTION

RIVER: Donahoo  
 REACH: South RS: 166

INPUT

Description:  
 Station Elevation Data num= 26  
 Sta Elev Sta Elev Sta Elev Sta Elev Sta Elev Sta Elev  
 0 7368 10.34 7368 42.55 7367 76.04 7366 94.83 7365  
 104.93 7364 113.94 7363 118.98 7362 124.29 7361 140.74 7361  
 144.96 7362 147.89 7363 150.68 7364 153.39 7365 158.13 7366  
 163.31 7367 168.56 7368 174.47 7369 181.11 7370 187.84 7371  
 196.06 7372 204.09 7373 212.12 7374 221.58 7375 232.37 7376  
 239.16 7376

Manning's n Values num= 3  
 Sta n Val Sta n Val  
 0 .037 104.93 .037 150.68 .037

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
 104.93 150.68 55.66 55.66 55.66 .1 .3

CROSS SECTION

RIVER: Donahoo  
 REACH: South RS: 111

INPUT

Description:  
 Station Elevation Data num= 25  
 Sta Elev Sta Elev Sta Elev Sta Elev Sta Elev Sta Elev  
 0 7368 14.36 7368 65.95 7367 84.24 7366 107.56 7365  
 135.8 7364 147.04 7363 157.63 7362 164.37 7361 168.49 7360  
 180.87 7360 186.93 7361 190.31 7362 193.29 7363 198.02 7364  
 205.49 7365 213.01 7366 220.19 7367 228.13 7368 235.14 7369  
 241.75 7370 249.21 7371 261.55 7372 273.23 7373 277.73 7373

Manning's n Values num= 3

Sta n Val Sta n Val Sta n Val  
 0 .037 135.8 .037 198.02 .037

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
 135.8 198.02 54.05 54.05 54.05 .1 .3

CROSS SECTION

RIVER: Donahoo  
 REACH: South RS: 57

INPUT  
 Description:

Station	Elevation	Data	num=	36	Sta	Elev	Sta	Elev	Sta	Elev
0	7373	5.32	7373	14.62	7372	19.03	7371	51.22	7371	7371
59.89	7370	62.22	7369	64.49	7368	73.31	7367.35	77.97	7367	7367
190.51	7366	228.78	7365	243.38	7364	254.24	7363	261.08	7362	7362
264.67	7361	267.4	7360	270.65	7359	274.58	7358	274.97	7358	7358
281.02	7358.37	291.22	7359	295.26	7360	299.4	7361	304.29	7362	7362
310.04	7363	315.53	7364	321.49	7365	327.9	7366	335.3	7367	7367
343.03	7368	350.62	7369	358.73	7370	367.63	7371	375.61	7372	7372
386.77	7372									

Manning's n Values num= 3  
 Sta n Val Sta n Val Sta n Val  
 0 .037 228.78 .037 321.49 .037

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
 228.78 321.49 57.33 57.33 57.33 .1 .3

CROSS SECTION

RIVER: Donahoo  
 REACH: South RS: 0

INPUT  
 Description:

Station	Elevation	Data	num=	34	Sta	Elev	Sta	Elev	Sta	Elev
0	7372	11.31	7372	16.35	7371	44.64	7371	56.99	7370	7370
59.44	7369	62.15	7368	75.09	7367	157.34	7366	214.53	7365	7365
240.08	7364.21	246.85	7364	263.25	7363	271.08	7362	276.58	7361	7361
279.84	7360	282.52	7359	284.91	7358	287.22	7357	295.87	7357	7357
305.08	7358	308.09	7359	310.96	7360	314.12	7361	317.63	7362	7362
321.63	7363	330.11	7364	337.51	7365	344.65	7366	355.48	7367	7367
365.25	7368	375.06	7369	385.24	7370	392.43	7370			

Manning's n Values num= 3  
 Sta n Val Sta n Val Sta n Val  
 0 .037 263.25 .037 321.63 .037

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
 263.25 321.63 67.85 67.85 67.85 .1 .3

CROSS SECTION

RIVER: Donahoo  
 REACH: South RS: -68

INPUT  
 Description:

Station	Elevation	Data	num=	28	Sta	Elev	Sta	Elev	Sta	Elev
0	7372	10.27	7372	16.57	7371	39.23	7371	55.65	7370	7370
59.35	7370	61.64	7369	63.66	7368	77.78	7367	140.63	7366	7366
199.52	7365	240.15	7364	271.25	7363.14	276.04	7363	288.48	7362	7362
306.18	7361	309.4	7360	312.21	7359	315.17	7358	318.58	7357	7357

328.13	7357	332.46	7358	337.46	7359	344.44	7360	355.47	7361
370.25	7362	385.19	7363	426.42	7363				

Manning's n Values num= 3  
 Sta n Val Sta n Val Sta n Val  
 0 .037 276.04 .037 385.19 .037

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
 276.04 385.19 0 0 0 .1 .3

CROSS SECTION

RIVER: Donahoo  
 REACH: West RS: 980

INPUT  
 Description:

Station	Elevation	Data	num=	40						
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	
0	7368	9.88	7368	33.61	7367	65.56	7366	112.68	7365	
119.66	7364	127.47	7363	137.38	7362	152.4	7361	164.29	7360	
189.33	7360	215.55	7359	243.07	7359	260.42	7358	279.04	7358	
289.41	7357	298.59	7356	303.19	7355.27	304.85	7355	307.91	7355	
311.43	7355.27	321.29	7356	395.22	7357	402.51	7358	407.16	7359	
412.74	7360	423.73	7361	437.76	7362	451.64	7363	467.42	7364	
481.96	7365	490.43	7366	496.81	7367	507.21	7368	516.61	7369	
524.91	7370	533.83	7371	543.14	7372	552.45	7373	553.94	7373	

Manning's n Values num= 3  
 Sta n Val Sta n Val Sta n Val  
 0 .037 164.29 .037 412.74 .037

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
 164.29 412.74 5.44 5.44 5.44 .1 .3

CROSS SECTION

RIVER: Donahoo  
 REACH: West RS: 975

INPUT  
 Description:

Station	Elevation	Data	num=	43						
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	
0	7368	8.76	7368	30.19	7367	59.56	7366	87.84	7365	
95.25	7364	103.27	7363	121.05	7362	130.93	7361	150.38	7360	
173.48	7360	204.03	7359	213.55	7359	246.09	7358	266.91	7358	
278.37	7357	281.44	7356.54	284.98	7356	291.13	7355	298.39	7355	
306.3	7356	316.62	7356.14	379.41	7357	390.5	7358	397.84	7359	
403.41	7360	406.13	7360.15	421.74	7361	422.15	7361	439.5	7362	
461.53	7363	491.23	7364	500.39	7364.73	503.88	7365	511.35	7366	
526.09	7367	530.99	7367.33	540.89	7368	550.48	7369	563.65	7370	
570.85	7371	576.3	7372	605.56	7372					

Manning's n Values num= 3  
 Sta n Val Sta n Val Sta n Val  
 0 .037 173.48 .037 403.41 .037

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.  
 173.48 403.41 10.13 10.13 10.13 .1 .3

CROSS SECTION

RIVER: Donahoo  
 REACH: West RS: 965

INPUT  
 Description:

Station Elevation Data		num= 43									
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	7368	5.43	7368	25.38	7367	54.81	7366	67.47	7365		
74.83	7364	91.64	7363	104.62	7362	114.99	7361	126.37	7361		
153.59	7360	172.11	7360	206.3	7359	218.91	7358	227.31	7358		
267.83	7357.08	271.31	7357	281.26	7356	299.68	7356	305.59	7356.08		
370.58	7357	389.14	7358	398.34	7359	403.79	7360	407.96	7361		
411.9	7362	415.79	7363	419.63	7364	423.33	7365	426.95	7366		
430.6	7367	434.85	7368	438.85	7369	443.86	7370	451.15	7371		
465.71	7372	485.31	7373	501.84	7374	515.58	7375	527.74	7376		
543.23	7377	558.44	7378	566.22	7378						

Manning's n Values		num= 3			
Sta	n Val	Sta	n Val	Sta	n Val
0	.037	172.11	.037	403.79	.037

Bank Sta:	Left	Right	Lengths:	Left	Channel	Right	Coeff	Contr.	Expan.
	172.11	403.79		148	148	148		.1	.3

CROSS SECTION

RIVER: Donahoo  
REACH: West RS: 708

INPUT

Description:

Station Elevation Data		num= 22									
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	7369	6.5	7369	22.93	7368	43.2	7368	53.71	7367		
60.52	7366	66.57	7365	76.39	7364	116.32	7364	136.83	7365		
317.26	7365	343.53	7366	353.71	7366	356.36	7366	439.5	7366		
443.36	7367	453.29	7368	469.51	7369	479.22	7370	488.9	7371		
520.82	7372	535.14	7372								

Manning's n Values		num= 3			
Sta	n Val	Sta	n Val	Sta	n Val
0	.037	66.57	.037	136.83	.037

Bank Sta:	Left	Right	Lengths:	Left	Channel	Right	Coeff	Contr.	Expan.
	66.57	136.83		12.49	12.49	12.49		.1	.3

CROSS SECTION

RIVER: Donahoo  
REACH: West RS: 696

INPUT

Description:

Station Elevation Data		num= 22									
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	7369	6.58	7369	25.78	7368	29.89	7368	53.51	7367		
61.23	7366	67.5	7365	131.45	7365	139.54	7366	147.3	7367		
159.63	7368	312.83	7368	345.47	7368.56	371.75	7369	396.11	7369		
410.09	7368	456.38	7368	468.47	7369	474.74	7370	480.61	7371		
488.95	7372	508.39	7372								

Manning's n Values		num= 3			
Sta	n Val	Sta	n Val	Sta	n Val
0	.037	53.51	.037	147.3	.037

Bank Sta:	Left	Right	Lengths:	Left	Channel	Right	Coeff	Contr.	Expan.
	53.51	147.3		7.45	7.45	7.45		.1	.3

CROSS SECTION

RIVER: Donahoo  
REACH: West RS: 691



111.35	224.52		1.76	1.76	1.76		.1	.3
Ineffective Flow		num=	1					
Sta L	Sta R	Elev	Permanent					
229.34	540.86	7364.99	T					

CROSS SECTION

RIVER: Donahoo  
 REACH: West RS: 577

INPUT

Description:

Station	Elevation	Data	num=	33						
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	
73	7365	80.64	7365	100.8	7364.34	109.67	7364	146.29	7363	
192.85	7363	202.26	7364	206.43	7364	210.52	7363	214.29	7362	
241.2	7361	267.98	7360	282.41	7359	318.14	7358	362.71	7358	
372.65	7359	387.53	7360	403.09	7360	415.32	7359	433.67	7359	
437.96	7360	439.95	7361	441.94	7362	444.57	7363	448.76	7364	
455.39	7365	461.96	7366	468.49	7367	475.4	7368	483.81	7369	
490.93	7370	498.33	7371	504.84	7371					

Manning's n	Values	num=	3			
Sta	n Val	Sta	n Val	Sta	n Val	
73	.037	109.67	.037	455.39	.037	

Bank Sta:	Left	Right	Lengths:	Left	Channel	Right	Coeff	Contr.	Expan.
	109.67	455.39		5.9	5.9	5.9		.1	.3

Ineffective Flow	num=	1						
Sta L	Sta R	Elev	Permanent					
206.68	504.84	7364.01	T					

CROSS SECTION

RIVER: Donahoo  
 REACH: West RS: 551

INPUT

Description:

Station	Elevation	Data	num=	32						
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	
0	7363	20.3	7363	58.2	7362	75.53	7362	82.41	7363	
96.61	7363	101.29	7362	119.76	7361	150.04	7360	166.34	7359	
189.99	7358	231.07	7357.21	241.79	7357	293.41	7357	299.71	7356	
302.21	7356	310.71	7357	315.9	7358	321.02	7359	323.24	7360	
325.46	7361	327.53	7362	329.56	7363	335.74	7364	341.59	7365	
347.6	7366	354.58	7367	362.04	7368	369.92	7369	378.71	7370	
386.19	7371	387.66	7371							

Manning's n	Values	num=	3			
Sta	n Val	Sta	n Val	Sta	n Val	
0	.037	20.3	.037	321.02	.037	

Bank Sta:	Left	Right	Lengths:	Left	Channel	Right	Coeff	Contr.	Expan.
	20.3	321.02		117.49	117.49	117.49		.1	.3

Ineffective Flow	num=	1						
Sta L	Sta R	Elev	Permanent					
97.27	387.66	7362.98	T					

CROSS SECTION

RIVER: Donahoo  
 REACH: West RS: 434

INPUT

Description:

Station	Elevation	Data	num=	36						
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	

0	7363	7.97	7363	34.61	7362	64.74	7361	93.01	7360
114.23	7359	137.27	7358	154.37	7357.88	173.29	7357.7	203.33	7357.42
236.01	7357	236.83	7357	280.24	7356	290.93	7355	295.09	7354
299.84	7353	317.36	7353	323.42	7354	329.34	7355	332.81	7356
336.31	7357	339.65	7358	341.59	7359	343.32	7360	345.12	7361
346.94	7362	350.28	7363	360.03	7364	367.67	7365	374.92	7366
381.17	7367	387.19	7368	393.77	7369	400.02	7370	406.13	7371
416.33	7371								

Manning's n Values

num=	3
Sta n Val	Sta n Val
0 .037	280.24 .037

Bank Sta: Left	Right	Lengths: Left	Channel	Right	Coeff	Contr.	Expan.
280.24	332.81	99.9	99.9	99.9		.1	.3

CROSS SECTION

RIVER: Donahoo  
REACH: West RS: 334

INPUT

Description:

Station Elevation Data	num=	38
Sta Elev Sta Elev Sta Elev Sta Elev Sta Elev		
0 7363 6.11 7363 30.86 7362 60.38 7361 75.78 7360.46		
89.03 7360 118.76 7359 141.12 7358 157.3 7357 181.32 7356		
194.55 7356 226.89 7355 230.87 7354 234.6 7353 241.49 7352.93		
260.49 7352.46 279.57 7352 299.37 7352 303.3 7353 307 7354		
310.39 7355 312.91 7356 315.36 7357 317.91 7358 320.5 7359		
323.06 7360 328.09 7361 334.68 7362 341.93 7363 349.95 7364		
357.98 7365 366.3 7366 372.63 7367 378.43 7368 385.35 7369		
393.5 7370 412.42 7371 415.14 7371		

Manning's n Values

num=	3
Sta n Val	Sta n Val
0 .037	226.89 .037

Bank Sta: Left	Right	Lengths: Left	Channel	Right	Coeff	Contr.	Expan.
226.89	310.39	41.18	41.18	41.18		.1	.3

CROSS SECTION

RIVER: Donahoo  
REACH: West RS: 293

INPUT

Description:

Station Elevation Data	num=	35
Sta Elev Sta Elev Sta Elev Sta Elev Sta Elev		
0 7360.28 53.27 7360.28 53.27 7361 57.91 7361 76.23 7360.51		
94.57 7360 124.82 7359 142.44 7358 160.36 7357 184.78 7356		
205 7356 227.64 7355 230.69 7354 234.42 7353 247.93 7352		
257.18 7351 261.84 7351 266.98 7352 272.41 7353 277.47 7354		
280.46 7355 283.4 7356 286.19 7357 289.28 7358 295.48 7359		
301.69 7360 308.11 7361 314.56 7362 321.37 7363 329.19 7364		
343.81 7365 380.75 7366 390 7366 390 7364.13 395.26 7364.13		

Manning's n Values

num=	3
Sta n Val	Sta n Val
0 .037	230.69 .037

Bank Sta: Left	Right	Lengths: Left	Channel	Right	Coeff	Contr.	Expan.
230.69	277.47	74.34	74.34	74.34		.1	.3

CROSS SECTION

RIVER: Donahoo

REACH: West RS: 219

INPUT

Description:

Station	Elevation	Data	num=	33	Sta	Elev	Sta	Elev	Sta	Elev
0	7361	16.73	7361	42.79	7360	82.74	7359	119.54	7358	
123.52	7358	143.97	7357.72	196.79	7357	217.14	7356	226.5	7355	
227.01	7355	235.62	7354	243.69	7353	252.5	7352	277.45	7351.19	
284.31	7352	287.14	7352.48	290.24	7353	295.89	7354	311.34	7355	
326.67	7356	327.75	7356	348.75	7357	359.81	7357	367.65	7358	
371.75	7359	393.03	7359	396.55	7358	426.48	7358	442.95	7359	
462.05	7360	487.93	7361	506.06	7361					

Manning's n Values

Sta	n Val	Sta	n Val	Sta	n Val
0	.037	227.01	.037	311.34	.037

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.	Expan.
	227.01	311.34		76.13	76.13		.1	.3

CULVERT

RIVER: Donahoo

REACH: West RS: 183

INPUT

Description:

Distance from Upstream XS = 20.44

Deck/Roadway Width = 27.92

Weir Coefficient = 2.6

Upstream Deck/Roadway Coordinates

num=	28	Sta	Hi	Cord	Lo	Cord	Sta	Hi	Cord	Lo	Cord
-177.92	7363.3	0	-176.64	7363	0	-145.12	7362	0			
-110.69	7361	0	-68.83	7358.6	0	-9.45	7359	0			
0	7363.32	0	0	7363.05	0	1.13	7363.29	0			
45.21	7361.94	0	97.44	7360.34	0	98.79	7360.32	0			
99.47	7360.31	0	175.65	7359.14	0	199.85	7358.77	0			
200.52	7358.77	0	234.94	7358.64	0	273.32	7358.5	0			
276.48	7358.49	0	277.01	7358.49	0	285.3	7358.46	0			
288.69	7358.51	0	373.47	7359.76	0	400.59	7360.73	0			
449.42	7362.47	0	505.72	7364.77	0	507.07	7364.83	0			
507.75	7362.23	0									

Upstream Bridge Cross Section Data

Station	Elevation	Data	num=	33	Sta	Elev	Sta	Elev	Sta	Elev
0	7361	16.73	7361	42.79	7360	82.74	7359	119.54	7358	
123.52	7358	143.97	7357.72	196.79	7357	217.14	7356	226.5	7355	
227.01	7355	235.62	7354	243.69	7353	252.5	7352	277.45	7351.19	
284.31	7352	287.14	7352.48	290.24	7353	295.89	7354	311.34	7355	
326.67	7356	327.75	7356	348.75	7357	359.81	7357	367.65	7358	
371.75	7359	393.03	7359	396.55	7358	426.48	7358	442.95	7359	
462.05	7360	487.93	7361	506.06	7361					

Manning's n Values

Sta	n Val	Sta	n Val	Sta	n Val
0	.037	227.01	.037	311.34	.037

Bank Sta:	Left	Right	Coeff	Contr.	Expan.
	227.01	311.34		.1	.3

Downstream Deck/Roadway Coordinates

num=	28	Sta	Hi	Cord	Lo	Cord	Sta	Hi	Cord	Lo	Cord
-177.92	7363.3	0	-176.64	7363	0	-145.12	7362	0			
-110.69	7361	0	-68.83	7358.6	0	-9.45	7359	0			
0	7363.32	0	0	7363.05	0	1.13	7363.29	0			
45.21	7361.94	0	97.44	7360.34	0	98.79	7360.32	0			

99.47	7360.31	0	175.65	7359.14	0	199.85	7358.77	0
200.52	7358.77	0	234.94	7358.64	0	273.32	7358.5	0
276.48	7358.49	0	277.01	7358.49	0	285.3	7358.46	0
288.69	7358.51	0	373.47	7359.76	0	400.59	7360.73	0
449.42	7362.47	0	505.72	7364.77	0	507.07	7364.83	0
507.75	7362.23	0						

Downstream Bridge Cross Section Data

Station	Elevation	Data	num=	31						
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	
0	7364	11.36	7364	30.29	7363	49.58	7362	74.37	7361	
97.87	7360	116.86	7359	140.68	7358	165.55	7357	184.12	7356	
250.96	7355	262.04	7354	269.53	7353	279.68	7352	292.9	7351.02	
293.13	7351	296.65	7350	305.63	7350	315.12	7350.98	315.32	7351	
318.49	7352	321.67	7353	327.92	7354	372.9	7355	399.41	7356	
424.04	7357	452.89	7358	467.24	7359	481.6	7360	500.57	7361	
504.34	7361									

Manning's n Values

num=	3				
Sta	n Val	Sta	n Val	Sta	n Val
0	.037	269.53	.037	321.67	.037

Bank Sta:	Left	Right	Coeff	Contr.	Expan.
	269.53	321.67	.1		.3

Upstream Embankment side slope = 1.7 horiz. to 1.0 vertical  
Downstream Embankment side slope = 2 horiz. to 1.0 vertical  
Maximum allowable submergence for weir flow = .98  
Elevation at which weir flow begins =  
Energy head used in spillway design =  
Spillway height used in design =  
Weir crest shape = Broad Crested

Number of Culverts = 1

Culvert Name	Shape	Rise	Span
Culvert #1	Circular	5	

FHWA Chart # 2 - Corrugated Metal Pipe Culvert  
FHWA Scale # 2 - Mitered to conform to slope  
Solution Criteria = Highest U.S. EG

Culvert Upstrm Dist	Length	Top n	Bottom n	Depth Blocked	Entrance Loss Coef	Exit Loss Coef
2.49	61.42	.023	.023	0	.7	1

Number of Barrels = 2  
Upstream Elevation = 7350.5  
Centerline Stations  
Sta. Sta.  
272.91 280.64  
Downstream Elevation = 7349.9  
Centerline Stations  
Sta. Sta.  
301.4 309.2

CROSS SECTION

RIVER: Donahoo  
REACH: West RS: 142

INPUT

Description:

Station	Elevation	Data	num=	31						
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	
0	7364	11.36	7364	30.29	7363	49.58	7362	74.37	7361	
97.87	7360	116.86	7359	140.68	7358	165.55	7357	184.12	7356	
250.96	7355	262.04	7354	269.53	7353	279.68	7352	292.9	7351.02	
293.13	7351	296.65	7350	305.63	7350	315.12	7350.98	315.32	7351	
318.49	7352	321.67	7353	327.92	7354	372.9	7355	399.41	7356	
424.04	7357	452.89	7358	467.24	7359	481.6	7360	500.57	7361	
504.34	7361									

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
0	.037	269.53	.037	321.67	.037

Bank Sta:	Left	Right	Lengths:	Left	Channel	Right	Coeff	Contr.	Expan.
	269.53	321.67		40.73	40.73	40.73		.1	.3

CROSS SECTION

RIVER: Donahoo  
REACH: West RS: 102

INPUT  
Description:  
Station Elevation Data num= 12

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	7354	8.14	7354	10.96	7353	13.8	7352	17.74	7351
40.46	7350	66.02	7350	68.83	7351	71.64	7352	74.46	7353
127.15	7354	131.66	7354						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
0	.037	10.96	.037	74.46	.037

Bank Sta:	Left	Right	Lengths:	Left	Channel	Right	Coeff	Contr.	Expan.
	10.96	74.46		42.06	42.06	42.06		.1	.3

CROSS SECTION

RIVER: Donahoo  
REACH: West RS: 60

INPUT  
Description:  
Station Elevation Data num= 13

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	7353	2.46	7353	5.62	7352	8.69	7351	19.17	7350
26.62	7349.8	50.6	7349	63.21	7349	73.56	7350	76.57	7351
79.6	7352	84.49	7353	142.41	7353				

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
0	.037	5.62	.037	79.6	.037

Bank Sta:	Left	Right	Lengths:	Left	Channel	Right	Coeff	Contr.	Expan.
	5.62	79.6		57.32	57.32	57.32		.1	.3

CROSS SECTION

RIVER: Donahoo  
REACH: West RS: 2

INPUT  
Description:  
Station Elevation Data num= 15

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	7353	22.44	7353	25.86	7352	29.31	7351	36.51	7350
97.41	7349	99.26	7348.9	113.03	7348	120.89	7348	125.35	7349
128.46	7350	130.83	7350.82	131.38	7351	138.75	7352	190.16	7352

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
0	.037	29.31	.037	131.38	.037

Bank Sta:	Left	Right	Lengths:	Left	Channel	Right	Coeff	Contr.	Expan.
	29.31	131.38		0	0	0		.1	.3

SUMMARY OF MANNING'S N VALUES

River: Donahoo

Reach	River Sta.	n1	n2	n3
East	728	.037	.037	.037
East	676	.037	.037	.037
East	624	.037	.037	.037
East	572	.037	.037	.037
East	520	.037	.037	.037
East	468	.037	.037	.037
East	416	.037	.037	.037
East	364	.037	.037	.037
East	312	.037	.037	.037
East	260	.037	.037	.037
East	210	.037	.037	.037
East	159	.037	.037	.037
East	109	.037	.037	.037
East	53	.037	.037	.037
East	14	.037	.037	.037
East	-49	.037	.037	.037
South	220	.037	.037	.037
South	166	.037	.037	.037
South	111	.037	.037	.037
South	57	.037	.037	.037
South	0	.037	.037	.037
South	-68	.037	.037	.037
West	980	.037	.037	.037
West	975	.037	.037	.037
West	965	.037	.037	.037
West	708	.037	.037	.037
West	696	.037	.037	.037
West	691	.037	.037	.037
West	674	.037	.037	.037
West	603	.037	.037	.037
West	577	.037	.037	.037
West	551	.037	.037	.037
West	434	.037	.037	.037
West	334	.037	.037	.037
West	293	.037	.037	.037
West	219	.037	.037	.037
West	183	Culvert		
West	142	.037	.037	.037
West	102	.037	.037	.037
West	60	.037	.037	.037
West	2	.037	.037	.037

SUMMARY OF REACH LENGTHS

River: Donahoo

Reach	River Sta.	Left	Channel	Right
East	728	51.56	51.56	51.56
East	676	51.56	51.56	51.56
East	624	51.56	51.56	51.56
East	572	51.56	51.56	51.56
East	520	51.56	51.56	51.56
East	468	51.56	51.56	51.56
East	416	51.56	51.56	51.56
East	364	51.56	51.56	51.56
East	312	51.56	51.56	51.56
East	260	49.2	49.2	49.2
East	210	51.1	51.1	51.1
East	159	49.3	49.3	49.3
East	109	55.64	55.64	55.64
East	53	39.8	39.8	39.8

East	14	62.95	62.95	62.95
East	-49	0	0	0
South	220	54.51	54.51	54.51
South	166	55.66	55.66	55.66
South	111	54.05	54.05	54.05
South	57	57.33	57.33	57.33
South	0	67.85	67.85	67.85
South	-68	0	0	0
West	980	5.44	5.44	5.44
West	975	10.13	10.13	10.13
West	965	148	148	148
West	708	12.49	12.49	12.49
West	696	7.45	7.45	7.45
West	691	15.64	15.64	15.64
West	674	2.03	2.03	2.03
West	603	1.76	1.76	1.76
West	577	5.9	5.9	5.9
West	551	117.49	117.49	117.49
West	434	99.9	99.9	99.9
West	334	41.18	41.18	41.18
West	293	74.34	74.34	74.34
West	219	76.13	76.13	76.13
West	183	Culvert		
West	142	40.73	40.73	40.73
West	102	42.06	42.06	42.06
West	60	57.32	57.32	57.32
West	2	0	0	0

SUMMARY OF CONTRACTION AND EXPANSION COEFFICIENTS  
River: Donahoo

Reach	River Sta.	Contr.	Expan.
East	728	.1	.3
East	676	.1	.3
East	624	.1	.3
East	572	.1	.3
East	520	.1	.3
East	468	.1	.3
East	416	.1	.3
East	364	.1	.3
East	312	.1	.3
East	260	.1	.3
East	210	.1	.3
East	159	.1	.3
East	109	.1	.3
East	53	.1	.3
East	14	.1	.3
East	-49	.1	.3
South	220	.1	.3
South	166	.1	.3
South	111	.1	.3
South	57	.1	.3
South	0	.1	.3
South	-68	.1	.3
West	980	.1	.3
West	975	.1	.3
West	965	.1	.3
West	708	.1	.3
West	696	.1	.3
West	691	.1	.3
West	674	.1	.3
West	603	.1	.3
West	577	.1	.3
West	551	.1	.3
West	434	.1	.3
West	334	.1	.3

West	293	.1	.3
West	219	.1	.3
West	183	Culvert	
West	142	.1	.3
West	102	.1	.3
West	60	.1	.3
West	2	.1	.3

Profile Output Table - MVE Standard Table

Reach	River Sta	Profile	Q Total (cfs)	Min Ch El (ft)	W.S. Elev (ft)	Crit W.S. (ft)	E.G. Elev (ft)	E.G. Slope (ft/ft)	Max Chl Dpth (ft)	Hydr Depth C (ft)	Flow Area (sq ft)	Top Width (ft)	Vel Chnl (ft/s)	Froude # Ch1	Shear Chan (lb/sq ft)
East	728	100yr	391.90	7373.00	7374.60	7374.62	7375.30	0.019389	1.60	1.33	58.18	43.65	6.74	1.03	1.60
East	728	5yr	74.80	7373.00	7373.56	7373.56	7373.84	0.026162	0.56	0.52	17.85	34.33	4.19	1.02	0.85
East	676	100yr	391.90	7371.00	7372.51	7372.90	7373.85	0.040244	1.51	1.25	42.28	33.88	9.27	1.46	3.10
East	676	5yr	74.80	7371.00	7371.56	7371.68	7372.04	0.047445	0.56	0.51	13.46	26.43	5.56	1.37	1.50
East	624	100yr	391.90	7370.00	7372.78	7372.19	7373.16	0.006551	2.78	1.90	79.40	41.89	4.94	0.63	0.77
East	624	5yr	74.80	7370.00	7371.35	7370.99	7371.46	0.005582	1.34	0.88	27.19	30.78	2.75	0.52	0.31
East	572	100yr	391.90	7370.00	7372.03	7371.89	7372.66	0.013720	2.03	1.60	61.46	40.14	6.38	0.89	1.35
East	572	5yr	74.80	7370.00	7370.80	7371.02	7371.02	0.014274	0.80	0.70	19.94	28.67	3.75	0.79	0.62
East	520	100yr	391.90	7369.00	7371.07	7371.07	7371.84	0.017753	2.07	1.54	55.38	36.59	7.08	1.00	1.69
East	520	5yr	74.80	7369.00	7369.89	7369.84	7370.17	0.019173	0.89	0.66	17.79	26.86	4.20	0.91	0.79
East	468	100yr	391.90	7368.00	7369.86	7370.00	7370.78	0.023807	1.86	1.39	51.09	36.71	7.67	1.15	2.05
East	468	5yr	74.80	7368.00	7368.75	7368.75	7369.08	0.023466	0.75	0.64	16.43	25.65	4.55	1.00	0.93
East	416	100yr	391.90	7366.00	7367.48	7367.94	7368.96	0.052396	1.48	1.10	40.14	36.39	9.76	1.64	3.58
East	416	5yr	74.80	7366.00	7366.57	7366.75	7367.17	0.064055	0.57	0.48	12.01	24.94	6.23	1.58	1.92
East	364	100yr	391.90	7365.00	7367.94	7366.74	7368.12	0.002511	2.94	2.26	114.33	50.66	3.43	0.40	0.35
East	364	5yr	74.80	7365.00	7366.13	7365.67	7366.20	0.003554	1.13	0.89	33.86	38.03	2.21	0.41	0.20
East	312	100yr	391.90	7364.00	7367.90	7368.02	7368.02	0.001035	3.90	3.23	142.41	48.59	2.79	0.27	0.20
East	312	5yr	74.80	7364.00	7366.12	7366.12	7366.14	0.000413	2.12	1.70	64.97	38.21	1.15	0.16	0.04
East	260	100yr	391.90	7363.00	7367.91	7367.98	7367.98	0.000425	4.90	4.50	197.94	62.93	2.23	0.19	0.12
East	260	5yr	74.80	7363.00	7366.12	7366.12	7366.13	0.000102	3.12	2.71	100.39	46.68	0.78	0.08	0.02
East	210	100yr	391.90	7361.00	7367.93	7367.93	7367.95	0.000115	6.93	5.34	332.96	95.48	1.30	0.10	0.04
East	210	5yr	74.80	7361.00	7366.12	7366.12	7366.12	0.000019	5.12	3.54	189.09	56.92	0.40	0.04	0.00
East	159	100yr	391.90	7360.00	7367.93	7367.93	7367.94	0.000051	7.93	6.69	481.58	112.94	1.01	0.07	0.02
East	159	5yr	74.80	7360.00	7366.12	7366.12	7366.12	0.000007	6.12	4.87	294.38	94.87	0.31	0.02	0.00
East	109	100yr	391.90	7359.00	7367.93	7367.93	7367.94	0.000025	8.93	7.64	632.15	128.16	0.77	0.05	0.01
East	109	5yr	74.80	7359.00	7366.12	7366.12	7366.12	0.000003	7.12	5.83	415.34	110.86	0.22	0.02	0.00
East	53	100yr	391.90	7359.00	7367.93	7367.93	7367.94	0.000019	8.93	6.81	695.40	137.40	0.63	0.04	0.01
East	53	5yr	74.80	7359.00	7366.12	7366.12	7366.12	0.000002	7.12	5.00	463.95	117.97	0.17	0.01	0.00
East	14	100yr	391.90	7358.00	7367.93	7367.93	7367.94	0.000014	9.93	8.32	802.08	162.67	0.60	0.04	0.01
East	14	5yr	74.80	7358.00	7366.12	7366.12	7366.12	0.000001	8.12	6.50	521.49	146.94	0.17	0.01	0.00
East	-49	100yr	391.90	7357.00	7367.94	7367.94	7367.94	0.000006	10.93	9.54	1047.48	165.13	0.45	0.03	0.00
East	-49	5yr	74.80	7357.00	7366.12	7366.12	7366.12	0.000001	9.12	7.73	761.66	149.42	0.12	0.01	0.00
South	220	100yr	597.20	7362.00	7367.91	7364.76	7367.98	0.000407	5.91	4.79	299.89	95.56	2.28	0.18	0.12
South	220	5yr	120.30	7362.00	7366.12	7363.10	7366.13	0.000098	4.12	3.00	153.56	66.79	0.82	0.08	0.02
South	166	100yr	597.20	7361.00	7367.92	7367.92	7367.96	0.000181	6.92	5.91	442.10	155.28	1.75	0.13	0.07
South	166	5yr	120.30	7361.00	7366.12	7366.12	7366.13	0.000035	5.12	4.11	223.61	86.72	0.60	0.05	0.01
South	111	100yr	597.20	7360.00	7367.93	7367.93	7367.95	0.000081	7.93	6.16	642.74	209.56	1.20	0.09	0.03
South	111	5yr	120.30	7360.00	7366.12	7366.12	7366.12	0.000014	6.12	4.35	347.93	131.84	0.40	0.03	0.00

South	57	100yr	597.20	7358.00	7367.93		7367.94	0.000042	9.93	6.18	862.35	277.09	0.87	0.06	0.02
South	57	5yr	120.30	7358.00	7366.12		7366.12	0.000008	8.12	4.37	433.38	151.86	0.29	0.02	0.00
South	0	100yr	597.20	7357.00	7367.93		7367.94	0.000027	10.93	8.26	1028.47	301.55	0.83	0.05	0.01
South	0	5yr	120.30	7357.00	7366.12		7366.12	0.000004	9.12	6.45	546.81	198.54	0.28	0.02	0.00
South	-68	100yr	597.20	7357.00	7367.93		7367.94	0.000010	10.93	7.39	1548.16	361.83	0.49	0.03	0.00
South	-68	5yr	120.30	7357.00	7366.12		7366.12	0.000002	9.12	5.58	934.05	293.37	0.16	0.01	0.00
West	980	100yr	1105.10	7355.00	7367.94		7367.94	0.000004	12.93	10.16	3393.73	495.10	0.37	0.02	0.00
West	980	5yr	212.50	7355.00	7366.12		7366.12	0.000000	11.12	8.34	2553.62	429.51	0.09	0.01	0.00
West	975	100yr	1105.10	7355.00	7367.94		7367.94	0.000004	12.94	10.39	3649.52	529.78	0.36	0.02	0.00
West	975	5yr	212.50	7355.00	7366.12		7366.12	0.000000	11.12	8.57	2751.16	457.13	0.09	0.01	0.00
West	965	100yr	1105.10	7356.00	7367.94		7367.94	0.000004	11.93	10.45	3290.98	427.84	0.38	0.02	0.00
West	965	5yr	212.50	7356.00	7366.12		7366.12	0.000000	10.12	8.64	2558.33	376.15	0.09	0.01	0.00
West	708	100yr	1105.10	7364.00	7367.92		7367.93	0.000174	3.92	3.70	1071.56	408.36	1.26	0.12	0.04
West	708	5yr	212.50	7364.00	7366.11		7366.12	0.000179	2.11	1.90	364.94	380.19	0.82	0.11	0.02
West	696	100yr	1105.10	7365.00	7367.36	7366.95	7367.88	0.008056	2.36	2.03	193.16	106.69	5.78	0.71	1.02
West	696	5yr	212.50	7365.00	7365.94		7365.10	0.007836	0.94	0.86	66.34	77.43	3.20	0.61	0.42
West	691	100yr	1105.10	7365.00	7366.94	7366.94	7367.76	0.017131	1.94	1.64	151.52	92.40	7.29	1.00	1.75
West	691	5yr	212.50	7365.00	7365.67	7365.67	7365.99	0.023282	0.67	0.64	46.96	73.90	4.52	1.00	0.92
West	674	100yr	1105.10	7364.00	7366.35	7366.35	7366.68	0.007677	8.35	1.76	293.20	413.43	5.12	0.68	0.84
West	674	5yr	212.50	7364.00	7365.00	7365.00	7365.30	0.024109	7.00	0.60	48.09	365.12	4.42	1.01	0.90
West	603	100yr	1105.10	7363.00	7365.30	7365.28	7365.66	0.008398	7.29	1.66	269.74	386.95	5.16	0.71	0.87
West	603	5yr	212.50	7363.00	7363.93	7363.93	7364.23	0.024188	5.93	0.59	48.43	328.41	4.39	1.01	0.89
West	577	100yr	1105.10	7358.00	7364.15	7364.50	7365.52	0.228423	6.15	0.34	117.58	343.92	9.41	2.83	4.90
West	577	5yr	212.50	7358.00	7363.60	7363.76	7364.14	0.056161	5.60	0.49	36.08	313.10	5.89	1.49	1.71
West	551	100yr	1105.10	7356.00	7363.26	7363.57	7364.38	0.148661	7.26	0.41	131.53	331.19	8.55	2.35	3.80
West	551	5yr	212.50	7356.00	7362.79	7363.09	7363.70	0.085443	6.79	0.53	27.80	284.37	7.65	1.86	2.80
West	434	100yr	1105.10	7353.00	7360.01	7356.57	7360.05	0.000223	7.01	5.94	779.60	250.56	1.95	0.14	0.08
West	434	5yr	212.50	7353.00	7355.42	7354.41	7355.55	0.002653	2.42	1.66	73.74	44.38	2.88	0.39	0.27
West	334	100yr	1105.10	7352.00	7360.01		7360.03	0.000080	8.01	7.34	1017.00	234.31	1.35	0.09	0.04
West	334	5yr	212.50	7352.00	7355.47		7355.48	0.000130	3.47	2.80	237.59	99.81	0.91	0.10	0.02
West	293	100yr	1105.10	7351.00	7359.98		7360.03	0.000152	8.98	7.75	790.94	206.51	1.92	0.12	0.07
West	293	5yr	212.50	7351.00	7355.44		7355.47	0.000258	4.44	3.21	158.37	64.11	1.39	0.14	0.05
West	219	100yr	1127.20	7351.19	7359.99	7354.55	7360.01	0.000070	8.80	7.10	1305.19	418.86	1.23	0.08	0.03
West	219	5yr	216.00	7351.19	7355.44	7352.70	7355.45	0.000181	4.25	2.54	217.06	95.59	1.00	0.11	0.03
West	183			Culvert											
West	142	100yr	1127.20	7350.00	7353.73	7353.73	7354.88	0.013976	3.73	2.48	133.08	62.13	8.64	0.97	2.14
West	142	5yr	216.00	7350.00	7351.81	7351.75	7352.29	0.017121	1.81	1.09	38.97	35.64	5.54	0.93	1.16
West	102	100yr	1127.20	7350.00	7352.22	7352.69	7353.99	0.032702	2.22	1.79	105.90	59.11	10.64	1.40	3.62
West	102	5yr	216.00	7350.00	7351.07	7351.07	7351.48	0.021961	1.07	0.81	41.83	51.55	5.16	1.01	1.11
West	60	100yr	1127.20	7349.00	7351.48	7351.67	7352.70	0.022508	2.48	1.80	127.13	70.79	8.87	1.17	2.51
West	60	5yr	216.00	7349.00	7350.45	7350.19	7350.66	0.008714	1.45	0.97	58.80	60.47	3.67	0.66	0.53
West	2	100yr	1127.20	7348.00	7350.82	7350.84	7351.63	0.017727	2.82	1.56	156.92	100.27	7.18	1.01	1.72
West	2	5yr	216.00	7348.00	7349.65	7349.58	7349.95	0.018718	1.65	0.71	49.47	69.57	4.37	0.91	0.83

ERRORS WARNINGS AND NOTES

Errors Warnings and Notes for Plan : Default

River: Donahoo Reach: East RS: 728 Profile: 5yr  
Warning: The energy equation could not be balanced within the specified number of iterations. The program used critical depth for the water surface and continued on with the calculations.  
Warning: The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross section. This may indicate the need for additional cross sections.  
Warning: During the standard step iterations, when the assumed water surface was set equal to critical depth, the calculated water surface came back below critical depth. This indicates that there is not a valid subcritical answer. The program defaulted to critical depth.

River: Donahoo Reach: East RS: 676 Profile: 100yr  
Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.  
Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4. This may indicate the need for additional cross sections.  
Warning: The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross section. This may indicate the need for additional cross sections.

River: Donahoo Reach: East RS: 676 Profile: 5yr  
Warning: The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross section. This may indicate the need for additional cross sections.

River: Donahoo Reach: East RS: 624 Profile: 100yr  
Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4. This may indicate the need for additional cross sections.  
Note: Hydraulic jump has occurred between this cross section and the previous upstream section.

River: Donahoo Reach: East RS: 624 Profile: 5yr  
Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4. This may indicate the need for additional cross sections.  
Note: Hydraulic jump has occurred between this cross section and the previous upstream section.

River: Donahoo Reach: East RS: 520 Profile: 100yr  
Warning: The energy equation could not be balanced within the specified number of iterations. The program used critical depth for the water surface and continued on with the calculations.  
Warning: The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross section. This may indicate the need for additional cross sections.  
Warning: During the standard step iterations, when the assumed water surface was set equal to critical depth, the calculated water surface came back below critical depth. This indicates that there is not a valid subcritical answer. The program defaulted to critical depth.

River: Donahoo Reach: East RS: 520 Profile: 5yr  
Warning: The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross section. This may indicate the need for additional cross sections.

River: Donahoo Reach: East RS: 468 Profile: 100yr  
Warning: The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross section. This may indicate the need for additional cross sections.  
Note: Program found supercritical flow starting at this cross section.

River: Donahoo Reach: East RS: 468 Profile: 5yr  
Warning: The energy equation could not be balanced within the specified number of iterations. The program used critical depth for the water surface and continued on with the calculations.  
Warning: The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross section. This may indicate the need for additional cross sections.  
Warning: During the standard step iterations, when the assumed water surface was set equal to critical depth, the calculated water surface came back below critical depth. This indicates that there is not a valid subcritical answer. The program defaulted to critical depth.

River: Donahoo Reach: East RS: 416 Profile: 100yr  
Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.  
Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4. This may indicate the need for additional cross sections.  
Warning: The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross section. This may indicate the need for additional cross sections.

River: Donahoo Reach: East RS: 416 Profile: 5yr  
Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4. This may indicate the need for additional cross sections.  
Warning: The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross section. This may indicate the need for additional cross sections.  
Note: Program found supercritical flow starting at this cross section.

River: Donahoo Reach: East RS: 364 Profile: 100yr  
Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4. This may indicate the need for additional cross sections.  
Note: Hydraulic jump has occurred between this cross section and the previous upstream section.

River: Donahoo Reach: East RS: 364 Profile: 5yr  
Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4. This may indicate the need for additional cross sections.  
Note: Hydraulic jump has occurred between this cross section and the previous upstream section.

River: Donahoo Reach: East RS: 312 Profile: 100yr  
Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4. This may indicate the need for additional cross sections.



Warning:The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.  
This may indicate the need for additional cross sections.

River: Donahoo Reach: West RS: 691 Profile: 100yr  
Warning:The energy equation could not be balanced within the specified number of iterations. The program used critical depth for the water surface and continued on with the calculations.

Warning:The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.  
This may indicate the need for additional cross sections.

Warning:The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross section. This may indicate the need for additional cross sections.

Warning:During the standard step iterations, when the assumed water surface was set equal to critical depth, the calculated water surface came back below critical depth. This indicates that there is not a valid subcritical answer. The program defaulted to critical depth.

River: Donahoo Reach: West RS: 691 Profile: 5yr  
Warning:The energy equation could not be balanced within the specified number of iterations. The program used critical depth for the water surface and continued on with the calculations.

Warning:During the standard step iterations, when the assumed water surface was set equal to critical depth, the calculated water surface came back below critical depth. This indicates that there is not a valid subcritical answer. The program defaulted to critical depth.

River: Donahoo Reach: West RS: 674 Profile: 100yr  
Warning:The energy equation could not be balanced within the specified number of iterations. The program used critical depth for the water surface and continued on with the calculations.

Warning:The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.  
This may indicate the need for additional cross sections.

Warning:The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross section. This may indicate the need for additional cross sections.

Note: Program found supercritical flow starting at this cross section.

River: Donahoo Reach: West RS: 674 Profile: 5yr  
Warning:The energy equation could not be balanced within the specified number of iterations. The program used critical depth for the water surface and continued on with the calculations.

Warning:Divided flow computed for this cross-section.

Warning:The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross section. This may indicate the need for additional cross sections.

Warning:During the standard step iterations, when the assumed water surface was set equal to critical depth, the calculated water surface came back below critical depth. This indicates that there is not a valid subcritical answer. The program defaulted to critical depth.

River: Donahoo Reach: West RS: 603 Profile: 100yr  
Warning:The energy equation could not be balanced within the specified number of iterations. The program used critical depth for the water surface and continued on with the calculations.

Warning:The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.  
This may indicate the need for additional cross sections.

Warning:During the standard step iterations, when the assumed water surface was set equal to critical depth, the calculated water surface came back below critical depth. This indicates that there is not a valid subcritical answer. The program defaulted to critical depth.

River: Donahoo Reach: West RS: 603 Profile: 5yr  
Warning:The energy equation could not be balanced within the specified number of iterations. The program used critical depth for the water surface and continued on with the calculations.

Warning:Divided flow computed for this cross-section.

Warning:During the standard step iterations, when the assumed water surface was set equal to critical depth, the calculated water surface came back below critical depth. This indicates that there is not a valid subcritical answer. The program defaulted to critical depth.

River: Donahoo Reach: West RS: 577 Profile: 100yr  
Warning:The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.

Warning:The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.  
This may indicate the need for additional cross sections.

River: Donahoo Reach: West RS: 577 Profile: 5yr  
Warning:Divided flow computed for this cross-section.

Warning:The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.  
This may indicate the need for additional cross sections.

River: Donahoo Reach: West RS: 551 Profile: 100yr  
Warning:The cross-section end points had to be extended vertically for the computed water surface.

Warning:The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross section. This may indicate the need for additional cross sections.

River: Donahoo Reach: West RS: 551 Profile: 5yr  
Warning:Divided flow computed for this cross-section.

River: Donahoo Reach: West RS: 434 Profile: 100yr  
Warning:The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.  
This may indicate the need for additional cross sections.

Note: Hydraulic jump has occurred between this cross section and the previous upstream section.

River: Donahoo Reach: West RS: 434 Profile: 5yr  
Warning:The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.  
This may indicate the need for additional cross sections.

Note: Hydraulic jump has occurred between this cross section and the previous upstream section.

River: Donahoo Reach: West RS: 334 Profile: 5yr  
Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.  
This may indicate the need for additional cross sections.

River: Donahoo Reach: West RS: 293 Profile: 100yr  
Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.  
This may indicate the need for additional cross sections.

River: Donahoo Reach: West RS: 183 Profile: 100yr  
Warning: The flow through the culvert is supercritical. However, since there is flow over the road (weir flow), the program cannot determine if the downstream cross section should be subcritical or supercritical. The program used the downstream subcritical answer, even though it may not be valid.

River: Donahoo Reach: West RS: 183 Profile: 100yr Culv: Culvert #1  
Warning: During the supercritical analysis, the program could not converge on a supercritical answer in the downstream cross section. The program used the solution with the least error.

Note: The normal depth exceeds the height of the culvert. The program assumes that the normal depth is equal to the height of the culvert.

Note: The flow in the culvert is entirely supercritical.

River: Donahoo Reach: West RS: 142 Profile: 100yr  
Warning: The energy equation could not be balanced within the specified number of iterations. The program used critical depth for the water surface and continued on with the calculations.  
Warning: The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross section. This may indicate the need for additional cross sections.  
Warning: During the standard step iterations, when the assumed water surface was set equal to critical depth, the calculated water surface came back below critical depth. This indicates that there is not a valid subcritical answer. The program defaulted to critical depth.

River: Donahoo Reach: West RS: 102 Profile: 100yr  
Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.  
Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.  
This may indicate the need for additional cross sections.

River: Donahoo Reach: West RS: 102 Profile: 5yr  
Warning: The energy equation could not be balanced within the specified number of iterations. The program used critical depth for the water surface and continued on with the calculations.  
Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.  
This may indicate the need for additional cross sections.  
Warning: During the standard step iterations, when the assumed water surface was set equal to critical depth, the calculated water surface came back below critical depth. This indicates that there is not a valid subcritical answer. The program defaulted to critical depth.

River: Donahoo Reach: West RS: 60 Profile: 100yr  
Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.  
Warning: The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross section. This may indicate the need for additional cross sections.

River: Donahoo Reach: West RS: 60 Profile: 5yr  
Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.  
This may indicate the need for additional cross sections.

Note: Hydraulic jump has occurred between this cross section and the previous upstream section.

River: Donahoo Reach: West RS: 2 Profile: 100yr  
Warning: Slope too steep for slope area to converge during supercritical flow calculations (normal depth is below critical depth). Water surface set to critical depth.

## **VI. Permissible Shear and Velocity for Selected Lining Materials**



**Table 2. Permissible Shear and Velocity for Selected Lining Materials<sup>1</sup>**

Boundary Category	Boundary Type	Permissible Shear Stress (lb/sq ft)	Permissible Velocity (ft/sec)	Citation(s)
<u>Soils</u>	Fine colloidal sand	0.02 - 0.03	1.5	A
	Sandy loam (noncolloidal)	0.03 - 0.04	1.75	A
	Alluvial silt (noncolloidal)	0.045 - 0.05	2	A
	Silty loam (noncolloidal)	0.045 - 0.05	1.75 – 2.25	A
	Firm loam	0.075	2.5	A
	Fine gravels	0.075	2.5	A
	Stiff clay	0.26	3 – 4.5	A, F
	Alluvial silt (colloidal)	0.26	3.75	A
	Graded loam to cobbles	0.38	3.75	A
	Graded silts to cobbles	0.43	4	A
	Shales and hardpan	0.67	6	A
<u>Gravel/Cobble</u>	1-in.	0.33	2.5 – 5	A
	2-in.	0.67	3 – 6	A
	6-in.	2.0	4 – 7.5	A
	12-in.	4.0	5.5 – 12	A
<u>Vegetation</u>	Class A turf	3.7	6 – 8	E, N
	Class B turf	2.1	4 - 7	E, N
	Class C turf	1.0	3.5	E, N
	Long native grasses	1.2 – 1.7	4 – 6	G, H, L, N
	Short native and bunch grass	0.7 - 0.95	3 – 4	G, H, L, N
<u>Temporary Degradable RECPS</u>	Reed plantings	0.1-0.6	N/A	E, N
	Hardwood tree plantings	0.41-2.5	N/A	E, N
	Jute net	0.45	1 – 2.5	E, H, M
	Straw with net	1.5 – 1.65	1 – 3	E, H, M
	Coconut fiber with net	2.25	3 – 4	E, M
<u>Non-Degradable RECPS</u>	Fiberglass roving	2.00	2.5 – 7	E, H, M
	Unvegetated	3.00	5 – 7	E, G, M
	Partially established	4.0-6.0	7.5 – 15	E, G, M
	Fully vegetated	8.00	8 – 21	F, L, M
<u>Riprap</u>	6 – in. d <sub>50</sub>	2.5	5 – 10	H
	9 – in. d <sub>50</sub>	3.8	7 – 11	H
	12 – in. d <sub>50</sub>	5.1	10 – 13	H
	18 – in. d <sub>50</sub>	7.6	12 – 16	H
	24 – in. d <sub>50</sub>	10.1	14 – 18	E
	<u>Soil Bioengineering</u>	Wattles	0.2 – 1.0	3
Reed fascine		0.6-1.25	5	E
Coir roll		3 - 5	8	E, M, N
Vegetated coir mat		4 - 8	9.5	E, M, N
Live brush mattress (initial)		0.4 – 4.1	4	B, E, I
Live brush mattress (grown)		3.90-8.2	12	B, C, E, I, N
Brush layering (initial/grown)		0.4 – 6.25	12	E, I, N
Live fascine		1.25-3.10	6 – 8	C, E, I, J
Live willow stakes		2.10-3.10	3 – 10	E, N, O
<u>Hard Surfacing</u>		Gabions	10	14 – 19
	Concrete	12.5	>18	H

<sup>1</sup> Ranges of values generally reflect multiple sources of data or different testing conditions.

A. Chang, H.H. (1988).

B. Florineth. (1982)

C. Gerstgraser, C. (1998).

D. Goff, K. (1999).

E. Gray, D.H., and Sotir, R.B. (1996).

F. Julien, P.Y. (1995).

G. Kouwen, N.; Li, R. M.; and Simons, D.B., (1980).

H. Norman, J. N. (1975).

I. Schiechl, H. M. and R. Stern. (1996).

J. Schoklisch, A. (1937).

K. Sprague, C.J. (1999).

L. Temple, D.M. (1980).


M. TXDOT (1999)

N. Data from Author (2001)

O. USACE (1997).

## **D. Report Maps**

- I. Drainage Map (Off-Site)
- II. Drainage Map (Existing)
- III. Drainage Map (Proposed)




**EXISTING OFF-SITE DRAINAGE SUMMARY TABLE**

JUNCTION	INCLUDED BASINS	INCLUDED REACHES	AREA (ACRE)	RUNOFF (CFS)	
				Q5	Q100
1	1, 2		215.57	51.9	272.3
2	1, 2, 3, 4, 5	1	447.35	113.0	556.6
3	1, 2, 3, 4, 5, 6, 7	1, 2	502.17	120.2	597.1
4	8, 9, 10		198.59	44.5	220.7
5	8, 9, 10, 11	4	288.66	62.1	320.1
6	8, 9, 10, 11, 12, 13	4, 5	360.79	74.8	391.9
7	8, 9, 10, 11, 12, 13, 14	1, 2, 3, 4, 5, 6	971.75	212.3	1104.4
8	1 - 16	1, 2, 3, 4, 5, 6, 7	999.62	215.6	1126.0

**EXISTING OFF-SITE DRAINAGE SUMMARY TABLE**

JUNCTION	INCLUDED BASINS	INCLUDED REACHES	AREA (ACRE)	RUNOFF (CFS)	
				Q5	Q100
1	1, 2		215.57	51.9	272.3
2	1, 2, 3, 4, 5	1	447.35	113.0	556.6
3	1, 2, 3, 4, 5, 6, 7	1, 2	502.17	120.3	597.2
4	8, 9, 10		198.59	44.5	220.7
5	8, 9, 10, 11	4	288.66	62.1	320.1
6	8, 9, 10, 11, 12, 13	4, 5	360.79	74.8	391.9
7	8, 9, 10, 11, 12, 13, 14	1, 2, 3, 4, 5, 6	971.75	212.5	1105.1
8	1 - 16	1, 2, 3, 4, 5, 6, 7	999.62	216.0	1127.2

**FLOODPLAIN STATEMENT**  
 NO PORTION OF THE SUBJECT PROPERTY IS LOCATED WITHIN A FEMA DESIGNATED SPECIAL FLOOD HAZARD AREA (SFHA) AS INDICATED ON THE FLOOD INSURANCE RATE MAPS (FIRM) FOR EL PASO COUNTY, COLORADO AND INCORPORATED AREAS - MAP NUMBERS 08D41C0310 G, EFFECTIVE DECEMBER 7, 2018.



**MVE, INC.**  
 ENGINEERS / SURVEYORS

1903 Leary Street, Suite 200 Colorado Springs, CO 80909 719.635.5736

DESIGNED BY \_\_\_\_\_  
 DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_  
 AS-BUILTS BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_



REVISIONS

**HIGH FOREST ESTATES  
 SUBDIVISION FILING NO. 1**


**DRAINAGE MAP  
 (OFF-SITE)**

MVE PROJECT 61188  
 MVE DRAWING DRAIN-OS

**APRIL 18, 2023  
 SHEET 1 OF 1**



VICINITY MAP  
NOT TO SCALE



**MVE, INC.**  
ENGINEERS & SURVEYORS

1903 Leary Street, Suite 200, Colorado Springs, CO 80909 719.635.5736

REVISIONS

DESIGNED BY \_\_\_\_\_  
DRAWN BY \_\_\_\_\_  
CHECKED BY \_\_\_\_\_  
AS-BUILT BY \_\_\_\_\_  
CHECKED BY \_\_\_\_\_

HIGH FOREST ESTATES  
SUBDIVISION FILING NO. 1

**DRAINAGE MAP  
(EXISTING)**

MVE PROJECT 61188  
MVE DRAWING DRAIN-EX

**MAY 3, 2023  
SHEET 1 OF 1**

**DESIGN POINTS SUMMARY TABLE**

DESIGN POINTS	INCLUDED BASINS AND DESIGN POINTS	AREA (AC)	Tc (RATIONAL) (MIN.)	Q5 (CFS)	Q100 (CFS)	METHOD
DPOS1	OS-15	82.59	27.1	19.8	132.1	RATIONAL
DPOS2	OS-1, OS-2, OS-3, OS-4, OS-5, OS-6, OS-7	502.17	120.2	597.1	HEC-HMS	
DPOS3	OS-8, OS-9, OS-10, OS-11, OS-12, OS-13	360.79	74.8	391.9	HEC-HMS	
DPOS4	OS-14	20.95	18.5	6.1	40.6	RATIONAL
DPOS5	OS-16	24.31	20.8	6.6	44.5	RATIONAL
DP1	A1, A2, A3, A4, DPOS1, DPOS2, DPOS3, DPOS4	971.75	212.3	1104.4	HEC-HMS	
DP2	A5, DP1, DPOS5	999.62	215.6	1126.0	HEC-HMS	

**ON-SITE BASIN SUMMARY TABLE**

INCLUDED BASINS	AREA (AC)	Tc (MIN.)	RUNOFF	
			Q5 (CFS)	Q100 (CFS)
EX-A1	1.16	12.2	0.5	2.8
EX-A2	1.11	12.0	0.3	2.5
EX-A3	4.45	15.4	1.5	9.5
EX-A4	4.08	14.0	1.5	9.0
EX-A5	3.56	14.1	1.7	8.3

**FLOODPLAIN STATEMENT**

NO PORTION OF THE SUBJECT PROPERTY IS LOCATED WITHIN A FEMA DESIGNATED SPECIAL FLOOD HAZARD AREA (SFHA) AS INDICATED ON THE FLOOD INSURANCE RATE MAPS (FIRM) FOR EL PASO COUNTY, COLORADO AND INCORPORATED AREAS - MAP NUMBERS 08041 C0310 G, EFFECTIVE DECEMBER 7, 2018.

NOTE: SEE BASIN MAP FOR OFFSITE BASIN DETAILS

OS1  
L=90.45'  
Δ=40°06'21"  
R=129.22'  
CB=N69°06'43"W,  
CL=88.62'

OS-15  
82.59 AC  
2.4% IMP

WALKER ROAD  
(60' PUBLIC R.O.W.)

S 8°00'30" E, 40.00'

(RECORDED AS L=89.85' WITH RECEPTION #437944)

TABLE ROCK ROAD  
(60' PUBLIC R.O.W.)

N 89°03'30" W, 831.84'

OS5

OS-5  
24.31 AC  
2.0% IMP

EX-A5  
3.56 AC  
8.0% IMP

EX-A4  
4.08 AC  
3.0% IMP


EX-A3  
4.45 AC  
2.6% IMP

EX-A2  
1.11 AC  
0.0% IMP

EX-A1  
1.16 AC  
6.1% IMP


OS-14  
20.95 AC  
2.0% IMP

OS-16  
24.31 AC  
2.0% IMP



**LEGEND**

- PROPERTY LINE
- EASEMENT LINE
- LOT LINE
- EXISTING INDEX CONTOUR
- EXISTING INTERMEDIATE CONTOUR
- PROPOSED INDEX CONTOUR
- PROPOSED INTERMEDIATE CONTOUR
- BASIN BOUNDARY
- FLOW DIRECTION
- BASIN LABEL
- AREA IN ACRES
- PERCENT IMPERVIOUS
- DESIGN POINT
- 100 YEAR STORM WATER FLOOD LEVEL
- DRAINAGE EASEMENT NO BUILD / NO STORAGE



BENCHMARK

1" = 50' 1:600

**MVE, INC.**  
ENGINEERS & SURVEYORS

1903 Library Street, Suite 200, Colorado Springs, CO 80909 719.635.5736

DESIGNED BY \_\_\_\_\_  
 DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_  
 AS-BUILTS BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_

HIGH FOREST ESTATES  
 SUBDIVISION FILING NO. 1

**DRAINAGE MAP  
 (PROPOSED)**

MVE PROJECT 61188  
 MVE DRAWING DRAIN-PP

**MAY 3, 2023**  
**SHEET 1 OF 1**

**DESIGN POINTS SUMMARY TABLE**

DESIGN POINTS	INCLUDED BASINS AND DESIGN POINTS	AREA (AC)	Tc (RATIONAL) (MIN.)	Q5 (CFS)	Q100 (CFS)	METHOD
DPOS1	OS-15	82.59	27.1	19.8	132.1	RATIONAL
DPOS2	OS-1, OS-2, OS-3, OS-4, OS-5, OS-6, OS-7	502.17		120.3	597.2	HEC-HMS
DPOS3	OS-8, OS-9, OS-10, OS-11, OS-12, OS-13	360.79		74.8	391.9	HEC-HMS
DPOS4	OS-14	20.95	18.5	6.1	40.6	RATIONAL
DPOS5	OS-16	24.31	20.8	6.6	44.5	RATIONAL
DP1	A1, A2, A3, A4, DPOS1, DPOS2, DPOS3, DPOS4	971.75		212.5	1105.1	HEC-HMS
DP2	A5, DP1, DPOS5	999.62		216.0	1127.2	HEC-HMS

**ON-SITE BASIN SUMMARY TABLE**

INCLUDED BASINS	AREA (AC)	Tc (MIN.)	RUNOFF	
			Q5 (CFS)	Q100 (CFS)
A1	1.16	12.2	0.5	2.8
A2	1.11	12.0	0.3	2.5
A3	4.45	15.4	1.5	9.5
A4	4.08	14.0	1.5	9.0
A5	3.56	14.1	2.1	8.9

**FLOODPLAIN STATEMENT**

NO PORTION OF THE SUBJECT PROPERTY IS LOCATED WITHIN A FEMA DESIGNATED SPECIAL FLOOD HAZARD AREA (SFHA) AS INDICATED ON THE FLOOD INSURANCE RATE MAPS (FIRM) FOR EL PASO COUNTY, COLORADO AND INCORPORATED AREAS - MAP NUMBERS 08041 C0310 G, EFFECTIVE DECEMBER 7, 2018.

NOTE: SEE BASIN MAP FOR OFFSITE BASIN DETAILS

# V1\_Drainage Report Final\_Comments.pdf Markup Summary

---

## Callout (2)

---



**Subject:** Callout  
**Page Label:** 7  
**Author:** lpackman  
**Date:** 5/30/2023 12:10:13 PM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

Per ECM 3.2.4 developed flows have to exit at a suitable outfall. Revise to include in the narrative the condition of the culverts and whether they can handle additional flows. Provide an analysis of the culverts.



**Subject:** Callout  
**Page Label:** 14  
**Author:** lpackman  
**Date:** 5/30/2023 12:10:57 PM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

Provide correspondence from State Dam Engineer's office to determine whether this embankment is jurisdictional or not. If applicant does not have rights to have embankment they might require it to be removed.

---

## Text Box (1)

---



**Subject:** Text Box  
**Page Label:** 1  
**Author:** Carlos  
**Date:** 5/30/2023 10:59:44 AM  
**Status:**  
**Color:** ■  
**Layer:**  
**Space:**

Add "VR2311"